

Application #54419 "Remodel 2294 SW JUNCTION RD FORT WHITE, FL 32038

NEEDED:

1. ENV HEALTH (?) The square footage of structure will not be increased. A 900 gallon septic tank and 200 sqft drainfield was installed April 21, 2022 by Howard Septic Tank Service.
2. MANUAL J AND ENERGY CODE FORMS (?) Using existing heating and A/C equipment,(1400 SEER 2.5 Ton Goodman Heat Pump installed in 2015 by Fleming Heating & Air.
3. NEED PLAN ON HOW BLOCK WALL WILL BE ATTACHED TO EXISTING CONCRETE EPOXY IN REBAR ETC.
? The block wall was attached to the existing concrete slab with epoxy and 4x8x16 blocks. The wall was attached to the existing block sides using 8 x8 blocks and concrete mortar. Concrete mortar mix was also used between all surfaces and blocks. The opening was already supportive of a weight bearing wall with a solid top header about 10 inches high which extended the entire length of the garage opening.