

SCOPE OF WORK

WOOD RAMP INSTALLATION FOR 425 NW WINFIELD ST, LAKE CITY, FL 32055

INSTALL 30' WOOD RAMP WITH HANDRAILS AT 1:12 SLOPE WITH 2" PROTECTIVE EDGES.

INSTALL 5'x5' WOOD LANDING WITH HANDRAILS AT THE ENTRANCE.

INSTALL 4'x8' WOOD TURNING LANDING WITH HANDRAILS.

INSTALL BOTTOM CONCRETE 5'x5' LANDING.