



Columbia County, FL.

Roof Replacement or Repair Permit #000047144

Issued May 04, 2023



* Request inspections by calling 386-719-2023 or visiting <https://www.columbiacountyfla.com/PermitSearch/InspectionCalendar.aspx>

OWNER: KUNZLER WILLIAM J, KUNZLER
ANNA L

PHONE:

ADDRESS: 340 SW CALLAWAY DR LAKE CITY, FL 32024

PARCEL: 15-4S-16-03023-250

ZONING: RESIDENTIAL - LOW RSF-2

FLOOD ZONE: A

Coords: 30.15,-82.69

SUBDIVISION: CALLAWAY PHASE 2

LOT: 50

BLK:

PHASE:

UNIT:

ACRES: 0.51

CONTRACTORS

NAME: JORDAN R WEBB

BUSINESS: REDTAIL ROOFING LLC

ADDRESS:

7643 GATE PARKWAY104177
JACKSONVILLE, FL 32256

PHONE: 904.504.5381

LICENSE: CCC1331300 -

PROJECT DETAILS

TYPE ROOFING JOB:

Replacement - Tear off Existing and Replace

FURTHER JOB DETAILS (EXPLAIN IF DECKING IS BEING
REPLACED AND OR REPAIRS ARE BEING DONE.):

Reroof 53.33sq 8/12

TYPE OF STRUCTURE:

House

COMMERCIAL OR RESIDENTIAL:

Residential

ROOF AREA (FOR THIS JOB) SQ FT:

3405

NO. OF STORIES:

1

VENTILATION::

Off-ridge Vent

FLASHING::

Replace All

DRIP EDGE::

Replace All

VALLEY TREATMENT:

New Mineral Surface

ROOF PITCH:

4:12 or Greater

ANY CABLE AND/OR RACE-WAY WIRING LOCATED ON OR WITHIN
THE ROOF ASSEMBLY?:

No

IS THE EXISTING ROOF BEING REMOVED?:

Yes

TYPE OF NEW ROOFING PRODUCT:

Asphalt Shingles

FLORIDA PRODUCT APPROVAL NUMBER:

FL10674-R16

PRODUCT MANUFACTURER :

OWENS CORNING

PRODUCT DESCRIPTION:

SHINGLES

NOTICE: Addition to the requirements of this permit, there may be restrictions applicable to this property that may be found in the public records of this county and there may be additional permits required from other governmental entities such as water management districts, state or federal agencies.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

NOTICE: All work is to be completed in accordance with the permitted plans and applicable codes of Columbia County, Florida. In order to maintain a valid permit the work authorized must commence within 180 days of issuance and have an approved inspection within every 180 days thereafter.

MUST POST ON THE JOBSITE: Copies of the Permit and Recorded Notice of Commencement for inspection.

5/4/2023 4:23 PM

with ASTM D1970 or a minimum 3 3/4 - inch wide strip of selfadhering flexible flashing tape complying with AAMA 711, applied over all joints in the roof decking. A felt underlayment complying with ASTM D226 Type II, ASTM D4869 Type III or IV, or ASTM D6757, or a synthetic underlayment meeting the performance requirements specified, is required to be applied over the strips/tape over the entire roof.

BUILDING CODE EDITION:

2020 Florida Building Code 7th Edition and Florida Statute 553.844

FEMA MAP NUMBER :

12023C0289D

NOTICE: Addition to the requirements of this permit, there may be restrictions applicable to this property that may be found in the public records of this county and there may be additional permits required from other governmental entities such as water management districts, state or federal agencies.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

NOTICE: All work is to be completed in accordance with the permitted plans and applicable codes of Columbia County, Florida. In order to maintain a valid permit the work authorized must commence within 180 days of issuance and have an approved inspection within every 180 days thereafter.

MUST POST ON THE JOBSITE: Copies of the **Permit and Recorded Notice of Commencement** for inspection.

5/4/2023 4:23 PM