


STEM WALL HEIGHT (FEET)	UNBALANCED BACKFILL HEIGHT	VERTICAL REINFORCEMENT FOR 6" CMU STEM WALL (INCHES O.C.)			VERTICAL REINFORCEMENT FOR 12" CMU STEM WALL (INCHES O.C.)		
		#5	#7	#8	#5	#7	#8
3.3	3.0	96	96	96	96	96	96
4.0	3.7	96	96	96	96	96	96
4.7	4.3	88	96	96	96	96	96
5.3	5.0	56	96	96	96	96	96
6.0	5.7	40	80	96	80	96	96
6.7	6.3	32	56	80	56	96	96
7.3	7.0	24	40	56	40	80	96
8.0	7.7	16	32	48	32	64	80
8.7	8.3	8	24	32	24	48	64
9.3	9.0	8	16	24	16	40	48

MASONRY NOTE:
MASONRY CONSTRUCTION AND MATERIALS FOR THIS PROJECT SHALL CONFORM TO ALL REQUIREMENTS OF "SPECIFICATION FOR MASONRY STRUCTURES" (ACI 530.1/ASCE 6/TMS 602). THE CONTRACTOR AND MASON MUST IMMEDIATELY, BEFORE PROCEEDING, NOTIFY THE ENGINEER OF ANY CONFLICTS BETWEEN ACI 530.1-02 AND THESE DESIGN DRAWINGS. ANY EXCEPTIONS TO ACI 530.1-02 MUST BE APPROVED BY THE ENGINEER IN WRITING.

SECTION 05100 - FINISHING		Specific Requirements
1.4A	Compressive strength	8" block bearing walls F _m = 1500 psi
2.1	Mortar	ASTM C 270, Type N, UNO
2.2	Grout	ASTM C 478, admixtures require approval
2.3	CMU standard	ASTM C 90, standard, Normal weight, Hollow, hollow core type, 8"x8"x16" running bond and 12"x12"x16" 100% hollow column block
2.3	Clay brick standard	ASTM C 216.02, Grade SW, Type FBS, S-2 S-2-2-11-57
2.4	Reinforcing bars, #3-#11	ASTM A615, Grade 60, F _y = 40ksi, Lap splices 11in 40 bar uls, (25" for #5)
2.4F	Coating for corrosion protection	Anchors, sheet metal lvs completely embedded in mortar or grout ASTM A525, Class G80, 0.60 oz/sq ft or 304SS
2.4F	Coating for corrosion protection	Joint reinforcement in walls exposed to moisture or wire lvs, sheet metal lvs not completely embedded in mortar or grout, ASTM A153, Class B2, 1.50 oz/sq ft or 304SS
3.3.E.2	Pipes, conduits, and accessories	Any not shown on the project drawings require engineering approval
3.3.E.7	Movement joints	Contractor assumes responsibility for type and location of movement joints. Not installed on project drawings

BOTTOM OF EXTERIOR FOOTINGS SHALL BE A MINIMUM OF
12" BELOW UNDISTURBED SOIL OR ENGINEERED FILL



FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

FOUNDATION NOTES

- | | |
|--------|--|
| FN - 1 | DIMENSIONS ON FOUNDATION & STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL PLANS FOR ACTUAL DIMENSIONS, RECESSES IN SLAB, CHAIRS, DOWNS, ETC. DIMENSIONS OF RECESSES OR MARK DISOWPAY, PE IS NOT RESPONSIBLE FOR DIMENSION ERRORS ON THIS PLAN. |
| FN - 2 | CONTRACTOR SHALL VERIFY NEED FOR INTERIOR BEARING WALLS AS REVIEWED BY THE ENGINEER FOR TRUSS PLAN (BY THE SUPPLIER) BEFORE FINALIZING FOUNDATION PLAN |
| FN - 3 | THE SLAB SHALL BE: A' CONCRETE SLAB REINFORCED w/ 6X6-1 #14 WELDED WIRE MESH PLACED ON CHAIRS 6" DEPTH OR MORE. REINFORCING BARS SHALL BE 6-MIL. 1/4" W/ PLY BARRIER w/ 6" LAPS SEALED w/ POLY TAPE OVER THERMITE-TREATED & COMPACTED FILL (ALSO, ANY OTHER CODE APPROVED THERMITE-TREATMENT METHOD CAN BE USED) |

Nettles Res.

PROJECT ADDRESS: Columbia County, FL

Glenwood
King
Construction
Inc.

FL PE 53915

This item has been digitally signed and sealed
Mark Disosway PE on digital signature data
Printed copies of this document are not consid-
signed and sealed and the signature must
verified on any electronic copies.



C=US, O=Florida
dnQualifier=A
10C0000017E
DE07CA0007
0, CN=Mark
Disosway
2023-12-28 1
11:15

DIMENSIONS:
Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS: Mark Disosway, P.E. hereby expressly reserves all common law copyrights and property rights in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering, comply with the 8th Edition Florida Building Code Residential (2023)

LIMITATION: This design is valid for one building, at specified location.

Mark Disosway P.E.
163 SW Midtown Place
Suite 103
Lake City, Florida 32025
386.754.5419
disoswaydesign@gmail.com

JOB NUMBER:
231515

S-2
OF 3 SHEET