



- NOTES:**
1. ALL SENSORS ARE MOUNTED TO COLUMNS ON THE SALES FLOOR AND MUST BE AFFIXED TO THE SURFACE OF THE COLUMN THAT FACES THE CENTER OF THE SALES AREA. ALL SENSORS ARE INSTALLED BY EMS VENDOR.
 2. CONTRACTOR SHALL INSTALL CONDUIT, BOXES, AND CONTROL CABLING AS SHOWN FOR FUTURE INSTALLATION OF SENSORS. MECHANICAL CONTRACTOR SHALL PROVIDE TEMPORARY T-STATS TO RUN THE UNITS PRIOR TO EMS INSTALLATION.
 3. CONTRACTOR SHALL LABEL EACH SENSOR FOR RTU SERVED.

