

DATE 07/25/2005

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000023411

APPLICANT LINDA RODER PHONE 752-2281
ADDRESS 387 SW KEMP COURT LAKE CITY FL 32024
OWNER ED & DIANE WHITE PHONE
ADDRESS 7018 SW STATE ROAD 47 LAKE CITY FL 32024
CONTRACTOR ISAAC CONSTRUCTION PHONE 719-7143
LOCATION OF PROPERTY 47S, 1 MILE PAST WALTER AVE ON RIGHT

TYPE DEVELOPMENT ADDITION TO SFD ESTIMATED COST OF CONSTRUCTION .00
HEATED FLOOR AREA 2440.00 TOTAL AREA 2440.00 HEIGHT .00 STORIES 2
FOUNDATION CONC WALLS FRAMED ROOF PITCH 3/12 FLOOR SLAB
LAND USE & ZONING A-3 MAX. HEIGHT 32
Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00
NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 02-5S-16-03443-002 SUBDIVISION
LOT BLOCK PHASE UNIT TOTAL ACRES

CBC059323
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
EXISTING 05-0461-N BK N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: ONE FOOT ABOVE THE ROAD, NOC ON FILE

Check # or Cash 807

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by
Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by
Framing date/app. by Rough-in plumbing above slab and below wood floor date/app. by
Electrical rough-in date/app. by Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by
Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by
M/H tie downs, blocking, electricity and plumbing date/app. by Pool date/app. by
Reconnection date/app. by Pump pole date/app. by Utility Pole date/app. by
M/H Pole date/app. by Travel Trailer date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 950.00 CERTIFICATION FEE \$ 12.20 SURCHARGE FEE \$ 12.20
MISC. FEES \$.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ WASTE FEE \$
FLOOD ZONE DEVELOPMENT FEE \$ CULVERT FEE \$ TOTAL FEE 1024.40
INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVENIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Edward C White
Diane Bishop White
P O Box 2111
Lake City, FL 32056
386-758-9486

July 28, 2006

John Kerce, Building Official
Columbia County Building and Zoning Department
135 NE Hernando Avenue
Suite B21
Lake City, Florida 32055

Dear Mr. Kerce;

In compliance with the directive that I received from Mr. Joe Haltiwanger issued with regard to my property at 7018 SW SR 47 on December 13, 2005, I am reporting to you on results of structural evaluations on a residential home at the above listed address. According to the professional engineers that examined this structure, your inspectors were indeed correct with regard to structural deficiencies in this project. Additionally, during an inspection yesterday, a structural engineer pointed out that completed work seriously deviated from permitted plans. To him, this constitutes a serious violation of the permit obtained for this project.

Based on this latest information, I feel that your department should conduct an additional inspection of this job site. If it is found that the permit was, in fact, violated, I would expect appropriate actions to be taken to include written documentation of the permit violations.

This has been a long and painful process for my wife and I at a time when we lost our parents to painful illness and tried to transition to our family home here in Lake City. Your immediate attention to this prolonged process would be most appreciated.

Respectfully,


Ed White

FEAGLE & FEAGLE, ATTORNEYS, P.A.
ATTORNEYS AT LAW
153 NE MADISON STREET
POST OFFICE BOX 1653
LAKE CITY, FLORIDA 32056-1653
(386) 752-7191
Fax: (386) 758-0950

Marlin M. Feagle
e-mail: leagle@bellsouth.net

Mark E. Feagle
e-mail: mefeagle@bellsouth.net

August 24, 2006

Mr. Joe Haltiwanger
Plan Examiner
Columbia County Building Department
135 NE Hernando Avenue, Suite B21
Lake City, Florida 32055

Re: Edward C. White and his wife, Diane Bishop White

Dear Joe:

This will confirm our recent office conference where we discussed the letter from Edward White dated July 28, 2006 addressed to John Kerce, a copy of which is enclosed for your reference. In his letter Mr. White describes that according to the professional engineers that examined the structure, his home, structural deficiencies were noted. Mr. White also points out that during an inspection the structural engineer pointed out that completed work deviated from permitted plans.

Mr. White will need to have his structural engineer and/or architect complete their inspection and investigation. Then, they will need to provide the County with a specific corrective action plan. Based upon this corrective action plan which may include modification of the original construction plans, the County should be in a position to review the same and issue a second permit to either the owner or a state certified licensed building contractor. The County cannot issue a second permit until this information is provided to the County.

If Mr. White believes his state licensed contractor failed to complete the work in a professional manner, his complaint and recourse should be directed to the State of Florida, Department of Business and Professional Regulations, which regulates licensed contractors.

If you need anything further in this regard, please do not hesitate to give me a call.

Very truly yours,


Marlin M. Feagle

MMF:dse



Engineers • Planners

161 N.W. Madison St., Suite 102
Lake City, Florida 32055
Tel: 386-758-4209
Fax: 386-758-4290

7/28/2006

Ed White
P. O. Box 1376
Lake City, FL. 32056

Re: Structural Inspection

Dear Mr. White,

I have completed the structural inspection and have reviewed the original plans and the following evidence is evident:

The plans call for an exterior bearing wall height of 9'0". The exterior bearing walls were constructed at an 8'0" height. The ceiling height of the master bedroom is shown as a 9'0" ceiling height but was constructed as a 10'0" ceiling height. During construction the roof of the first floor interfered with the floor level of the second floor since the wall was constructed 1'0" too short and the floor level 1'0" too high. This caused a problem with floor joist layout as indicated on the plans. Since the floor joists interfered with the incorrectly placed roof system, the floor joists were altered so that they were no longer bearing on the walls as indicated on the plans. The plans did indicate structural load bearing walls to support the upper floor joist system, however, by shifting the bearing locations to new non-structural walls there was no provision for a structural foundation or structural headers. This could cause failure in the slab and wall components.

The two-story portion of the house was not constructed to the proper wall height as indicated on the plans. The original design called for a set of four (4) beams to run continuous from front to rear of the structure. The exterior walls were constructed in this manner to perform as a post and beam system. The beams are intended to span a certain distance and then bear on a post which has a structural footing directly underneath. The exterior walls on the two story portion were altered to bring the height up according to the original design. When this was done, the structural beam was removed in order to build a new knee wall above the original wall that was built too low. This created two main problems. When the beam was removed, the post-beam structure became a continuous load-bearing wall. There is no interior structural footing to carry the load along the entire length of wall. When the knee wall was constructed to extend the

wall height per design, a hinge point was created in the wall. This could likely fail when wind pressure is applied to the wall.

A new wall was constructed on top of the original house. At this point, there is no evidence that the exterior wall is resting on anything structural. The weight of the wall and the roof trusses are only bearing on the existing roof decking and is showing signs of excessive deflection. The load-bearing wall needs to have a continuous load path from the foundation, up to the roof.

In order to solve the issues discussed above the structure would need to be dismantled. A redesign of the project should be accomplished taking into account the correct pitch of the existing roof. It should contain detail for the joining of the new and the old structure and foundation requirements to support changes in the correct plans. Because the structure could not be completed the trusses have now been exposed to the weather for nearly a year and have shown signs of twisting and buckling.

If you have any questions, you may contact me at (386) 758-4209.

Sincerely,

A handwritten signature in black ink, appearing to read "William Freeman". The signature is fluid and cursive, with the first name "William" and last name "Freeman" clearly distinguishable.

William Freeman, P.E.

From: The Columbia County Building Department
Plans Review
135 NE Hernando Av.
P. O Box 1529
Lake City Florida, 32056-1529

Dear Mr. Ed White

On December 13, 2005 per your request Mr. Randy Jones Assistant Building Official, Mr. Harry Dicks Building Inspector and I as the Plans Examiner accompanied you with a structural inspection of your resident at 7018 SW SR 47. The inspection pertains to Building permit number 23411 issued July 25, 2005 to ISAAC. This build permit was to construct an addition on to an existing single family dwelling.

You requested that we inspect the structural framing which has been completed thus far for building code compliance. The Columbia County Building Department has several concerns which are:

1. Mr. Robert Taylor Architect, of Associated Florida Architects, Inc. 802 NW 23rd Avenue Gainesville Florida, State of Florida Registration Number AR-0007526 filed a letter with the Columbia County Building Department on July 22, 2005 which stated that Associated Florida Architects, Inc. were the architects of record for the construction of a addition on to your single family dwelling. Mr. Robert Taylor in this letter also stated that certain structural issues which I as the plan examiner had would be addressed once the construction of this addition was started. Mr. Robert Taylor stated that within forty-five (45) days of commencing with construction a written structural report addressing the needed issues would be filed with the Columbia County Building Department. **No reports have been**

**filed with the Columbia County Building Department by Mr. Taylor or
Associated Florida Architects.**





2. An example of one of the issues which was not addressed was the use of an exterior load bearing foundations and shear walls which was used to construct a second story load bearing wall without the contractor and the architect confirming that the foundation and the structural walls could safely support the additional structural load-bearing weight which has been applied to the foundation and walls for of a second story and a roof truss system.
3. The addition onto the structure of 3,044 square feet incorporated a first and second floor, using wood frame structural walls. Within the first floor several exterior and interior load bearing walls have been created to provide support for the second floor, flooring and roof truss system. Several first floor walls lack sufficient structural strength to properly support the second floor.
2. The roof trusses have been modified by the contractor, the truss designer will be required to assess the trusses system to certify that the trusses system meet the original truss system design.




In order to continue work on this structure, a structural evaluation by a professional architect or engineer is needed to comply with the Florida Building Codes 2001. If you should have any additional question please contact me.

Thank you,








Joe Haltiwanger
Plan Examiner
Columbia County Building Department



















associated florida architects, inc.

florida registration AA-C001907

802 nw 23rd avenue • gainesville, florida 32609-3534

352 375-3005 • 352 378-2523 • 352 375-5397 fax

July 22, 2005

Columbia County Building Department

135 NE Hernando Ave.

Lake City, FL 32055

Re: Ed & Diane Bishop-white Residence

To Whom It May Concern:

We are the architects for the referenced project. We have a full service contract with the owners including contract administration.

Due to the fact that this is an addition we will be able to do the discovery work on the existing residence when construction commences.

We will write a report with findings and recommendations within forty-five (45) days of start of construction. As per 3401.8.2.3.1, 3401.8.2.3.2 and 3401.8.2.3.3 of 2001 Florida Building Code.

Robert S. Taylor, Sr. - Architect

Florida Registration AR-0007526



associated florida architects, inc.

florida registration AA-C001907

802 nw 23rd avenue • gainesville, florida 32609-3534

352 375-3005 • 352 378-2523 • 352 375-5397 fax

July 22, 2005

Isaac Construction
Lake City, Florida 34474

ADDENDUM NUMBER ONE:

Contract Drawings – Dated 09 May 05


Revision Date 21 July 2005

Architect's File Number 0317

The following changes, revisions or deletions to the original Drawings, or previously issued Addenda shall be made by this Addendum.

This Addendum is issued to revise and clarify items addressed by a Letter from the Columbia County Building & Zoning Department dated 08 July 2005 dealing with Plan Review.

- 1.) REPLACE EXISTING FLOOR PLAN SHEET WITH NEW FLOOR PLAN (SHOWING DOOR SIZES)
- 2.) REPLACE EXISTING FRAMING PLAN SHEET WITH NEW FRAMING PLAN SHEET.
- 3.) REPLACE EXISTING ELEVATION SHEET WITH NEW ELEVATION SHEET.
- 4.) ADD SHEETS S-1 (STRUCTURAL NOTES) AND S-2 (STRUCTURAL DETAILS).
- 5.) PROVIDE G.F.C.I. OUTLETS IN ALL SLEEPING ROOMS AS PER 2001 FLORIDA BUILDING CODE.
- 6.) PROVIDE SMOKE DETECTORS AS PER 2001 FLORIDA BUILDING CODE
- 7.) ALL GLASS WITH 18 INCHES ABOVE THE FLOOR SHALL AND THE GARDEN TUB SHALL BE SAFETY GLAZING AS PER 2405.2.4. OF THE 2001 FLORIDA BUILDING CODE.


Robert S. Taylor, Sr. - Architect
Florida Registration AR-0007526

Date	Inspection	Inspect.	Owner	Pass	Location	Permit
08/09/05	Temp Service	Randy	Issac Bratkovich - White	OK	7018 SW SR 47	23411
08/15/05	Rough Plumbing	Randy	Issac Bratkovich - White	OK	7018 SW SR 47	23411
09/06/05	Mono Slab	Randy	Issac Bratkovich - White	OK	7018 SW SR 47	23411
09/06/05	Set Backs	Randy	Issac Bratkovich - White	OK	7018 SW SR 47	23411
12/13/05	Complaint	HD-RJ-JH	Issac Bratkovich - White	Met With	7018 SW SR 47	23411

New Construction Subterranean Termite Soil Treatment Record

OMB Approval No. 2502-0525
(exp. 10/31/2005)

This form is completed by the licensed Pest Control Company.

Public reporting burden for this collection of information is estimated to average 15 minutes per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. This information is mandatory and is required to obtain benefits. HUD may not collect this information, and you are not required to complete this form, unless it displays a currently valid OMB control number.

Section 24 CFR 200.926d(b)(3) requires that the sites for HUD insured structures must be free of termite hazards. This information collection requires the builder to certify that an authorized Pest Control company performed all required treatment for termites, and that the builder guarantees the treated area against infestation for one year. Builders, pest control companies, mortgage lenders, homebuyers, and HUD as a record of treatment for specific homes will use the information collected. The information is not considered confidential.

This report is submitted for informational purposes to the builder on proposed (new) construction cases when soil treatment for prevention of subterranean termite infestation is specified by the builder, architect, or required by the lender, architect, FHA, or VA.

All contracts for services are between the Pest Control Operator and builder, unless stated otherwise.

#23411

Section 1: General Information (Treating Company Information)

Company Name: Aspen Pest Control, Inc.
Company Address: 301 NW Cole Terrace City Lake City State FL Zip 32055
Company Business License No. JB109476 Company Phone No. 386-755-3611
FHA/VA Case No. (if any) _____

Section 2: Builder Information

Company Name: Isador Court Company Phone No. _____

Section 3: Property Information

Location of Structure(s) Treated (Street Address or Legal Description, City, State and Zip) 7014 S.W. 5th. Ad 47
70th E. St.

Type of Construction (More than one box may be checked) ☒ Slab ☐ Basement ☐ Crawl ☐ Other _____
Approximate Depth of Footing: Outside 0 Inside 0 Type of Fill Gravel

Section 4: Treatment Information

Date(s) of Treatment(s) 9-6-05
Brand Name of Product(s) Used Terminator
EPA Registration No. 70907-7-53443
Approximate Final Mix Solution % 0.5%
Approximate Size of Treatment Area: Sq. ft. 2440 Linear ft. 0 Linear ft. of Masonry Voids 0
Approximate Total Gallons of Solution Applied 245
Was treatment completed on exterior? ☐ Yes ☒ No
Service Agreement Available? ☐ Yes ☒ No

Note: Some state laws require service agreements to be issued. This form does not preempt state law.

Attachments (List) _____

Comments 2440 sq ft mound addition to south end
of home

Name of Applicator(s) John Brown Certification No. (if required by State law) JB104376

The applicator has used a product in accordance with the product label and state requirements. All treatment materials and methods used comply with state and federal regulations.

Authorized Signature John Brown Date 9-6-05

Warning: HUD will prosecute false claims and statements. Conviction may result in criminal and/or civil penalties. (18 U.S.C. 1001, 1010, 1012; 31 U.S.C. 3729, 3802)

Form **NPCA-99-B** may still be used

form HUD-NPCA-99-B (04/2003)

Reorder Product #2581 • From Crown Graphics, Inc. • 1-800-252-4011

04/19/2004 23:01

38675282160

BLDG AND ZONING

PAGE 01

Columbia County Building Permit Application

Revised 9-23-04

For Office Use Only Application # 05016-88 Date Received 6/28/05 By JW Permit # 23411
 Application Approved by - Zoning Official BLK Date 13.07.05 Plans Examiner OKJH Date 7-22-05
 Flood Zone X Development Permit N/A Zoning A-3 Land Use Plan Map Category A-3
 Comments _____

- NOC. NEEDED -

Applicants Name Linda or Melanie Roder Phone 752-2281
 Address 387 S.W. Kemp Ct. Lake City FL 32024
 Owners Name Ed & Diane White Phone _____
 911 Address 7018 S.W. State Rd 97 Lake City FL 32024
 Contractors Name Isaac Construction, Inc. Phone 719-7143
 Address 1005 S.W. Walter Ave.
 Fee Simple Owner Name & Address _____

Bonding Co. Name & Address _____

Architect/Engineer Name & Address Associated Florida Architects/Mark Disosway
 Mortgage Lenders Name & Address Columbia County Bank

Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progressive Energy

Property ID Number 02-53-16-03443-002 Estimated Cost of Construction 190,000 change

Subdivision Name _____ Lot _____ Block _____ Unit _____ Phase _____

Driving Directions 47 S. 1 mile past Walter ave see Isaac sign
On R - that is the driveway, go R

Type of Construction SFD addition Number of Existing Dwellings on Property 1
 Total Acreage 10 Lot Size _____ Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
 Actual Distance of Structure from Property Lines - Front 300' Side 400' Side 1000' Rear 500'
 Total Building Height 32' w/ 28' Removal Number of Stories 2 Heated Floor Area 3044 Root Pitch 3-12
of addition

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Owner Builder or Agent (Including Agent) Batara C. Webster

STATE OF FLORIDA
 COUNTY OF COLUMBIA



Commission # DD329279
 Expires July 2, 2008
 Bonded Tray Pain - Insurance, Inc. 800-385-7018

Sworn to (or affirmed) and subscribed before me

this 22nd day of April 2005

Personally known X or Produced Identification _____

Contractor Signature Isaac Construction

Contractors License Number CBC 059323

Competency Card Number _____

NOTARY STAMP/SEAL

Batara C. Webster

Notary Signature

THIS DOCUMENT WAS PREPARED WITHOUT BENEFIT
OF TITLE SEARCH.

FOR RECORDER

THIS INSTRUMENT WAS PREPARED BY:
Krista L. Waldron, Esquire (PES)
Fisher, Tousey, Leas & Ball, P.A.
818 North A1A, Suite 104
Ponte Vedra Beach, Florida 32082

Inst: 2003008855 Date: 04/29/2003 Time: 09:29

Doc Stamp-Deed : 0.70

MCK DC, P. DeWitt Cason, Columbia County B: 981 P: 2183

SPECIAL WARRANTY DEED

THIS INDENTURE, made this 28 day of APRIL, 2003, between VIRGINIA H. BISHOP, as Trustee of the Virginia H. Bishop Living Trust, whose address is P. O. Box 1298, Lake City, Florida 32056, party of the first part, and EDWARD C. WHITE, JR. and DIANE B. WHITE, husband and wife, whose address is 80 Cliffcreek Trace, Atlanta, Georgia 30350, parties of the second part.

WITNESSETH:

That the said party of the first part, in consideration of love and affection, has granted, bargained, and conveyed to the said parties of the second part, their heirs, successors and assigns forever, her remaining one-half interest in the following described lands, situate, lying and being in Columbia County, Florida, to wit:

Commence at the Southwest Corner of the Southwest $\frac{1}{4}$ of Northwest $\frac{1}{4}$ of Section 2, Township 5 South, Range 16 East and run thence North 0 degrees 49 minutes West along the West line of said Section 2, 658.91 feet for Point of Beginning; thence continue North 0 degrees 49 minutes West along the West line of said Section 2, 500 feet; thence run South 65 degrees 59 minutes 30 seconds East, 1000.05 feet to the Northerly line of State Road No. 47; thence run South 40 degrees 53 minutes West along the West line of State Road No. 47 a distance of 474.23 feet; thence run North 65 degrees 59 minutes 30 seconds West, a distance of 652.5 feet more or less to the Point of Beginning, said land lying in the Southwest $\frac{1}{4}$ of the Northwest $\frac{1}{4}$ of Section 2, Township 5 South, Range 16 East, Columbia County, Florida, containing 10 acres, more or less.

Real Estate Assessment No: 02-SS-16-03443-002

Subject to covenants, restrictions, easements, mortgages and all other encumbrances of record and taxes assessed subsequent to December 31, 2002; provided, however, this reference will not serve to reimpose any such covenants, restrictions or easements.

Inst: 2003008895 Date: 04/29/2003 Time: 09:29

cc Stamp-Deed : 0.70

DC, P. DeWitt Cason, Columbia County B: 981 P: 2184

And the said party of the first part does hereby fully warrant the title to said land, and will defend the same against the lawful claims of all persons whomsoever claiming by, through or under the said party of the first part, but not otherwise.

IN WITNESS WHEREOF, the undersigned has hereunto set her hand and seal as of the day and year first above written.

Signed and Sealed in Our
Presence:

Sign: Doris A. Johnson
Print Name: Doris A. Johnson


Virginia H. Bishop
VIRGINIA H. BISHOP, as Trustee of the
Virginia H. Bishop Living Trust

Sign: Sheryl Litteral
Print Name: Sheryl Litteral

STATE OF FLORIDA
COUNTY OF Columbia

The foregoing instrument was acknowledged before me this 28 day of April, 2003, by VIRGINIA H. BISHOP, as Trustee of the Virginia H. Bishop Living Trust, (notary must check one box):
☒ who is personally known to me or () who has produced _____ (State) driver's license No. _____ as identification.


Elaine K. Tolar
Name: ELAINE K. TOLAR
NOTARY PUBLIC, State of FLORIDA
Commission Number: _____



**Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan**
Permit Application Number: 05-0461N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT


WHITE/
CR 04-2765



Site Plan Submitted By Paul L. L. Date 4/21/05
Plan Approved ☒ Not Approved ☐ Date 6-23-05
By M. S. L. Columbia CPHU

Notes:

0506-88



FAX

Date: 7-12-05

To: Brian Kepler

From: Linda

North Florida Permit Services, INC.


Ph: 386-752-2281 Fax: 386-752-2282

Pages: 2

Attn: Brian

Here is revised site plan for Ed White.

— Linda



This information, GIS Map Updated: 6/2/2005, was derived from data which was compiled by the Columbia County Property Appraiser Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data herein, its use, or its interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.

HALL'S PUMP & WELL SERVICE, INC.

SPECIALIZING IN 4"-6" WELLS



DONALD AND MARY HALL
OWNERS

PHONE (904) 752-1854
FAX (904) 755-7022
~~XXXXXX FIRST STREET~~
LAKE CITY, FLORIDA 32055
904 NW Main Blvd.


June 12, 2002


NOTICE TO ALL CONTRACTORS

Please be advised that due to the new building codes we will use a large capacity diaphragm tank on all new wells. This will insure a minimum of one (1) minute draw down or one (1) minute refill. If a smaller diaphragm tank is used then we will install a cycle stop valve which will produce the same results.

If you have any questions please feel free to call our office anytime.

Thank you,


Donald D. Hall
DDH/jk

**Columbia County Property Appraiser**

J. Doyle Crews, CFA - Lake City, Florida - 386-758-1083

PARCEL: 02-5S-16-03443-002 - IMPROVED A (005000)

COMM SW COR OF SW1/4 OF NW1/4, RUN N 658.91 FT FOR POB, CONT N 500 FT, SE 1000.05 FT TO W

Name: WHITE EDWARD C JR & DIANE B

Site: SR 47

Mail: P O BOX 2111

LAKE CITY, FL 32056

Sales 4/28/2003 \$100.00 I / U

Info 7/26/2001 \$100.00 I / U

LandVal \$9,600.00

BldgVal \$92,283.00

ApprVal \$106,960.00

JustVal \$145,858.00

Assd \$106,960.00

Exmpt \$0.00

Taxable \$106,960.00

0 100 200 300 ft




This information, GIS Map Updated: 4/4/2005, was derived from data which was compiled by the Columbia County Property Appraiser Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data herein, it's use, or it's interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.

Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan
Permit Application Number: 05-0461N


ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

WHITE/
CR 04-2765



Site Plan Submitted By Paul L. L. Date 4/21/05
Plan Approved ☒ Not Approved ☐ Date 6-28-05
By M. S. L. Columbia CPHU

Notes:



Columbia County Property Appraiser

J. Doyle Crews, CFA - Lake City, Florida - 386-758-1083

PARCEL: 02-5S-16-03443-002 - IMPROVED A (005000)

COMM SW COR OF SW1/4 OF NW1/4, RUN N 658.91 FT FOR POB, CONT N 500 FT, SE 1000.05 FT TO W

Name: WHITE EDWARD C JR & DIANE B

Site: SR 47

Mail: P O BOX 2111

LAKE CITY, FL 32056

Sales 4/28/2003 \$100.00 I / U

Info 7/26/2001 \$100.00 I / U

LandVal \$9,600.00

BldgVal \$92,283.00

ApprVal \$106,960.00

JustVal \$145,858.00

Assd \$106,960.00

Exmpt \$0.00

Taxable \$106,960.00

0 100 200 300 ft



This information, GIS Map Updated: 4/4/2005, was derived from data which was compiled by the Columbia County Property Appraiser Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data herein, its use, or its interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.

Compliance with Method B Chapter 6 of the Florida Energy Efficiency Code may be demonstrated by the use of Form 600B for single and multifamily residences of 3 stories or less in height, and additions to existing residential buildings. To comply, a building must meet or exceed all of the energy efficiency prescriptives in any one of the prescriptive component packages and comply with the prescriptive measures listed in Table 6B-1 of this form. An alternative method is provided for additions of 600 square feet or less by use of Form 600C. If a building does not comply with this method, it may still comply under other sections in Chapter 6 of the Code.

PROJECT NAME: AND ADDRESS:	Bishop White	BUILDER:		PERMITTING OFFICE:	Columbia County	CLIMATE ZONE:	1 <input type="checkbox"/> 2 <input type="checkbox"/> 3 <input type="checkbox"/>
OWNER:	Ed & Diane Bishop White	PERMIT NO.:				JURISDICTION NO.:	

GENERAL DIRECTIONS

1. New construction including additions which incorporates any of the following features cannot comply using this method: steel stud walls, single assembly roof/ceiling construction, or skylights or other non-vertical roof glass.
2. Choose one of the component packages "A" through "E" from Table 6B-1 by which you intend to comply with the Code. Circle the column of the package you have chosen.
3. Fill in all the applicable spaces of the "To Be Installed" column on Table 6B-1 with the information requested. All "To Be Installed" values must be equal to or more efficient than the required levels.
4. Complete page 1 based on the "To Be Installed" column information.
5. Read "Minimum Requirements for All Packages", Table 6B-2 and check each box to indicate your intent to comply with all applicable items.
6. Read, sign and date the "Prepared By" certification statement at the bottom of page 1. The owner or owner's agent must also sign and date the form.

Please Print

CK

1. Compliance package chosen (A-F)
2. New construction or addition
3. Single family detached or Multifamily attached
4. If Multifamily—No. of units covered by this submission
5. Is this a worst case? (yes / no)
6. Conditioned floor area (sq. ft.)
7. Predominant eave overhang (ft.)
8. Glass type and area :
 - a. Clear glass
 - b. Tint, film or solar screen
9. Percentage of glass to floor area
10. Floor type, area or perimeter, and insulation:
 - a. Slab on grade (R-value)
 - b. Wood, raised (R-value)
 - c. Wood, common (R-value)
 - d. Concrete, raised (R-value)
 - e. Concrete, common (R-value)
11. Wall type, area and insulation:
 - a. Exterior: 1. Masonry (Insulation R-value)
2. Wood frame (Insulation R-value)
 - b. Adjacent: 1. Masonry (Insulation R-value)
2. Wood frame (Insulation R-value)
12. Ceiling type, area and insulation:
 - a. Under attic (Insulation R-value)
 - b. Single assembly (Insulation R-value)
13. Air Distribution System: Duct insulation, location
Test report (attach if required)
14. Cooling system
(Types: central, room unit, package terminal A.C., gas, none)
15. Heating system:
(Types: heat pump, elec. strip, nat. gas, L.P. gas, gas h.p., room or PTAC, none)
16. Hot water system:
(Types: elec., nat. gas, L.P. gas, solar, heat rec., ded. heat pump, other, none)

1.	D		
2.	Addition		
3.	Single Fam.		
4.			
5.	NO		
6.	3044		
7.	3		
	Single Pane	Double Pane	
8a.			sq. ft.
8b.			sq. ft.
9.	20		%
10a.	R= 0		lin. ft.
10b.	R=		sq. ft.
10c.	R=		sq. ft.
10d.	R=		sq. ft.
10e.	R=		sq. ft.
11a-1	R=		sq. ft.
11a-2	R= 11	1749	sq. ft.
11b-1	R=		sq. ft.
11b-2	R=		sq. ft.
12a.	R= 30	2440	sq. ft.
12b.	R=		sq. ft.
13.	R= 6		
14a.	Type: Central		
14b.	SEER/EER: 12.5		
14c.	Capacity: 5 Ton		
15a.	Type: Heat Pump		
15b.	HSPF/COP/AFUE:		
15c.	Capacity: 600K		
16a.	Type: Elect. HRV		
16b.	EF:		

I hereby certify that the plans and specifications covered by the calculation are in compliance with the Florida Energy Code.

PREPARED BY: Ken [Signature] DATE: 6-6-05

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER AGENT: [Signature] DATE: 6-7-05

Review of plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed, this building will be inspected for compliance in accordance with Section 553.908, F.S.

BUILDING OFFICIAL:

DATE:

TABLE 6B-1

MINIMUM REQUIREMENTS

Climate Zones 1 2 3

COMPONENTS		PACKAGES FOR NEW CONSTRUCTION				
		A	B	C	D	E
GLASS	Max. % of glass to Floor Area	15%	15%	20%	20%	25%
	Type	Double Clear (DC)	Double Clear (DC)	Double Clear (DC)	Double Clear (DC)	Double Tint (DT)
	Overhang	1'4"	2'	2'	2'	2'
WALLS	Masonry	EXTERIOR AND ADJACENT MASONRY WALLS R-5 COMMON MASONRY WALLS R-3 EACH SIDE.				
	Wood Frame	EXTERIOR, ADJACENT, AND COMMON WOOD FRAME WALLS R-11				
CEILING		R-30	R-30	R-30	R-30	R-30
		(NO SINGLE ASSEMBLY CEILINGS ALLOWED)				
FLOORS	Slab-On-Grade	R-0				
	Raised Wood	R-19 (ONLY STEM WALL CONSTRUCTION ALLOWED EXCEPT PACKAGE C)				
	Raised Concrete	R-7				
DUCTS		R-6	R-6	R-6, TESTED	R-6	R-6, TESTED
SPACE COOLING (SEER)		12.0	10.5	12.0	11.0	12.0
HEAT	Elect. (HSPF)	7.9	7.1	7.4	7.4	7.4
	Gas/Oil (AFUE)	MINIMUM OF .73 (Direct heating) or .78 (Central)				
HOT WATER SYSTEM	Electric Resistance**	EF .88	NOT ALLOWED (SEE BELOW)	EF .91	NOT ALLOWED (SEE BELOW)	EF .91
	Gas & Oil **	MINIMUM EF OF .54				NATURAL GAS ONLY (SEE BELOW)
	Other	Any of the following are allowed: dedicated heat pump, heat recovery unit or solar system.				

* Single package units minimum SEER=9.7, HSPF = 6.6.

** Minimum efficiencies for gas and electric hot water systems apply to 40 gallon water heaters. Refer to Table 6-12 for minimum Code efficiencies for oil water heaters and other sizes.

DESCRIPTION OF BUILDING COMPONENTS LISTED

Percent of Glass to Floor Area: This percentage is calculated by dividing the total of all glass areas by the total conditioned floor area.

Overhang: The overhang is the distance the roof or soffit projects out horizontally from the face of the glass. All glass areas shall be under an overhang of at least the prescribed length with the following exceptions:

1) glass on the gabled ends of a house and 2) the glass in the lower stories of a multi-story house.

Wall, Ceiling and Floor Insulation Values: The R-values indicated represent the minimum acceptable insulation level added to the structural components of the wall, ceiling or floor. The R-value of the structural building materials shall not be included in this calculation. "Common" components are those separating conditioned tenancies in a multifamily building. "Adjacent" components separate conditioned space from unconditioned but enclosed space.

"Exterior" components separate conditioned space from unconditioned and unenclosed space.

Floor: Slab-on-grade floors without edge insulation are acceptable. Raised wood floors shall have continuous stem walls with insulation placed on the stem wall or under the floor except Package C.

Ducts: "TESTED" shall mean the ducts have less than 5% leakage based on a certified test report by a State-approved tester.

Space Cooling System: Cooling systems shall have a Seasonal Energy Efficiency Ratio (SEER) for central units or Energy Efficiency Ratio (EER) for room units or PTAC's equal to or greater than the prescribed value.

Electric Space Heating Option: Heat pump systems shall be rated with a Heating Seasonal Performance Factor (HSPF) equal to or greater than the prescribed HSPF. Heat pump systems may contain electric strip backups meeting the criteria of section 608.1.ABC.3.2.1.2. No electric resistance space heat is allowed for these packages.

Electric Resistance Hot Water Option: For packages designated "Not Allowed", an electric resistance hot water system may be installed only in conjunction with one of the "Other Hot Water System Options". See below.

Other Hot Water System Options: Any dedicated heat pump, heat recovery unit, or solar hot water system may be installed. Solar systems must have an EF of 1.5 or higher. Electric resistance systems having an EF of .88 or greater, or natural gas systems with EF .54 or greater may be used in conjunction with these systems.

TO BE INSTALLED	
DC: <input checked="" type="checkbox"/>	DT: <input type="checkbox"/>
2 FEET	
EXT: R =	
ADJ: R =	
COM: R =	
EXT: R = 13	
ADJ: R =	
COM: R =	
UNDER ATTIC: R = 30	
COMMON: R =	
R = 0	
R =	
R =	
R = 6 COND. <input type="checkbox"/>	
SEER = 12.0	
COP = 7.4	
AFUE =	
EF =	
EF =	
DHP: <input checked="" type="checkbox"/>	EF =
HRU: <input checked="" type="checkbox"/>	EF =
SOLAR: <input type="checkbox"/>	EF =


TABLE 6B-2 MINIMUM REQUIREMENTS FOR ALL PACKAGES

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Exterior Joints & Cracks	606.1	To be caulked, gasketed, weather-stripped or otherwise sealed.	<input checked="" type="checkbox"/>
Exterior Windows & Doors	606.1	Max .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	<input checked="" type="checkbox"/>
Sole & Top Plates	606.1	Sole plates and penetrations through top plates of exterior walls must be sealed.	<input checked="" type="checkbox"/>
Recessed Lighting	606.1	Type IC rated with no penetrations (two alternatives allowed).	<input checked="" type="checkbox"/>
Multi-story Houses	606.1	Air barrier on perimeter of floor cavity between floors.	<input checked="" type="checkbox"/>
Exhaust Fans	606.1	Exhaust fans vented to unconditioned space shall have dampers, except for combustion devices with integral exhaust ductwork.	<input checked="" type="checkbox"/>
Water Heaters	612.1	Comply with efficiency requirements in Table 6-12. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required for vertical pipe risers.	<input checked="" type="checkbox"/>
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have minimum thermal efficiency of 78%.	<input checked="" type="checkbox"/>
Hot Water Pipes	612.1	Insulation is required for hot water circulating systems (including heat recovery units).	<input checked="" type="checkbox"/>
Shower Heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	<input checked="" type="checkbox"/>
HVAC Duct Construction, Insulation & Installation	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated and installed in accordance with the criteria of Section 610.1. Ducts in attics must be insulated to a minimum of R-6.	<input checked="" type="checkbox"/>
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	<input checked="" type="checkbox"/>

Boozler


QTY

- 1.) (2) 90° CORNERS (BOTH GLAZED)
80" TAIL




- 2.) (2) 36" X 80" STORE FRONT

- 3.) (1) 84" X 72" STOREFRONT PENTAGON



- 4.) (2) 90° CORNERS (BOTH GLAZED)
80" TAIL




- 5.) (1) 84" X 80" STORE FRONT

- 6.) (2) 96" X 108" STORE FRONT

THIS MUST BE SPLIT
into 2 pcs.


- 7.) (2) 90° CORNERS (BOTH GLAZED)
108" TAIL





- 8.) (1) 84" X 108" STORE FRONT

THIS MUST BE
SPLIT INTO 2 PCS.

- 9.) (2) 60" X 48" STORE FRONT
1-LEFT 1-RIGHT





$\frac{1}{8}'' = 1' \text{ Foot}$
To Scale

386-454-0395

Chris Whitfield

11:22 AM 05 07:24

Compliance with Method B Chapter 6 of the Florida Energy Efficiency Code may be demonstrated by the use of Form 600B for single and multifamily residences of 3 stories or less in height, and additions to existing residential buildings. To comply, a building must meet or exceed all of the energy efficiency prescriptives in any one of the prescriptive component packages and comply with the prescriptive measures listed in Table 6B-1 of this form. An alternative method is provided for additions of 600 square feet or less by use of Form 600C. If a building does not comply with this method, it may still comply under other sections in Chapter 6 of the Code.

PROJECT NAME: AND ADDRESS:	Bishop White	BUILDER:		CLIMATE ZONE:	1 <input type="checkbox"/> 2 <input type="checkbox"/> 3 <input checked="" type="checkbox"/>
OWNER:	Ed & Diane Bishop White	PERMITTING OFFICE:	Columbia County	PERMIT NO.:	234111
				JURISDICTION NO.:	421000

GENERAL DIRECTIONS

1. New construction including additions which incorporates any of the following features cannot comply using this method: steel stud walls, single assembly roof/ceiling construction, or skylights or other non-vertical roof glass.
2. Choose one of the component packages "A" through "E" from Table 6B-1 by which you intend to comply with the Code. Circle the column of the package you have chosen.
3. Fill in all the applicable spaces of the "To Be Installed" column on Table 6B-1 with the information requested. All "To Be Installed" values must be equal to or more efficient than the required levels.
4. Complete page 1 based on the "To Be Installed" column information.
5. Read "Minimum Requirements for All Packages", Table 6B-2 and check each box to indicate your intent to comply with all applicable items.
6. Read, sign and date the "Prepared By" certification statement at the bottom of page 1. The owner or owner's agent must also sign and date the form.

Please Print

CK

1. Compliance package chosen (A-F)
2. New construction or addition
3. Single family detached or Multifamily attached
4. If Multifamily—No. of units covered by this submission
5. Is this a worst case? (yes / no)
6. Conditioned floor area (sq. ft.)
7. Predominant eave overhang (ft.)
8. Glass type and area :
 - a. Clear glass
 - b. Tint, film or solar screen
9. Percentage of glass to floor area
10. Floor type, area or perimeter, and insulation:
 - a. Slab on grade (R-value)
 - b. Wood, raised (R-value)
 - c. Wood, common (R-value)
 - d. Concrete, raised (R-value)
 - e. Concrete, common (R-value)
11. Wall type, area and insulation:
 - a. Exterior: 1. Masonry (Insulation R-value)
2. Wood frame (Insulation R-value)
 - b. Adjacent: 1. Masonry (Insulation R-value)
2. Wood frame (Insulation R-value)
12. Ceiling type, area and insulation:
 - a. Under attic (Insulation R-value)
 - b. Single assembly (Insulation R-value)
13. Air Distribution System: Duct insulation, location
Test report (attach if required)
14. Cooling system
(Types: central, room unit, package terminal A.C., gas, none)
15. Heating system:
(Types: heat pump, elec. strip, nat. gas, L.P. gas, gas h.p., room or PTAC, none)
16. Hot water system:
(Types: elec., nat. gas, L.P. gas, solar, heat rec., ded. heat pump, other, none)

1.	D	
2.	addition	
3.	sq. ft. form.	
4.		
5.	NO	
6.	3044	
7.	3	
	Single Pane	Double Pane
8a.	sq. ft.	sq. ft.
8b.	sq. ft.	634 sq. ft.
9.	20 %	
10a.	R= 0	lin. ft.
10b.	R=	sq. ft.
10c.	R=	sq. ft.
10d.	R=	sq. ft.
10e.	R=	sq. ft.
11a-1	R=	sq. ft.
11a-2	R= 11	1749 sq. ft.
11b-1	R=	sq. ft.
11b-2	R=	sq. ft.
12a.	R= 30	2440 sq. ft.
12b.	R=	sq. ft.
13.	R= 6	
14a.	Type: CENTRAL	
14b.	SEER/EER: 12.5	
14c.	Capacity: 5 Ton	
15a.	Type: Heat Pump	
15b.	HSPF/COP/AFUE:	
15c.	Capacity: 60K	
16a.	Type: Elect. HRV	
16b.	EF:	

I hereby certify that the plans and specifications covered by the calculation are in compliance with the Florida Energy Code.

PREPARED BY: [Signature] DATE: 6-6-05

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER AGENT: [Signature] DATE: 6-7-05

Review of plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed, this building will be inspected for compliance in accordance with Section 553.908, F.S.


BUILDING OFFICIAL: _____

DATE: _____

White Residence Boozler


QTY

- 1.) (2) 90° CORNERS (BOTH GLAZED)
80" TAIL




- 2.) (2) 36" X 80" STORE FRONT

- 3.) (1) 84" X 72" STOREFRONT PENTAGON



- 4.) (2) 90° CORNERS (BOTH GLAZED)
80" TAIL




- 5.) (1) 84" X 80" STORE FRONT

- 6.) (2) 96" X 108" STORE FRONT

THIS MUST BE Split
into 2 pcs.


- 7.) (2) 90° CORNERS (BOTH GLAZED)
108" TAIL





- 8.) (1) 84" X 108" STORE FRONT

THIS MUST BE
Split into 2 pcs.

- 9.) (2) 60" X 48" STORE FRONT
1-LEFT 1-RIGHT





1/8" = 1' Foot
To Scale

NOTICE OF COMMENCEMENT FORM
COLUMBIA COUNTY, FLORIDA

THE UNDERSIGNED hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

Parcel ID Number Part of 03-55-16-03445-001

Description of property: (legal description of the property and street address or 911 address)

7018 SW SR 47 Lake City, FL 32024

Inst:2005016124 Date:07/08/2005 Time:10:33

SLH DC, P. DeWitt Cason, Columbia County B:1051 P:653

General description of improvement: Single Family Dwelling

Owner Name & Address Ed and Diane White P.O. Box 28639

Atlanta, GA 30358

Interest in Property _____

Name & Address of Fee Simple Owner (if other than owner): _____

Contractor Name Isaac Construction, Inc.

Phone Number (386)-719-7143

Address 144 SW Waterford Ct. Lake City FL 32025

Surety Holders Name N/A

Phone Number _____

Address _____

Amount of Bond N/A

Lender Name N/A

Phone Number _____

Address _____

Persons within the State of Florida designated by the Owner upon whom notices or other documents may be served as provided by section 718.13 (1)(a) 7; Florida Statutes:

Name N/A

Phone Number _____

Address _____

In addition to himself/herself the owner designates N/A of

to receive a copy of the Lienor's Notice as provided in Section 713.13 (1) -

(a) 7. Phone Number of the designee _____

Expiration date of the Notice of Commencement (the expiration date is 1 (one) year from the date of recording,

(Unless a different date is specified): _____

NOTICE AS PER CHAPTER 713, Florida Statutes:

The owner must sign the notice of commencement and no one else may be permitted to sign in his/her stead.

Sworn to (or affirmed) and subscribed before
day of 12 July, 2005

NOTARY STAMP/SEAL

Ed and Diane White
Signature of Owner



Barbara C. Webster

Commission # DD329279

Expires July 2, 2008

Bonded Troy Pain - Insurance, Inc. 800-366-7019

Barbara C. Webster

Signature of Notary

ISAAC Construction Inc.

Remodel & Addition of a single family dwelling

Property owner Edward & Diane White

Application for building permit # 0506-88 date file 6/28/05

July 21, 2005 a meeting at the Columbia County Building Department with Robert Taylor (Associated Florida Architects Inc). Edward White (Property owner) Isaac Bratkovich (ISAAC Construction Inc.) Joe Haltiwanger (Columbia County Building Department Plan Examiner) to review structural plans as presented with application for permit number 0506-88.

July 22, 2005 Robert Taylor (Associated Florida Architects Inc) submits a letter of discovery, filed with application for permit number 0506-88.

July 22, 2005 Addendum Number One submitted from: Robert Taylor (Associated Florida Architects Inc) to application for permit number 0506-88.

July 25, 2005 Columbia County Building Department issues building permit to ISAAC Construction Inc. Permit number 23411

August 09, 2005 Temporary power service inspection by Randy Jones (Assistant Building Official) Passed inspection.

August 15, 2005 Rough plumbing inspection by Randy Jones (Assistant Building Official) Passed inspection

September 06, 2005 Foundation inspection (Monolithic Slab) for addition by Randy Jones (Assistant Building Official) Passed inspection.

September 06, 2005 Zoning land use setback inspection by Randy Jones (Assistant Building Official) Passed inspection.

December 13, 2005 Inspection of dwelling requested by owner Edward White, whom was present with Personal from Columbia County Building Department, Randy Jones Assistant Building Official, Harry Dicks Building Inspector and Joe Haltiwanger Plans Examiner. Performed inspection and photographed construction site.

December 15, 2005 a letter from the Columbia County Building Department was given to Mr. White and ISAAC Construction Inc. This letter included photographs and structural deficiency found on the date of the inspection. This letter also required a structural evaluation be preformed by a professional architect or engineer before continuing work on the dwelling.

July 25, 2006 building permit number 23411expries, no request by ISAAC Construction Inc. was made for an extension of the building permit.

July 28, 2006 the Columbia County Building Department received a hand delivered letter from Edward White to John Kerce Columbia County Building Official. This letter informed the building department that a professional engineer had made an inspection of the dwelling. This letter also requested that additional inspections be preformed by the Columbia County Building Department to take action of permit violations.

August 21, 2006 Letter from Edward White to John Kerce Columbia County Building Official was forwarded to Columbia County Attorney Marlin Feagle.

August 24, 2006 a letter from Columbia County Attorney Marlin Feagle to Columbia County plans examiner Joe Haltiwanger was received.

This letter informed Mr. White the process to renew the expired permit and the method to file a compliant with the Florida Department of Business and Professional Regulations due the contractor Isaac Bratkovich CBC059323 (ISAAC Construction Inc.) is licensed and regulate by the Florida Department of Business and Professional Regulations.

August 29, 2006 the Columbia County Attorney Marlin Feagle and Columbia County Building Department personal Randy Jones Assistant Building Official, Harry Dicks Building Inspector and Joe Haltiwanger Plans Examiner met with Mr. Edward White at the Columbia County Building Department office. A letter from William Freeman P.E. (Freeman Design Group Inc.) was presented, which detailed a structural inspection preformed by Mr. Freeman. This letter presented methods to correct structural problems and was placed into Mr. White file.

Columbia County Attorney Marlin Feagle presented to Mr. White methods to resolve the financial aspect of his request to the Columbia County Building Department. Mr. Feagle explained that Columbia County Building Department did not license or regulate Mr. Robert Taylor or Mr. Isaac Bratkovich, but the building department would contact the Florida Department of Business and Professional Regulations and assist this department after a formal complaint was filed by Mr. White with the Florida Department of Business and Professional Regulations.

August 30, 2006 Harry Dicks Building Inspector with the Columbia County Building Department spoke by phone to Mr. Jim Patton field investigator with the Florida Department of Business and Professional Regulations. Mr. Dicks discussed the request from Mr. White to the Columbia County Building Department. Mr. Patton advised Mr. Dicks that he would contact Mr. White and assist him in making any formal complaints to his department.

August 30, 2006 Mr. Jim Patton field investigator with the Florida Department of Business and Professional Regulations contacted Mr. Harry Dicks Columbia County Building Inspector by phone and advised that after contacting Mr. White by phone Mr. White at this date wish not to make any formal complaint to the Florida Department of Business and Professional Regulations on either Mr. Isaac Bratkovich or Mr. Robert Taylor.

Alpine Engineered Products, Inc.

1950 Marley Drive Haines City, FL 33844
Florida Engineering Certificate of Authorization Number: 567
Florida Certificate of Product Approval # FL1999
Page 1 of 1 Document ID:1SNC487-Z0125081043

Truss Fabricator: Anderson Truss Company
Job Identification: 5-214-ISAAC CONST/ED & DIANE WHITE - ROOF
Truss Count: 13
Model Code: Florida Building Code 2001
Truss Criteria: ANSI/TPI-1995
Engineering Software: Alpine Software, Version 7.04.
Structural Engineer of Record:
Address:
Minimum Design Loads: Roof - 40.0 PSF @ 1.25 Duration
Floor - N/A
Wind - 110 MPH ASCE 7-98 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1-1995 Section 2.2
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR487

Details: BRCLBSUB-A11015EC-GBLLETIN




Seal Date: 05/25/2005

-Truss Design Engineer-
Arthur R. Fisher
Florida License Number: 59687
1950 Marley Drive
Haines City, FL 33844

#	Ref	Description	Drawing#	Date
1	66515--A		05144001	05/24/05
2	66516--AS		05144002	05/24/05
3	66517--AGE		05144003	05/24/05
4	66518--B		05144004	05/24/05
5	66519--BS		05144005	05/24/05
6	66520--BGE		05144006	05/24/05
7	66521--C		05144007	05/24/05
8	66522--CGE		05144013	05/24/05
9	66523--M		05144008	05/24/05
10	66524--MGE		05144009	05/24/05
11	66525--ASGE		05144010	05/24/05
12	66526--T		05144011	05/24/05
13	66527--TGE		05144012	05/24/05






ISAAC CONSTRUCTION/
ED & DIANE WHITE /ROOF

DESIGNED BY:		JOB DESCRIPTION: ISAAC CONST/ED & DIANE WHITE	JOB LOCATION:
JOB NO: 5-214			
PAGE NO: 1 OF 1			

ISAAC CONSTRUCTION/
ED & DIANE WHITE
LOWER ROOF & JOISTS



EXISTING BUILDING

JOB LOCATION:	JOB DESCRIPTION: ISAAC CONST/ED & DIANE WHITE	DESIGNED BY:	JOB NO: 5-214A PAGE NO: 1 OF 1
---------------	--	--------------	---


OF 214 ISAAC CONST/ED & DIANE WHITE - ROOF - A)

1110 mph wind, 12.91 ft mean hgt., ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

	Top chord	2x4	SP #2	Dense
	Bot chord	2x4	SP #2	Dense
	Webbs	2x4	SP #3	Dense: W6, W16 2x4 SP #2 Dense:

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.

(**) Plate relocated as shown.



Notes: All plates are 3x4 Except As Shown.


PI T TYP Wave TPI

Periods Cwit. TDT-1995(STD)/FRC

702

Scale = .125"/Ft.

TC LL	20.0 PSF	REF R487 -- 66515
TC DL	10.0 PSF	DATE 05/24/05
BC DL	10.0 PSF	DRW HCURS487 05144001
BC LL	0.0 PSF	HC-ENG JB/AF
TOT.LD.	40.0 PSF	SEQN- 17112
DUR.FAC.	1.25	
SPACING	24.0"	JREF- 1SNC487_Z01

[illegible]


(5-214-ISAAC CONST/ED & DIANE WHITE - ROOF - AS)
Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3 :W14 2x4 SP #2 Dense:

(A) Continuous lateral bracing equally spaced on member.
Deflection meets L/360 live and L/240 total load.

(**) Plate relocated as shown.

110 mph wind, 12.91 ft mean hgt. ASCE 7-98, CLOSED bldg. Located anywhere in roof, CAT II, Exp B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.




Note: All Plates Are 3X4 Except As Shown.

PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

Scale = .125"/Ft.


REF	R487--	66516
DATE	05/24/05	
DRW	HCUSR487	05144002
HC-ENG	JB/AF	
SEQN	17128	
DUR.FAC.	1.25	
SPACING	24.0"	
JREF	1SNC487_Z01	



****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO RCES 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE STEEL INSTITUTE, 503 D'ONOFIO DR., SUITE 200, MADISON, WI 53719, AND AISC 308 (STEEL ERECTORS' HANDBOOK), PUBLISHED BY THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 530 N. DEARBORN AVE., CHICAGO, IL 60610, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ANY FAILURE TO BUILD THE TRUSS IN ACCORDANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLER. THE STEEL INSTITUTE, 503 D'ONOFIO DR., SUITE 200, MADISON, WI 53719, AND AISC 308 (STEEL ERECTORS' HANDBOOK), PUBLISHED BY THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 530 N. DEARBORN AVE., CHICAGO, IL 60610, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

ALPINE ENGINEERED PRODUCTS, INC.
1950 MARLEY DRIVE
334-444



Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

SPECIAL LOADS
----- (LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)
TC - From 81 PLF at -3.07 to 61 PLF at 46.12
TC - From 60 PLF at 46.12 to 4 PLF at 46.40
BC - From 4 PLF at -3.07 to 20 PLF at 43.33
BC - From 20 PLF at 0.00 to 20 PLF at 43.33
BC - From 4 PLF at 43.33 to 4 PLF at 46.40


(**) Plate relocated as shown.

110 mph wind, 12.66 ft mean ht, ASCE 7-98, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.

See DWGS A11015EN1103 & GBLLETIN1103 for more requirements.



Note: All Plates Are 1.5X4 Except As Shown.

Design Crit: TPI-1995(STD)/FBC


7.04.05

Scale = .125"/Ft.

REF	R487--	66517
DATE	05/24/05	
DRW	HCUSR487	05144003
HC-ENG	JB/AF	
SEON-	17159	
DUR.FAC.	1.25	
SPACING	24.0"	




PLT TYP. Wave TPI



ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THE DESIGN OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES, OR FOR ANY FAILURE TO BUILD THE TRUSSES IN ACCORDANCE WITH TPI OR AISC DESIGN SPEC. BY AISC AND TPI. ALPINE TRUSSES CONFORM WITH APPLICABLE PROVISIONS OF AISC (AISC 360) AND AISC 360-2. CORROSION RESISTANT TRUSSES ARE MADE OF 6061-T6 ALUMINUM. POSITION PER DRAWING 100A-2. PLATES TO EACH FACE OF TRUSS AND, UNLESS SHOWN OTHERWISE, SHALL BE PER AISC 360-2. ANY INSPECTION OF PLATES FOLLOWED BY VISUAL INSPECTION OF THE TRUSS COMPONENT DRAWING INDICATES ACCEPTANCE OF THE PROFESSIONAL ENGINEERING RESPONSIBILITY OF THE DESIGNER. THE SUSTAINABILITY OF THE TRUSS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER AISC 360-2.

(5-214-ISAAC CONST/ED & DIANE WHITE - ROOF - B)
Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3
Deflection meets L/360 live and L/240 total load.
(**) plate relocated as shown.

110 mph wind, 12.08 ft mean hgt, ASCE 7-98, CLOSED bldg. located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

Scale = .1875"/Ft.

REF R487-- 66518

DATE 05/24/05

DRW HCUSR487 0514004

HC-ENG JB/AF

SEQN- 17168

DUR.FAC. 1.25

SPACING 24.0"

JREF- 1SNC487_Z01

7.045083

FL/-/3/-/-/R/-

20.0 PSF

10.0 PSF

10.0 PSF

0.0 PSF

40.0 PSF

1.25

24.0"

ARTHUR R. FISHER

CERTIFICATE

No. 59887

STATE OF FLORIDA

PROFESSIONAL ENGINEER

May 25 '05

ALPINE

Alpine Engineered Products, Inc.

1950 Marley Drive

Fort Worth, TX 76104

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTALLATION), D'ONOFRIO DR., SUITE 200, MADISON, WI 53719, AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6000 W. 10TH AVE., SUITE 100, DENVER, CO 80202) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ANY FAILURE TO BUILD THE PRODUCTS SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. TRUSSES SHALL CONFORM WITH APPLICABLE PROVISIONS OF AISC (NATIONAL STEEL CONSTRUCTION INSTITUTE, 500 N. MICHIGAN, CHICAGO, IL 60610) AND TPI. CONNECTOR PLATES ARE MADE OF 20/107106A (0.4/5/3) ALUMINUM, GRADE 40/60 (0.4/5) GALV. STEEL. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE NOTED ON THIS DESIGN, POSITION PER DRAWING 100A.2. ANY INSPECTION OF PLATES FOLLOWED BY (1) VISUAL INSPECTION AND (2) MECHANICAL TESTING SHALL BE THE RESPONSIBILITY OF THE DESIGNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

(5-214-ISAAC CONST/ED & DIANE WHITE - ROOF - BS)


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

110 mph wind, 12.08 ft mean hgt, ASCE 7-98, CLOSED bldg, Located
anywhere in roof, CAT II, Exp B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

(A) Continuous lateral bracing equally spaced on member.

Deflection meets L/360 live and L/240 total load.

(**) Plate relocated as shown.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04



FL/-3/-1-/R/-

Scale = .1875"/Ft.

REF	R487--	66519
DATE	05/24/05	
DRW	HCUSR487	05144005
HC-ENG	JB/AF	
SEQN-	17180	
TOT.LD.	40.0 PSF	
DUR.FAC.	1.25	
SPACING	24.0"	
JREF-	1SNC487_Z01	

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ORFORD DR., SUITE 200, MADISON, WI 53719) AND AISC (AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 500 N. MICHIGAN, CHICAGO, IL 60611) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE SPECIFIED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATIONS FROM THE DESIGN OR FOR ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI. PROVIDE TO THE INSTALLATION CONTRACTOR A COPY OF THIS DESIGN AND TPI. DESIGN CONFORMS WITH AISC 360-10 (STEEL STRUCTURAL DESIGN SPECIFICATION) AND AISC 360-10 (STEEL STRUCTURAL DESIGN SPECIFICATION) WITH ADDITIONAL PROVISIONS OF AISC 360-10 (STEEL STRUCTURAL DESIGN SPECIFICATION) AND AISC 360-10 (STEEL STRUCTURAL DESIGN SPECIFICATION). ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER. SEE ANNEX A3 OF TPI-2002 SEC.3.



Top	chord	2x4	SP	#2	Dense
Bot	chord	2x4	SP	#2	Dense
	webs	2x4	SP	#3	

110 mph wind, 11.16 ft mean hgt., ASCE 7-98, CLOSED bldg. Located anywhere in roof. CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.


Deflection meets L/360 live and L/240 total load.

(**) Plate relocated as shown.

SPECIAL LOADS

SPECIAL LOADS		DUR. F.A.C. = 1.25 / PLATE DUR. F.A.C. = 1.25)	
--- (LUMBER			
TC	From	81 PLF at 3.07 to	41 PLF at 22.40
BC	From	4 PLF at 3.07 to	4 PLF at 0.00
BC	From	20 PLF at 0.00 to	20 PLF at 19.33
BC	From	4 PLF at 19.33 to	20 PLF at 19.33
BC	From	4 PLF at 19.33 to	4 PLF at 22.40

see DWGS A11015FN1103 & GBULLETIN1103 for more requirements.



Note: All Plates Are 1.5X4 Except As Shown.

PIT TYP. Wave TPI

Design Crit: TPI-1995 (STD) / FBC


FI 1-131-1-1R/-

Scale = .25"/Ft.

Design CR-1: IPI-1993/03/07/06

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO PCS1 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY IPI (TRUSS PLATE INSTITUTE, 583 D'ORPHEUS DR., SUITE 200, MADISON, WI 53719) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE IN. MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED BRACE. SEE DETAIL C7E11.ING.

**** IMPORTANT **** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERING, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE PRESS IN CONFORMANCE WITH THIS DESIGN, FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF THIS PRESS DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF 803 CMR (SECTION 8.00) AND 609 CMR (8.00), STEEL, CONSTRUCTION, AND 803 CMR (SECTION 8.00) AND 609 CMR (8.00), STEEL, APPLY TO EACH CASE OF THIS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2 THROUGH 160A-5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN OF THE SEAM ON THE DRAWING INDICATES. ACCEPTANCE OF PROFESSIONAL ENGINEERING FOR THE DESIGN SHALL BE THE RESPONSIBILITY OF THE DESIGNING ENGINEER. THE CONTRACTOR FOR ANY BUILDING IS THE RESPONSIBILITY OF THE DESIGNING ENGINEER. SEE 211 CMR (SECTION 21.00) AND 609 CMR (8.00), STEEL.




May 25 '05

JREF- 1SNC487 Z01

110 mph wind, 11.41 ft mean hgt., ASCE 7-98, CLOSED bldg., Located anywhere in roof, CAT II, Exp B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

no deflection meets L/360 live and L/240 total load.

(**) Plate relocated as shown.



Notes: All plates are 3X4 except as shown.

PIT TYP. Wave TPI


Design Crit: TPI-1995 (STD) / FBC

Scale = .25"/ft.

TC LL	20.0 PSF	REF R487 - - 66521
TC DL	10.0 PSF	DATE 05/24/05
BC DL	10.0 PSF	DRW HCUR487 05144007
BC LL	0.0 PSF	HC-ENG JB/AF
TOT.LD.	40.0 PSF	SEON - 17206
DUR.FAC.	1.25	
SPACING	24.0"	JREF- 1SNC487_Z01

****WARNING**** TROSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BECSI 1-03 (BUILDING COMPONENT SAFETY INFORMATION), TROSS COUNCIL OF AMERICA, 6500 ENTERPRISE IN WILMINGTON, DE., SUITE 200, WILMINGTON, MI 48091 AND UTA (WOOD TROSS SYSTEMS, MI 52719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED TOP CHORD CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DETAILING OR DESIGN. DESIGNER: ARV FAILURE TO BUILD THE PRODUCTS IN CONFORMANCE WITH TP1. OR FABRICATION, INSTALLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN COMPONENTS WITH APPLICABLE PROVISIONS OF THE NATIONAL DESIGN SPEC., BY AFAPA) AND TP1. APPLY CONNECTOR PLATE) ARE HOLD OF TP1. OR FABRICATION, INSTALLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN COMPONENTS WITH APPLICABLE PROVISIONS OF THE NATIONAL DESIGN SPEC., BY AFAPA) AND TP1. APPLY PLATES TO EACH FACTOR. AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS FROM 2. AND THESE PRACTICES FOLLOWED BY (1) SHALL BE PER AMERX 43 OF TP1-9002 SEC.3. THE RESPONSIBILITY OF THE DESIGNER INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE DESIGN COMPONENTS SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER AM51/TP1 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844


Haines City, FL 33844
City of Authorization # 567

110 mph wind, 11.82 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.

(**) Plate relocated as shown.

THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.



Note: All Plates Are 1.5X4 Except As Shown.

PLT TYP. Wave TPI

Design Crit: $\text{TPI}-1995(\text{STD})/\text{FBC}$

7.

04.0805.131C

Scale = .1875"/Ft.

***WARNING:** THESE RESCUE EXERCISE CARP IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO RESCUE 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (CHASSIS PLATE INSTITUTE, 3812 E. WILSON DR., SUITE 200, MADISON, WI 53719), AND MICA (MOTOR TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE, LUCY MADISON, WI 53719) FOR SAFETY PRECAUTIONS PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED TOP CHORD SEALING.

[illegible]

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

May 25, 2005

JREF - 15NCA87 701

(5-214-ISAAC CONST/ED & DIANE WHITE - ROOF - M)


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Deflection meets L/360 live and L/240 total load.

(**) plate relocated as shown.

110 mph wind, 11.58 ft mean hgt., ASCE 7-98, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.



PLT TYP. Wave TPI	Design Crit: TPI-1995(STD)/FBC	7.04	FL/- /3/- /- /R/-	Scale = .375"/Ft.
PLT TYP. Wave TPI				REF R487 -- 66523
PLT TYP. Wave TPI				DATE 05/24/05
PLT TYP. Wave TPI				DRW HCUSR487 05144008
PLT TYP. Wave TPI				HC-ENG JB/AF
PLT TYP. Wave TPI				SEQN- 17228
PLT TYP. Wave TPI				JREF- 1SNC487_201

Professional Engineer
No. 59687
State of Florida
May 25 '05

ALPINE
Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO RCSS 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 1000 MADISON DR., SUITE 200, MADISON, WI 53719, AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, OTHERWISE INDICATED, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATIONS FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR ANY OTHER CODES, SPECIFICATIONS, OR STANDARDS, SHALL BE THE RESPONSIBILITY OF THE INSTALLER. DESIGN CONFORMS WITH APPLICABLE RCSS 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 1000 MADISON DR., SUITE 200, MADISON, WI 53719, AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, OTHERWISE INDICATED, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

110 mph wind, 11.32 ft mean hgt., ASCE 7-98, CLOSED bldg. Located everywhere in roof CAT II, Exp B. wind TC DL=5.0 psf, wind BC DL=5.0 psf.


Top	chord	2x4	SP	#2	Dense
Bot	chord	2x4	SP	#2	Dense
	webs	2x4	SP	#3	

SPECIAL LOADS

SPECIAL LOANS		DUR. FAC. = 1.25 / PLATE DUR. FAC. = 1.25	
(LUMBER)		81 PLF at	20 PLF at
TC	From	3.07 to	11.00
BC	From	3.07 to	11.00
RC	From	3.07 to	11.00

+ MEMBER TO BE Laterally Braced For Horizontal Wind Loads.
Bracing System To Be Designed And Furnished By Others.

See DWGS A11015EN1103 & GBLLETIN1103 for more requirements.



Note: All plates are 1.5X4 except as shown.

DIT TYP Wave TPI

Design Crit: TPI-1995 (STD) / FBC

Scale = .375"/Ft.


TC LL	20.0	PSF
TC DL	10.0	PSF
BC DL	10.0	PSF
BC LL	0.0	PSF
TOT.LD.	40.0	PSF
DUR.FAC.	1.25	
SPACING	24.0"	

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844


Haines City, FL 33844
EI Certificate of Authorization # 567

[illegible]

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THE DESIGN SPECIFICATIONS. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TP1 OR FABRICATING, OR INSTALLING, OR BRACING OF TRUSSES, ALPINE DESIGN SPEC., BY AEPAN AND TP1. ALPINE DESIGNER SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS. THE TRUSS SHALL BE DESIGNED TO SUPPORT THE TRUSS CONNECTOR PLATES WITH APPLICABLE PROVISIONS: AISC/AISI A563 GRADE 40 (60 A, 4/16-5/8) GALV. STEEL, 2" PLATES TO EACH CHORD. UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER AISC/AISI 1.5 SEC. 2.



GABLE DETAIL
FOR LET-IN VERTICALS




GABLE VERTICAL PLATE SIZES

VERTICAL LENGTH BETWEEN CHORDS	PLATE SIZE	IF PLATES OVERLAP*
LESS THAN 4' 0"	1X4 OR 2X3	2X8
GREATER THAN 4' 0", BUT LESS THAN 11' 6"	2X4	2X8
GREATER THAN 11' 6"	2X4	2X8

⊕ REFER TO ENGINEERED TRUSS DESIGN FOR PEAK, SPLICE, WEB AND HEEL PLATES.

* IF GABLE VERTICAL PLATES OVERLAP, USE A SINGLE PLATE TO SPAN THE WEB.

EXAMPLE:



TO CONVERT FROM "L" TO "T" REINFORCING MEMBERS, MULTIPLY "T" FACTOR BY LENGTH (BASED ON GABLE VERTICAL SPECIES, GRADE AND SPACING) FOR (1) 2X4 "L" BRACE, GROUP A, OBTAINED FROM THE APPROPRIATE ALPINE GABLE DETAIL FOR ASCE OR SBCCI WIND LOAD.

MAXIMUM ALLOWABLE "T" REINFORCED GABLE VERTICAL LENGTH IS 14' FROM TOP TO BOTTOM CHORD.

WEB LENGTH INCREASE W/ "T" BRACE

WIND SPEED AND MRH	"T" REINF. MBR. SIZE	SBCCI	ASCE
110 MPH	2x4	10 %	10 %
15 FT	2x6	40 %	50 %
110 MPH	2x4	10 %	10 %
30 FT	2x6	50 %	50 %
100 MPH	2x4	10 %	10 %
15 FT	2x6	30 %	50 %
100 MPH	2x4	10 %	10 %
30 FT	2x6	40 %	40 %
90 MPH	2x4	20 %	10 %
15 FT	2x6	20 %	40 %
90 MPH	2x4	10 %	10 %
30 FT	2x6	30 %	50 %
80 MPH	2x4	10 %	20 %
15 FT	2x6	10 %	30 %
80 MPH	2x4	20 %	10 %
30 FT	2x6	20 %	40 %
70 MPH	2x4	0 %	20 %
15 FT	2x6	0 %	20 %
70 MPH	2x4	10 %	20 %
30 FT	2x6	10 %	30 %

EXAMPLE:

ASCE WIND SPEED = 100 MPH

MEAN ROOF HEIGHT = 30 FT

GABLE VERTICAL = 24" O.C. SP #3

"T" REINFORCING MEMBER SIZE = 2X4

(1) 2X4 "L" BRACE LENGTH = 6' 7"

MAXIMUM "T" REINFORCED GABLE VERTICAL LENGTH

1.10 x 6' 7" = 7' 3"

PROVIDE CONNECTIONS FOR UPLIFT SPECIFIED ON THE ENGINEERED TRUSS DESIGN.

ATTACH EACH "T" REINFORCING MEMBER WITH

HAND DRIVEN NAILS:

10d COMMON TOENAILS AT 4" O.C. PLUS (4) 16d COMMON TOENAILS IN TOP

AND BOTTOM CHORD.

GUN DRIVEN NAILS - 0.131" X 3"

TOENAILS AT 4" O.C. PLUS (4) TOENAILS IN TOP AND BOTTOM CHORD.

THIS DETAIL TO BE USED WITH THE APPROPRIATE ALPINE GABLE DETAIL FOR ASCE OR SBCCI WIND LOAD.

ASCE 7-93 GABLE DETAIL DRAWINGS

A11015EN1103, A10015EN1103, A09015EN1103, A08015EN1103, A07015EN1103

A11030EN1103, A10030EN1103, A09030EN1103, A08030EN1103, A07030EN1103

ASCE 7-98 GABLE DETAIL DRAWINGS

A13015EC1103, A12015EC1103, A11015EC1103, A08515EC1103

A13030EC1103, A12030EC1103, A11030EC1103, A08530EC1103

SBCCI GABLE DETAIL DRAWINGS

S11015EN1103, S10015EN1103, S09015EN1103, S08015EN1103, S07015EN1103

S11030EN1103, S10030EN1103, S09030EN1103, S08030EN1103, S07030EN1103

SEE APPROPRIATE ALPINE GABLE DETAIL (ASCE OR SBCCI

WIND LOAD) FOR MAXIMUM UNREINFORCED GABLE


VERTICAL LENGTH

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC311-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 DODGEFRID DR., SUITE 200, MADISON, WI 53719), AND VTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/SP) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 6061-T6 ALUMINUM (AIA/SP) GRADE 40/60 (AIA/SP) GALV. STEEL. APPLY CONNECTOR PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF TRUSSES SHALL BE PERFORMED BY A QUALIFIED INSPECTOR. A PROFESSIONAL ENGINEER SHALL BE RESPONSIBLE FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER. PER ANSI/TPI 1 SEC. 2.



ALPINE ENGINEERED PRODUCTS, INC.
POMPAHO BEACH, FLORIDA



REPLACES DRAWINGS GAB98117 876.719 & HC26294035

REF LET-IN VERT

DATE 01/16/04

DRWG GBLTIN1103

-ENG DLJ/KAR

MAX TOT. LD. 60 PSF

DUR. FAC. ANY

MAX SPACING 24.0"

2X4 GABLE TRUSS		BRACE		NO BRACES		(1) 1X4 "L" BRACE		(2) 2X4 "L" BRACE		(1) 2X6 "L" BRACE		(2) 2X6 "L" BRACE		MAX GABLE VERTICAL LENGTH	
		GABLE VERTICAL SPACING	GRADE	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B		
24" O.C.		SPF	#1 / #2	6' 8"	6' 10"	7' 11"	8' 1"	9' 5"	9' 8"	12' 5"	12' 9"	14' 0"	14' 0"		
		HF	STUD	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 3"	12' 4"	14' 0"	14' 0"		
		SP	STANDARD	5' 2"	5' 2"	6' 9"	6' 9"	9' 1"	9' 1"	10' 7"	10' 7"	14' 0"	14' 0"		
		DFL	#1	6' 8"	7' 2"	7' 11"	8' 6"	9' 5"	10' 2"	12' 5"	13' 5"	14' 0"	14' 0"		
16" O.C.		SP	#2	6' 2"	6' 2"	7' 11"	8' 1"	9' 5"	10' 2"	12' 5"	13' 5"	14' 0"	14' 0"		
		HF	#3	6' 2"	6' 2"	7' 11"	8' 1"	9' 5"	10' 2"	12' 5"	13' 5"	14' 0"	14' 0"		
		SP	STUD	5' 3"	5' 3"	6' 11"	6' 11"	9' 4"	9' 4"	10' 10"	10' 10"	14' 0"	14' 0"		
		DFL	#1 / #2	7' 4"	7' 4"	9' 1"	9' 1"	10' 10"	10' 10"	14' 0"	14' 0"	14' 0"	14' 0"		
12" O.C.		SPF	#3	7' 4"	7' 4"	9' 1"	9' 1"	10' 10"	10' 10"	14' 0"	14' 0"	14' 0"	14' 0"		
		HF	STANDARD	6' 4"	6' 4"	8' 4"	8' 4"	10' 10"	10' 10"	12' 11"	12' 11"	14' 0"	14' 0"		
		SP	#1	7' 8"	8' 3"	9' 1"	9' 9"	10' 10"	11' 8"	14' 0"	14' 0"	14' 0"	14' 0"		
		DFL	#2	7' 7"	7' 7"	9' 1"	9' 6"	10' 10"	11' 4"	14' 0"	14' 0"	14' 0"	14' 0"		
MAX GABLE VERTICAL LENGTH		SPF	#3	6' 5"	6' 5"	8' 6"	8' 6"	10' 10"	11' 1"	13' 3"	13' 3"	14' 0"	14' 0"		
		HF	STUD	8' 5"	8' 5"	10' 0"	10' 0"	11' 11"	11' 11"	14' 0"	14' 0"	14' 0"	14' 0"		
		SP	#1 / #2	8' 5"	8' 5"	10' 0"	10' 0"	11' 11"	11' 11"	14' 0"	14' 0"	14' 0"	14' 0"		
		DFL	STANDARD	7' 3"	7' 3"	9' 7"	9' 7"	11' 11"	11' 11"	14' 0"	14' 0"	14' 0"	14' 0"		
MAX GABLE VERTICAL LENGTH		SPF	#2	8' 5"	8' 5"	10' 0"	10' 0"	11' 11"	11' 11"	14' 0"	14' 0"	14' 0"	14' 0"		
		HF	#3	8' 5"	8' 5"	10' 0"	10' 0"	11' 11"	11' 11"	14' 0"	14' 0"	14' 0"	14' 0"		
		SP	STUD	8' 5"	8' 5"	10' 0"	10' 0"	11' 11"	11' 11"	14' 0"	14' 0"	14' 0"	14' 0"		
		DFL	STANDARD	7' 5"	7' 5"	9' 10"	9' 10"	11' 11"	12' 3"	14' 0"	14' 0"	14' 0"	14' 0"		

BRACING GROUP SPECIES AND GRADES:			
GROUP A:			
SPRUCE-PINE-FIR		HEM-FIR	
#1 / #2	STANDARD	#2	STUD
#3		#3	STANDARD
GROUP B:			
DOUGLAS FIR-LARCH		SOUTHERN PINE	
#3	STUD	#3	STUD
STANDARD			STANDARD

DOUGLAS FIR-LARCH		SOUTHERN PINE	
#1	#2	#1	#2
#1 & BTR			

GABLE TRUSS DETAIL NOTES:

LIVE LOAD DEFLECTION CRITERIA IS L/240.

PROVIDE UPLIFT CONNECTIONS FOR 80 PLF OVER CONTINUOUS BEARING (5 PSF TC DEAD LOAD).

GABLE END SUPPORTS LOAD FROM 4' 0" OUTLOOKERS WITH 2' 0" OVERHANG, OR 12" PLYWOOD OVERHANG.

ATTACH EACH "L" BRACE WITH 10d NAILS


* FOR (1) "L" BRACE: SPACE NAILS AT 2' 0" O.C. IN 18" END ZONES AND 4' 0" O.C. BETWEEN ZONES.

** FOR (2) "L" BRACES: SPACE NAILS AT 3' 0" O.C. IN 18" END ZONES AND 6' 0" O.C. BETWEEN ZONES.


"L" BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

GABLE VERTICAL PLATE SIZES	
VERTICAL LENGTH	NO SPLICE
LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0" BUT LESS THAN 11' 6"	2X4
GREATER THAN 11' 6"	2.5X4

+ REFER TO COMMON TRUSS DESIGN FOR
PEAK, SPLICE, AND HEEL PLATES.



REFER TO CHART ABOVE FOR MAXIMUM BRACE LENGTH.



ALPINE

ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 I-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI TRUSS & PLATE INSTITUTE, 983 DUNDAS RD., SUITE 200, MADISON, WI 53719, AND TPI TRUSS & PLATE INSTITUTE OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719, FOR SPECIFIC INSTRUCTIONS PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, ALL TRUSS CHORDS SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR APPLICABLE PROVISIONS OF THE NATIONAL DESIGN SPEC. BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE NATIONAL DESIGN SPEC. BY AEP&P AND TPI. ALPINE ENGINEERED PRODUCTS ARE MADE OF 20/18/16/14/12/10/8/6/4/2/1/0/1/2/3/4/5/6/7/8/9/10/11/12/13/14/15/16/17/18/19/20/21/22/23/24/25/26/27/28/29/30/31/32/33/34/35/36/37/38/39/40/41/42/43/44/45/46/47/48/49/50/51/52/53/54/55/56/57/58/59/60/61/62/63/64/65/66/67/68/69/70/71/72/73/74/75/76/77/78/79/80/81/82/83/84/85/86/87/88/89/90/91/92/93/94/95/96/97/98/99/100/101/102/103/104/105/106/107/108/109/110/111/112/113/114/115/116/117/118/119/120/121/122/123/124/125/126/127/128/129/130/131/132/133/134/135/136/137/138/139/140/141/142/143/144/145/146/147/148/149/150/151/152/153/154/155/156/157/158/159/160/161/162/163/164/165/166/167/168/169/170/171/172/173/174/175/176/177/178/179/180/181/182/183/184/185/186/187/188/189/190/191/192/193/194/195/196/197/198/199/200/201/202/203/204/205/206/207/208/209/210/211/212/213/214/215/216/217/218/219/220/221/222/223/224/225/226/227/228/229/230/231/232/233/234/235/236/237/238/239/240/241/242/243/244/245/246/247/248/249/250/251/252/253/254/255/256/257/258/259/260/261/262/263/264/265/266/267/268/269/270/271/272/273/274/275/276/277/278/279/280/281/282/283/284/285/286/287/288/289/290/291/292/293/294/295/296/297/298/299/300/301/302/303/304/305/306/307/308/309/310/311/312/313/314/315/316/317/318/319/320/321/322/323/324/325/326/327/328/329/330/331/332/333/334/335/336/337/338/339/340/341/342/343/344/345/346/347/348/349/350/351/352/353/354/355/356/357/358/359/360/361/362/363/364/365/366/367/368/369/370/371/372/373/374/375/376/377/378/379/380/381/382/383/384/385/386/387/388/389/390/391/392/393/394/395/396/397/398/399/400/401/402/403/404/405/406/407/408/409/410/411/412/413/414/415/416/417/418/419/420/421/422/423/424/425/426/427/428/429/430/431/432/433/434/435/436/437/438/439/440/441/442/443/444/445/446/447/448/449/450/451/452/453/454/455/456/457/458/459/460/461/462/463/464/465/466/467/468/469/470/471/472/473/474/475/476/477/478/479/480/481/482/483/484/485/486/487/488/489/490/491/492/493/494/495/496/497/498/499/500/501/502/503/504/505/506/507/508/509/510/511/512/513/514/515/516/517/518/519/520/521/522/523/524/525/526/527/528/529/530/531/532/533/534/535/536/537/538/539/540/541/542/543/544/545/546/547/548/549/550/551/552/553/554/555/556/557/558/559/560/561/562/563/564/565/566/567/568/569/570/571/572/573/574/575/576/577/578/579/580/581/582/583/584/585/586/587/588/589/590/591/592/593/594/595/596/597/598/599/600/601/602/603/604/605/606/607/608/609/610/611/612/613/614/615/616/617/618/619/620/621/622/623/624/625/626/627/628/629/630/631/632/633/634/635/636/637/638/639/640/641/642/643/644/645/646/647/648/649/650/651/652/653/654/655/656/657/658/659/660/661/662/663/664/665/666/667/668/669/670/671/672/673/674/675/676/677/678/679/680/681/682/683/684/685/686/687/688/689/690/691/692/693/694/695/696/697/698/699/700/701/702/703/704/705/706/707/708/709/710/711/712/713/714/715/716/717/718/719/720/721/722/723/724/725/726/727/728/729/730/731/732/733/734/735/736/737/738/739/740/741/742/743/744/745/746/747/748/749/750/751/752/753/754/755/756/757/758/759/760/761/762/763/764/765/766/767/768/769/770/771/772/773/774/775/776/777/778/779/780/781/782/783/784/785/786/787/788/789/790/791/792/793/794/795/796/797/798/799/800/801/802/803/804/805/806/807/808/809/810/811/812/813/814/815/816/817/818/819/820/821/822/823/824/825/826/827/828/829/830/831/832/833/834/835/836/837/838/839/840/841/842/843/844/845/846/847/848/849/850/851/852/853/854/855/856/857/858/859/860/861/862/863/864/865/866/867/868/869/870/871/872/873/874/875/876/877/878/879/880/881/882/883/884/885/886/887/888/889/890/891/892/893/894/895/896/897/898/899/900/901/902/903/904/905/906/907/908/909/910/911/912/913/914/915/916/917/918/919/920/921/922/923/924/925/926/927/928/929/930/931/932/933/934/935/936/937/938/939/940/941/942/943/944/945/946/947/948/949/950/951/952/953/954/955/956/957/958/959/960/961/962/963/964/965/966/967/968/969/970/971/972/973/974/975/976/977/978/979/980/981/982/983/984/985/986/987/988/989/990/991/992/993/994/995/996/997/998/999/1000/1001/1002/1003/1004/1005/1006/1007/1008/1009/1010/1011/1012/1013/1014/1015/1016/1017/1018/1019/1020/1021/1022/1023/1024/1025/1026/1027/1028/1029/1030/1031/1032/1033/1034/1035/1036/1037/1038/1039/1040/1041/1042/1043/1044/1045/1046/1047/1048/1049/1050/1051/1052/1053/1054/1055/1056/1057/1058/1059/1060/1061/1062/1063/1064/1065/1066/1067/1068/1069/1070/1071/1072/1073/1074/1075/1076/1077/1078/1079/1080/1081/1082/1083/1084/1085/1086/1087/1088/1089/1090/1091/1092/1093/1094/1095/1096/1097/1098/1099/1100/1101/1102/1103/1104/1105/1106/1107/1108/1109/1110/1111/1112/1113/1114/1115/1116/1117/1118/1119/1120/1121/1122/1123/1124/1125/1126/1127/1128/1129/1130/1131/1132/1133/1134/1135/1136/1137/1138/1139/1140/1141/1142/1143/1144/1145/1146/1147/1148/1149/1150/1151/1152/1153/1154/1155/1156/1157/1158/1159/1160/1161/1162/1163/1164/1165/1166/1167/1168/1169/1170/1171/1172/1173/1174/1175/1176/1177/1178/1179/1180/1181/1182/1183/1184/1185/1186/1187/1188/1189/1190/1191/1192/1193/1194/1195/1196/1197/1198/1199/1200/1201/1202/1203/1204/1205/1206/1207/1208/1209/1210/1211/1212/1213/1214/1215/1216/1217/1218/1219/1220/1221/1222/1223/1224/1225/1226/1227/1228/1229/1230/1231/1232/1233/1234/1235/1236/1237/1238/1239/1240/1241/1242/1243/1244/1245/1246/1247/1248/1249/1250/1251/1252/1253/1254/1255/1256/1257/1258/1259/1260/1261/1262/1263/1264/1265/1266/1267/1268/1269/1270/1271/1272/1273/1274/1275/1276/1277/1278/1279/1280/1281/1282/1283/1284/1285/1286/1287/1288/1289/1290/1291/1292/1293/1294/1295/1296/1297/1298/1299/1300/1301/1302/1303/1304/1305/1306/1307/1308/1309/1310/1311/1312/1313/1314/1315/1316/1317/1318/1319/1320/1321/1322/1323/1324/1325/1326/1327/1328/1329/1330/1331/1332/1333/1334/1335/1336/1337/1338/1339/1340/1341/1342/1343/1344/1345/1346/1347/1348/1349/1350/1351/1352/1353/1354/1355/1356/1357/1358/1359/1360/1361/1362/1363/1364/1365/1366/1367/1368/1369/1370/1371/1372/1373/1374/1375/1376/1377/1378/1379/1380/1381/1382/1383/1384/1385/1386/1387/1388/1389/1390/1391/1392/1393/1394/1395/1396/1397/1398/1399/1400/1401/1402/1403/1404/1405/1406/1407/1408/1409/1410/1411/1412/1413/1414/1415/1416/1417/1418/1419/1420/1421/1422/1423/1424/1425/1426/1427/1428/1429/1430/1431/1432/1433/1434/1435/1436/1437/1438/1439/1440/1441/1442/1443/1444/1445/1446/1447/1448/1449/1450/1451/1452/1453/1454/1455/1456/1457/1458/1459/1460/1461/1462/1463/1464/1465/1466/1467/1468/1469/1470/1471/1472/1473/1474/1475/1476/1477/1478/1479/1480/1481/1482/1483/1484/1485/1486/1487/1488/1489/1490/1491/1492/1493/1494/1495/1496/1497/1498/1499/1500/1501/1502/1503/1504/1505/1506/1507/1508/1509/1510/1511/1512/1513/1514/1515/1516/1517/1518/1519/1520/1521/1522/1523/1524/1525/1526/1527/1528/1529/1530/1531/1532/1533/1534/1535/1536/1537/1538/1539/1540/1541/1542/1543/1544/1545/1546/1547/1548/1549/1550/1551/1552/1553/1554/1555/1556/1557/1558/1559/1560/1561/1562/1563/1564/1565/1566/1567/1568/1569/1570/1571/1572/1573/1574/1575/1576/1577/1578/1579/1580/1581/1582/1583/1584/1585/1586/1587/1588/1589/1590/1591/1592/1593/1594/1595/1596/1597/1598/1599/1600/1601/1602/1603/1604/1605/1606/1607/1608/1609/1610/1611/1612/1613/1614/1615/1616/1617/1618/1619/1620/1621/1622/1623/1624/1625/1626/1627/

CLB WEB BRACE SUBSTITUTION

THIS DETAIL IS TO BE USED WHEN CONTINUOUS LATERAL BRACING (CLB) IS SPECIFIED ON AN ALPINE TRUSS DESIGN BUT AN ALTERNATIVE WEB BRACING METHOD IS DESIRED.

NOTES:

THIS DETAIL IS ONLY APPLICABLE FOR CHANGING THE SPECIFIED CLB SHOWN ON SINGLE PLY SEALED DESIGNS TO T-BRACING OR SCAB BRACING.

ALTERNATIVE BRACING SPECIFIED IN CHART BELOW MAY BE CONSERVATIVE. FOR MINIMUM ALTERNATIVE BRACING, RE-RUN DESIGN WITH APPROPRIATE BRACING.

WEB MEMBER SIZE	SPECIFIED CLB BRACING	T OR L-BRACE	ALTERNATIVE BRACING SCAB BRACE
2X3 OR 2X4	1 ROW	2X4	1-2X4
2X3 OR 2X4	2 ROWS	2X6	2-2X4
2X6	1 ROW	2X4	1-2X6
2X6	2 ROWS	2X6	2-2X4(*)
2X8	1 ROW	2X6	1-2X8
2X8	2 ROWS	2X6	2-2X6(*)

T-BRACE, L-BRACE AND SCAB BRACE TO BE SAME SPECIES AND GRADE OR BETTER THAN WEB MEMBER UNLESS SPECIFIED OTHERWISE ON ENGINEER'S SEALED DESIGN.

(*) CENTER SCAB ON WIDE FACE OF WEB. APPLY (1) SCAB TO EACH FACE OF WEB.




ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 DODDRIED DR., SUITE 200, MADISON, WI 53719) AND WTC (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONTRACTORS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (A/H/S/X) ASTM A653 GRADE 40/50 (A/H/S/X) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (C) SHALL BE PER ANNEX A3 OF TPI 1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF THE PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUSTAINABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER. PER ANSI/TPI 1 SEC. 2.


T-BRACING
OR
L-BRACING:

APPLY TO EITHER SIDE OF WEB
NARROW FACE
ATTACH WITH 16d NAILS AT 6" O.C.
BRACE IS A MINIMUM 80% OF WEB
MEMBER LENGTH



SCAB BRACING:

APPLY SCAB(S) TO WIDE FACE OF WEB.
NO MORE THAN (1) SCAB PER FACE.
ATTACH WITH 10d OR .128"x3" GUN
NAILS AT 6" O.C. BRACE IS A MINIMUM
80% OF WEB MEMBER LENGTH



THIS DRAWING REPLACES DRAWING 579.640

TC LL	PSF	REF	CLB SUBST.
TC DL	PSF	DATE	11/26/03
BC DL	PSF	DRWG	BRCLEBSUB1103
BC LL	PSF	-ENG	MLH/KAR
TOT. LD.	PSF		
DUR. FAC.			
SPACING			

Top	chord	2x4	Sp	#2	Dense
Bot	chord	2x4	Sp	#2	Dense
	webs	2x4	Sp	#3	


SPECIAL LOADS

SPECIAL LOADS		----- (LUMBER)		DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25	
TC	- From	81	PLF at -3.07	to	81 PLF at 28.74
BC	- From	4	PLF at -3.07	to	4 PLF at -2.77
BC	- From	24	PLF at -2.77	to	24 PLF at 0.00
BC	- From	20	PLF at 0.00	to	20 PLF at 25.67
BC	- From	24	PLF at 25.67	to	24 PLF at 28.43
BC	- From	4	PLF at 28.43	to	4 PLF at 28.74

110 mph wind, 22.55 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.

Shim all supports to solid bearing.



Note: All Plates Are 3X4 Except As Shown.

PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

4508

Scale = .1875"/Ft.

TC LL	20.0 PSF	REF R487 - - 66527
TC DL	10.0 PSF	DATE 05/24/05
BC DL	10.0 PSF	DRW HCUSR487 05144012
BC LL	0.0 PSF	HC-ENG JB/AF
TOT.LD.	40.0 PSF	SEQN - 17305
DUR.FAC.	1.25	



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

*WARNING** TROSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. TO ACCESS FIG. 1-101 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 583 MADISON, ST. LOUIS, MISSOURI 63103, CALL (314) 527-1919. AND AISC (AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC.), 1801 MARKET STREET, PITTSBURGH, PENNSYLVANIA 15222, CALL (412) 328-7145. FOR SAFETY INFORMATION, SEE FIG. 1-101. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED CONNECTIONS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID JOINTS.

*IMPORTANT- FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPHINE ENGINEERING, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISC (NATIONAL DESIGN SPEC. BY AISC) AND TPI. ALPHINE ENGINEERING, INC. HAS BEEN LICENSED UNDER U.S. PATENT NO. 4,870,690 (U.S. PAT. NO. 4,870,690). APPLY TO EACH FACE OF TRUSS AND OTHER MEMBERS. STAINLESS GRADE 304/304 L (U.S. PAT. NO. 4,870,690). STEEL PLATES TO EACH FACE OF TRUSS AND OTHER MEMBERS. UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE PER SECTION 3. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A OF TPI-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE DESIGNER.


May 25 1965

Top chord	2x4	SP	#2	Dense
Bot chord	2x4	SP	#2	Dense
Webbs	2x4	SP	#3	

110 mph wind, 22.81 ft mean hgt., ASCE 7-98, CLOSED bldg. Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.

Shim all supports to solid bearing.




Note: All Plates Are 3X4 Except As Shown.

PLT TYP. Wave TPI

Design Crit: TPI-1995 (STD)/FBC

Scale = .1875"/Ft.

TC LL	20.0 PSF	REF R487 - - 66526
TC DL	10.0 PSF	DATE 05/24/05
BC DL	10.0 PSF	DRW HCUSR487 05144011
BC LL	0.0 PSF	HC-ENG JB/AF
TOT.LD.	40.0 PSF	SEQN- 17297
DUR.FAC.	1.25	

[illegible]

Ed + Diane White

COLUMBIA COUNTY BUILDING DEPARTMENT

RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR FLORIDA BUILDING CODE 2001

ONE (1) AND TWO (2) FAMILY DWELLINGS

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

EFFECTIVE MARCH 1, 2002

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 1606 OF THE FLORIDA BUILDING CODE 2001 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1606 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE ----- 110 MPH
3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERAL REQUIREMENTS: Two (2) complete sets of plans containing the following:

Applicant

Plans Examiner



All drawings must be clear, concise and drawn to scale ("Optional" details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.



Designers name and signature on document (FBC 104.2.1). If licensed architect or engineer, official seal shall be affixed.



Site Plan including:

- a) Dimensions of lot
- b) Dimensions of building set backs
- c) Location of all other buildings on lot, well and septic tank if applicable, and all utility easements.
- d) Provide a full legal description of property.



Wind-load Engineering Summary, calculations and any details required

- a) Plans or specifications must state compliance with FBC Section 1606
- b) The following information must be shown as per section 1606.1.7 FBC
 - a. Basic wind speed (MPH)
 - b. Wind importance factor (I) and building category
 - c. Wind exposure - if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated
 - d. The applicable internal pressure coefficient
 - e. Components and Cladding. The design wind pressure in terms of psf (kN/m²), to be used for the design of exterior component and cladding materials not specifically designed by the registered design professional



Elevations including:

- a) All sides
- b) Roof pitch
- c) Overhang dimensions and detail with attic ventilation
- d) Location, size and height above roof of chimneys
- e) Location and size of skylights
- f) Building height
- e) Number of stories



c. Crawl space (if applicable)

☐ ☐ b) Wood frame wall

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termitecide or alternative method)
11. Slab on grade
 - a. Vapor retarder (6Mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

☐ ☐ c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)

Floor Framing System:

- a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer
- b) Floor joist size and spacing
- c) Girder size and spacing
- d) Attachment of joist to girder
- e) Wind load requirements where applicable

Plumbing Fixture layout

Electrical layout including:

- a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified
- b) Ceiling fans
- c) Smoke detectors
- d) Service panel and sub-panel size and location(s)
- e) Meter location with type of service entrance (overhead or underground)
- f) Appliances and HVAC equipment

HVAC information

- a) Manual J sizing equipment or equivalent computation
- b) Exhaust fans in bathroom

Energy Calculations (dimensions shall match plans)

Gas System Type (LP or Natural) Location and BTU demand of equipment

Disclosure Statement for Owner Builders

Notice Of Commencement

Private Potable Water

- a) Size of pump motor
- b) Size of pressure tank
- c) Cycle stop valve if used

XX

Glazed Outswing Unit

COP-WL-JH4162-02

WOOD-EDGE STEEL DOORS

APPROVED DOOR STYLES:**3/4 GLASS:**


404 Series





410 Series



450 Series

FULL GLASS:


109 Series

114, 120, 122
Series

152 Series



149 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1864-5, 6, 7, 8; NCTL 210-2178-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum bumper threshold.

PRODUCT COMPLIANCE LABELING:TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. - License Number 56533

Johnson
EntrySystems

March 29, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.




Exclusively from

Masonite
Masonite International Corporation

XX

Glazed Outswing Unit

COP-WL-JH4162-02

WOOD-EDGE STEEL DOORS**APPROVED ARRANGEMENT:****Note:**

Units of other sizes are covered by this report as long as the panels used do not exceed 3'0" x 6'8".

Double Door

Maximum unit size = 6'0" x 6'8"

Design Pressure**+40.5/-40.5**

Limited water unless special threshold design is used.

Large Missile Impact Resistance**Hurricane protective system (shutters) is REQUIRED.**

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed – see MAD-WL-MA0012-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed – see MID-WL-MA0002-02.

APPROVED DOOR STYLES:**1/4 GLASS:**

100 Series



133, 135 Series



136 Series



680 Series



822 Series

1/2 GLASS:

105 Series*



106, 160 Series*




129 Series*



200 Series*

12 R/L, 23 R/L, 24 R/L
Series*

107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

Johnson
EntrySystems

March 29, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.

PREMDOR Collection
Premium Quality Doors




Exclusively from

Masonite


Masonite International Corporation

OUTSWING UNITS WITH DOUBLE DOOR


TYPICAL HINGE ATTACHMENT




TYPICAL ASTRAGAL PROFILES




ALUMINUM EXTRUDED ASTRAGAL (0.06" MINIMUM WALL THICKNESS) WITH ADDED REINFORCEMENT INSERTS AT TOP EXTENSION BOLT, BOTTOM EXTENSION BOLT AND CYLINDRICAL/DEADBOLT LATCHING LOCATIONS. ATTACH WITH #8 X 1" PAN HEAD SCREWS - LOCATE 1" FROM EACH END MINIMUM AND 22" O.C. MAXIMUM.




TYPICAL HEADER & SIDE JAMB ATTACHMENT



TYPICAL THRESHOLD & SIDE JAMB ATTACHMENT



DOUBLE DOOR



Minimum Fastener Count

- 6 per vertical framing member
- 8 per horizontal framing member

Hinge and strike plates require two 2-1/2" long screws per location.

Latching Hardware:

- Compliance requires that GRADE 2 or better (ANSI/BHMA A156.2) cylindrical and deadlock hardware be installed.

Notes:

1. Anchor calculations have been carried out with the lowest (least) fastener rating from the different fasteners being considered for use. Fasteners analyzed for this unit include #8 and #10 wood screws or 3/16" Tapcons.
2. The wood screw single shear design values come from Table 11.3A of ANSI/AF & PA NDS for southern pine lumber with a side member thickness of 1-1/4" and achievement of minimum embedment. The 3/16" Tapcon single shear design values come from the ITW and ELCO Dade County approvals respectively, each with minimum 1-1/4" embedment.
3. Wood bucks by others, must be anchored properly to transfer loads to the structure.

March 29, 2002


Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.




Exclusively from

Masonite®
Masonite International Corporation

GLASS INSERT IN DOOR OR SIDELITE PANEL



SECTION A-A TYPICAL RIGID PLASTIC LIP LITE SURROUND



March 29, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.

PREMIER Collection
Premium Quality Doors

Exclusively from
Masonite
Masonite International Corporation

THIS DOCUMENT WAS PREPARED WITHOUT BENEFIT
OF TITLE SEARCH.

FOR RECORDER

THIS INSTRUMENT WAS PREPARED BY:
Krista L. Waldron, Esquire (PES)
Fisher, Tousey, Leas & Ball, P.A.
818 North A1A, Suite 104
Ponte Vedra Beach, Florida 32082

Inst: 2003008855 Date: 04/29/2003 Time: 09:29

cc Stamp-Deed : 0.70

WCK DC, P. DeWitt Cason, Columbia County B:981 P:2183

SPECIAL WARRANTY DEED

THIS INDENTURE, made this 28 day of APRIL, 2003, between VIRGINIA H. BISHOP, as Trustee of the Virginia H. Bishop Living Trust, whose address is P. O. Box 1298, Lake City, Florida 32056, party of the first part, and **EDWARD C. WHITE, JR. and DIANE B. WHITE**, husband and wife, whose address is 80 Cliffcreek Trace, Atlanta, Georgia 30350, parties of the second part.

WITNESSETH:

That the said party of the first part, in consideration of love and affection, has granted, bargained, and conveyed to the said parties of the second part, their heirs, successors and assigns forever, her remaining one-half interest in the following described lands, situate, lying and being in Columbia County, Florida, to wit:

Commence at the Southwest Corner of the Southwest $\frac{1}{4}$ of Northwest $\frac{1}{4}$ of Section 2, Township 5 South, Range 16 East and run thence North 0 degrees 49 minutes West along the West line of said Section 2, 658.91 feet for Point of Beginning; thence continue North 0 degrees 49 minutes West along the West line of said Section 2, 500 feet; thence run South 65 degrees 59 minutes 30 seconds East, 1000.05 feet to the Northerly line of State Road No. 47; thence run South 40 degrees 53 minutes West along the West line of State Road No. 47 a distance of 474.23 feet; thence run North 65 degrees 59 minutes 30 seconds West, a distance of 652.5 feet more or less to the Point of Beginning, said land lying in the Southwest $\frac{1}{4}$ of the Northwest $\frac{1}{4}$ of Section 2, Township 5 South, Range 16 East, Columbia County, Florida, containing: 10 acres, more or less.

Real Estate Assessment No: 02-5S-16-03443-002

Subject to covenants, restrictions, easements, mortgages and all other encumbrances of record and taxes assessed subsequent to December 31, 2002; provided, however, this reference will not serve to reimpose any such covenants, restrictions or easements.

Inst: 2003008895 Date: 04/29/2003 Time: 09:29

cc Stamp-Deed : 0.70

ML DC, P. DeWitt Cason, Columbia County B: 981 P: 2184

And the said party of the first part does hereby fully warrant the title to said land, and will defend the same against the lawful claims of all persons whomsoever claiming by, through or under the said party of the first part, but not otherwise.

IN WITNESS WHEREOF, the undersigned has hereunto set her hand and seal as of the day and year first above written.

Signed and Sealed in Our
Presence:

Sign: Doris A. Johnson
Print Name: Doris A. Johnson

Virginia H. Bishop
VIRGINIA H. BISHOP, as Trustee of the
Virginia H. Bishop Living Trust

Sign: Sheryl Litteral
Print Name: Sheryl Litteral

STATE OF FLORIDA
COUNTY OF Columbia


The foregoing instrument was acknowledged before me this 28 day of April, 2003, by VIRGINIA H. BISHOP, as Trustee of the Virginia H. Bishop Living Trust, (notary must check one box):
☒ who is personally known to me or () who has produced _____ (State) driver's license No. _____ as identification.

Elaine K. Tolar

Name: ELAINE K. TOLAR

NOTARY PUBLIC, State of FLORIDA

Commission Number: _____




VENT-FREE

This unit is A.G.A. certified as a heater with 99% heat efficiency

No chimney or flue system required

Wide selection of factory installed options offered





VF-4000

- 14,000 – 25,000 Btu/hr with manual control valve
- 19,500 – 25,000 Btu/hr with millivolt control valve
- Fully assembled and ready to install
- Attractive wood surrounds available
- 15" x 30" fixed or operable screen opening

VF-5000

- 25,000 Btu/hr millivolt variable heat output
- 15" X 30" glass or screen viewing area
- Clean burning, safe and easy to install
- Realistic charred oak logs with glowing embers



VF-6000

- 32,000 Btu/hr millivolt variable heat output
- Beautiful 20" X 34" glass or screen viewing area
- Will operate during a power failure
- Designed for large rooms

SUPERIOR



VF-4000/5000/6000




VF-6000 surrounds.

Controls hidden in access compartment.



Optional FAB-1100 Blower.

Fixed or operable heavy duty mesh screen.



VF-4000


Optional brass hoods, arches, glass panel and fine mesh screen.

Controls hidden in access compartment.




Optional FAB-1100 Blower.

Millivolt controls and piezo ignition operate during a power failure.



VF-5000/6000



Refractory tan brick panels



Gas flex liner kit.



Square brass trim kit.



Brass Louver Kit (For VF-4 only)




Screen panel kit. (For VF-5 & VF6 only)



Arch kit. (For VF-5 & VF6 only)



Glass door kit. (For VF-5 & VF6 only)



Brass hood. (For VF-5 & VF6 only)




Wall switch or optional wireless remote available. (For VF-4MV, VF-5 & VF-6)




Wall thermostat. (For VF-4MV, VF-5 & VF-6)


Front View



Left Side View



Top View



Vent-Free Product Dimensions

	VF-4000/5000C	VF-6000C
A	42-1/8"	42-1/8"
B	31-1/2"	36-5/8"
C	20"	20"
D	30"	34"
E	40"	40"
F	5-1/2"	5-1/2"
G	1-1/2"	1-1/2"
H	3-3/4"	3-3/4"
I	8-1/2"	8-1/2"
J	3"	3"
K	19-1/2"	19-1/2"
L	27"	28-1/2"

Btu Chart

Model	Natural	Propane
VF-4000 manual	14,000 - 25,000	14,000 - 25,000
VF-4000/5000 millivolt	19,500 - 25,000	19,500 - 25,000
VF-6000	25,000 - 32,000	25,000 - 32,000

Framing Dimension

Model	Width	Height	Depth
VF-4000/5000	37"	37-1/4"	15-1/2"
VF-6000	41"	42-5/8"	19-1/2"

NOTE: Diagrams and illustrations are not to scale. Product designs, materials, dimensions, specifications, colors and prices subject to change or discontinuation without notice. Built to ANSI Z21.11.2 standard and approved by A.G.A. (report # L2970017).

Consult your distributor for local fireplace code information.





SUPERIOR

www.LennoxHearthProducts.com

SURROUNDS

The Charleston Poplar Surround is hand crafted using a combination of solid Poplar and Poplar veneer. Using the unique wood type of Poplar allows you the option to paint or stain this elegantly detailed surround. The surround is constructed using easy to assemble cam locks, and available in corner and wall units.



Distributed by:



The Florida Department of Community Affairs Building Code Information System

FLORIDA BUILDING CODE

Overview User Registration Organization Search Authentication

Select the organization type, status, or name to find an organization

Organization Type: Product Manufacturer

Approval Status: (All)

Organization Name: General American Door - Product Manufacturer

Cancel

Search

Result List for Organizations


Displaying 1-1 of 1

Name	City	Contact	Phone	Type	Expiry	Status
General American Door	Montgomery	James Campbell	6368591000	Product Manufacturer	01/01/2009	Approved
Org Code: PDM System ID: 3385				Site Link: www.gadeo.com		


Displaying 1-1 of 1

Copyright 2004 by The Florida Department of Community Affairs. All rights reserved. This system is a proprietary system of the Florida Department of Community Affairs. No part of this system may be reproduced or transmitted in any form or by any means electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without permission in writing from the Florida Department of Community Affairs.


The seal on this drawing only certifies that the product(s) illustrated and described herein represent the configuration(s) of the door as tested.




FASTENER ARRANGEMENT A




SEC D-D
PAN ATTACHMENT
TO STILE
GAS TESTED




SEC D-D
PAN ATTACHMENT
TO STILE
(OPTIONAL)




SEC G-G
CENTER STILE
20 GA GALVANIZED




SEC G-G
CENTER STILE
20 GA GALVANIZED



2x6 PRESSURE TREATED LUMBER
GRADE #2 OR BETTER SOUTHERN PINE




SEC F-F
END STILE
20 GA PAINTED STEEL



SEC E-E




SEC A-A




5-3/8" 20 GA. 80 KSI YIELD
STROUT APPLIED WITH
2 TEK SCREWS PER HINGE
OR STILE LOCATION
(14 PER STROUT, MINIMUM)

4 HINGE BRACKET



12 SIDE LOCK




REV	DATE	BY	DESCRIPTION
1	11-27-01	GM	SEE FOR R&M
2	12-1-00	GM	SEE FOR R&M

ITEM	PART NO.	DESCRIPTION
1	10000000	VERTICAL TRACK (16 GA.)
2	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
3	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
4	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
5	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
6	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
7	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
8	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
9	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
10	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
11	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
12	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
13	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
14	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
15	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
16	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
17	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
18	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
19	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
20	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
21	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
22	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
23	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
24	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
25	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
26	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
27	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
28	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
29	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
30	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
31	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
32	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
33	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
34	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
35	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
36	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
37	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
38	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
39	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
40	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
41	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
42	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
43	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
44	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
45	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
46	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
47	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
48	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
49	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI
50	10000000	1" SQUARE STROUTED GA. MIN YIELD STG. 80KSI

GENERAL AMERICAN DOOR COMPANY
5050 BASELINE ROAD
MONTGOMERY, IL 60538

WIND LOAD VS. ANCHOR SPACING




MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)
LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS
FT²

1) USE 22" SPACING
 2) USE 21" SPACING
 3) USE 19" SPACING
 SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS



SEAL
PE NO. 024280

ASER R KEYVAN

3/8/2002

2X6 JAMB TO SUPPORTING STRUCTURE ATTACHMENT

2X6 PRESSURE TREATED (GRADE #2 OR BETTER SOUTHERN PINE) WOOD JAMB SHALL BE ANCHORED TO BUILDING WOOD FRAME, GROUTED AND REINFORCED CONCRETE MASONRY UNIT (CMU) WALLS OR COLUMNS, OR REINFORCED CONCRETE COLUMNS.

NOTES:

- 1) ALL DOOR OPENING SURROUNDING STRUCTURE TO BE DESIGNED BY REGISTERED ENGINEER OR ARCHITECT WITH DUE CONSIDERATION GIVEN TO INSTALLATIONS USING CENTER "HURRICANE" POSTS.
- 2) ALL DOOR OPENING STRUCTURE AND FASTENERS TO COMPLY WITH ALL APPLICABLE CODES INCLUDING SBCCI "STANDARD FOR HURRICANE RESISTANT RESIDENTIAL CONSTRUCTION" SSTB 10, CURRENT EDITION.
- 3) ALL FASTENERS TO BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS, INSTRUCTIONS AND RECOMMENDATIONS.
- 4) WOOD FRAME BUILDINGS: STUDS AT EACH SIDE OF DOOR OPENING SHALL BE PROPERLY DESIGNED, CORRECTED, ANCHORED AND SHALL CONSIST OF A MINIMUM OF THREE (3) LAMINATIONS OF 2X6 PRESSURE TREATED SOUTHERN PINE (#2 GRADE OR BETTER) WALL STUDS CONTINUOUS FROM FLOODING TO DOUBLE TOP PLATE.
- 5) REINFORCED CMU OR CONCRETE: 2X6 WOOD JAMB SHALL BE ANCHORED TO SOLIDLY GROUTED AND REINFORCED CONCRETE MASONRY UNIT (CMU) WALLS OR COLUMNS, OR REINFORCED CONCRETE COLUMNS. ANCHOR SPACING AND EMBEDMENT IS BASED ON CONCRETE MASONRY UNITS COMPLYING WITH ASTM C90 WITH A MINIMUM NET AREA COMPRESSIVE STRENGTH OF 2150 PSI, GROUT WITH A MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI, REINFORCED CONCRETE COLUMNS WITH A MINIMUM COMPRESSIVE STRENGTH OF 2500 PSI.
- 6) EMBEDMENTS LISTED ARE THE MINIMUM ALLOWABLE EMBEDMENTS.
- 7) ANCHORS FOR CONCRETE AND CONCRETE MASONRY UNITS (CMU) SHALL HAVE A MINIMUM 3" EDGE DISTANCE FROM ALL EDGES OF CONCRETE OR CONCRETE MASONRY UNITS. ANCHORS FOR CONCRETE AND CMU SHALL HAVE A MINIMUM SPACING OF 3-3/4".
- 8) LAG SCREWS SHALL BE CENTERED IN ONE OF THE 1-1/2" DIMENSION FACES OF THE TRIPLE 2X6 WALL STUDS.
- 9) WASHERS ARE REQUIRED ON ALL FASTENERS.
- 10) THE WIND LOAD VS. ANCHOR SPACING CHART IS FOR A MAXIMUM DOOR SIZE OF 18' X 8' AT A MAXIMUM 42 PSF DESIGN WIND LOAD.
- 11) FOR THE UPPER THREE INDIVIDUAL STEEL JAMB BRACKETS, BRACKETS SHALL BE CENTERED BETWEEN THE TWO CLOSEST 2X6 WOOD JAMB ANCHORS. IF THE STEEL JAMB BRACKET IS NOT CENTERED BETWEEN THE TWO CLOSEST 2X6 WOOD JAMB ANCHORS, ADD AN ADDITIONAL 2X6 WOOD JAMB ANCHOR NEAR THAT STEEL BRACKET TO INSURE THAT THE LOAD FROM THE STEEL BRACKET IS EQUALLY TRANSFERRED TO TWO WOOD JAMB ANCHORS.

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING

USE 21" SPACING

USE 19" SPACING

SEE NOTE 11 FOR ADDITIONAL REQUIRED 2X6 WOOD JAMB ANCHORS

SEAL

PE NO. 024280

ASER R KEYVAN

3/8/2002

WIND LOAD (LBS)

MAXIMUM ANCHOR SPACING (INCHES) PER EACH JAMB

DESIGN (LBS) X GARAGE DOOR AREA (WIDTH-FT X HEIGHT-FT) = WIND LOAD (LBS)

LOAD FT²

EXAMPLE

30 LBS. X (16 FT WIDE X 8 FT HIGH) = 3840 LBS

USE 22" SPACING



USE 21" SPACING

USE 1

NOTES:

1. TESTED TO POSITIVE AND NEGATIVE 20 PSF DESIGN AND POSITIVE AND NEGATIVE 30 PSF TEST PRESSURES PER ASTM E-330
2. MAXIMUM SECTION HEIGHT: 21'
3. SECTION HEIGHTS OF 21' OR AND 19'50" ARE AVAILABLE AND MAY BE USED IN ANY COMBINATION TO ACHIEVE VARIOUS DOOR HEIGHTS.
4. WINDOWS MAY BE INSTALLED IN THE TOP SECTION, OR IN THE SECTION IMMEDIATELY BELOW THE TOP SECTION.
5. MINIMUM LENGTH OF ROLLER STICH IS 51" (7' AS TESTED)
6. THE STRUT PLACEMENT ON DOOR MUST BE CONSISTENT WITH THE DOOR SHOWN.
7. STRUTS SECURED AT ALL LOCATIONS WITH TIE SCREWS.
8. QUANTITY OF SIDE LIDS CAN BE 0, 1, OR 2 AS TESTED.
9. DROP BY TYPE OF INSULATION IS OPTIONAL.

NOT PART OF WIND LOAD SYSTEM
EXTENSION SPRING COUNTERBALANCE
TORSION SPRING COUNTERBALANCE



INSIDE ELEVATION


ALL ROLLER CARRIERS
AND HINGES ARE 14 GA

12 GA. JAMB BRACKET, MAXIMUM SPACING = 19-1/2\"/>

The seal on this drawing only illustrates the product(s) that the product(s) of the door as tested. Dimensions and configuration of the door as tested.



REPORT NO. 2202



TEST REPORTS ON FILE VIDEO 10/19/00 (002933)

GABCO DOORS

SERIES 7400, EXTERIOR STEEL = 0.17 MIN (AS TESTED)
SERIES 7825, EXTERIOR STEEL = 0.19\"/>



GENERAL AMERICAN DOOR COMPANY
5050 BASELINE ROAD
MONTICOMERY, IL 60538

SCALE 1/8\"/>

APPROVED BY

DRAWN BY: D. VILKMAN

DATE: 10-20-00

REVIEWED

(A) 11-10-00

DESCRIPTION

16' X 7' MAX RAISED PANEL STEEL DOOR - WINDLOAD 40 PSF

PART NUMBER

PAGE 1 OF 2

DRAWING NUMBER V13220-1

REV.	DATE	BY	DESCRIPTION
A-1	11-10-00	DM	SEE E.C.N. 311

DOOR
DATAMIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDINGBUILDING CODE COMPLIANCE OFFICE
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908CONTRACTOR LICENSING SECTION
(305) 375-2527 FAX (305) 375-2558CONTRACTOR ENFORCEMENT DIVISION
(305) 375-2966 FAX (305) 375-2908PRODUCT CONTROL DIVISION
(305) 375-2902 FAX (305) 372-6339**PRODUCT CONTROL NOTICE OF ACCEPTANCE**Premdor Entry Systems
911 E. Jefferson, P.O. Box 76
Pittsburgh, KS 66762

Your application for Notice of Acceptance (NOA) of:
Entergy 6-8 S-W/E Inswing Opaque Double w/sidelites Residential Insulated Steel Door
 under Chapter 8 of the Code of Miami-Dade County governing the use of Alternate Materials and Types of Construction, and completely described herein, has been recommended for acceptance by the Miami-Dade County Building Code Compliance Office (BCCO) under the conditions specified herein.

This NOA shall not be valid after the expiration date stated below. BCCO reserves the right to secure this product or material at any time from a jobsite or manufacturer's plant for quality control testing. If this product or material fails to perform in the approved manner, BCCO may revoke, modify, or suspend the use of such product or material immediately. BCCO reserves the right to revoke this approval, if it is determined by BCCO that this product or material fails to meet the requirements of the South Florida Building Code.

The expense of such testing will be incurred by the manufacturer.


ACCEPTANCE NO.: 01-0314.24
 EXPIRES: 04/02/2006



Raul Rodriguez
 Chief Product Control Division


**THIS IS THE COVERSHEET. SEE ADDITIONAL PAGES FOR SPECIFIC AND GENERAL
 CONDITIONS
 BUILDING CODE & PRODUCT REVIEW COMMITTEE**

This application for Product Approval has been reviewed by the BCCO and approved by the Building Code and Product Review Committee to be used in Miami-Dade County, Florida under the conditions set forth above.



Francisco J. Quintana, R.A.
 Director
 Miami-Dade County
 Building Code Compliance Office

APPROVED: 06/05/2001



MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING

BUILDING CODE COMPLIANCE OFFICE
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

PRODUCT CONTROL NOTICE OF ACCEPTANCE

Premdor Entry Systems
911 E. Jefferson, P.O. Box 76
Pittsburgh, KS 66762

CONTRACTOR LICENSING SECTION
(305) 375-2527 FAX (305) 375-2558

CONTRACTOR ENFORCEMENT DIVISION
(305) 375-2966 FAX (305) 375-2908

PRODUCT CONTROL DIVISION
(305) 375-2902 FAX (305) 375-2939

Your application for Notice of Acceptance (NOA) of:

Entergy 6-8 S-W/E Inswing Opaque Single w/sidelites Residential Insulated Steel Door
under Chapter 8 of the Code of Miami-Dade County governing the use of Alternate Materials and Types of Construction, and completely described herein, has been recommended for acceptance by the Miami-Dade County Building Code Compliance Office (BCCO) under the conditions specified herein.

This NOA shall not be valid after the expiration date stated below. BCCO reserves the right to secure this product or material at any time from a jobsite or manufacturer's plant for quality control testing. If this product or material fails to perform in the approved manner, BCCO may revoke, modify, or suspend the use of such product or material immediately. BCCO reserves the right to revoke this approval, if it is determined by BCCO that this product or material fails to meet the requirements of the South Florida Building Code.

The expense of such testing will be incurred by the manufacturer.

ACCEPTANCE NO.: 01-0314.18
EXPIRES: 04/02/2006

Raul Rodriguez
Chief Product Control Division

THIS IS THE COVERSHEET, SEE ADDITIONAL PAGES FOR SPECIFIC AND GENERAL
CONDITIONS
BUILDING CODE & PRODUCT REVIEW COMMITTEE

This application for Product Approval has been reviewed by the BCCO and approved by the Building Code and Product Review Committee to be used in Miami-Dade County, Florida under the conditions set forth above.

Francisco J. Quintana, R.A.
Director
Miami-Dade County
Building Code Compliance Office

APPROVED: 06/05/2001

**AAMA/NWDA 101/LS-2-97
TEST REPORT SUMMARY**

Rendered to:

MI HOME PRODUCTS, INC.


SERIES/MODEL: 650

TYPE: Aluminum Picture Window

Title of Test	Results
Rating	F-R45 60 x 80
Overall Design Pressure	+45.0 psf -47.2 psf
Air Infiltration	0.04 cfm/ft ²
Water Resistance	8.25 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41135.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.


Mark A. Hess, Technician

MAH:nlb

Allen N. Reeves
1 APRIL 2002





Architectural Testing

AAMA/NWWDA 101/LS.2-97 TEST REPORT

Rendered to:

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41135.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650, aluminum picture window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a F-R45 60 x 80 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/LS.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description

Series/Model: 650

Type: Aluminum Picture Window

Overall Size: 5' 0" wide by 6' 8" high

Daylight Opening Size: 4' 9-1/4" wide by 6' 5-1/4" high

Finish All aluminum was white.

Glazing Details: The test specimen utilized 7/8" thick, sealed insulating glass constructed from two sheets of 3/16" thick, clear annealed glass and a metal reinforced butyl spacer system. The glass was interior glazed against double-sided adhesive foam tape and secured with aluminum snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen M. Rasmussen
1 APR 12 2002



Test Specimen Description: (Continued)

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss.

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck. #8 x 2-1/2" installation screws were utilized 18" on center around the interior perimeter. Polyurethane was utilized to seal the exterior.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.04 cfm/ft ²	0.3 cfm/ft ² max.
<i>Note #1: The tested specimen meets the performance levels specified in AAMA/NWDA 101/I.S. 2-97 for air infiltration.</i>			
	Water Resistance (ASTM E 547-00) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the jamb) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.01" 0.01"	0.41" max. 0.41" max.
2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the jamb) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.0" 0.01"	0.29" max. 0.29" max.

Allen H. Reeves
1 APRIL 2002



Test Results: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
	Forced Entry Resistance (ASTM F 588-97)		
	Type: D		
	Grade: 10		
	Hand and Tool Manipulation Test	No entry	No entry

Optional Performance

4.3	Water Resistance (ASTM E 547-00)		
	WTP = 8.25 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97)		
	(Measurements reported were taken on the jamb)		
	(Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.02"	0.41" max.
	@ 47.2 psf (negative)	0.02"	0.41" max.
	Uniform Load Structural (ASTM E 330-97)		
	(Measurements reported were taken on the jamb)		
	(Loads were held for 10 seconds)		
	@ 67.5 psf (positive)	0.01"	0.29" max.
	@ 70.8 psf (negative)	0.02"	0.29" max.

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess

Mark A. Hess
Technician

MAH:nlb
01-41135.01

Allen N. Reeves

Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002



**AAMA/NWDA 101/LS-2-97
TEST REPORT SUMMARY**

Rendered to:


MI HOME PRODUCTS, INC.

**SERIES/MODEL: 650 Fin
TYPE: Aluminum Single Hung Window**


Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf -47.2 psf
Operating Force	11 lb max.
Air Infiltration	0.13 cfm/ft ²
Water Resistance	6.00 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.


Mark A. Hess, Technician

MAH:nib


1 APRIL 2002



II

Architectural Testing

AAMA/NWDA 101/LS-2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41134.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWDA 101/LS-2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high


Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap-around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen N. Remer
1 APRIL 2002



III

Test Specimen Description: (Continued)

Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Metal cam lock with keeper		Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail

Allen N. Reeves
1 APRIL 2002



Test Specimen Description: (Continued)

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.1	Operating Force	11 lbs	30 lbs max
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.13 cfm/ft ²	0.3 cfm/ft ² max

Note #1: The tested specimen meets the performance levels specified in AAMA/NWDA 101/I.S. 2-97 for air infiltration.

	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.42"* 0.43"*	0.26" max. 0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.02" 0.02"	0.18" max. 0.18" max.
---------	---	----------------	--------------------------

Allen N. Reeves
1 APRIL 2002



Test Specimen Description: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.2	Deglazing Test (ASTM E 987) In operating direction at 70 lbs		
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
	Forced Entry Resistance (ASTM F 588-97)		
	Type: A		
	Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Tests A1 through A5	No entry	No entry
	Test A7	No entry	No entry
	Lock Manipulation Test	No entry	No entry

Optional Performance

4.3	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 6.00 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.47"	0.26" max.
	@ 47.2 psf (negative)	0.46"	0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds)	
@ 67.5 psf (positive)	0.05"
@ 70.8 psf (negative)	0.05"


Allen N. Reeves
1 APRIL 2002




VI

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:


Mark A. Hess
Technician

MAH:nlb
01-41134.01


Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002



A

**AAMA/NWWDA 101/I.S.2-97
TEST REPORT**

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 650

TYPE: Aluminum Triple Single Hung Window

Title of Test	Summary of Results
AAMA Rating	H-R35 112 x 72
Uniform Load Deflection Test Pressure	+35.3 psf -47.2 psf
Operating Force	25 lb max.
Air Infiltration	0.16 cfm/ft ²
Water Resistance Test Pressure	5.25 psf
Uniform Load Structural Test Pressure	+53.0 psf -52.5 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to ATI Report No. 01-41641.01 for complete description and data.

Allen N. Reeves
7 JUNE 2002





AAMA/NWWDA 101/LS.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
P.O. Box 370
650 West Market Street
Gratz, Pennsylvania 17030-0370

Report No: 01-41641.01
Test Date: 05/13/02
And: 05/16/02
Report Date: 06/05/02
Expiration Date: 05/16/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to witness testing on a Series/Model 650, aluminum triple single hung window at their facility located in Elizabethville, Pennsylvania. The sample tested successfully met the performance requirements for a H-R35 112 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/LS.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650

Type: Aluminum Triple Single Hung Window

Overall Size: 9' 3-1/2" wide by 5' 11-11/16" high

Active Sash Size (3): 3' 0-1/4" wide by 2' 10-3/4" high

Fixed Daylight Opening Size (3): 2' 8-1/4" wide by 2' 9-1/8" high

Screen Size (3): 2' 9-1/8" wide by 2' 11" high

Finish: All aluminum was painted white.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com



Allen H. Reeves
7 JUNE 2002

Test Specimen Description: (Continued)

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap-around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" by 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. The meeting rail was secured to the frame utilizing two 1-1/4" screws. The mullions were secured utilizing four #8 x 1-1/4" screws through the head and sill into the mullion screw boss.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each stiles' screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.



Test Specimen Description: (Continued)

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Metal cam lock with keeper	1	Midspan of each active meeting rail with adjacent keepers
Plastic tilt latch	2	Each active sash meeting rail ends
Metal tilt pin	2	Each active sash bottom rail ends
Balance assembly	2	Each active sash contained one in each jamb
Screen plunger	2	Each screen contained two 4" from rail ends on top rail

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows.

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.1	Operating Force	25 lbs	30 lbs max.
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.16 cfm/ft ²	0.3 cfm/ft ² max.

Note #1: The tested specimen meets the performance levels specified in AAMA/NWDA 101/I.S. 2-97 for air infiltration.

Water Resistance (ASTM E 547-00)
(with and without screen)
WTP = 2.86 psf

No leakage

Allen N. Reeves
7 JUNE 2002



Test Results: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the mullion) (Loads were held for 52 seconds) @ 15.0 psf (positive) @ 15.0 psf (negative)	0.15" 0.29"	0.41" max. 0.41" max.
2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the mullion) (Loads were held for 10 seconds) @ 22.5 psf (positive) @ 22.5 psf (negative)	0.01" 0.01"	0.29" max. 0.29" max.
2.2 .6.2	Deglazing Test (ASTM E 987-88) In operating direction at 70 lbs Right sash, meeting rail Right sash, bottom rail Middle sash, meeting rail Middle sash, bottom rail Left sash, meeting rail Left sash, bottom rail In remaining direction at 50 lbs Right sash, right stile Right sash, left stile Middle sash, right stile Middle sash, left stile Left sash, right stile Left sash, left stile	0.12"/25% 0.12"/25% 0.12"/25% 0.12"/25% 0.12"/25% 0.12"/25% 0.06"/12% 0.06"/12% 0.06"/12% 0.06"/12% 0.06"/12% 0.06"/12%	0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100% 0.50"/100%
2 .8	Forced Entry Resistance (ASTM F 588-97) Type: A Grade: 10 Lock Manipulation Test Test A1 through A5 Test A7 Lock Manipulation Test	No entry No entry No entry No entry	No entry No entry No entry No entry

Allen N. Reeves
7 JUNE 2002



Test Results: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
<u>Optional Performance</u>			
4.3	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 5.25 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the mullion) (Loads were held for 52 seconds)		
	@ 35.3 psf (positive)	0.46"	0.41" max
	@ 47.2 psf (negative)	0.67"	0.41" max
<i>*Exceeds L/175 for deflection, but meets all other test requirements.</i>			
	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the mullion) (Loads were held for 10 seconds)		
	@ 53.0 psf (positive)	0.03"	0.29" max
	@ 52.5 psf (negative)	0.02"	0.29" max

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess
Mark A. Hess
Technician

MAH:nlb
01-41641.01

Allen N. Reeves
Allen N. Reeves, P.E.
Director - Engineering Services
7 JUNE 2002



Premdor Entry Systems

ACCEPTANCE No.: 01-0314.18


APPROVED : JUN 05 2001

EXPIRES : April 02, 2006

NOTICE OF ACCEPTANCE: STANDARD CONDITIONS

1. Renewal of this Acceptance (approval) shall be considered after a renewal application has been filed and the original submitted documentation, including test supporting data, engineering documents, are no older than eight (8) years.
2. Any and all approved products shall be permanently labeled with the manufacturer's name, city, state, and the following statement: "Miami-Dade County Product Control Approved", or as specifically stated in the specific conditions of this Acceptance.
3. Renewals of Acceptance will not be considered if:
 - a. There has been a change in the South Florida Building Code affecting the evaluation of this product and the product is not in compliance with the code changes.
 - b. The product is no longer the same product (identical) as the one originally approved.
 - c. If the Acceptance holder has not complied with all the requirements of this acceptance, including the correct installation of the product.
 - d. The engineer who originally prepared, signed and sealed the required documentation initially submitted, is no longer practicing the engineering profession.
4. Any revision or change in the materials, use, and/or manufacture of the product or process shall automatically be cause for termination of this Acceptance, unless prior written approval has been requested (through the filing of a revision application with appropriate fee) and granted by this office.
5. Any of the following shall also be grounds for removal of this Acceptance:
 - a. Unsatisfactory performance of this product or process.
 - b. Misuse of this Acceptance as an endorsement of any product, for sales, advertising or any other purposes.
6. The Notice of Acceptance number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the Notice of Acceptance is displayed, then it shall be done in its entirety.
7. A copy of this Acceptance as well as approved drawings and other documents, where it applies, shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at all time. The engineer needs not reseal the copies.
8. Failure to comply with any section of this Acceptance shall be cause for termination and removal of Acceptance.
9. This Notice of Acceptance consists of pages 1, 2 and this last page 3.

END OF THIS ACCEPTANCE


Manuel Perez, P.E., Product Control Examiner
Product Control Division

Premdor Entry Systems

ACCEPTANCE No.: 01-0314.18

APPROVED : JUN 05 2001

EXPIRES : April 02, 2006

NOTICE OF ACCEPTANCE: SPECIFIC CONDITIONS

1. SCOPE

- 1.1 This renews the Notice of Acceptance No. 00-0321.20 which was issued on April 28, 2000. It approves a residential insulated door, as described in Section 2 of this Notice of Acceptance, designed to comply with the South Florida Building Code (SFBC), 1994 Edition for Miami-Dade County, for the locations where the pressure requirements, as determined by SFBC Chapter 23, do not exceed the Design Pressure Rating values indicated in the approved drawings.

2. PRODUCT DESCRIPTION

- 2.1 The Series Entergy 6-8 S-W/E Inswing Opaque Single Residential Insulated Steel Door with Sidelites- Impact Resistant Door Slab Only and its components shall be constructed in strict compliance with the following documents: Drawing No 31-1020-EW-I, Sheets 1 through 6 of 6, titled "Premdor (Entergy Brand) Wood Edge Single Door in Wood Frames with a Bumper Threshold (Inswing)," prepared by manufacturer, dated 7/29/97 with revision C dated 01/15/01, bearing the Miami-Dade County Product Control approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Division. These documents shall hereinafter be referred to as the approved drawings.

3. LIMITATIONS

- 3.1 This approval applies to single unit applications of single door only, as shown in approved drawings.
- 3.2 Unit shall be installed only at locations protected by a canopy or overhang such that the angle between the edge of canopy or overhang to sill is less than 45 degrees. Unless unit is installed in non-habitable areas where the unit and the area are designed to accept water infiltration.

4. INSTALLATION


- 4.1 The residential insulated steel door and its components shall be installed in strict compliance with the approved drawings.
- 4.2 Hurricane protection system (shutters):
- 4.2.1 Door: the installation of this unit will not require a hurricane protection system.
- 4.2.2 Sidelite: the installation of this unit will require a hurricane protection system.

5. LABELING

- 5.1 Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved".

6. BUILDING PERMIT REQUIREMENTS

- 6.1 Application for building permit shall be accompanied by copies of the following:
- 6.1.1 This Notice of Acceptance
- 6.1.2 Duplicate copies of the approved drawings, as identified in Section 2 of this Notice of Acceptance, clearly marked to show the components selected for the proposed installation.
- 6.1.3 Any other documents required by the Building Official or the South Florida Building Code (SFBC) in order to properly evaluate the installation of this system.


Manuel Perez, P.E. Product Control Examiner
Product Control Division



FEB - 4 2002

January 31, 2002

TO: OUR FLORIDA CUSTOMERS:

Effective February 1, 2002, the following TAMKO shingles, as manufactured at TAMKO's Tuscaloosa, Alabama, facility, comply with ASTM D-3161, Type I modified to 110 mph. Testing was conducted using four nails per shingle. These shingles also comply with Florida Building Code TAS 100 for wind driven rain.

- Glass-Seal AR
- Elite Glass-Seal AR
- ASTM Heritage 30 AR (formerly ASTM Heritage 25 AR)
- Heritage 40 AR (formerly Heritage 30 AR)
- Heritage 50 AR (formerly Heritage 40 AR)

All testing was performed by Florida State certified independent labs.



Please direct all questions to TAMKO's Technical Services Department at 1-800-641-4691.

TAMKO Roofing Products, Inc.




Application Instructions For Heritage® 25 Series Shingles

SPECIFICATIONS (APPROX.)	
Length	37"
Width	12"
Bundles per Sq.	3
Shingles per Sq.	78
Shingles per Bundle	26
Coverage per Sq. (Sq. Ft.)	100
Exposure	5"



The 4 cuts in the first 10 courses:



In the first 10 courses, there are 4 cuts and no waste.

When you reach the other side of the roof, whatever has to be trimmed off can be used in the field of roofing.

For additional application information consult the application instructions printed on the product package.

NOTE: These application instructions apply only to Heritage 25 and Heritage 25 AR shingles.



Application Instructions for

- Glass-Seal
 - Glass-Seal AR
 - Elite Glass-Seal®
 - Elite Glass-Seal® AR
- ### THREE-TAB ASPHALT SHINGLES

THESE ARE THE MANUFACTURER'S APPLICATION INSTRUCTIONS FOR THE ROOFING CONDITIONS DESCRIBED. TAMKO ROOFING PRODUCTS, INC. ASSUMES NO RESPONSIBILITY FOR LEAKS OR OTHER ROOFING DEFECTS RESULTING FROM FAILURE TO FOLLOW THE MANUFACTURER'S INSTRUCTIONS.

THIS PRODUCT IS COVERED BY A LIMITED WARRANTY, THE TERMS OF WHICH ARE PRINTED ON THE WRAPPER. IN COLD WEATHER (BELOW 40°F), CARE MUST BE TAKEN TO AVOID DAMAGE TO THE EDGES AND CORNERS OF THE SHINGLES.

IMPORTANT: It is not necessary to remove the plastic strip from the back of the shingles.

1. ROOF DECK

These shingles are for application to roof decks capable of receiving and retaining fasteners, and to inclines of not less than 2 in. per foot. For roofs having pitches 2 in. per foot to less than 4 in. per foot, refer to special instructions titled "Low Slope Application". Shingles must be applied properly. TAMKO assumes no responsibility for leaks or defects resulting from improper application, or failure to properly prepare the surface to be roofed over.

NEW ROOF DECK CONSTRUCTION: Roof deck must be smooth, dry and free from warped surfaces. It is recommended that metal drip edges be installed at eaves and rakes.

PLYWOOD: All plywood shall be exterior grade as defined by the American Plywood Association. Plywood shall be a minimum of 3/8 in. thickness and applied in accordance with the recommendations of the American Plywood Association.

SHEATHING BOARDS: Boards shall be well-seasoned tongue-and-groove boards and not over 6 in. nominal width. Boards shall be a 1 in. nominal minimum thickness. Boards shall be properly spaced and nailed.

2. VENTILATION

Inadequate ventilation of attic spaces can cause accumulation of moisture in winter months and a build up of heat in the summer. These conditions can lead to:

1. Vapor Condensation
2. Buckling of shingles due to deck movement
3. Rotting of wood members.
4. Premature failure of roof.

To insure adequate ventilation and circulation of air, place louvers of sufficient size high in the gable ends and/or install continuous ridge and soffit vents.

FHA minimum property standards require one square foot of net free ventilation area to each 150 square feet of space to be vented, or one square foot per 300 square feet if a vapor barrier is installed on the warm side of the ceiling or if at least one half of the ventilation is provided near the ridge. If the ventilation openings are screened, the total area should be doubled.

IT IS PARTICULARLY IMPORTANT TO PROVIDE ADEQUATE VENTILATION.

3. FASTENING

NAILS: TAMKO recommends the use of nails as the preferred method of application.


WIND CAUTION: Extreme wind velocities can damage these shingles after application when proper sealing of the shingles does not occur. This can especially be a problem if the shingles are applied in cooler months or in areas on the roof that do not receive direct sunlight. These

conditions may impede the sealing of the adhesive strips on the shingles. The inability to seal down may be compounded by prolonged cold weather conditions and/or blowing dust. In these situations, hand sealing of the shingles is recommended. Shingles must also be fastened according to the fastening instructions described below.


Correct placement of the fasteners is critical to the performance of the shingle. If the fasteners are not placed as shown in the diagram and described below, TAMKO will not be responsible for any shingles blown off or displaced. TAMKO will not be responsible for damage to shingles caused by winds or gusts exceeding gale force. Gale force shall be the standard as defined by the U.S. Weather Bureau.

FASTENING PATTERNS: Fasteners must be placed above or below the factory applied sealant in an area between 5-1/2" and 6-3/4" from the butt edge of the shingle. Fasteners should be located horizontally according to the diagram below. Do not nail into the sealant. TAMKO recommends nailing below the sealant whenever possible for greater wind resistance.

- 1) Standard Fastening Pattern. (For use on decks with slopes 2 in. per foot to 21 in. per foot.) One fastener 1 in. back from each end and one 12 in. back from each end of the shingle for a total of 4 fasteners. (See standard fastening pattern illustrated below.)



- 2) Mansard or High Wind Fastening Pattern. (For use on decks with slopes greater than 21 in. per foot.) One fastener 1 in. back from each end and one fastener 10-1/2 in. back from each end and one fastener 13-1/2 in. back from each end for a total of 6 fasteners per shingle. (See Mansard fastening pattern illustrated below.)



NAILS: TAMKO recommends the use of nails as the preferred method of application. Standard type roofing nails should be used. Nail shanks should be made of minimum 12-gauge wire, and a minimum head diameter of 3/8 in. Nails should be long enough to penetrate 3/4 in.

(Continued)

Visit Our Web Site at
www.tamko.com

Central District	220 West 4th St., Joplin, MO 64801	800-641-4691
Northeast District	4500 Tamko Dr., Frederick, MD 21701	800-368-2056
Southeast District	2300 35th St., Tuscaloosa, AL 35401	800-229-2656
Southwest District	7910 S. Central Exp., Dallas, TX 75216	800-443-1834
Western District	5300 East 43rd Ave., Denver, CO 80216	800-530-8868

07/c1

- Glass-Seal
- Glass-Seal AR

- Elite Glass-Seal®
- Elite Glass-Seal® AR

THREE-TAB ASPHALT SHINGLES

with quick setting asphalt adhesive cement immediately upon installation. Spots of cement must be equivalent in size to a \$.25 piece and applied to shingles with a 5 in. exposure, use 6 fasteners per shingle. See Section 3 for the Mansard Fastening Pattern.

9. RE-ROOFING

Before re-roofing, be certain to inspect the roof decks. All plywood shall meet the requirements listed in Section 1.

Nail down or remove curled or broken shingles from the existing roof. Replace all missing shingles with new ones to provide a smooth base. Shingles that are buckled usually indicate warped decking or protruding nails. Hammer down all protruding nails or remove them and refasten in a new location. Remove all drip edge metal and replace with new.


If re-roofing over an existing roof where new flashing is required to protect against ice dams (freeze/thaw cycle of water and/or the backup of water in frozen or clogged gutters), remove the old roofing to a point at least 24 in. beyond the interior wall line and apply TAMKO's Moisture Guard Plus® waterproofing underlayment. Contact TAMKO's Technical Services Department for more information.

The nesting procedure described below is the preferred method for re-roofing over square tab strip shingles with a 5 in. exposure.

Starter Course: Begin by using TAMKO Shingle Starter or by cutting shingles into 5 x 36 inch strips. This is done by removing the 5 in. tabs from the bottom and approximately 2 in. from the top of the shingles so that the remaining portion is the same width as the exposure of the old shingles. Apply the starter piece so that the self-sealing adhesive lies along the eaves and is even with the existing roof. The starter strip should be wide enough to overhang the eaves and carry water into the gutter. Remove 3 in. from the length of the first starter shingle to ensure that the joints from the old roof do not align with the new.

First Course: Cut off approximately 2 in. from the bottom edge of the shingles so that the shingles fit beneath the existing third course and align with the edge of the starter strip. Start the first course with a full 36 in. long shingle and fasten according to the instructions printed in Section 3.

Second and Succeeding Courses: According to the off-set application method you choose to use, remove the appropriate length from the



rake end of the first shingle in each succeeding course. Place the top edge of the new shingle against the butt edge of the old shingles in the courses above. The full width shingle used on the second course will reduce the exposure of the first course to 3 in. The remaining courses will automatically have a 5 in. exposure.

9. VALLEY APPLICATION

Over the shingle underlayment, center a 36 in. wide sheet of TAMKO Nail-Fast® or a minimum 50 lb. roll roofing in the valley. Nail the felt only where necessary to hold it in place and then only nail the outside edges.

IMPORTANT: PRIOR TO INSTALLATION WARM SHINGLES TO PREVENT DAMAGE WHICH CAN OCCUR WHILE BENDING SHINGLES TO FORM VALLEY.

- Apply the first course of shingles along the eaves of one of the intersecting roof planes and across the valley.

Note: For proper flow of water over the trimmed shingle, always start applying the shingles on the roof plane that has the lower slope or less height.

- Extend the end shingle at least 12 in. onto the adjoining roof. Apply succeeding courses in the same manner, extending them across the valley and onto the adjoining roof.
- Do not trim if the shingle length exceeds 12 in. Lengths should vary.
- Press the shingles tightly into the valley.
- Use normal shingle fastening methods.

Note: No fastener should be within 6 in. of the valley centerline, and two fasteners should be placed at the end of each shingle crossing the valley.

- To the adjoining roof plane, apply one row of shingles extending it over previously applied shingles and trim a minimum of 2 in. back from the centerline of the valley.


Note: For a neater installation, snap a chalkline over the shingles for guidance.

- Clip the upper corner of each shingle at a 45-degree angle and embed the end of the shingle in a 3 in. wide strip of asphalt plastic cement. This will prevent water from penetrating between the courses by directing it into the valley.

CAUTION: Adhesive must be applied in smooth, thin, even layers.

Excessive use of adhesive will cause blistering to this product.

TAMKO assumes no responsibility for blistering.



(Continued)

Visit Our Web Site at
www.tamko.com

Central District
Northeast District
Southeast District
Southwest District
Western District

220 West 4th St., Joplin, MO 64801
4500 Tamko Dr., Frederick, MD 21701
2300 35th St., Tuscaloosa, AL 35401
7910 S. Central Exp., Dallas, TX 75216
5300 East 43rd Ave., Denver, CO 80216

800-641-4691
800-368-2055
800-228-2656
800-443-1834
800-530-8868

07/01



(CONTINUED from Pg. 3)

• Glass-Seal
• Glass-Seal AR

• Elite Glass-Seal®
• Elite Glass-Seal® AR

THREE-TAB ASPHALT SHINGLES

FOR ALTERNATE VALLEY APPLICATION METHODS, PLEASE CONTACT TAMKO'S TECHNICAL SERVICES DEPARTMENT.

10. HIP AND RIDGE FASTENING DETAIL

Apply the shingles with a 5 in. exposure beginning at the bottom of the hip or from the end of the ridge opposite the direction of the prevailing winds. Secure each shingle with one fastener 5-1/2 in. back from the exposed end and 1 in. up from the edge. Do not nail directly into the sealant.


TAMKO recommends the use of TAMKO Hip & Ridge shingle products. Where matching colors are available, it is acceptable to use TAMKO's Glass-Seal or Elite Glass-Seal shingles cut down to 12 in. pieces.

NOTE: AR type shingle products should be used as Hip & Ridge on Glass-Seal AR and Elite Glass-Seal AR shingles.

Fasteners should be 1/4 in. longer than the one used for shingles.

IMPORTANT: PRIOR TO INSTALLATION, CARE NEEDS TO BE TAKEN TO PREVENT DAMAGE WHICH CAN OCCUR WHILE BENDING SHINGLES IN COOL WEATHER.

THESE ARE THE MANUFACTURER'S APPLICATION INSTRUCTIONS FOR THE ROOFING CONDITIONS DESCRIBED. TAMKO ROOFING PRODUCTS, INC. ASSUMES NO RESPONSIBILITY FOR LEAKS OR OTHER ROOFING DEFECTS RESULTING FROM FAILURE TO FOLLOW THE MANUFACTURER'S INSTRUCTIONS.



THIS PRODUCT IS COVERED BY A LIMITED WARRANTY. THE TERMS OF WHICH ARE PRINTED ON THE WRAPPER.

IMPORTANT - READ CAREFULLY BEFORE OPENING BUNDLE

In this paragraph "You" and "Your" refer to the installer of the shingles and the owner of the building on which these shingles will be installed. This is a legally binding agreement between You and TAMKO Roofing Products, Inc. ("TAMKO"). By opening this bundle You agree: (a) to install the shingles strictly in accordance with the instructions printed on this wrapper; or (b) that shingles which are not installed strictly in accordance with the instructions printed on this wrapper are sold "AS IS" and are not covered by the limited warranty that is also printed on this wrapper, or any other warranty, including, but not limited to (except where prohibited by law) implied warranties of MERCHANTABILITY and FITNESS FOR USE.

Visit Our Web Site at
www.tamko.com

Central District	220 West 4th St., Joplin, MO 64801
Northeast District	4500 Tamko Dr., Frederick, MD 21701
Southeast District	2300 35th St., Tuscaloosa, AL 35401
Southwest District	7910 S. Central Exp., Dallas, TX 75216
Western District	5300 East 43rd Ave., Denver, CO 80216

800-641-4691
800-368-2055
800-228-2656
800-443-1834
800-530-8868

07/01

Project Review and Design Remediation Recommendations

for the

**Remodeling and Addition to Existing Residence for
Mr. Ed and Diane Bishop White of Lake City, Florida**

prepared for:

**Mr. Jefferson Braswell of the law firm
Scruggs and Carmichael, PA of Gainesville, Florida.**

Prepared by:

**Martin Gold, AIA
AR 93691
m_gold design and Consulting
2710 NW 27th Place
Gainesville, Florida**

20 March 2007

Executive Summary

The execution of the residential addition design, as envisioned by Mr. and Mrs. White has been severely compromised through the architectural development and the execution of the phases of construction that have occurred up to 13 December, 2005. Errors in the drawings and unconventional building practices (that do not meet the minimum standard set by the Florida Building Code) have produced a partial structure that cannot be effectively completed as illustrated in the architectural drawings.

The fundamental massing, balance and proportion of an architectural composition compatible with the existing residence cannot be physically achieved with the construction that is presently in-place. This conclusion is based on the fact that the existing residence, of noted architectural integrity, has a roof pitch of 2 in 12 (2 foot rise in 12 feet of horizontal run), yet the design of the addition is based on a 3 in 12 roof pitch. The roof pitch is a critical global architectural parameter that establishes the building proportion, aesthetic symmetry, potential for room height and detailing required for the integration of second floor and loft space. The base bearing elevation of the roof was incorrectly identified on the drawings with the existing roof shown approximately 1' - 0" higher than it actually is. Furthermore, the relationship between the building and the ground is not correctly represented in the drawings — a critical error given the multiple ground levels around the building. Unfortunately, errors of incorrectly representing the existing roof pitch; incorrectly establishing the building ground relationship, using multiple incorrect dimensions; and incorrectly establishing the existing building height are present throughout the drawings. These errors do not seem to have been detected until late in the construction phase.

Many unconventional structural framing practices seem to have been developed by the contractor including the cutting and modification of trusses and engineered wood structural members in a manner inconsistent with the architectural and structural drawings and the Florida Building Code. The initial compromised structural integrity of the phase of construction completed to date has been exacerbated by exposure to weather rendering it unusable. Please also refer to the detailed structural assessment provided by TLC Engineering for Architecture (dated August 28, 2006) and the Freeman Design Group, Inc. (dated July, 28, 2006). Furthermore, these deficiencies were also documented in a facsimile follow-up letter and stop work order based on site inspections conducted December 13, 2005 by Columbia County Building Department officials.

We recommend a complete redesign of the addition to be architecturally compatible with the existing home. In order to use conventional structural systems and that would meet or exceed the standard of the Florida Building Code, the existing addition should be demolished. The incorrect 3 in 12 roof pitch and excessive building height results in massing and structural incongruities in the present construction that poses such a complex puzzle of questions regarding the usability of the slab as a 'correct footprint'; a suitable foundation for structural bearing; and the probable relocation of in-slab elements such as plumbing and electrical systems renders the slab likely unusable. Detailed structural analysis would be required to verify the integrity of the slab which would add expense and may prove it to be useless. Therefore, we suggest a complete demolition of the current phase of construction as the most efficacious solution to achieve an architecturally compatible and complete residential addition.

Introduction

M_gold design and consulting has been engaged to evaluate the architectural design drawings of the *Remodeling and Addition to Existing Residence for Mr. Ed and Diane Bishop White* dated 9 May, 2005 with revisions on 21, July 2005; 23 July, 2005; 13 September, 2005; and 13 November 2005 as provided by Associated Florida Architects, Inc. The drawing set was signed and sealed by Mr. Robert S. Taylor, Sr., Architect, AR-0007526. We inspected the remaining existing structure and unfinished construction of the proposed design and met with Mr. White on February 6, 2007. Our analysis, recommendations and this report is based on the review of architectural drawings noted above, site visits, meetings with Mr. White and reviews of structural engineering reports and notes from the Columbia County Building Department. Detailed evaluations of the architectural drawings are included under the heading Drawing Review.

Architectural Integrity

The existing residence of Mr. and Mrs. White is architecturally notable as a Prairie style home. The prairie style, developed by Frank Lloyd Wright in the first decades of the 20th Century, is characterized by a low-pitched roof, overhanging eaves, horizontal lines, central hearth (fireplace) corner windows, open floor plan and clerestory windows. These characteristics are important as the roof pitch is one of the fundamental defining features of the prairie style. Furthermore, the existing home represented a very high quality design interpretation that can be clearly characterized as prairie style architecture. Mr. and Mrs. White were quite sensitive to the architectural character of their home and engaged Associated Florida Architects, Inc. to translate their expansion ideas and spatial needs into an addition that would compliment the existing prairie style home.

Drawing Review

This section includes our review of the individual drawing sheets that were provided by Associated Florida Architects, Inc. This review is not an extensive review and does not propose to detail all of the inconsistencies between the individual drawings, drawings and the existing structure nor conflicts between the drawings and the construction phase completed as of 13 December, 2005. Our comments are intended to reveal important inconsistencies that would cause serious difficulties in completing the project as shown in the drawings.

Field measurements were conducted to verify that the existing roof pitch has a slope of 2 feet of rise in 12 feet of run (2 in 12). The drawings prepared by Associated Florida Architects, Inc. represents the existing roof as having a 3 in 12 roof pitch. Field measurements were also used to verify the height of bearing at the lower eave walls to establish a reference for projecting the roof slope. We found the height of the existing wall at the lowest roof bearing to be approximately eight feet (8' - ½" actual) from the top of slab to the roof bearing point. The architectural drawings provided by Associated Florida Architects, Inc. , incorrectly, show this existing height of bearing to be nine feet (9') — an error of 1'-0".

Sheet	Description/Comments (in italics)	
Cover	Cover, Index, Site Plan @ 1"=30'	(09 May 2005)
	• <i>no site plan actually shown on the cover sheet.</i>	
A - 1.01	Existing Floor Plan @ 1/8" = 1'-0" Demolition Plan @ 1/8" = 1'-0"	(09 May 2005)
	• <i>no accordion door and transom shown at bedroom entry.</i>	
A - 2.01	Floor Plan @ 1/8" = 1'-0" Second Floor Plan 1/8" = 1'-0"	(Rev 13 Nov. 2005)
	• <i>The stairs to the second level show 15 risers on the First Floor Plan and 16 risers on the Second Floor Plan. The landing location is not consistent between the plans resulting in ambiguity as to the circulation to and from the second level.</i>	
	• <i>Gate/entry fence columns not centered on courtyard doors nor are they aligned with the centers of the structural columns of the high ceiling family room. This imbalance will appear as odd.</i>	

- *Roof overhang is not centered on Family Room facade. There is a 2'-0" overhang at the Garage side and a 1'-6" overhang at the existing residence side — they are both shown as 1'-6" on the elevation drawings (A - 4.01, revised 21, July, 2005).*
- *no door shown at bedroom entry in existing residence.*

A - 4.01 Elevations @ 1/4" = 1 foot (Rev, 13 Sep. 2005)
(field directive number one)

- *The elevation drawings show the existing walls at the lowest roof bearing to be approximately 9' tall. Field measurements revealed this dimension to be 8' - 1/2". This error can cause substantial problems in construction especially with a two-story, low roof slope design.*
- *The elevation drawings incorrectly show the building ground relationship of the existing structure.*
- *The elevation drawings incorrectly show the existing eave (overhang) to be 3'-0" when in fact it is actually 5' - 0".*
- *Multiple dimensions on the "Right Side Elevation" as shown on the drawings do not match field measurements with differences of 1'-4" in a dimension of less than 7' - 0". This is far beyond normal tolerances for architectural design at a the drawing scale of 1/8" = 1 foot used in the elevation drawings.*
- *no chimney or fire place venting system is shown for the existing fire place(s). The chimney element is usually a notable design feature of prairie style architecture.*
- *The spiral stair connecting the deck at the second level to the ground should be shown on the elevation as it makes a significant visual impact on the design.*
- *Brick veneer is shown graphically two different sizes of brick.*

A - 6.01 Building Section @ 1/4" = 1' - 0" (9 May 2005)

- *The building section is not keyed to the plan as is standard practice. Without the reference to the plan it is somewhat ambiguous as to where the section is taken.*
- *The circulation connection between the Entry Foyer (area inside of the entry doors) and the Family Room is not shown*

on this drawing. There should be an opening of some kind to show how these spaces will be connected.

- The high roof structure is not shown. The structural system and depth of the structure should be shown for this element as is shown for other framing systems.
- 16 stair risers are shown on the Building Section which is inconsistent with the First Floor Plan. Furthermore, all risers are not shown with the same height — The Florida Building Code requires all stair risers to be the same height.
- The Partial Stair Section detail calls for 7-3/4" risers, which with 16 risers would come to 10' - 4" above the first floor — the second floor is shown at 10' - 0". With 15 stair risers, as is shown on some drawings, the height of the stair would be 9" - 8-1/4 ". The stairs do not connect with the second floor level as shown in any of the drawings.

A - 7.01 Typical Wall Sections @ 3/4" = 1' - 0" (09 May 2005)

- We count at least six different wall/roof or wall/deck bearing conditions. As only one "typical" detail is provided, there is great ambiguity as to how the roof and walls will be joined the variety of configurations that exist in the design.
- The "Optional Typical Detail @ Existing Roof" does not have dimensions noted. When the detail is scaled as per the 3/4" = 1' - 0" scale, the wall height is shown at nine feet (9' - 0"). Field measurements indicate the existing wall is approximately eight feet tall (8' - 1/2" actual).

M - 1.01 Mechanical Plan - First Floor @ 1/8" = 1' - 0" (09 May 2005)
Mechanical Plan - Second Floor @ 1/8" = 1' - 0"

- No drop ceiling or duct soffit shown for supply and return air outlets in the Pub space.
- The supply duct leading to the playroom looks like it will be exposed on the elevation of the building if it is run up to typical supply air height. This plan also shows a window at the top of the stairs that is not in the final version of the plan and elevation drawings.
- A curved landing is also shown here that does not appear in other drawings.

E - 1.01 Electrical Plan - First Floor @ 1/8" = 1' - 0" (09 May 2005)
Electrical Plan - Second Floor @ 1/8" = 1' - 0"

- *The existing panel box is shown to be located on a wall that is shown as removed on the floor plan (A - 2.01, all revision dates) and on the building section (A - 6.01, 9 May, 2005).*
- *A light is shown at a balcony on the second floor. This balcony is not shown in the most recent First Floor Plan or Second Floor Plan.*

S - 1.01 Details, Foundation Plan @ 1/8" = 1' - 0" (09 May 2005)

- *No comments*

S - 2.01 Roof Framing Plan: New Addition (13 Sep. 2005)
@ 1/8" = 1' - 0", Notes, Details

- *Bearing details for framing over the existing structurally modified wall are not shown. This is a complicated structural connection that should be detailed and reviewed by a licensed structural engineer.*
- *The new second level deck is in conflict with the existing roof edge based on the drawings — they are shown to overlap.*
- *18 stair risers shown on the First Floor Framing Plan (15 and 16 risers shown on other drawings as noted above).*
- *A Balcony is shown at the Second Level that is not shown in the most recent Second Floor Plan (13 Sep. 2005).*

The drawings do not meet, in our professional opinion, the minimum standard of care expected for architectural design. There are substantial conflicts between and within the drawings of various dates including the most recent revision. There are, in our professional judgement, significant omissions of important details and drawings such as building sections or wall sections that show the integration of details with major building components.

Structural Integrity

There are serious concerns with the structural integrity of the construction phase that is in place at the time of this report. Deficiencies and inconsistencies regarding the structural veracity of the Construction Documents drawings and the existing partial structure are well documented by the structural evaluation conducted by TLC Engineering for Architects dated August 28, 2006. The review and recommendations by the Freeman Design Group Engineers and Planners points out many difficulties that seemed to arise from trying to correct design conflicts during construction. Furthermore, the building officials from Columbia County in their follow-up letter from a December 13, 2005 site inspection clearly notes the deficiency of the first floor walls ability to support the second floor. These are very serious deficiencies that could lead to structural failure.

Course of Action

A complete redesign of the addition based on the original sketches that Mr. White developed is required to achieve the renovated home originally commissioned. The correct eave wall height and roof pitch of the existing prairie style home must be used in the earliest phases of design to achieve an integrated and aesthetically balanced union between the new and existing structures. The design should not only be studied in orthographic drawings (2D) but also in 3D computer models and/or physical scale models. This is required to work out the complexities of multiple levels interpenetrating a low-slope (2 in 12) roof system.

Demolish, in it's entirety, the partially complete addition that is in place.

A budget cost estimate must be developed based on new construction costs in the locality and projected out to the estimated time of actual construction. This construction cost estimate should be based on the square foot area with specific adjustments for the quality of materials that are clearly indicated in the design proposal by Associated Architects. Furthermore, adjustments will be required for integrating the structural connection between the new addition and the existing residence — this may need to go beyond the original design as structural analysis does not seem to have been integrated into the construction drawings. A qualified cost consultant should be engaged to develop a project budget based on a best estimate given the quality and scope (area and massing) of the design suggested in drawings by Associated Florida Architects, Inc. The cost estimate must include any specific materials, appliances and finishes called out in the construction documents including the Architectural Specifications for the project.

A demolition cost estimate will also need to be developed.

Architects fees and engineering fees will need to be estimated. These fees can be estimated as a percentage of the cost of construction. Architectural services for design phases, construction documents phases and site supervision phase for a home of this scale and architectural significance would be approximately 10% of the actual cost of construction. Engineering fees could range from 1% to 3% of the cost of construction — an engineering firm should be consulted to hone this estimate.


Conclusions

1. The drawings provided by Associated Florida Architects, Inc. do not meet the minimum professional standard and are rife with significant errors and omissions.
2. The Associated Florida Architects, Inc. drawings incorrectly establish the roof pitch of the existing structure subsequently compromising the design of the addition — as drawn, it will not match the existing when constructed.
3. The Associated Florida Architects, Inc. drawings incorrectly establish the height of the low eave bearing point with an error of approximately one foot — the addition, if constructed to the drawings, will not align architecturally with the existing structure when constructed.
4. The Associated Florida Architects, Inc. drawings incorrectly establish the various ground/foundation heights of the existing structure.
5. Modifications to the design were made in the field to correct design errors that contributed to additional conflicts and the noted lack of structural integrity.
6. The exposed frame structure has been compromised by the weather, moisture and molds and is unusable.
7. The structural integrity of the slab does not meet, as per the TLC engineering report, the bearing capacity required for the roof and wall loads.
8. The partially complete addition should be entirely demolished and removed.
9. A complete redesign of the addition is required to integrate the original plan provided by Mr. and Mrs. White with the prairie style existing


home. This will require new and complete architectural and engineering services.

10. A project construction budget must be established based on the built floor area and adjustments for structural requirements and the quality of finishes (as already defined) to establish the professional fees.
11. A complete redesign with integrated structural analysis could take 6 to 12 months.

End of Report



Martin A. Gold, AIA
Principal Architect
AR 93691



Existing Residence

As-built condition shown in grey

AFA, Inc. is Associated Florida Architects, Inc., the incorrect elevation drawing shown in red above is taken from Sheet A-4.01 updated 13 Sept. 2005 and signed and sealed by Robert S. Taylor Sr., AR 0007526.



August 28, 2006

Ed and Diane White
P.O. Box 2111
Lake City, FL 32024

Re: Ed and Diane White Residence
Structural Condition Survey Report
TLC Project No. 106628

Dear Mr. & Mrs. White:

In accordance with your request, on July 27, 2006 a Registered Engineer from this office of TLC Engineering for Architecture, Inc. (TLC) conducted limited visual observations of your residence located approximately 7 miles southwest of Lake City, Florida on State Route 47.

The purpose of this inspection was to observe existing structural conditions and gather information that would enable TLC to render an opinion concerning the condition of the construction work of the building addition to your residence. In addition to evaluating the condition of the work in-place, TLC was asked to review the construction documents prepared by Robert S. Taylor, Sr., Associated Florida Architects, Gainesville, Florida and Tamara G. Baker, P.E., Baker Engineering & Consulting, P.L., Jacksonville, Florida and render an opinion regarding the content of the construction documents. TLC's field visit and this report are not intended to cover hidden defects, hazardous materials, mechanical, electrical or architectural features.

GENERAL INFORMATION

Ed and Diane White are the owners of the residence constructed in 1966 by the father of Diane White. It was the desire of the White's to construct a large, 2-story, 3000 square foot building addition to the existing structure and hired Associated Florida Architects (AFA) to prepare the construction documents. The Whites gave AFA floor plan design sketches and building elevations as a general basis of their concept for the design. AFA prepared construction documents and submitted them to the Columbia County Building Authority for construction permit. A building permit was issued July 25, 2005. Isaac Construction Company, Lake City, Florida was hired by the Whites to construct the building addition. On December 13, 2005, Columbia County Building Authority issued a Stop Work Order and directed the structure be evaluated by a Florida Professional Engineer for compliance with Florida Building Code 2001. To date, no further construction work has been performed by Isaac Construction.

TLC was given copies of many of the construction documents prepared by AFA and Baker Engineering and Consulting, L.P., Jacksonville, Florida. The AFA permit drawings consisted of the following sheets dated May 9, 2005:

Cover	Index of drawings and Wind Load Design Parameters
A1.01	Existing Floor Plan, Demolition Plan
A2.01	First & Second Floor Plans
A4.01	Exterior Building Elevations
A6.01	Building Sections
A7.01	Typical Wall Sections
M1.01	Mechanical Plan First Floor, Mechanical Plan Second Floor
E1.01	Electrical Plan First Floor, Electrical Plan Second Floor
S1.01	Foundation Plan and Details
S2.01	Roof Framing Plan: New Addition, Notes, Details

Revised drawings dated July 21, 2005, identified as Addendum Number One:

A2.01	First & Second Floor Plans, Finish Schedules, Partial Stair Section, Wall Legend
A4.01	Exterior Building Elevations (4 Each)
S2.01	First & Second Floor Roof Framing Plans

Structural drawings prepared by Baker Engineering & Consulting Signed/Sealed May 23, 2005 for inclusion in Addendum Number One.

S-1	General Structural Notes
S-2	Framing Details

OBSERVATIONS

The following is a list of comments concerning the content of the construction documents:

1. Construction drawings and details do not specify an adequate building lateral bracing system to resist Florida Building Code 2001, with 2003 Revisions Building Code (FBC) minimum specified Main Wind Force Pressures. The construction documents do not meet, in our professional opinion, the minimum standard of care for the building structural systems.
2. Construction drawings and details do not specify adequate building foundations at building columns to resist FBC minimum specified Main Wind Force uplift pressures and gravity loads. The construction documents do not meet, in our professional opinion, the minimum standard of care for the building structural systems.
3. Construction drawings and details do not, in our professional opinion, provide adequate fastening and anchoring of new wall sections and roof members to existing structure.



4. Construction drawings and details do not correctly portray the roof pitch of the existing building structure. The design of the building addition was based on faulty information and resulted in building elevations not consistent with as built conditions. The building elevations depicted in the construction drawings and the expectations of the Owners could not be achieved as represented by the drawings. The architect did not verify the as built conditions and developed a design not constructible as shown on the drawings. In our professional opinion, the construction drawings do not meet the minimum standard of care for professionally prepared construction documents.

The following is a list of observations made during the site investigation July 27, 2006:

5. The high roof area is constructed without any evidence of a lateral bracing system to resist FBC main wind forces.
6. Anchoring of the new wall on the west end of the existing building structure is structurally inadequate. No continuous load path to foundation for wind lateral and uplift loads is provided.
7. Columns supporting the high roof structure, second floor loft area and the rear second floor deck structure are not as specified on the construction drawings. No column foundations were observed for these columns.
8. Extension of the side walls supporting the high roof structure is unconventional and does not provide continuous load path for wind uplift forces.
9. Construction of cantilevered engineered wood beams supporting high roof structure is unconventionally framed. The framing does not provide continuous load path to the foundation for lateral and uplift wind forces.
10. Construction of the east wall supporting high roof structure was founded on the existing roof structure not competent to support the loads. Fastening of the new wall to the existing structure is structurally inadequate and provides no continuous load path to foundation for wind lateral and uplift forces.
11. Modification of high roof structure pre-engineered wood trusses is unconventional and structurally inadequate. The truss modifications appear to be absent of engineering input from the truss engineer.
12. The foundation slab on grade was observed to have minimum random cracks. No settlement of the foundation slab was observed. Verification of the foundation size and depth was not made.
13. Mono-pitched roof framing at the second floor loft area is unconventional framing and structurally inadequate. The beam splice/connection is on the verge of structural failure.

14. Construction of second floor deck framing is improperly framed to direct rain water away from the building interior.
15. Interior wood columns supporting the high roof structure are not the members specified on the construction documents and are inadequate to support the roof loads. The columns as constructed bear on the second floor sheathing and are not continuous members to the foundation level. The framing system is unconventional and not compliant with building code standards.
16. High roof trusses are not anchored by metal straps as specified in contract documents and are not in compliant with building code standards.
17. The exposed to weather wood framing materials are severely deteriorated and warped. The majority of the exposed framing must be replaced because of deterioration and sub-standard framing assemblies.

CONCLUSIONS

Based on our observations, we have the following comments:

1. The construction documents do not, in our professional opinion, meet the standard of care for professionally prepared documents. The documents are incomplete, incorrect depiction of as built conditions and structurally inadequate to specify the contraction of the work in accordance with building code standards and accepted engineering standards.
2. The contractor proceeded with construction of the work prior to verification of as built conditions and specifically the roof slope. In our professional opinion, the work proceeded long after the roof slope discrepancy was discovered and framing alterations were initiated by the contractor to compensate for the roof slope discrepancy. Much of the framing alterations were made, in our professional opinion, in the absence of structural engineering consultations as evidenced by the large extent of unconventional framing observed. At the time of the Stop Work Order by Colombia County Building Authority, the as built configuration of the building addition did not resemble the building elevations shown in the construction documents.
3. Construction of the work did not comply with the specified 6"x6" square wood structural columns and isolated concrete foundations shown on the construction documents for the high roof and rear deck structure. The columns constructed are not adequate to support the loads of the structure. The concrete foundations were not constructed.
4. Deterioration of the exposed to weather wood framing is severe and in our professional opinion, should be removed. The extent of the deterioration of the under roof structure framing is, in our professional opinion, minor to severe. However, the extent of unconventional framing and



absences of consistent load path through the structure to the foundation indicates the entire framing be removed from the site and reconstructed to building code standards.

5. Further investigation of the foundation slab on grade is recommended to verify if the foundation system as built is in accordance with building code standards. The existing slab was observed to be generally free of random cracking and a portion of the slab could be used if investigation proves the construction is acceptable. Although several isolated column foundations were not constructed, the foundations could be added to the existing slab on grade if deemed cost effective.


Our opinions are based upon engineering judgment to an extent normal for a field review of this type. We reserve the right to revise or amend our opinions if additional information becomes available in the future. Our review was walk-through in nature and we did not use any special tools or instruments were used for our observations. No material testing, intrusive investigations or structural analysis were made for preparation of this report.

This report is prepared for the sole benefit of Ed and Diane White. Unauthorized use of the information contained in this report without our permission shall result in no liability or legal exposure to TLC.

We appreciate this opportunity to be of service to you. If we can be of further assistance, please call me.

Very truly yours,

TLC ENGINEERING FOR ARCHITECTURE, INC.



David B. Griffith, PE
Principal/Senior Project Engineer



Roger L. Jeffery, P.E.
Principal/Structural Division Director



From: The Columbia County Building Department
Plans Review
135 NE Hernando Av.
P. O Box 1529
Lake City Florida, 32056-1529

Dear Mr. Ed White

On December 13, 2005 per your request Mr. Randy Jones Assistant Building Official, Mr. Harry Dicks Building Inspector and I as the Plans Examiner accompanied you with a structural inspection of your resident at 7018 SW SR 47. The inspection pertains to Building permit number 23411 issued July 25, 2005 to ISAAC. This build permit was to construct an addition on to an existing single family dwelling.

You requested that we inspect the structural framing which has been completed thus far for building code compliance. The Columbia County Building Department has several concerns which are:

1. Mr. Robert Taylor Architect, of Associated Florida Architects, Inc. 802 NW 23rd Avenue Gainesville Florida, State of Florida Registration Number AR-0007526 filed a letter with the Columbia County Building Department on July 22, 2005 which stated that Associated Florida Architects, Inc. were the architects of record for the construction of a addition on to your single family dwelling. Mr. Robert Taylor in this letter also stated that certain structural issues which I as the plan examiner had would be addressed once the construction of this addition was started. Mr. Robert Taylor stated that within forty-five (45) days of commencing with construction a written structural report addressing the needed issues would be filed with the Columbia County Building Department. **No reports have been**

filed with the Columbia County Building Department by Mr. Taylor or Associated Florida Architects.

2. An example of one of the issues which was not addressed was the use of an exterior load bearing foundations and shear walls which was used to construct a second story load bearing wall without the contractor and the architect confirming that the foundation and the structural walls could safely support the additional structural load-bearing weight which has been applied to the foundation and walls for of a second story and a roof truss system.
3. The addition onto the structure of 3,044 square feet incorporated a first and second floor, using wood frame structural walls. Within the first floor several exterior and interior load bearing walls have been created to provide support for the second floor, flooring and roof truss system. Several first floor walls lack sufficient structural strength to properly support the second floor.
2. The roof trusses have been modified by the contractor, the truss designer will be required to assess the trusses system to certify that the trusses system meet the original truss system design.

In order to continue work on this structure, a structural evaluation by a professional architect or engineer is needed to comply with the Florida Building Codes 2001. If you should have any additional question please contact me.

Thank you,



Joe Haltiwanger
Plan Examiner
Columbia County Building Department



Engineers • Planners

161 N.W. Madison St., Suite 102
Lake City, Florida 32055
Tel: 386-758-4209
Fax: 386-758-4290

7/28/2006

Ed White
P. O. Box 1376
Lake City, FL. 32056

Re: Structural Inspection

Dear Mr. White,

I have completed the structural inspection and have reviewed the original plans and the following evidence is evident:

The plans call for an exterior bearing wall height of 9'0". The exterior bearing walls were constructed at an 8'0" height. The ceiling height of the master bedroom is shown as a 9'0" ceiling height but was constructed as a 10'0" ceiling height. During construction the roof of the first floor interfered with the floor level of the second floor since the wall was constructed 1'0" too short and the floor level 1'0" too high. This caused a problem with floor joist layout as indicated on the plans. Since the floor joists interfered with the incorrectly placed roof system, the floor joists were altered so that they were no longer bearing on the walls as indicated on the plans. The plans did indicate structural load bearing walls to support the upper floor joist system, however, by shifting the bearing locations to new non-structural walls there was no provision for a structural foundation or structural headers. This could cause failure in the slab and wall components.

The two-story portion of the house was not constructed to the proper wall height as indicated on the plans. The original design called for a set of four (4) beams to run continuous from front to rear of the structure. The exterior walls were constructed in this manner to perform as a post and beam system. The beams are intended to span a certain distance and then bear on a post which has a structural footing directly underneath. The exterior walls on the two story portion were altered to bring the height up according to the original design. When this was done, the structural beam was removed in order to build a new knee wall above the original wall that was built too low. This created two main problems. When the beam was removed, the post-beam structure became a continuous load-bearing wall. There is no interior structural footing to carry the load along the entire length of wall. When the knee wall was constructed to extend the

wall height per design, a hinge point was created in the wall. This could likely fail when wind pressure is applied to the wall.

A new wall was constructed on top of the original house. At this point, there is no evidence that the exterior wall is resting on anything structural. The weight of the wall and the roof trusses are only bearing on the existing roof decking and is showing signs of excessive deflection. The load-bearing wall needs to have a continuous load path from the foundation, up to the roof.

In order to solve the issues discussed above the structure would need to be dismantled. A redesign of the project should be accomplished taking into account the correct pitch of the existing roof. It should contain detail for the joining of the new and the old structure and foundation requirements to support changes in the correct plans. Because the structure could not be completed the trusses have now been exposed to the weather for nearly a year and have shown signs of twisting and buckling.

If you have any questions, you may contact me at (386) 758-4209.

Sincerely,

A handwritten signature in dark ink, appearing to read 'William Freeman', written in a cursive style.

William Freeman, P.E.

From: The Columbia County Building Department
Plans Review
135 NE Hernando Av.
P. O Box 1529
Lake City Florida, 32056-1529

Dear Mr. Ed White

On December 13, 2005 per your request Mr. Randy Jones Assistant Building Official, Mr. Harry Dicks Building Inspector and I as the Plans Examiner accompanied you with a structural inspection of your resident at 7018 SW Kemp Court. The inspection pertains to Building permit number 23411 issued July 25, 2005 to ISAAC. A Build Permit to construction an addition on to an existing single family dwelling.

You requested that we inspect the structural framing which has been completed thus far for building code compliance. The Columbia County Building Department has several questions and concerns which are describer below.

1. Mr. Robert Taylor Architect, of Associated Florida Architects, Inc. 802 NW 23rd Avenue Gainesville Florida, State of Florida Registration Number AR-0007526 filed a letter (attached) with the Columbia County Building Department on July 22, 2005 which stated that Associated Florida Architects, Inc. were the architects of record for the construction of a addition on to your single family dwelling. Mr. Robert Taylor in this letter also stated that certain structural issues which I as the plan examiner had would be address once the construction of this addition was started. Also with this correspondence Mr. Robert Taylor confirmed that within forty-five (45) day/of commencing with construction a written report would be filed with the Columbia County Building Department to comply with the Florida Building Code 2001 Chapter thirty four (34) sections 3401.8.2.3.1, 3401.8.2.3.2

and 3401.8.2.3.3 which are attached. As of this date these code requirements have not be fulfilled by Mr. Taylor

2. The north existing wall prior to construction was a shear wall for the single family dwelling, additional structural load-bearing weight has been applied to the foundation and wall by the contractor without confirming that the foundation and the structural wall could accommodate these structural loads for of a second story and a roof truss system. The building department questions the foundation integrity to have sufficient load bearing capacity to support the additional weight which has been applied to this foundation and wall. An engineering report will be required to be submitted to building department to state that the existing foundation and wall as modified complies with the Florida building code, as this code relates to foundation and wind-load design requirements for a structural wall of the height to which the wall has been constructed and all components of the wall will receive the required anchoring and strapping devices to comply with the wind-load design requirements.
3. The addition onto the structure of 3,044 square feet incorporated a first and second floor, with wood frame structural walls. Within the first floor several exterior and interior load bearing wall were created to provide support for the second floor, flooring system and roof trusses. Several of these first floor walls lack sufficient structural strength to properly support the second floor. An engineering review of these load bearing walls will be required to bring these walls into compliance with the Florida building code requirements for load bearing walls.

4. Several of the second story roof trusses have been modified by the builder, the engineered truss designer will be required to assess the trusses as modified to certify that these trusses still meet the original truss design.
5. In order to continue work on this structure, a structural evaluation by a professional architect or engineer will be required to be preformed to meet the requirement of chapter 34 of the Florida Building Code sections 3401.8.2.3.1, 3401.8.2.3.2 and 3401.8.2.3.3.

If you should have any question please contact me.

Thank you,



Joe Haltiwanger
Plan Examiner
Columbia County Building Department



associated florida architects, inc.

florida registration AA-C001907

802 nw 23rd avenue • gainesville, florida 32609-3534

352 375-3005 • 352 378-2523 • 352 375-5397 fax

July 22, 2005

Columbia County Building Department

135 NE Hernando Ave.

Lake City, FL 32055

Re: Ed & Diane Bishop-white Residence

To Whom It May Concern:

We are the architects for the referenced project. We have a full service contract with the owners including contract administration.

Due to the fact that this is an addition we will be able to do the discovery work on the existing residence when construction commences.

We will write a report with findings and recommendations within forty-five (45) days of start of construction. As per 3401.8.2.3.1, 3401.8.2.3.2 and 3401.8.2.3.3 of 2001 Florida Building Code.

Robert S. Taylor, Sr. Architect

Florida Registration AR-0007526

3401.8.1.2 The requirements of this section shall not supersede specific requirements of the code for construction in Fire Zones.

3401.8.2 Additions

3401.8.2.1 Any addition or alterations increasing the floor area of the building, shall meet the requirements of this section. For purposes of this section, whether an addition falls within the stated percentages shall be calculated based on the cumulative increase of the building during the course of one calendar year.

3401.8.2.2 All except Group R3 occupancies shall comply with the following:

3401.8.2.2.1 When additions, or alterations increasing floor area, are made to an existing building, and the addition and existing building are separated by a fire rated wall, as defined in Section 704, the addition shall conform to all the requirements of the code applicable to a building of the area of the addition.

3401.8.2.2.2 Where the existing building and the addition are not separated by a fire rated wall and the area of the addition is 25 percent or more of the area of the existing building, the existing building and the addition shall be made to comply with all requirements of the code for a building of area equal to the combined area for the addition and existing building.

3401.8.2.2.3 Where the existing building and the addition are not separated by a fire rated wall or where the addition is vertically superimposed on an existing building, and the area of the addition is less than 25 percent of the area of the existing building, the following requirements shall apply:

1. The addition shall conform to all requirements of the code applicable to a building having the combined area and height of the existing building and the addition.
2. The existing building shall conform to all requirements of the means of egress for a building of the combined area and height of the addition and the existing building.
3. An approved detection, alarm and communications system, detecting products of combustion, shall be required for all public areas and means of egress within the existing building.

3401.8.2.3 Group R3 Occupancies shall comply with the following:

3401.8.2.3.1 When additions, or alterations increasing floor area, are made to an existing building and the addition constitutes 25 percent or more of the area of the existing building, the addition shall be made to comply with all the requirements of the code and the existing building shall comply with the following:

1. Impact resistance devices having a valid NOA shall be installed at openings to provide protection against storms.
2. Corners of buildings of masonry construction shall be checked for tie downs. If tie downs are not found in corners, testing shall be performed to locate tie downs in all walls. Proper installation of tie downs shall be done at 20 foot intervals and at each corner except that interior tie downs may be provided in each side not less than 2 feet on each side of each corner.

2.1 Tie down refers to the anchorage from the foundation to the tie beam and shall provide the equivalent strength of a vertical #5 reinforcing bar properly attached to the foundation and tie beam encased in concrete or mortar and lapped a minimum of 30 inches or otherwise spliced in a manner which will develop the full strength of the bar.

2.2 Alternate methods of providing anchorage of equivalent strength to that described in 2.1 may be used where design calculations which admit rational analysis are submitted by a Registered Engineer or Architect proficient in structural design.

3. Roof anchorage shall be checked at all walls where the addition connects to the existing building. If major deficiencies are found and the anchorage is not in compliance with the minimum requirements of the code, the roof anchorage shall be checked for all the existing roof. Minimum anchorage shall be provided to each member bearing on the exterior walls.
4. Permanent roof bracing shall be provided at all gable ends.
5. G.F.C.I. outlets shall be installed where required by the code.
6. Smoke detectors shall be installed where required by the code.

3401.8.2.3.2 The design professional shall conduct a site visit to ascertain the necessary work to be performed to comply with the requirements of this Section.

3401.8.2.3.3 The design professional shall provide an inspection report and indicate on the drawings all remedial actions to be performed on the building submittal as a part of the permit plans.

3401.8.3 Repairs and alterations

3401.8.3.1 Repairs and alterations not increasing the area of the building, made within any 12 month period, shall meet the requirements of this section.