

DATE 02/15/2019

Columbia County Building Permit

This Permit Must Be Prominently Posted on Premises During Construction

PERMIT

000037753

APPLICANT ROBERT PRATA PHONE 401-862.3339

ADDRESS 5187 FLT RIVER ROAD GREENE RI 02827

OWNER ROBERT & GAIL PRATA PHONE 401-862-3339

ADDRESS 924 SW HIGHFIELD TERR LAKE CITY FL 32024

CONTRACTOR ROBERT & GAIL PRATA PHONE 401.862.3339

LOCATION OF PROPERTY 441 S, R TUSTENUGGEE, R MEADOWLANDS, R HIGHFIELD TERR.  
ON LEFT JUST PAST KELTON (CORNER LOT)

TYPE DEVELOPMENT SFD/UTILITY ESTIMATED COST OF CONSTRUCTION 130000.00

HEATED FLOOR AREA 1350.00 TOTAL AREA 2600.00 HEIGHT 1 STORIES 1

FOUNDATION CONC WALLS FRAMED ROOF PITCH 6'12 FLOOR CONC

LAND USE & ZONING A-3 MAX. HEIGHT

Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00

NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 01-6S-16-03761-161 SUBDIVISION MEADOWLANDS

LOT 61 BLOCK PHASE 4 UNIT TOTAL ACRES 5.00

OWNERS Robert D. Prata

Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor

EXISTING 19-0010 LN TC N

Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident Time/STUP No.

COMMENTS: 1 FOOT ABOVE ROAD.  
12 MONTH RV- WHILE CONSTRUCTING SFD.(37231)

Check # or Cash 103

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by

Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by

Framing date/app. by Insulation date/app. by

Rough-in plumbing above slab and below wood floor date/app. by Electrical rough-in date/app. by

Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by Pool date/app. by

Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by

Pump pole date/app. by Utility Pole date/app. by M/H tie downs, blocking, electricity and plumbing date/app. by

Reconnection date/app. by RV date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 650.00 CERTIFICATION FEE \$ 13.00 SURCHARGE FEE \$ 13.00

MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$

PLAN REVIEW FEE \$ 163.00 DP & FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ TOTAL FEE 914.00

INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY.

NOTICE: ALL OTHER APPLICABLE STATE OR FEDERAL PERMITS SHALL BE OBTAINED BEFORE COMMENCEMENT OF THIS PERMITTED DEVELOPMENT.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED NOT SUSPENDED, ABANDONED OR INVALID WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS OT THE PREVIOUS INSPECTION.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.



For Office Use Only Application # 1811-70 Date Received 11/21 By JTW Permit # 37753  
Zoning Official LN Date 12-17 Flood Zone X Land Use A Zoning A-3  
FEMA Map # \_\_\_\_\_ Elevation \_\_\_\_\_ MFE 1.82 River valley Plans Examiner J.C. Date 12-17-18  
Comments Corrected Elevation 4/19/19 - Plat requires MFE of 83.0' Need Elevation Confirmation Letter at 5/14/19  
☒ NOC ☒ EH ☒ Deed or PA ☒ Site Plan ☐ State Road Info ☒ Well letter ☒ 911 Sheet ☐ Parent Parcel # \_\_\_\_\_  
☐ Dev Permit # \_\_\_\_\_ ☐ In Floodway ☐ Letter of Auth. from Contractor ☐ F W Comp. letter  
☒ Owner Builder Disclosure Statement ☐ Land Owner Affidavit ☐ Ellisville Water ☒ App Fee Paid ☒ Sub VF Form  
Septic Permit No. 19-0010 OR City Water ☐ Fax \_\_\_\_\_  
Applicant (Who will sign/pickup the permit) GAIL & Bob Prata Phone 401 741-8111  
Address 5187 Flat River Rd - Greene, MS 38227  
Owners Name Robert & Gail Prata Phone 401-862-3339 Bob  
401-741-8111 GAIL  
911 Address 924 S.W. High Field Terr - Lake City, FL 32024  
Contractors Name Bob Prata Phone 401-862-3339  
Address 924 S.W. High Field Terr. - Lake City, FL 32024  
Contractor Email bobprata@cox.net \*\*\*Include to get updates on this job.  
Fee Simple Owner Name & Address \_\_\_\_\_  
Bonding Co. Name & Address N/A  
Architect/Engineer Name & Address MARK Disasway P.E.; 163 S.W. Midtown Place Ste 103 L.C. FL 32025  
Mortgage Lenders Name & Address N/A  
Circle the correct power company ☐ FL Power & Light ☒ Clay Elec. ☐ Suwannee Valley Elec. ☐ Duke Energy  
Property ID Number 01-65-16-03761-161 Estimated Construction Cost \$150,000-  
Subdivision Name Meadowlands phase 4 Lot 61 Block \_\_\_\_\_ Unit \_\_\_\_\_ Phase 4  
Driving Directions from a Major Road S.W. Tuskenagee to S.W. Meadowslands to High Field Terrace - Lake City, FL 32024 41/44FS TO C-131 S. TR TO MEADOWLANDS, TR to high Field, TR on L just KELTON (CORNER lot  
Construction of SFD Commercial ☐ OR ☒ Residential  
Proposed Use/Occupancy yes RESIDENTIAL Number of Existing Dwellings on Property 0  
Is the Building Fire Sprinkled? No If Yes, blueprints included \_\_\_\_\_ Or Explain 6'12"  
Circle Proposed ☒ Culvert Permit or ☐ Culvert Waiver or ☐ D.O.T. Permit or ☒ Have an Existing Drive  
Actual Distance of Structure from Property Lines - Front 197' Side 120' Side 145' Rear 377'  
Number of Stories 1 Heated Floor Area 1350 sq ft Total Floor Area 2600 Acreage 5  
Zoning Applications applied for (Site & Development Plan, Special Exception, etc.) N/A  
JTW sent email 11.21.18 JTW spoke w/ Gail 12.17.18



**Columbia County Building Permit Application**

**CODE: Florida Building Code 2017 and the 2014 National Electrical Code.**

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

**TIME LIMITATIONS OF APPLICATION :** An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless pursued in good faith or a permit has been issued.

**TIME LIMITATIONS OF PERMITS:** Every permit issued shall become invalid unless the work authorized by such permit is commenced within 180 days after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of 180 days after the time work is commenced. A valid permit receives an approved inspection every 180 days. Work shall be considered not suspended, abandoned or invalid when the permit has received an approved inspection within 180 days of the previous approved inspection.

**FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment:** According to Florida Law, those who work on your property or provide materials, and are not paid-in-full, have a right to enforce their claim for payment against your property. This claim is known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look to your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

**NOTICE OF RESPONSIBILITY TO CONTRACTOR AND AGENT:** **YOU ARE HEREBY NOTIFIED** as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that result in ponding of water, or other damage to roadway and other public infrastructure facilities caused by you or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.

**WARNING TO OWNER:** YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

**OWNERS CERTIFICATION:** I CERTIFY THAT ALL THE FOREGOING INFORMATION IS ACCURATE AND THAT ALL WORK WILL BE DONE IN COMPLIANCE WITH ALL APPLICABLE LAWS REGULATING CONSTRUCTION AND ZONING.

**NOTICE TO OWNER:** There are some properties that may have deed restrictions recorded upon them. These restrictions may limit or prohibit the work applied for in your building permit. You must verify if your property is encumbered by any restrictions or face possible litigation and or fines.

Robert D. Prata  
Print Owners Name

Robert D. Prata  
Owners Signature

**\*\*Property owners must sign here  
before any permit will be issued.**

**\*\*If this is an Owner Builder Permit Application then, ONLY the owner can sign the building permit when it is issued.**

**CONTRACTORS AFFIDAVIT:** By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit including all application and permit time limitations.

Robert D. Prata - homeowner  
Contractor's Signature


Contractor's License Number \_\_\_\_\_  
Columbia County  
Competency Card Number \_\_\_\_\_

Affirmed under penalty of perjury to by the Contractor and subscribed before me this \_\_\_\_ day of \_\_\_\_\_ 20\_\_.

Personally known ☐ or Produced Identification \_\_\_\_\_

SEAL:

\_\_\_\_\_  
State of Florida Notary Signature (For the Contractor)





**A&B Well Drilling, Inc.**

5673 NW Lake Jeffery Road  
Lake City, FL 32055  
Telephone: (386) 758-3409  
Cell: (386) 623-3151  
Fax: (386) 758-3410  
Owner: Bruce Park

September 9, 2018

To: Columbia County Building Department

Description of Well to be installed for Customer Bob Prata

Located @ Address: 924 SW Highfield Terr

1 HP 20 GPM submersible pump, 1 1/4" drop pipe, 85 gallon captive tank, and backflow prevention.  
With SRWMD permit.

Bruce Park

Sincerely,  
Bruce N. Park  
President

*needed for building permit*

FIFTEEN





## **COLUMBIA COUNTY BUILDING DEPARTMENT**

135 NE Hernando Ave., Suite B-21

Lake City, FL 32055

Office: 386-758-1008 Fax: 386-758-2160

### **OWNER BUILDER DISCLOSURE STATEMENT**

I understand that state law requires construction to be done by a licensed contractor and have applied for an owner-builder permit under an exemption from the law. The exemption specifies that I, as the owner of the property listed, may act as my own contractor with certain restrictions even though I do not have a license.

I understand that building permits are not required to be signed by a property owner unless he or she is responsible for the construction and is not hiring a licensed contractor to assume responsibility.

I understand that, as an owner-builder, I am the responsible party of record on a permit. I understand that I may protect myself from potential financial risk by hiring a licensed contractor and having the permit filed in his or her name instead of my own name. I also understand that a contractor is required by law to be licensed and bonded in Florida and to list his or her license numbers on permits and contracts.

I understand that I may build or improve a one-family or two-family residence or farm outbuilding. I may also build or improve a commercial building if the costs do not exceed \$75,000. The building or residence must be for my own use or occupancy. It may not be built or substantially improved for sale or lease. If a building or residence that I have built or substantially improved myself is sold or leased within 1 year after the construction is complete, the law will presume that I built or substantially improved it for sale or lease, which violates the exemption.

I understand that, as the owner-builder, I must provide direct, onsite supervision of the construction.

I understand that I may not hire an unlicensed person to act as my contractor or to supervise persons working on my building or residence. It is my responsibility to ensure that the persons whom I employ have the licenses required by law and by county or municipal ordinance.

I understand that it is frequent practice of unlicensed persons to have the property owner obtain an owner-builder permit that erroneously implies that the property owner is providing his or her own labor and materials. I, as an owner-builder, may be held liable and subjected to serious financial risk for any injuries sustained by an unlicensed person or his or her employees while working on my property. My homeowner's insurance may not provide coverage for those injuries. I am willfully acting as an owner-builder and am aware of the limits of my insurance coverage for injuries to workers on my property.



I understand that I may not delegate the responsibility for supervising work to a licensed contractor who is not licensed to perform the work being done. Any person working on my building who is not licensed must work under my direct supervision and must be employed by me, which means that I must comply with laws requiring the withholding of federal income tax and social security contributions under the Federal Insurance Contributions Act (FICA) and must provide workers' compensation for the employee. I understand that my failure to follow these laws may subject me to serious financial risk.

I agree that, as the party legally and financially responsible for this proposed construction activity, I will abide by all applicable laws and requirements that govern owner-builders as well as employers. I also understand that the construction must comply with all applicable laws, ordinances, building codes, and zoning regulations.

I understand that I may obtain more information regarding my obligations as an employer from the Internal Revenue Service, the United States Small Business Administration, the Florida Department of Financial Services, and the Florida Department of Revenue. I also understand that I may contact the Florida Construction Industry Licensing Board at 850-487-1395 or Internet website address <http://www.myfloridalicense.com/dbpr/> for more information about licensed contractors.

I am aware of, and consent to, an owner-builder building permit applied for in my name and understand that I am the party legally and financially responsible for the proposed construction activity at the following address:

924 S.W. High Field Terrace - Lake City, Fl. 32024.

I agree to notify Columbia County Building Department immediately of any additions, deletions, or changes to any of the information that I have provided on this disclosure. Licensed contractors are regulated by laws designed to protect the public. If you contract with a person who does not have a license, the Construction Industry Licensing Board and Department of Business and Professional Regulation may be unable to assist you with any financial loss that you sustain as a result of a complaint. Your only remedy against an unlicensed contractor may be in civil court. It is also important for you to understand that, if an unlicensed contractor or employee of an individual of firm is injured while working on your property, you may be held liable for damages. If you obtain an owner-builder permit and wish to hire a licensed contractor, you will be responsible for verifying whether the contractor is properly licensed and the status of the contractor's workers' compensation coverage.

I understand that if I hire subcontractors they must be licensed for that type of work in Columbia County, ex: framing, stucco, masonry, and state registered builders. Registered Contractors must have a minimum of \$300,000.00 in General Liability insurance coverage and the proper workers' compensation. Specialty Contractors must have a minimum of \$100,000.00 in General Liability insurance coverage and the proper workers' compensation coverage.



Before a building permit can be issued, this disclosure statement must be completed and signed by the property owner and returned to Columbia County Building Department.

#### TYPE OF CONSTRUCTION

- ☒ Single Family Dwelling    ☐ Two-Family Residence    ☐ Farm Outbuilding  
☐ Addition, Alteration, Modification or other Improvement  
☐ Commercial, Cost of Construction \_\_\_\_\_ for construction of \_\_\_\_\_  
☐ Other \_\_\_\_\_


I, Robert D. Prata, have been advised of the above disclosure statement for exemption from contractor licensing as an owner/builder. I agree to comply with all requirements provided for in Florida Statutes allowing this exception for the construction permitted by Columbia County Building Permit.

Robert D. Prata                      9/25/18  
Owner Builder Signature                      Date

#### NOTARY OF OWNER BUILDER SIGNATURE

The above signer is personally known to me or produced identification DL

Notary Signature [Signature]                      Date 9.25.18



#### FOR BUILDING DEPARTMENT USE ONLY

I hereby certify that the above listed owner builder has been given notice of the restriction stated above.

Building Official/Representative [Signature]

# Columbia County Property Appraiser

updated: 11/1/2018

## 2018 Tax Roll Year

Parcel: 01-6S-16-03761-161

&lt;&lt; Next Lower Parcel   Next Higher Parcel &gt;&gt;

Tax Collector

Tax Estimator

Property Card

Parcel List Generator

2018 TRIM (pdf)


Interactive GIS Map

Print

Search Result: 1 of 1

### Owner & Property Info

Owner's Name	PRATA ROBERT D & GAIL M		
Mailing Address	734 SHOREHAVEN DR KISSIMMEE, FL 34759		
Site Address			
Use Desc. (code)	VACANT (000000)		
Tax District	3 (County)	Neighborhood	1616
Land Area	5.000 ACRES	Market Area	02
Description	NOTE: This description is not to be used as the Legal Description for this parcel in any legal transaction.		
LOT 61 MEADOWLANDS S/D PHASE 4 LOT 61 MEADOWLANDS S/D PHASE 4 AG 1061-1343, WD 1128-157,159 AG 1061-1343, WD 1128-157,159 WD 1247-440 WD 1247-440, WD 1365-186,			



### Property & Assessment Values

#### 2018 Certified Values

There are no 2018 Certified Values for this parcel

#### 2019 Working Values

( Hide Values)

<b>Mkt Land Value</b>	cnt: (0)	\$29,000.00
<b>Ag Land Value</b>	cnt: (1)	\$0.00
<b>Building Value</b>	cnt: (0)	\$0.00
<b>XFOB Value</b>	cnt: (0)	\$0.00
<b>Total Appraised Value</b>		\$29,000.00
<b>Just Value</b>		\$29,000.00
<b>Class Value</b>		\$0.00
<b>Assessed Value</b>		\$29,000.00
<b>Exempt Value</b>		\$0.00
<b>Total Taxable Value</b>		Cnty: \$29,000 Other: \$29,000   Schl: \$29,000

**NOTE: 2019 Working Values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.**

### Sales History

Show Similar Sales within 1/2 mile

Sale Date	OR Book/Page	OR Code	Vacant / Improved	Qualified Sale	Sale RCode	Sale Price
7/18/2018	1365/186	WD	V	Q	01	\$50,000.00
12/31/2012	1247/440	WD	V	U	30	\$100.00
8/10/2007	1128/159	WD	V	Q		\$60,000.00
8/9/2007	1128/157	WD	V	U	04	\$100.00
2/18/2005	1061/1343	AG	V	U	01	\$48,000.00
5/10/1993	774/1235	WD	V	U	34	\$20,000.00
10/20/1988	665/185	WD	I	Q		\$128,000.00
7/17/1987	628/157	WD	I	U		\$35,000.00

### Building Characteristics



District No. 1 - Ronald Williams  
District No. 2 - Rusty DePratter  
District No. 3 - Bucky Nash  
District No. 4 - Everett Phillips  
District No. 5 - Tim Murphy



**BOARD OF COUNTY COMMISSIONERS • COLUMBIA COUNTY**

**Address Assignment and Maintenance Document**

To maintain the county wide Addressing Policy you must make application for a 9-1-1 Address at the time you apply for a building permit. The established standards for addressing and posting numbers to all principal buildings, dwellings, businesses and industries are contained in Columbia County Ordinance 2001-9. The addressing system is to enable Emergency Services Agencies to locate you in an emergency, and to assist the United States Postal Service and the public in the timely and efficient provision of services to residents and businesses of Columbia County

Date/Time Issued: 8/10/2018 11:15:07 AM  
Address: 924 SW HIGH FIELD Ter  
City: LAKE CITY  
State: FL  
Zip Code: 32024

Parcel ID 03761-161

REMARKS: Address for proposed structure on parcel.

**NOTICE: THIS ADDRESS WAS ISSUED BASED ON LOCATION AND ACCESS INFORMATION RECEIVED FROM THE REQUESTER. SHOULD, AT A LATER DATE, THE LOCATION AND/OR ACCESS INFORMATION BE FOUND TO BE IN ERROR OR CHANGED, THIS ADDRESS IS SUBJECT TO CHANGE.**

Address Issued By: **Signed:/ Matt Crews**

Columbia County GIS/911 Addressing Coordinator

**COLUMBIA COUNTY  
911 ADDRESSING / GIS DEPARTMENT**

263 NW Lake City Ave., Lake City, FL 32055 Telephone: (386) 758 1125  
Email: [gis@columbiacountyfla.com](mailto:gis@columbiacountyfla.com)


- ✓ 2) Footprint of proposed and existing structures (including decks) label these with existing addresses
- ✓ 3) Distance from structures to all property lines
- ✓ 4) Location and size of easements
- ✓ 5) Driveway path and distance at the entrance to the nearest property line 44' to center of SW
- ✓ 6) Location and distance from any waters, sink holes, wetlands, and etc
- ✓ 7) Show slopes and or drainage paths
- ✓ 8) Arrow showing North direction

### SITE PLAN EXAMPLE

Revised 7-1-15

**NOTE:**  
This site plan can be copied and used with the 911 Addressing Dept. application forms.

SW Keltax Glen





**A&B Well Drilling, Inc.**

5673 NW Lake Jeffery Road  
Lake City, FL 32055  
Telephone: (386) 758-3409  
Cell: (386) 623-3151  
Fax: (386) 758-3410  
Owner: Bruce Park

September 9, 2018

To: Columbia County Building Department

Description of Well to be installed for Customer Bob Prata

Located @ Address: 924 SW Highfield Terr

1 HP 20 GPM submersible pump, 1 1/4" drop pipe, 85 gallon captive tank, and backflow prevention.  
With SRWMD permit.

Bruce Park

Sincerely,  
Bruce N. Park  
President

*needed for building permit*

*FIFTEEN*

# SUBCONTRACTOR VERIFICATION

APPLICATION/PERMIT # 1811-70 JOB NAME Robert & Gail Prata  
924 S.W. HIGH FIELD TER, Lake City  
**THIS FORM MUST BE SUBMITTED BEFORE A PERMIT WILL BE ISSUED** 320240

Columbia County issues combination permits. One permit will cover all trades doing work at the permitted site. It is **REQUIRED** that we have records of the subcontractors who actually did the trade specific work under the general contractors permit.

**NOTE:** It shall be the responsibility of the general contractor to make sure that all of the subcontractors are licensed with the Columbia County Building Department.

**Use website to confirm licenses:** <http://www.columbiacountyfla.com/PermitSearch/ContractorSearch.aspx>

**NOTE:** If this should change prior to completion of the project, it is your responsibility to have a corrected form submitted to our office, before that work has begun.

Violations will result in stop work orders and/or fines.

<b>ELECTRICAL</b> <input type="checkbox"/>	Print Name <u>Robert Prata</u> Signature <u>Robert D. Prata</u>	Need <input type="checkbox"/> Lic <input type="checkbox"/> Liab <input type="checkbox"/> W/C <input type="checkbox"/> EX <input type="checkbox"/> DE
CC# _____	Company Name: _____ License #: _____ Phone #: <u>401-862-3339</u>	
<b>MECHANICAL/A/C</b> <input type="checkbox"/>	Print Name <u>Robert Prata</u> Signature <u>Robert D. Prata</u>	Need <input type="checkbox"/> Lic <input type="checkbox"/> Liab <input type="checkbox"/> W/C <input type="checkbox"/> EX <input type="checkbox"/> DE
CC# _____	Company Name: _____ License #: _____ Phone #: <u>401-862-3339</u>	
<b>PLUMBING/GAS</b> <input type="checkbox"/>	Print Name <u>Robert Prata</u> Signature <u>Robert D. Prata</u>	Need <input type="checkbox"/> Lic <input type="checkbox"/> Liab <input type="checkbox"/> W/C <input type="checkbox"/> EX <input type="checkbox"/> DE
CC# _____	Company Name: _____ License #: _____ Phone #: _____	
<b>ROOFING</b> <input type="checkbox"/>	Print Name <u>Robert Prata</u> Signature <u>Robert D. Prata</u>	Need <input type="checkbox"/> Lic <input type="checkbox"/> Liab <input type="checkbox"/> W/C <input type="checkbox"/> EX <input type="checkbox"/> DE
CC# _____	Company Name: _____ License #: _____ Phone #: <u>401-862-3339</u>	
<b>SHEET METAL</b> <input type="checkbox"/>	Print Name <u>Robert Prata</u> Signature <u>Robert D. Prata</u>	Need <input type="checkbox"/> Lic <input type="checkbox"/> Liab <input type="checkbox"/> W/C <input type="checkbox"/> EX <input type="checkbox"/> DE
CC# _____	Company Name: _____ License #: _____ Phone #: <u>401-862-3339</u>	
<b>FIRE SYSTEM/SPRINKLER</b> <input type="checkbox"/>	Print Name _____ Signature _____	Need <input type="checkbox"/> Lic <input type="checkbox"/> Liab <input type="checkbox"/> W/C <input type="checkbox"/> EX <input type="checkbox"/> DE
CC# _____	Company Name: _____ License #: _____ Phone #: _____	
<b>SOLAR</b> <input type="checkbox"/>	Print Name _____ Signature _____	Need <input type="checkbox"/> Lic <input type="checkbox"/> Liab <input type="checkbox"/> W/C <input type="checkbox"/> EX <input type="checkbox"/> DE
CC# _____	Company Name: _____ License #: _____ Phone #: _____	
<b>STATE SPECIALTY</b> <input type="checkbox"/>	Print Name _____ Signature _____	Need <input type="checkbox"/> Lic <input type="checkbox"/> Liab <input type="checkbox"/> W/C <input type="checkbox"/> EX <input type="checkbox"/> DE
CC# _____	Company Name: _____ License #: _____ Phone #: _____	





STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
ONSITE SEWAGE TREATMENT AND DISPOSAL  
SYSTEM  
APPLICATION FOR CONSTRUCTION PERMIT

PERMIT NO. 19-8010  
DATE PAID: 1-4-19  
FEE PAID: 200.00  
RECEIPT #: 1391021

## APPLICATION FOR:

☒ New System ☒ Existing System ☐ Holding Tank ☐ Innovative  
☐ Repair ☐ Abandonment ☐ Temporary ☐

APPLICANT: Robert E GAIL PrataAGENT: N/ATELEPHONE: 401-741-8111MAILING ADDRESS: 5187 FLAT RIVER Rd ~ Greene, FL 02827

TO BE COMPLETED BY APPLICANT OR APPLICANT'S AUTHORIZED AGENT. SYSTEMS MUST BE CONSTRUCTED BY A PERSON LICENSED PURSUANT TO 489.105 (3) (m) OR 489.552, FLORIDA STATUTES. IT IS THE APPLICANT'S RESPONSIBILITY TO PROVIDE DOCUMENTATION OF THE DATE THE LOT WAS CREATED OR PLATTED (MM/DD/YY) IF REQUESTING CONSIDERATION OF STATUTORY GRANDFATHER PROVISIONS.

## PROPERTY INFORMATION

LOT: 61 BLOCK:        SUBDIVISION: Meadowlands <sup>Phase</sup> 4 PLATTED: yes

PROPERTY ID #: 01-6S-16-03761-161 ZONING: AG I/M OR EQUIVALENT: ☐ Y ☒ N

PROPERTY SIZE: 5 ACRES WATER SUPPLY: ☒ PRIVATE PUBLIC ☐ ☐ ≤2000GPD ☐ >2000GPD

IS SEWER AVAILABLE AS PER 381.0065, FS? ☒ Y ☒ N DISTANCE TO SEWER:        FT

PROPERTY ADDRESS: 924 S.W. High Field Terrace, Lake City, FL 32024

DIRECTIONS TO PROPERTY: Rt 411 to Tuskenugue to Meadowlands Dr to S.W. High Field Terrace. Corner lot w/ S.W. Keltor on side of house

## BUILDING INFORMATION

☒ RESIDENTIAL ☐ COMMERCIAL

Unit No	Type of Establishment	No. of Bedrooms	Building Area Sqft	Commercial/Institutional System Design Table 1, Chapter 64E-6, FAC
1	<u>Home (SINGLE)</u>	<u>2</u>	<u>2600</u>	
2				
3				
4				

☐ Floor/Equipment Drains ☐ Other (Specify)       

SIGNATURE: Rhonda PrataDATE: 1/26/19

STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
APPLICATION FOR CONSTRUCTION PERMIT


Permit Application Number 19-0010

Prata

## - PART II - SITEPLAN

Scale: Each block represents 10 feet and 1 inch = 40 feet.

Scale: 1 inch = 40 feet.



**Notes:**

Site Plan submitted by:

Plan Approved

Not Approved

Date 1.7.19

By\_

County Health Department

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT



# NOTICE OF COMMENCEMENT

Tax Parcel Identification Number:

01-65-16-03761-161

Clerk's Office Stamp

Inst: 201912003717 Date: 02/15/2019 Time: 11:56AM  
Page 1 of 1 B: 1378 P: 1026, P. DeWitt Cason, Clerk of Court  
Columbia, County, By: BD  
Deputy Clerk

THE UNDERSIGNED hereby gives notice that improvements will be made to certain real property, and in accordance with Section 713.13 of the Florida Statutes, the following information is provided in this NOTICE OF COMMENCEMENT.

1. Description of property (legal description): 5 Acre Parcel  
a) Street (job) Address: 924 SW High Field Terrace
2. General description of improvements: New home
3. Owner Information or Lessee information if the Lessee contracted for the improvements:  
a) Name and address: Robert & Gail Prata 924 High Field Terrace  
b) Name and address of fee simple titleholder (if other than owner):  
c) Interest in property: OWNERS
4. Contractor Information  
a) Name and address: Robert Prata - 924 SW High Field Terrace  
b) Telephone No.: 401-862-3339
5. Surety Information (if applicable, a copy of the payment bond is attached):  
a) Name and address: N/A  
b) Amount of Bond:  
c) Telephone No.:
6. Lender  
a) Name and address: N/A  
b) Phone No.:
7. Person within the State of Florida designated by Owner upon whom notices or other documents may be served as provided by Section 713.13(1)(a)7., Florida Statutes:  
a) Name and address: Robert Prata 924 SW High Field Terrace  
b) Telephone No.: 401-862-3339
8. In addition to himself or herself, Owner designates the following person to receive a copy of the Lienor's Notice as provided in Section 713.13(1)(b), Florida Statutes:  
a) Name: \_\_\_\_\_ OF \_\_\_\_\_  
b) Telephone No.: \_\_\_\_\_
9. Expiration date of Notice of Commencement (the expiration date will be 1 year from the date of recording unless a different date is specified): \_\_\_\_\_

**WARNING TO OWNER: ANY PAYMENTS MADE BY THE OWNER AFTER THE EXPIRATION OF THE NOTICE OF COMMENCEMENT ARE CONSIDERED IMPROPER PAYMENTS UNDER CHAPTER 713, PART I, SECTION 713.13, FLORIDA STATUTES, AND CAN RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY; A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT YOUR LENDER OR AN ATTORNEY BEFORE COMMENCING WORK OR RECORDING YOUR NOTICE OF COMMENCEMENT.**

STATE OF FLORIDA  
COUNTY OF COLUMBIA

10. Gail Prata  
Signature of Owner or Lessee, or Owner's or Lessee's Authorized Office/Director/Partner/Manager

Gail Prata  
Printed Name and Signatory's Title/Office

The foregoing instrument was acknowledged before me, a Florida Notary, this 15th day of Feb, 2019, by:

Gail Prata as Owner for \_\_\_\_\_  
(Name of Person) (Type of Authority) (name of party on behalf of whom instrument was executed)

Personally Known \_\_\_\_\_ OR Produced Identification ☒ Type RI D/L

Notary Signature

Frances Voncile Dow

Notary Stamp or Seal:



FRANCES VONCILE DOW  
Commission # GG 263070  
Expires October 3, 2022  
Bonded Thru Budget Notary Services

1811-70

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and approval numbers on the building components listed below if they will be utilized on the construction project for which you are applying for a building permit. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. Statewide approved products are listed online @ [www.floridabuilding.org](http://www.floridabuilding.org)

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
<b>1. EXTERIOR DOORS</b>			
A. SWINGING	MASONITE	In/out Swinging fiberglass	FL-8228R7
B. SLIDING	MASONITE	In/out Swinging fiberglass	FL-8228R7
C. SECTIONAL/ROLL UP			
D. OTHER			
<b>2. WINDOWS</b>			
A. SINGLE/DOUBLE HUNG	Anderson	Series 400	FL-1091.1
B. HORIZONTAL SLIDER			
C. CASEMENT			
D. FIXED			
E. MULLION			
F. SKYLIGHTS	Velux		
G. OTHER			
<b>3. PANEL WALL</b>			
A. SIDING	Baycan	Vinyl Siding	FL-15867-R1
B. SOFFITS	Raycan	Vinyl / PVC - Aluminum	FL-16503
C. STOREFRONTS			
D. GLASS BLOCK			
E. OTHER			
<b>4. ROOFING PRODUCTS</b>			
A. ASPHALT SHINGLES	Certainteed	Asphalt Shingles	FL-5444
B. NON-STRUCTURAL METAL			
C. ROOFING TILES			
D. SINGLE PLY ROOF			
E. OTHER			
<b>5. STRUCTURAL COMPONENTS</b>			
A. WOOD CONNECTORS	on prints		
B. WOOD ANCHORS			
C. TRUSS PLATES			
D. INSULATION FORMS			
E. LINTELS			
F. OTHERS			
<b>6. NEW EXTERIOR</b>			
<b>ENVELOPE PRODUCTS</b>			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturers installation requirements.

Further, I understand these products may have to be removed if approval cannot be demonstrated during inspection.

Contractor OR Agent Signature

Date

NOTES



## COLUMBIA COUNTY BUILDING DEPARTMENT RESIDENTIAL CHECK LIST

MINIMUM PLAN REQUIREMENTS: FLORIDA BUILDING CODE RESIDENTIAL 2017 EFFECTIVE 1 JANUARY 2018  
AND THE NATIONAL ELECTRICAL 2014 EFFECTIVE 1 JANUARY 2018

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

**ALL BUILDING PLANS MUST INDICATE COMPLIANCE WITH THE CURRENT FLORIDA BUILDING CODES RESIDENTIAL AND THE NATIONAL ELECTRICAL CODE. ALL PLANS OR DRAWINGS SHALL PROVIDE CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS, FBC 1609.3.1 THRU 1609.3.3.**

**FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER FLORIDA BUILDING CODE FIGURE 1609-A THROUGH 1609-C ULTIMATE DESIGN WIND SPEEDS FOR RISK CATEGORY AND BUILDINGS AND OTHER STRUCTURES**

Revised 7/1/18

**Website:** <http://www.columbiacountyfla.com/BuildingandZoning.asp>

Items to Include-  
Each Box shall be  
Circled as  
Applicable

### GENERAL REQUIREMENTS:

**APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL**

Select From Drop down

1	Two (2) complete sets of plans containing the following:	<input checked="" type="checkbox"/>		
2	All drawings must be clear, concise, drawn to scale, details that are not used shall be marked void	<input checked="" type="checkbox"/>		
3	Condition space (Sq. Ft.) 1350	Total (Sq. Ft.) under roof 2600	Yes	No NA

Designers name and signature shall be on all documents and a licensed architect or engineer, signature and official embossed seal shall be affixed to the plans and documents as per the FLORIDA BUILDING CODES RESIDENTIAL 107.1.

### Site Plan information including:

4	Dimensions of lot or parcel of land	Yes		
5	Dimensions of all building set backs	Yes		
6	Location of all other structures (include square footage of structures) on parcel, existing or proposed well and septic tank and all utility easements.	Yes		
7	Provide a full legal description of property.	Yes		

### Wind-load Engineering Summary, calculations and any details are required.

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable		
8	Plans or specifications must show compliance with FBCR Chapter 3	Yes	No	NA
		Select From Drop down		
9	Basic wind speed (3-second gust), miles per hour	Yes		
10	(Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated)	Yes		
11	Wind importance factor and nature of occupancy	Yes		
12	The applicable internal pressure coefficient, Components and Cladding	Yes		
13	The design wind pressure in terms of psf (kN/m <sup>2</sup> ), to be used for the design of exterior component, cladding materials not specifi ally designed by the registered design professional.	Yes		

### Elevations Drawing including:

14	All side views of the structure	Yes		
15	Roof pitch	Yes		
16	Overhang dimensions and detail with attic ventilation	Yes		
17	Location, size and height above roof of chimneys	NA		
18	Location and size of skylights with Florida Product Approval	NA		
19	Number of stories	Yes		
20	Building height from the established grade to the roofs highest peak	Yes		



**Floor Plan Including:**

21	Dimensioned area plan showing rooms, attached garage, breeze ways, covered porches, deck, balconies	Yes		
22	Raised floor surfaces located more than 30 inches above the floor or grade	NA		
23	All exterior and interior shear walls indicated	Yes		
24	Shear wall opening shown (Windows, Doors and Garage doors)	Yes		
25	Show compliance with Section FBCR 310 Emergency escape and rescue opening shown in each bedroom (net clear opening shown) and Show compliance with Section FBC 1405.13.2 where the opening of an operable window is located more than 72 inches above the finished grade or surface below, the lowest part of the clear opening of the window shall be a minimum of 24 inches above the finished floor of the room in which the window is located. Glazing between the floor and 24 inches shall be fixed or have openings through which a 4-inch-diameter sphere cannot pass.	Yes		
26	Safety glazing of glass where needed	Yes		
27	Fireplaces types (gas appliance) (vented or non-vented) or wood burning with Hearth (see chapter 10 and chapter 24 of FBCR)	NA		
28	Show stairs with dimensions (width, tread and riser and total run) details of guardrails, Handrails	NA		
29	Identify accessibility of bathroom (see FBCR SECTION 320)	Yes		

**All materials placed within opening or onto/into exterior walls, soffits or roofs shall have Florida product approval number and mfg. installation information submitted with the plans (see Florida product approval form)**

<b>GENERAL REQUIREMENTS:</b> <b>APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL</b>		Items to Include- Each Box shall be Circled as Applicable		
---	--	--	--	--

**FBCR 403: Foundation Plans**

		Select From Drop down		
30	Location of all load-bearing walls footings indicated as standard, monolithic, dimensions, size and type of reinforcing.	Yes		
31	All posts and/or column footing including size and reinforcing	Yes		
32	Any special support required by soil analysis such as piling.	NA		
33	Assumed load-bearing value of soil                      Pound Per Square Foot	NA		
34	Location of horizontal and vertical steel, for foundation or walls (include # size and type) For structures with foundation which establish new electrical utility companies service connection a Concrete Encased Electrode will be required within the foundation to serve as an grounding electrode system. Per the National Electrical Code article 250.52.3	Yes		

**FBCR 506: CONCRETE SLAB ON GRADE**

35	Show Vapor retarder (6mil. Polyethylene with joints taped 6 inches and sealed)	Yes		
36	Show control joints, synthetic fiber reinforcement or welded fire fabric reinforcement and Supports	Yes		

**FBCR 318: PROTECTION AGAINST TERMITES**

37	Indicate on the foundation plan if soil treatment is used for subterranean termite prevention or Submit other approved termite protection methods. Protection shall be provided by registered termiticides	Yes		
----	--	-----	--	--

**FBCR 606: Masonry Walls and Stem walls (load bearing & shear Walls)**

38	Show all materials making up walls, wall height, and Block size, mortar type	Yes		
39	Show all Lintel sizes, type, spans and tie-beam sizes and spacing of reinforcement	Yes		

**Metal frame shear wall and roof systems shall be designed, signed and sealed by Florida Prof. Engineer or Architect**

**Floor Framing System: First and/or second story**

40	Floor truss package shall including layout and details, signed and sealed by Florida Registered Professional Engineer	NA		
41	Show conventional floor joist type, size, span, spacing and attachment to load bearing walls, stem walls and/or piers	Yes		
42	Girder type, size and spacing to load bearing walls, stem wall and/or piers	Yes		
43	Attachment of joist to girder	NA		
44	Wind load requirements where applicable	Yes		
45	Show required under-floor crawl space	NA		
46	Show required amount of ventilation opening for under-floor spaces	NA		
47	Show required covering of ventilation opening	NA		
48	Show the required access opening to access to under-floor spaces	NA		
49	Show the sub-floor structural panel sheathing type, thickness and fastener schedule on the edges & intermediate of the areas structural panel sheathing	NA		
50	Show Draftstopping, Fire caulking and Fire blocking	Yes		
51	Show fireproofing requirements for garages attached to living spaces, per FBCR section 302.6	Yes		
52	Provide live and dead load rating of floor framing systems (psf).	NA		

**FBCR CHAPTER 6 WOOD WALL FRAMING CONSTRUCTION**

<b>GENERAL REQUIREMENTS:</b> <b>APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL</b>		<b>Items to Include- Each Box shall be Circled as Applicable</b>		
---	--	--	--	--

Select from Drop down

53	Stud type, grade, size, wall height and oc spacing for all load bearing or shear walls	Yes		
54	Fastener schedule for structural members per table FBC-R602.3.2 are to be shown	Yes		
55	Show wood structural panel's sheathing attachment to studs, joist, trusses, rafters and structural members, showing fastener schedule attachment on the edges & intermediate of the areas structural panel sheathing	Yes		
56	Show all required connectors with a max uplift rating and required number of connectors and oc spacing for continuous connection of structural walls to foundation and roof trusses or rafter systems	Yes		
57	Show sizes, type, span lengths and required number of support jack studs, king studs for shear wall opening and girder or header per FBC-R602.7.	Yes		
58	Indicate where pressure treated wood will be placed	Yes		
59	Show all wall structural panel sheathing, grade, thickness and show fastener schedule for structural panel sheathing edges & intermediate areas	Yes		
60	A detail showing gable truss bracing, wall balloon framing details or/ and wall hinge bracing detail	Yes		

**FBCR :ROOF SYSTEMS:**

61	Truss design drawing shall meet section FBC-R 802.10. 1 Wood trusses	Yes		
62	Include a layout and truss details, signed and sealed by Florida Professional Engineer	Yes		
63	Show types of connector's assemblies' and resistance uplift rating for all trusses and rafters	Yes		
64	Show gable ends with rake beams showing reinforcement or gable truss and wall bracing details	Yes		
65	Provide dead load rating of trusses	Yes		

**FBCR 802:Conventional Roof Framing Layout**

66	Rafter and ridge beams sizes, span, species and spacing	NA		
67	Connectors to wall assemblies' include assemblies' resistance to uplift rating	NA		
68	Valley framing and support details	NA		
69	Provide dead load rating of rafter system	NA		

**FBCR 803 ROOF SHEATHING**

70	Include all materials which will make up the roof decking, identification of structural panel sheathing, grade, thickness	Yes		
71	Show fastener Size and schedule for structural panel sheathing on the edges & intermediate areas	Yes		

## ROOF ASSEMBLIES FRC Chapter 9

72	Include all materials which will make up the roof assemblies covering	Yes		
73	Submit Florida Product Approval numbers for each component of the roof assemblies covering	Yes		

## FBCR Chapter 11 Energy Efficiency Code for Residential Building

Residential construction shall comply with this code by using the following compliance methods in the FBCR Chapter 11 Residential buildings compliance methods. **Two of the required forms are to be submitted, N1100.1.1.1 As an alternative to the computerized Compliance Method A, the Alternate Residential Point System Method hand calculation, Alternate Form 600A, may be used. All requirements specific to this calculation are located in Sub appendix C to Appendix G. Buildings complying by this alternative shall meet all mandatory requirements of this chapter. Computerized versions of the Alternate Residential Point System Method shall not be acceptable for code compliance.**

GENERAL REQUIREMENTS: APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable		
---	--	--	--	--

Select from Drop Down

74	Show the insulation R value for the following areas of the structure	Yes		
75	Attic space	Yes		
76	Exterior wall cavity	Yes		
77	Crawl space	NA		

## HVAC information

78	Submit two copies of a Manual J sizing equipment or equivalent computation study	Yes		
79	Exhaust fans shown in bathrooms <b>Mechanical exhaust capacity of 50 cfm intermittent or 20 cfm continuous required</b>	Yes		
80	Show clothes dryer route and total run of exhaust duct	Yes		

## Plumbing Fixture layout shown

81	All fixtures waste water lines shall be shown on the foundation plan	Yes		
82	Show the location of water heater	Yes		

## Private Potable Water

83	Pump motor horse power	Yes		
84	Reservoir pressure tank gallon capacity	Yes		
85	Rating of cycle stop valve if used	Yes		

## Electrical layout shown including

86	Show Switches, receptacles outlets, lighting fixtures and Ceiling fans	Yes		
87	Show all 120-volt, single phase, 15- and 20-ampere branch circuits outlets required to be protected by <b>Ground-Fault Circuit Interrupter (GFCI) Article 210.8 A</b>	Yes		
88	Show the location of smoke detectors & Carbon monoxide detectors	Yes		
89	Show service panel, sub-panel, location(s) and total ampere ratings	Yes		
90	On the electrical plans identify the electrical service overcurrent protection device for the main electrical service. This device shall be installed on the exterior of structures to serve as a disconnecting means for the utility company electrical service. Conductors used from the exterior disconnecting means to a panel or sub panel shall have four-wire conductors, of which one conductor shall be used as an equipment ground. Indicate if the utility company service entrance cable will be of the overhead or underground type.  For structures with foundation which establish new electrical utility companies service connection a Concrete Encased Electrode will be required within the foundation to serve as an Grounding electrode system. Per the National Electrical Code article 250.52.3	Yes		
91	Appliances and HVAC equipment and disconnects	Yes		
92	Show all 120-volt, single phase, 15- and 20-ampere branch circuits supplying outlets installed in dwelling unit family rooms, dining rooms, living rooms, parlors, libraries, dens, bedrooms, sunrooms, recreation rooms, closets, hallways, or similar rooms or areas shall be protected by a listed <b>Combination arc-fault circuit interrupter, Protection device.</b>	Yes		



**Notice Of Commencement:**

A notice of commencement form **RECORDED** in the Columbia County Clerk Office is required to be filed with the Building Department **BEFORE ANY INSPECTIONS** can be performed.

<b>GENERAL REQUIREMENTS:</b> <b>APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL</b>	<b>Items to Include-</b> Each Box shall be Circled as Applicable
---	---

**\*\*ITEMS 95, 96, & 98 Are Required After APPROVAL from the ZONING DEPT.\*\***

Select from Drop down

<b>93</b>	<b>Building Permit Application</b> A current Building Permit Application is to be completed, by following the Checklist all supporting documents must be submitted. There is a <b>\$15.00</b> application fee. The completed application with attached documents and application fee can be mailed.	Yes		
<b>94</b>	<b>Parcel Number</b> The parcel number (Tax ID number) from the Property Appraisers Office (386) 758-1083 is required. A copy of property deed is also required. <a href="http://www.columbiacountyfla.com">www.columbiacountyfla.com</a>	Yes		
<b>95</b>	<b>Environmental Health Permit or Sewer Tap Approval</b> A copy of a approved Columbia County Environmental Health (386) 758-1058	Yes		
<b>96</b>	<b>City of Lake City</b> A City Water and/or Sewer letter. Call 386-752-2031	NA		
<b>97</b>	<b>Toilet facilities shall be provided for all construction sites</b>	Yes		
<b>98</b>	<b>Town of Fort White</b> (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White, an approval land use development letter issued by the Town of Fort is required to be submitted with the application for a building permit.	NA		
<b>99</b>	<b>Flood Information:</b> All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting a application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.5.2 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.5.3 of the Columbia County Land Development Regulations ( <a href="http://Municode.com">Municode.com</a> )	Yes		
<b>100</b>	<b>CERTIFIED FINISHED FLOOR ELEVATIONS</b> will be required on any project where the approved FIRM Flood Maps show the property is in a AE, Floodway, and AH flood zones. Additionally One Foot Rise letters are required for AE and AH zones. In the Floodway Flood zones a Zero Rise letter is required.	Yes		
<b>101</b>	A Flood development permit is also required for AE, Floodway & AH. Development permit cost is <b>\$50.00</b>	-		
<b>102</b>	<b>Driveway Connection:</b> If the property does not have an existing access to a public road, then an application for a culvert permit ( <b>\$25.00</b> ) must be made. County Public Works Dept. determines the size and length of every culvert before instillation and completes a final inspection before permanent power is granted. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver ( <b>\$50.00</b> ) Separate Check when issued. If the project is to be located on an F.D.O.T. maintained road, then an F.D.O.T. access permit is required.	Yes		
<b>103</b>	<b>911 Address:</b> An application for a 911 address must be applied for and received through the Columbia County Emergency Management Office of 911 Addressing Department (386) 758-1125.	Yes		

**Ordinance Sec. 90-75. - Construction debris.** (e) It shall be unlawful for any person to dispose of or discard solid waste, including construction or demolition debris at any place within the county other than on an authorized disposal site or at the county's solid waste facilities. The temporary storage, not to exceed seven days of solid waste (excluding construction and demolition debris) on the premises where generated or vegetative trash pending disposition as authorized by law or ordinance, shall not be deemed a violation of this section. The temporary storage of construction and demolition debris on the premises where generated or vegetative trash pending disposition as authorized by law or ordinance shall not be deemed in violation of this section; provided, however, such construction and demolition debris must be disposed of in accordance with this article prior to the county's issuance of a certificate of occupancy for the premises. The burning of lumber from a construction or demolition project or vegetative trash when done so with legal and proper permits from the authorized agencies and in accordance with such agencies' rules and regulations, shall not be deemed a violation of this section. No person shall bury, throw, place, or deposit, or cause to be buried, thrown, placed, or deposited, any solid waste, special waste, or debris of any kind into or on any of the public streets, road right-of-way, highways, bridges, alleys, lanes, thoroughfares, waters, canals, or vacant lots or lands within the county. No person shall bury any vegetative trash on any of the public streets, road right-of-way, highways, bridges, lanes, thoroughfares, waters, canals, or lots less than ten acres in size within the county.

**Disclosure Statement for Owner Builders:**

If you as the Applicant will be acting as your own contractor or owner/builder under section 489.103(7) Florida Statutes, you must submit the required notarized Owner Builder Disclosure Statement form.

**\*\*This form can be printed from the Columbia County Website on the Building and Zoning page under Documents. Web address is - <http://www.columbiacountyfla.com/BuildingandZoning.asp>**

**Section 105 of the Florida Building Code defines the:**

**Time limitation of application.**

An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

**Single-family residential dwelling.**

Section 105.3.4 A building permit for a single-family residential dwelling must be issued within 30 working days of application therefor unless unusual circumstances require a longer time for processing the application or unless the permit application fails to satisfy the Florida Building Code or the enforcing agency's laws or ordinances.

**Permit intent.**

Section 105.4.1: A permit issued shall be constructed to be a license to proceed with the work and not as authority to violate, cancel, alter or set aside any of the provisions of the technical codes, nor shall issuance of a permit prevent the building official from thereafter requiring a correction of errors in plans, construction or violations of this code. Every permit issued shall become invalid unless the work authorized by such permit is commenced within six months after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of six months after the time the work is commenced.

**If work has commenced.**

Section 105.4.1.1: If work has commenced and the permit is revoked, becomes null and void, or expires because of lack of progress or abandonment, a new permit covering the proposed construction shall be obtained before proceeding with the work.

**New Permit.**

Section 105.4.1.2: If a new permit is not obtained within 180 days from the date the initial permit became null and void, the building official is authorized to require that any work which has been commenced or completed be removed from the building site. Alternately, a new permit may be issued on application, providing the work in place and required to complete the structure meets all applicable regulations in effect at the time the initial permit became null and void and any regulations which may have become effective between the date of expiration and the date of issuance of the new permit.

**Work Shall Be:**

Section 105.4.1.3: Work shall be considered to be in active progress when the permit has received an approved inspection within 180 days. This provision shall not be applicable in case of civil commotion or strike or when the building work is halted due directly to judicial injunction, order or similar process.

**The Fee:**

Section 105.4.1.4: The fee for renewal reissuance and extension of a permit shall be set forth by the administrative authority.

**Notification:**

When the application is approved for permitting the applicant will be notified by phone as to the status by the Columbia County Building & Zoning Department.

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and approval numbers for the building components listed below if they will be utilized on the construction project for which you are applying for a building permit. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. Statewide approved products are listed online @ [www.floridabuilding.org](http://www.floridabuilding.org)

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
<b>1. EXTERIOR DOORS</b>			
A. SWINGING	MASONITE	In/Out Swinging Fiberglass	FL-322SR7
B. SLIDING	MASONITE	In/Out Swinging Fiberglass	FL-322SR7
C. SECTIONAL/ROLL UP			
D. OTHER			
<b>2. WINDOWS</b>			
A. SINGLE/DOUBLE HUNG	Anderson	Series 400	FL-1091-1
B. HORIZONTAL SLIDER			
C. CASEMENT			
D. FIXED			
E. MULLION			
F. SKYLIGHTS	Velux		
G. OTHER			
<b>3. PANEL WALL</b>			
A. SIDING	Baycan	Vinyl Siding	FL-15867-R1
B. SOFFITS	Baycan	Vinyl / PVC - Aluminum	FL-16003
C. STOREFRONTS			
D. GLASS BLOCK			
E. OTHER			
<b>4. ROOFING PRODUCTS</b>			
A. ASPHALT SHINGLES	Certainteed	Asphalt Shingles	FL-2444
B. NON-STRUCTURAL METAL			
C. ROOFING TILES			
D. SINGLE PLY ROOF			
E. OTHER			
<b>5. STRUCTURAL COMPONENTS</b>			
A. WOOD CONNECTORS	OR prints		
B. WOOD ANCHORS			
C. TRUSS PLATES			
D. INSULATION FORMS			
E. LINTELS			
F. OTHERS			
<b>6. NEW EXTERIOR ENVELOPE PRODUCTS</b>			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite: 1) copy of the product approval, 2) performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturer's installation requirements.

Further, I understand these products may have to be removed if approval cannot be demonstrated during inspection.

Contractor OR Agent Signature

Date

NOTES





Lumber design values are in accordance with ANSI/TPI 1 section 6.3  
These truss designs rely on lumber values established by others.

RE: 1559709 - PRATA RES.

**MiTek USA, Inc.**

6904 Parke East Blvd.  
Tampa, FL 33610-4115

**Site Information:**

Customer Info: Bob Prata Project Name: O/B Model: Prata Res.  
Lot/Block: N/A Subdivision: N/A  
Address: 924 SW Highfield Terrace, n/a  
City: Columbia Cty State: FL

**Name Address and License # of Structural Engineer of Record, if there is one, for the building.**

Name: License #:  
Address:  
City: State:


**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: FBC2017/TPI2014 Design Program: MiTek 20/20 8.2  
Wind Code: ASCE 7-10 Wind Speed: 130 mph  
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 4 individual, Truss Design Drawings and 0 Additional Drawings.

With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No.	Seal#	Truss Name	Date
1	T15267767	T01	10/5/18
2	T15267768	T01G	10/5/18
3	T15267769	T02	10/5/18
4	T15267770	T03	10/5/18



The truss drawing(s) referenced above have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource-Jacksonville.

Truss Design Engineer's Name: Finn, Walter

My license renewal date for the state of Florida is February 28, 2019.

**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Walter P. Finn PE No.22839  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

October 5, 2018

Finn, Walter

1 of 1

Job 1559709	Truss T01	Truss Type Common	Qty 8	Ply 1	PRATA RES. Job Reference (optional)	T15267767
----------------	--------------	----------------------	----------	----------	--	-----------

Builders FirstSource, Jacksonville, FL - 32244,

8.220 s Sep 24 2018 MiTek Industries, Inc. Fri Oct 5 12:13:40 2018 Page 1

ID:GWVY1p9Xvx9X6yxtEucPovzuswj-SESmzBkkoSrAFwuTpkHcEfh7ycKle7E6\_Yu1i0yWTlv

-2-0-0	6-9-12	13-3-7	20-0-0	26-8-9	33-2-4	40-0-0	42-0-0
2-0-0	6-9-12	6-5-12	6-8-9	6-8-9	6-5-12	6-9-12	2-0-0

Scale = 1:70.5




Plate Offsets (X, Y)-- [2-0-1-15-0-1-8], [10-0-1-15-0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.49	Vert(LL)	-0.32 14-16	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.99	Vert(CT)	-0.57 14-16	>840	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.46	Horz(CT)	0.12 10	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-AS						
								Weight: 209 lb	FT = 20%

**LUMBER-**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2 \*Except\*  
13-15: 2x4 SP M 31  
WEBS 2x4 SP No.3

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied.  
BOT CHORD Rigid ceiling directly applied.  
WEBS 1 Row at midpt 6-14, 7-14, 5-14

**REACTIONS.** (lb/size) 2=1588/0-3-8, 10=1588/0-3-8  
Max Horz 2=149(LC 10)  
Max Uplift 2=349(LC 12), 10=349(LC 13)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2774/1480, 3-5=-2539/1417, 5-6=-1754/1088, 6-7=-1754/1088, 7-9=-2539/1417,  
9-10=-2774/1480  
BOT CHORD 2-16=-1151/2421, 14-16=-830/1960, 12-14=-835/1960, 10-12=-1173/2421  
WEBS 6-14=-674/1196, 7-14=-673/523, 7-12=-231/556, 9-12=-335/347, 5-14=-673/524,  
5-16=-231/556, 3-16=-335/347

- NOTES-** (7)
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf, BCDL=3.0psf, h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=349, 10=349.
  - 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
  - 7) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.



Walter P. Finn PE No.22839  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

October 5, 2018

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MI-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BC81 Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 36610




Job 1559709	Truss T01G	Truss Type Common Supported Gable	Qty 2	Ply 1	PRATA RES.	T15267768
----------------	---------------	--------------------------------------	----------	----------	------------	-----------

Builders FirstSource, Jacksonville, FL - 32244,

8.220 s Sep 24 2018 MiTek Industries, Inc. Fri Oct 5 12:13:42 2018 Page 1

ID:GWVY1p9Xvx9X6yxtEucPovzuswj-OcaWOsm\_J35uVE2sw9J4J4nW8PD16?wPRsN8nvyWTft



Scale = 1:74.1




Plate Offsets (X,Y)- [2-0-4-0-0-3-1], [24-0-4-0-0-3-1], [30-0-3-0-0-3-0], [38-0-3-0-0-3-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.31	Vert(LL)	-0.02	25	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.10	Vert(CT)	-0.02	25	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.12	Horz(CT)	0.01	24	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-S							
									Weight: 272 lb	FT = 20%

**LUMBER-**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.3

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.  
WEBS 1 Row at midpt 13-34, 12-35, 14-33

**REACTIONS.** All bearings 40-0-0.  
(lb) - Max Horz 2=-144(LC 10)  
Max Uplift All uplift 100 lb or less at joint(s) 2, 35, 36, 37, 38, 39, 40, 41, 42, 33, 32, 31, 30, 29, 28, 27, 26, 24  
Max Grav All reactions 250 lb or less at joint(s) 34, 35, 36, 37, 38, 39, 40, 41, 42, 33, 32, 31, 30, 29, 28, 27, 26 except 2=268(LC 1), 24=268(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 10-11=88/269, 11-12=110/333, 12-13=130/387, 13-14=130/387, 14-15=110/333, 15-16=88/269

- NOTES-** (10)
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 35, 36, 37, 38, 39, 40, 41, 42, 33, 32, 31, 30, 29, 28, 27, 26, 24.
  - This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.



Walter P. Finn PE No.22839  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

October 5, 2018

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610




Job 1559709	Truss T02	Truss Type Common	Qty 12	Ply 1	PRATA RES.	T15267769
----------------	--------------	----------------------	-----------	----------	------------	-----------

Builders FirstSource, Jacksonville, FL - 32244,

8.220 s Sep 24 2018 MiTek Industries, Inc. Fri Oct 5 12:13:44 2018 Page 1  
ID:GWY1p9Xvx9X6yxtEucPovzuswj-K?hGoYoErgLckXBF2aLYOVspZDiXaovivAsFmyVTlr

-2-0-0	6-4-15	13-3-7	20-0-0	26-8-9	33-7-1	40-0-0	42-0-0
2-0-0	6-4-15	6-10-8	6-8-9	6-8-9	6-10-8	6-4-15	2-0-0

Scale = 1:70.5



10-1-12	20-0-0	28-10-4	40-0-0
10-1-12	9-10-4	9-10-4	10-1-12

Plate Offsets (X,Y)-- [2-0-1-15,0-1-8], [10-0-1-15,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.51	Vert(LL)	0.41 12-22	>299	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.93	Vert(CT)	0.35 12-22	>347	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.48	Horz(CT)	0.04 12	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-AS						
									Weight: 210 lb FT = 20%

**LUMBER-**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.3

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied.  
BOT CHORD Rigid ceiling directly applied.  
WEBS 1 Row at midpt 5-14, 7-12

**REACTIONS.** (lb/size) 2=1130/0-3-8, 12=1807/0-3-8, 10=239/0-3-8  
Max Horz 2=-149(LC 10)  
Max Uplift 2=-266(LC 12), 12=-338(LC 13), 10=-188(LC 8)  
Max Grav 2=1130(LC 1), 12=1807(LC 1), 10=338(LC 24)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1773/982, 3-5=-1499/859, 5-6=-733/553, 6-7=-732/552, 7-9=-153/635,  
9-10=-89/407  
BOT CHORD 2-16=-705/1578, 14-16=-351/1110, 10-12=-296/120  
WEBS 3-16=-367/370, 5-16=-206/554, 5-14=-692/535, 6-14=-198/348, 7-14=-127/698,  
7-12=-1481/772, 9-12=-394/471

- NOTES-** (B)
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - All plates are 3x6 MT20 unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=266, 12=338, 10=188.
  - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
  - This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.



Walter P. Finn PE No.22839  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

October 5,2018

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610

Job 1559709	Truss T03	Truss Type Roof Special	Qty 12	Ply 1	PRATA RES. T15267770
----------------	--------------	----------------------------	-----------	----------	-------------------------

Builders FirstSource, Jacksonville, FL - 32244,

8.220 s Sep 24 2018 MiTek Industries, Inc. Fri Oct 5 12:13:45 2018 Page 1

ID:GWY1p9Xvx9X8yxtEucPovzswj-oBF10uosc\_TTMhmRcdHnxjPzVd6wJ80r7qboNEyWTlq

-2-0-0	5-5-14	10-2-1	15-0-0	20-0-0	24-11-13	29-8-8	34-3-2	40-0-0	42-0-0
2-0-0	5-5-14	4-8-2	4-9-15	5-0-0	4-11-13	4-8-11	4-8-10	5-8-15	2-0-0

Scale = 1:71.7




Plate Offsets (X,Y)-- [4:0-3-0-0-3-0], [8:0-4-0-0-3-0], [10:0-2-15-Edge], [13:0-6-0-0-3-0]									
LOADING (psf)	SPACING	2-0-0	CSI	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.56	Vert(LL)	-0.19 16-17	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.67	Vert(CT)	-0.39 16-17	>905	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.93	Horz(CT)	0.19 13	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-AS						
				Weight: 224 lb		FT = 20%			

**LUMBER-**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.3

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied.  
BOT CHORD Rigid ceiling directly applied.  
WEBS 1 Row at midpt 5-15

**REACTIONS.** (lb/size) 2=945/0-3-8, 13=2498/0-3-8, 10=267/0-3-8  
Max Horz 2=149(LC 11)  
Max Uplift 2=227(LC 12), 13=474(LC 12), 10=471(LC 23)  
Max Grav 2=945(LC 1), 13=2498(LC 1), 10=122(LC 12)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=2574/1307, 3-4=2267/1105, 4-5=1292/589, 5-6=350/313, 6-7=351/314,  
7-8=68/459, 8-9=722/1706, 9-10=337/1310  
BOT CHORD 2-17=1023/2327, 16-17=642/1812, 15-16=152/1149, 14-15=422/468, 13-14=1619/981,  
12-13=1128/444, 10-12=1128/444  
WEBS 3-17=269/313, 4-17=182/522, 4-16=664/513, 5-16=296/1018, 5-15=1211/559,  
7-15=250/847, 7-14=1183/574, 8-14=654/1567, 8-13=1782/895, 9-13=454/583

- NOTES-** (8)
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=227, 13=474, 10=471.
  - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
  - 8) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.



Walter P. Finn PE No.22839  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

October 5,2018

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, D9B-89 and BC91 Building Component Safety Information available from Truss Plate Institute, 216 N. Lee Street, Suite 312, Alexandria, VA 22314.





6904 Parke East Blvd.  
Tampa, FL 33610



# Symbols

## PLATE LOCATION AND ORIENTATION



For 4 x 2 orientation, locate plates 0-  $\frac{1}{16}$ " from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in MITek 20/20 software or upon request.

## PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

## BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

## Industry Standards:

ANSI/TP11: National Design Specification for Metal Plate Connected Wood Truss Construction.  
DSB-89: Design Standard for Bracing.  
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

# Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

## PRODUCT CODE APPROVALS


ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988  
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved



MITek Engineering Reference Sheet: Mil-7473 rev. 10/03/2015

# General Safety Notes


Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.



# 6/12 PITCH - 24" O/H

65-00-00



FL Approval Codes - Mitek Plates #'s 2197.2 - 2197.4. Versa-Lam #1644-R4 & BCI Joists #1392-R4

BEARING HEIGHT SCHEDULE

q 1-1/8"

**NOTES:**

- 1) REFER TO BID #1 RECOMMENDATIONS FOR TRUSS AND JOIST INSTALLATION AND TYPICAL BRACING DETAILING. BRACING DETAILING IS REQUIRED FOR TRUSS AND JOIST CONNECTIONS.
- 2) ALL TRUSSES INCLUDING JOIST/CEILING JOIST TRUSSES MUST BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING:
  - a) ALL TRUSSES MUST BE ADJUSTED TO BE PLUMB AND TRUE TO THE CENTERLINE OF THE CEILING.
  - b) ALL TRUSSES MUST BE CONNECTED TO THE CEILING JOIST TRUSSES.
  - c) ALL TRUSSES MUST BE CONNECTED TO THE CEILING JOIST TRUSSES.
  - d) ALL TRUSSES MUST BE CONNECTED TO THE CEILING JOIST TRUSSES.
  - e) ALL TRUSSES MUST BE CONNECTED TO THE CEILING JOIST TRUSSES.
- 3) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 4) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 5) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 6) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 7) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 8) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 9) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 10) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 11) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 12) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 13) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 14) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 15) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 16) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 17) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 18) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 19) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 20) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 21) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 22) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 23) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 24) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 25) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 26) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 27) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 28) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 29) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 30) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 31) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 32) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 33) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 34) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 35) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 36) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 37) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 38) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 39) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 40) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 41) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 42) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 43) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 44) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 45) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 46) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 47) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 48) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 49) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 50) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 51) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 52) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 53) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 54) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 55) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 56) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 57) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 58) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 59) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 60) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 61) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 62) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 63) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 64) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 65) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 66) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 67) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 68) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 69) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 70) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 71) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 72) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 73) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 74) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 75) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 76) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 77) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 78) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 79) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 80) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 81) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 82) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 83) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 84) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 85) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 86) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 87) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 88) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 89) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 90) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 91) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 92) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 93) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 94) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 95) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 96) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 97) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 98) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 99) ALL TRUSSES ARE REQUIRED TO BE 2x6.
- 100) ALL TRUSSES ARE REQUIRED TO BE 2x6.



**Jack's onfile**  
**Tampa**  
 PHONE: 813-421-4001 FAX: 813-421-4006  
**Freepoint**  
 PHONE: 813-421-4001 FAX: 813-421-4006

**PRATA RES.**

DATE	BY	REVISION
10-5-18	K.H	1559709
10-5-18	K.H	1559709
10-5-18	K.H	1559709

## RESIDENTIAL ENERGY CONSERVATION CODE DOCUMENTATION CHECKLIST

### Florida Department of Business and Professional Regulation Simulated Performance Alternative (Performance) Method

**Applications for compliance with the 2017 Florida Building Code, Energy Conservation via the residential Simulated Performance Method shall include:**

- ☐ This checklist
- ☐ A Form R405 report that documents that the Proposed Design complies with Section R405.3 of the Florida Energy Code. This form shall include a summary page indicating home address, e-ratio and the pass or fail status along with summary areas and types of components, whether the home was simulated as a worst-case orientation, name and version of the compliance software tool, name of individual completing the compliance report (one page) and an input summary checklist that can be used for field verification (usually four pages/may be greater).
- ☐ Energy Performance Level (EPL) Display Card (one page)
- ☐ HVAC system sizing and selection based on ACCA Manual S or per exceptions provided in Section R403.7
- ☐ Mandatory Requirements (five pages)

#### **Required prior to CO for the Performance Method:**

- ☐ Air Barrier and Insulation Inspection Component Criteria checklist (Table R402.4.1.1 - one page)
- ☐ A completed Envelope Leakage Test Report (usually one page)
- ☐ If Form R405 duct leakage type indicates anything other than "default leakage", then a completed Form R405 Duct Leakage Test Report (usually one page)







## INPUT SUMMARY CHECKLIST REPORT

## PROJECT

Title:	181003 Prata Res	Bedrooms:	2	Address Type:	Street Address
Building Type:	User	Conditioned Area:	1351	Lot #	
Owner Name:	Prata Res	Total Stories:	1	Block/Subdivision:	
# of Units:	1	Worst Case:	No	PlatBook:	
Builder Name:		Rotate Angle:	270	Street:	924 SW Highfield Terr
Permit Office:		Cross Ventilation:		County:	Columbia
Jurisdiction:		Whole House Fan:		City, State, Zip:	Lake City , FL ,
Family Type:	Single-family				
New/Existing:	New (From Plans)				
Comment:					

## CLIMATE

✓	Design Location	TMY Site	Design Temp 97.5 %	2.5 %	Int Design Temp Winter	Summer	Heating Degree Days	Design Moisture	Daily Temp Range
_____	FL, Gainesville	FL_GAINESVILLE_REGI	32	92	70	75	1305.5	51	Medium

## BLOCKS

Number	Name	Area	Volume
1	Block1	1351	12159

## SPACES

Number	Name	Area	Volume	Kitchen	Occupants	Bedrooms	Infil ID	Finished	Cooled	Heated
1	Main	1351	12159	Yes	4	2	1	Yes	Yes	Yes

## FLOORS

✓	#	Floor Type	Space	Perimeter	R-Value	Area		Tile	Wood	Carpet
_____	1	Slab-On-Grade Edge Insulatio	Main	160 ft	0	1351 ft²	----	0.3	0.3	0.4

## ROOF

✓	#	Type	Materials	Roof Area	Gable Area	Roof Color	Solar Absor.	SA Tested	Emitt	Emitt Tested	Deck Insul.	Pitch (deg)
_____	1	Hip	Composition shingles	1511 ft²	0 ft²	Dark	0.92	No	0.9	No	0	26.6

## ATTIC

✓	#	Type	Ventilation	Vent Ratio (1 in)	Area	RBS	IRCC
_____	1	Full attic	Vented	300	1351 ft²	N	N

## CEILING

✓	#	Ceiling Type	Space	R-Value	Ins Type	Area	Framing Frac	Truss Type
_____	1	Under Attic (Vented)	Main	38	Blown	1351 ft²	0	Wood

## INPUT SUMMARY CHECKLIST REPORT

## WALLS

✓	#	Ornt	Adjacent To	Wall Type	Space	Cavity R-Value	Width Ft	In	Height Ft	In	Area	Sheathing R-Value	Framing Fraction	Solar Absor.	Below Grade%
✓	1	N=>W	Exterior	Frame - Wood	Main	13	40		9		360.0 ft²		0.23	0.75	0
✓	2	E=>N	Garage	Frame - Wood	Main	13	30		9		270.0 ft²		0.23	0.75	0
✓	3	S=>E	Exterior	Frame - Wood	Main	13	24		9		216.0 ft²		0.23	0.75	0
✓	4	E=>N	Exterior	Frame - Wood	Main	13	10		9		90.0 ft²		0.23	0.75	0
✓	5	S=>E	Exterior	Frame - Wood	Main	13	16		9		144.0 ft²		0.23	0.75	0
✓	6	W=>S	Exterior	Frame - Wood	Main	13	40		9		360.0 ft²		0.23	0.75	0

## DOORS

✓	#	Ornt	Door Type	Space	Storms	U-Value	Width Ft	In	Height Ft	In	Area
✓	1	N=>W	Insulated	Main	None	.4	2		6	8	13.3 ft²
✓	2	E=>N	Insulated	Main	None	.4	2	8	6	8	17.8 ft²
✓	3	S=>E	Insulated	Main	None	.4	3		6	8	20 ft²

## WINDOWS

Orientation shown is the entered orientation (=&gt;) changed to As Built (rotated 270 degrees).

✓	#	Ornt	Wall ID	Frame	Panes	NFRC	U-Factor	SHGC	Imp	Area	Overhang Depth	Separation	Int Shade	Screening
✓	1	N=>W	1	Metal	Low-E Double	Yes	0.3	0.2	N	30.0 ft²	1 ft 6 in	1 ft 0 in	None	None
✓	2	N=>W	1	Metal	Low-E Double	Yes	0.3	0.2	N	26.7 ft²	1 ft 6 in	1 ft 0 in	None	None
✓	3	N=>W	1	Metal	Low-E Double	Yes	0.3	0.2	N	9.0 ft²	1 ft 6 in	1 ft 0 in	None	None
✓	4	S=>E	3	Metal	Low-E Double	Yes	0.3	0.2	N	30.0 ft²	11 ft 6 in	1 ft 0 in	None	None
✓	5	S=>E	5	Metal	Low-E Double	Yes	0.3	0.2	N	30.0 ft²	1 ft 6 in	1 ft 0 in	None	None
✓	6	W=>S	6	Metal	Low-E Double	Yes	0.3	0.2	N	6.0 ft²	1 ft 6 in	8 ft 0 in	None	None

## GARAGE

✓	#	Floor Area	Ceiling Area	Exposed Wall Perimeter	Avg. Wall Height	Exposed Wall Insulation
✓	1	759 ft²	759 ft²	80 ft	9 ft	1

## INFILTRATION

#	Scope	Method	SLA	CFM 50	ELA	EqLA	ACH	ACH 50
1	Wholehouse	Proposed ACH(50)	.0004	1418.6	77.88	146.46	.3169	7

## HEATING SYSTEM

✓	#	System Type	Subtype	Efficiency	Capacity	Block	Ducts
✓	1	Electric Heat Pump/	None	HSPF:8.9	28 kBtu/hr	1	sys#1

## INPUT SUMMARY CHECKLIST REPORT

## COOLING SYSTEM

✓	#	System Type	Subtype	Efficiency	Capacity	Air Flow	SHR	Block	Ducts
✓	1	Central Unit/	None	SEER: 15	28 kBtu/hr	840 cfm	0.75	1	sys#1

## HOT WATER SYSTEM

✓	#	System Type	SubType	Location	EF	Cap	Use	SetPnt	Conservation
✓	1	Electric	None	Garage	0.96	40 gal	50 gal	120 deg	None

## SOLAR HOT WATER SYSTEM

✓	FSEC Cert #	Company Name	System Model #	Collector Model #	Collector Area	Storage Volume	FEF
✓	None	None			ft²		

## DUCTS

✓	#	Location	Supply R-Value	Area	Location	Return Area	Leakage Type	Air Handler	CFM 25 TOT	CFM25 OUT	QN	RLF	HVAC # Heat	Cool
✓	1	Attic	6	270.2 ft	Attic	67.55 ft	Default Leakage	Garage	(Default)	(Default)			1	1

## TEMPERATURES

Programable Thermostat: Y

Ceiling Fans:

Cooling	[X] Jan	[X] Feb	[X] Mar	[ ] Apr	[ ] May	[X] Jun	[X] Jul	[X] Aug	[X] Sep	[ ] Oct	[X] Nov	[X] Dec
Heating	[X] Jan	[X] Feb	[X] Mar	[X] Apr	[ ] May	[X] Jun	[X] Jul	[X] Aug	[X] Sep	[X] Oct	[X] Nov	[X] Dec
Venting	[X] Jan	[X] Feb	[X] Mar	[X] Apr	[ ] May	[X] Jun	[X] Jul	[X] Aug	[X] Sep	[X] Oct	[X] Nov	[X] Dec

Thermostat Schedule: HERS 2006 Reference

Hours

Schedule Type		1	2	3	4	5	6	7	8	9	10	11	12
Cooling (WD)	AM	78	78	78	78	78	78	78	78	80	80	80	80
	PM	80	80	78	78	78	78	78	78	78	78	78	78
Cooling (WEH)	AM	78	78	78	78	78	78	78	78	78	78	78	78
	PM	78	78	78	78	78	78	78	78	78	78	78	78
Heating (WD)	AM	66	66	66	66	66	68	68	68	68	68	68	68
	PM	68	68	68	68	68	68	68	68	68	68	66	66
Heating (WEH)	AM	66	66	66	66	66	68	68	68	68	68	68	68
	PM	68	68	68	68	68	68	68	68	68	68	66	66

## MASS

Mass Type	Area	Thickness	Furniture Fraction	Space
Default(8 lbs/sq.ft.	0 ft²	0 ft	0.3	Main

Name: no

Signature: \_\_\_\_\_

Rating Compant: no

Date: \_\_\_\_\_



# ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE INDEX\* = 100

The lower the Energy Performance Index, the more efficient the home.

1. New home or, addition	1. <u>New (From Plans)</u>	12. Ducts, location & insulation level	
2. Single-family or multiple-family	2. <u>Single-family</u>	a) Supply ducts	R <u>6.0</u>
3. No. of units (if multiple-family)	3. <u>1</u>	b) Return ducts	R <u>6.0</u>
4. Number of bedrooms	4. <u>2</u>	c) AHU location	Attic/Attic
5. Is this a worst case? (yes/no)	5. <u>No</u>	13. Cooling system:	Capacity <u>28.0</u>
6. Conditioned floor area (sq. ft.)	6. <u>1351</u>	a) Split system	SEER <u>        </u>
7. Windows, type and area		b) Single package	SEER <u>        </u>
a) U-factor:(weighted average)	7a. <u>0.300</u>	c) Ground/water source	SEER/COP <u>        </u>
b) Solar Heat Gain Coefficient (SHGC)	7b. <u>0.200</u>	d) Room unit/PTAC	EER <u>        </u>
c) Area	7c. <u>131.7</u>	e) Other	<u>15.0</u>
8. Skylights		14. Heating system:	Capacity <u>28.0</u>
a) U-factor:(weighted average)	8a. <u>NA</u>	a) Split system heat pump	HSPF <u>        </u>
b) Solar Heat Gain Coefficient (SHGC)	8b. <u>NA</u>	b) Single package heat pump	HSPF <u>        </u>
9. Floor type, insulation level:		c) Electric resistance	COP <u>        </u>
a) Slab-on-grade (R-value)	9a. <u>0.0</u>	d) Gas furnace, natural gas	AFUE <u>        </u>
b) Wood, raised (R-value)	9b. <u>        </u>	e) Gas furnace, LPG	AFUE <u>        </u>
c) Concrete, raised (R-value)	9c. <u>        </u>	f) Other	<u>8.90</u>
10. Wall type and insulation:		15. Water heating system	
A. Exterior:		a) Electric resistance	EF <u>0.96</u>
1. Wood frame (Insulation R-value)	10A1. <u>13.0</u>	b) Gas fired, natural gas	EF <u>        </u>
2. Masonry (Insulation R-value)	10A2. <u>        </u>	c) Gas fired, LPG	EF <u>        </u>
B. Adjacent:		d) Solar system with tank	EF <u>        </u>
1. Wood frame (Insulation R-value)	10B1. <u>13.0</u>	e) Dedicated heat pump with tank	EF <u>        </u>
2. Masonry (Insulation R-value)	10B2. <u>        </u>	f) Heat recovery unit	HeatRec% <u>        </u>
11. Ceiling type and insulation level		g) Other	
a) Under attic	11a. <u>38.0</u>	16. HVAC credits claimed (Performance Method)	
b) Single assembly	11b. <u>        </u>	a) Ceiling fans	<u>        </u>
c) Knee walls/skylight walls	11c. <u>        </u>	b) Cross ventilation	<u>No</u>
d) Radiant barrier installed	11d. <u>No</u>	c) Whole house fan	<u>No</u>
		d) Multizone cooling credit	<u>        </u>
		e) Multizone heating credit	<u>        </u>
		f) Programmable thermostat	<u>Yes</u>

\*Label required by Section R303.1.3 of the Florida Building Code, Energy Conservation, if not DEFAULT.

I certify that this home has complied with the Florida Building Code, Energy Conservation, through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL display card will be completed based on installed code compliant features.

Builder Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Address of New Home: 924 SW Highfield Terr City/FL Zip: Lake City, FL

# Florida Building Code, Energy Conservation, 6th Edition (2017)

## Mandatory Requirements for Residential Performance, Prescriptive and ERI Methods

ADDRESS: 924 SW Highfield Terr  
Lake City, FL

Permit Number:

**MANDATORY REQUIREMENTS** See individual code sections for full details.



### SECTION R401 GENERAL

- ☐ **R401.3 Energy Performance Level (EPL) display card (Mandatory).** The building official shall require that an energy performance level (EPL) display card be completed and certified by the builder to be accurate and correct before final approval of the building for occupancy. Florida law (Section 553.9085, Florida Statutes) requires the EPL display card to be included as an addendum to each sales contract for both presold and nonpresold residential buildings. The EPL display card contains information indicating the energy performance level and efficiencies of components installed in a dwelling unit. The building official shall verify that the EPL display card completed and signed by the builder accurately reflects the plans and specifications submitted to demonstrate code compliance for the building. A copy of the EPL display card can be found in Appendix RD.

- ☐ **R402.4 Air leakage (Mandatory).** The building thermal envelope shall be constructed to limit air leakage in accordance with the requirements of Sections R402.4.1 through R402.4.5.

**Exception:** Dwelling units of R-2 Occupancies and multiple attached single family dwellings shall be permitted to comply with Section C402.5.

- ☐ **R402.4.1 Building thermal envelope.** The building thermal envelope shall comply with Sections R402.4.1.1 and R402.4.1.2. The sealing methods between dissimilar materials shall allow for differential expansion and contraction.

- ☐ **R402.4.1.1 Installation.** The components of the building thermal envelope as listed in Table R402.4.1.1 shall be installed in accordance with the manufacturer's instructions and the criteria listed in Table R402.4.1.1, as applicable to the method of construction. Where required by the code official, an approved third party shall inspect all components and verify compliance.

- ☐ **R402.4.1.2 Testing.** The building or dwelling unit shall be tested and verified as having an air leakage rate not exceeding seven air changes per hour in Climate Zones 1 and 2, and three air changes per hour in Climate Zones 3 through 8. Testing shall be conducted in accordance with ANSI/RESNET/ICC 380 and reported at a pressure of 0.2 inch w.g. (50 pascals). Testing shall be conducted by either individuals as defined in Section 553.993(5) or (7), Florida Statutes, or individuals licensed as set forth in Section 489.105(3)(f), (g) or (i) or an approved third party. A written report of the results of the test shall be signed by the party conducting the test and provided to the code official. Testing shall be performed at any time after creation of all penetrations of the building thermal envelope.

**Exception:** Testing is not required for additions, alterations, renovations, or repairs, of the building thermal envelope of existing buildings in which the new construction is less than 85 percent of the building thermal envelope.

During testing:

1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures.
2. Dampers including exhaust, intake, makeup air, backdraft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures.
3. Interior doors, if installed at the time of the test, shall be open.
4. Exterior doors for continuous ventilation systems and heat recovery ventilators shall be closed and sealed.
5. Heating and cooling systems, if installed at the time of the test, shall be turned off.
6. Supply and return registers, if installed at the time of the test, shall be fully open.

- ☐ **R402.4.2 Fireplaces.** New wood-burning fireplaces shall have tight-fitting flue dampers or doors, and outdoor combustion air. Where using tight-fitting doors on factory-built fireplaces listed and labeled in accordance with UL 127, the doors shall be tested and listed for the fireplace. Where using tight-fitting doors on masonry fireplaces, the doors shall be listed and labeled in accordance with UL 907.

- ☐ **R402.4.3 Fenestration air leakage.** Windows, skylights and sliding glass doors shall have an air infiltration rate of no more than 0.3 cfm per square foot (1.5 L/s/m<sup>2</sup>), and swinging doors no more than 0.5 cfm per square foot (2.6 L/s/m<sup>2</sup>), when tested according to NFRC 400 or AAMA/WDMA/CSA 101/I.S.2/A440 by an accredited, independent laboratory and listed and labeled by the manufacturer.

**Exception:** Site-built windows, skylights and doors.

## MANDATORY REQUIREMENTS - (Continued)

- ☐ **R402.4.4 Rooms containing fuel-burning appliances.** In Climate Zones 3 through 8, where open combustion air ducts provide combustion air to open combustion fuel burning appliances, the appliances and combustion air opening shall be located outside the building thermal envelope or enclosed in a room, isolated from inside the thermal envelope. Such rooms shall be sealed and insulated in accordance with the envelope requirements of Table R402.1.2, where the walls, floors and ceilings shall meet not less than the basement wall R-value requirement. The door into the room shall be fully gasketed and any water lines and ducts in the room insulated in accordance with Section R403. The combustion air duct shall be insulated where it passes through conditioned space to a minimum of R-8.

### Exceptions:

1. Direct vent appliances with both intake and exhaust pipes installed continuous to the outside.
2. Fireplaces and stoves complying with Section R402.4.2 and Section R1006 of the Florida Building Code, Residential.

- ☐ **R402.4.5 Recessed lighting.** Recessed luminaires installed in the building thermal envelope shall be sealed to limit air leakage between conditioned and unconditioned spaces. All recessed luminaires shall be IC-rated and labeled as having an air leakage rate not more than 2.0 cfm (0.944 L/s) when tested in accordance with ASTM E283 at a 1.57 psf (75 Pa) pressure differential. All recessed luminaires shall be sealed with a gasket or caulk between the housing and the interior wall or ceiling covering.

## SECTION R403 SYSTEMS

### R403.1 Controls.

- ☐ **R403.1.1 Thermostat provision (Mandatory).** At least one thermostat shall be provided for each separate heating and cooling system.
- ☐ **R403.1.3 Heat pump supplementary heat (Mandatory).** Heat pumps having supplementary electric-resistance heat shall have controls that, except during defrost, prevent supplemental heat operation when the heat pump compressor can meet the heating load.

- ☐ **R403.3.2 Sealing (Mandatory)** All ducts, air handlers, filter boxes and building cavities that form the primary air containment passageways for air distribution systems shall be considered ducts or plenum chambers, shall be constructed and sealed in accordance with Section C403.2.9.2 of the Commercial Provisions of this code and shall be shown to meet duct tightness criteria below.

Duct tightness shall be verified by testing in accordance with ANSI/RESNET/ICC 380 by either individuals as defined in Section 553.993(5) or (7), Florida Statutes, or individuals licensed as set forth in Section 489.105(3)(f), (g) or (i), Florida Statutes, to be "substantially leak free" in accordance with Section R403.3.3.

- ☐ **R403.3.2.1 Sealed air handler.** Air handlers shall have a manufacturer's designation for an air leakage of no more than 2 percent of the design airflow rate when tested in accordance with ASHRAE 193.

- ☐ **R403.3.3 Duct testing (Mandatory).** Ducts shall be pressure tested to determine air leakage by one of the following methods:

1. Rough-in test: Total leakage shall be measured with a pressure differential of 0.1 inch w.g. (25 Pa) across the system, including the manufacturer's air handler enclosure if installed at the time of the test. All registers shall be taped or otherwise sealed during the test.
2. Postconstruction test: Total leakage shall be measured with a pressure differential of 0.1 inch w.g. (25 Pa) across the entire system, including the manufacturer's air handler enclosure. Registers shall be taped or otherwise sealed during the test.

### Exceptions:

1. A duct air leakage test shall not be required where the ducts and air handlers are located entirely within the building thermal envelope.
2. Duct testing is not mandatory for buildings complying by Section 405 of this code.

A written report of the results of the test shall be signed by the party conducting the test and provided to the code official.

- ☐ **R403.3.5 Building cavities (Mandatory).** Building framing cavities shall not be used as ducts or plenums.

- ☐ **R403.4 Mechanical system piping insulation (Mandatory).** Mechanical system piping capable of carrying fluids above 105°F (41°C) or below 55°F (13°C) shall be insulated to a minimum of R-3.

- ☐ **R403.4.1 Protection of piping insulation.** Piping insulation exposed to weather shall be protected from damage, including that caused by sunlight, moisture, equipment maintenance and wind, and shall provide shielding from solar radiation that can cause degradation of the material. Adhesive tape shall not be permitted.

- ☐ **R403.5.1 Heated water circulation and temperature maintenance systems (Mandatory)** Heated water circulation systems shall be in accordance with Section R403.5.1.1. Heat trace temperature maintenance systems shall be in accordance with Section R403.5.1.2. Automatic controls, temperature sensors and pumps shall be accessible. Manual controls shall be readily accessible.

- ☐ **R403.5.1.1 Circulation systems.** Heated water circulation systems shall be provided with a circulation pump. The system return pipe shall be a dedicated return pipe or a cold water supply pipe. Gravity and thermosiphon circulation systems shall be prohibited. Controls for circulating hot water system pumps shall start the pump based on the identification of a demand for hot water within the occupancy. The controls shall automatically turn off the pump when the water in the circulation loop is at the desired temperature and when there is no demand for hot water.

- ☐ **R403.5.1.2 Heat trace systems.** Electric heat trace systems shall comply with IEEE 515.1 or UL 515. Controls for such systems shall automatically adjust the energy input to the heat tracing to maintain the desired water temperature in the piping in accordance with the times when heated water is used in the occupancy.



## MANDATORY REQUIREMENTS - (Continued)

- ☐ **R403.5.5 Heat traps (Mandatory).** Storage water heaters not equipped with integral heat traps and having vertical pipe risers shall have heat traps installed on both the inlets and outlets. External heat traps shall consist of either a commercially available heat trap or a downward and upward bend of at least 3 ½ inches (89 mm) in the hot water distribution line and cold water line located as close as possible to the storage tank.
- R403.5.6 Water heater efficiencies (Mandatory).**
- ☐ **R403.5.6.1.1 Automatic controls.** Service water-heating systems shall be equipped with automatic temperature controls capable of adjustment from the lowest to the highest acceptable temperature settings for the intended use. The minimum temperature setting range shall be from 100°F to 140°F (38°C to 60°C).
- ☐ **R403.5.6.1.2 Shut down.** A separate switch or a clearly marked circuit breaker shall be provided to permit the power supplied to electric service systems to be turned off. A separate valve shall be provided to permit the energy supplied to the main burner(s) of combustion types of service water-heating systems to be turned off.
- ☐ **R403.5.6.2 Water-heating equipment.** Water-heating equipment installed in residential units shall meet the minimum efficiencies of Table C404.2 in Chapter 4 of the Florida Building Code, Energy Conservation, Commercial Provisions, for the type of equipment installed. Equipment used to provide heating functions as part of a combination system shall satisfy all stated requirements for the appropriate water-heating category. Solar water heaters shall meet the criteria of Section R403.5.6.2.1.
- ☐ **R403.5.6.2.1 Solar water-heating systems.** Solar systems for domestic hot water production are rated by the annual solar energy factor of the system. The solar energy factor of a system shall be determined from the Florida Solar Energy Center Directory of Certified Solar Systems. Solar collectors shall be tested in accordance with ISO Standard 9806, Test Methods for Solar Collectors, and SRCC Standard TM-1, Solar Domestic Hot Water System and Component Test Protocol. Collectors in installed solar water-heating systems should meet the following criteria:
1. Be installed with a tilt angle between 10 degrees and 40 degrees of the horizontal; and
  2. Be installed at an orientation within 45 degrees of true south.
- ☐ **R403.6 Mechanical ventilation (Mandatory).** The building shall be provided with ventilation that meets the requirements of the Florida Building Code, Residential, or Florida Building Code, Mechanical, as applicable, or with other approved means of ventilation including: Natural, Infiltration or Mechanical means. Outdoor air intakes and exhausts shall have automatic or gravity dampers that close when the ventilation system is not operating.
- ☐ **R403.6.1 Whole-house mechanical ventilation system fan efficacy.** When installed to function as a whole-house mechanical ventilation system, fans shall meet the efficacy requirements of Table R403.6.1.
- Exception:** Where whole-house mechanical ventilation fans are integral to tested and listed HVAC equipment, they shall be powered by an electronically commutated motor.
- ☐ **R403.6.2 Ventilation air.** Residential buildings designed to be operated at a positive indoor pressure or for mechanical ventilation shall meet the following criteria:
1. The design air change per hour minimums for residential buildings in ASHRAE 62.2, Ventilation for Acceptable Indoor Air Quality, shall be the maximum rates allowed for residential applications.
  2. No ventilation or air-conditioning system make-up air shall be provided to conditioned space from attics, crawlspaces, attached enclosed garages or outdoor spaces adjacent to swimming pools or spas.
  3. If ventilation air is drawn from enclosed space(s), then the walls of the space(s) from which air is drawn shall be insulated to a minimum of R-11 and the ceiling shall be insulated to a minimum of R-19, space permitting, or R-10 otherwise.
- R403.7 Heating and cooling equipment (Mandatory).**
- ☐ **R403.7.1 Equipment sizing.** Heating and cooling equipment shall be sized in accordance with ACCA Manual S based on the equipment loads calculated in accordance with ACCA Manual J or other approved heating and cooling calculation methodologies, based on building loads for the directional orientation of the building. The manufacturer and model number of the outdoor and indoor units (if split system) shall be submitted along with the sensible and total cooling capacities at the design conditions described in Section R302.1. This Code does not allow designer safety factors, provisions for future expansion or other factors that affect equipment sizing. System sizing calculations shall not include loads created by local intermittent mechanical ventilation such as standard kitchen and bathroom exhaust systems. New or replacement heating and cooling equipment shall have an efficiency rating equal to or greater than the minimum required by federal law for the geographic location where the equipment is installed.

**TABLE R403.6.1  
WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM FAN EFFICACY**

FAN LOCATION	AIRFLOW RATE MINIMUM (CFM)	MINIMUM EFFICACY <sup>a</sup> (CFM/WATT)	AIRFLOW RATE MAXIMUM (CFM)
Range hoods	Any	2.8 cfm/watt	Any
In-line fan	Any	2.8 cfm/watt	Any
Bathroom, utility room	10	1.4 cfm/watt	<90
Bathroom, utility room	90	2.8 cfm/watt	Any

For SI: 1 cfm = 28.3 L/min.

a. When tested in accordance with HVI Standard 916

## MANDATORY REQUIREMENTS - (Continued)

- ☐ **R403.7.1.1 Cooling equipment capacity.** Cooling only equipment shall be selected so that its total capacity is not less than the calculated total load but not more than 1.15 times greater than the total load calculated according to the procedure selected in Section 403.7, or the closest available size provided by the manufacturer's product lines. The corresponding latent capacity of the equipment shall not be less than the calculated latent load.

The published value for AHRI total capacity is a nominal, rating-test value and shall not be used for equipment sizing. Manufacturer's expanded performance data shall be used to select cooling-only equipment. This selection shall be based on the outdoor design dry-bulb temperature for the load calculation (or entering water temperature for water-source equipment), the blower CFM provided by the expanded performance data, the design value for entering wet-bulb temperature and the design value for entering dry-bulb temperature.

Design values for entering wet-bulb and dry-bulb temperatures shall be for the indoor dry bulb and relative humidity used for the load calculation and shall be adjusted for return side gains if the return duct(s) is installed in an unconditioned space.

### Exceptions:

1. Attached single- and multiple-family residential equipment sizing may be selected so that its cooling capacity is less than the calculated total sensible load but not less than 80 percent of that load.
2. When signed and sealed by a Florida-registered engineer, in attached single- and multiple-family units, the capacity of equipment may be sized in accordance with good design practice.

### R403.7.1.2 Heating equipment capacity.

- ☐ **R403.7.1.2.1 Heat pumps.** Heat pump sizing shall be based on the cooling requirements as calculated according to Section R403.7.1.1, and the heat pump total cooling capacity shall not be more than 1.15 times greater than the design cooling load even if the design heating load is 1.15 times greater than the design cooling load.

- ☐ **R403.7.1.2.2 Electric resistance furnaces.** Electric resistance furnaces shall be sized within 4 kW of the design requirements calculated according to the procedure selected in Section R403.7.1.

- ☐ **R403.7.1.2.3 Fossil fuel heating equipment.** The capacity of fossil fuel heating equipment with natural draft atmospheric burners shall not be less than the design load calculated in accordance with Section R403.7.1.

- ☐ **R403.7.1.3 Extra capacity required for special occasions.** Residences requiring excess cooling or heating equipment capacity on an intermittent basis, such as anticipated additional loads caused by major entertainment events, shall have equipment sized or controlled to prevent continuous space cooling or heating within that space by one or more of the following options:

1. A separate cooling or heating system is utilized to provide cooling or heating to the major entertainment areas.
2. A variable capacity system sized for optimum performance during base load periods is utilized.

- ☐ **R403.8 Systems serving multiple dwelling units (Mandatory).** Systems serving multiple dwelling units shall comply with Sections C403 and C404 of the IECC—Commercial Provisions in lieu of Section R403.

- ☐ **R403.9 Snow melt and ice system controls (Mandatory)** Snow- and ice-melting systems, supplied through energy service to the building, shall include automatic controls capable of shutting off the system when the pavement temperature is above 50°F (10°C), and no precipitation is falling and an automatic or manual control that will allow shutoff when the outdoor temperature is above 40°F (4.8°C).

- ☐ **R403.10 Pools and permanent spa energy consumption (Mandatory).** The energy consumption of pools and permanent spas shall be in accordance with Sections R403.10.1 through R403.10.5.

- ☐ **R403.10.1 Heaters.** The electric power to heaters shall be controlled by a readily accessible on-off switch that is an integral part of the heater mounted on the exterior of the heater, or external to and within 3 feet (914 mm) of the heater. Operation of such switch shall not change the setting of the heater thermostat. Such switches shall be in addition to a circuit breaker for the power to the heater. Gas-fired heaters shall not be equipped with continuously burning ignition pilots.

- ☐ **R403.10.2 Time switches.** Time switches or other control methods that can automatically turn off and on according to a preset schedule shall be installed for heaters and pump motors. Heaters and pump motors that have built-in time switches shall be in compliance with this section.

### Exceptions:

1. Where public health standards require 24-hour pump operation.
2. Pumps that operate solar- and waste-heat-recovery pool heating systems.
3. Where pumps are powered exclusively from on-site renewable generation.

- ☐ **R403.10.3 Covers.** Outdoor heated swimming pools and outdoor permanent spas shall be equipped with a vapor-retardant cover on or at the water surface or a liquid cover or other means proven to reduce heat loss.

**Exception:** Where more than 70 percent of the energy for heating, computed over an operation season, is from site-recovered energy, such as from a heat pump or solar energy source, covers or other vapor-retardant means shall not be required.

- ☐ **R403.10.4 Gas- and oil-fired pool and spa heaters.** All gas- and oil-fired pool and spa heaters shall have a minimum thermal efficiency of 82 percent for heaters manufactured on or after April 16, 2013, when tested in accordance with ANSI Z 21.56. Pool heaters fired by natural or LP gas shall not have continuously burning pilot lights.

- ☐ **R403.10.5 Heat pump pool heaters.** Heat pump pool heaters shall have a minimum COP of 4.0 when tested in accordance with AHRI 1160, Table 2, Standard Rating Conditions-Low Air Temperature. A test report from an independent laboratory is required to verify procedure compliance. Geothermal swimming pool heat pumps are not required to meet this standard.
- ☐ **R403.11 Portable spas (Mandatory)** The energy consumption of electric-powered portable spas shall be controlled by the requirements of APSP-14.

## SECTION R404

### ELECTRICAL POWER AND LIGHTING SYSTEMS

- ☐ **R404.1 Lighting equipment (Mandatory).** Not less than 75 percent of the lamps in permanently installed lighting fixtures shall be high-efficacy lamps or not less than 75 percent of the permanently installed lighting fixtures shall contain only high-efficacy lamps.
- Exception:** Low-voltage lighting.
- R404.1.1 Lighting equipment (Mandatory)** Fuel gas lighting systems shall not have continuously burning pilot lights.



# 2017 - AIR BARRIER AND INSULATION INSPECTION COMPONENT CRITERIA

**TABLE 402.4.1.1**  
**AIR BARRIER AND INSULATION INSPECTION COMPONENT CRITERIA**

Project Name: 181003 Prata Res Street: 924 SW Highfield Terr City, State, Zip: Lake City, FL, Owner: Prata Res Design Location: FL, Gainesville			Builder Name: Permit Office: Permit Number: Jurisdiction:	CHECK
COMPONENT	AIR BARRIER CRITERIA	INSULATION INSTALLATION CRITERIA		
General requirements	A continuous air barrier shall be installed in the building envelope. The exterior thermal envelope contains a continuous air barrier. Breaks or joints in the air barrier shall be sealed.	Air-permeable insulation shall not be used as a sealing material.		
Ceiling/attic	The air barrier in any dropped ceiling/soffit shall be aligned with the insulation and any gaps in the air barrier shall be sealed. Access openings, drop down stairs or knee wall doors to unconditioned attic spaces shall be sealed.	The insulation in any dropped ceiling/soffit shall be aligned with the air barrier.		
Walls	The junction of the foundation and sill plate shall be sealed. The junction of the top plate and the top of exterior walls shall be sealed. Knee walls shall be sealed.	Cavities within corners and headers of frame walls shall be insulated by completely filling the cavity with a material having a thermal resistance of R-3 per inch minimum. Exterior thermal envelope insulation for framed walls shall be installed in substantial contact and continuous alignment with the air barrier.		
Windows, skylights and doors	The space between window/door jambs and framing, and skylights and framing shall be sealed.			
Rim joists	Rim joists shall include the air barrier.	Rim joists shall be insulated.		
Floors (including above-garage and cantilevered floors)	The air barrier shall be installed at any exposed edge of insulation.	Floor framing cavity insulation shall be installed to maintain permanent contact with the underside of subfloor decking, or floor framing cavity insulation shall be permitted to be in contact with the top side of sheathing, or continuous insulation installed on the underside of floor framing and extends from the bottom to the top of all perimeter floor framing members.		
Crawl space walls	Exposed earth in unvented crawl spaces shall be covered with a Class I vapor retarder with overlapping joints taped.	Where provided instead of floor insulation, insulation shall be permanently attached to the crawlspace		
Shafts, penetrations	Duct shafts, utility penetrations, and flue shafts opening to exterior or unconditioned space shall be sealed.			
Narrow cavities		Batts in narrow cavities shall be cut to fit, or narrow cavities shall be filled by insulation that on installation readily conforms to the available cavity spaces.		
Garage separation	Air sealing shall be provided between the garage and conditioned spaces.			
Recessed lighting	Recessed light fixtures installed in the building thermal envelope shall be sealed to the drywall.	Recessed light fixtures installed in the building thermal envelope shall be air tight and IC rated.		
Plumbing and wiring		Batt insulation shall be cut neatly to fit around wiring and plumbing in exterior walls, or insulation that on installation readily conforms to available space shall extend behind piping and wiring.		
Shower/tub on exterior wall	The air barrier installed at exterior walls adjacent to showers and tubs shall separate them from the showers and tubs.	Exterior walls adjacent to showers and tubs shall be insulated.		
Electrical/phone box on exterior walls	The air barrier shall be installed behind electrical or communication boxes or air-sealed boxes shall be installed.			
HVAC register boots	HVAC register boots that penetrate building thermal envelope shall be sealed to the sub-floor or drywall.			
Concealed sprinklers	When required to be sealed, concealed fire sprinklers shall only be sealed in a manner that is recommended by the manufacturer. Caulking or other adhesive sealants shall not be used to fill voids between fire sprinkler cover plates and walls or ceilings.			

a. In addition, inspection of log walls shall be in accordance with the provisions of ICC-400.

# Envelope Leakage Test Report (Blower Door Test)

## Residential Prescriptive, Performance or ERI Method Compliance

### 2017 Florida Building Code, Energy Conservation, 6th Edition

Jurisdiction: \_\_\_\_\_

Permit #: \_\_\_\_\_

#### Job Information

Builder: \_\_\_\_\_

Community: \_\_\_\_\_

Lot: NA

Address: 924 SW Highfield Terr

City: Lake City

State: FL

Zip: \_\_\_\_\_

#### Air Leakage Test Results Passing results must meet either the Performance, Prescriptive, or ERI Method

☐ **PRESCRIPTIVE METHOD**-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding 7 air changes per hour at a pressure of 0.2 inch w.g. (50 Pascals) in Climate Zones 1 and 2.

☐ **PERFORMANCE or ERI METHOD**-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding the selected ACH(50) value, as shown on Form R405-2017 (Performance) or R406-2017 (ERI), section labeled as infiltration, sub-section ACH50.  
ACH(50) specified on Form R405-2017-Energy Calc (Performance) or R406-2017 (ERI): 7.000

$$\frac{\text{CFM}(50)}{\text{Building Volume}} \times 60 \div \frac{12159}{\text{ACH}(50)} = \text{ACH}(50)$$

☒ **PASS**

☐ When ACH(50) is less than 3, Mechanical Ventilation installation must be verified by building department.

Method for calculating building volume:

☐ Retrieved from architectural plans

☒ Code software calculated

☐ Field measured and calculated

**R402.4.1.2 Testing.** Testing shall be conducted in accordance with ANSI/RESNET/ICC 380 and reported at a pressure of 0.2 inch w.g. (50 Pascals). Testing shall be conducted by either individuals as defined in Section 553.993(5) or (7), *Florida Statutes*, or individuals licensed as set forth in Section 489.105(3)(f), (g), or (i) or an approved third party. A written report of the results of the test shall be signed by the party conducting the test and provided to the code official. Testing shall be performed at any time after creation of all penetrations of the *building thermal envelope*.

During testing:

1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures.
2. Dampers including exhaust, intake, makeup air, back draft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures.
3. Interior doors, if installed at the time of the test, shall be open.
4. Exterior doors for continuous ventilation systems and heat recovery ventilators shall be closed and sealed.
5. Heating and cooling systems, if installed at the time of the test, shall be turned off.
6. Supply and return registers, if installed at the time of the test, shall be fully open.

#### Testing Company

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

I hereby verify that the above Air Leakage results are in accordance with the 2017 6th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.

Signature of Tester: \_\_\_\_\_ Date of Test: \_\_\_\_\_

Printed Name of Tester: \_\_\_\_\_

License/Certification #: \_\_\_\_\_ Issuing Authority: \_\_\_\_\_

# Residential System Sizing Calculation

## Summary

Prata Res  
924 SW Highfield Terr  
Lake City, FL

Project Title:  
181003 Prata Res


2018-09-28

Location for weather data: Gainesville, FL - Defaults: Latitude(29.7) Altitude(152 ft.) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(51gr.)			
Winter design temperature(TMY3 99%)	30 F	Summer design temperature(TMY3 99%)	94 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	40 F	Summer temperature difference	19 F
<b>Total heating load calculation</b>	<b>23474 Btuh</b>	<b>Total cooling load calculation</b>	<b>21359 Btuh</b>
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	119.3 28000	Sensible (SHR = 0.75)	122.6 21000
Heat Pump + Auxiliary(0.0kW)	119.3 28000	Latent	165.3 7000
		Total (Electric Heat Pump)	131.1 28000

## WINTER CALCULATIONS

Winter Heating Load (for 1351 sqft)


Load component		Load	
Window total	132 sqft	1580	Btuh
Wall total	1257 sqft	4464	Btuh
Door total	51 sqft	818	Btuh
Ceiling total	1351 sqft	1372	Btuh
Floor total	1351 sqft	7552	Btuh
Infiltration	103 cfm	4500	Btuh
Duct loss		3189	Btuh
<b>Subtotal</b>		<b>23474</b>	<b>Btuh</b>
Ventilation	0 cfm	0	Btuh
<b>TOTAL HEAT LOSS</b>		<b>23474</b>	<b>Btuh</b>



## SUMMER CALCULATIONS

Summer Cooling Load (for 1351 sqft)

Load component		Load	
Window total	132 sqft	3090	Btuh
Wall total	1257 sqft	2700	Btuh
Door total	51 sqft	613	Btuh
Ceiling total	1351 sqft	1852	Btuh
Floor total		0	Btuh
Infiltration	77 cfm	1603	Btuh
Internal gain		3320	Btuh
Duct gain		3945	Btuh
Sens. Ventilation	0 cfm	0	Btuh
Blower Load		0	Btuh
<b>Total sensible gain</b>		<b>17124</b>	<b>Btuh</b>
Latent gain(ducts)		776	Btuh
Latent gain(infiltration)		2660	Btuh
Latent gain(ventilation)		0	Btuh
Latent gain(internal/occupants/other)		800	Btuh
<b>Total latent gain</b>		<b>4236</b>	<b>Btuh</b>
<b>TOTAL HEAT GAIN</b>		<b>21359</b>	<b>Btuh</b>



8th Edition

EnergyGauge® System Sizing

PREPARED BY: GIAN PRATA RES

DATE: 2018-09-28



# System Sizing Calculations - Winter

## Residential Load - Whole House Component Details

Prata Res  
924 SW Highfield Terr  
Lake City, FL

Project Title:  
181003 Prata Res  
Building Type: User

2018-09-28

Reference City: Gainesville, FL (Defaults) Winter Temperature Difference: 40.0 F (TMY3 99%)

Component Loads for Whole House								
Window	Panes/Type	Frame	U	Orientation	Area(sqft)	X	HTM=	Load
1	2, NFRC 0.20	Metal	0.30	W	30.0		12.0	360 Btuh
2	2, NFRC 0.20	Metal	0.30	W	26.7		12.0	320 Btuh
3	2, NFRC 0.20	Metal	0.30	W	9.0		12.0	108 Btuh
4	2, NFRC 0.20	Metal	0.30	E	30.0		12.0	360 Btuh
5	2, NFRC 0.20	Metal	0.30	E	30.0		12.0	360 Btuh
6	2, NFRC 0.20	Metal	0.30	S	6.0		12.0	72 Btuh
Window Total					131.7(sqft)			1580 Btuh
Walls	Type	Ornt.	Ueff.	R-Value (Cav/Sh)	Area	X	HTM=	Load
1	Frame - Wood	- Ext	(0.089)	13.0/0.0	281		3.55	998 Btuh
2	Frame - Wood	- Adj	(0.089)	13.0/0.0	252		3.55	895 Btuh
3	Frame - Wood	- Ext	(0.089)	13.0/0.0	166		3.55	589 Btuh
4	Frame - Wood	- Ext	(0.089)	13.0/0.0	90		3.55	320 Btuh
5	Frame - Wood	- Ext	(0.089)	13.0/0.0	114		3.55	405 Btuh
6	Frame - Wood	- Ext	(0.089)	13.0/0.0	354		3.55	1257 Btuh
Wall Total					1257(sqft)			4464 Btuh
Doors	Type	Storm	Ueff.		Area	X	HTM=	Load
1	Insulated - Exterior, n		(0.400)		13		16.0	213 Btuh
2	Insulated - Garage, n		(0.400)		18		16.0	284 Btuh
3	Insulated - Exterior, n		(0.400)		20		16.0	320 Btuh
Door Total					51(sqft)			818Btuh
Ceilings	Type/Color/Surface		Ueff.	R-Value	Area	X	HTM=	Load
1	Vented Attic/D/Shing		(0.025)	38.0/0.0	1351		1.0	1372 Btuh
Ceiling Total					1351(sqft)			1372Btuh
Floors	Type		Ueff.	R-Value	Size	X	HTM=	Load
1	Slab On Grade		(1.180)	0.0	160.0 ft(perim.)		47.2	7552 Btuh
Floor Total					1351 sqft			7552 Btuh
	Envelope Subtotal:							15785 Btuh
Infiltration	Type	Wholehouse	ACH	Volume(cuft)	Wall Ratio		CFM=	
	Natural		0.51	12159	1.00		102.8	4500 Btuh
Duct load	Average sealed, R6.0, Supply(Att), Return(Att)						(DLM of 0.157)	3189 Btuh
All Zones	Sensible Subtotal All Zones							23474 Btuh

# Manual J Winter Calculations

## Residential Load - Component Details (continued)

Prata Res  
924 SW Highfield Terr  
Lake City, FL

Project Title:  
181003 Prata Res  
Building Type: User

2018-09-28

### WHOLE HOUSE TOTALS

<b>Totals for Heating</b>	Subtotal Sensible Heat Loss	23474 Btuh
	Ventilation Sensible Heat Loss	0 Btuh
	<b>Total Heat Loss</b>	<b>23474 Btuh</b>

### EQUIPMENT

1. Electric Heat Pump	#	28000 Btuh
-----------------------	---	------------

Key: Window types - NFRC (Requires U-Factor and Shading coefficient(SHGC) of glass as numerical values)  
or - Glass as 'Clear' or 'Tint' (Uses U-Factor and SHGC defaults)  
U - (Window U-Factor)  
HTM - (ManualJ Heat Transfer Multiplier)



Version 8

# System Sizing Calculations - Summer

## Residential Load - Whole House Component Details

Prata Res  
924 SW Highfield Terr  
Lake City, FL

Project Title:  
181003 Prata Res

2018-09-28

Reference City: Gainesville, FL

Temperature Difference: 19.0F(TMY3 99%) Humidity difference: 51gr.

### Component Loads for Whole House

Window	Type*						Overhang		Window Area(sqft)			HTM		Load	
	Panes	SHGC	U	InSh	IS	Ornt	Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded		
1	2 NFRC	0.20, 0.30	No	No	No	W	1.5ft.	1.0ft.	30.0	1.5	28.5	10	25	727	Btuh
2	2 NFRC	0.20, 0.30	No	No	No	W	1.5ft.	1.0ft.	26.7	1.0	25.7	10	25	651	Btuh
3	2 NFRC	0.20, 0.30	No	No	No	W	1.5ft.	1.0ft.	9.0	0.7	8.3	10	25	214	Btuh
4	2 NFRC	0.20, 0.30	No	No	No	E	11.5f	1.0ft.	30.0	30.0	0.0	10	25	297	Btuh
5	2 NFRC	0.20, 0.30	No	No	No	E	1.5ft.	1.0ft.	30.0	1.5	28.5	10	25	727	Btuh
6	2 NFRC	0.20, 0.30	No	No	No	S	1.5ft.	8.0ft.	6.0	1.0	5.0	10	11	67	Btuh
	Excursion													406	Btuh
	Window Total								132 (sqft)					3090	Btuh
Walls	Type					U-Value	R-Value		Area(sqft)		HTM		Load		
							Cav/Sheath								
1	Frame - Wood - Ext					0.09	13.0/0.0		281.0		2.3		636 Btuh		
2	Frame - Wood - Adj					0.09	13.0/0.0		252.2		1.7		425 Btuh		
3	Frame - Wood - Ext					0.09	13.0/0.0		166.0		2.3		376 Btuh		
4	Frame - Wood - Ext					0.09	13.0/0.0		90.0		2.3		204 Btuh		
5	Frame - Wood - Ext					0.09	13.0/0.0		114.0		2.3		258 Btuh		
6	Frame - Wood - Ext					0.09	13.0/0.0		354.0		2.3		801 Btuh		
	Wall Total								1257 (sqft)					2700	Btuh
Doors	Type								Area (sqft)		HTM		Load		
1	Insulated - Exterior								13.3		12.0		160 Btuh		
2	Insulated - Garage								17.8		12.0		213 Btuh		
3	Insulated - Exterior								20.0		12.0		240 Btuh		
	Door Total								51 (sqft)					613	Btuh
Ceilings	Type/Color/Surface					U-Value	R-Value		Area(sqft)		HTM		Load		
1	Vented Attic/DarkShingle					0.025	38.0/0.0		1351.0		1.37		1852 Btuh		
	Ceiling Total								1351 (sqft)					1852	Btuh
Floors	Type					R-Value		Size		HTM		Load			
1	Slab On Grade					0.0		1351 (ft-perimeter)		0.0		0 Btuh			
	Floor Total								1351.0 (sqft)					0	Btuh
	Envelope Subtotal:													8255	Btuh
Infiltration	Type					Average ACH		Volume(cuft)		Wall Ratio		CFM=		Load	
	Natural					0.38		12159		1		77.1		1603 Btuh	
Internal gain						Occupants		Btuh/occupant		Appliance		Load			
						4		X 230		+ <td colspan="2">2400</td> <td colspan="2">3320 Btuh</td>		2400		3320 Btuh	
	Sensible Envelope Load:													13179	Btuh
Duct load	Average sealed, Supply(R6.0-Attic), Return(R6.0-Attic)										(DGM of 0.299)			3945	Btuh
	Sensible Load All Zones													17124	Btuh



# Manual J Summer Calculations

## Residential Load - Component Details (continued)

Prata Res  
924 SW Highfield Terr  
Lake City, FL

Project Title:  
181003 Prata Res

Climate: FL\_GAINESVILLE\_REGIONAL\_A

2018-09-28

### WHOLE HOUSE TOTALS

<b>Whole House Totals for Cooling</b>	<b>Sensible Envelope Load All Zones</b>	<b>13179 Btuh</b>
	Sensible Duct Load	3945 Btuh
	<b>Total Sensible Zone Loads</b>	<b>17124 Btuh</b>
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	<b>Total sensible gain</b>	<b>17124 Btuh</b>
	Latent infiltration gain (for 51 gr. humidity difference)	2660 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	776 Btuh
	Latent occupant gain (4.0 people @ 200 Btuh per person)	800 Btuh
	Latent other gain	0 Btuh
	<b>Latent total gain</b>	<b>4236 Btuh</b>
	<b>TOTAL GAIN</b>	<b>21359 Btuh</b>

### EQUIPMENT

1. Central Unit	#	28000 Btuh
-----------------	---	------------

\*Key: Window types (Panels - Number and type of panes of glass)  
(SHGC - Shading coefficient of glass as SHGC numerical value)  
(U - Window U-Factor)  
(InSh - Interior shading device: none(No), Blinds(B), Draperies(D) or Roller Shades(R))  
- For Blinds: Assume medium color, half closed  
For Draperies: Assume medium weave, half closed  
For Roller shades: Assume translucent, half closed  
(IS - Insect screen: none(N), Full(F) or Half(½))  
(Ornt - compass orientation)



Version 8