



Duct System Summary

Split System

New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...

Date: 05/06/2024

By: John PirkI

Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Calculation method: EqualFric Supply FR (in/100ft): 0.880 Return FR (in/100ft): 0.880

Equipment pressure losses (in H2O): Heating 0.090 Cooling 0.090
Duct system losses (in H2O): 16.185 16.113
Total fan pressure (in H2O): 16.275 16.203
Fan air flow (cfm): 2000 2000

Supply Branch Summary

Name	Htg Load (Btuh)	Clg Load (Btuh)	Design AVF (cfm)	Veloc (fpm)	Shape	Duct Size (in)	Duct Matl	Cumm. Loss (in H2O)
Hall	1393	2057	h 147	549	Round	7	VinIFlx	9.790
Hall-A	1393	2057	h 147	549	Round	7	VinIFlx	10.707
Hall-B	1393	2057	h 147	549	Round	7	VinIFlx	4.465
Hall-C	1393	2057	h 147	549	Round	7	VinIFlx	11.621
Hall-D	1393	2057	h 147	549	Round	7	VinIFlx	5.371
Hall-E	1393	2057	h 147	549	Round	7	VinIFlx	3.644
Office #1	1947	3435	c 206	589	Round	8	VinIFlx	2.699
Office #1-A	1947	3435	c 206	589	Round	8	VinIFlx	1.810
Office #2	898	2545	c 152	570	Round	7	VinIFlx	6.234
Office #2-A	898	2545	c 152	570	Round	7	VinIFlx	7.134
Office #3	681	2201	c 132	671	Round	6	VinIFlx	8.026
Office #3-A	681	2201	c 132	671	Round	6	VinIFlx	8.940
Strg #1	490	1900	c 114	579	Round	6	VinIFlx	2.694
Strg #2	1543	1406	h 163	608	Round	7	VinIFlx	10.707
Strg #2-A	1543	1406	h 163	608	Round	7	VinIFlx	11.589

Supply Trunk Summary

Name	Htg Load (Btuh)	Clg Load (Btuh)	Design AVF (cfm)	Veloc (fpm)	Shape	Duct Size (in)	Duct Matl	Pres Loss (in H2O)
st1	18987	33417	h 2000	889	Rect	18 x 18	RectFbg	0.002
st2	17040	29983	h 1795	798	Rect	18 x 18	RectFbg	0.008
st3	14602	24647	h 1538	865	Rect	16 x 16	RectFbg	0.007
st4	13209	22590	h 1391	783	Rect	16 x 16	RectFbg	0.003
st6	10423	18475	c 1106	812	Rect	14 x 14	RectFbg	0.008
st5	11816	20533	h 1245	700	Rect	16 x 16	RectFbg	0.002
st8	8627	13386	h 909	909	Rect	12 x 12	RectFbg	0.017
st7	9525	15930	h 1003	737	Rect	14 x 14	RectFbg	0.003
st10	7265	8984	h 765	765	Rect	12 x 12	RectFbg	0.006
st9	7946	11185	h 837	837	Rect	12 x 12	RectFbg	0.005
st12	2936	3463	h 309	445	Rect	10 x 10	RectFbg	0.002
st11	5872	6927	h 619	891	Rect	10 x 10	RectFbg	0.005



Return Branch Summary

Name	Htg Load (Btuh)	Clg Load (Btuh)	Design AVF (cfm)	Veloc (fpm)	Shape	Duct Size (in)	Duct Matl	Cumm. Loss (in H2O)
rb15	3894	6870	c 411	523	Round	12	VinlFlx	2.744
rb9	4670	8072	h 492	626	Round	12	VinlFlx	3.698
rb11	7265	8984	h 765	548	Round	16	VinlFlx	4.565
rb12	1362	4402	c 263	596	Round	9	VinlFlx	4.520
rb14	1796	5090	c 305	689	Round	9	VinlFlx	3.691

Return Trunk Summary

Name	Htg Load (Btuh)	Clg Load (Btuh)	Design AVF (cfm)	Veloc (fpm)	Shape	Duct Size (in)	Duct Matl	Pres Loss (in H2O)
rt2	18987	33417	c 2000	655	Rect	20 x 22	RectFbg	0.001
rt3	15093	26548	h 1590	636	Rect	18 x 20	RectFbg	0.011
rt4	8627	13386	h 909	364	Rect	18 x 20	RectFbg	0.000
rt1	18987	33417	c 2000	655	Rect	20 x 22	RectFbg	0.006

EnergyGaugeSummit® 8.0
INPUT DATA REPORT

Project Information

Project Name: School

Project Title: Kingdom Culture School

Address: Kingdom Culture School
217 S.W. Dyal Avenue

State: Florida

Zip: 32024

Owner: Kingdom Culture School

Orientation: 0 Deg Clockwise. Walls &

Windows will be rotated
Building Type: School/University
accordingly

Building Classification: New Finished building

No.of Stories: 1

GrossArea: 6481 SF

Zones

No	Acronym	Description	Type	Area [sf]	Multiplier	Total Area [sf]	
1	Mini Splts	Mini Splts	CONDITIONED	4329.8	1	4329.8	☐
2	5 Ton Zone	5 Ton Zone	CONDITIONED	2150.8	1	2150.8	☐

Spaces										
No	Acronym	Description	Type	Depth [ft]	Width [ft]	Height [ft]	Multi plier	Total Area [sf]	Total Volume [cf]	
In Zone: Mini Splts										
1	Classroom #1	Classroom #1	Classroom/Lecture Hall	22.50	25.50	10.00	1	573.8	5737.5	☐
2	Classroom #2	Classroom #2	Classroom/Lecture Hall	22.50	25.50	10.00	1	573.8	5737.5	☐
3	Classroom #3	Classroom #3	Classroom/Lecture Hall	25.50	21.50	10.00	1	548.3	5482.5	☐
4	Classroom #4	Classroom #4	Classroom/Lecture Hall	25.50	20.50	10.00	1	522.8	5227.5	☐
5	Classroom #5	Classroom #5	Classroom/Lecture Hall	25.50	17.50	10.00	1	446.3	4462.5	☐
6	Classroom #6	Classroom #6	Classroom/Lecture Hall	22.50	25.00	10.00	1	562.5	5625.0	☐
7	Classroom #7	Classroom #7	Classroom/Lecture Hall	22.50	24.50	10.00	1	551.3	5512.5	☐
8	Classroom #8	Classroom #8	Classroom/Lecture Hall	22.50	24.50	10.00	1	551.3	5512.5	☐
In Zone: 5 Ton Zone										
1	Hall	Hall	Corridor	21.82	50.00	10.00	1	1091.0	10910.0	☐
2	Strg #1	Strg #1	Storage & Warehouse - Inactive Storage	16.50	9.50	10.00	1	156.8	1567.5	☐
3	Strg #2	Strg #2	Storage & Warehouse - Inactive Storage	22.50	6.50	10.00	1	146.3	1462.5	☐
4	Office #1	Office #1	Office - Enclosed	22.50	15.50	10.00	1	348.8	3487.5	☐
5	Office #2	Office #2	Office - Enclosed	14.50	16.00	10.00	1	232.0	2320.0	☐
6	Office #3	Office #3	Office - Enclosed	11.00	16.00	10.00	1	176.0	1760.0	☐

Lighting							
No	Type	Category	No. of Luminaires	Watts per Luminaire	Power [W]	Control Type	No.of Ctrl pts
In Zone: Mini Splts							
In Space: Classroom #1							

	1	LED	General Lighting	1	500	500	Manual On/Off	1	☐
In Space:	Classroom #2								
	1	LED	General Lighting	1	500	500	Manual On/Off	1	☐
In Space:	Classroom #3								
	1	LED	General Lighting	1	500	500	Manual On/Off	1	☐
In Space:	Classroom #4								
	1	LED	General Lighting	1	500	500	Manual On/Off	1	☐
In Space:	Classroom #5								
	1	LED	General Lighting	1	400	400	Manual On/Off	1	☐
In Space:	Classroom #6								
	1	LED	General Lighting	1	500	500	Manual On/Off	1	☐
In Space:	Classroom #7								
	1	LED	General Lighting	1	500	500	Manual On/Off	1	☐
In Space:	Classroom #8								
	1	LED	General Lighting	1	500	500	Manual On/Off	1	☐
In Zone:	5 Ton Zone								
In Space:	Hall								
	1	LED	General Lighting	1	400	400	Manual On/Off	1	☐
In Space:	Strg #1								
	1	LED	General Lighting	1	50	50	Manual On/Off	1	☐
In Space:	Strg #2								
	1	LED	General Lighting	1	50	50	Manual On/Off	1	☐
In Space:	Office #1								
	1	LED	General Lighting	1	300	300	Manual On/Off	1	☐
In Space:	Office #2								
	1	LED	General Lighting	1	200	200	Manual On/Off	1	☐
In Space:	Office #3								
	1	LED	General Lighting	1	150	150	Manual On/Off	1	☐

Walls (Walls will be rotated clockwise by building rotation value)													
No	Description	Type	Width [ft]	H (Effec) [ft]	Multi plier	Area [sf]	Orientation	Conductance [Btu/hr. sf. F]	Heat Capacity [Btu/sf.F]	Dens. [lb/cf]	R-Value [h.sf.F/Btu]		
In Zone:		Mini Splts											
1	North		Metal/R19/1/2" Gyp	51.00	10.00	1	510.0	North	0.0444	1.009	8.59	22.5	☐
2	South		Metal/R19/1/2" Gyp	74.00	10.00	1	740.0	South	0.0444	1.009	8.59	22.5	☐
3	West		Metal/R19/1/2" Gyp	71.00	10.00	1	710.0	West	0.0444	1.009	8.59	22.5	☐
In Zone:		5 Ton Zone											
1	South		Metal/R19/1/2" Gyp	6.50	10.00	1	65.0	South	0.0444	1.009	8.59	22.5	☐
2	North		Metal/R19/1/2" Gyp	30.00	10.00	1	300.0	North	0.0444	1.009	8.59	22.5	☐
3	East		Metal/R19/1/2" Gyp	80.00	10.00	1	800.0	East	0.0444	1.009	8.59	22.5	☐

Windows (Windows will be rotated clockwise by building rotation value)											
No	Description	Orientation	Shaded	U [Btu/hr sf F]	SHGC	Vis.Tra	W [ft]	H (Effec) [ft]	Multi plier	Total Area [sf]	
In Zone: In Wall:											
											☐

Doors												
No	Description	Type	Shaded?	Width [ft]	H (Effec [ft]	Multi plier	Area [sf]	Cond. [Btu/hr. sf. F]	Dens. [lb/cf]	Heat Cap. [Btu/sf. F]	R-Value [h.sf.F/Btu]	
In Zone: Mini Splts												
In Wall:	North											
1	North	Polyurethane core (24 ga steel) 2	No	3.00	7.00	2	21.0	0.2410	0.00	0.00	4.15	☐
In Wall:	South											
1	South	Polyurethane core (24 ga steel) 2	No	3.00	7.00	3	21.0	0.2410	0.00	0.00	4.15	☐
In Zone: 5 Ton Zone												
In Wall:	South											

	1	South	Polyurethane core (24 ga steel) 2	No	3.00	7.00	1	21.0	0.2410	0.00	0.00	4.15	☐
In Wall:		North											
	1	South	Polyurethane core (24 ga steel) 2	No	3.00	7.00	1	21.0	0.2410	0.00	0.00	4.15	☐
In Wall:		East											
	1	East	Polyurethane core (24 ga steel) 2	No	3.00	7.00	2	21.0	0.2410	0.00	0.00	4.15	☐

Roofs												
No	Description	Type	Width [ft]	H (Effec) [ft]	Multi plier	Area [sf]	Tilt [deg]	Cond. [Btu/hr. Sf. F]	Heat Cap [Btu/sf. F]	Dens. [lb/cf]	R-Value [h.sf.F/Btu]	
In Zone: Mini Splts												
1	Classroom #1	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	25.50	22.50	1	573.8	0.00	0.0320	1.50	8.22	31.2	☐
2	Classroom #2	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	25.50	22.50	1	573.8	0.00	0.0320	1.50	8.22	31.2	☐
3	Classroom #3	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	21.50	25.50	1	548.3	0.00	0.0320	1.50	8.22	31.2	☐
4	Classroom #4	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	20.50	25.50	1	522.8	0.00	0.0320	1.50	8.22	31.2	☐
5	Classroom #5	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	17.50	25.50	1	446.3	0.00	0.0320	1.50	8.22	31.2	☐
6	Classroom #6	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	25.00	22.50	1	562.5	0.00	0.0320	1.50	8.22	31.2	☐
7	Classroom #7	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	24.50	22.50	1	551.3	0.00	0.0320	1.50	8.22	31.2	☐
8	Classroom #8	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	24.50	22.50	1	551.3	0.00	0.0320	1.50	8.22	31.2	☐
In Zone: 5 Ton Zone												

1	Hall	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	50.00	21.82	1	1091.0	0.00	0.0320	1.50	8.22	31.2	☐
2	Strg #1	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	9.50	16.50	1	156.8	0.00	0.0320	1.50	8.22	31.2	☐
3	Strg #2	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	6.50	22.50	1	146.3	0.00	0.0320	1.50	8.22	31.2	☐
4	Office #1	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	15.50	22.50	1	348.8	0.00	0.0320	1.50	8.22	31.2	☐
5	Office #2	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	16.00	14.50	1	232.0	0.00	0.0320	1.50	8.22	31.2	☐
6	Office #3	Metal/1/2"WD Deck/WD Truss/9" Batt/Acous Tile	16.00	11.00	1	176.0	0.00	0.0320	1.50	8.22	31.2	☐

Skylights

No	Description	Type	U [Btu/hr sf F]	SHGC	Vis.Trans	W [ft]	H (Effec) [ft]	Multiplier	Area [Sf]	Total Area [Sf]	
In Zone:											
In Roof:											
☐											

Floors

No	Description	Type	Width [ft]	H (Effec) [ft]	Multi plier	Area [sf]	Cond. [Btu/hr. sf. F]	Heat Cap. [Btu/sf. F]	Dens. [lb/cf]	R-Value [h.sf.F/Btu]	
In Zone: Mini Splts											
1	Classroom #1	Concrete floor, carpet and rubber pad	25.50	22.50	1	573.8	0.5987	9.33	140.00	1.67	☐

2	Classroom #2	Concrete floor, carpet and rubber pad	25.50	22.50	1	573.8	0.5987	9.33	140.00	1.67	☐
3	Classroom #3	Concrete floor, carpet and rubber pad	21.50	25.50	1	548.3	0.5987	9.33	140.00	1.67	☐
4	Classroom #4	Concrete floor, carpet and rubber pad	20.50	25.50	1	522.8	0.5987	9.33	140.00	1.67	☐
5	Classroom #5	Concrete floor, carpet and rubber pad	17.50	25.50	1	446.3	0.5987	9.33	140.00	1.67	☐
6	Classroom #6	Concrete floor, carpet and rubber pad	25.00	22.50	1	562.5	0.5987	9.33	140.00	1.67	☐
7	Classroom #7	Concrete floor, carpet and rubber pad	24.50	22.50	1	551.3	0.5987	9.33	140.00	1.67	☐
8	Classroom #8	Concrete floor, carpet and rubber pad	24.50	22.50	1	551.3	0.5987	9.33	140.00	1.67	☐
In Zone: 5 Ton Zone											
1	Hall	Concrete floor, carpet and rubber pad	50.00	21.82	1	1091.0	0.5987	9.33	140.00	1.67	☐
2	Strg #1	Concrete floor, carpet and rubber pad	9.50	16.50	1	156.8	0.5987	9.33	140.00	1.67	☐
3	Strg #2	Concrete floor, carpet and rubber pad	6.50	22.50	1	146.3	0.5987	9.33	140.00	1.67	☐
4	Office #1	Concrete floor, carpet and rubber pad	15.50	22.50	1	348.8	0.5987	9.33	140.00	1.67	☐
5	Office #2	Concrete floor, carpet and rubber pad	16.00	14.50	1	232.0	0.5987	9.33	140.00	1.67	☐
6	Office #3	Concrete floor, carpet and rubber pad	16.00	11.00	1	176.0	0.5987	9.33	140.00	1.67	☐

Systems

12K HP Mini Split		12K HP Mini Split	Constant Volume Air Cooled Split System < 65000 Btu/hr		No. Of Units	8
Component	Category	Capacity	Efficiency	IPLV		
1	Cooling System	12000.00	17.40	8.00		☐
2	Heating System	12000.00	8.70			☐
3	Air Handling System -Supply	400.00	0.32			☐
4	Air Handling System - Return	400.00	0.32			☐
5	Air Distribution System (Sup)		6.00			☐
6	Air Distribution System (Ret)		6.00			☐

5 Ton HP Split		5 Ton HP Split	Constant Volume Air Cooled Split System < 65000 Btu/hr		No. Of Units	1
Component	Category	Capacity	Efficiency	IPLV		
1	Cooling System	60000.00	14.30	8.00		☐
2	Heating System	60000.00	7.50			☐
3	Air Handling System -Supply	2000.00	0.32			☐
4	Air Handling System - Return	2000.00	0.32			☐
5	Air Distribution System (Sup)		6.00			☐
6	Air Distribution System (Ret)		6.00			☐

Plant

Equipment	Category	Size	Inst.No	Eff.	IPLV
					☐

Water Heaters

W-Heater Description	Capacity Cap.Unit	I/P Rt.	Efficiency	Loss

1	Electric Storage water heater (1 units)	50 [Gal]	13 [kW]	0.9450 [Ef]	%	☐
---	---	----------	---------	-------------	---	--------------------------

Ext-Lighting						
Description	Category	No. of Luminaires	Watts per Luminaire	Area/Len/No. of units [sf/ft/No]	Control Type	Wattage [W]
☐						

Piping						
No	Type	Operating Temperature [F]	Insulation Conductivity [Btu-in/h.sf.F]	Nomonal pipe Diameter [in]	Insulation Thickness [in]	Is Runout?
☐						

Fenestration Used					
Name	Glass Type	No. of Panels	Glass Conductance [Btu/h.sf.F]	SHGC	VLT
☐					

Materials Used								
Mat No	Acronym	Description	Only R-Value Used	RValue [h.sf.F/Btu]	Thickness [ft]	Conductivity [Btu/h.ft.F]	Density [lb/cf]	SpecificHeat [Btu/lb.F]
187	Matl187	GYP OR PLAS BOARD,1/2IN	No	0.4533	0.0417	0.0920	50.00	0.2000
151	Matl151	CONC HW, DRD, 140LB, 4IN	No	0.4403	0.3333	0.7570	140.00	0.2000

178	Matl178	CARPET W/RUBBER PAD	Yes	1.2300					☐
211	Matl211	POLYSTYRENE,EXP.,1/2IN	No	2.0850	0.0417	0.0200	1.80	0.2900	☐
12	Matl12	3 in. Insulation	No	10.0000	0.2500	0.0250	2.00	0.2000	☐
23	Matl23	6 in. Insulation	No	20.0000	0.5000	0.0250	5.70	0.2000	☐
287	Matl287	Polyurethane core (24 ga steel) 2	Yes	4.1500					☐
81	Matl81	ASPHALT-ROOFING, ROLL	Yes	0.1500					☐
244	Matl244	PLYWOOD, 1/2IN	No	0.6318	0.0417	0.0660	34.00	0.2900	☐

Constructs Used

No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1004	Concrete floor, carpet and rubber pad	No	No	0.60	9.33	140.00	1.7	☐
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	151	CONC HW, DRD, 140LB, 4IN	0.3333	0.000			☐
	2	178	CARPET W/RUBBER PAD		0.000			☐
No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1017	Metal/R19/1/2" Gyp	No	No	0.04	1.01	8.59	22.5	☐
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	211	POLYSTYRENE,EXP.,1/2IN,	0.0417	0.000			☐
	2	23	6 in. Insulation	0.5000	0.000			☐
	3	187	GYP OR PLAS BOARD,1/2IN	0.0417	0.000			☐

No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1036	Polyurethane core (24 ga steel) 2	No	Yes	0.24			4.2	☐
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	287	Polyurethane core (24 ga steel) 2		0.000			☐
No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1038	Metal/1/2"WD Deck/WD Truss/9" Batt/Acoustic Tile	No	No	0.03	1.50	8.22	31.2	☐
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	81	ASPHALT-ROOFING, ROLL		0.000			☐
	2	244	PLYWOOD, 1/2IN	0.0417	0.000			☐
	3	12	3 in. Insulation	0.2500	0.000			☐
	4	23	6 in. Insulation	0.5000	0.000			☐
	5	187	GYP OR PLAS BOARD,1/2IN	0.0417	0.000			☐



Right-Suite® Universal 2023 Short Form

Mini Split #1

New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...

Date: 05/06/2024

By: John PirkI

Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	33	91
Outside wb	(°F)	-	49
Daily range	(°F)	-	76
Moisture diff.	(gr/lb)	-	18
			44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	70	75
Inside wb	(°F)	-	50
Design TD	(°F)	-	63
		37	16

Heating Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
Efficiency	8.7 HSPF2
Heating Input	
Heating Output	12.0 MBtuh @ 47°F
Humidifier	4.6 gpd
Leaving Air Temp	97.4 °F
Actual Heating Fan	400 cfm

Cooling Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
COP / EER / SEER	17.4
Sensible Cooling	8.4 MBtuh
Latent Cooling	3.6 MBtuh
Total Cooling	12.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	400 cfm

Equipment Location	Mini Split #1
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Classroom #1	574	9945	8586	2887	400	400	Jul 1800 LDT
Mini Split #1	574	9945	8586	2887	400	400	Jul 1800 LDT





Right-Suite® Universal 2023 Short Form
Mini Split #2
New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...
Date: 05/06/2024
By: John PirkI
Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	33	91
Outside wb	(°F)	-	49
Daily range	(°F)	-	76
Moisture diff.	(gr/lb)	-	18
			44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	70	75
Inside wb	(°F)	-	50
Design TD	(°F)	-	63
		37	16

Heating Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
Efficiency	8.7 HSPF2
Heating Input	
Heating Output	12.0 MBtuh @ 47°F
Humidifier	4.6 gpd
Leaving Air Temp	97.4 °F
Actual Heating Fan	400 cfm

Cooling Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
COP / EER / SEER	17.4
Sensible Cooling	8.4 MBtuh
Latent Cooling	3.6 MBtuh
Total Cooling	12.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	400 cfm

Equipment Location	Mini Split #2
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Classroom #2	574	8284	7792	2887	400	400	Jul 1800 LDT
Mini Split #2	574	8284	7792	2887	400	400	Jul 1800 LDT





Right-Suite® Universal 2023 Short Form
Mini Split #3
New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...
Date: 05/06/2024
By: John PirkI
Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	33	91
Outside wb	(°F)	-	49
Daily range	(°F)	-	76
Moisture diff.	(gr/lb)	-	18
			44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	70	75
Inside wb	(°F)	-	50
Design TD	(°F)	-	63
		37	16

Heating Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
Efficiency	8.7 HSPF2
Heating Input	
Heating Output	12.0 MBtuh @ 47°F
Humidifier	4.0 gpd
Leaving Air Temp	97.4 °F
Actual Heating Fan	400 cfm

Cooling Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
COP / EER / SEER	17.4
Sensible Cooling	8.4 MBtuh
Latent Cooling	3.6 MBtuh
Total Cooling	12.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	400 cfm

Equipment Location	Mini Split #3
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Classroom #3	548	7492	7857	2709	400	400	Jul 1800 LDT
Mini Split #3	548	7492	7857	2709	400	400	Jul 1800 LDT





Right-Suite® Universal 2023 Short Form

Mini Split #4

New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...

Date: 05/06/2024

By: John PirkI

Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	33	91
Outside wb	(°F)	-	49
Daily range	(°F)	-	76
Moisture diff.	(gr/lb)	-	18
			44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	70	75
Inside wb	(°F)	-	50
Design TD	(°F)	-	63
		37	16

Heating Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
Efficiency	8.7 HSPF2
Heating Input	
Heating Output	12.0 MBtuh @ 47°F
Humidifier	3.9 gpd
Leaving Air Temp	97.4 °F
Actual Heating Fan	400 cfm

Cooling Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
COP / EER / SEER	17.4
Sensible Cooling	8.4 MBtuh
Latent Cooling	3.6 MBtuh
Total Cooling	12.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	400 cfm

Equipment Location	Mini Split #4
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Classroom #4	523	5509	6747	2709	400	400	Jul 1800 LDT
Mini Split #4	523	5509	6747	2709	400	400	Jul 1800 LDT





Right-Suite® Universal 2023 Short Form

Mini Split #5

New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...

Date: 05/06/2024

By: John PirkI

Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	33	91
Outside wb	(°F)	-	49
Daily range	(°F)	-	76
Moisture diff.	(gr/lb)	-	18
			44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	70	75
Inside wb	(°F)	-	50
Design TD	(°F)	-	63
		37	16

Heating Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
Efficiency	8.7 HSPF2
Heating Input	
Heating Output	12.0 MBtuh @ 47°F
Humidifier	4.6 gpd
Leaving Air Temp	97.4 °F
Actual Heating Fan	400 cfm

Cooling Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
COP / EER / SEER	17.4
Sensible Cooling	8.4 MBtuh
Latent Cooling	3.6 MBtuh
Total Cooling	12.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	400 cfm

Equipment Location	Mini Split #5
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Classroom #5	446	6349	6938	3612	400	400	Jul 1800 LDT
Mini Split #5	446	6349	6938	3612	400	400	Jul 1800 LDT





Right-Suite® Universal 2023 Short Form

Mini Split #6

New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...

Date: 05/06/2024

By: John PirkI

Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	33	91
Outside wb	(°F)	-	49
Daily range	(°F)	-	76
Moisture diff.	(gr/lb)	-	18
			44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	70	75
Inside wb	(°F)	-	50
Design TD	(°F)	-	63
		37	16

Heating Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
Efficiency	8.7 HSPF2
Heating Input	
Heating Output	12.0 MBtuh @ 47°F
Humidifier	4.5 gpd
Leaving Air Temp	97.4 °F
Actual Heating Fan	400 cfm

Cooling Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
COP / EER / SEER	17.4
Sensible Cooling	8.4 MBtuh
Latent Cooling	3.6 MBtuh
Total Cooling	12.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	400 cfm

Equipment Location	Mini Split #6
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Classroom #6	563	9863	8594	2887	400	400	Jul 1800 LDT
Mini Split #6	563	9863	8594	2887	400	400	Jul 1800 LDT





Right-Suite® Universal 2023 Short Form

Mini Split #7

New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...

Date: 05/06/2024

By: John PirkI

Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	33	91
Outside wb	(°F)	-	49
Daily range	(°F)	-	76
Moisture diff.	(gr/lb)	-	18
			44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	70	75
Inside wb	(°F)	-	50
Design TD	(°F)	-	63
		37	16

Heating Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
Efficiency	8.7 HSPF2
Heating Input	
Heating Output	12.0 MBtuh @ 47°F
Humidifier	4.5 gpd
Leaving Air Temp	97.4 °F
Actual Heating Fan	400 cfm

Cooling Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
COP / EER / SEER	17.4
Sensible Cooling	8.4 MBtuh
Latent Cooling	3.6 MBtuh
Total Cooling	12.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	400 cfm

Equipment Location	Mini Split #7
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Classroom #7	551	8121	7006	2887	400	400	Jul 1800 LDT
Mini Split #7	551	8121	7006	2887	400	400	Jul 1800 LDT





Right-Suite® Universal 2023 Short Form

Mini Split #8

New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...

Date: 05/06/2024

By: John PirkI

Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	33	91
Outside wb	(°F)	-	49
Daily range	(°F)	-	76
Moisture diff.	(gr/lb)	-	18
			44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	70	75
Inside wb	(°F)	-	50
Design TD	(°F)	-	63
		37	16

Heating Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
Efficiency	8.7 HSPF2
Heating Input	
Heating Output	12.0 MBtuh @ 47°F
Humidifier	4.5 gpd
Leaving Air Temp	97.4 °F
Actual Heating Fan	400 cfm

Cooling Equipment

Make	CARRIER
Model	38MVRAQ12AA1
Type	Split ASHP
COP / EER / SEER	17.4
Sensible Cooling	8.4 MBtuh
Latent Cooling	3.6 MBtuh
Total Cooling	12.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	400 cfm

Equipment Location	Mini Split #8
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Classroom #8	551	8121	7695	2887	400	400	Jul 1800 LDT
Mini Split #8	551	8121	7695	2887	400	400	Jul 1800 LDT





Right-Suite® Universal 2023 Short Form
Split System
New Age Dimensions, L.L.C.

Job: Kingdom Culture Acade...
Date: 05/06/2024
By: John PirkI
Plan: Manual N and D

14080 S.E. 122nd Lane Road, Ocklawaha, FL 32179 Phone: (352) 288 - 0686 Fax: (352) 288 - 0684 Email: john.newage@gmail.com Web: www.newagedimensions.webs.com

Project Information

For: Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue, Gainesville, FL 32609
Phone: (352) 316 - 4573

Outside db	(°F)	Htg	Clg
Outside RH	(%)	-	49
Outside wb	(°F)	-	76
Daily range	(°F)	-	18
Moisture diff.	(gr/lb)	-	44

Inside db	(°F)	Htg	Clg
Inside RH	(%)	-	50
Inside wb	(°F)	-	63
Design TD	(°F)	37	16

Heating Equipment

Make	Bryant
Model	PH5SAN46000AA0
Type	Split ASHP
Efficiency	7.5 HSPF2
Heating Input	
Heating Output	57.0 MBtuh @ 47°F
Humidifier	17.1 gpd
Leaving Air Temp	96.0 °F
Actual Heating Fan	2000 cfm



Cooling Equipment

Make	Bryant
Model	PH5SAN46000AA0
Type	Split ASHP
COP / EER / SEER	14.3
Sensible Cooling	39.9 MBtuh
Latent Cooling	17.1 MBtuh
Total Cooling	57.0 MBtuh
Leaving Air Temp	55.0 °F
Actual Cooling Fan	2000 cfm

Equipment Location	Split System
System Type	PEAKCV
Fan Motor Heat Type	PACKAGE
Fan & Motor Combined Efficiency	0 %
Static Pressure Across Fan	0 in H2O

NAME	Area ft²	Heat Loss	Sensible Gain	Latent Gain	Htg cfm	Clg cfm	Time
Hall	1091	14708	13852	5580	881	739	Jul 1800 LDT
Strg #2	146	4161	3010	438	325	168	Jul 1800 LDT
Office #3	176	3368	5067	1706	143	263	Jul 1800 LDT
Office #2	232	4076	5833	1806	189	305	Jul 1800 LDT
Office #1	349	6843	7788	2013	410	411	Jul 1800 LDT
Strg #1	157	1738	2287	558	52	114	Jul 1800 LDT
Split System	2151	34894	37837	12101	2000	2000	Jul 1800 LDT





**Job #: Kingdom Culture Academy
Performed by John PirkI for:**

Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue
Gainesville, FL 32609
Phone: (352) 316 - 4573

New Age Dimensions, L.L.C.

14080 S.E. 122nd Lane Road
Ocklawaha, FL 32179
Phone: (352) 288 - 0686 Fax: (352) 288 - 0684
www.newagedimensions.webs.com john.newage@gmail.com

Scale: 1 : 163

Page 1

Right-Suite® Universal 2023

23.0.05 RSU02050

2024-May-09 08:36:39

...e Academy Ventilation Design.rup

Florida Building Code, 8th Edition (2023) - Energy Conservation

EnergyGauge Summit® Fla/Com-2023, Effective Date: Dec 31, 2023

C401.2.1: ASHRAE Energy Cost Budget Option

Compliance applying ASHRAE Section 11

Check List

Applications for compliance with the Florida Building Code, Energy Conservation shall include:

- ☐ The full compliance report generated by the software that contains the project summary, compliance summary, certifications and detailed component compliance reports.
- ☐ The compliance report must include the full input report generated by the software as contiguous part of the compliance report.
- ☐ Boxes appropriately checked in the Mandatory Section of the compliance report.

PROJECT SUMMARY

Short Desc: School

Description: Kingdom Culture School

Owner: Kingdom Culture School

Address1: Kingdom Culture School

City: Lake City

Address2: 217 S.W. Dyal Avenue

State: Florida

Zip: 32024

Type: School/University

Class: New Finished building

Jurisdiction: LAKE CITY, COLUMBIA COUNTY, FL (221200)

Conditioned Area: 6480 SF

Conditioned & UnConditioned Area: 6480 SF

No of Stories: 1

Area entered from Plans 6480 SF

Permit No: 0

Max Tonnage 5

If different, write in: _____

Compliance Summary			
Component	Design	Criteria	Result
Gross Energy Cost (in \$)	3705.00	3839.00	PASSED
LIGHTING CONTROLS			PASSES
EXTERNAL LIGHTING			No Entry
HVAC SYSTEM			PASSES
PLANT			No Entry
WATER HEATING SYSTEMS			PASSES
PIPING SYSTEMS			No Entry
Met all required compliance from Check List?			Yes/No/NA
IMPORTANT MESSAGE Info 5009 -- -- -- An input report of this design building must be submitted along with this Compliance Report			

CERTIFICATIONS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code

Prepared By: John PirkI

Building _____

Official:

Date: _____

Date: _____

I certify that this building is in compliance with the FLorida Energy Efficiency Code

Owner Agent: Kingdom Culture School

Date: _____

If Required by Florida law, I hereby certify (*) that the system design is in compliance with the Florida Energy Efficiency Code

Architect: Nicholas Paul Geisler

Reg No: 0007005 Signature_____

Electrical Designer: Nicholas Paul Geisler

Reg No: 0007005 Signature_____

Lighting Designer: Nicholas Paul Geisler

Reg No: 0007005 Signature_____

Mechanical Designer: Jarvis Heat & Air, LLC

Reg No: 1816766 Signature_____

Plumbing Designer: Nicholas Paul Geisler

Reg No: 0007005 Signature_____

(*) Signature is required where Florida Law requires design to be performed by registered design professionals per C103.1.1.1.2

Project: School
Title: Kingdom Culture School
Type: School/University
(WEA File: FL_JACKSONVILLE_INTL_ARPT.tn3)

Building End Uses

	1) Proposed	2) Baseline
Total	235.50	243.28
	\$3,705	\$3,839
ELECTRICITY(MBtu/kWh/\$)	235.50	243.28
	68996	71283
	\$3,705	\$3,839
AREA LIGHTS	52.80	43.70
	15466	12805
	\$831	\$690
MISC EQUIPMT	57.40	57.40
	16830	16830
	\$904	\$906
PUMPS & MISC	0.30	0.30
	82	85
	\$4	\$5
SPACE COOL	63.50	70.90
	18597	20764
	\$999	\$1,118
SPACE HEAT	12.50	14.55
	3651	4263
	\$196	\$230
VENT FANS	49.00	56.43
	14370	16537
	\$772	\$890

Credits Applied: None

Passing Criteria = 3839

Design (including any credits) = 3705

Passing requires Proposed Building cost to be at most 100% of
Baseline cost. This Proposed Building is at 96.5%

PASSES

External Lighting Compliance						
Description	Category	Tradable?	Allowance (W/Unit)	Area or Length or No. of Units (Sqft or ft)	ELPA (W)	CLP (W)
					None	

Project: School
 Title: Kingdom Culture School
 Type: School/University
 (WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Lighting Controls Compliance

Acronym	ID	Description	Area (sq.ft)	Compliance
<u>Classroom #1</u>	<u>14</u>	<u>Classroom #1</u> <u>(Classroom/Lecture Hall)</u>	<u>574</u>	COMPLIANCE: PASSES REQUIRED: All of 1 4 8 ; one of 2 3 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 3-Occupant Sensor (50%) 4-Light Reduction (30%-70%) 5-Daylight Responsive (Sidelighting) 6-Daylight Responsive (Toplighting) 7-Occupant Sensor Auto OFF (Full or Partial) 8-Occupant Sensor Auto Full OFF 9-Time-Switch: Auto Full Off or Scheduled Off
<u>Classroom #2</u>	<u>14</u>	<u>Classroom #2</u> <u>(Classroom/Lecture Hall)</u>	<u>574</u>	COMPLIANCE: PASSES REQUIRED: All of 1 4 8 ; one of 2 3 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 3-Occupant Sensor (50%) 4-Light Reduction (30%-70%) 5-Daylight Responsive (Sidelighting) 6-Daylight Responsive (Toplighting) 7-Occupant Sensor Auto OFF (Full or Partial) 8-Occupant Sensor Auto Full OFF 9-Time-Switch: Auto Full Off or Scheduled Off

Classroom #3

**14 Classroom #3
(Classroom/Lecture Hall)**

548 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

Classroom #4

**14 Classroom #4
(Classroom/Lecture Hall)**

523 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

Classroom #5

**14 Classroom #5
(Classroom/Lecture Hall)**

446 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

Classroom #6

**14 Classroom #6
(Classroom/Lecture Hall)**

563 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

Classroom #7

**14 Classroom #7
(Classroom/Lecture Hall)**

551 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

Classroom #8

**14 Classroom #8
(Classroom/Lecture Hall)**

551 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

<u>Hall</u>	5 <u>Hall (Corridor)</u>	1,091 COMPLIANCE: PASSES REQUIRED: All of 1 7 ; one of 8 9 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 3-Occupant Sensor (50%) 4-Light Reduction (30%-70%) 5-Daylight Responsive (Sidelighting) 6-Daylight Responsive (Toplighting) 7-Occupant Sensor Auto OFF (Full or Partial) 8-Occupant Sensor Auto Full OFF 9-Time-Switch: Auto Full Off or Scheduled Off
<u>Strg #1</u>	2 <u>Strg #1 (Storage & Warehouse - Inactive Storage)</u>	157 COMPLIANCE: PASSES REQUIRED: All of 1 4 7 ; one of 2 3 ; one of 8 9 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 3-Occupant Sensor (50%) 4-Light Reduction (30%-70%) 5-Daylight Responsive (Sidelighting) 6-Daylight Responsive (Toplighting) 7-Occupant Sensor Auto OFF (Full or Partial) 8-Occupant Sensor Auto Full OFF 9-Time-Switch: Auto Full Off or Scheduled Off
<u>Strg #2</u>	2 <u>Strg #2 (Storage & Warehouse - Inactive Storage)</u>	146 COMPLIANCE: PASSES REQUIRED: All of 1 4 7 ; one of 2 3 ; one of 8 9 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 3-Occupant Sensor (50%) 4-Light Reduction (30%-70%) 5-Daylight Responsive (Sidelighting) 6-Daylight Responsive (Toplighting) 7-Occupant Sensor Auto OFF (Full or Partial) 8-Occupant Sensor Auto Full OFF 9-Time-Switch: Auto Full Off or Scheduled Off

Office #1

17 Office #1 (Office - Enclosed)

349 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

Office #2

17 Office #2 (Office - Enclosed)

232 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

Office #3

17 Office #3 (Office - Enclosed)

176 COMPLIANCE: PASSES
REQUIRED:
All of |1|4|8|; one of |2|3|
CONTROLS IN SPACE:
1-Manual (Local Control)
2-Occupancy Sensor - Manual ON
only
3-Occupant Sensor (50%)
4-Light Reduction (30%-70%)
5-Daylight Responsive (Sidelighting)
6-Daylight Responsive (Toplighting)
7-Occupant Sensor Auto OFF (Full or
Partial)
8-Occupant Sensor Auto Full OFF
9-Time-Switch: Auto Full Off or
Scheduled Off

PASSES

Project: School
Title: Kingdom Culture School
Type: School/University
(WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

System Report Compliance

12K HP Mini Split		Constant Volume Air Cooled Split System < 65000 Btu/hr					No. of Units
12K HP Mini Split							8
Component	Category	Capacity	Eff Design	Eff Criteria	Integrated Eff-Design	Integrated Eff-Criteria	Compliance
Cooling System	Air Conditioners Air Cooled Split System < 45000 Btu/h Cooling Capacity	12000	17.40	14.30	8.00		PASSES
Heating System	Heat Pumps Air Cooled (Heating Mode) Split System < 65000 Btu/h Cooling Capacity	12000	8.70	7.50			PASSES
Air Handling System -Supply	Air Handler (Supply) - Constant Volume	400	0.32	0.82			PASSES
Air Handling System - Return	Air Handler (Return) - Constant Volume	400	0.32	0.82			PASSES
Air Distribution System (Sup)	Not in Check list - Compliance Ignored		6.00	6.00			N/A
Air Distribution System (Ret)	Not in Check list - Compliance Ignored		6.00	6.00			N/A
5 Ton HP Split		Constant Volume Air Cooled Split System < 65000 Btu/hr					No. of Units
5 Ton HP Split							1
Component	Category	Capacity	Eff Design	Eff Criteria	Integrated Eff-Design	Integrated Eff-Criteria	Compliance
Cooling System	Air Conditioners Air Cooled Split System 45000 - 65000 Btu/h Cooling Capacity	60000	14.30	13.80	8.00		PASSES
Heating System	Heat Pumps Air Cooled (Heating Mode) Split System < 65000 Btu/h Cooling Capacity	60000	7.50	7.50			PASSES
Air Handling System -Supply	Air Handler (Supply) - Constant Volume	2000	0.32	0.82			PASSES
Air Handling System - Return	Air Handler (Return) - Constant Volume	2000	0.32	0.82			PASSES
Air Distribution System (Sup)	Not in Check list - Compliance Ignored		6.00	6.00			N/A
Air Distribution System (Ret)	Not in Check list - Compliance Ignored		6.00	6.00			N/A

PASSES

None

PASSES

None

Mandatory Requirements (as applicable)

Requirements compiled by US Department of Energy and Pacific Northwest National Laboratory. Adopted for FBC with permission. Not all may be applicable

Topic	Section	Component	Description	Yes	N/A	Exempt
1. To be checked by Designer or Engineer						
5140 Controls	10.4.3	Mechanical	Elevators are designed with the proper lighting, ventilation power, and standby mode. []- Exception 1:10.4.3: Requirement does not apply.	☐	☐	☐
5012 Insulation	5.5.3.5	Envelope	Slab edge insulation depth/length shall be per Tables 5.5-0 through 5.5-8.	☐	☐	☐
5027 Fenestration	5.5.3.6	Envelope	U-factor of opaque doors associated with the building thermal envelope meets requirements.	☐	☐	☐
5021 Fenestration	5.5.4.3a	Envelope	Vertical fenestration shall have a U-factor $\leq$ the values specified in Tables 5.5-0 through 5.5-8.	☐	☐	☐
5022 Fenestration	5.5.4.3b	Envelope	Skylight shall have a U-factor $\leq$ the values specified in Tables 5.5-0 through 5.5-8.	☐	☐	☐
5023 Fenestration	5.5.4.4.1	Envelope	Vertical fenestration SHGC value.	☐	☐	☐
5024 Fenestration	5.5.4.4.2	Envelope	Skylight SHGC value.	☐	☐	☐
5014 Insulation	5.8.1.7.3	Envelope	Insulation in contact with the ground has $\leq 0.3\%$ water absorption rate per ASTM C272.	☐	☐	☐
5016 Insulation	6.4.4.1.5	Envelope	Bottom surface of floor structures incorporating radiant heating insulated to $\geq R-3.5$. []- Exception 1:6.4.4.1.5: Requirement does not apply.	☐	☐	☐

5045 HVAC	6.5.1, 6.5.1.1, 6.5.1.3, 6.5.1.4	Mechanical	Air economizers provided where required (and not exempted), meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off, integrated economizer control, and provide a means to relieve excess outside air during operation. []- Exception 1:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4: High-efficiency cooling equipment has been installed. The qualifying minimum equipment efficiency has been computed and is represented above. []- Exception 2:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4: Air/evap condenser serving space with open-case refrigeration. []- Exception 3:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4: Filtration requirements applicable to the conditioned area would be compromised per Section 6.2.1 in Standard 62.1. []- Exception 4:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4: Medical facility where 75% of design air is to be humidified above 35°F, other buildings more than 25% of design air designed is it to be humidified above 35°F dew-point temperature (not applicable to computer rooms). []- Exception 5:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4: Systems that will be operated < 20 hours per week. []- Exception 6:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4: Systems serving residential spaces with system capacity < 675 kBtu/h. []- Exception 7:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4: System has condenser heat recovery serving service water heat. []- Exception 8:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4: System serves computer room that have total design cooling load < 3,000 kBut/h and building not served by centralized chilled water plant, or room design load < 600 kBtu/hr and is served by centralized chilled water plant, or cooling towers are not permit []- Exception 9:6.5.1_6.5.1.1_6.5.1.3_6.5.1.4Exception9: Transmission and infiltration losses at outdoor temp = 60°F are > sensible design cooling loads (net of losses).	☐	☐	☐
5046 HVAC	6.5.1, 6.5.1.2, 6.5.1.2.1, 6.5.1.3	Mechanical	Water economizers provided where required , meet the requirements for design capacity, maximum pressure drop and integrated economizer control. Capable if providing 100% of the expected system cooling load when outdoor air <= 50F. []- Exception 1:6.5.1_6.5.1.2_6.5.1.2.1_6.5.1.3: Requirement does not apply.	☐	☐	☐
5047 HVAC	6.5.1.5	Mechanical	Economizer operation will not increase heating energy use during normal operation. []- Exception 1:6.5.1.5: Economizers on VAV systems that raise zone heating due to a reduction in supply air temperature.	☐	☐	☐
5058 HVAC	6.5.1.5	Mechanical	Water economizer specified on hydronic cooling and humidification systems designed to maintain inside humidity at >35 °F dewpoint if an economizer is required.	☐	☐	☐

EnergyGauge Summit® Fla/Com-2023. Effective Date: Dec 31, 2023

Florida Building Code, 8th Edition (2023) - Energy Conservation C401.2.1: ASHRAE Energy Cost Budget Option

5053 HVAC	6.5.2.2.3	Mechanical	Hydronic heat pump systems connected to a common water loop meet heat rejection and heat addition requirements. []- Exception 1:6.5.2.2.3: A deadband of less than 20°F is allowed where a temperature optimization controller is used.	☐ ☐ ☐
5167 HVAC	6.5.2.6	Mechanical	Units that provide ventilation air to multiple zones and operate in conjunction with zone heating and cooling systems are prevented from using heating or heat recovery to warm supply air above 60°F when representative building loads or outdoor air temperature indicate that most zones demand cooling. []- Exception 1:6.5.2.6: Requirement does not apply.	☐ ☐ ☐
5059 HVAC	6.5.3.1.1	Mechanical	HVAC fan systems at design conditions do not exceed allowable fan system motor nameplate hp or fan system bhp. []- Exception 1:6.5.3.1.1: Hospital and laboratory systems that utilize flow control devices on exhaust and/or return. []- Exception 2:6.5.3.1.1: Individual exhaust fans with motor nameplate horsepower of 1 hp or less. []- Exception 3:6.5.3.1.1: Fans exhausting air from fume hoods.	☐ ☐ ☐
5060 HVAC	6.5.3.1.2	Mechanical	For each HVAC fan less than 6 bhp, the selected fan motor shall be no larger than the first available motor with a nameplate rating greater than 1.5 times the bhp and For each HVAC fan 6 bhp and larger, the selected fan motor shall be no larger than the first available motor with a nameplate rating greater than 1.3 times the bhp. []- Exception 1:6.5.3.1.2: Motors equipped with electronic speed control devices to vary the fan airflow as a function of load. []- Exception 2:6.5.3.1.2: Systems complying with Section 6.5.3.1.1, Option 1. []- Exception 3:6.5.3.1.2: Fans with motor nameplate horsepower of less than 1 hp. []- Exception 4:6.5.3.1.2: Fans with a fan nameplate electrical input power of less than 0.89 kW.	☐ ☐ ☐
5166 HVAC	6.5.3.2.4	Mechanical	Return and relief fans used to meet Section 6.5.1.1.5 have relief air rate controlled to maintain building pressure through differential supply-return airflow tracking. Systems with supply fans allowed to control the relief system based on outdoor air damper position. Fans have variable speed control or other devices for managing total return/relief fan system demand per section threshold. []- Exception 1:6.5.3.2.4: Return or relief fans with total motor size <= 0.5 hp. []- Exception 2:6.5.3.2.4: Staged relief fans with >= 4 stages. []- Exception 3:6.5.3.2.4: Requirement does not apply.	☐ ☐ ☐

5169 HVAC	6.5.3.4	Mechanical	Parallel-flow fan-powered VAV air terminals have automatic controls to a) turn off the terminal fan except when space heating is required or if required for ventilation; b) turn on the terminal fan as the first stage of heating before the heating coil is activated; and c) during heating for warmup or setback temperature control, either operate the terminal fan and heating coil without primary air or reverse the terminal damper logic and provide heating from the central air handler through primary air. []- Exception 1:6.5.3.4: Requirement does not apply.	☐	☐	☐
5062 HVAC	6.5.3.6	Mechanical	Motors for fans $\geq 1/12$ hp and < 1 hp are electronically-commutated motors or have a minimum motor efficiency of 70%. These motors are also speed adjustable for either balancing or remote control. []- Exception 1:6.5.3.6: Motors in the airstream within fan-coils and termina units that operate only when providing heat. []- Exception 2:6.5.3.6: Motors installed in space conditioning equipment certified under Section 6.4.1. []- Exception 3:6.5.3.6: Motors covered by Table 10.8-4 or 10.8-5. []- Exception 4:6.5.3.6: Requirement does not apply.	☐	☐	☐
5170 HVAC	6.5.3.7	Mechanical	Required minimum outdoor air rate is the larger of minimum outdoor air rate or minimum exhaust air rate required by Standard 62.1, Standard 170, or applicable codes or accreditation standards. Outdoor air ventilation systems shall comply with one of the following: a) design minimum system outdoor air provided $< 135\%$ of the required minimum outdoor air rate, b) dampers, ductwork, and controls allow the system to supply $\geq$ the required minimum outdoor air rate with a single set-point adjustment., or c) system includes exhaust air energy recovery complying with Section 6.5.6.1. []- Exception 1:6.5.3.7: Requirement does not apply.	☐	☐	☐

5168 HVAC	6.5.4.7	Mechanical	Chilled-water cooling coils provide a 15°F or higher temperature difference between leaving and entering water temperatures and a minimum of 57°F leaving water temperature at design conditions []- Exception 1:6.5.4.7: Chilled-water cooling coils that have an air-side pressure drop exceeding 0.70 in. of water when rated at 500 fpm face velocity and dry conditions. []- Exception 2:6.5.4.7: Individual fan-cooling units with a design supply airflow rate 5000 cfm and less. []- Exception 3:6.5.4.7: Constant-air-volume systems. []- Exception 4:6.5.4.7: Coils selected at the maximum temperature difference allowed by the chiller. []- Exception 5:6.5.4.7: Passive coils (no mechanically supplied airflow). []- Exception 6:6.5.4.7: Coils with design entering chilled-water temperatures of 50°F and higher. []- Exception 7:6.5.4.7: Coils with design entering air dry-bulb temperatures of 65°F and lower. []- Exception 8:6.5.4.7: Requirement does not apply.	☐	☐	☐
5077 HVAC	6.5.5.2.3	Mechanical	None	☐	☐	☐
5078 HVAC	6.5.6.1	Mechanical	Exhaust air energy recovery on systems meeting Tables 6.5.6.1.2-1, and 6.5.6.1.2-2. []- Exception 1:6.5.6.1: Laboratory fume hood systems with a total exhaust rate <= 5000 cfm. []- Exception 2:6.5.6.1: Systems serving spaces that are not cooled and heated to <60°F. []- Exception 3:6.5.6.1: Systems with more than 60% of the outdoor heating energy is provided from site-recovered or site solar energy. []- Exception 4:6.5.6.1: Systems requiring dehumidification with cooling coil energy recovery in series with the cooling coil. []- Exception 5:6.5.6.1: Where the largest exhaust source is less than 75% of the design outdoor airflow. []- Exception 6:6.5.6.1: Enthalpy energy recovery ratio requirements at heating design condition in Climate Zones 0, 1, and 2. []- Exception 7:6.5.6.1: Enthalpy recovery ratio requirements at cooling design condition in Climate Zones 3C, 4C, 5B, 5C, 6B, 7, and 8. []- Exception 8:6.5.6.1: Operating < 20 hours per week at the outdoor air percentage covered by Table 6.5.6.1.2-1. []- Exception 9:6.5.6.1Exception9: Requirement does not apply.	☐	☐	☐

5130 HVAC	6.7.3.3	Mechanical	HVAC control systems have been tested to ensure proper operation, calibration and adjustment of controls.	☐	☐	☐
5171 HVAC	6.8.1-13 or 6.8.1-14	Mechanical	Electrically operated DX-DOAS units meet requirements per Tables 6.8.1-13 or 6.8.1-14. []- Exception 1:6.8.1-13_6.8.1-14: Requirement does not apply.	☐	☐	☐
5090 HVAC	7.4.2	Mechanical	Service water heating equipment meets efficiency requirements. []- Exception 1:7.4.2: Water heating equipment >140 gallon capacity is not required to meet standby loss requirements when insulated, no pilot light, and flue damper or fan-assisted combustion. []- Exception 2:7.4.2: Storage water heater capacity <20 gallons.	☐	☐	☐
5092 HVAC	7.5.2	Mechanical	Service water heating equipment used for space heating complies with the service water heating equipment requirements.	☐	☐	☐
5156 HVAC	7.5.3	Mechanical	Gas-fired water-heating equipment installed in new buildings: where a singular piece of water-heating equipment $\geq 1,000$ kBtu/h serves the entire building, thermal efficiency must be ≥ 90 Et. Where multiple pieces of water-heating equipment serve the building with combined rating is $\geq 1,000$ kBtu/h, the combined input-capacity-weighted-average thermal efficiency, thermal efficiency must be ≥ 90 Et. Exclude input rating of equipment in individual dwelling units and equipment ≥ 100 kBtu/h. []- Exception 1:7.5.3: 25 percent of the annual service water heating requirement is provided by site-solar or site-recovered energy. []- Exception 2:7.5.3: Requirement does not apply.	☐	☐	☐
2. To be checked by Plan Reviewer						
5100 Other Equipment	10.4.1	Mechanical	Electric motors meet requirements where applicable.	☐	☐	☐
5001 Plan Review	4.2.2, 5.4.3.1.1, 5.7	Envelope	Plans and/or specifications provide all information with which compliance can be determined for the building envelope and document where exceptions to the standard are claimed.	☐	☐	☐
5002 Plan Review	4.2.2, 6.4.4.2.1, 6.7.2	Mechanical	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks.	☐	☐	☐
5003 Plan Review	4.2.2, 7.7.1, 10.4.2	Mechanical	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the service water heating systems and equipment and document where exceptions to the standard are claimed. Hot water system sized per manufacturer's sizing guide.	☐	☐	☐

5004 Plan Review	4.2.2, 8.4.1.1, 8.4.1.2, 8.7	Project	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the electrical systems and equipment and document where exceptions are claimed. Feeder connectors sized in accordance with approved plans and branch circuits sized for maximum drop of 3%.	☐	☐	☐
5005 Plan Review	4.2.2, 9.4.3, 9.7	Interior Lighting	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the interior lighting and electrical systems and equipment and document where exceptions to the standard are claimed. Information provided should include interior lighting power calculations, wattage of bulbs and ballasts, transformers and control devices.	☐	☐	☐
5019 Air Leakage	5.4.3.3	Envelope	Vestibules are installed where building entrances separate conditioned space from the exterior, and meet exterior envelope requirements. Doors have self-closing devices, and are ≥ 7 ft apart (≤ 16 ft apart for adjoining floor area ≤ 40000 sq.ft.). Vestibule floor area ≤ 50 sq.ft. or 2 percent of the adjoining conditioned floor area. []- Exception 1:5.4.3.3: Building entrances with revolving doors. []- Exception 2:5.4.3.3: Doors not intended to be used as a building entrance. []- Exception 3:5.4.3.3: Doors opening directly from a dwelling unit. []- Exception 4:5.4.3.3: Building entrances in buildings located in Climate Zone 1 or 2. []- Exception 5:5.4.3.3: Doors opening into semiheated spaces. []- Exception 6:5.4.3.3: Enclosed elevator lobbies for building entrances directly from parking garages. []- Exception 7:5.4.3.3: Building entrances in buildings that are located in Climate Zone 3, where the building is less than four stories above grade and less than 10,000 ft² in gross conditioned floor area. []- Exception 8:5.4.3.3: Building entrances in buildings that are located in Climate Zone 0, 4, 5, 6, 7, or 8, where the building is less than 1000 ft² in gross conditioned floor area. []- Exception 9:5.4.3.3: Doors that open directly from a space ≤ 3000 ft² and separated from the building entrance. []- Exception 10:5.4.3.3: Self-closing doors in buildings in Climate Zones 0, 3, and 4 that have an air curtain complying with Section 10.4.5. []- Exception 11:5.4.3.3: Self-closing doors in buildings 15 stories or less in Climate Zones 5 through 8 that have an air curtain complying with Section 10.4.5. []- Exception 12:5.4.3.3: Requirement does not apply.	☐	☐	☐

5020 Plan Review	5.5.4.2.3	Envelope	In buildings > 2,500 ft², any enclosed spaces directly under a roof with ceiling heights > 15 ft. and used as an office, lobby, atrium, concourse, corridor, storage (including nonrefrigerated warehouse), gymnasium, fitness/exercise area, playing area, gymnasium seating area, convention exhibit/event space, courtroom, automotive service, fire station engine room, manufacturing corridor/transition and bay areas, retail, library reading and stack areas, distribution/sorting area, transportation baggage and seating areas, or workshop, the following requirements apply: The daylight zone under skylights is $\geq$ half the floor area and (a) the skylight area to daylight zone is $\geq$ 3 percent with a skylight VT $\geq$ 0.40 or (b) the minimum skylight effective aperture $\geq$ 1 percent. The skylights have a measured haze value > 90 percent. []- Exception 1:5.5.4.2.3: Enclosed spaces in Climate Zones 6 through 8. []- Exception 2:5.5.4.2.3: Areas with obstructions that block direct beam sunlight on $\geq$ 1/2 of the roof over the enclosed area for more than 1,500 daytime hours per year between 8 am and 4 pm. []- Exception 3:5.5.4.2.3: Spaces where the daylight zone under rooftop monitors is > 50 percent of the enclosed space floor area. []- Exception 4:5.5.4.2.3: Enclosed spaces where 90 percent of the skylight area is shaded on June 21 at noon by permanent architectural features of the building (documentation required). []- Exception 5:5.5.4.2.3: Enclosed spaces where the total area minus the primary and secondary sidelighted area(s) is less than 2500 ft² and where the lighting is controlled according to sidelighting requirements described in Section 9.4.1.1(e). []- Exception 6:5.5.4.2.3: Requirement does not apply.	☐ ☐ ☐
5063 HVAC	6.4.3.10	Mechanical	DDC system installed and capable of and configured to provide control logic including monitoring zone and system demand for fan pressure, pump pressure, heating, and cooling; transferring zone and system demand information from zones to air distribution system controllers and from air distribution systems to heating and cooling plant controllers; automatically detecting and alerting system operator when zones and systems excessively drive the reset logic; allow operator removal of zone(s) from the reset algorithm; AND capable of trending and graphically displaying input and output points. []- Exception 1:6.4.3.10: DDC is not required for systems using the simplified approach to compliance in accordance with Section 6.3 []- Exception 2:6.4.3.10: Requirement does not apply.	☐ ☐ ☐

5121 HVAC	6.4.3.3.2	Mechanical	Setback controls allow automatic restart and temporary operation as required for maintenance. ☐- Exception 1:6.4.3.3.2: Radiant floor and ceiling heating systems with heat setback $\geq$ 4F below occupied heating setpoint. ☐- Exception 2:6.4.3.3.2: Systems designed for continuous operation. ☐- Exception 3:6.4.3.3.2: Systems with capacity <15,000 Btu/h and with manual controls.	☐	☐	☐
5122 HVAC	6.4.3.3.3	Mechanical	Systems with setback controls and DDC include optimum start controls. Optimum start algorithm considers mass radiant slab floor temperature. ☐- Exception 1:6.4.3.3.3: Systems designed for continuous operation. ☐- Exception 2:6.4.3.3.3: Systems with capacity <15,000 Btu/h and with manual controls.	☐	☐	☐
5123 HVAC	6.4.3.3.4	Mechanical	Zone isolation devices and controls. ☐- Exception 1:6.4.3.3.4: Exhaust and outdoor air connections having fan systems 5000 cfm or smaller. ☐- Exception 2:6.4.3.3.4: Exhaust airflow less than 10% of design. ☐- Exception 3:6.4.3.3.4: Zones and systems intended to operate continuously or are inoperative when all other zones are inoperative. ☐- Exception 4:6.4.3.3.4: Systems with capacity <15,000 Btu/h and with manual controls.	☐	☐	☐
5165 Controls	6.4.3.3.5	Mechanical	Hotels/motel w/ > 50 guest rooms have automatic controls for the HVAC equipment serving each room configured per Section 6.4.3.3.5 subsections 1-3. ☐- Exception 1:6.4.3.3.5: Requirement does not apply.	☐	☐	☐
5036 HVAC	6.4.3.4.4	Mechanical	Ventilation fans > 0.75 hp have automatic controls to shut off fan when not required. ☐- Exception 1:6.4.3.4.4: HVAC systems intended to operate continuously.	☐	☐	☐

5037 HVAC	6.4.3.8	Mechanical	Demand control ventilation provided for spaces <500 ft2 and <25 people/1000 ft2 occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow <3,000 cfm. []- Exception 1:6.4.3.8: Systems with heat recovery. []- Exception 2:6.4.3.8: Multiple-zone systems without DDC of individual zones communicating with a central control panel. []- Exception 3:6.4.3.8: Systems with a design outdoor airflow less than 750 cfm. []- Exception 4:6.4.3.8: Spaces where 75 percent of the supply outdoor airflow is required for makeup air that is exhausted from the space or transfer air required for makeup air that is exhausted from the space(s). []- Exception 5:6.4.3.8: Space is one of following occupancy type: Correctional cells, daycare sickrooms, science labs, laboratories, beauty and nail salons, and bowling alley seating.	☐	☐	☐
5054 HVAC	6.5.2.3	Mechanical	Dehumidification controls provided to prevent reheating, recooling, mixing of hot and cold airstreams or concurrent heating and cooling of the same airstream. []- Exception 1:6.5.2.3: Capability of first reducing supply air volume 50% or less of the design rate or minimum outdoor air ventilation, or per regulatory standard, whichever is larger, before combined heating/cooling occurs. []- Exception 2:6.5.2.3: Cooling capacity <65 kBtu/h and capability to unload cooling equipment. []- Exception 3:6.5.2.3: Cooling capacity <40 kBtu/h. []- Exception 4:6.5.2.3: Rigid humidity requirements. []- Exception 5:6.5.2.3: Site-recovered or site-solar energy sources or. []- Exception 6:6.5.2.3: Use of a desiccant systems.	☐	☐	☐

5061 HVAC	6.5.3.1.3	Mechanical	Fan have a fan energy index (FEI) ≥ 1.00 and a variable-air-volume system that meets the requirements of Section 6.5.3.2.1 shall have an FEI ≥ 0.95 at the design point of operation. []- Exception 1:6.5.3.1.3: Embedded fans with a motor nameplate horsepower of less than 1.0 hp or with a fan nameplate electrical input power of less than 0.89 kW. []- Exception 2:6.5.3.1.3: Individual fans with motor nameplate horsepower of ≤ 5 hp. []- Exception 3:6.5.3.1.3: Multiple fans in series or parallel have a combined motor nameplate horsepower of ≤ 5 hp and are operated functionally as a single fan. []- Exception 4:6.5.3.1.3: Fans integral to equipment listed under Section 6.4.1.1. []- Exception 5:6.5.3.1.3: Ceiling fans. []- Exception 6:6.5.3.1.3: Fans included in equipment having certified seal for air or energy performance of the equipment package. []- Exception 7:6.5.3.1.3: Powered wall/roof ventilators (PRV). []- Exception 8:6.5.3.1.3: Fans not covered by AMCA 205. []- Exception 9:6.5.3.1.3: Fans operate during emergency conditions.	☐	☐	☐
5038 HVAC	6.5.3.2.1	Mechanical	DX cooling systems ≥ 65 kBtu/h and chilled-water and evaporative cooling fan motor hp $\geq \frac{1}{4}$ designed to vary supply fan airflow as a function of load and comply with operational requirements. []- Exception 1:6.5.3.2.1: Chilled-water and evaporative cooling units with < 1 hp fan motors not used to provide ventilation air and the indoor fan cycles with the load. []- Exception 2:6.5.3.2.1: Minimum speed requirements of Standard 62.1 will be applied. []- Exception 3:6.5.3.2.1: Requirement does not apply.	☐	☐	☐
5065 HVAC	6.5.3.2.3	Mechanical	Reset static pressure setpoint for DDC controlled VAV boxes reporting to central controller based on the zones requiring the most pressure. Controls provide: zone damper monitoring or indicator of static pressure need; autodetection, alarm, and operator override of zones excessively triggering reset logic.	☐	☐	☐

5066 HVAC	6.5.3.3	Mechanical	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls. []- Exception 1:6.5.3.3: VAV systems that recirculate air from other zones without directly mixing it with outdoor air or dual-duct dual-fan VAV systems, or VAV systems with fan-powered terminal units. []- Exception 2:6.5.3.3: Systems where the design exhaust airflow is more than 70% of design outdoor air intake flow. []- Exception 3:6.5.3.3: Requirement does not apply.	☐	☐	☐
5067 HVAC	6.5.3.5	Mechanical	Multiple zone HVAC systems have supply air temperature reset controls. []- Exception 1:6.5.3.5: Systems that do not reheat, recool, or mix heated and cooled supply air. []- Exception 2:6.5.3.5: Systems that use site recovered or site solar energy for at least 75% of the energy for reheating (on an annual basis). []- Exception 3:6.5.3.5: Requirement does not apply. []- Exception 4:6.5.3.5: Systems in Climate Zones 0A, 1A, and 3A with less than 3000 cfm of design outdoor air. []- Exception 5:6.5.3.5: Systems in Climate Zone 2A with less than 10,000 cfm of design outdoor air. []- Exception 6:6.5.3.5: Systems in Climate Zones 0A, 1A, 2A, and 3A with at least 80% outdoor air and employing exhaust air energy recovery complying with Section 6.5.6.1.	☐	☐	☐
5068 HVAC	6.5.4.1	Mechanical	System turndown requirement met through multiple single-input boilers, one or more modulating boilers, or a combination of single-input and modulating boilers. Boiler input between 1.0 MBtu/h and 5 MBtu/h has 3:1 turndown ratio, boiler input between 5.0 MBtu/h and 10 MBtu/h has 4:1 turndown ratio, boiler input > 10.0 MBtu/h has 5:1 turndown ratio.	☐	☐	☐

5069 HVAC	6.5.4.2	Mechanical	HVAC pumping systems with ≥ 3 control valves designed for variable fluid flow (see section details). []- Exception 1:6.5.4.2: Differential pressure set-point reset is not required where valve position is used to comply with Section 6.5.4.4. []- Exception 2:6.5.4.2: Variable-pump flow control not required on heating-water pumps where more than 50% of annual heat is generated by an electric boiler. []- Exception 3:6.5.4.2: Variable flow not required for primary pumps in a primary/secondary system. []- Exception 4:6.5.4.2: Variable flow not required for a coil pump provided for freeze protection. []- Exception 5:6.5.4.2: Variable flow not required for heat recovery coil runaround loops. []- Exception 6:6.5.4.2: Requirement does not apply.	☐	☐	☐
5070 HVAC	6.5.4.3, 6.5.4.3.1, 6.5.4.3.2	Mechanical	Fluid flow shutdown in pumping systems to multiple chillers or boilers when systems are shut down. []- Exception 1:6.5.4.3_6.5.4.3.1_6.5.4.3.2: with Section 6.5.4.4.	☐	☐	☐
5071 HVAC	6.5.4.4	Mechanical	Temperature reset by representative building loads for chiller and boiler systems design capacity $>300,000$ Btu/h. []- Exception 1:6.5.4.4: Where chilled-water supply is already cold, such as chilled water supplied from a district cooling or thermal energy storage system, such that blending would be required to achieve the reset chilled-water supply temperature. []- Exception 2:6.5.4.4: Where a specific temperature is required for a process application. []- Exception 3:6.5.4.4: Water temperature reset is not required where valve position is used to comply with Section 6.5.4.2.	☐	☐	☐
5072 HVAC	6.5.4.5.1	Mechanical	Two-position automatic valve interlocked to shut off water flow when the compressor is off. []- Exception 1:6.5.4.5.1: Units employing a fluid economizer.	☐	☐	☐
5073 HVAC	6.5.4.5.2	Mechanical	Hydronic heat pumps and water-cooled unitary air conditioners with pump systems >5 hp have controls or devices to reduce pump motor demand. []- Exception 1:6.5.4.5.2: Requirement does not apply.	☐	☐	☐

5075 HVAC	6.5.5.2.1	Mechanical	Fan systems with motors or array of motors (including the motor service factor) with connected power totaling ≥ 5 hp associated with heat rejection equipment to have controls and/or devices that result in fanmotor demand of $\leq 30\%$ of design wattage at 50% of design airflow and automatically modulates fan speed to control the leaving fluid temperature or condensing temp/pressure of heat rejection device. []- Exception 1:6.5.5.2.1: Condenser fans serving multiple refrigerant or fluid cooling circuits. []- Exception 2:6.5.5.2.1: Condenser fans serving flooded condensers.	☐	☐	☐
5076 HVAC	6.5.5.2.2	Mechanical	Multicell heat rejection equipment with variable-speed fan drives installed that operate the maximum number of fans allowed that comply with manufacturers specs and control all fans to the same fan speed required for the instantaneous cooling duty.	☐	☐	☐
5080 HVAC	6.5.7.1	Mechanical	Conditioned supply air to space with mechanical exhaust $\leq$ the greater of criteria of supply flow, required ventilation rate, exhaust flow minus the available transfer air (see section details). []- Exception 1:6.5.7.1: Biosafety level ≥ 3. []- Exception 2:6.5.7.1: Vivarium spaces. []- Exception 3:6.5.7.1: Spaces with regulated positive pressure air flows. []- Exception 4:6.5.7.1: Requirement does not apply.	☐	☐	☐
5081 HVAC	6.5.7.2.1	Mechanical	Replacement air introduced directly into the hood cavity of kitchen exhaust hoods shall not exceed 10% of the hood exhaust airflow rate []- Exception 1:6.5.7.2.1: Where hoods are used to exhaust ventilation air that would otherwise exfiltrate or be exhausted by other fan systems. []- Exception 2:6.5.7.2.1: Certified grease extractor hoods that require a face velocity no greater than 60 fpm. []- Exception 3:6.5.7.2.1: Requirement does not apply.	☐	☐	☐
5082 HVAC	6.5.7.2.2	Mechanical	Kitchen hoods with a total exhaust airflow rate > 5000 cfm meet replacement air, ventilation system, or energy recovery requirements shown in Table 6.5.7.2.2. []- Exception 1:6.5.7.2.2: Systems where transfer air that would otherwise be exhausted is used for at least 75% of all the replacement air. []- Exception 2:6.5.7.2.2: Requirement does not apply.	☐	☐	☐
5083 HVAC	6.5.7.2.3	Mechanical	Kitchen hoods with a total exhaust airflow rate > 5000 cfm meet replacement air, ventilation system, or energy recovery requirements. []- Exception 1:6.5.7.2.3: Requirement does not apply.	☐	☐	☐
5085 HVAC	6.5.7.3	Mechanical	Fume hoods exhaust systems $\geq 5,000$ cfm have VAV hood exhaust and supply systems, direct make-up air or heat recovery. []- Exception 1:6.5.7.2: Requirement does not apply.	☐	☐	☐

5086 HVAC	6.5.8.1	Mechanical	Unenclosed spaces that are heated use only radiant heat. []- Exception 1:6.5.8.1: Loading docks with air curtains. []- Exception 2:6.5.8.1: Requirement does not apply.	☐ ☐ ☐
5164 Other Equipment	6.8.1-14	Mechanical	Vapor compression based indoor pool dehumidifiers (single package (indoor air/water cooled or w/out air-cooled condenser) or split system indoor air-cooled) must meet the minimum efficiency rating. []- Exception 1:6.8.1-14: Requirement does not apply.	☐ ☐ ☐
5091 HVAC	7.5.1	Mechanical	Combined space and water heating system not allowed unless standby loss less than calculated maximum. AHJ has approved or combined connected load <150 kBtu/h.	☐ ☐ ☐
5159 Controls	9.4.1.2a	Interior Lighting	Parking garage lighting is equipped with automatic shutoff controls per Section 9.4.1.1(i). []- Exception 1:9.4.1.2a: Requirement does not apply.	☐ ☐ ☐
5160 Controls	9.4.1.2b	Interior Lighting	Parking garage luminarie power is automatically reduced by at least 50% when zone < 3600 ft2 has no occupancy after 10 minutes. []- Exception 1:9.4.1.2b: Requirement does not apply.	☐ ☐ ☐
5161 Controls	9.4.1.2c	Interior Lighting	Parking garage luminaries in or around covered entrances/exits between building and garage automatically reduced no more than the general light level from sunset to sunrise. []- Exception 1:9.4.1.2c: Requirement does not apply.	☐ ☐ ☐
5162 Controls	9.4.1.2d	Interior Lighting	Parking garage power to any luminaire within 20 ft of perimeter wall openings totaling at least 24 ft2 shall be automatically reduced through continuous dimming in response to available daylight. []- Exception 1:9.4.1.2d: Lighting in non-parking daylight transition areas. []- Exception 2:9.4.1.2d: Requirement does not apply.	☐ ☐ ☐
5158 Controls	9.4.1.4d	Exterior Lighting	Outdoor parking area luminaires > 78W and <= 24 ft height controlled to reduce wattage by 50% when area unoccupied over 15 minutes. Controlled power limited to <= 1500W. []- Exception 1:9.4.1.4d: Covered vehicle entrance/exit areas requiring lighting for safety, security and eye adaptation. []- Exception 2:9.4.1.4d: Manufacturer installed luminaires integral to signage. []- Exception 3:9.4.1.4d: Requirement does not apply.	☐ ☐ ☐
5157 Wattage	9.4.3	Interior Lighting	At least 75% of all permanently installed lighting fixtures in dwelling units have >= 55 lm/W efficacy or a >= 45 lm/W total luminaire efficacy.	☐ ☐ ☐

5006 Plan Review	9.7	Exterior Lighting	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the exterior lighting and electrical systems and equipment and document where exceptions to the standard are claimed. Information provided should include exterior lighting power calculations, wattage of bulbs and ballasts, transformers and control devices.	☐	☐	☐
3. To be checked by Inspector						
5008 Insulation	4.2.4	Envelope	Installed below-grade wall insulation type and R-value consistent with insulation specifications reported in plans.	☐	☐	☐
5010 Insulation	4.2.4	Envelope	Installed slab-on-grade insulation type and R-value consistent with insulation specifications reported in plans.	☐	☐	☐
5102 Insulation	4.2.4	Envelope	Installed roof insulation type and R-value consistent with insulation specifications reported in plans. For some ceiling systems, verification may need to occur during Framing Inspection.	☐	☐	☐
5104 Insulation	4.2.4	Envelope	Installed above-grade wall insulation type and R-value consistent with insulation specifications reported in plans.	☐	☐	☐
5106 Insulation	4.2.4	Envelope	Installed floor insulation type and R-value consistent with insulation specifications reported in plans.	☐	☐	☐
5017 Air Leakage	5.4.3.1	Envelope	Continuous air barrier is wrapped, sealed, caulked, gasketed, and/or taped in an approved manner, except in semiheated spaces in climate zones 1-6. []- Exception 1:5.4.3.1: Single wythe concrete masonry buildings in climate zone 2B. []- Exception 2:5.4.3.1: Requirement does not apply.	☐	☐	☐
5116 Air Leakage	5.4.3.2	Envelope	Weatherseals installed on all loading dock cargo doors in Climate Zones 4-8. []- Exception 1:5.4.3.3: Requirement does not apply.	☐	☐	☐
5108 Insulation	5.8.1.1	Envelope	Building envelope insulation is labeled with R-value or insulation certificate has been provided listing R-value and other relevant data.	☐	☐	☐
5009 Insulation	5.8.1.2	Envelope	Below-grade wall insulation installed per manufacturer's instructions.	☐	☐	☐
5011 Insulation	5.8.1.2	Envelope	Slab edge insulation installed per manufacturer's instructions.	☐	☐	☐
5105 Insulation	5.8.1.2	Envelope	Above-grade wall insulation installed per manufacturer's instructions.	☐	☐	☐
5107 Insulation	5.8.1.2	Envelope	Floor insulation installed per manufacturer's instructions.	☐	☐	☐
5103 Insulation	5.8.1.2, 5.8.1.3	Envelope	Roof insulation installed per manufacturer's instructions. Blown or poured loose-fill insulation is installed only where the ceiling slope is > 3:12.	☐	☐	☐

5110 Insulation	5.8.1.4	Envelope	Eaves are baffled to deflect air to above the insulation.	☐	☐	☐
5111 Insulation	5.8.1.5	Envelope	Insulation is installed in substantial contact with the inside surface separating conditioned space from unconditional space. []- Exception 1:5.8.1.5: Insulation materials rely on air spaces adjacent to reflective surfaces in order to achieve rated performance.	☐	☐	☐
5112 Insulation	5.8.1.6	Envelope	Recessed equipment installed in building envelope assemblies does not compress the adjacent insulation.	☐	☐	☐
5013 Insulation	5.8.1.7	Envelope	Exterior insulation protected against damage, sunlight, moisture, wind, landscaping and equipment maintenance activities.	☐	☐	☐
5113 Insulation	5.8.1.7.1	Envelope	Attics and mechanical rooms have insulation protected where adjacent to attic or equipment access.	☐	☐	☐
5114 Insulation	5.8.1.7.2	Envelope	Foundation vents do not interfere with insulation.	☐	☐	☐
5115 Insulation	5.8.1.8	Envelope	Insulation intended to meet the roof insulation requirements cannot be installed on top of a suspended ceiling. Mark this requirement compliant if insulation is installed accordingly.	☐	☐	☐
5109 Insulation	5.8.1.9	Envelope	Building envelope insulation extends over the full area of the component at the proposed rated R or U value.	☐	☐	☐
5025 Fenestration	5.8.2.1, 5.8.2.3, 5.8.2.4, 5.8.2.5	Envelope	Fenestration products rated (U-factor, SHGC, and VT) in accordance with NFRC or energy code defaults are used.	☐	☐	☐
5026 Fenestration	5.8.2.2	Envelope	Fenestration and door products are labeled, or a signed and dated certificate listing the U-factor, SHGC, VT, and air leakage rate has been provided by the manufacturer.	☐	☐	☐
5018 Air Leakage	5.8.3.2	Envelope	Factory-built and site-assembled fenestration and doors are labeled or certified as meeting air leakage requirements. []- Exception 1:5.8.3.2: Field fabricated. []- Exception 2:5.8.3.2: Metal coiling doors in semiheated spaces in zones 1-6 when leakage is <= 1.0 CFM/ft2. []- Exception 3:5.8.3.2: Building complies with whole building air leakage rate of 0.4 cfm/sq.ft.	☐	☐	☐
5146 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7a	Mechanical	Heat Rejection Equipment - Propeller or Axial Fan Open-Circuit Cooling Tower: Minimum Efficiency Requirement >=40.2 gpm/hp .	☐	☐	☐
5147 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7a	Mechanical	Heat Rejection Equipment - Centrifugal Fan Open-Circuit Cooling Tower: Minimum Efficiency Requirement >=20.0 gpm/hp.	☐	☐	☐
5148 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7b	Mechanical	Heat Rejection Equipment - Propeller or Axial Fan Closed-Circuit Cooling Tower: Minimum Efficiency Requirement >=16.1 gpm/hp.	☐	☐	☐

5149 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7b	Mechanical	Heat Rejection Equipment - Centrifugal Fan Closed-Circuit Cooling Tower: Minimum Efficiency Requirement ≥ 7.0 gpm/hp	☐	☐	☐
5173 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7c	Mechanical	Heat Rejection Equipment - Propeller or Axial Fan Dry Coolers (air-cooled fluid coolers): Minimum Efficiency Requirement ≥ 4.5 gpm/hp	☐	☐	☐
5151 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7g	Mechanical	Heat Rejection Equipment - Air-Cooled Condensers: Minimum Efficiency Requirement ≥ 176 kBtu/h-hp	☐	☐	☐
5152 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7g	Mechanical	Heat Rejection Equipment - Propeller or Axial Evaporative Condenser: Minimum Efficiency Requirement ≥ 160 kBtu/h-hp w/ R-448A test fluid.	☐	☐	☐
5153 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7g	Mechanical	Heat Rejection Equipment - Propeller or Axial Evaporative Condenser: Minimum Efficiency Requirement ≥ 134 kBtu/h-hp w/ Ammonia test fluid.	☐	☐	☐
5154 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7g	Mechanical	Heat Rejection Equipment - Centrifugal Evaporative Condenser: Minimum Efficiency Requirement ≥ 137 kBtu/h-hp w/ R-448A test fluid.	☐	☐	☐
5155 SYSTEM_SPECIF	6.4.1.1, 6.8.1-7g	Mechanical	Heat Rejection Equipment - Centrifugal Evaporative Condenser: Minimum Efficiency Requirement ≥ 110 kBtu/h-hp w/ Ammonia test fluid.	☐	☐	☐
5031 HVAC	6.4.1.4, 6.4.1.5	Mechanical	HVAC equipment efficiency verified. Non-NAECA HVAC equipment labeled as meeting 90.1.	☐	☐	☐
5144 SYSTEM_SPECIF	6.4.1.4, 6.4.1.5	Mechanical	Equipment minimum efficiency:	☐	☐	☐
5145 SYSTEM_SPECIF	6.4.1.4, 6.4.1.5	Mechanical	Equipment minimum efficiency:	☐	☐	☐
5032 HVAC	6.4.1.6.2	Mechanical	PTAC and PTHP with sleeves 16 in. by 42 in. labeled for replacement only. []- Exception 1:6.4.1.5.2: Requirement does not apply.	☐	☐	☐
5117 HVAC	6.4.3.1.1	Mechanical	Heating and cooling to each zone is controlled by a thermostat control. []- Exception 1:6.4.3.1.1: Perimeter systems with one control for each exposure and with the thermostat located within the zones served.	☐	☐	☐
5118 HVAC	6.4.3.1.2	Mechanical	Thermostatic controls have a 5 °F deadband. []- Exception 1:6.4.3.1.2: Thermostats requiring manual changeover between heating and cooling. []- Exception 2:6.4.3.1.2: Where wide temperature ranges are not acceptable and are approved by the authority having jurisdiction. []- Exception 3:6.4.3.1.2: Requirement does not apply.	☐	☐	☐
5050 HVAC	6.4.3.11.1	Mechanical	Electric motor driven chilled-water plants have measurement devices installed and measure the electricity use and efficiency []- Exception 1:6.4.3.11.1: Requirement does not apply.	☐	☐	☐

5051 HVAC	6.4.3.11.2	Mechanical	Electricity use and efficiency are trended every 15 minutes and graphically displayed, including hourly, daily, monthly, and annual data. Data are preserved for 36 months or more. []- Exception 1:6.4.3.11.2: Requirement does not apply.	☐ ☐ ☐
5125 HVAC	6.4.3.12	Mechanical	Air economizer has a fault detection and diagnostics (FDD) system (see details for configuration and operational requirements). []- Exception 1:6.4.3.12: Requirement does not apply.	☐ ☐ ☐
5119 HVAC	6.4.3.2	Mechanical	Temperature controls have setpoint overlap restrictions. []- Exception 1:9.4.3: Lighting is controlled by dimmers or automatic control devices. []- Exception 2:9.4.3: Hotel/motel guest rooms.	☐ ☐ ☐
5120 HVAC	6.4.3.3.1	Mechanical	HVAC systems equipped with at least one automatic shutdown control. []- Exception 1:6.4.3.3.1: Controls for residential occupancies may start and stop the system under two schedules per week. []- Exception 2:6.4.3.3.1: Systems designed for continuous operation. []- Exception 3:6.4.3.3.1: Systems with capacity <15,000 Btu/h and with manual controls.	☐ ☐ ☐
5033 HVAC	6.4.3.4.1	Mechanical	Stair and elevator shaft vents have motorized dampers that automatically close. []- Exception 1:6.4.3.4.1: Requirement does not apply.	☐ ☐ ☐
5034 HVAC	6.4.3.4.2, 6.4.3.4.3	Mechanical	Outdoor air and exhaust systems have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Check gravity dampers where allowed. []- Exception 1:6.4.3.4.2_6.4.3.4.3: Ventilation systems serving unconditioned spaces. []- Exception 2:6.4.3.4.2_6.4.3.4.3: Gravity dampers acceptable in buildings <3 stories. []- Exception 3:6.4.3.4.2_6.4.3.4.3: Outdoor air intakes and exhaust and relief dampers in buildings of any height located in Climate Zones 0, 1, 2, and 3. []- Exception 4:6.4.3.4.2_6.4.3.4.3: Gravity dampers acceptable in systems with outside or exhaust air flow rates less than 300 cfm where dampers are interlocked with fan. []- Exception 5:6.4.3.4.2_6.4.3.4.3: Exhaust systems serving Type 1 kitchen exhaust hoods []- Exception 6:6.4.3.4.2_6.4.3.4.3: Systems intended to operate continuously	☐ ☐ ☐

5035 HVAC	6.4.3.4.5	Mechanical	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity. []- Exception 1:6.4.3.4.5: Garages with no mechanical cooling or heating that have an area of less than 30,000 ft2. []- Exception 2:6.4.3.4.5: Garages with no mechanical cooling or heating that have a ratio of garage area to ventilation system motor nameplate hp greater than 1500 ft2/hp. []- Exception 3:6.4.3.4.5: Where the authority having jurisdiction does not allow this requirement. []- Exception 4:6.4.3.4.5: Requirement does not apply.	☐	☐	☐
5124 HVAC	6.4.3.5	Mechanical	Heat pump controls prevent supplemental electric resistance heat from coming on when not needed. []- Exception 1:6.4.3.5: Heat pumps regulated by and meeting NAECA requirements and using internal electric resistance heating.	☐	☐	☐
5126 HVAC	6.4.3.6	Mechanical	When humidification and dehumidification are provided to a zone, simultaneous operation is prohibited. Humidity control prohibits the use of fossil fuel or electricity to produce RH > 30% in the warmest zone humidified and RH < 60% in the coldest zone dehumidified. []- Exception 1:6.4.3.6: Zones served by desiccant systems. []- Exception 2:6.4.3.6: Systems in zones requiring specific humidity levels as approval by AHJ.	☐	☐	☐
5015 HVAC	6.4.3.7	Mechanical	Freeze protection and snow/ice melting system sensors for future connection to controls. []- Exception 1:6.4.3.7: Requirement does not apply.	☐	☐	☐
5088 HVAC	6.4.3.9	Mechanical	Heating for vestibules and air curtains with integral heating include automatic controls that shut off the heating system when outdoor air temperatures > 45°F. Vestibule heating and cooling systems controlled by a thermostat in the vestibule with heating setpoint ≤ 60°F and cooling setpoint ≥ 80°F. []- Exception 1:6.4.3.9: Heating/cooling provided by site-recovered energy or with transfer air that would otherwise be exhausted. []- Exception 2:6.4.3.9: Requirement does not apply.	☐	☐	☐
5039 HVAC	6.4.4.1.1	Mechanical	Insulation exposed to weather protected from damage. Insulation outside of the conditioned space and associated with cooling systems is vapor retardant.	☐	☐	☐

5040 HVAC	6.4.4.1.2	Mechanical	HVAC ducts and plenums insulated per Table 6.8.2. Where ducts or plenums are installed in or under a slab, verification may need to occur during Foundation Inspection. []- Exception 1:6.4.4.1.2: Factory-installed as part of HVAC equipment. []- Exception 2:6.4.4.1.2: Ducts/plenums located in heated, semi-heated, or cooled spaces. []- Exception 3:6.4.4.1.2: R-3.5 for runouts <10 ft to air terminals/outlets. []- Exception 4:6.4.4.1.2: Backs of air outlets or outlet plenums to unconditioned or indirectly condition spaces.	☐	☐	☐
5041 HVAC	6.4.4.1.3	Mechanical	HVAC piping insulation thickness. Where piping is installed in or under a slab, verification may need to occur during Foundation Inspection. []- Exception 1:6.4.4.1.3: Piping within HVAC equipment. []- Exception 2:6.4.4.1.3: Fluid temperatures between 60 and 105°F. []- Exception 3:6.4.4.1.3: Fluid not heated or cooled. []- Exception 4:6.4.4.1.3: Runouts <4 ft in length. []- Exception 5:6.4.4.1.3: Pipe unions in heating systems. []- Exception 6:6.4.4.1.3: Requirement does not apply.	☐	☐	☐
5042 HVAC	6.4.4.1.4	Mechanical	Thermally ineffective panel surfaces of sensible heating panels have insulation $\geq$ R-3.5. []- Exception 1:6.4.4.1.4: Requirement does not apply.	☐	☐	☐
5043 HVAC	6.4.4.2.1	Mechanical	Ducts and plenums having pressure class ratings are Seal Class A construction. []- Exception 1:6.4.4.2.1: Requirement does not apply.	☐	☐	☐
5044 HVAC	6.4.4.2.2	Mechanical	Ductwork operating >3 in. water column requires air leakage testing. []- Exception 1:6.4.4.2.2: Requirement does not apply.	☐	☐	☐
5089 Controls	6.5.10	Mechanical	Doors separating conditioned space from the outdoors have controls that disable/reset heating and cooling system when open. []- Exception 1:6.5.10: Building entrances have automatic closing devices. []- Exception 2:6.5.10: Space has no thermostat. []- Exception 3:6.5.10: Alteration project to existing building. []- Exception 4:6.5.10: Loading dock.	☐	☐	☐

5048 HVAC	6.5.2.1	Mechanical	Zone controls can limit reheating, recooling, simultaneous heating and cooling and sequence heating and cooling to each zone. []- Exception 1:6.5.2.1: Zones for which the volume of air that is reheated, recooled, or mixed is no greater than required to meet Standard 62.1; 20% of the zone design peak supply for systems with DDC and 30% for other systems; air flow rate approved by the AHJ; OR airflow rate []- Exception 2:6.5.2.1: Zones with DDC include: larger of <=20% zone peak flow, flow required per Standard 62.1, higher rate approved by AHJ for outlying conditions, OR airflow rate that complies with applicable codes/accreditation standards; air flow reheated/recooled/mixed <= []- Exception 3:6.5.2.1: 75% of the energy is provided from site-recovered or site-solar energy. []- Exception 4:6.5.2.1: Laboratory exhaust systems compliant with Section 6.5.7.3. []- Exception 5:6.5.2.1: Requirement does not apply.	☐	☐	☐
5049 HVAC	6.5.2.2.1	Mechanical	Three-pipe hydronic systems using a common return for hot and chilled water are not used.	☐	☐	☐
5052 HVAC	6.5.2.2.2	Mechanical	Two-pipe hydronic systems using a common distribution system have controls to allow a deadband >=15 °F, allow operation in one mode for at least 4 hrs before changeover, and have reset controls to limit heating and cooling supply temperature to <=30 °F.	☐	☐	☐
5055 HVAC	6.5.2.4.1	Mechanical	Humidifiers with airstream mounted preheating jackets have preheat auto-shutoff value set to activate when humidification is not required. []- Exception 1:6.5.2.4.1: Requirement does not apply.	☐	☐	☐
5056 HVAC	6.5.2.4.2	Mechanical	Humidification system dispersion tube hot surfaces in the airstreams of ducts or air-handling units insulated >= R-0.5. []- Exception 1:6.5.2.4.2: Mechanical cooling (including economizer operation) does not occur simultaneously with humidification. []- Exception 2:6.5.2.4.2: Requirement does not apply.	☐	☐	☐
5057 HVAC	6.5.2.5	Mechanical	Preheat coils controlled to stop heat output whenever mechanical cooling, including economizer operation, is active.	☐	☐	☐
5064 HVAC	6.5.3.2.2	Mechanical	VAV fans have static pressure sensors positioned so setpoint <=1.2 in. w.c. design pressure. []- Exception 1:6.5.3.2.2: Systems with DDC of individual boxes reporting to the central control panel and reset of static pressure setpoint based on the zone requiring the most pressure.	☐	☐	☐

5074 HVAC	6.5.4.6	Mechanical	Chilled-water and condenser water piping sized according to design flow rate and total annual hours of operation (Table 6.5.4.6). []- Exception 1:6.5.4.6: Design flow rates exceeding the values in Table 6.5.4.6 are allowed in specific sections of piping if the piping in question is not in the critical circuit at design conditions and is not predicted to be in the critical circuit during more than 30% of ope []- Exception 2:6.5.4.6: Piping systems that have equivalent or lower total pressure drop than the same system constructed with standard weight steel pipe with piping and fittings sized per Table 6.5.4.6.	☐	☐	☐
5150 SYSTEM_SPECIF	6.5.5.3	Mechanical	Centrifugal fan open-circuit cooling towers having combined rated capacity >= 1100 gpm meets minimum efficiency requirement: >=40.2 gpm/hp. []- Exception 1:6.5.5.3: Centrifugal open-circuit cooling towers with external sound attenuation or that have ducted inlet or discharge.	☐	☐	☐
5079 HVAC	6.5.6.2	Mechanical	Condenser heat recovery system that can heat water to 85 °F or provide 60% of peak heat rejection is installed for preheating of service hot water. []- Exception 1:6.5.6.2: Facility operates < 24/7. []- Exception 2:6.5.6.2: Total installed heat capacity of water cooled systems <= 6 MMBtu/h of heat rejection. []- Exception 3:6.5.6.2: Design SWH load <= 1 MMBtu/h. []- Exception 4:6.5.6.2: Facilities using condenser heat recovery for space heating with heat recovery exceeding 30% of the peak water-cooled condenser load. []- Exception 5:6.5.6.2: Facilities providing 60% of their service water heating from site-solar, site-recovered, or other energy sources.	☐	☐	☐
5084 HVAC	6.5.7.2.4	Mechanical	Approved field test used to evaluate design air flow rates and demonstrate proper capture and containment of kitchen exhaust systems. []- Exception 1:6.5.7.2.4: Requirement does not apply.	☐	☐	☐
5087 HVAC	6.5.9	Mechanical	Hot gas bypass limited to: <=240 kBtu/h – 15% ; > 240 kBtu/h – 10%	☐	☐	☐
5141 HVAC	7.4.3	Mechanical	All piping in recirculating system insulated []- Exception 1:7.4.3: Requirement does not apply.	☐	☐	☐
5142 HVAC	7.4.3	Mechanical	First 8 ft of outlet piping in nonrecirculating storage system, or branch piping connected to recirculated, heat traced, or impedance heated piping is insulated. []- Exception 1:7.4.3: Requirement does not apply.	☐	☐	☐
5143 HVAC	7.4.3	Mechanical	All heat traced or externally heated piping insulated []- Exception 1:7.4.3: Requirement does not apply.	☐	☐	☐

5028 HVAC	7.4.4.1	Mechanical	Temperature controls installed on service water heating systems ($\leq 120^{\circ}\text{F}$ to maximum temperature for intended use). []- Exception 1:7.4.4.1: Manufacturer's instructions specify a higher minimum setting.	☐	☐	☐
5029 HVAC	7.4.4.2	Mechanical	Automatic time switches installed to automatically switch off the recirculating hot-water system or heat trace when hot water is not required.	☐	☐	☐
5131 HVAC	7.4.4.3	Mechanical	Public lavatory faucet water temperature $\leq 110^{\circ}\text{F}$.	☐	☐	☐
5132 HVAC	7.4.4.4	Mechanical	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank.	☐	☐	☐
5133 HVAC	7.4.5.1	Mechanical	Pool heaters are equipped with on/off switch and no continuously burning pilot light. []- Exception 1:7.4.5.1: Requirement does not apply.	☐	☐	☐
5134 HVAC	7.4.5.2	Mechanical	Pool covers are provided for heated pools and pools heated to $>90^{\circ}\text{F}$ have a cover $\geq R-12$. []- Exception 1:7.4.5.2: Pools deriving $>60\%$ of the energy for heating from site-recovered. []- Exception 2:7.4.5.2: Requirement does not apply.	☐	☐	☐
5135 HVAC	7.4.5.3	Mechanical	Time switches are installed on all pool heaters and pumps. []- Exception 1:7.4.5.3: Where 24-hr pump operation required for public health. []- Exception 2:7.4.5.3: Solar and waste heat recovery pool heating require pumps. []- Exception 3:7.4.5.3: Requirement does not apply.	☐	☐	☐
5030 HVAC	7.4.6	Mechanical	Heat traps installed on non-circulating storage water tanks.	☐	☐	☐
5093 Controls	8.4.2	Project	At least 50% of all 125 volt 15- and 20-Amp receptacles are controlled by an automatic control device. []- Exception 1:8.4.2: Receptacles intended for 24 hour operation of equipment. []- Exception 2:8.4.2: Spaces where safety or security concerns prohibit automatic shutoff. []- Exception 3:8.4.2: Space type is not private office, open office, conference room, Copy/Print room, break room, or classroom []- Exception 4:8.4.2: Requirement does not apply.	☐	☐	☐

5163 Controls	8.4.3	Project	New buildings have electrical energy use measurement devices installed. Where tenant spaces exist, each tenant is monitored separately. In buildings with a digital control system the energy use is transmitted to to control system and displayed graphically. []- Exception 1:8.4.3: Buildings less than 25,000 ft2. []- Exception 2:8.4.3: Individual tenant spaces less than 10,000 ft2. []- Exception 3:8.4.3: Dwelling units. []- Exception 4:8.4.3: Residential buildings with less than 10,000 ft2 of common area. []- Exception 5:8.4.3: Critical and Equipment branches of NEC Article 517. []- Exception 6:8.4.3: Requirement does not apply.	☐	☐	☐
5138 Wattage	9.2.2.3	Interior Lighting	Interior installed lamp and fixture lighting power is consistent with what is shown on the approved lighting plans, demonstrating proposed watts are less than or equal to allowed watts.	☐	☐	☐
5094 Controls	9.4.1.1	Interior Lighting	Automatic control requirements prescribed in Table 9.6.1, for the appropriate space type, are installed. Mandatory lighting controls (labeled as 'REQ') and optional choice controls (labeled as 'ADD1' and 'ADD2') are implemented.	☐	☐	☐
5095 Controls	9.4.1.1	Interior Lighting	Independent lighting controls installed per approved lighting plans and all manual controls readily accessible and visible to occupants. []- Exception 1:9.4.1.1: Remote locations permitted for safety or security if used with a clearly labeled indicator pilot light.	☐	☐	☐
5096 Controls	9.4.1.1f	Interior Lighting	Daylight areas under skylights and roof monitors that have more than 150 W combined input power for general lighting are controlled by photocontrols. []- Exception 1:9.4.1.1f: Daylighted areas under skylights existing adjacent structures or natural objects block direct beam sunlight for more than 1500 daytime hours per year between 8 a.m. and 4 p.m. []- Exception 2:9.4.1.1f: Daylighted areas where the skylight VT is less than 0.006. []- Exception 3:9.4.1.1f: Buildings in climate zone 8 where the input power of the general lighting is less than 200W. []- Exception 4:9.4.1.1f: Requirement does not apply.	☐	☐	☐

5172 Controls	9.4.1.1g	Interior Lighting	Automatic partial OFF (full OFF complies) control requirements prescribed in Table 9.6.1, for the appropriate space type, are installed. Mandatory lighting controls (labeled as 'REQ') and optional choice controls (labeled as 'ADD1' and 'ADD2') are implemented. []- Exception 1:9.4.1.1g: The space has an installed LPD of no more than 0.80 W/ft2 []- Exception 2:9.4.1.1g: The space is lighted by HID lamp []- Exception 3:9.4.1.1g: The general lighting power in the space is automatically reduced by at least 30% within 20 minutes of all occupants leaving the space []- Exception 4:9.4.1.1g: Lighting load does not exceed 0.02 W/ft2 multiplied by the gross lighted floor area of the building []- Exception 5:9.4.1.1g: Requirement does not apply.	☐	☐	☐
5098 Controls	9.4.1.3	Interior Lighting	Separate lighting control devices for specific uses installed per approved lighting plans.	☐	☐	☐
5097 Controls	9.4.1.4	Exterior Lighting	Automatic lighting controls for exterior lighting installed. []- Exception 1:9.4.1.4: Covered vehicle entrance/exit areas requiring lighting for safety, security and eye adaptation.	☐	☐	☐
5139 Wattage	9.4.2	Exterior Lighting	Exterior lighting power is consistent with what is shown on the approved lighting plans, demonstrating proposed watts are less than or equal to allowed watts.	☐	☐	☐
5099 Wattage	9.6.2	Interior Lighting	Additional interior lighting power allowed for special functions per the approved lighting plans and is automatically controlled and separated from general lighting.	☐	☐	☐
5101 Wattage	9.6.4	Interior Lighting	Where space LPD requirements are adjusted based on room cavity ratios, dimensions are consistent with approved plans. []- Exception 1:9.6.4: Requirement does not apply.	☐	☐	☐
4. To be checked by Inspector at Project Completion and Prior to Issuance of Certificate of Occupancy						

5007 Plan Review	4.2.5.2	Mechanical	Commissioning shall be performed as stated in Sections 5.9.2, 6.9.2, 7.9.2, 8.9.2, 9.9.2, 10.9.2, 11.2(d), and G1.2.1(c). Commissioning must utilize ASHRAE/IES Standard 202 or other generally accepted engineering standards acceptable to the building official. FPT and verification requirements for commissioning are as stated in Section 4.2.5.1. Commissioning shall document compliance of the building systems, controls, and building envelope with required provisions of this standard. Commissioning requirements shall be incorporated into the construction documents. []- Exception 1:4.2.5.2: Buildings, additions, or alterations with less than 10,000 ft² of conditioned space and combined heating, cooling, and service water heating equipment totaling less than 960,000 Btu/h in capacity. []- Exception 2:4.2.5.2: Buildings or portions of buildings that use the Simplified Approach Option for HVAC Systems in Section 6.3. []- Exception 3:4.2.5.2: Dwelling units. []- Exception 4:4.2.5.2: Nonrefrigerated warehouses.	☐	☐	☐
5127 Post Construction	6.7.3.1	Mechanical	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	☐	☐	☐
5128 Post Construction	6.7.3.2	Mechanical	Furnished operation and maintenance manuals for HVAC systems within 90 days of system acceptance.	☐	☐	☐
5129 Post Construction	6.7.3.3	Mechanical	An air and/or hydronic system balancing report is provided for HVAC systems serving zones >5,000 ft² of conditioned area. []- Exception 1:6.7.3.3: Pumps with pump motors of less than or equal to 10 hp []- Exception 2:6.7.3.3: when throttling results in no greater than 5% of the nameplate horsepower draw, or 3 hp, whichever is greater, above that required if the impeller was trimmed []- Exception 3:6.7.3.3: Requirement does not apply.	☐	☐	☐
5136 Post Construction	8.7.1	Interior Lighting	Furnished as-built drawings for electric power systems within 90 days of system acceptance.	☐	☐	☐
5137 Post Construction	8.7.3	Interior Lighting	Furnished operation and maintenance instructions for systems and equipment to the building owner or designated representative.	☐	☐	☐

Certificate of Product Ratings

AHRI Certified Reference Number : 205967943 Date : 05-08-2024 Model Status : Active

AHRI Type : HRCU-A-CB-O (Mini-Split Heat Pump, with Remote Outdoor Unit Air-Source, Free Delivery)

Outdoor Unit Brand Name : CARRIER

Outdoor Unit Model Number : 38MVRAQ12AA1

Indoor Type : Mini-Splits (Non-Ducted)

Indoor Model Number(s) : DHMVHAQ12XA1

Rated as follows in accordance with the latest edition of AHRI 210/240 - 2017 with Addendum 1, Performance Rating of Unitary Air-Conditioning & Air-Source Heat Pump Equipment and subject to rating accuracy by AHRI-sponsored, independent, third party testing:

Cooling Capacity (A2) - Single or High Stage (95F), btuh : 12000

SEER : 16.50

EER (A2) - Single or High Stage (95F) : 8.80

Heating Capacity (H12) - Single or High Stage (47F) : 12000

HSPF (Region IV) : 9.40

Rated as follows in accordance with the latest edition of AHRI 210/240 – 2023, Performance Rating of Unitary Air-Conditioning & Air-Source Heat Pump Equipment and subject to rating accuracy by AHRI-sponsored, independent, third party testing:

Cooling Capacity (A_{Full}) – Single or High Stage (95F), btuh : 12000

SEER2 : 17.40

EER2 (A_{Full}) – Single or High Stage (95F) : 8.80

Heating Capacity (H1_{Full}) – Single or High Stage (47F), btuh : 12000

HSPF2 (Region IV) : 8.70

Sold in? : USA, Canada

AHRI CERTIFIED®
www.ahridirectory.org

?"Active" Model Status are those that an AHRI Certification Program Participant is currently producing AND selling or offering for sale; OR new models that are being marketed but are not yet being produced. ?Production Stopped? Model Status are those that an AHRI Certification Program Participant is no longer producing BUT is still selling or offering for sale.

Ratings that are accompanied by WAS indicate an involuntary re-rate. The new published rating is shown along with the previous (i.e. WAS) rating.

The Department of Energy has published updated energy efficiency metrics for central air conditioners and heat pumps. This publication reflects both the 1987 metric (SEER) and the 2023 metric (SEER2). Efficiency requirements are published at 10 C.F.R. 430.32(c). Please refer to www.AHRI.net.org for more information about updated energy efficiency metrics.

DISCLAIMER

AHRI does not endorse the product(s) listed on this Certificate and makes no representations, warranties or guarantees as to, and assumes no responsibility for, the product(s) listed on this Certificate. AHRI expressly disclaims all liability for damages of any kind arising out of the use or performance of the product(s), or the unauthorized alteration of data listed on this Certificate. Certified ratings are valid only for models and configurations listed in the directory at www.ahridirectory.org.

TERMS AND CONDITIONS

This Certificate and its contents are proprietary products of AHRI. This Certificate shall only be used for individual, personal and confidential reference purposes. The contents of this Certificate may not, in whole or in part, be reproduced; copied; disseminated; entered into a computer database; or otherwise utilized, in any form or manner or by any means, except for the user's individual, personal and confidential reference.

CERTIFICATE VERIFICATION

The information for the model cited on this certificate can be verified at www.ahridirectory.org, click on "Verify Certificate" link and enter the AHRI Certified Reference Number and the date on which the certificate was issued, which is listed above, and the Certificate No., which is listed at bottom right.

© 2024 Air-Conditioning, Heating, and Refrigeration Institute



we make life better™

CERTIFICATE NO.:

133596578514097929

Certificate of Product Ratings

AHRI Certified Reference Number : 210998951 Date : 05-08-2024 Model Status : Active

AHRI Type : HRCU-A-CB (Split System: Heat Pump with Remote Outdoor Unit-Air-Source)

Series : 15 SEER2 HP

Outdoor Unit Brand Name : BRYANT HEATING AND COOLING SYSTEMS

Outdoor Unit Model Number (Condenser or Single Package) : PH5SAN460**AA*

Indoor Unit Model Number (Evaporator and/or Air Handler) : PF4MN*D60L*

The manufacturer of this BRYANT HEATING AND COOLING SYSTEMS product is responsible for the rating of this system combination.

Rated as follows in accordance with the latest edition of AHRI 210/240 – 2023, Performance Rating of Unitary Air-Conditioning & Air-Source Heat Pump Equipment and subject to rating accuracy by AHRI-sponsored, independent, third party testing:

Cooling Capacity (A_{Full}) – Single or High Stage (95F), btuh : 57000

SEER2 : 14.30

EER2 (A_{Full}) – Single or High Stage (95F) : 12.00

Heating Capacity (H1_{Full}) – Single or High Stage (47F), btuh : 57000

HSPF2 (Region IV) : 7.50



?"Active" Model Status are those that an AHRI Certification Program Participant is currently producing AND selling or offering for sale; OR new models that are being marketed but are not yet being produced. ?Production Stopped? Model Status are those that an AHRI Certification Program Participant is no longer producing BUT is still selling or offering for sale.

Ratings that are accompanied by WAS indicate an involuntary re-rate. The new published rating is shown along with the previous (i.e. WAS) rating.

The Department of Energy has published updated energy efficiency metrics for central air conditioners and heat pumps. This publication reflects both the 1987 metric (SEER) and the 2023 metric (SEER2). Efficiency requirements are published at 10 C.F.R. 430.32(c). Please refer to www.AHRInet.org for more information about updated energy efficiency metrics.

DISCLAIMER

AHRI does not endorse the product(s) listed on this Certificate and makes no representations, warranties or guarantees as to, and assumes no responsibility for, the product(s) listed on this Certificate. AHRI expressly disclaims all liability for damages of any kind arising out of the use or performance of the product(s), or the unauthorized alteration of data listed on this Certificate. Certified ratings are valid only for models and configurations listed in the directory at www.ahridirectory.org.

TERMS AND CONDITIONS

This Certificate and its contents are proprietary products of AHRI. This Certificate shall only be used for individual, personal and confidential reference purposes. The contents of this Certificate may not, in whole or in part, be reproduced; copied; disseminated; entered into a computer database; or otherwise utilized, in any form or manner or by any means, except for the user's individual, personal and confidential reference.

CERTIFICATE VERIFICATION

The information for the model cited on this certificate can be verified at www.ahridirectory.org, click on "Verify Certificate" link and enter the AHRI Certified Reference Number and the date on which the certificate was issued, which is listed above, and the Certificate No., which is listed at bottom right.

© 2024 Air-Conditioning, Heating, and Refrigeration Institute




CERTIFICATE NO.:

133596581136352513



Sheet 1



Job #: Kingdom Culture Academy
Performed by John PirkI for:

Jarvis Heat & Air, LLC
2001 N.E. 31st Avenue
Gainesville, FL 32609
Phone: (352) 316 - 4573

New Age Dimensions, L.L.C.

14080 S.E. 122nd Lane Road
Ocklawaha, FL 32179
Phone: (352) 288 - 0686 Fax: (352) 288 - 0684
www.newagedimensions.webs.com john.newage@gmail.com

Scale: 1 : 187

Page 1
Right-Suite@ Universal 2023
23.0.05 RSU02050
2024-May-08 20:05:08
... LLC\Kingdom Culture Academy.rup

Project Name: Seth & Angel Shaw Street: City, State, Zip: , FL, Owner: Design Location: FL, Gainesville	Builder Name: Permit Office: Permit Number: Jurisdiction: County: Columbia(Florida Climate Zone 2)
--	---

<table style="width: 100%;"> <tr> <td style="width: 40%;">1. New construction or existing</td> <td style="width: 60%;">New (From Plans)</td> </tr> <tr> <td>2. Single family or multiple family</td> <td>Detached</td> </tr> <tr> <td>3. Number of units, if multiple family</td> <td>1</td> </tr> <tr> <td>4. Number of Bedrooms</td> <td>4</td> </tr> <tr> <td>5. Is this a worst case?</td> <td>No</td> </tr> <tr> <td>6. Conditioned floor area above grade (ft²)</td> <td>2240</td> </tr> <tr> <td>Conditioned floor area below grade (ft²)</td> <td>0</td> </tr> <tr> <td>7. Windows(266.0 sqft.)</td> <td>Description Area</td> </tr> <tr> <td>a. U-Factor:</td> <td>Dbl, U=0.26 266.00 ft²</td> </tr> <tr> <td>SHGC:</td> <td>SHGC=0.20</td> </tr> <tr> <td>b. U-Factor:</td> <td>N/A ft²</td> </tr> <tr> <td>SHGC:</td> <td></td> </tr> <tr> <td>c. U-Factor:</td> <td>N/A ft²</td> </tr> <tr> <td>SHGC:</td> <td></td> </tr> <tr> <td>Area Weighted Average Overhang Depth:</td> <td>5.289 ft</td> </tr> <tr> <td>Area Weighted Average SHGC:</td> <td>0.200</td> </tr> <tr> <td>8. Skylights</td> <td>Description Area</td> </tr> <tr> <td>U-Factor:(AVG)</td> <td>N/A N/A ft²</td> </tr> <tr> <td>SHGC(AVG):</td> <td>N/A</td> </tr> <tr> <td>9. Floor Types</td> <td>Insulation Area</td> </tr> <tr> <td>a. Slab-On-Grade Edge Insulation</td> <td>R= 0.0 2240.00 ft²</td> </tr> <tr> <td>b. N/A</td> <td>R= ft²</td> </tr> <tr> <td>c. N/A</td> <td>R= ft²</td> </tr> </table>	1. New construction or existing	New (From Plans)	2. Single family or multiple family	Detached	3. Number of units, if multiple family	1	4. Number of Bedrooms	4	5. Is this a worst case?	No	6. Conditioned floor area above grade (ft²)	2240	Conditioned floor area below grade (ft²)	0	7. Windows(266.0 sqft.)	Description Area	a. U-Factor:	Dbl, U=0.26 266.00 ft²	SHGC:	SHGC=0.20	b. U-Factor:	N/A ft²	SHGC:		c. U-Factor:	N/A ft²	SHGC:		Area Weighted Average Overhang Depth:	5.289 ft	Area Weighted Average SHGC:	0.200	8. Skylights	Description Area	U-Factor:(AVG)	N/A N/A ft²	SHGC(AVG):	N/A	9. Floor Types	Insulation Area	a. Slab-On-Grade Edge Insulation	R= 0.0 2240.00 ft²	b. N/A	R= ft²	c. N/A	R= ft²	<table style="width: 100%;"> <tr> <td style="width: 40%;">10. Wall Types(2110.5 sqft.)</td> <td style="width: 20%;">Insulation</td> <td style="width: 40%;">Area</td> </tr> <tr> <td>a. Frame - Wood, Exterior</td> <td>R=13.0</td> <td>2110.50 ft²</td> </tr> <tr> <td>b. N/A</td> <td></td> <td></td> </tr> <tr> <td>c. N/A</td> <td></td> <td></td> </tr> <tr> <td>d. N/A</td> <td></td> <td></td> </tr> <tr> <td>11. Ceiling Types(2240.0 sqft.)</td> <td>Insulation</td> <td>Area</td> </tr> <tr> <td>a. Flat ceiling under att (Vented)</td> <td>R=30.0</td> <td>2240.00 ft²</td> </tr> <tr> <td>b. N/A</td> <td></td> <td></td> </tr> <tr> <td>c. N/A</td> <td></td> <td></td> </tr> <tr> <td>12. Roof(Metal, Vented)</td> <td>Deck R=0.0</td> <td>2593 ft²</td> </tr> <tr> <td>13. Ducts, location & insulation level</td> <td>R</td> <td>ft²</td> </tr> <tr> <td>a. Sup: Attic, Ret: Attic, AH: Main</td> <td>6</td> <td>448</td> </tr> <tr> <td>b.</td> <td></td> <td></td> </tr> <tr> <td>c.</td> <td></td> <td></td> </tr> <tr> <td>14. Cooling Systems</td> <td>kBtu/hr</td> <td>Efficiency</td> </tr> <tr> <td>a. Central Unit</td> <td>36.0</td> <td>SEER2:15.00</td> </tr> <tr> <td>15. Heating Systems</td> <td>kBtu/hr</td> <td>Efficiency</td> </tr> <tr> <td>a. Electric Heat Pump</td> <td>36.0</td> <td>HSPF2:8.50</td> </tr> <tr> <td>16. Hot Water Systems</td> <td></td> <td></td> </tr> <tr> <td>a. Electric</td> <td></td> <td>Cap: 50 gallons</td> </tr> <tr> <td></td> <td></td> <td>EF: 0.920</td> </tr> <tr> <td>b. Conservation features</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>None</td> </tr> <tr> <td>17. Credits</td> <td></td> <td>CF, Pstat</td> </tr> </table>	10. Wall Types(2110.5 sqft.)	Insulation	Area	a. Frame - Wood, Exterior	R=13.0	2110.50 ft²	b. N/A			c. N/A			d. N/A			11. Ceiling Types(2240.0 sqft.)	Insulation	Area	a. Flat ceiling under att (Vented)	R=30.0	2240.00 ft²	b. N/A			c. N/A			12. Roof(Metal, Vented)	Deck R=0.0	2593 ft²	13. Ducts, location & insulation level	R	ft²	a. Sup: Attic, Ret: Attic, AH: Main	6	448	b.			c.			14. Cooling Systems	kBtu/hr	Efficiency	a. Central Unit	36.0	SEER2:15.00	15. Heating Systems	kBtu/hr	Efficiency	a. Electric Heat Pump	36.0	HSPF2:8.50	16. Hot Water Systems			a. Electric		Cap: 50 gallons			EF: 0.920	b. Conservation features					None	17. Credits		CF, Pstat
1. New construction or existing	New (From Plans)																																																																																																																						
2. Single family or multiple family	Detached																																																																																																																						
3. Number of units, if multiple family	1																																																																																																																						
4. Number of Bedrooms	4																																																																																																																						
5. Is this a worst case?	No																																																																																																																						
6. Conditioned floor area above grade (ft²)	2240																																																																																																																						
Conditioned floor area below grade (ft²)	0																																																																																																																						
7. Windows(266.0 sqft.)	Description Area																																																																																																																						
a. U-Factor:	Dbl, U=0.26 266.00 ft²																																																																																																																						
SHGC:	SHGC=0.20																																																																																																																						
b. U-Factor:	N/A ft²																																																																																																																						
SHGC:																																																																																																																							
c. U-Factor:	N/A ft²																																																																																																																						
SHGC:																																																																																																																							
Area Weighted Average Overhang Depth:	5.289 ft																																																																																																																						
Area Weighted Average SHGC:	0.200																																																																																																																						
8. Skylights	Description Area																																																																																																																						
U-Factor:(AVG)	N/A N/A ft²																																																																																																																						
SHGC(AVG):	N/A																																																																																																																						
9. Floor Types	Insulation Area																																																																																																																						
a. Slab-On-Grade Edge Insulation	R= 0.0 2240.00 ft²																																																																																																																						
b. N/A	R= ft²																																																																																																																						
c. N/A	R= ft²																																																																																																																						
10. Wall Types(2110.5 sqft.)	Insulation	Area																																																																																																																					
a. Frame - Wood, Exterior	R=13.0	2110.50 ft²																																																																																																																					
b. N/A																																																																																																																							
c. N/A																																																																																																																							
d. N/A																																																																																																																							
11. Ceiling Types(2240.0 sqft.)	Insulation	Area																																																																																																																					
a. Flat ceiling under att (Vented)	R=30.0	2240.00 ft²																																																																																																																					
b. N/A																																																																																																																							
c. N/A																																																																																																																							
12. Roof(Metal, Vented)	Deck R=0.0	2593 ft²																																																																																																																					
13. Ducts, location & insulation level	R	ft²																																																																																																																					
a. Sup: Attic, Ret: Attic, AH: Main	6	448																																																																																																																					
b.																																																																																																																							
c.																																																																																																																							
14. Cooling Systems	kBtu/hr	Efficiency																																																																																																																					
a. Central Unit	36.0	SEER2:15.00																																																																																																																					
15. Heating Systems	kBtu/hr	Efficiency																																																																																																																					
a. Electric Heat Pump	36.0	HSPF2:8.50																																																																																																																					
16. Hot Water Systems																																																																																																																							
a. Electric		Cap: 50 gallons																																																																																																																					
		EF: 0.920																																																																																																																					
b. Conservation features																																																																																																																							
		None																																																																																																																					
17. Credits		CF, Pstat																																																																																																																					

Glass/Floor Area: 0.119	Total Proposed Modified Loads: 52.17	PASS
	Total Baseline Loads: 57.74	

NOTE: Proposed residence must have annual total normalized Modified Loads that are less than or equal to 95 percent of the annual total loads of the standard reference design in order to comply.

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code. PREPARED BY: _____ DATE: _____ I hereby certify that this building, as designed, is in compliance with the Florida Energy Code. OWNER/AGENT: _____ DATE: _____	Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes. BUILDING OFFICIAL: _____ DATE: _____
--	--

- 2/23/2024 11:40:53 AM EnergyGauge® USA 8.0.00 - FlaRes2023 FBC 8th Edition (2023) Compliant Software Page 1

INPUT SUMMARY CHECKLIST REPORT

PROJECT

Title: Seth & Angel Shaw

Building Type: User

Owner:

Builder Home ID:

Builder Name:

Permit Office:

Jurisdiction:

Family Type: Detached

New/Existing: New (From Plans)

Year Construct: 2024

Comment:

Bedrooms: 4

Conditioned Area: 2240

Total Stories: 1

Worst Case: No

Rotate Angle: 0

Cross Ventilation:

Whole House Fan:

Terrain: Rural

Shielding: Moderate/Rural

Address type: Street Address

Lot #: ---

Block/SubDivision: ---

PlatBook: ---

Street:

County: Columbia

City, State, Zip: , FL,

CLIMATE

✓ Design Location

Tmy Site

Design Temp

97.5% 2.5%

Int Design Temp

Winter Summer

Heating Degree Days

Design Moisture

Daily temp Range

___ FL, Gainesville

FL_GAINESVILLE_REGIONA

32 92

70 75

1305.5

51

Medium

BLOCKS

✓ Number

Name

Area

Volume

___ 1

Block1

2240

20160 cu ft

SPACES

✓ Number

Name

Area

Volume

Kitchen

Occupants

Bedrooms

Finished

Cooled

Heated

___ 1

Main

2240

20160

Yes

8

4

Yes

Yes

Yes

FLOORS (Total Exposed Area = 2240 sq.ft.)

✓ #

Floor Type

Space

Exposed Perim(ft)

Area

R-Value Perim.

U-Factor Joist

Slab Insul. Vert/Horiz

Tile

Wood

Carpet

___ 1

Slab-On-Grade Edge Ins

Main

224

2240 sqft

0 ---

0.600

2 (ft)/0 (ft)

0.33

0.33

0.34

ROOF

✓ #

Type

Materials

Roof Area

Gable Area

Roof Color

Rad Barr

Solar Absor.

SA Tested

Emitt

Emitt Tested

Deck Insul.

Pitch (deg)

___ 1

Gable or shed

Metal

2593 ft²

654 ft²

Light

N

0.6

No

0.9

No

0

30.26

ATTIC

✓ #

Type

Ventilation

Vent Ratio (1 in)

Area

RBS

IRCC

___ 1

Full attic

Vented

300

2240 ft²

N

N

CEILING (Total Exposed Area = 2240 sq.ft.)

✓ #

Ceiling Type

Space

R-Value

Ins. Type

Area

U-Factor

Framing Frac.

Truss Type

___ 1

Flat ceiling under attic(Vented)

Main

30.0

Blown

2240.0ft²

0.053

0.11

Wood

INPUT SUMMARY CHECKLIST REPORT

WALLS																	(Total Exposed Area = 2111 sq.ft.)			
✓ #	Ornt	Adjacent To	Wall Type	Space	Cavity R-Value	Width Ft	In	Height Ft	In	Area sq.ft.	U-Factor	Sheath R-Value	Frm. Frac.	Solar Absor.	Below Grade					
___ 1	N	Exterior	Frame - Wood	Main	13.0	19.0	0	9.0	0	171.0	0.087	0.625	0.23	0.75	0 %					
___ 2	E	Exterior	Frame - Wood	Main	13.0	9.0	0	9.0	0	81.0	0.087	0.625	0.23	0.75	0 %					
___ 3	N	Exterior	Frame - Wood	Main	13.0	25.0	8	10.0	0	256.7	0.087	0.625	0.23	0.75	0 %					
___ 4	W	Exterior	Frame - Wood	Main	13.0	9.0	0	9.0	0	81.0	0.087	0.625	0.23	0.75	0 %					
___ 5	N	Exterior	Frame - Wood	Main	13.0	16.0	4	9.0	0	147.0	0.087	0.625	0.23	0.75	0 %					
___ 6	E	Exterior	Frame - Wood	Main	13.0	38.0	4	9.0	0	345.0	0.087	0.625	0.23	0.75	0 %					
___ 7	S	Exterior	Frame - Wood	Main	13.0	12.0	4	9.0	0	111.0	0.087	0.625	0.23	0.75	0 %					
___ 8	E	Exterior	Frame - Wood	Main	13.0	3.0	8	9.0	0	33.0	0.087	0.625	0.23	0.75	0 %					
___ 9	S	Exterior	Frame - Wood	Main	13.0	35.0	10	10.0	0	358.3	0.087	0.625	0.23	0.75	0 %					
___ 10	W	Exterior	Frame - Wood	Main	13.0	3.0	8	9.0	0	33.0	0.087	0.625	0.23	0.75	0 %					
___ 11	S	Exterior	Frame - Wood	Main	13.0	12.0	10	9.0	0	115.5	0.087	0.625	0.23	0.75	0 %					
___ 12	W	Exterior	Frame - Wood	Main	13.0	42.0	0	9.0	0	378.0	0.087	0.625	0.23	0.75	0 %					

DOORS												(Total Exposed Area = 100 sq.ft.)		
✓ #	Ornt	Adjacent To	Door Type	Space	Storms	U-Value	Width Ft	In	Height Ft	In	Area			
___ 1	N	Exterior	Insulated	Main	None	0.40	5.00	0	8.00	0	40.0ft²			
___ 2	W	Exterior	Insulated	Main	None	0.40	3.00	0	6.00	8	20.0ft²			
___ 3	S	Exterior	Insulated	Main	None	0.40	5.00	0	8.00	0	40.0ft²			

WINDOWS																	(Total Exposed Area = 266 sq.ft.)			
✓ #	Ornt	Wall ID	Frame	Panes	NFRC U-Factor	SHGC	Imp	Storm	Total Area (ft²)	Same Units	Width (ft)	Height (ft)	--Overhang-- Depth (ft)	Sep. (ft)	Interior Shade	Screen				
___ 1	N	3	Vinyl	Low-E Double	Y	0.26	0.20	N	N	49.0	2	3.50	7.00	10.5	2.3	None	None			
___ 2	N	3	Vinyl	Low-E Double	Y	0.26	0.20	N	N	15.0	2	2.50	3.00	10.5	2.3	None	None			
___ 3	N	5	Vinyl	Low-E Double	Y	0.26	0.20	N	N	18.0	3	3.00	2.00	1.5	2.3	None	None			
___ 4	E	6	Vinyl	Low-E Double	Y	0.26	0.20	N	N	30.0	2	3.00	5.00	1.5	2.3	None	None			
___ 5	E	6	Vinyl	Low-E Double	Y	0.26	0.20	N	N	6.0	1	2.00	3.00	1.5	2.3	None	None			
___ 6	S	7	Vinyl	Low-E Double	Y	0.26	0.20	N	N	20.0	2	2.00	5.00	1.5	2.3	None	None			
___ 7	S	9	Vinyl	Low-E Double	Y	0.26	0.20	N	N	72.0	4	3.00	6.00	7.5	2.3	None	None			
___ 8	S	11	Vinyl	Low-E Double	Y	0.26	0.20	N	N	20.0	2	2.00	5.00	1.5	2.3	None	None			
___ 9	W	12	Vinyl	Low-E Double	Y	0.26	0.20	N	N	36.0	2	3.00	6.00	1.5	2.3	None	None			

INFILTRATION										
✓ #	Scope	Method	SLA	CFM50	ELA	EqLA	ACH	ACH50	Space(s)	Infiltration Test Volume
___ 1	Wholehouse	Proposed ACH(50)	0.00029	1680	92.17	173.04	0.1027	5.0	All	20160 cu ft

MASS					
✓ #	Mass Type	Area	Thickness	Furniture Fraction	Space
___ 1	Default(8 lbs/sq.ft.)	0 ft²	0 ft	0.30	Main

HEATING SYSTEM									
✓ #	System Type	Subtype/Speed	AHRI #	Efficiency	Capacity kBtu/hr	----Geothermal HeatPump---- Entry Power Volt Current	Ducts	Block	

INPUT SUMMARY CHECKLIST REPORT

HEATING SYSTEM(Continued)

1 Electric Heat Pump None/Single HSPF2: 8.50 36.0 0.00 0.00 0.00 sys#1 1

COOLING SYSTEM

1 Central Unit None/Single SEER2:15.0 36.0 1080 0.85 sys#1 1

HOT WATER SYSTEM

1 Electric None Main 0.92 (0.92) 50.00 gal 70 gal 120 deg Standard None 99

Recirculation System Recirc Control Type Loop length Branch length Pump power DWHR Facilities Connected Equal Flow DWHR Eff Other Credits

1 No NA NA NA No NA NA NA NA None

DUCTS

1 Attic 6.0 448 ft² Attic 6.0 112 ft² Prop. Leak Free Main --- --- 0.030 0.50 1 1

TEMPERATURES

Programable Thermostat: Y Ceiling Fans: N

Cooling [] Jan [] Feb [] Mar [] Apr [] May [X] Jun [X] Jul [X] Aug [X] Sep [] Oct [] Nov [] Dec

Heating [X] Jan [X] Feb [X] Mar [] Apr [] May [] Jun [] Jul [] Aug [] Sep [] Oct [X] Nov [X] Dec

Venting [] Jan [] Feb [X] Mar [X] Apr [] May [] Jun [] Jul [] Aug [] Sep [X] Oct [X] Nov [] Dec

Thermostat Schedule: HERS 2006 Reference

Schedule Type	1	2	3	4	5	6	7	8	9	10	11	12
Cooling (WD)	AM 78	PM 78	78	78	78	78	78	78	80	80	80	80
Cooling (WEH)	AM 78	PM 78	78	78	78	78	78	78	80	80	80	80
Heating (WD)	AM 65	PM 68	65	65	65	65	65	68	68	68	68	68
Heating (WEH)	AM 65	PM 68	65	65	65	65	65	68	68	68	68	68