

Lumber design values are in accordance with ANSI/TPI 1 section 6.3
These truss designs rely on lumber values established by others.

RE: 2570015 - CHEMERY CONST. - LOT 6 FWS

MiTek USA, Inc.

6904 Parke East Blvd.
Tampa, FL 33610-4115

Site Information:

Customer Info: Project Name: Model:
Lot/Block: Subdivision:
Address:
City: State:

Name Address and License # of Structural Engineer of Record, If there is one, for the building.

Name: License #:
Address:
City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2017/TPI2014 Design Program: MiTek 20/20 8.2
Wind Code: ASCE 7-10 Wind Speed: 130 mph
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 23 individual, Truss Design Drawings and 0 Additional Drawings.

With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.


No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	T22130456	CJ01	12/10/20	23	T22130478	T12	12/10/20
2	T22130457	CJ03	12/10/20				
3	T22130458	CJ05	12/10/20				
4	T22130459	EJ01	12/10/20				
5	T22130460	EJ02	12/10/20				
6	T22130461	EJ03	12/10/20				
7	T22130462	EJ04	12/10/20				
8	T22130463	HJ08	12/10/20				
9	T22130464	HJ10	12/10/20				
10	T22130465	T01	12/10/20				
11	T22130466	T01A	12/10/20				
12	T22130467	T02	12/10/20				
13	T22130468	T03	12/10/20				
14	T22130469	T04	12/10/20				
15	T22130470	T05	12/10/20				
16	T22130471	T06	12/10/20				
17	T22130472	T07	12/10/20				
18	T22130473	T08	12/10/20				
19	T22130474	T09	12/10/20				
20	T22130475	T10	12/10/20				
21	T22130476	T11	12/10/20				
22	T22130477	T11G	12/10/20				

The truss drawing(s) referenced above have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource-Jacksonville.

Truss Design Engineer's Name: Velez, Joaquin

My license renewal date for the state of Florida is February 28, 2021.

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020


Job 2570015	Truss CJ01	Truss Type Jack-Open	Qty 8	Ply 1	CHEMERY CONST. - LOT 6 FWS T22130456
----------------	---------------	-------------------------	----------	----------	---

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:21 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-CK1oEm4rMtdoSpu93p3GHcAEllnbg82ufABv8yAfKO



Scale = 1:8.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.23	Vert(LL)	0.00 5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.04	Vert(CT)	0.00 5	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00 2	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MP					Weight: 7 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-


TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=45(LC 8)
Max Uplift 3=-27(LC 1), 2=-146(LC 8), 4=-46(LC 1)
Max Grav 3=26(LC 8), 2=254(LC 1), 4=42(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 3, 146 lb uplift at joint 2 and 46 lb uplift at joint 4.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job 2570015	Truss CJ03	Truss Type Jack-Open	Qty 8	Ply 1	CHEMERY CONST. - LOT 6 FWS T22130457
Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,					Job Reference (optional)

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:24 2020 Page 1
ID:WyJ0ilnE7zBqL0C_WWagj0yzrQm-dvixso6jeo?NJHcklxdzvEol?Wp2t8tUadOrWTyAfKL



LOADING (psf)	SPACING-	CSL.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 20.0	2'-0-0	TC 0.23	Vert(LL)	-0.00	4-7	>999	240	MT20
TCDL 7.0	Plate Grip DOL 1.25	BC 0.06	Vert(CT)	-0.01	4-7	>999	180	244/190
BCLL 0.0 *	Lumber DOL 1.25	WB 0.00	Horz(CT)	0.00	3	n/a	n/a	
BCDL 10.0	Rep Stress Incr YES	Matrix-MP						
	Code FBC2017/TPI2014							
							Weight: 13 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-


TOP CHORD Structural wood sheathing directly applied or 3'-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=75(LC 12)
Max Uplift 3=-33(LC 12), 2=-103(LC 8)
Max Grav 3=51(LC 1), 2=253(LC 1), 4=47(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6-0 tall by 2'-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 3 and 103 lb uplift at joint 2.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130458
2570015	CJ05	Jack-Open	4	1		

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:25 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-55GJ387MP68ExRBwle8CSSLwQv6icb7epH8O2vyAfKK



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.25	Vert(LL)	-0.02	4-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.23	Vert(CT)	-0.05	4-7	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MP						Weight: 19 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=107(LC 12)
Max Uplift 3=68(LC 12), 2=-104(LC 12)
Max Grav 3=108(LC 1), 2=313(LC 1), 4=86(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 68 lb uplift at joint 3 and 104 lb uplift at joint 2.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610


Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130459
2570015	EJ01	Jack-Partial	16	1		

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:26 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-ZlqhHU8_APG5Zbm6sMfr_ft_pJOHL2Nn2xtxaMyAfKJ



Scale = 1:20.4

Plate Offsets (X,Y)--		[2:0-0-4,0-0-5]	
LOADING (psf)		SPACING-	2-0-0
TCLL 20.0		Plate Grip DOL	1.25
TCDL 7.0		Lumber DOL	1.25
BCLL 0.0 *		Rep Stress Incr	YES
BCDL 10.0		Code	FBC2017/TPI2014
		CSI.	
		TC	0.60
		BC	0.50
		WB	0.00
		Matrix-MS	
		DEFL.	
		Vert(LL)	0.10 4-7 >869 240
		Vert(CT)	-0.21 4-7 >400 180
		Horz(CT)	0.01 2 n/a n/a
		PLATES	MT20
		GRIP	244/190
		Weight: 25 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-


TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=139(LC 12)
Max Uplift 3=-101(LC 12), 2=-118(LC 12)
Max Grav 3=160(LC 1), 2=380(LC 1), 4=124(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 101 lb uplift at joint 3 and 118 lb uplift at joint 2.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610


Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130460
2570015	EJ02	Jack-Partial Girder	1	1		
Job Reference (optional)						

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:28 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-VgyRi99Ei1WpouwV_niv44zQ67_apr74VFM2fEyAfKH



Scale = 1:19.0

Plate Offsets (X,Y)--		[1:0-3-7,0-1-0]							
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	L/defl	L/d
TCLL 20.0		Plate Grip DOL	1.25	TC 0.22		Vert(LL)	-0.03 5-6	>999	240
TCDL 7.0		Lumber DOL	1.25	BC 0.79		Vert(CT)	-0.05 5-6	>999	180
BCLL 0.0 *		Rep Stress Incr	NO	WB 0.50		Horz(CT)	-0.01 3	n/a	n/a
BCDL 10.0		Code FBC2017/TPI2014		Matrix-MS					
						PLATES	GRIP		
						MT20	244/190		
						Weight: 34 lb	FT = 20%		

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-2-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-11-12 oc bracing.

REACTIONS.

(size) 1=0-3-8, 3=Mechanical, 4=Mechanical
Max Horz 1=112(LC 23)
Max Uplift 1=259(LC 8), 3=50(LC 8), 4=337(LC 8)
Max Grav 1=959(LC 1), 3=77(LC 1), 4=1174(LC 1)

FORCES.


(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1771/468
BOT CHORD 1-6=-509/1627, 5-6=-509/1627
WEBS 2-6=-322/1263, 2-5=-1811/566

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 259 lb uplift at joint 1, 50 lb uplift at joint 3 and 337 lb uplift at joint 4.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 565 lb down and 173 lb up at 2-0-12, and 565 lb down and 173 lb up at 4-0-12, and 567 lb down and 172 lb up at 6-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 1-4=-20
Concentrated Loads (lb)
Vert: 9=-565(B) 10=-565(B) 11=-567(B)



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610


Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130461
2570015	EJ03	Jack-Open Girder	1	1		
Job Reference (optional)						

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:29 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-zsWqvVAsTKegQ2VhXUD8cIvB5XNzYKAekv6cBgyAfKG



Scale = 1:19.0

Plate Offsets (X,Y)--		[1:0-3-3,0-0-12]					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 20.0	Plate Grip DOL	1.25	TC 0.21	Vert(LL)	-0.02 6-8	>999	240
TCDL 7.0	Lumber DOL	1.25	BC 0.59	Vert(CT)	-0.04 6-8	>999	180
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.38	Horz(CT)	-0.01 3	n/a	n/a
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MS				
				PLATES	GRIP		
				MT20	244/190		
				Weight: 34 lb	FT = 20%		

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-10-1 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=0-3-8, 3=Mechanical, 4=Mechanical
Max Horz 1=112(LC 8)
Max Uplift 1=231(LC 8), 3=45(LC 8), 4=252(LC 8)
Max Grav 1=845(LC 1), 3=67(LC 1), 4=846(LC 1)

FORCES.


(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1367/362
BOT CHORD 1-6=-408/1253, 5-6=-408/1253
WEBS 2-6=-257/1000, 2-5=-1431/466

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 231 lb uplift at joint 1, 45 lb uplift at joint 3 and 252 lb uplift at joint 4.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 415 lb down and 134 lb up at 1-6-12, and 415 lb down and 134 lb up at 3-6-12, and 415 lb down and 134 lb up at 5-6-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)

- Standard
- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 1-4=-20
Concentrated Loads (lb)
Vert: 6=-415(F) 9=-415(F) 10=-415(F)



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130463
2570015	HJ08	Diagonal Hip Girder	2	1		


Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:31 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-vFdaKBB6?yuOfMe4fvFchjbsFK7j0IMWBChIFZyAfKE



Scale = 1:18.3



										3-9-0				6-11-6				7-0-2		
										3-9-0				3-2-6				0-0-12		
LOADING (psf)		SPACING-			2-0-0		CSI.		DEFL.		in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL			1.25		TC	0.55	Vert(LL)	-0.03	7-10	>999		240		MT20		244/190		
TCDL	7.0	Lumber DOL			1.25		BC	0.38	Vert(CT)	0.03	7-10	>999		180						
BCLL	0.0 *	Rep Stress Incr			NO		WB	0.08	Horz(CT)	0.00	5	n/a		n/a						
BCDL	10.0	Code FBC2017/TPI2014					Matrix-MS										Weight: 32 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 4=Mechanical, 2=0-4-9, 5=Mechanical
Max Horz 2=122(LC 4)
Max Uplift 4=-53(LC 4), 2=-158(LC 4), 5=-13(LC 8)
Max Grav 4=92(LC 19), 2=359(LC 35), 5=147(LC 35)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-367/30
BOT CHORD 2-7=-47/322, 6-7=-47/322
WEBS 3-6=-346/51

NOTES-

- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 53 lb uplift at joint 4, 158 lb uplift at joint 2 and 13 lb uplift at joint 5.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 73 lb down and 103 lb up at 1-6-1, 73 lb down and 103 lb up at 1-6-1, and 21 lb down and 33 lb up at 4-4-0, and 21 lb down and 33 lb up at 4-4-0 on top chord, and 36 lb down and 74 lb up at 1-6-1, 36 lb down and 74 lb up at 1-6-1, and 25 lb down and 2 lb up at 4-4-0, and 25 lb down and 2 lb up at 4-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 5-8=-20
Concentrated Loads (lb)
Vert: 11=49(F=24, B=24) 13=70(F=35, B=35) 14=4(F=2, B=2)



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130464
2570015	HJ10	Diagonal Hip Girder	2	1		

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:32 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-ORByXXCImF0FHWDGDcmrEw70PkP4IlgigQsKGo?yAfKD



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.59	Vert(LL)	-0.06	6-7	>999	240	MT20
TCDL 7.0	Lumber DOL	1.25	BC 0.63	Vert(CT)	-0.13	6-7	>929	180	244/190
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.39	Horz(CT)	0.01	5	n/a	n/a	
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MS						
								Weight: 44 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 2=0-4-9, 5=Mechanical
Max Horz 2=154(LC 22)
Max Uplift 4=-98(LC 4), 2=-185(LC 4), 5=-44(LC 8)
Max Grav 4=151(LC 1), 2=464(LC 1), 5=265(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-735/170
BOT CHORD 2-7=-216/680, 6-7=-216/680
WEBS 3-6=-705/224

NOTES-

- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 98 lb uplift at joint 4, 185 lb uplift at joint 2 and 44 lb uplift at joint 5.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 73 lb down and 103 lb up at 1-6-1, 73 lb down and 103 lb up at 1-6-1, 21 lb down and 33 lb up at 4-4-0, 21 lb down and 33 lb up at 4-4-0, and 43 lb down and 78 lb up at 7-1-15, and 43 lb down and 78 lb up at 7-1-15 on top chord, and 36 lb down and 74 lb up at 1-6-1, 36 lb down and 74 lb up at 1-6-1, 25 lb down and 2 lb up at 4-4-0, 25 lb down and 2 lb up at 4-4-0, and 37 lb down at 7-1-15, and 37 lb down at 7-1-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 5-8=-20
Concentrated Loads (lb)
Vert: 7=4(F=2, B=2) 11=49(F=24, B=24) 12=-63(F=-31, B=-31) 13=70(F=35, B=35) 14=-50(F=-25, B=-25)



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130465
2570015	T01	Hip Girder	1	2	Job Reference (optional)	


Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.240 s Mar 9 2020
MiTek Industries, Inc.
Wed Dec 9 15:32:36 2020
Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-GDRTNvFFpUWgl7X1SSmOmlc2LnahPUGLUITxnyAfK9

-2-0-0 | 3-11-15 | 7-0-0 | 12-6-14 | 18-0-0 | 23-5-2 | 29-0-0 | 32-0-1 | 36-0-0 | 38-0-0 |
2-0-0 | 3-11-15 | 3-0-1 | 5-6-14 | 5-5-2 | 5-5-2 | 5-6-14 | 3-0-1 | 3-11-15 | 2-0-0 |

Scale = 1:65.2




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 1.00	Vert(LL)	-0.39 14-15	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.53	Vert(CT)	-0.73 14-15	>594	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.73	Horz(CT)	0.10 10	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MS					Weight: 418 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x6 SP M 26	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

REACTIONS.	(size) 2=0-3-8, 10=0-3-8
	Max Horz 2=63(LC 31)
	Max Uplift 2=881(LC 4), 10=795(LC 9)
	Max Grav 2=2889(LC 1), 10=2560(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-6742/2016, 3-4=-6624/2013, 4-5=-8924/2806, 5-6=-8924/2806, 6-7=-8616/2699, 7-8=-8616/2699, 8-9=-5724/1734, 9-10=-5875/1797
BOT CHORD 2-18=-1839/6176, 16-18=-1788/6136, 15-16=-3187/10438, 14-15=-3187/10438, 12-14=-1522/5277, 10-12=-1583/5383
WEBS 4-18=-64/725, 4-16=-1045/3192, 5-16=-617/386, 6-16=-1760/586, 6-15=-228/1229, 6-14=-2117/750, 7-14=-309/183, 8-14=-1223/3821, 8-12=-44/292

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TC DL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 881 lb uplift at joint 2 and 795 lb uplift at joint 10.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 125 lb down and 104 lb up at 7-0-0, 106 lb down and 104 lb up at 9-0-12, 106 lb down and 104 lb up at 11-0-12, 106 lb down and 104 lb up at 13-0-12, 106 lb down and 104 lb up at 15-0-12, 106 lb down and 104 lb up at 17-0-12, and 106 lb down and 104 lb up at 19-0-12, and 27 lb down and 52 lb up at 19-11-4 on top chord, and 292 lb down and 71 lb up at 7-0-0, 84 lb down at 9-0-12, 84 lb down at 11-0-12, 84 lb down at 13-0-12, 84 lb down at 15-0-12, 84 lb down at 17-0-12, and 84 lb down at 19-0-12, and 1154 lb down and 357 lb up at 19-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.



LOAD CASE(S) Standard	December 10,2020
-----------------------	------------------

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130465
2570015	T01	Hip Girder	1	2	Job Reference (optional)	

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 4-8=-54, 8-11=-54, 2-10=-20

Concentrated Loads (lb)

Vert: 4=-106(B) 18=-284(B) 23=-106(B) 24=-106(B) 25=-106(B) 26=-106(B) 27=-106(B) 28=-106(B) 29=-23(B) 30=-61(B) 31=-61(B) 32=-61(B) 33=-61(B) 34=-61(B) 35=-61(B) 36=-1154(B)



Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130466
2570015	T01A	Hip Girder	1	2	Job Reference (optional)	

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:40 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-9_g_DGImtj06EkqohlVjZcTlUyBkdCfrG6Gh4YyAfK5

-2-0-0

3-11-15

7-0-0

12-6-14

18-0-0

23-5-2

29-0-0

32-0-1

36-0-0

38-0-0

2-0-0

3-11-15

3-0-1

5-6-14

5-5-2

5-5-2


5-6-14

3-0-1

3-11-15

2-0-0

Scale = 1:65.2



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.97	Vert(LL)	-0.36	15	>999	240	
TCDL 7.0	Lumber DOL	1.25	BC 0.32	Vert(CT)	-0.67	15	>642	180	
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.72	Horz(CT)	0.09	10	n/a	n/a	
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MS						
Weight: 418 lb									FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x6 SP M 26	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

REACTIONS.	(size) 2=0-3-8, 10=0-3-8
	Max Horz 2=63(LC 8)
	Max Uplift 2=861(LC 8), 10=844(LC 9)
	Max Grav 2=2774(LC 1), 10=2671(LC 1)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-6439/1964, 3-4=-6317/1939, 4-5=-8468/2699, 5-6=-8468/2699, 6-7=-8884/2843, 7-8=-8884/2843, 8-9=-6061/1877, 9-10=-6200/1936
BOT CHORD	2-18=-1799/5898, 16-18=-1721/5851, 15-16=-2976/9590, 14-15=-2976/9590, 12-14=-1657/5596, 10-12=-1711/5679
WEBS	4-18=-54/705, 4-16=-1002/2999, 5-16=-603/378, 6-16=-1315/468, 6-15=0/524, 6-14=-850/319, 7-14=-480/304, 8-14=-1233/3763, 8-12=-67/400

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TC DL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 861 lb uplift at joint 2 and 844 lb uplift at joint 10.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 125 lb down and 104 lb up at 7-0-0, 106 lb down and 104 lb up at 9-0-12, 106 lb down and 104 lb up at 11-0-12, 106 lb down and 104 lb up at 13-0-12, 106 lb down and 104 lb up at 15-0-12, 106 lb down and 104 lb up at 17-0-12, 106 lb down and 104 lb up at 19-0-12, 106 lb down and 104 lb up at 21-0-12, 106 lb down and 104 lb up at 23-0-12, and 23 lb down and 45 lb up at 23-11-4 on top chord, and 292 lb down and 71 lb up at 7-0-0, 84 lb down at 9-0-12, 84 lb down at 11-0-12, 84 lb down at 13-0-12, 84 lb down at 15-0-12, 84 lb down at 17-0-12, 84 lb down at 19-0-12, 84 lb down at 21-0-12, and 84 lb down at 23-0-12, and 826 lb down and 272 lb up at 23-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

Continued on page 2

LOAD CASE(S) Standard

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

JOAQUIN VELEZ

LICENSE

No 68182

STATE OF FLORIDA

PROFESSIONAL ENGINEER


Joaquin Velez PE No.68182

MiTek USA, Inc. FL Cert 6634

6904 Parke East Blvd. Tampa FL 33610

Date:

December 10,2020



Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130466
2570015	T01A	Hip Girder	1	2	Job Reference (optional)	

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 4-8=-54, 8-11=-54, 2-10=-20

Concentrated Loads (lb)

Vert: 4=-106(F) 18=-284(F) 23=-106(F) 24=-106(F) 25=-106(F) 26=-106(F) 27=-106(F) 28=-106(F) 29=-106(F) 30=-106(F) 31=-13(F) 32=-61(F) 33=-61(F) 34=-61(F) 35=-61(F) 36=-61(F) 37=-61(F) 38=-61(F) 39=-61(F) 40=-826(F)



Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130467
2570015	T02	Hip	2	1		

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:42 2020 Page 1

-2-0-0
2-0-0

4-10-1
4-10-1

9-0-0
4-1-15

15-0-9
6-0-9

20-11-7
5-10-14

27-0-0
6-0-9

31-1-15
4-1-15

36-0-0
4-10-1

38-0-0
2-0-0

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-5NokeyK0PKHqT2_BojyBe1YINmjf54J8jQlo8QyAfK3

Job Reference (optional)

Scale = 1:65.2





Plate Offsets (X,Y)--		[2:0-2-6,0-1-8], [4:0-3-0,0-2-4], [8:0-3-0,0-2-4], [10:0-2-6,0-1-8]							
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES	
TCLL	20.0	Plate Grip DOL		TC	0.49	in (loc)		MT20	
TCDL	7.0	Lumber DOL		BC	1.00	l/defl		244/190	
BCLL	0.0 *	Rep Stress Incr		WB	0.83	L/d			
BCDL	10.0	Code FBC2017/TPI2014		Matrix-MS		Horz(CT)		Weight: 174 lb FT = 20%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-1-3 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS. (size) 2=0-3-8, 10=0-3-8
Max Horz 2=77(LC 12)
Max Uplift 2=408(LC 12), 10=408(LC 13)
Max Grav 2=1440(LC 1), 10=1440(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2890/1056, 3-4=-2611/929, 4-5=-2396/897, 5-7=-3120/1133, 7-8=-2396/897, 8-9=-2611/929, 9-10=-2890/1056
BOT CHORD 2-16=-860/2628, 14-16=-960/3052, 12-14=-963/3052, 10-12=-886/2628
WEBS 3-16=-287/205, 4-16=-194/720, 5-16=-866/314, 7-12=-866/314, 8-12=-194/720, 9-12=-287/205

- NOTES-**
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCdL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 408 lb uplift at joint 2 and 408 lb uplift at joint 10.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130468
2570015	T03	Hip	2	1		


Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:44 2020 Page 1

ID:WyJ0ilnE7zBqLOC_WWagj0yZrQm-1lwV3eMGxxXYjM8aw8_fjSd1ZaUqZ6DRBkEuDjyAfK1



Scale = 1:65.2



	5-4-12	11-0-0	18-0-0	25-0-0	30-7-4	36-0-0	
	5-4-12	5-7-4	7-0-0	7-0-0	5-7-4	5-4-12	

Plate Offsets (X,Y)-- [4:0-5-12,0-2-8], [6:0-5-12,0-2-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.71	Vert(LL)	-0.23 13	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.69	Vert(CT)	-0.43 13-15	>998	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.36	Horz(CT)	0.14 8	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MS					Weight: 183 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-3-13 oc bracing.

REACTIONS.


(size) 2=0-3-8, 8=0-3-8
Max Horz 2=-91(LC 13)
Max Uplift 2=-407(LC 12), 8=-407(LC 13)
Max Grav 2=1440(LC 1), 8=1440(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2913/1047, 3-4=-2436/902, 4-5=-2623/1019, 5-6=-2623/1019, 6-7=-2436/902, 7-8=-2913/1047
BOT CHORD 2-16=-852/2643, 15-16=-852/2643, 13-15=-641/2203, 11-13=-647/2203, 10-11=-877/2643, 8-10=-877/2643
WEBS 3-15=-491/251, 4-15=-61/398, 4-13=-211/632, 5-13=-431/243, 6-13=-211/632, 6-11=-60/398, 7-11=-491/251

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 407 lb uplift at joint 2 and 407 lb uplift at joint 8.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130469
2570015	T04	Hip	2	1		

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:47 2020 Page 1

ID:WyJ0iinE7zBqL0C_WWagj0yZrQm-RKbdhfO9Esv6apt8bGXML5FagnQBmP3ttiTZqeyAfK_

-2-0-0

6-6-1

13-0-0

18-0-0

23-0-0

29-5-15

36-0-0

38-0-0

2-0-0

6-6-1

6-5-15

5-0-0


5-0-0

6-5-15

6-6-1

2-0-0

Scale = 1:66.2




	6-6-1	13-0-0	23-0-0	29-5-15	36-0-0	
	6-6-1	6-5-15	10-0-0	6-5-15	6-6-1	
Plate Offsets (X,Y)--	[3:0-3-0,0-3-0], [4:0-3-0,0-2-4], [6:0-3-0,0-2-4], [7:0-3-0,0-3-0]					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.		PLATES
TCLL 20.0	Plate Grip DOL	1.25	TC 0.59	in (loc) l/defl L/d		GRIP
TCDL 7.0	Lumber DOL	1.25	BC 0.97	Vert(LL) -0.31 12-13 >999 240		MT20 244/190
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.61	Vert(CT) -0.65 12-13 >666 180		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MS	Horz(CT) 0.14 8 n/a n/a		
						Weight: 181 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-0-15 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3	

REACTIONS. (size) 2=0-3-8, 8=0-3-8
Max Horz 2=-105(LC 13)
Max Uplift 2=-405(LC 12), 8=-405(LC 13)
Max Grav 2=1440(LC 1), 8=1440(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2868/1049, 3-4=-2271/858, 4-5=-2042/838, 5-6=-2042/838, 6-7=-2271/858, 7-8=-2868/1049
BOT CHORD 2-15=-846/2594, 13-15=-847/2591, 12-13=-643/2166, 10-12=-869/2591, 8-10=-868/2594
WEBS 3-13=-619/324, 4-13=-152/561, 5-13=-324/159, 5-12=-324/159, 6-12=-152/561, 7-12=-619/324

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCdL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 405 lb uplift at joint 2 and 405 lb uplift at joint 8.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130470
2570015	T05	Hip	2	1		

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:50 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-svHmJhQ1WnHhRHbjGO53zjt3d_VvzrvJZgiDPzyAfJx

Job Reference (optional)

-2-0-0	7-7-5	15-0-0	21-0-0	28-4-11	36-0-0	38-0-0
2-0-0	7-7-5	7-4-11	6-0-0	7-4-11	7-7-5	2-0-0

Scale = 1:66.2




Plate Offsets (X,Y)--		[3:0-3-0,0-3-4], [4:0-5-12,0-2-8], [5:0-3-0,0-2-4], [6:0-3-0,0-3-4]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.73
TCDL 7.0	Lumber DOL	1.25	BC 0.78
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.28
BCDL 10.0	Code	FBC2017/TPI2014	Matrix-MS
		DEFL.	PLATES
		in (loc) l/defl L/d	MT20 244/190
		Vert(LL) -0.18 12 >999 240	
		Vert(CT) -0.39 12-14 >999 180	
		Horz(CT) 0.13 7 n/a n/a	
		Weight: 180 lb FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-3-12 oc bracing.
WEBS 1 Row at midpt 3-12, 4-11, 6-11

REACTIONS.


(size) 2=0-3-8, 7=0-3-8
Max Horz 2=-118(LC 13)
Max Uplift 2=-402(LC 12), 7=-402(LC 13)
Max Grav 2=1440(LC 1), 7=1440(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2826/1045, 3-4=-2087/823, 4-5=-1858/810, 5-6=-2087/823, 6-7=-2826/1045
BOT CHORD 2-14=-837/2548, 12-14=-837/2545, 11-12=-511/1857, 9-11=-856/2545, 7-9=-855/2548
WEBS 3-14=0/317, 3-12=-765/378, 4-12=-111/481, 5-11=-110/481, 6-11=-765/378, 6-9=0/317

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 402 lb uplift at joint 2 and 402 lb uplift at joint 7.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130471
2570015	T06	Hip	2	1		

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,


8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:52 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-oIPWkNSI2PXPgal6Op7X28yVoo9RRf1c0_BKUrYAfJv

Job Reference (optional)

-2-0-0	6-0-9	11-5-4	17-0-0	19-0-0	24-6-12	29-11-7	36-0-0	38-0-0
2-0-0	6-0-9	5-4-11	5-6-12	2-0-0	5-6-12	5-4-11	6-0-9	2-0-0

Scale = 1:66.2



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.37	Vert(LL) -0.19 13-15	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.90	Vert(CT) -0.44 13-15	>987	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.69	Horz(CT) 0.13 11	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014	Matrix-MS				Weight: 196 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-1-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-2-3 oc bracing.

REACTIONS.


(size) 2=0-3-8, 11=0-3-8
Max Horz 2=-132(LC 13)
Max Uplift 2=-400(LC 12), 11=-400(LC 13)
Max Grav 2=1440(LC 1), 11=1440(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2858/1091, 3-5=-2626/1019, 5-6=-1872/793, 6-7=-1678/771, 7-8=-1870/792,
8-10=-2627/1019, 10-11=-2858/1091
BOT CHORD 2-18=-888/2589, 16-18=-687/2152, 15-16=-437/1675, 13-15=-693/2152, 11-13=-910/2590
WEBS 3-18=-301/220, 5-18=-112/495, 5-16=-637/339, 6-16=-188/507, 7-15=-187/504,
8-15=-640/340, 8-13=-113/496, 10-13=-301/220

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 400 lb uplift at joint 2 and 400 lb uplift at joint 11.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130472
2570015	T07	Common	5	1		


Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:54 2020 Page 1

ID:WyJ0iinE7zBqLOC_WWagj0yZrQm-kgWG92TYa0n7vuvVVE9?7Z2r7cqdvX5vUlgQYkyAfJt

-2-0-0	6-3-0	12-0-15	18-0-0	23-11-1	29-9-0	36-0-0	38-0-0
2-0-0	6-3-0	5-9-15	5-11-1	5-11-1	5-9-15	6-3-0	2-0-0

Scale: 3/16"=1'



8-8-15		18-0-0		27-3-1		36-0-0	
8-8-15		9-3-1		9-3-1		8-8-15	
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 20.0	Plate Grip DOL	1.25	TC 0.38	Vert(LL)	-0.25 14-16	>999	240
TCDL 7.0	Lumber DOL	1.25	BC 0.92	Vert(CT)	-0.50 14-16	>869	180
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.78	Horz(CT)	0.13 10	n/a	n/a
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MS				
				PLATES		GRIP	
				MT20		244/190	
				Weight: 179 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-1-13 oc purlins.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

REACTIONS.


(size) 2=0-3-8, 10=0-3-8
Max Horz 2=139(LC 16)
Max Uplift 2=-398(LC 12), 10=-398(LC 13)
Max Grav 2=1440(LC 1), 10=1440(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2852/1097, 3-5=-2617/1028, 5-6=-1803/777, 6-7=-1803/777, 7-9=-2617/1028,
9-10=-2852/1097
BOT CHORD 2-16=-893/2583, 14-16=-672/2098, 12-14=-676/2098, 10-12=-914/2583
WEBS 6-14=-408/1043, 7-14=-664/357, 7-12=-132/525, 9-12=-317/234, 5-14=-664/357,
5-16=-132/525, 3-16=-317/234

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 398 lb uplift at joint 2 and 398 lb uplift at joint 10.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130473
2570015	T08	Hip Girder	1	1		

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:55 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-Ct4fMOUALKv_X2Uh3yhEgna1e?Jde923jxP_5AyAfJs



Scale = 1:26.1




Plate Offsets (X,Y)--		[3:0-5-4,0-2-0]									
LOADING	(psf)	SPACING-	2-0-0	CSI.		DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC	0.27	Vert(LL)	-0.03 8	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.36	Vert(CT)	-0.06 8-11	>999	180		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.10	Horz(CT)	0.02 5	n/a	n/a		
BCDL	10.0	Code FBC2017/TPI2014		Matrix-MS						Weight: 53 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-2-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 5=0-3-8
Max Horz 2=-49(LC 9)
Max Uplift 2=-243(LC 8), 5=-239(LC 9)
Max Grav 2=734(LC 1), 5=736(LC 1)

FORCES.


(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1129/332, 3-4=-1016/322, 4-5=-1137/336
BOT CHORD 2-8=-273/997, 7-8=-273/1009, 5-7=-262/1003
WEBS 3-8=-6/254, 4-7=-4/252

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 243 lb uplift at joint 2 and 239 lb uplift at joint 5.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 73 lb down and 71 lb up at 5-0-0, and 116 lb down and 124 lb up at 7-0-0 on top chord, and 150 lb down and 30 lb up at 5-0-0, and 150 lb down and 30 lb up at 6-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)

- Standard
- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-4=-54, 4-6=-54, 9-12=-20
Concentrated Loads (lb)
Vert: 3=-54(B) 4=-69(B) 8=-122(B) 7=-122(B)



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job 2570015	Truss T09	Truss Type Common	Qty 4	Ply 1	CHEMERY CONST. - LOT 6 FWS T22130474
----------------	--------------	----------------------	----------	----------	---


Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:56 2020 Page 1

ID:WyJ0ilnE7zBqLOC_WWagi0yzrQm-h3e1akVo6d1r9C3tdfCTC_7BLPfiNbECxb9XdcyAfJr



Scale = 1:25.7



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.33	Vert(LL)	-0.03	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.37	Vert(CT)	-0.06				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.01				
BCDL	10.0	Code	FBC2017/TPI2014	Matrix-MS							
								Weight: 47 lb FT = 20%			

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 2=0-3-8, 4=0-3-8
Max Horz 2=56(LC 16)
Max Uplift 2=-168(LC 12), 4=-168(LC 13)
Max Grav 2=552(LC 1), 4=552(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-653/259, 3-4=-653/259
BOT CHORD 2-6=-127/551, 4-6=-127/551
WEBS 3-6=0/265

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 168 lb uplift at joint 2 and 168 lb uplift at joint 4.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130475
2570015	T10	Common	4	1		


Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:57 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-9FCPn4WQtxAinMe3AMjilCgMKp_f62SLAFu493yAfJq



Scale = 1:22.4



LOADING (psf)	SPACING-	CSL.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.38	Vert(LL)	-0.05	5-8	>999	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.39	Vert(CT)	-0.09	5-8	>999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.10	Horz(CT)	0.01	4	n/a		
BCDL 10.0	Code FBC2017/TPI2014	Matrix-MS						
							Weight: 44 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 4=Mechanical, 2=0-3-8
Max Horz 2=69(LC 12)
Max Uplift 4=-114(LC 13), 2=-170(LC 12)
Max Grav 4=435(LC 1), 2=561(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-684/297, 3-4=-681/295
BOT CHORD 2-5=-200/581, 4-5=-200/581
WEBS 3-5=-9/269

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 114 lb uplift at joint 4 and 170 lb uplift at joint 2.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


December 10,2020


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244, 8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:58 2020 Page 1
 ID:WyJ0ilnE7zBqLOC_WWagj0yzzQm-dSmn?QW2eFIYOVDGk4ExHPCqgDGhrU8VPveehVvAfJp

 Scale: 3/8"=1'



REACTIONS. (size) 2=0-3-8, 4=0-3-8
 Max Horz 2=70(LC 16)
 Max Uplift 2=-317(LC 8), 4=-317(LC 9)
 Max Grav 2=700(LC 1), 4=700(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-917/944, 3-4=-917/944
BOT CHORD	2-6=-755/778, 4-6=-755/778
WEBS	3-6=-427/364

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 317 lb uplift at joint 2 and 317 lb uplift at joint 4.
- 




December 10, 2020

Job	Truss	Truss Type	Qty	Ply	CHEMERY CONST. - LOT 6 FWS	T22130477
2570015	T11G	GABLE	1	1		

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Dec 9 15:32:59 2020 Page 1

ID:WyJ0ilnE7zBqL0C_WWagj0yZrQm-5eK9CmXhPYQP0fnSlnIAqdlGde6aypedZNBExyAfJo



Scale = 1:33.1




Plate Offsets (X,Y)--		[2:0-3-5,0-1-0], [2:0-0-9,Edge], [6:0-3-5,0-1-0], [6:0-0-9,Edge]							
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	l/defl	L/d
TCLL 20.0		Plate Grip DOL	1.25	TC 0.42		Vert(LL)	0.14 8-23	>999	240
TCDL 7.0		Lumber DOL	1.25	BC 0.52		Vert(CT)	-0.13 8-19	>999	180
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.11		Horz(CT)	0.02 6	n/a	n/a
BCDL 10.0		Code FBC2017/TPI2014		Matrix-MS					
						PLATES	GRIP		
						MT20	244/190		
						Weight: 88 lb	FT = 20%		

LUMBER-

TOP CHORD 2x4 SP No.2 *Except*
2-4,4-6: 2x6 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 5-3-3 oc bracing.

REACTIONS.


(size) 2=0-3-8, 6=0-3-8
Max Horz 2=63(LC 16)
Max Uplift 2=318(LC 8), 6=318(LC 9)
Max Grav 2=697(LC 1), 6=697(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-4=-860/920, 4-6=-860/919
BOT CHORD 2-8=-1134/1054, 6-8=-1134/1054
WEBS 4-8=-327/293

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 318 lb uplift at joint 2 and 318 lb uplift at joint 6.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

December 10,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless X, Y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{1}{16}$ " from outside edge of truss.

—
—
This symbol indicates the required direction of slots in connector plates.

*** Plate location details available in MITek 20120 software or upon request.**

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1.1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved



MITek Engineering Reference Sheet: MII-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.