

BEARING HEIGHT SCHEDULE

8'-0"

6/12 PITCH
2' OH

NOTES:

- 1) REFER TO HIB 91 (RECOMMENDATIONS FOR HANDING INSTALLATION AND TEMPORARY BRACING) REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED
- 2) ALL TRUSSES INCLUDING TRUSSES UNDER VALLEY TRUSSES SHALL BE DESIGNED TO MEET ALL VIBES FOR ALTERNATE BRACING REQUIREMENTS
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER
- 4) ALL TRUSSES ARE DESIGNED FOR 2 o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED
- 6) 5/42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP
- 7) ALL ROOF TRUSS HANGERS TO BE SIMPSON HUS26 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSS HANGERS TO BE SIMPSON TH4422 UNLESS OTHERWISE NOTED
- 8) BEARING ADAPTERS (HAR) TO BE FURNISHED BY BUILDER

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND VIDS. ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST DAMAGES THAT WILL RESULT IN EXTRA CHARGES TO YOU!

Issued/Revised Date: _____

Approved By: _____ Date: _____



Bunnell
PHONE 904-437-3549 FAX 904-437-3994
Jacksonville
PHONE 904-772-6100 FAX 904-772-1973
Lake City
PHONE 904-755-6844 FAX 904-755-7973
Sanford
PHONE 407-322-0059 FAX 407-322-5553

BUILDER
JOHN NORRIS

ISSUE ADDRESS

WORK	REVISION
SIERRA	NTS
DATE	ISSUED BY
5-4-06	JRD

