



RE: 3434903
IC CONST. - MAGNOLIA MODEL

MiTek USA, Inc.
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Site Information:

Customer: IC CONSTRUCTION Project Name: 3434903
Lot/Block: 6 Model: Magnolia
Address: TDB Subdivision: TBD
City: Columbia Cty State: FL

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):


Design Code: FBC2020/TPI2014 Design Program: MiTek 20/20 8.5
Wind Code: ASCE 7-16 Wind Speed: 130 mph
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 7 individual, dated Truss Design Drawings and 0 Additional Drawings.
With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No.	Seal#	Truss Name	Date
1	T29882007	T01	2/23/2023
2	T29882008	T01G	2/23/2023
3	T29882009	T02	2/23/2023
4	T29882010	T02G	2/23/2023
5	T29882011	T03	2/23/2023
6	T29882012	T04	2/23/2023
7	T29882013	T04G	2/23/2023

This item has been electronically signed and sealed by O'Regan, Philip using a Digital Signature.
Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies
The truss drawing(s) referenced above have been prepared by
MiTek USA, Inc under my direct supervision
based on the parameters provided by Builders FirstSource-Lake City, FL.
Truss Design Engineer's Name: O'Regan, Philip
My license renewal date for the state of Florida is February 28, 2025.
Florida COA: 6634

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Philip J. O'Regan PE No. 58126
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

February 23, 2023

Job	Truss	Truss Type	Qty	Ply	IC CONST. - MAGNOLIA MODEL	T29882007
3434903	T01	Common	7	1		





Plate Offsets (X, Y)--		[3:0-3-0,0-3-0], [5:0-3-0,0-3-0], [6:0-2-8,Edge], [9:0-4-0,0-3-0]									
LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES	
TCLL	20.0	2-0-0		TC 0.50		in (loc)		l/defl		MT20	
TCDL	7.0	Plate Grip DOL 1.25		BC 0.61		Vert(LL) -0.08 9-10		>999		244/190	
BCLL	0.0 *	Lumber DOL 1.25		WB 0.67		Vert(CT) -0.18 9-10		>999			
BCDL	10.0	Rep Stress Incr YES		Matrix-MS		Horz(CT) 0.06 6		n/a		Weight: 140 lb	
		Code FBC2020/TPI2014								FT = 20%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-2-1 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS.	
(size)	2=0-3-8, 6=0-3-8
Max Horz	2=-196(LC 10)
Max Uplift	2=-239(LC 12), 6=-239(LC 13)
Max Grav	2=1099(LC 1), 6=1099(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	2-3=-1656/315, 3-4=-1125/271, 4-5=-1125/271, 5-6=-1656/316
BOT CHORD	2-10=-300/1363, 9-10=-306/1334, 8-9=-181/1334, 6-8=-174/1363
WEBS	4-9=-129/697, 5-9=-553/256, 5-8=0/289, 3-9=-553/256, 3-10=0/289

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 13-9-0, Exterior(2R) 13-9-0 to 16-9-0, Interior(1) 16-9-0 to 29-0-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=239, 6=239.

This item has been electronically signed and sealed by O'Regan, Philip, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

February 23,2023

Job	Truss	Truss Type	Qty	Ply	IC CONST. - MAGNOLIA MODEL	T29882008
3434903	T01G	Common Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),
Lake City, FL - 32055,

8.530 s Aug 11 2022 MiTek Industries, Inc.
Wed Feb 22 07:17:47 2023
Page 1

ID:rWNsTK1yoWaak6pkUAcd30zifjX-QbCQGanC6OhW7MNRXUpbSEUxP9tnlYp3ToKzR?zifQ2

-1-6-0
1-6-0

13-9-0
13-9-0

27-6-0
13-9-0

29-0-0
1-6-0




Plate Offsets (X,Y)--										[2:0-3-8,Edge], [18:0-3-8,Edge], [20:0-1-15,0-11-13], [28:0-2-0,0-1-8], [33:0-1-15,0-11-13]												
LOADING (psf)		SPACING-			2-0-0		CSI.		DEFL.				in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL			1.25		TC	0.13	Vert(LL)	-0.01	19	n/r	120					MT20		244/190		
TCDL	7.0	Lumber DOL			1.25		BC	0.03	Vert(CT)	-0.01	19	n/r	120									
BCLL	0.0	Rep Stress Incr			YES		WB	0.15	Horz(CT)	0.01	18	n/a	n/a									
BCDL	10.0	Code FBC2020/TPI2014					Matrix-S												Weight: 171 lb		FT = 20%	

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD 2-0-0 oc purlins (6-0-0 max.).
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 27-6-0.

(lb) - Max Horz 2=-189(LC 10)

Max Uplift All uplift 100 lb or less at joint(s) 2, 18, 27, 29, 30, 31, 32, 33, 25, 24, 23, 22, 21, 20

Max Grav All reactions 250 lb or less at joint(s) 2, 18, 26, 27, 29, 30, 31, 32, 33, 25, 24, 23, 22, 21, 20

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.



- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCdL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3E) -1-6-0 to 1-9-0, Exterior(2N) 1-9-0 to 13-9-0, Corner(3R) 13-9-0 to 16-9-0, Exterior(2N) 16-9-0 to 29-0-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 18, 27, 29, 30, 31, 32, 33, 25, 24, 23, 22, 21, 20.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by ORegan, Philip, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

February 23,2023

Job	Truss	Truss Type	Qty	Ply	IC CONST. - MAGNOLIA MODEL	T29882009
3434903	T02	Common	6	1		
Job Reference (optional)						



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.54	Vert(LL)	0.09 11-14	MT20	244/190		
TCDL	7.0	Lumber DOL	1.25	BC	0.53	Vert(CT)	-0.13 8-10				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.68	Horz(CT)	0.02 6				
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 140 lb	FT = 20%

LUMBER-				BRACING-			
TOP CHORD	2x4 SP No.2			TOP CHORD	Structural wood sheathing directly applied or 4-11-14 oc purlins.		
BOT CHORD	2x4 SP No.2			BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.		
WEBS	2x4 SP No.3						

REACTIONS. (size) 2=0-3-8, 11=0-3-8, 6=0-3-8
Max Horz 2=-196(LC 10)
Max Uplift 2=-63(LC 12), 11=-226(LC 12), 6=-211(LC 13)
Max Grav 2=260(LC 23), 11=1138(LC 1), 6=845(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-51/266, 3-4=-626/211, 4-5=-625/198, 5-6=-1167/261
BOT CHORD 8-10=-127/911, 6-8=-121/942
WEBS 4-10=-73/303, 5-10=-562/257, 5-8=0/295, 3-10=-14/444, 3-11=-982/254

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 13-9-0, Exterior(2R) 13-9-0 to 16-9-0, Interior(1) 16-9-0 to 29-0-0 zone; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 11=226, 6=211.

This item has been electronically signed and sealed by ORegan, Philip, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

February 23,2023

Job	Truss	Truss Type	Qty	Ply	IC CONST. - MAGNOLIA MODEL	T29882010
3434903	T02G	Common Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),
Lake City, FL - 32055,

8.530 s Aug 11 2022 MiTek Industries, Inc.
Wed Feb 22 07:17:52 2023
Page 1
ID:rWNsTK1yoWaak6pkUacd30zifjX-nY?JJlrLxxJpE8FOK1Pm9HCmJAV3zoaad42k6CzifPz

-1-6-0

1-6-0

13-9-0

13-9-0

27-6-0

13-9-0

29-0-0

1-6-0

Scale = 1:54.6




Plate Offsets (X,Y)--		[2:0-4-1,0-1-12], [16:0-4-1,0-1-12], [23:0-3-0,0-3-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.25
TCDL 7.0	Lumber DOL	1.25	BC 0.34
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.18
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-S
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) 0.06 2-29 >999 240
			Vert(CT) -0.06 2-29 >999 180
			Horz(CT) 0.01 16 n/a n/a
			PLATES GRIP
			MT20 244/190
			Weight: 170 lb FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD 2-0-0 oc purlins (6-0-0 max.).
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. All bearings 21-6-0 except (jt=length) 2=0-3-8, 27=0-3-8.

(lb) - Max Horz 26=-189(LC 10)

Max Uplift All uplift 100 lb or less at joint(s) 2, 16, 24, 25, 26, 22, 21, 20, 19, 18 except 27=-181(LC 12)

Max Grav All reactions 250 lb or less at joint(s) 16, 23, 24, 25, 26, 22, 21, 20, 19, 18 except 2=265(LC 23), 27=460(LC 23)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3E) -1-6-0 to 1-6-0, Exterior(2N) 1-6-0 to 13-9-0, Corner(3R) 13-9-0 to 16-9-0, Exterior(2N) 16-9-0 to 29-0-0 zone; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 16, 24, 25, 26, 22, 21, 20, 19, 18 except (jt=lb) 27=181.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by ORegan, Philip, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.


Philip J. O'Regan PE No.58126
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

February 23,2023



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - MAGNOLIA MODEL	T29882011
3434903	T03	Common	8	1	Job Reference (optional)	



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.54	Vert(LL)	0.09 10-13	MT20	244/190		
TCDL	7.0	Lumber DOL	1.25	BC	0.53	Vert(CT)	-0.13 7-8				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.69	Horz(CT)	0.02 6				
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS						Weight: 137 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-11-2 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS.	
(size)	2=0-3-8, 10=0-3-8, 6=0-3-8
Max Horz	2=189(LC 11)
Max Uplift	2=-60(LC 12), 10=-231(LC 12), 6=-175(LC 13)
Max Grav	2=261(LC 23), 10=1141(LC 1), 6=761(LC 1)

FORCES.	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	2-3=-58/260, 3-4=-629/209, 4-5=-628/194, 5-6=-1182/265
BOT CHORD	7-8=-156/925, 6-7=-152/957
WEBS	4-8=-71/304, 5-8=-574/264, 5-7=0/297, 3-8=-23/447, 3-10=-984/259

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 13-9-0, Exterior(2R) 13-9-0 to 16-9-0, Interior(1) 16-9-0 to 27-6-0 zone; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 10=231, 6=175.

This item has been electronically signed and sealed by O'Regan, Philip, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.


Philip J. O'Regan PE No.58126
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

February 23,2023



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.530 s Aug 11 2022 MiTek Industries, Inc. Wed Feb 22 07:17:55 2023 Page 1
 ID:rWNsTK1yoWaak6pkUAcD30zifjX-B7hRxJtDDshN5b_z?9zUnwq9gNS?999REJ2GPiXzifPw
 -1-6-0 8-0-0 16-0-0 17-6-0
 1-6-0 8-0-0 8-0-0 1-6-0
 4x6 = Scale = 1:33.8



REACTIONS. (size) 2=0-3-8, 4=0-3-8
 Max Horz 2=-122(LC 10)
 Max Uplift 2=-153(LC 12), 4=-153(LC 13)
 Max Grav 2=673(LC 1), 4=673(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-763/610, 3-4=-763/610
BOT CHORD	2-6=-420/572, 4-6=-420/572
WEBS	3-6=-406/371

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCdL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 8-0-0, Exterior(2R) 8-0-0 to 11-0-0, Interior(1) 11-0-0 to 17-6-0 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=153. 4=153.

This item has been electronically signed and sealed by ORegan, Philip, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

February 23, 2023

 **WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with Mitek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

Job	Truss	Truss Type	Qty	Ply	IC CONST. - MAGNOLIA MODEL	T29882013
3434903	T04G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.530 s Aug 11 2022 MiTek Industries, Inc. Wed Feb 22 07:17:57 2023 Page 1
ID:rWNsTK1yoWaak6pkUAcd30zifjX-7WoCM?vUITY5Kv8M7a?ysLvUTB81d2dXmMlVnQzifPu




Plate Offsets (X,Y)--		[2:0-4-1,0-1-12], [6:0-4-1,0-1-12]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.80
TCDL 7.0	Lumber DOL	1.25	BC 0.68
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.19
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) 0.26 8-22 >733 240
			Vert(CT) -0.25 8-19 >741 180
			Horz(CT) 0.02 2 n/a n/a
			PLATES GRIP
			MT20 244/190
			Weight: 82 lb FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD 2-0-0 oc purlins (4-4-5 max.).
BOT CHORD Rigid ceiling directly applied or 6-6-5 oc bracing.

REACTIONS. (size) 2=0-3-8, 6=0-3-8
Max Horz 2=-115(LC 10)
Max Uplift 2=-155(LC 12), 6=-155(LC 13)
Max Grav 2=670(LC 1), 6=670(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-751/817, 4-6=-751/817
BOT CHORD 2-8=-589/599, 6-8=-589/599
WEBS 4-8=-518/369

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3E) -1-6-0 to 1-6-0, Exterior(2N) 1-6-0 to 8-0-0, Corner(3R) 8-0-0 to 11-0-0, Exterior(2N) 11-0-0 to 17-6-0 zone; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 5) All plates are 2x4 MT20 unless otherwise indicated.
 - 6) Gable studs spaced at 2-0-0 oc.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=155, 6=155.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by O'Regan, Philip, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

February 23,2023

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless X, Y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{3}{16}$ " from outside edge of truss.

— This symbol indicates the required direction of slots in connector plates.

*** Plate location details available in MiTek 2012 software or upon request.**

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1.1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MiTek® All Rights Reserved



MiTek Engineering Reference Sheet: MII-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.