

Attn: Columbia County Bldg Dept.
Re USDA Building Lake City Florida

O'Neil Construction of High Springs Scope of work

Demo:

Remove walls as shown on print
Remove paneling

Carpentry:

Build new walls @ new office
Build wall at Lan room
Bring walls @ storage area/Lan room up to ceiling
Move counter top
Replace two exterior doors with store front type doors

Painting:

Repaint interior walls
Paint exterior doors
Paint T-1-11 on exterior

Floor Covering:

Carpet tiles through out
Vinyl plank at back door
Vinyl plank at public side of counters

Lan Room:

Install new door
Remove back wall and extend room

Sheet rock:

New walls hang board and plaster to match
Existing panel walls hang board and plaster to match
Patch as needed

Electrical:

Install new LED lights
Install CAT6 low voltage wiring
Install 2- A1 phones
Demo electric in walls as needed
Add electric in new office walls

Parking lot:

Seal and stripe

Misc.:

Replace soffit as needed

