



[illegible]



Y	N	MASTER BA. OPTIONS
		3040 (1) PC. FIBERGLAS SHOWER IN LIEU OF LINEN CLOSET W/ (2) L.E.D. LT.

OPT. MASTER BATH

SCALE: 1/4" = 1'-0"



FLOOR PLAN ELEVATION "B"

SCALE: 1/4" = 1'-0"

NOTE:

○ INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

WALL LEGEND

- FRAMED WALL
- BEARING FRAME WALL
- FRAMED WALL W/ BRICK VENEER
- FRAMED WALL W/ SIDING OR STUCCO

GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used I.L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration: Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum rigid nonmetallic class 0 or class 1 duct board or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycombcore steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surface and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
- Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and it's attic as required by Table R302.6. From the residence and attics by not less than 1/2 inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.2.1 Window sills in dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below on the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
- M1502.4.5 Duct length: The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3.
 - M1502.3 Duct termination: Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
- Porch Ceilings: (See plan for the following options)
 - Option 1. Gypsum: 1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The gypsum board shall be attached w/ Type "VF" 1 1/4" drywall screws at 8" O.C. in field and edges.
 - Option 2. Plaster Base: 7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
- Energy Code Compliance Path is Performance Based Path. Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

AREA CALCULATIONS

1st FLOOR	2177 S.F.
TOTAL LIVING (AC)	2177 S.F.
GARAGE	420 S.F.
COVERED ENTRY	134 S.F.
COVERED PATIO/LANAI	
TOTAL AREA UNDER ROOF	2847 S.F.



100% Employee Owned
myTSGhome.com



MUNICIPAL STAMP AREA

SIGNATURE & SEAL
9/16/2025

To the best of the Engineer's knowledge, information and belief, the structural plans on this specification contain within these drawings comply with the 2023 Florida Building Code-Residential 8th Edition. The Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

Builder: Division Location: GAINESVILLE

LOT:	35	UNIT:	
Community:	Preserve at Laurel Lake	Plan Name:	2240
Project Address:	525 SW Bellflower Dr.	State City FL	
Client No.:			

Project No:

Sheet No:

2

FLOOR PLAN



FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

ELEVATION "B"

(*) SLOPE MAY VARY 24" MAXIMUM DEPTH. IF GREATER THAN 24" CONTACT EOR OR REFERENCE FMSW FOR STEM WALL OPTION	
---	--

FM11	STEP DOWN BRG.	1/2" = 1'-0"	FM12	STEP DOWN NON BRG.	1/2" = 1'-0"
FM14	SECTION @ RECESS SHOWER	1/2" = 1'-0"	FM18	TYP. STEP FTG. DETAIL	1/2" = 1'-0"
FM19	TYP. CORNER BAR DETAIL	1 1/2" = 1'-0"	FM23	TYP. FND PENETRATION	1/2" = 1'-0"

STEMWALL SCHEDULE							
STEMWALL HEIGHT (ft)	FOOTING DIMENSION				NUMBER/SIZE OF BARS	LAT.	MAXIMUM F.C. SPACING (O.C.) IN STEM WALL
	d 1 STORY	d 2 STORY	b 1 STORY	b 2 STORY			
0'-0" - 2'-0"	8"	10"	16"	20"	W/ (2) #5 BARS	<674#	6'-8"
2'-0" - 3'-4"	10"	10"	20"	24"	W/ (3) #5 BARS	674#	5'-4"
3'-4" - 4'-0"	12"	12"	32"	32"	W/ (4) #5 BARS	845#	4'-0"
>4'-0" - 5'-4"	16"	16"	48"	48"	W/ (5) #5 BARS CONT. & #5 @ 18" O.C. TRANSV.	1162#	2'-8"

NOTES:

- VERTICAL REINF. IN SOLID GROUTED CELLS AT ALL CORNERS, JAMBS, WALL INTERSECTIONS, BELOW GIRDER TRUSS LOCATIONS, AND AT THE MAXIMUM SPACING STATED IN SCHEDULE.
- W.W.M. IS REQUIRED TO MAKE ADEQUATE CONNECTION BETWEEN SLAB AND WALL WHEN STEM WALL EXCEEDS 4'-0". FIBERMESH CAN NOT BE USED AND #4 TURN BARS ARE REQUIRED @ EACH FILLED CELL LOCATION. EACH BAR TO TIE INTO VERTICAL BAR AND EXTEND OUT A MIN. 4'-0" INTO SLAB/ STEM.
- IF STEM IS REQ'D TO BE HIGHER CONTACT ENGINEER OF RECORD PRIOR TO CONSTRUCTION FOR MORE INFORMATION.
- G.C. TO PROVIDE ADEQUATE BRACING OF STEM WALL WHEN UNEVEN BACK FILLING IS TAKING PLACE.
- #5 HORIZONTAL CORNER BARS WITH 4'-0" LEGS IN KNOCKOUT BLOCK @ 16" O.C. VERTICAL. GROUTED SOLID WHEN STEM WALL IS GREATER THAN 4'-0" TALL (TYPICAL ALL CORNERS).
- IF STEMWALL IS WITH IN 5'-0" OF POOL OR WATER FEATURE FOUNDATIONS TO BE A MINIMUM 12" BELOW BOTTOM OF POOL OR WATER FEATURE.
- ALL STEM WALLS GREATER THAN (4) COURSES SHALL BE FULLY GROUTED.
- R.403.1.4 MINIMUM DEPTH: ALL EXTERIOR FOOTINGS (BOTTOM) SHALL BE PLACED AT LEAST 12" BELOW THE UNDISTURBED GROUND SURFACE.

EXTERIOR SHORING BY CONTRACTOR AS REQ'D WHEN STEM WALL IS OVER 4'-0"

SEE CHART ABOVE STEMWALL F.C. SPACING

(1) #5 CONT. TIED TO EACH VERT. REINF. BAR

#4 TURN BAR AT STEM WALLS GREATER THAN 4'-0"

IF USED: W.W.M. TO BE TIED TO #5 CONT. REBAR

COMPACTED CLEAN FILL

SEE SCHEDULE FOR REINF.

MIN. 8" COVER REQ'D

3" COVER TYP.

FINISH GRADE

SEE FLOOR FOR BASE CONNECTION

SEE SCHEDULE FOR REINF.

FMASW	ALTERNATE STEM WALL FOOTING SCHEDULE	1/2" = 1'-0"
--------------	--------------------------------------	--------------


BEARING WOOD INTERIOR WALL SCHEDULE				
MARK	STUD SPACING	CONNECTION & FASTENERS		LUMBER SPECIES
		TOP	BOTTOM	
BW1	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF
BW2	16"	SP2 W/ (6)-10d NAILS	SP1 W/ (6)-10d NAILS	SPF
BW3	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF
BW4	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP
BW5	16"	SP2 W/ (6)-10d NAILS	SP1 W/ (6)-10d NAILS	SYP
BW6	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP
BW7	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF
BW8	12"	SP2 W/ (6)-10d NAILS	SP1 W/ (6)-10d NAILS	SPF
BW9	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF
BW10	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP
BW11	12"	SP2 W/ (6)-10d NAILS	SP1 W/ (6)-10d NAILS	SYP
BW12	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP

NOTE: 2 x 4 WALLS ARE ASSUMED U.N.O. ON FLOOR PLANS

* ALL LUMBER TO BE GRADE #2

** CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED

*** SP6'S & SP8'S CAN BE SUB. FOR SP4'S W/ RESPECT TO STUD SIZE



BEARING INTERIOR WALL DETAIL	
GENERAL NOTES	
1. SEE FLOOR PLAN FOR WALL SIZE. ASSUME 2x4 STUDS USED UNO.	
2. ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 UNO ON PLAN.	
3. CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED	
4. CONTACT E.O.R. IF SP4'S SP6'S OR SP8'S CONNECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS	
5. IF "BW" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORED. SEE WF06/S3.1 OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2nd FLOOR TO FIRST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY)	
6. IF "SW" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES MIN. 7/16" OSB PLYWOOD W/ 8d NAILS AT 4" O.C. IN FIELD AND EDGE TO (c) SIDE OF WALL	
7. ALL 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE ACT AS SHEARWALLS. SEE PLAN AND WALLS SECTIONS FOR STUD SPACING AND GRADE	
8. IF THE BEARING WALL IS INDICATED WITH THE BW1, BW4, BW7, BW10 THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT. THE STUDS ARE TOE NAILED TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CASED NAILS (GUN NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.	

FOOTING SCHEDULE				
MARK	SIZE	DEPTH	REINFORCING	GRAVITY CAP. (lbs)
F1.0	1'-0" X CONT.	1'-0"	2 #5 E.W. BOT.	2000
F2.0	2'-0" X 2'-0"	1'-0"	3 #5 E.W. BOT.	7200
F2.5	2'-6" X 2'-6"	1'-0"	3 #5 E.W. BOT.	11000
F3.0	3'-0" X 3'-0"	1'-0"	4 #5 E.W. BOT.	15600
F3.5	3'-6" X 3'-6"	1'-0"	4 #5 E.W. BOT.	21500
F4.0	4'-0" X 4'-0"	1'-0"	5 #5 E.W. BOT.	28000
F4.5	4'-6" X 4'-6"	1'-4"	5 #5 E.W. BOT.	34500
F5.0	5'-0" X 5'-0"	1'-4"	6 #5 E.W. BOT.	42500
F6.0	6'-0" X 6'-0"	1'-4"	7 #5 E.W. BOT.	61500

COLUMN SCHEDULE		
MARK	COLUMN SIZE	(BASE) CONN. & FASTENER
C1	(3) 2 x 4 #2 SPF	(4) - 16d TOENAILS
C2	(3) 2 x 4 #2 SPF	DT12Z W/ 1/2" WEDGE ANCHOR* & (8) 1/4" X 1 1/2" SDS SCREWS
C3	(3) 2 x 4 SYP #1 -OR-	(4) - 16d TOENAILS
C4	(4) 2 x 4 SPF #2	DT12Z W/ 1/2" WEDGE ANCHOR* & (8) 1/4" X 1 1/2" SDS SCREWS
C5	4 x 4 P.T.#2 SYP POST	ABU44 W/ 5/8" ATR** & (12) - 16d NAILS
C6	6 x 6 P.T. #2 SYP POST	ABU66 W/ 5/8" ATR** & (12) - 16d NAILS
C7	8 x 8 P.T. #2 SYP POST	ABU88 W/ (2) - 5/8" ATR** & (18) - 16d NAILS
C8	3.5 x 3.5 P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**
C9	3.5 x 3.5 P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**
C10	3.5 x 7 P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**
C11	5.25 x 5.25 P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**
C12	7 x 7 P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**
C13	5.25" x 7" P.L. 1.8E Fb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ 7/8" ATR AND (20) 1/4" x 3/4" SDS WOOD SCREWS

GENERAL COLUMN NOTES

- SEE FLOOR PLAN FOR WALL WIDTH. STUD PACKS TO MATCH WALL WIDTH UNO.
- ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 UNO ON PLAN.
- NAIL BUILT UP STUDS PER DETAIL WF37
- MINIMUM BOLT EMBEDMENT: 5" EMBEDMENT FOR 1/2" ATR 6" EMBEDMENT FOR 5/8" ATR 8" EMBEDMENT FOR 7/8" ATR
- IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL OUT ON PLAN FOR ATTACHMENT)
- SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION
- SAME NOMINAL SIZE PARALLEL COLUMNS (1.8E) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOTED IN THE PLANS**

COMMON NAIL vs. PNEUMATIC GUN NAILS:

COMMON NAIL	DIA. / LENGTH	PNEUMATIC GUN NAIL DIA-LENGTH	COMMON vs. GUN NAIL SPACING	APPLICATION
8d	0.131" X 2 1/2"	0.131" X 2 1/2"	SEE PLAN RING SHANK ON ROOF	SHEATHING ROOF & WALLS
10d OR 12d	0.148" X 3" 0.148" X 3 3/4"	0.131" X 3" 0.131" X 3 3/4"	SEE PLAN	BLOCKING & TOE NAILS & TOP PLATE
12d	0.148" X 3 3/4"	0.131" X 3 3/4"	8" O.C.(COMMON) 6" O.C.(GUN NAIL)	STUD WALL CORNERS
10d	0.148" X 3"	0.131" X 3"	8" O.C.(COMMON) 6" O.C.(GUN NAIL)	STUD PACK COLUMNS
16d	0.162" X 3 3/4"	0.131" X 3 3/4"	(2) 16d (COMMON) (3) 16d (GUN NAILS)	SEE PLAN

GENERAL FOUNDATION NOTES (U.N.O.)

- PROVIDE MIN. 6 MIL. APPROVED VAPOR BARRIER. ALL JOINTS TO BE LAPPED MIN. 6" AND SEALED.
- 2" 2500 PSI CONC. SLAB W/ 6X6 W1.4 X WL4 OR FIBERMESH FIBERMESH ADDED TO THE CONCRETE. IN ACCORDANCE W/ MANUF.'S INSTRUCTIONS AND PER 204 FOR FIBERMESH OR NER-414 FOR FIBERMESH, OVER 6 MIL VISQUEEN VAPOR BARRIER, GC SHALL PROVIDE APPROVED SOIL OR BORATE TERMITE TREATMENT.
- INDICATES FILLED CELL W/3000 PSI CONC. FROM FTR. TO BEAM W/ (1) #5 REBAR TYPICAL ABOVE SLAB. HOOKED FTG. DOWELS 17" EMBEDMENT W/ 30" EXT. ABOVE SLAB.
- CONSULT W/ MANUF. SPECIFICATIONS PRIOR TO POURING OR RECESSING DOOR SILLS OR SLIDING GLASS DOOR SILLS.
- EXTERIOR SLABS SHALL SLOPE MIN. 2% OR 1/4" PER FOOT AWAY FROM HOUSE U.N.O. ON PLAN.
- CONTROL JOINTS (IF SHOWN) ARE NOT REQUIRED BY CODE BUT ARE SUGGESTED (ESPECIALLY WHEN USING FIBER REINF. CONCRETE OR IN EXTERIOR CONDITIONS). CONTROL JOINTS TO BE 1/8" SAW CUT A DEPTH OF 1/4 OF THE THICKNESS OF THE SLAB AND SPACED MAX. 10' APART. FILL CUT W/ APPROVED JOINT MATERIAL OR USE ALTERNATE APPROVED METHOD.
- NO WOOD STAKES PERMITTED IN FOUNDATION.
- PENDING SITE CONDITIONS, FOUNDATION MAY HAVE TO BE STEPPED DOWN. G.C. TO DETERMINE STEP LOCATIONS IF REQUIRED.
- R403.1.4 MINIMUM DEPTH. EXTERIOR FOOTINGS SHALL BE PLACED NOT LESS THAN 12 INCHES BELOW THE FINISHED GRADE OF GROUND SURFACE. WHERE APPLICABLE, THE DEPTH OF FOOTINGS SHALL ALSO CONFORM TO SECTION R403.1.4.1.
- MASON TO COORDINATE WITH BUILDER ANY ELECTRICAL REQUIREMENT THROUGH SLAB
- PROVIDE 4" STEPDOWN TO SIDEWALK FROM ENTRY
- ASSUMED ALLOWABLE SOIL BEARING PRESSURE AFTER COMPACTION: 2000 PSF SEE SOILS REPORT AND SPECIFICATIONS FOR COMPACTION REQUIREMENTS IF SOIL CONDITIONS IN THE PROJECT DO NOT MEET OR EXCEED THE CAPACITY THE GENERAL CONTRACTOR SHALL CONTACT THE ENGINEER PRIOR TO FOUNDATION POUR FOR VERIFICATION OF FOUNDATION DESIGN. SOIL TO BE COMPACTED TO AT LEAST 95% OF MAX. DRY DENSITY AS DETERMINED BY ASTM - 1557 (MODIFIED PROCTOR) THE FOUNDATION SIZES INDICATED ON THE FOUNDATION PLAN HAS BEEN DESIGNED FOR A MINIMUM SOIL BEARING CAPACITY OF 2000 PSF.

HEADER SCHEDULE		
MARK	HEADER SIZE	REMARKS
H1	(2) - 2X6 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H2	(2) - 2X8 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H3	(2) - 2X10 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H4	(2) - 2X12 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H5	(2) - 1 3/4" X 11 1/4" LVL 2.0E Fb=2600 PSI	ATTACH TOGETHER W/ (2) ROWS 1/4" X 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE
H6	(2) - 1 3/4" X 9 1/4" LVL 2.0E Fb=2600 PSI	ATTACH TOGETHER W/ (3) ROWS 1/4" X 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE

HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS

OPENING SIZE	2x4 WALL JACKS EA. END	KINGS EA. END	2x6 OR 2x8 WALL JACKS EA. END	KINGS EA. END
1'-0" - 3'-11"	(1)	(2)	(1)	(2)
4'-0" - 9'-11"	(2)	(3)	(2)	(2)
10'-0" - 16'-0"	(3)	(4)	(3)	(4)

GENERAL HEADER NOTES

- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
- IF HEADER IS ON THE 1st FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INDICATIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS UNO ON PLAN
- IF HEADER IS ON THE 2nd FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS.
- ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL WF37.
- FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" o.c. ALONG EACH EDGE OR (3) ROWS IF 2x10 OR LARGER.
- FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d TOENAILS PER SIDE
- IF HEADER IS NOT SPECIFIED CONTACT E.O.R.

BEAM SCHEDULE		
MARK	BEAM SIZE	CONNECTIONS
BM1	(2) - 2 x 8 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA18 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM2	(2) - 2 x 10 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA20 TO WOOD POST OR (2) SIMPSON HTS20 TO CMU COL. U.N.O. ON ROOF PLAN.
BM3	(2) - 2 x 12 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM4	(2) - 1 3/4" x 11 1/4" LVL 2.0E Fb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE.	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM5	(2) - 1 3/4" x 11 7/8" LVL 2.0E Fb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM6	(2) - 1 3/4" x 16" LVL 2.0E Fb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.

GENERAL BEAM NOTES	
1. VERIFY WITH PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEARING EACH END)	
2. SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS	
3. BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.	

LEGEND

	- INDICATES SINGLE STORY FOOTING
	- INDICATES TWO STORY FOOTING
	- INDICATES PAD FOOTING

OSL

CA 945 9141 AL260015

Making Dreams Come True

TOTAL SOLUTIONS GROUP
 258 Southhall Lane, Suite 200
 Maitland, Florida, 32751
 (407) 800-2333
 CARL A. BROWN, PE - FL # 58126
 SCOTT LEWKOWSKI, PE - FL #78750
100% Employee Owned
 myTSHome.com

100% Employee Owned
myTSHome.com

ADAMS HOMES
 FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502
 Division Location: GAINESVILLE

Signature & Seal
 9/16/2023

Community: Preserve at Laurel Lake
 Plot Name: 2240
 Project Address: 526 SW Bellflower Dr. Lake City, FL
 Client No.:

COPIES: 35

Project No.: 3.1
DETAILS & SCHEDULES

3" VTR

1 1/2" VTR

2" VTR

3" LAV

3" W/C

4" TUB

3" DBL SINK W/D/SP.

2" CLEAN OUT

3" W/C

2" LAV


3" LAV

3" TUB

4" TO SANITARY SEWER

HANSON

2240 PLUMBING RISER



SCALE: 1/4" = 1'-0"
ELEVATION "B"

ELECTRICAL OUTLET HEIGHTS AS MEASURED FROM FINISHED FLOOR TO CENTER LINE OF THE BOX TO BE: 16" AFF. GENERAL, IN A FLOOR ZONE, ALL ELECTRICAL EQUIPMENT TO BE AT OR ABOVE DFE.

KITCHEN:

BATHROOM: 39" AFF.

LAUNDRY ROOM: 36" AFF.

EXTERIOR WATERPROOF: 12" AFF.

GARAGE — GENERAL PURPOSE 42" AFF.

RANGE: 2" AFF.

3. ALL TIE-OUTS AND DEVICES TO BE GANGED, WHERE POSSIBLE.

3. ELECTRICAL SWITCHES TO BE AT 42" CENTERLINE ABOVE FINISHED FLOOR.

4. ELECTRICAL PLAN IS INTENDED FOR RED PURPOSES ONLY. ALL WORK SHALL BE DONE IN STRICT ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) LATEST EDITION, BY A LICENSED ELECTRICAL CONTRACTOR WHO SHALL BE RESPONSIBLE FOR THE INSTALLATION & SIZING OF ALL ELECTRICAL, WIRING & ACCESSORIES.

5. SMOKE ALARMS SHALL COMPLY WITH NFPA 722 AND SECTION R314.4 AND SHALL BE LISTED IN ACCORDANCE WITH UL 217. COMBINATION SMOKE AND CARBON MONOXIDE ALARMS SHALL BE LISTED IN ACCORDANCE WITH UL 217 AND 217.2.

6. PROVIDE A/C (ARC-FAULT CIRCUIT INTERRUPTERS) COMBINATION TYPE INSTALLED TO PROVIDE PROTECTION OF ALL CIRCUITS IN ALL DWELLING UNITS PER NPA 700 (CURRENT EDITION) AND THE NEC AND AS DEFINED IN UL 1699.

7. PROVIDE TAMPER RESISTANT RECEPTACLES AS REQUIRED BY THE NFPA 700 (CURRENT EDITION).

8. CARBON MONOXIDE PROTECTORS: CARBON MONOXIDE ALARMS OR DETECTORS SHALL BE INSTALLED IN ALL DWELLING UNITS IN ACCORDANCE WITH IRC R314.5 AND NPA 700. SUCH DEVICES SHALL BE LISTED BY THE APPROPRIATE STANDARD, EITHER ANSI/UL 2034, STANDARD FOR SINGLE AND MULTIPLE STATION CO ALARMS OR UL 2075, GAS AND VAPOR DETECTOR SENSOR, ACCORDING TO THE INSTALLATION.

9. R314.5 COMBINATION ALARMS: COMBINATION SMOKE/CARBON MONOXIDE ALARMS SHALL BE LISTED AND LABELED BY A NATIONALLY RECOGNIZED TESTING LABORATORY.

10. KEEP ALL SMOKE DETECTORS MINIMUM OF 36" FROM BATHROOM DOORS.

11. IN NEW OR EXISTING, SMOKE DETECTOR SHALL BE HARDWIRED INTO AN A/C ELECTRICAL POWER SOURCE AND SHALL BE EQUIPPED WITH A MONITORED BATTERY BACKUP.

12. BATHROOM EXHAUST FANS MUST VENT TO THE EXTERIOR OF THE BUILDING, VENTILATION TO ATTIC SPACE AND TO THE EXTERIOR.

13. CHAPTER 45 PRIVATE SWIMMING POOLS — OUTDOOR SWIMMING POOLS SHALL BE PROVIDED WITH A BARRIER COMPLYING WITH R4501.2.7.1 THROUGH R4501.4.7.1.4.4.

14. ALL RECEPTACLES IN LAUNDRY ROOMS AND UTILITY ROOMS OF DWELLINGS WHEN INSTALLED WITHIN 6" OF THE OUTSIDE EDGE OF A SINK, THIS WORK INCLUDING THE RECEPTACLE INSTALLED FOR A WASHING MACHINE, RECEPTACLE OUTLETS SHALL NOT BE REQUIRED ON A WALL DIRECTLY BEHIND A RANGE OR REFRIGERATOR. RECEPTACLE OUTLETS EVERY 24" OF THE WIDTH OF THE SINK OR RANGE IS NOT TO BE INCLUDED IN THE SPACING OF THE OUTLETS UNLESS THE DISTANCE FROM THE SINK OR RANGE IS GREATER THAN 12" FOR STRAIGHT COUNTER TOPS AND 18" FOR SINKS AND RANGES INSTALLED IN CORNER COUNTERS.

15. ALL RECEPTACLES INSTALLED IN DWELLING UNITS SHALL BE INSTALLED IN AN INDIVIDUAL DWELLING UNIT IN ACCORDANCE WITH SECTION R314.3, THE ALARM DEVICES SHALL BE INTERCONNECTED IN SUCH A MANNER THAT THE ACTIVATION OF ONE ALARM WILL ACTIVATE ALL OF THE ALARMS IN THE INDIVIDUAL DWELLING UNIT. PHYSICAL INTERCONNECTING OF THE ALARMS IS NOT REQUIRED WHERE LISTED. ALL SMOKE ALARMS ARE TO BE LISTED AND ALL ALARMS SOUND UPON ACTIVATION OF ONE ALARM.

16. FOR ONE- AND TWO-FAMILY DWELLING UNITS, ALL SERVICE DISCONNECTS SHALL TERMINATE IN PHYSICAL SEPARATION FROM THE MAIN PANEL AND BE LOCATED OUTSIDE THE MAIN PANEL OR PANEL CURRENTLY INSTALLED IN A READILY ACCESSIBLE OUTDOOR LOCATION, EACH DISCONNECT SHALL BE ONE OF THE FOLLOWING:

(1) SERVICE DISCONNECTS MARKED AS FOLLOWS:

EMERGENCY DISCONNECT

SERVICE DISCONNECT

(2) METER DISCONNECTS INSTALLED PER 230 82(3) AND MARKED AS FOLLOWS:

EMERGENCY DISCONNECT

METER DISCONNECT

NO SERVICE EQUIPMENT

(3) OTHER DISCONNECT SWITCHES OR CIRCUIT BREAKERS ON THE SUPPLY SIDE OF EACH SERVICE DISCONNECT THAT ARE SUITABLE FOR USE AS SERVICE EQUIPMENT AND MARKED AS FOLLOWS:


EMERGENCY DISCONNECT

NO SERVICE EQUIPMENT

MARINGS SHALL COMPLY WITH 210.2(14B).

17. ALL PERMANENTLY INSTALLED LUMINAIRES, EXCLUDING THOSE IN KITCHEN APPLIANCES, SHALL HAVE AN EFFICACY OF AT LEAST 45 LUMENS/PERWATT, SHALL UTILIZE LAMPS WITH AN EFFICACY OF NOT LESS THAN 65 LUMENS/PER-WATT.

	SINGLE POLE SWITCH		SMOKE DETECTOR
	DOUBLE POLE SWITCH		CARBON MONOXIDE/ SMOKE DETECTOR
	THREE-WAY SWITCH		COMBO UNIT
	FOUR-WAY SWITCH		FLOOD LIGHT
	DIMMER SWITCH		FLUORESCENT LIGHTING
	CEILING MOUNTED FIXTURE		TRACK LIGHTING
	SCOUNCE (WALL MOUNTED) FIXTURE		CEILING FAN
	110 VOLT DUPLEX OUTLET		DOOR BELL CHIMES
	110 VOLT SPLIT SWITCHED OUTLET		DOOR BELL
	GROUND FAULT INTERRUPT		DISPOSAL
	WATER PROOF W/ GROUND FAULT		DISCONNECT SWITCH
	220 VOLT OUTLET		PREWIRE SPEAKER
	SPECIAL SERVICES OUTLET		JUNCTION BOX
	T.V. CABLE OUTLET		THERMOSTAT
	TELEPHONE CABLE OUTLET		LOW VOLTAGE LIGHTING
	RECESSED LIGHTING		INTERCOM SYSTEM
	WATER PROOF RECESSED LIGHTING		GARAGE DOOR PUSH BUTTON
	BATH FAN		
	BATH FAN W/ LIGHT		
	L.E.D. DISC LIGHT		



ELECTRICAL

TSG

AA#26203115
CA#16-9161

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 800-2333
CARLA A. BROWN, PE - FL #56126
SCOTT LEWIKOWSKI, PE - FL #78760

100% Employee Owned
myTSGhome.com

Making Dreams Come True




MUNICIPAL STAMP AREA


SIGNATURE & SEAL
9/16/2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.


 DAMS HOMES FLORIDA CONTRACTORS LICENSE NO. CRC1330146 100 WEST GARDEN STREET PENSACOLA FL 32502	Division Location: GAINESVILLE
--	---

LOT: 35	B.L.K.	UNIT:
Community:		
Preserve at Laurel Lake		
Plan Name:		
2240		
Project Address:		
2240 Laurel Flower Dr.		
Laurel Lake City, FL		
Client No.:		







BD12 TYPICAL WALL SECTION 3/4" = 1'-0"




WF37 TYPICAL COLUMNS DETAILS N.T.S.




WF17 TOP PLATE SPLICE DETAIL 3/4" = 1'-0"




CD24 POST & BEAM DETAIL 1/2" = 1'-0"




SW01 INTERIOR BEARING SHEARWALL w/UPLIFT N.T.S.




BD07 BRICK SHELF DETAIL N.T.S.




WC08 STEP UP @ CORNER & RAISED BEAM N.T.S.




SE TYPICAL SOFFIT AND EAVE DETAIL 3/4" = 1'-0"



WF63 SECTION AT DOUBLE BEARING N.T.S.



WC07 STEP UP @ CORNER & RAISED BEAM 1/2" = 1'-0"



SW04 INTERIOR SHEARWALL @ TRUSSES 3/4" = 1'-0"


TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 800-2333
CARL A. BROWN, PE - FL # 56126
SCOTT LEVKOWSKI, PE - FL # 78750
100% Employee Owned
myTSGhome.com

Signature & Seal
9/16/2025
To the best of the Engineer's knowledge, information and belief, the structure, plans and specifications contain within these drawings comply with the 2023 Florida Building Code, Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.


DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502
Division Location: GAINESVILLE

Project Information
Community: Preserve at Laurel Lake
Plan Name: 2240
Project Address: 100 West Garden Dr, Pensacola, FL 32502
Client Name: [Redacted]

Project Details
Project No: [Redacted]
Sheet No: **S-3**
TYPICAL WALL DETAILS




TB01 TYPICAL CROSS BRACING DETAIL N.T.S.




TB02 TYPICAL CROSS BRACING DETAIL N.T.S.


THE HEIGHT OF THE CHIMNEY SHOULD EXTEND 2' ABOVE THE POINT WHERE THE CHIMNEY IS 10' FROM THE NEAREST BUILDING SURFACE.




CH01 TYPICAL CHIMNEY FRAME DETAIL 3/4" = 1'-0"




TB17 CONV. FRAMING & VALLEY FRAMING N.T.S.




TB03 HIP / RIDGE BLOCKING DETAIL N.T.S.



TB04 TRUSS BRACING OVERLAP DETAIL (TYP) N.T.S.






GE04 "T" BRACE CONNECTION @ GABLE END W/ VOLUME CEILING 3/4" = 1'-0"




WF05 DORMER FRAMING DETAIL N.T.S.

TRUSS NOTES:

- 1. WOOD TRUSS ERECTOR SHALL PROVIDE BRACING ACCORDING TO ANSI/TPI-2014 (TRUSS PLATE INSTITUTE) NOTE THAT THE COMBINED WIND AREA IS GREATER BEFORE THE ROOF SHEATHING IS APPLIED, AND BRACING SHALL THEREFORE BE INSTALLED AS THE TRUSSES ARE ERECTED. INADEQUATE BRACING IS THE MOST COMMON CAUSE OF ACCIDENT IN WOOD TRUSS CONSTRUCTION. FULL BUILDERS OR SHEATHING SHALL NOT BE PLACED ON TRUSSES. THIS CONSTRUCTION LOAD SHOULD BE LIMITED TO 8 SHEETS OF SHEATHING ON ANY PAIR OF TRUSSES & SHALL BE LOCATED ADJACENT TO THE SUPPORTS. NO EXCESS CONCENTRATION OF ANY CONSTRUCTION MATERIAL (SUCH AS CORBEL OR SHINGLES) SHALL BE PLACED ON THE TRUSSES IN ANY ONE AREA THEY SHALL BE SPREAD OUT EVENLY OVER A LARGE AREA SO AS TO AVOID OVERLOADING ANY ONE TRUSS.
- 2. ALL BRACING (DE CB,BB) SHOWN ABOVE SHALL BE IN ADDITION TO CONTINUOUS LATERAL BRACING SPECIFIED BY THE TRUSS MANUFACTURER. ALL LATERAL BRACING SPECIFIED BY TRUSS MANUFACTURER SHALL HAVE ADDITIONAL DIAGONAL BRACES AT 20'-0" O.C. MAXIMUM.
- 3. ALL BRACES SHALL BE 2x4 NOMINAL DIMENSION LUMBER & SHALL BE ATTACHED W/ (3) 12d NAILS AT EACH TRUSS INTERSECTION.
- 4. ADDITIONAL BOTTOM CHORD BRACING SHALL BE INSTALLED AS REQUIRED BY TRUSS DESIGN WHEREVER ADEQUATE STRUCTURAL CEILING ARE NOT ATTACHED DIRECTLY TO THE BOTTOM CHORD OF THE TRUSS.
- 5. PROVIDE TRUSS BLOCKING AT ALL TRUSS BEARING SUPPORTS WHERE TRUSS DEPTH EXCEEDS STANDARD HEEL HEIGHT. SEE TYP. TRUSS BLOCKING DETAILS



TYP. WOOD TRUSS BLOCKING @ RAISED HEEL DETAIL



A-A ALTERNATE BLOCKING DETAIL @ INTERIOR BEARING

TB06 BLOCKING AND CONVENTIONAL FRAME DETAILS 3/4" = 1'-0"

tsG TOTAL SOLUTIONS GROUP 258 Southhall Lane, Suite 200 Maitland, Florida, 32751 (407) 800-2333 CARL A. BROWN, PE - FL #56126 SCOTT LEWKOWSKI, PE - FL #78750 100% Employee Owned myTSGhome.com

ATA fhba GO BA

MUNICIPAL STAMP AREA


SIGNATURE & SEAL 9/16/2023

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code, Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.


ADAMS HOMES FLORIDA CONTRACTORS LICENSE NO. CRC1330146 100 WEST GARDEN STREET PENSACOLA FL 32502 Gainesville

Community: Preserve at Laurel Lake Plot Name: 2240 Project Address: 825 SW Bellflower Dr. Lake City FL Client No.:


Project No: S-4 ROOF FRAMING AND BRACING DETAILS




GE05 GABLE END BRACING - FRAME WALL N.T.S.




GE22 GABLE END BRACING w/ VOL CEILING 1/2"=1'-0"




GE23 GABLE END BRACING w/o VOLUME CEILING 1/2"=1'-0"




GE24 GABLE @ VAULT N.T.S.




WF72 LEDGER N.T.S.




WF73 KNEEWALL @ DORMER N.T.S.





GE21 SECTION @ DUTCH GABLE 3/4" = 1'-0"




LD02 SHEAR TRANSFER EXTERIOR WALL N.T.S.



GE23.1 GABLE END OVERHANG 1/2"=1'-0"



SR01 SECTION AT SHED ROOF 3/4" = 1'-0"



GE15 FALSE BEAM AT GABLE END N.T.S.

