


<div>TERMITE SPECIFICATIONS:</div> <div><p>R318.1 TERMITE PROTECTION SHALL BE PROVIDED BY REGISTERED TERMITICIDES, INCLUDING SOIL APPLIED PESTICIDES, BAITING SYSTEMS, AND TREATMENT APPLIED TO WOOD, OR OTHER APPROVED METHODS OF TERMITE PROTECTION LABELED FOR USE AS A PREVENTATIVE TREATMENT TO NEW CONSTRUCTION (SEE SECTION 202 , REGISTERED TERMITICIDE), UPON COMPLETION OF THE APPLICATION OF THE TERMITE PROTECTIVE TREATMENT, A CERTIFICATE OF COMPLIANCE SHALL BE ISSUED TO THE BUILDING DEPARTMENT BY THE LICENSED PEST CONTROL COMPANY THAT CONTAINS THE FOLLOWING STATEMENT: "THE BUILDING HAS RECEIVED A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES. TREATMENT IS IN ACCORDANCE WITH RULES AND LAWS ESTABLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES."</p><p>NOTES:</p><ol style="list-style-type: none"><li>METHOD OF TREATMENT SHALL BE APPROVED BY THE GOVERNING JURISDICTION "LIQUID BORATE OR BOR-A-COR" PRODUCT METHODS MUST BE DETERMINED AT PERMIT STAGE AND PRODUCT APPROVAL DATA MUST BE ON FILE WITH THE BUILDING DEPARTMENT</li><li>PRESSURE TREATED LUMBER THAT HAS BEEN CUT OR DRILLED THAT EXPOSES UNTREATED PORTIONS OF WOOD ARE REQUIRED TO BE FILLED TREATED TO PREVENT INSECT INFESTATION</li><li>OPTIONAL BORATE APPLIED TO ALL FRAME MEMBERS WITHIN 24" A.F.F.</li></ol></div>		<div>STRUCTURAL NOTES:</div> <div><div>CAST IN PLACE CONCRETE</div><ol style="list-style-type: none"><li>ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 2500 PSI (SLABS) 3000 PSI (COLUMNS AND BEAMS), A SLUMP OF 5" PLUS OR MINUS 1", AND HAVE 2 TO 5% AIR ENTRAINMENT, AND A MAXIMUM WATER/CEMENT RATIO OF 0.63.</li><li>HOOKS SHALL BE PROVIDED AT DISCONTINUOUS ENDS OF ALL TOP BARS OF BEAMS.</li><li>HORIZONTAL FOOTING BARS SHALL BE BENT 25° AROUND CORNERS OR CORNER BARS WITH A 25" LAP PROVIDED EACH WAY.</li><li>CONCRETE COVER MIN. 3" WHEN EXPOSED TO EARTH OR 1 1/2" TO FORM &amp; NO CONCRETE.</li><li>WELDED WIRE FABRIC SHALL CONFORM TO ASTM A1064/ A1064M. WWF SHALL BE LAPPED AT LEAST 6" AND CONTAIN AT LEAST ONE CROSS WIRE WITHIN THE 6", OR POLYPROPYLENE FIBERS FOR SLABS ON GRADE TO BE MIN. 75 LBS OF FIBER PER CUBIC YARD.</li><li>ALL REINFORCING STEEL / STIRRUPS AND TIES SHALL BE NEW DOMESTIC DEFORMED BARS FREE FROM RUST SCALE &amp; OIL, &amp; SHALL MEET ASTM 615, ASTM A706, OR ASTM A996 GRADE 40 U.N.O. REINFORCING FOR FOOTING SHALL BE SUPPORTED ON PRE-CAST CONCRETE PADS, STEEL WIRE OR PLASTIC SUPPORTS. TOP REINFORCING SHALL BE POSITIVELY SUPPORTED BY TEMPORARY STRIKERS, DOWELS FOR COLUMNS &amp; FILLED CELLS SHALL BE SECURED IN PLACE BY USING ADDITIONAL CROSS-REINFORCING TIE TO FOOTING REINFORCING. SPLICES IN REINFORCING WHERE PERMITTED SHALL BE AS PER DETAIL MS05/S-1. SEE PLAN SET.</li><li>HIGH STRENGTH SIMPSON SET EPOXY TIE ANCHORING ADHESIVE WAS USED IN THE DESIGN OF THIS PRODUCT. IF CONTRACTORS WISH TO USE A DIFFERENT EPOXY, THEY MUST FIRST CONTACT THE ENGINEER OF RECORD FOR WRITTEN APPROVAL.</li><li>WHERE PROJECT IS TO BE LOCATED IN KNOWN RADON GAS PREVALENT AREAS, APPENDIX "F" OF THE FLORIDA BUILDING CODE 8th. EDITION (2023) IS TO BE IMPLEMENTED. F303.4.1 CONCRETE STRENGTH IN THESE AREAS ARE TO BE A MINIMUM OF 3000 P.S.I. THEREFORE, ANY AND ALL NOTES ON THESE PLANS THAT INDICATE 2500 P.S.I. SHALL BE REPLICED WITH 3000 P.S.I. FOR THE CONCRETE STRENGTH.</li></ol></div> <div><div>MASONRY WALL CONST.</div><ol style="list-style-type: none"><li>HOLLOW LOAD BEARING UNITS SHALL BE NORMAL WEIGHT, GRADE N, TYPE 2, CONFORMING TO ASTM C90-2016A, WITH A MINIMUM NET COMPRESSIVE STRENGTH OF 2000 PSI (f<sub>m</sub> = 2000 PSI)</li><li>MORTAR SHALL BE TYPE "S", CONFORMING TO ASTM C270-14A.</li><li>COARSE GROUT SHALL CONFORM TO ASTM C476-19 WITH A MAXIMUM AGGREGATE SIZE OF 3/8" AND A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 3000 PSI SLUMP 8" TO 11". CONTINUOUS MASONRY INSPECTIONS ARE REQUIRED DURING CONSTRUCTION.</li><li>GRADE 40 U.N.O. VERTICAL REINFORCEMENT SHALL BE AS NOTED ON THE DRAWINGS WITH THE CELLS FILLED WITH COARSE GROUT.</li><li>REINFORCING STEEL SHALL BE LAPPED PER DETAIL MS05/S-1, UNLESS OTHERWISE NOTED ON THE DRAWINGS.</li><li>GROUT STOPS SHALL BE PROVIDED BELOW BOND BEAD PLASTIC SCREEN. METAL LATH STRIP OR CAVITY CAPS MAY BE USED TO PREVENT THE FLOW OF GROUT INTO CELLS BELOW. THE USE OF FELT PAPER AS A STOP IS PROHIBITED.</li><li>TEMPORARY BRACING AND SHORING OF WALL TO PROVIDE STABILITY DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR</li><li>TYPICAL FILLED CELL REINFORCING SIZE AND SPACING SHALL BE ABOVE AND BELOW ALL WALL OPENINGS.</li><li>DO NOT APPLY UNIFORM LOADS TO MASONRY WALLS FOR (3) DAYS AND NO CONCENTRATED LOADS FOR (7) DAYS. PER CODE ACI 318-19.</li><li>CONSOLIDATE AND RECONSOLIDATE GROUT POURS PER CODE. GROUT SHALL BE FLUSH WITH TOP OF WALL.</li></ol></div>	
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--

 STRUCTURAL DESIGN CRITERIA  CODE CRITERIA   - FLORIDA BUILDING CODE 8TH EDITION (2023) RESIDENTIAL - FLORIDA FIRE PREVENTION CODE 8TH EDITION (2023) - FLORIDA BUILDING CODE ACCESSIBILITY 8TH EDITION (2023) RESIDENTIAL - NFPA 70-20, NATIONAL ELECTRICAL CODES (NEC 2020) - BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE — (ACI 318-19) - SPECIFICATIONS FOR STRUCTURAL CONCRETE — (ACI 308-20) - BUILDING CODE REQUIREMENTS FOR MASONRY STRUCTURES — (ACI 530-13) - NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION — 2018 EDITION - WOOD FRAMED CONSTRUCTION MANUAL 2018 EDITION - APA PLW/WOOD DESIGN SPECIFICATION E30-19 - AMERICAN SOCIETY OF CIVIL ENGINEERS, ASCE /SEI 7-22 - ALUMINUM DESIGN MANUAL — AAF-20 (AA ADM-2020)  - CODE REQUIREMENTS: IT IS THE INTENT THAT ALL WORK SHALL CONFORM TO THE ADOPTED CODES, STANDARDS AND RULES OF THE ADMINISTRATIVE AUTHORITY HAVING JURISDICTION. - ALL WORK SHALL CONFORM WITH DRAWINGS AND SPECIFICATIONS IN ACCORDANCE WITH THE REQUIREMENTS OF ALL THE FOLLOWING WHERE APPLICABLE: (A) GOVERNING MUNICIPAL AND REGULATORY AGENCIES (B) LOCAL STATE AND FEDERAL BODIES  DEFLECTION CRITERIA   |                         |        |        |           | |-------------------------|--------|--------|-----------| | ROOF TRUSSES*           | LL/360 | TL/240 | COMMENTS: | | ROOF RAFTERS            | LL/180 | TL/120 |           | | ROOF RAFTERS (W/O CLG.) | LL/360 | TL/240 |           | | FLOOR TRUSSES*/BEAMS ** | LL/360 | TL/240 |           | | FLOOR JOIST ***         | LL/480 | TL/240 |           |   \*TL MAX 2" UP TO 40FT SPAN \*\*TL MAX 3/4" \*\*\*TL MAX 1/2"  \*\*\*\*TL MAX 1/4" DIFFERENTIAL BETWEEN ADJACENT TRUSSES  GENERAL ROOF LOADING   |                  | SHINGLE/METAL ROOF (PSF) | FLAT ROOF (PSF) | TILE ROOF (PSF) | HEAVY ROOF (PSF) | |------------------|--------------------------|-----------------|-----------------|------------------| | TOP CHORD LL     | 20                       | 10              | 20              | 20               | | TOP CHORD DL     | 10                       | 30              | 15              | 25               | | BOTTOM CHORD LL* | 0                        | 0               | 0               | 0                | | BOTTOM CHORD DL  | 10                       | 10              | 10              | 10               | | TOTAL (PSF)      | 40                       | 50              | 45              | 55               |   TOP CHORD LL (OPT) ATTICS W/ LIMITED STORAGE 20 ATTICS W/ HEAVY STORAGE 50 \* ATTICS W/ NO STORAGE 10 (NON-CONCURRENT)  NOTE: LL REDUCTIONS ARE ALLOWED PER CODE BUT ONLY WITH WRITTEN APPROVAL FROM EOR OR INDICATED ON PLAN  GENERAL FLOOR LOADING   |                 |          |           | |-----------------|----------|-----------| | TOP CHORD LL    | 40 (PSF) | COMMENTS: | | TOP CHORD DL    | 10 (PSF) |           | | BOTTOM CHORD LL | 0 (PSF)  |           | | BOTTOM CHORD DL | 5 (PSF)  |           |  SPECIAL FLOOR LOADING   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                         |                     | |-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------|---------------------| | COMMENTS:                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | GAME ROOM                               | 60 (PSF)            | | (PSF) = UNIFORM LOADS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | BALCONIES/ DECKS                        | 40 (PSF)            | | (LBS) = CONCENTRATED LOADS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | BALCONIES OVER 100 SQ-FT                | 100 (PSF)           | |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | LIGHT STORAGE                           | 125 (PSF)           | | c. INDIVIDUAL STAIR TREADS SHALL BE CAPABLE OF SUPPORTING THE UNIFORMLY DISTRIBUTED LIVE LOAD OR A 300-POUND CONCENTRATED LOAD APPLIED ON AN AREA OF 2 INCHES BY 2 INCHES, WHICHEVER PRODUCES THE GREATER STRESSES                                                                                                                                                                                                                                                                                                                  | LIBRARIES READING ROOMS                 | 60 (PSF)            | |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | LIBRARIES STACK ROOMS                   | 150 (PSF)           | | d. A SINGLE CONCENTRATED LOAD APPLIED IN ANY DIRECTION AT ANY POINT ALONG THE TOP, FOR A GUARD NOT REQUIRED TO SERVE AS A HANDRAIL, THE LOAD NEED NOT BE APPLIED TO THE TOP ELEMENT OF THE GUARD IN A DIRECTION PARALLEL TO SUCH ELEMENT                                                                                                                                                                                                                                                                                            | HANDRAILS (i)                           | 200 (LBS) (h,i)     | |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | GUARD RAILS IN FILL COMP. (f)           | 200 (PSF) (h)       | |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | STAIRS                                  | 40 (PSF) 300 (LBS)  | |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | SLON SLEEPING ROOMS                     | 40 (PSF)            | |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | HABITABLE ATTICS SERVED W/ FIXED STAIRS | 30 (PSF)            | |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | PASSENGER VEHICLE GARAGES               | 50 (PSF) 2000 (LBS) | | f. BALUSTRADE AND PANELS FILLERS SHALL BE DESIGNED TO WITHSTAND A HORIZONTALLY APPLIED NORMAL LOAD OF 50 POUNDS ON AN AREA EQUAL TO 1 SQ. FT.                                                                                                                                                                                                                                                                                                                                                                                       |                                         |                     | | h. INTERSECTION OF HANDRAIL ASSEMBLIES AND GUARDS SHALL BE DESIGNED WITH A LOAD ADJUSTMENT FACTOR OF 4. THE LOAD ADJUSTMENT FACTOR SHALL BE APPLIED TO EACH OF THE CONCENTRATED LOADS APPLIED TO THE TOP OF THE RAIL, AND TO THE LOAD ON THE IN-FILL COMPONENTS. THESE LOADS SHALL BE DETERMINED INDEPENDENT OF ONE ANOTHER, AND LOADS ARE ASSUMED NOT TO OCCUR WITH ANY OTHER LIVE LOAD.                                                                                                                                           |                                         |                     | | i. WHERE THE TOP OF A GUARD SYSTEM IS NOT REQUIRED TO SERVE AS A HANDRAIL, THE SINGLE CONCENTRATED LOAD SHALL BE APPLIED AT ANY POINT ALONG THE TOP, IN THE VERTICAL DOWNWARD DIRECTION AND IN THE HORIZONTAL DIRECTION AWAY FROM THE WALKING SURFACE. WHERE THE TOP OF A GUARD IS ALSO SERVING AS THE HANDRAIL, A SINGLE CONCENTRATED LOAD SHALL BE APPLIED IN ANY DIRECTION AT ANY POINT ALONG THE TOP. CONCENTRATED LOAD SHALL NOT BE APPLIED CONCURRENTLY ANOTHER, AND LOADS ARE ASSUMED NOT TO OCCUR WITH ANY OTHER LIVE LOAD. |                                         |                     |  CARE AND MAINTENANCE  YEARLY MAINTENANCE AND INSPECTIONS BY THE BUILDER/HOMEOWNER ARE NECESSARY FOR THE FUTURE LIFE OF THIS HOME. CARE MUST BE TAKEN TO CHECK WINDOWS AND DOORS FOR CAULKING, REMOVE LEAVES AND DEBRIS OFF ROOFS, MAKE SURE THAT WATER FLOW IS AWAY FROM THE HOUSE AND HAVE YOUR HOME REPAINTED EVERY 3 — 5 YEARS TO PROTECT THE COATINGS. THE DESIGNER AND ENGINEER OF RECORD ARE NOT RESPONSIBLE FOR THE UPKEEP OF THE HOME AND WILL NOT BE HELD LIABLE FOR INSTANCES THAT MAY OCCUR OVER THE NORMAL LIFE OF THE HOME WITHOUT PROPER MAINTENANCE. | | INDEX OF DRAWINGS   | SHT # | TITLE                | |-------|----------------------| | 1     | COVER SHEET          | | 2     | 1st FLOOR PLAN       | | 2.1   | 2nd FLOOR PLAN       | | 3     | FOUNDATION PLAN      | | 4     | ELECTRICAL PLAN      | | 5     | ELEVATIONS           | | S-1   | TRUSS LAYOUT         | | S-1.1 | FLOOR FRAMING LAYOUT | | S-2   | DETAILS              | | S-2.1 | DETAILS</            | | |



BEARING WOOD INTERIOR WALL SCHEDULE					
MARK	STUD SPACING	CONNECTION & FASTENERS		LUMBER SPECIES	UPLIFT CAP (#/F)
		TOP	BOTTOM		
BW1	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
BW2	16"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SPF	402
BW3	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	571
BW4	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
BW5	16"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SYP	439
BW6	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	665
BW7	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
BW8	12"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SPF	535
BW9	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	760
BW10	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
BW11	12"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SYP	585
BW12	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	885

NOTE: 2 x 4 WALLS ARE ASSUMED U.N.O. ON FLOOR PLANS  
\* ALL LUMBER TO BE GRADE #2  
\*\* CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED  
\*\*\* SPFS & SPFS CAN BE SUB. FOR SPFS W/ RESPECT TO STUD SIZE



BEARING INTERIOR WALL DETAIL

- ### GENERAL NOTES
- SEE FLOOR PLAN FOR WALL SIZE, ASSUME 2x4 STUDS USED U.N.O.
  - ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 U.N.O. ON PLAN.
  - CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
  - CONTACT E.O.R. IF SPS S, SPFS S OR SPFS S CONNECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
  - IF "BW" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORED. SEE W/05/33 OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2nd FLOOR TO FIRST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY)
  - IF "SW" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES MIN. 1/4" OSB PLYWOOD W/ 16d NAILS AT 11" O.C. IN FIELD AND EDGE TO 11" SIDE OF WALL.
  - ALL 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE ACT AS SHEARWALLS. SEE PLAN AND WALLS SECTIONS FOR STUD SPACING AND GRADE.
  - IF THE BEARING WALL IS NOTICED WITH THE BWL, BWL, BWL, BWL THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT. THE STUDS ARE TOE FASTENED TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CASED NAILS (GUN NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.

MARK	COLUMN SIZE	(BASE) CONN. & FASTENER	UPLIFT(Lb)
C1	(3) 2 x 4 #2 SPF	(4) - 16d TOENAILS	0
C2	(3) 2 x 4 #2 SPF	DT122 W/ 1/2" WEDGE ANCHOR & (8) 1/4" X 1 1/2" SDS SCREWS	2145
C3	(3) 2 x 4 SYP #1 GR.	(4) - 16d TOENAILS	0
C4	(4) 2 x 4 SPF #2	DT122 W/ 1/2" WEDGE ANCHOR & (8) 1/4" X 1 1/2" SDS SCREWS	2145
C5	4 x 1 P.T. #2 SYP POST	AD144 W/ 5/8" ATR** & (12) - 16d NAILS	G = 6665 U = 2200
C6	6 x 6 P.T. #2 SYP POST	AB166 W/ 5/8" ATR** & (12) - 16d NAILS	G = 12000 U = 2890
C7	8 x 8 P.T. #2 SYP POST	AB188 W/ (2) - 5/8" ATR** & (18) - 16d NAILS	G = 24335 U = 2320
C8	3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
C9	3.5 x 5.25 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
C10	3.5 x 7 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	6970
C11	5.25 x 5.25 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870
C12	7 x 7 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870
C13	5.25" x 7" P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ 7/8" ATR AND (20) 1/4" x 1/2" SDS WOOD SCREWS	7870

- ### GENERAL COLUMN NOTES
- SEE FLOOR PLAN FOR WALL WIDTH, STUD PICKS TO MATCH WALL WIDTH U.N.O.
  - ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 U.N.O. ON PLAN.
  - NAIL BUILD UP STUDS PER DETAIL W/37
  - MINIMUM BOLT EMBEDMENT:
    - 5" EMBEDMENT FOR 1/2" ATR
    - 6" EMBEDMENT FOR 5/8" ATR
    - 8" EMBEDMENT FOR 7/8" ATR
  - IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL OUT ON PLAN FOR ATTACHMENT)
  - SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION
  - SAVE NOMINAL SIZE PARALLEL COLUMNS (LSE) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOTED IN THE PLANS

COMMON NAIL	DIA. / LENGTH	PNEUMATIC GUN NAIL DIA. LENGTH	COMMON vs. GUN NAIL DIA. LENGTH	APPLICATION
B1	0.131" X 2 1/2"	0.131" X 2 1/2"	SEE PLAN RING SHAWL ON ROOF	SHEATHING ROOF & WALLS
10d OR 12d	0.148" X 3"	0.131" X 3"	SEE PLAN	BLOCKING & TOE NAILS & TOP PLATE
12d	0.148" X 3 1/4"	0.131" X 3 1/4"	8" O.C. (COMMON)	STUD WALL CORNERS
10d	0.148" X 3"	0.131" X 3"	8" O.C. (COMMON)	STUD PICK COLUMNS
16d	0.162" X 3 1/2"	0.131" X 3 1/4"	(2) 16d (COMMON)	SEE PLAN


HEADER SCHEDULE		
(IF USED, SEE DET. "H" ON SHEET S-2 FOR ENERGY STAR INSULATION ON HEADERS)		
MARK	HEADER SIZE	REMARKS
H1	(2) - 2X6 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H2	(2) - 2X8 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H3	(2) - 2X10 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H4	(2) - 2X12 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H5	(2) - 1 3/4" X 11 1/4" LVL 2.0E Fb-2600 PSI	ATTACH TOGETHER W/ (3) ROWS 14" X 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE
H6	(2) - 1 3/4" X 9 1/4" LVL 2.0E Fb-2600 PSI	ATTACH TOGETHER W/ (3) ROWS 14" X 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE

HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS				
OPENING SIZE	2x4 WALL		2x6 OR 2x8 WALL	
	JACKS EA. END	KINGS EA. END	JACKS EA. END	KINGS EA. END
1'-0" - 3'-11"	(1)	(2)	(1)	(2)
4'-0" - 9'-11"	(2)	(3)	(2)	(3)
10'-0" - 16'-0"	(3)	(4)	(3)	(4)

- ### GENERAL HEADER NOTES
- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
  - IF HEADER IS ON THE 1st FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS U.N.O. ON PLAN
  - IF HEADER IS ON THE 2nd FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS
  - ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL W/37
  - FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" o.c. ALONG EACH EDGE OR (3) ROWS IF 2x10 OR LARGER.
  - FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d TOENAILS PER SIDE
  - IF HEADER IS NOT SPECIFIED CONTACT E.O.R.


MARK	BEAM SIZE	CONNECTIONS
BM1	(2) - 2 x 8 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA18 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM2	(2) - 2 x 10 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM3	(2) - 2 x 12 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM4	(2) - 1 3/4" x 11 1/4" LVL 2.0E Fb-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM5	(2) - 1 3/4" x 11 7/8" LVL 2.0E Fb-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM6	(2) - 1 3/4" x 16" LVL 2.0E Fb-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.

- ### GENERAL BEAM NOTES
- VERIFY WITH PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEARING EACH END)
  - SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
  - BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.



Y	N	MASTER BA. OPTIONS
X		3040 (1) PC. FIBERGLASS SHOWER IN LIEU OF LINEN CLOSET W/ (1) L.E.D. LT.

OPT. MASTER BATH  
SCALE: 1/4" = 1'-0"



1ST FLOOR PLAN  
SCALE: 1/4" = 1'-0"  
ALL ELEVATIONS

NOTE:  
INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

### WALL LEGEND

- FRAMED WALL
- BEARING FRAME WALL
- FRAMED WALL W/ BRICK VENEER
- FRAMED WALL W/ SIDING OR STUCCO

### GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used I.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycomb core steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surfaces and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
- Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.2.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below on the exterior of the building, the operable window shall comply with one of the following:
  - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
  - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
  - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC. R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
- M1502.4.5 Duct length  
The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3  
M1502.3 Duct termination.  
Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
- Porch Ceilings: (See plan for the following options)  
Option 1: Gypsum:  
1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.  
The gypsum board shall be attached W/ Type "W" 1x4 drywall screws at 8" O.C. in field and edges.  
Option 2: Plywood Soffit:  
7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
- Energy Code Compliance Path is Performance Based Path. Code cycle is FBC 2023 8th Edition.

\* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

### AREA CALCULATIONS

1st FLOOR	1287 S.F.
2nd FLOOR	1434 S.F.
TOTAL LIVING (AC)	2721 S.F.
GARAGE	469 S.F.
COVERED ENTRY (BASE)	103 S.F.
COVERED PATIO/LANAI	140 S.F.
TOTAL AREA UNDER ROOF	3433 S.F.

COUNTY SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.  
CA No. 9161 AA26003115

**TOTAL SOLUTIONS GROUP**  
258 Southhall Lane, Suite 200  
Maitland, Florida, 32751  
(407) 880 2333

100% Employee Owned  
myTSGhome.com

**DAMS HOMES**  
FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
**100 WEST GARDEN STREET**  
**PENSACOLA FL 32502**

DIVISION LOCATION:

Job Information:

**INVENTORY**

LOT: 93  
BLK:  
SEC:  
SUB: Preserve at Laurel Lake  
761 SW Rosemary Dr  
Lake City, FL

Model Name / Number:

2705

Plan Issue Date:  
Friday, January 31, 2025

KA PROJECT NUMBER:

24-13140

Sheet: 2 Of:

1ST FLOOR PLAN

Friday, January 31, 2025
















SCALE: 1/4" = 1'-0"

ALL ELEVATIONS



VENTILATION CALCULATION		
Soffit product provides	4.12	net sq in / sf
Ridge vent provides	18.00	net sq in / lf
Off ridge vent provides	138.00	net sq in / sf
Overhang distance	2.00	ft
S.F. of Area to be vented (SF)	1480	s.f.
Total needed for exhaust for upper 1/3	355	net sq inches
Total needed for intake (soffit area, lower)	355	net sq inches
Number of Off Ridge Vents for upper 1/3 needed	3	
L.F. of Ridge Vent needed (can be used in combo with ORV)	20	
Lineal Feet of Soffit needed to meet required	43	
Lineal S.F. provided by plan	78	

COUNTY  
SEAL

Friday, January 31, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code: Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP  
258 Southhall Lane, Suite 200  
Maitland, Florida, 32751  
(407) 880 2333

100% Employee Owned  
myISGhome.com

**DAMS HOMES**  
FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
**100 WEST GARDEN STREET  
PENSACOLA FL 32502**

DIVISION LOCATION:

Job Information:

INVENTORY

LOT: 93  
BLK:  
SEC:  
SUB: Preserve at Laurel Lake  
761 SW Rosemary Dr  
Lake City, FL

Model Name / Number:

2705

Plan Issue Date:

Friday, January 31, 2025

KA PROJECT NUMBER:

24-13140

Sheet:

5

Of:

ELEVATIONS




RIGHT ELEVATION "A"

SCALE: 1/4" = 1'-0"




REAR ELEVATION "A"

SCALE: 1/4" = 1'-0"



LEFT ELEVATION "A"

SCALE: 1/4" = 1'-0"



FRONT ELEVATION "A"


SCALE: 1/4" = 1'-0"










<b>TB05</b>	REQUIRED MINIMUM PERMANENT TRUSS BRACING PLAN	NTS
-------------	-----------------------------------------------	-----



WALL SHEATHING MAY BE INSTALLED VERTICALLY OR HORIZONTALLY. ATTACH PER WALLING SCHEDULE. PANEL EDGES WILL NEED TO BE ATTACHED TO STUD AND OR BLOCKING AT ALL EDGES. A MINIMUM 1" SPACE IS RECOMMENDED BETWEEN PANELS AT EDGES AND END JOINTS TO ALLOW FOR EXPANSION. FASTENERS SHALL NOT PENETRATE SURFACE MORE THAN 1/4".



<b>TB13</b>	WALL SHEATHING INSTALLATION AND NAILING SCHEDULES	N.T.S.
-------------	---------------------------------------------------	--------



# FLOOR FRAMING

SCALE: 1/4" = 1'-0"

[illegible]

# ROOF FRAMING NOTES

1. SINGLE OR METAL ROOFING SYSTEM (SEE ARCH.) SHEATHING - SEE [RSH] SCHEDULE THIS SHEET. FOR SHT G+ FASTENERS ON PRE-ENGINEERED WOOD TRUSSES AT 2'-0" O.C. MAX. OF CONVENTIONAL FRAME ROOF (SEE PLAN FOR SIZE AND SPACING. SEE ARCHITECTURAL PLAN FOR TRUSS ROOF SLOPE AND TRUSS SPACING). TRUSS ROOFING SYSTEM (SEE ARCH.) SEE [RSH] SCHEDULE THIS SHEET
2. THE EXTERIOR CEILING FOR THE ENTRIES AND PORCHES SHALL HAVE EITHER 7/16" OSB EXPOSURE 1 SHEATHING OR 1/2" DENSGLASS TO THE UNDERSIDE OF THE ROOF TRUSSES. ALL PANEL EDGES ARE TO BE BLOCKED SOLID WITH 2x4 #2 SYP WITH (3) 10d TONENAILS EACH END. THE SHEATHING IS TO BE NAILLED WITH 80 NAILS AT 12" ON CENTER AT ALL EDGES AND THEN 8" ON CENTER IN FIELD.
3. FOR UNDERLAYMENT REQUIREMENTS SEE R905.1.1.1


--- NOTE TO FRAMER ---

IF ROOF TRUSS LAYOUT SHOWS TRUSS ID'S, THIS LAYOUT HAS BEEN PROVIDED BY THE CLIENT/DESIGNER OF ARCHITECT TO USE FOR THE DESIGN OF THIS PROJECT. OTHERWISE A GENERIC LAYOUT HAS BEEN DETERMINED, BUT PRIOR TO CONSTRUCTION OR TRUSS FABRICATION, FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS ARE TO BE SUBMITTED TO THE ENGINEER OF RECORD (E.O.R.) FOR REVIEW AND APPROVAL. AT THIS TIME THE E.O.R. RESERVES THE RIGHT TO REQUEST ANY CHANGES OR CORRECTIONS TO THE TRUSS LAYOUT AND TRUSS SHOP DRAWINGS. ADDITIONAL FEES MAY APPLY. STARTING CONSTRUCTION OR TRUSS FABRICATION PRIOR TO THIS REVIEW IS NOT ADVISED, AND THE E.O.R. IS NOT RESPONSIBLE FOR ANY COSTS DUE TO CHANGES OF THE PLAN. IF CONVENTIONAL FRAMING IS SHOWN, NO TRUSS APPROVAL IS REQUIRED, UNLESS LAYOUT IS REVISIONED W/O WRITTEN APPROVAL FROM FDS.


**SEE PLAN SET FOR TRUSS BRACING AND  
ADDITIONAL ROOF INFORMATION**

COUNTY SEAL	
Friday, January 31, 2025	
To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.	
CA No. 9161	AA26003115
TOTAL SOLUTIONS GROUP 258 Southhall Lane, Suite 200 Maitland, Florida, 32751 (407) 880 2333	
100% Employee Owned myTSGhome.com	
FLORIDA CONTRACTORS LICENSE NO. CRC1330146 <b>100 WEST GARDEN STREET PENSACOLA FL 32502</b>	
DIVISION LOCATION:	
Job Information:	
INVENTORY	LOT: 93 BLK: SEC: SUB: Preserve at Laure Lake 761 SW Rosemary Dr Lake City, FL
Model Name / Number: <b>2705</b>	
Plan Issue Date: Friday, January 31, 2025	
KA PROJECT NUMBER: <b>24-13140</b>	
Sheet: <b>S-1.1</b>	Of:
FLOOR FRAMING PLAN	







**TB15** EXTERIOR NON-BEARING WALL DETAIL N.T.S.




**WC04** GARAGE HEADER ANCHOR 3/4" = 1'-0"




**WC05** SECT. OVERHEAD GAR. DOOR INSTALL N.T.S.




**WF64** EXTERIOR NON BRG. WALL DETAIL N.T.S.




**WF43** EXTERIOR ANGLED WALL DETAIL N.T.S.




**WC03** WALL TO WALL CONN. @ END OF SHEARWALL 1 1/2" = 1'-0"




**CD11** COMMON BEAM ATTACHMENT N.T.S.




**CD25** BEAM TO WALL CONNECTION N.T.S.




**WF66** TYPICAL BEARING WALL N.T.S.




**WC09** WALL STEP @ CORNER N.T.S.




**WC06** EXTERIOR FRAME CORNER 3/4" = 1'-0"



**RD01** VALLEY FLASHING DETAIL N.T.S.



**CD26** GIRDER BASE CONNECTION 1/2" = 1'-0"



**WF68** CORNER CONNECTION N.T.S.

COUNTY SEAL

Friday, January 31, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161      AA26003115

TS&G

CA No. 9161      AA26003115

Making Dreams Come True

TOTAL SOLUTIONS GROUP  
258 Southhall Lane, Suite 200  
Maitland, Florida, 32751  
(407) 880 2333

100% Employee Owned  
myTS&Ghome.com

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

**100 WEST GARDEN STREET**  
**PENSACOLA FL 32502**

DIVISION LOCATION:

Job Information:

INVENTORY

LOT: 93  
BLK:  
SEC:  
SUB: Preserve at Laurel Lake  
761 SW Rosemary Dr  
Lake City, FL

Model Name / Number:

**2705**

Plan Issue Date:

Friday, January 31, 2025


KA PROJECT NUMBER:

**24-13140**


Sheet: **S-2** Of:

TYPICAL FRAMING DETAILS






**WF39** TRANSOM DETAIL AT ENTRY 1/2" = 1'-0"



**WF67** WALL FRAMING 3/4" = 1'-0"



**WF09** WALL HEADER DETAIL N.T.S.

**STAIR NOTES**  
STAIRWAY CONSTRUCTION SHALL CONFORM TO THE FBC-R (CURRENT EDITION) SECTIONS R311.7, R312 AND R302.7.

**RISER HEIGHT:**  
THE RISER HEIGHT SHALL BE NOT MORE THAN 7¾ INCHES. THE RISER HEIGHT SHALL BE MEASURED VERTICALLY BETWEEN LEADING EDGES OF THE ADJACENT TREADS. THE GREATEST RISER HEIGHT WITHIN ANY FLIGHT OF STAIRS SHALL NOT EXCEED THE SMALLEST BY MORE THAN 3/8 INCH. RISERS SHALL BE VERTICAL OR SLOPED FROM THE UNDERSIDE OF THE NOSING OF THE TREAD ABOVE. OPEN RISERS ARE PERMITTED PROVIDED THAT THE OPENINGS LOCATED MORE THAN 30 INCHES, AS MEASURED VERTICALLY, TO THE FLOOR OR GRADE BELOW DO NOT PERMIT THE PASSAGE OF A 4-INCH DIAMETER SPHERE.

**TREAD DEPTH:**  
THE TREAD DEPTH SHALL BE NOT LESS THAN 10 INCHES. THE TREAD DEPTH SHALL BE MEASURED HORIZONTALLY BETWEEN THE VERTICAL PLANES OF THE FOREMOST PROJECTION OF ADJACENT TREADS AND AT A RIGHT ANGLE TO THE TREAD'S LEADING EDGE. THE GREATEST TREAD DEPTH WITHIN ANY FLIGHT OF STAIRS SHALL NOT EXCEED THE SMALLEST BY MORE THAN 3/8 INCH.

**WINDERS:**  
WINDER TREADS SHALL HAVE A TREAD DEPTH OF NOT LESS THAN 10 INCHES MEASURED BETWEEN THE VERTICAL PLANES OF THE FOREMOST PROJECTION OF ADJACENT TREADS AT THE INTERSECTIONS WITH THE WALKLINE. WINDER TREADS SHALL HAVE A TREAD DEPTH OF NOT LESS THAN 6 INCHES AT ANY POINT WITHIN THE CLEAR WIDTH OF THE STAIR.


**NOSINGS:**  
NOSINGS AT TREADS, LANDINGS AND FLOORS OF STAIRWAYS SHALL HAVE A RADIUS OF CURVATURE AT THE NOSING NOT GREATER THAN 9/16 INCH OR A BEVEL NOT EXCEEDING ½ INCH. A NOSING PROJECTION NOT LESS THAN 3/4 INCH AND NOT MORE THAN 1¼ INCHES SHALL BE PROVIDED ON STAIRWAYS. THE GREATEST NOSING PROJECTION SHALL NOT EXCEED THE SMALLEST NOSING PROJECTION BY MORE THAN 3/8 INCH WITHIN A STAIRWAY.

**HANDRAILS:**  
HANDRAILS SHALL BE PROVIDED ON NOT LESS THAN ONE SIDE OF EACH FLIGHT WITH FOUR OR MORE RISERS. HANDRAIL HEIGHT MEASURED VERTICALLY FROM THE SLOPED PLANE ADJOINING THE TREAD NOSING, OR FINISH SURFACE OF RAMP SLOPE, SHALL BE NOT LESS THAN 34 INCHES AND NOT MORE THAN 38 INCHES. HANDRAILS FOR STAIRWAYS SHALL BE CONTINUOUS FOR THE FULL LENGTH OF THE FLIGHT, FROM A POINT DIRECTLY ABOVE THE TOP RISER OF THE FLIGHT TO A POINT DIRECTLY ABOVE THE LOWEST RISER OF THE FLIGHT. HANDRAIL ENDS SHALL BE RETURNED OR SHALL TERMINATE IN NEWEL POSTS OR SAFETY TERMINALS. HANDRAILS ADJACENT TO A WALL SHALL HAVE A SPACE OF NOT LESS THAN 1½ INCHES BETWEEN THE WALL AND THE HANDRAILS.


**GRIP-SIZE:**  
HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF NOT LESS THAN 1¼ INCHES AND NOT GREATER THAN 2 INCHES OR PROVIDE EQUIVALENT GRASP-ABILITY IN COMPLIANCE WITH SECTION R311.7.B.3.

**GUARDS:**  
GUARDS SHALL BE PROVIDED FOR THOSE PORTIONS OF OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, RAMPS AND LANDINGS, THAT ARE LOCATED MORE THAN 30 INCHES MEASURED VERTICALLY TO THE FLOOR OR GRADE BELOW AT ANY POINT WITHIN 24 INCHES HORIZONTALLY TO THE EDGE OF THE OPEN SIDE. REQUIRED GUARDS AT OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, PORCHES, BALCONIES OR LANDINGS, SHALL BE NOT LESS THAN 36 INCHES IN HEIGHT AS MEASURED VERTICALLY ABOVE THE ADJACENT WALKING SURFACE OR THE LINE CONNECTING THE LEADING EDGES OF THE TREADS. REQUIRED GUARDS SHALL NOT HAVE OPENINGS FROM THE WALKING SURFACE TO THE REQUIRED GUARD HEIGHT THAT ALLOW PASSAGE OF A SPHERE 4 INCHES IN DIAMETER.

**UNDER-STAIR PROTECTION:**  
ENCLOSED SPACE UNDER STAIRS THAT IS ACCESSED BY A DOOR OR ACCESS PANEL SHALL HAVE WALLS, UNDER-STAIR SURFACE AND ANY SOFFITS PROTECTED ON THE ENCLOSED SIDE WITH 1/2-INCH GYPSUM BOARD.



**INTERIOR STAIR SECTION**  
N.T.S.



**SD04** GENERAL LANDING FRAMING INFO. N.T.S.

COUNTY SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115

**TS** Making Dreams Come True

CA No. 9161 AA26003115

**TOTAL SOLUTIONS GROUP**  
258 Southhall Lane, Suite 200  
Maitland, Florida, 32751  
(407) 880 2333

100% Employee Owned  
myTSGhome.com

**DAMS HOMES**

FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
**100 WEST GARDEN STREET**  
**PENSACOLA FL 32502**

**DIVISION LOCATION:**

Job Information:

**INVENTORY**

LOT: 93  
BLK:  
SEC:  
SUB: Preserve at Laurel Lake  
761 SW Rosemary Dr  
Lake City, FL

Model Name / Number:

**2705**

Plan Issue Date:

Friday, January 31, 2025

KA PROJECT NUMBER:


**24-13140**

Sheet: **S-2.1** of:


TYPICAL FRAMING DETAILS

Friday, January 31, 2025







**WS02** TYPICAL WALL SECTION EXTERIOR FRAME 3/4" = 1'-0"




**SE** TYPICAL SOFFIT AND EAVE DETAIL 3/4" = 1'-0"




**WF37** TYPICAL COLUMNS DETAILS N.T.S.




**WF17** TOP PLATE SPLICE DETAIL 3/4" = 1'-0"




**WF63** SECTION AT DOUBLE BEARING N.T.S.




**CD24** POST & BEAM DETAIL 1/2" = 1'-0"




**SW01** INTERIOR BEARING SHEARWALL w/UPLIFT N.T.S.




**WC07** STEP UP @ CORNER & RAISED BEAM 1/2" = 1'-0"



**BD07** BRICK SHELF DETAIL N.T.S.



**WC08** STEP UP @ CORNER & RAISED BEAM N.T.S.



**SW04** INTERIOR SHEARWALL @ TRUSSES 3/4" = 1'-0"

COUNTY SEAL

Friday, January 31, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.  
CA No. 9161 AA26003115



FLORIDA CONTRACTORS LICENSE NO. CRC1330148  
**100 WEST GARDEN STREET**  
**PENSACOLA FL 32502**

**DIVISION LOCATION:**

**Job Information:**

**INVENTORY**  
LOT: 93  
BLK:  
SEC:  
SUB: Preserve at Laurel Lake  
761 SW Rosemary Dr  
Lake City, FL

**Model Name / Number:**

**2705**

**Plan Issue Date:**

Friday, January 31, 2025


**KA PROJECT NUMBER:**

**24-13140**


Sheet: **S-3** Of:

TYPICAL WALL DETAILS







**SG01** GIRDER/COLUMN @ 2ND FLR w/HIGH BM N.T.S.




**SH05** HEADER CONNECTION @ 2ND FLOOR 1/2" = 1'-0"




**WF69** WALL @ 2ND FLOOR N.T.S.




**18** FLOOR CONNECTION N.T.S.




**FB12** BLOCKING DETAIL 3/4" = 1'-0"




**WS06** FLOOR ATTACHMENT DETAIL 3/4" = 1'-0"




**WF70** CANTELIVER FLOOR SECTION N.T.S.




**WF65** LOW ROOF TO SECOND FLOOR CONN. N.T.S.




**WF71** KNEEWALL AT DORMER N.T.S.



**SH07** ALTERNATE HEADER CONDITIONS N.T.S.



**WF06** 2 STORY INTERIOR BEARING WALL N.T.S.



**WS04** TYPICAL TWO STORY WALL SECTION 3/4" = 1'-0"

COUNTY  
SEAL

Friday, January 31, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing the engineer's signature and seal.  
CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP  
258 Southhall Lane, Suite 200  
Maitland, Florida, 32751  
(407) 880 2333

100% Employee Owned  
myTSGhome.com



FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
100 WEST GARDEN STREET  
PENSACOLA FL 32502

DIVISION LOCATION:

Job Information:

**INVENTORY**  
LOT: 93  
BLK: SEC:  
SUB: Preserve at Laurel Lake  
761 SW Rosemary Dr  
Lake City, FL

Model Name / Number:

**2705**

Plan Issue Date:

Friday, January 31, 2025


KA PROJECT NUMBER:

**24-13140**


Sheet: **S-3.1** Of:

TYPICAL WALL DETAILS






**TB01** TYPICAL CROSS BRACING DETAIL N.T.S.




**TB02** TYPICAL CROSS BRACING DETAIL N.T.S.

THE HEIGHT OF THE CHIMNEY SHOULD EXTEND 2' ABOVE THE POINT WHERE THE CHIMNEY IS 10' FROM THE NEAREST BUILDING SURFACE.




**CH01** TYPICAL CHIMNEY FRAME DETAIL 3/4" = 1'-0"


RAFTER SIZE	
0'-8" SPAN -	2"x6" W/4-12d EACH END
8'-12" SPAN -	2"x8" W/4-12d EACH END
12'-15" SPAN -	2"x10" W/ SIMPSON A 34 @ EA. END
15'-18" SPAN -	2"x12" W/ SIMPSON A 34 @ EA. END




**TB17** CONV. FRAMING & VALLEY FRAMING N.T.S.




**TB03** HIP / RIDGE BLOCKING DETAIL N.T.S.



**TB04** TRUSS BRACING OVERLAP DETAIL (TYP) N.T.S.






**GE04** "T" BRACE CONNECTION @ GABLE END W/ VOLUME CEILING 3/4" = 1'-0"



**WF05** DORMER FRAMING DETAIL N.T.S.

#### TRUSS NOTES:

- WOOD TRUSS ERECTOR SHALL PROVIDE BRACING ACCORDING TO ANSI/TPI-2014 (TRUSS PLATE INSTITUTE) NOTE THAT THE COMBINED WIND AREA IS GREATER BEFORE THE ROOF SHEATHING IS APPLIED, AND BRACING SHALL THEREFORE BE INSTALLED AS THE TRUSSES ARE ERECTED. INADEQUATE BRACING IS THE MOST COMMON CAUSE OF ACCIDENT IN WOOD TRUSS CONSTRUCTION. FULL BUNDLES OF SHEATHING SHALL NOT BE PLACED ON TRUSSES. THIS CONSTRUCTION LOAD SHOULD BE LIMITED TO 8 SHEETS OF SHEATHING ON ANY PAIR OF TRUSSES & SHALL BE LOCATED ADJACENT TO THE SUPPORTS. NO EXCESS CONCENTRATION OF ANY CONSTRUCTION MATERIAL (SUCH AS GRAVEL OR SHINGLES) SHALL BE PLACED ON THE TRUSSES IN ANY ONE AREA THEY SHALL BE SPREAD OUT EVENLY OVER A LARGE AREA SO AS TO AVOID OVERLOADING ANY ONE TRUSS.
- ALL BRACING (DB, CB, BB) SHOWN ABOVE SHALL BE IN ADDITION TO CONTINUOUS LATERAL BRACING SPECIFIED BY THE TRUSS MANUFACTURER. ALL LATERAL BRACING SPECIFIED BY TRUSS MANUF. SHALL HAVE ADDITIONAL DIAGONAL BRACES AT 20'-0" O.C. MAXIMUM.
- ALL BRACES SHALL BE 2x4 NOMINAL DIMENSION LUMBER & SHALL BE ATTACHED W/ (3) 12d NAILS AT EACH TRUSS INTERSECTION.
- ADDITIONAL BOTTOM CHORD BRACING SHALL BE INSTALLED AS REQUIRED BY TRUSS DESIGN WHEREVER ADEQUATE STRUCTURAL CEILING ARE NOT ATTACHED DIRECTLY TO THE BOTTOM CHORD OF THE TRUSS.
- PROVIDE TRUSS BLOCKING AT ALL TRUSS BEARING SUPPORTS WHERE TRUSS DEPTH EXCEEDS STANDARD HEEL HEIGHT. SEE TYP. TRUSS BLOCKING DETAILS.



**A-A** ALTERNATE BLOCKING DETAIL @ INTERIOR BEARING

**TYP. WOOD TRUSS BLOCKING @ RAISED HEEL DETAIL**

**TB06** BLOCKING AND CONVENTIONAL FRAME DETAILS 3/4" = 1'-0"

COUNTY SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



**TOTAL SOLUTIONS GROUP**  
258 Southhall Lane, Suite 200  
Maitland, Florida, 32751  
(407) 880 2333

**100% Employee Owned**  
myTSGhome.com

**DAMS HOMES**  
FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
**100 WEST GARDEN STREET**  
**PENSACOLA FL 32502**

**DIVISION LOCATION:**

**Job Information:**

**INVENTORY**

LOT: 93  
BLK: SEC:  
SUB:

Preserve at Laurel Lake  
761 SW Rosemary Dr  
Lake City, FL

**Model Name / Number:**

**2705**

**Plan Issue Date:**

Friday, January 31, 2025

**KA PROJECT NUMBER:**

**24-13140**

Sheet:


**S-4**

Of:


**ROOF FRAMING AND BRACING DETAILS**

Friday, January 31, 2025







**GE05** GABLE END BRACING - FRAME WALL N.T.S.




**GE22** GABLE END BRACING w/ VOL CEILING 1/2"=1'-0"




**GE23** GABLE END BRACING w/o VOLUME CEILING 1/2"=1'-0"




**GE24** GABLE @ VAULT N.T.S.




**WF72** LEDGER N.T.S.




**WF73** KNEEWALL @ DORMER N.T.S.




**GE21** SECTION @ DUTCH GABLE 3/4"=1'-0"




**LD02** SHEAR TRANSFER EXTERIOR WALL N.T.S.



**GE23.1** GABLE END OVERHANG 1/2"=1'-0"



**SECTION A-A**



**SR01** SECTION AT SHED ROOF 3/4"=1'-0"

COUNTY  
SEAL

Friday, January 31, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.  
CA No. 9161 AA26003115



**TOTAL SOLUTIONS GROUP**  
258 Southhall Lane, Suite 200  
Maitland, Florida, 32751  
(407) 880 2333

**100% Employee Owned**  
myTSGhome.com



FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
**100 WEST GARDEN STREET**  
**PENSACOLA FL 32502**

**DIVISION LOCATION:**

Job Information:

**INVENTORY**

LOT: 93

BLK:

SEC:

SUB: Preserve at Laurel Lake

761 SW Rosemary Dr  
Lake City, FL

Model Name / Number:

**2705**

Plan Issue Date:

Friday, January 31, 2025

KA PROJECT NUMBER:

**24-13140**


Sheet:

**S-4.1**

Of:

**ROOF FRAMING  
AND BRACING DETAILS**






- HEAD FLASHING TIE-IN INSTRUCTIONS:
1. Cut, fold up & temporarily secure weather resistive barrier above header to allow for flashing installation
  2. Self-adhered flashing plus head flashing under weather resistive barrier
  3. Fold weather resistive barrier back over head flashing and seal with tape

①  
②

SELF-ADHERED FLASHING  
FLASHING INSTALLATION AFTER WEATHER RESISTIVE BARRIER

Scale: NTS


WP01



①  
②  
③  
④  
⑤  
⑥  
⑦  
⑧

SELF-ADHERED FLASHING  
HALF ROUND WINDOW


WP04



②

SELF-ADHERED FLASHING  
W0.8362x;DECK JOIST


WP07



- NOTES:
1. INSTALL WINDOW PER MANUFACTURER'S RECOMMENDATION AND USE APPROPRIATE SEALANT FOR WINDOW AND WOOD BUCK
  2. WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.

RECESSED WINDOW


WP10



①  
②

SELF-ADHERED FLASHING  
EXTERIOR DOOR WITH DECK - SECTION A


WP02



①  
②

SELF-ADHERED FLASHING  
EXTERIOR DOOR WITH DECK


WP05



①  
②  
③  
④  
⑤

SELF-ADHERED FLASHING  
OUTSIDE CORNER


WP08



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
  2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.

WALL-TO-WALL OUTSIDE CORNER


WP11



- NOTES:
1. INSTALL WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.
  2. FOR SILL PAN DEPTHS GREATER THAN 6 INCHES, A SLOPED SILL IS REQUIRED IN ACCORDANCE WITH ASTM E 2112.
  3. A BACK DAM CAN BE ACCOMPLISHED USING A WOODEN FURRING STRIP OR BY FOLDING THE ADHESIVE LAYER ONTO ITSELF.
  4. EXTEND SELF-ADHERED FLASHING OVER NAILING FLANGE OF THE LAST COMPLETE COURSE OF SIDING PANEL AND TRIM TO PROTECT FROM PERMANENT EXPOSURE TO UV.

TIE-IN WITH VINYL SIDING  
AT WINDOW SILL

WP03



②  
③  
④  
⑤  
⑥  
⑦

SELF-ADHERED FLASHING  
INSIDE CORNER


WP06



①  
②  
③  
④  
⑤

SELF-ADHERED FLASHING  
OUTSIDE CORNER


WP08



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
  2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.

WALL-TO-WALL OUTSIDE CORNER

WP11



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
  2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.

WALL-TO-WALL INSIDE CORNER

WP12

THESE DETAILS ARE GENERIC AND MEANT TO SHOW  
GENERAL FLASHING AND WATERPROOFING METHODS  
TO BE USED.

## SELF-ADHERED FLASHING PRODUCTS DETAILS

TWO LAYERS OF FELT OR ONE LAYER OF HOUSE WRAP AND  
ONE LAYER OF FELT ARE REQUIRED BEHIND STUCCO. FBC R703.2

### DETAIL INSTRUCTIONS

REFER TO THE NUMBER MARKED AS (#) IN EACH DETAIL THAT  
CORRESPONDS TO THE NUMBERED ITEMS IN THE LIST OF  
INSTRUCTIONS BELOW:

1. INSTALL SELF-ADHERED FLASHING IN ORDER AS SHOWN BY NUMBERS.
2. INSTALL FLASHING AND WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.
3. SELF-ADHERED FLASHING CAN BE SUBSTITUTED FOR BUILDING PAPER.
4. SPLIT THE RELEASE PAPER USING THE RIPCORD (SPLIT RELEASE ON DEMAND, EMBEDDED IN THE ADHESIVE LAYER) - FOR EASE OF INSTALLATION AND TO MINIMIZE SCORING CUTS.
5. REMOVE ALL RELEASE PAPER PER STANDARD INSTALLATION INSTRUCTIONS AND ADHERE TO SUBSTRATE USING A SQUARE PIECE OF FLASHING MATERIAL (6" X 6" MINIMUM).
6. FOLD AS SHOWN BY ARROWS.
7. ANGLE OF CORNER MAY VARY, ADJUST FOLDING OF THE FLASHING ACCORDINGLY TO FIT TIGHT TO CORNER.
8. MECHANICALLY FASTEN AS NECESSARY.

## FLASHING REQUIREMENTS

R703.1 GENERAL. EXTERIOR WALLS SHALL PROVIDE THE BUILDING WITH A WEATHER-RESISTANT EXTERIOR WALL ENVELOPE. THE EXTERIOR WALL ENVELOPE SHALL INCLUDE FLASHING AS DESCRIBED IN SECTION R703.4. A WATER-RESISTIVE BARRIER IS DESCRIBED AS A MATERIAL, BEHIND AN EXTERIOR WALL COVERING THAT IS INTENDED TO RESIST LIQUID WATER THAT HAS PENETRATED BEHIND THE EXTERIOR COVERING FROM FURTHER INTRUDING INTO THE EXTERIOR WALL ASSEMBLY. AN EXTERIOR WALL COVERING IS DESCRIBED AS A MATERIAL OR ASSEMBLY OF MATERIALS APPLIED ON THE EXTERIOR SIDE OF EXTERIOR WALLS FOR THE PURPOSE OF PROVIDING A WEATHER-RESISTIVE BARRIER, INSULATION, OR FOR AESTHETICS, INCLUDING BUT NOT LIMITED TO, VENEERS, SIDING, EXTERIOR INSULATION AND FINISH SYSTEMS, ARCHITECTURAL TRIM AND EMBELLISHMENTS SUCH AS CORNICES, SOFFITS, AND FASCIA.

R703.2 WATER-RESISTIVE BARRIER. ONE LAYER OF NO. 15 ASPHALT FELT, FREE FROM HOLES AND BREAKS, COMPLYING WITH ASTM D228 FOR TYPE I FELT OR OTHER APPROVED WATER-RESISTIVE BARRIER SHALL BE APPLIED OVER STUDS OR SHEATHING OF ALL EXTERIOR WALLS. SUCH FELT OR MATERIAL SHALL BE APPLIED HORIZONTALLY, WITH THE UPPER LAYER LAPPED OVER THE LOWER LAYER NOT LESS THAN 2 INCHES (51 MM) WHERE JOINTS OCCUR. FELT SHALL BE LAPPED NOT LESS THAN 6 INCHES (152 MM). THE FELT OR OTHER APPROVED MATERIAL SHALL BE CONTINUOUS TO THE TOP OF WALLS AND TERMINATED AT PENETRATIONS AND BUILDING APPENDAGES IN A MANNER TO MEET THE REQUIREMENTS OF THE EXTERIOR WALL ENVELOPE AS DESCRIBED IN SECTION R703.1.

R703.3 WATER-RESISTIVE BARRIERS SHALL BE INSTALLED AS REQUIRED IN SECTION R703.2 AND, WHERE APPLIED OVER WOOD-BASED SHEATHING, SHALL INCLUDE A WATER-RESISTIVE VAPOR-PERMEABLE BARRIER WITH A PERFORMANCE AT LEAST EQUIVALENT TO TWO LAYERS OF GRADE D PAPER. THE INDIVIDUAL LAYERS SHALL BE INSTALLED INDEPENDENTLY SUCH THAT EACH LAYER PROVIDES A SEPARATE CONTINUOUS PLANE AND ANY FLASHING (INSTALLED IN ACCORDANCE WITH SECTION R703.4) INTENDED TO DRAIN TO THE WATER-RESISTIVE BARRIER IS DIRECTED BETWEEN THE LAYERS.

EXCEPTION: WHERE THE WATER-RESISTIVE BARRIER THAT IS APPLIED OVER WOOD-BASED SHEATHING HAS A WATER RESISTANCE EQUAL TO OR GREATER THAN THAT OF 60-MINUTE GRADE D PAPER AND IS SEPARATED FROM THE STUCCO BY AN INTERVENING, SUBSTANTIALLY NONWATER-ABSORBING LAYER OR DESIGNED DRAINAGE SPACE.

R703.4 FLASHING. APPROVED CORROSION-RESISTANT FLASHING SHALL BE APPLIED SHINGLE-FASHION IN A MANNER TO PREVENT ENTRY OF WATER INTO THE WALL CAVITY OR PENETRATION OF WATER TO THE BUILDING STRUCTURAL FRAMING COMPONENTS. SELF-ADHERED MEMBRANES USED AS FLASHING SHALL COMPLY WITH AAMA 711. ALL EXTERIOR PENETRATION PRODUCTS SHALL BE SEALED AT THE JUNCTURE WITH THE BUILDING WALL WITH A SEALANT COMPLYING WITH AAMA 800 OR ASTM C920 CLASS 25 GRADE NS OR GREATER FOR PROPER JOINT EXPANSION AND CONTRACTION. ASTM C1281, AAMA 812, OR OTHER APPROVED STANDARD AS APPROPRIATE FOR THE TYPE OF SEALANT. FLUID-APPLIED MEMBRANES USED AS FLASHING IN EXTERIOR WALLS SHALL COMPLY WITH AAMA 714. THE FLASHING SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH. APPROVED CORROSION-RESISTANT FLASHINGS SHALL BE INSTALLED AT THE FOLLOWING LOCATIONS:

1. EXTERIOR WINDOW AND DOOR OPENINGS. FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER-RESISTIVE BARRIER COMPLYING WITH SECTION 703.2 FOR SUBSEQUENT DRAINAGE. MECHANICALLY ATTACHED FLEXIBLE FLASHINGS SHALL COMPLY WITH AAMA 712. FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL BE INSTALLED IN ACCORDANCE WITH ONE OR MORE OF THE FOLLOWING:
  - 1.1 THE FENESTRATION MANUFACTURER'S INSTALLATION AND FLASHING INSTRUCTIONS, OR FOR APPLICATIONS NOT ADDRESSED IN THE FENESTRATION MANUFACTURER'S INSTRUCTIONS, IN ACCORDANCE WITH THE FLASHING MANUFACTURER'S INSTRUCTIONS, WHERE FLASHING INSTRUCTIONS OR DETAILS ARE NOT PROVIDED. PAN FLASHING SHALL BE INSTALLED AT THE SILL OF EXTERIOR WINDOW AND DOOR OPENINGS. PAN FLASHING SHALL BE SEALED OR SLOPED IN SUCH A MANNER AS TO DIRECT WATER TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER RESISTIVE BARRIER FOR SUBSEQUENT DRAINAGE. OPENINGS USING PAN FLASHING SHALL INCORPORATE FLASHING OR PROTECTION AT THE HEAD AND SIDES.
  - 1.2. IN ACCORDANCE WITH THE FLASHING DESIGN OR METHOD OF A REGISTERED DESIGN PROFESSIONAL.
  - 1.3. IN ACCORDANCE WITH OTHER APPROVED METHODS.
  - 1.4. IN ACCORDANCE WITH FMA/AAMA 100, FMA/AAMA 200, FMA/WDMA 250, FMA/AAMA/WDMA 300 OR FMA/AAMA/WDMA 400.
2. AT THE INTERSECTION OF CHIMNEYS OR OTHER MASONRY CONSTRUCTION WITH FRAME OR STUCCO WALLS, WITH PROJECTING LIPS ON BOTH SIDES UNDER STUCCO CORNICES.
3. UNDER AND AT THE ENDS OF MASONRY, WOOD OR METAL COPINGS AND SILLS.
4. CONTINUOUSLY ABOVE ALL PROJECTING WOOD TRIM.
5. WHERE EXTERIOR PORCHES, DECKS OR STAIRS ATTACH TO A WALL OR FLOOR ASSEMBLY OF WOOD-FRAME CONSTRUCTION.
6. AT WALL AND ROOF INTERSECTIONS.
7. AT BUILT-IN GUTTERS.

COUNTY  
SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code-Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115

**TSG**  
TOTAL SOLUTIONS GROUP  
258 Southhall Lane, Suite 200  
Maitland, Florida, 32751  
(407) 880 2333  
100% Employee Owned  
myTSGhome.com

**DAMS HOMES**  
FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
100 WEST GARDEN STREET  
PENSACOLA FL 32502

DIVISION LOCATION:

Job Information:

**INVENTORY**  
LOT: 93  
BLK:  
SEC:  
SUB: Preserve at Laurel Lake  
761 SW Rosemary Dr  
Lake City, FL

Model Name / Number:

2705

Plan Issue Date:

Friday, January 31, 2025

KA PROJECT NUMBER:

24-13140

Sheet: WP

WATER PROOF  
DETAILS

Friday, January 31, 2025