

COLD FORMED METAL FRAMING: (SHOP DRAWINGS REQUIRED)

y = 33 KS.I.) STEEL, AND DESIGNED IN ACCORDANCE WITH THE LATEST S.S.M.A. ANCHOR BOLTS AS PER THE FOUNDATION PLAN AND SHALL BE FURTHER SPECIFACATIONS FOR THE DESIGN, FABRICATION AND ERECTION OF COLD FORMED METAL FRAMING AND THE S.S.M.A. CODE OF STANDARD PRACTICE.

2. ALL CFMF COMPONENTS SHALL BE MANUFACTURED AS PER ASTM C 955 AND BE GALVANIZED WITH A MINIMUM G-60 COATING PER ASTM C 955.

ALL PRODUCTS SHALL BE FREE OF RUST, DENTS, BENDS & TWISTS AND STORED ON A FLAT PLANE PRIOR TO INCLUSION IN THE WORK.


3. ALL WELDING TO BE IN ACCORDANCE WITH A.W.S. LATEST, El.3 & DI.3 "STRUCTURAL WELDING CODE - STEEL". CLEAN AND RUSTPROOF ALL FIELD WELDS WITH ZINK RICH RUSTPROOFING PAINT.

1. ALL COLD FORMED METAL FRAMING SHALL BE DOMESTIC A.S.T.M. A 653 4. BOTTOM TRACK SHALL BE SECURED TO THE CONCRETE FOUNDATION W/ FASTENED AT EA. FULL STUD W/ .177" + X 11/2" PAF, SHOT THROUGH A 1" + X 16 GA HOLELESS WASHER

> 5. ALL CONNECTIONS TO BE FIELD AND SHOP WELDED AND TO FULLY DEVELOP MEMBER IN SHEAR

6. SPLICE LOCATIONS TO BE REVIEWED BY ARCHITECT/ENGINEER

T. STEEL BEARING ON STEEL TO BE WELDED THERETO.




CONCRETE / MASONRY / METALS GENERAL NOTES:


- 1. DESIGN SOIL BEARING PRESSURE: 1000 PSF.
- 2. EXPANSIVE SOILS: WHERE DIRECTED BY THE SOILS ENGINEER, SOIL AUGMENTATION PER THE SOILS ENGINEER'S SPECIFICATIONS SHALL BE IMPLEMENTED PRIOR TO PLACING ANY FOUNDATIONS - TESTS AS SPECIFIED SHALL BE PREFORMED TO DETERMINE THE SUITABILITY OF THE SUB-GRADE TO SUPPORT THE DESIGN LOADS.
- 3. CLEAN SAND FILL OVER STRIPPED AND COMPACTED EXISTING GD. SHALL BE PLACED IN 12" LIFTS. BOTH SUB-SOIL AND FILL COMPAC-TION SHALL BE NOT LESS THAN 98% AS MEASURED BY A MODIFIED PROCTOR TEST AT THE RATE OF ONE TEST FOR EACH 1500 SF OF BUILDING PAD AREA, OR FRACTION THEREOF, FOR EACH 12" LIFT.
- REINFORCING STEEL SHALL BE GRADE 60 AND MEET THE REQUIRE-MENTS OF ASTM A615, ALL BENDS SHALL BE MADE COLD.
- 5. WELDED WIRE MESH SLAB REINFORCING SHALL MEET THE REQUIRE-MENTS OF ASTM A185 - MIN. YEILD STRESS = 85 KSI.
- 6. CONCRETE SHALL BE STANDARD MIX F'C = 3000 PSI FOR ALL FTGS, SLABS, COLUMNS AND BEAMS OR SHALL BE STANDARD PUMP MIX F'c = 3000 PSI. STRENGTH SHALL BE ATTAINED WITHIN 28 DAYS OF PLACE-MENT. MIXING, PLACING AND FINISHING SHALL BE AS PER ACI STANDARDS.
- 1. CONCRETE BLOCK SHALL BE AS PER MANUFACTURER'S PRODUCT GUIDE FOR ASTM C-90 REQUIREMENTS WITH MEDIUM SURFACE FINISH -F'm = 1500 PSI.
- 8. MORTAR SHALL BE TYPE "M" OR "N" FOR ALL MASONRY UNITS.
- 9. STRUCTURAL STEEL SHALL CONFORM TO ASTM A36 STANDARDS FOR STRENGTH, BOLTS SHALL BE ASTM A307 / GRADE 1 OR A325, AS PER PLAN REQUIREMENTS.
- 10. WELDS SHALL BE AS PER "AMERICAN WELDING SOCIETY" STANDARDS FOR STRUCTURAL STEEL APPLICATIONS.

WOOD STRUCTURAL NOTES

- 1. TEMPORARY BRACING OF THE STRUCTURE DURING ERECTION, REQUIRED FOR SAFE AND STABLE CONSTRUCTION, SHALL BE THE SOLE RESPON-SIBILITY OF THE CONTRACTOR SO ENGAGED. TEMPORARY & PERMANENT BRACING OF ROOF TRUSSES SHALL BE AS PER THE STANDARD GUIDE-LINES OF THE "TRUSS PLATE INSTITUTE".
- 2. ALL TRUSSES SHALL BE DESIGNED BY A LICENSED PROFESSIONAL ENGINEER & SHALL BE SIGNED AND SEALED BY SAME, TRUSS DESIGN SHALL INCLUDE PLACEMENT PLANS, TRUSS DETAILS, TRUSS TO TRUSS CONNECTIONS & THE STANDARD SPECIFICATIONS & RECOMMENDATIONS OF INSTALLATION OF THE "TRUSS PLATE INSTITUTE".
- 3. WOOD STUDS IN EXTERIOR WALLS & INTERIOR BEARING WALLS SHALL BE NOT LESS THAN Nr.2 HEM-FIR OR BETTER.
- 4. CONNECTORS FOR WOOD FRAMING SHALL BE GALVANIZED METAL OR BLACK METAL AS MANUFACTURED OR AS CALLED FOR IN THE PLANS AND BE OF A DESIGN SUITABLE FOR THE LOADS AND USE INTENDED. REFER TO THE JOINT REINFORCEMENT SCHEDULE FOR PRINCIPLE CON-NECTIONS.



Built-Up Column
Thru-Bolt DETAIL



Girder Truss Column DETAIL

SCALE: NONE



Copyright 2012 © N.P. Geisler, Architect

nog

REVISION:

DRAWN

WORDEIN

30 JUL 2012 COMM


2K1239

SHEET:

DATE:

OF

AR0007005



SCALE: 1/4" = 1'-0"