


BEARING WOOD INTERIOR WALL SCHEDULE					
MARK	STUD SPACING	CONNECTION & FASTENERS	LUMBER SPECIES	UPLIFT CAP (PIF)	
		TOP	BOTTOM		
[BW1]	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
[BW2]	16"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SPF	402
[BW3]	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	571
[BW4]	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
[BW5]	16"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SYP	439
[BW6]	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	665
[BW7]	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
[BW8]	12"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SPF	535
[BW9]	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	760
[BW10]	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
[BW11]	12"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SYP	585
[BW12]	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	885

NOTE: 2 x 4 WALLS ARE ASSUMED U.N.O. ON FLOOR PLANS
* ALL LUMBER TO BE GRADE #2
** CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED
*** SPFS & SPFS CAN BE SUB. TOP SPFS W/ RESPECT TO STUD SIZE



GENERAL NOTES

- SEE FLOOR PLAN FOR WALL SIZE. ASSUME 2x4 STUDS USED U.N.O.
- ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 U.N.O. ON PLAN.
- CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
- CONTACT E.O.R. IF SP4'S SPFS OR SPFS'S CONNECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
- IF "BW" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORE. SEE WORK/S.S. OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2nd FLOOR TO FIRST FLOOR CONNECTION. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY).
- IF "SW" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES MIN. 1/4" OSB PLYWOOD W/ 16d NAILS AT 4" O.C. IN FIELD AND EDGE TO 11" SIDE OF WALL.
- ALL 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE ATT AS SHEARWALLS. SEE PLAN AND WALL SECTIONS FOR STUD SPACING AND GRADE.
- IF THE BEARING WALL IS INDICATED WITH THE BWI, BWI, BWI, BWI THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT. THE STUDS ARE TOE SCREWS TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CASED NAILS (GUN NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.

MARK	COLUMN SIZE	(BASE) CONN. & FASTENER	UPLIFT(LBS)
[C1]	(3) 2 x 4 #2 SPF	(4) 16d TOENAILS	0
[C2]	(3) 2 x 4 #2 SPF	DT122 W/ 1/2" WEDGE ANCHOR* & (8) 1/4" X 1 1/2" SDS SCREWS	2145
[C3]	(3) 2 x 4 SYP #1 GR.	(4) 16d TOENAILS	0
[C4]	(4) 2 x 4 SPF #2	DT122 W/ 1/2" WEDGE ANCHOR* & (8) 1/4" X 1 1/2" SDS SCREWS	2145
[C5]	4 x 4 P.T. #2 SYP POST	AB144 W/ 5/8" ATR** & (12) 16d NAILS	G = 6665 U = 2200
[C6]	6 x 6 P.T. #2 SYP POST	AB166 W/ 5/8" ATR** & (12) 16d NAILS	G = 12000 U = 2200
[C7]	8 x 8 P.T. #2 SYP POST	AB188 W/ (2) 5/8" ATR** & (18) 16d NAILS	G = 24335 U = 2330
[C8]	3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (14) 1/4" X 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
[C9]	3.5 x 5.25 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (14) 1/4" X 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
[C10]	3.5 x 7 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	6970
[C11]	5.25 x 5.25 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870
[C12]	7 x 7 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870
[C13]	5.25" x 7" P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	HDUS-SDS2.5 W/ 7/8" ATR AND (20) 1/4" X 1/2" SDS WOOD SCREWS	7870

GENERAL COLUMN NOTES

- SEE FLOOR PLAN FOR WALL WIDTH. STUD PACKS TO MATCH WALL WIDTH U.N.O.
- ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 U.N.O. ON PLAN.
- NAIL BUILD UP STUDS PER DETAIL WF37
- MINIMUM BOLT EMBEDMENT:
 - 5" EMBEDMENT FOR 1/2" ATR
 - 6" EMBEDMENT FOR 5/8" ATR
 - 8" EMBEDMENT FOR 7/8" ATR
- IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL OUT ON PLAN FOR ATTACHMENT)
- SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION
- SAME NOMINAL SIZE PARALLEL COLUMNS (L&R) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOTED IN THE PLANS

COMMON NAIL vs. PNEUMATIC GUN NAILS:

COMMON NAIL	DIA. / LENGTH	PNEUMATIC GUN NAIL	COMMON vs. GUN	APPLICATION
	NAIL DIA. LENGTH	NAIL DIA. LENGTH		
8d	0.131" X 2 1/2"	0.131" X 2 1/2"		SEE PLAN RING SHANK ON ROOF
10d OR 12d	0.148" X 3"	0.131" X 3"		SEE PLAN
12d	0.148" X 3 1/4"	0.131" X 3 1/4"		SEE PLAN
12d	0.148" X 3 1/4"	0.131" X 3 1/4"	8" O.C. (COMMON)	STUD WALL CORNERS
10d	0.148" X 3"	0.131" X 3"	8" O.C. (COMMON)	STUD PACK COLUMNS
16d	0.162" X 3 1/2"	0.131" X 3 1/2"	(2) 16d (COMMON)	SEE PLAN

MARK	HEADER SIZE	REMARKS
[H1]	(2) - 2X6 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
[H2]	(2) - 2X8 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
[H3]	(2) - 2X10 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
[H4]	(2) - 2X12 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
[H5]	(2) - 1 3/4" X 11 1/4" LVL 2.0E FB-2600 PSI	ATTACH TOGETHER W/ (2) ROWS 14" X 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE
[H6]	(2) - 1 3/4" X 9 1/4" LVL 2.0E FB-2600 PSI	ATTACH TOGETHER W/ (3) ROWS 14" X 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE

HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS

OPENING SIZE	2x4 WALL JACKS EA. END	2x6 OR 2x8 WALL JACKS EA. END
1'-0" - 3'-11"	(1)	(2)
4'-0" - 9'-11"	(2)	(3)
10'-0" - 16'-0"	(3)	(4)


GENERAL HEADER NOTES

- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
- IF HEADER IS ON THE 1st FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS U.N.O. ON PLAN
- IF HEADER IS ON THE 2nd FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS
- ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL WF37
- FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" o.c. ALONG EACH EDGE OR (3) ROWS IF 2x10 OR LARGER
- FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d TOENAILS PER SIDE
- IF HEADER IS NOT SPECIFIED CONTACT E.O.R.

MARK	BEAM SIZE	CONNECTIONS
[BM1]	(2) - 2 x 8 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HTA16 TO CMU COL. U.N.O. ON ROOF PLAN.
[BM2]	(2) - 2 x 10 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HTA16 TO CMU COL. U.N.O. ON ROOF PLAN.
[BM3]	(2) - 2 x 12 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HTA16 TO CMU COL. U.N.O. ON ROOF PLAN.
[BM4]	(2) - 1 3/4" X 11 1/4" LVL 2.0E FB-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HTA16 TO CMU COL. U.N.O. ON ROOF PLAN.
[BM5]	(2) - 1 3/4" X 11 7/8" LVL 2.0E FB-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HTA16 TO CMU COL. U.N.O. ON ROOF PLAN.
[BM6]	(2) - 1 3/4" X 16" LVL 2.0E FB-2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HTA16 TO CMU COL. U.N.O. ON ROOF PLAN.

GENERAL BEAM NOTES


- VERIFY WITH PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEARING EACH END)
- SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
- BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.



Y	N	MASTER BA. OPTIONS
X		4030 TILE SHOWER IN LIEU OF LINEN CLOSET W/ (3) L.E.D. DISC LT.

OPTIONAL MASTER BATH

NOTE: NO DIMENSIONAL CHANGES



FLOOR PLAN

SCALE: 1/4" = 1'-0"
ELEVATION "A", "B"

NOTE:
INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

WALL LEGEND

- FRAMED WALL
- BEARING FRAME WALL
- FRAMED WALL W/ BRICK VENEER
- FRAMED WALL W/ SIDING OR STUCCO

GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used I.L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycombcore steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surfaces and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
- Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.2.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below or the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
 - M1502.4.5 Duct length
The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3
M1502.3 Duct termination
Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
 - Porch Ceilings: (See plan for the following options)
 - Option 1: Gypsum:
 - 1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
 - The gypsum board shall be attached w/ Type "W" 1x4" drywall screws at 8" O.C. in field and edges.
 - Option 2: Plaster Base:
 - 7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
 - Energy Code Compliance Plan is Performance Based Path Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FLOORING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

AREA CALCULATIONS

1st FLOOR	1816 S.F.
TOTAL LIVING (AC)	1816 S.F.
GARAGE	401 S.F.
COVERED ENTRY (BASE)	76 S.F.
COVERED PATIO/LANAI	104 S.F.
TOTAL AREA UNDER ROOF	2397 S.F.

COUNTY SEAL

www.roseandfrees.com

KEESSEE ASSOCIATES ARCHITECTURE DESIGN

2200 W. Main Street, Suite 200
Gainesville, TX 77901
Tel: 817.580.2355
goveesee.com

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

Model Name / Number:

1820

Plan Issue Date:
Wednesday, July 24, 2024

KA PROJECT NUMBER:
24-08046

Sheet: 2

OR:






FLOOR PLAN A

INVENTORY

LOT: 140
BLK:
SEC:
SUB: Preserve of Laurel Lake
SW Silver Palm Drive
Lake City

Carl A. Brown, P.E.
Scott A. Lemkowski, PE # 78750
Then Bao Duong, PE # 94452

Wednesday, July 24, 2024



STEMWALL SCHEDULE					
STEMWALL HEIGHT (ft)	FOOTING DIMENSION				MAXIMUM F.C. SPACING (O.C.) IN STEM WALL
	d 1 STORY	b 2 STORY	b 1 STORY	b 2 STORY	
0'-0" - 2'-0"	8"	16"	20"	24"	6'-8"
>2'-0" - 3'-4"	10"	10"	20"	24"	5'-4"
>3'-4" - 4'-0"	12"	12"	32"	32"	4'-0"
>4'-0" - 5'-4"	16"	16"	48"	48"	2'-8"

NOTES:

- VERTICAL REIN. IN SOLID GROUTED CELLS AT ALL CORNERS, JAMBS, WALL INTERSECTIONS, BELOW GIRDER TRUSS LOCATIONS, AND AT THE MAXIMUM SPACING STATED IN SCHEDULE
- W.W.M. IS REQUIRED TO MAKE ADEQUATE CONNECTION BETWEEN SLAB AND WALL WHEN STEM WALL EXCEEDS 4'-0". FIBERMESH CAN NOT BE USED AND #4 TURN BARS ARE REQUIRED @ EACH FILLED CELL LOCATION. EACH BAR TO TIE INTO VERTICAL BAR AND EXTEND OUT A MIN. 4'-0" INTO SLAB/STEM
- IF STEM IS REQ'D TO BE HIGHER CONTACT ENGINEER OF RECORD PRIOR TO CONSTRUCTION FOR MORE INFORMATION
- G.C. TO PROVIDE ADEQUATE BRACING OF STEM WALL WHEN UNEVEN BACK FILLING IS TAKING PLACE
- #5 HORIZONTAL CORNER BARS WITH 4'-0" LEGS IN KNOCKOUT BLOCK @ 16" O.C. VERTICAL. GROUTED SOLID WHEN STEM WALL IS GREATER THAN 4'-0" TALL (TYPICAL ALL CORNERS)
- IF STEMWALL IS WITH IN 2'-0" OF POOL OR WATER FEATURE FOUNDATIONS TO BE A MINIMUM 12" BELOW BOTTOM OF POOL OR WATER FEATURE.
- ALL STEM WALLS GREATER THAN (4) COURSES SHALL BE FULLY GROUTED.
- R.403.1.4 MINIMUM DEPTH: ALL EXTERIOR FOOTINGS (BOTTOM) SHALL BE PLACED AT LEAST 12" BELOW THE UNDISTURBED GROUND SURFACE.

SEE CHART ABOVE STEMWALL F.C. SPACING

EXTERIOR SHORING BY CONTRACTOR AS REQ'D WHEN STEM WALL IS OVER 4'-0"

FINISH GRADE

MIN. 8" COVER REQ'D

3" COVER TYP.

SEE SCHEDULE FOR REIN.

SEE CHART ABOVE STEMWALL F.C. SPACING

IF USED: W.W.M. TO BE TIED TO #5 CONT. REBAR

COMPACTED CLEAN FILL


SEE SCHEDULE FOR REIN.

FMSW ALTERNATE STEM WALL FOOTING SCHEDULE 1/2" = 1'-0"

GENERAL FOUNDATION NOTES (U.N.O.)				
1	PROVIDE MIN. 6 MIL. APPROVED VAPOR BARRIER. ALL JOINTS TO BE LAPPED MIN. 6" AND SEALED.			
2	4" 2500 PSI CONC. SLAB W/ 6X6 W1.4 x W1.4 OR FIBERMESH / FIBERMIX ADDED TO THE CONCRETE. IN ACCORDANCE W/ MANUF'S INSTRUCTIONS AND NER-284 FOR FIBERMESH OR NER-41.2 FOR FIBERMIX, OVER 6 MIL VISCQUEEN VAPOR BARRIER. GC SHALL PROVIDE APPROVED SOIL OR BORATE THERMIT TREATMENT.			
3	INDICATES FILLED CELL W/ 3000 PSI CONC. FROM FTR. TO BEAM W/ (1) #5 REBAR TYPICAL ABOVE SLAB. HOOKED FTG. DOWELS 17" EMBEDMENT W/ 30" EXT. ABOVE SLAB.			
4	CONSULT W/ MANUF. SPECIFICATIONS PRIOR TO POURING OR RECESSING DOOR SILLS OR SLIDING GLASS DOOR SILLS.			
5	EXTERIOR SLABS SHALL SLOPE MIN. 2% OR 1/4" PER FOOT AWAY FROM HOUSE U.N.O. ON PLAN.			
6	CONTROL JOINTS (IF SHOWN) ARE NOT REQUIRED BY CODE BUT ARE SUGGESTED (ESPECIALLY WHEN USING FIBER REIN. CONCRETE OR IN EXTERIOR CONDITIONS). CONTROL JOINTS TO BE 1/8" SAW CUT A DEPTH OF 1/4 OF THE THICKNESS OF THE SLAB AND SPACED MAX. 10' APART. FILL CUT W/ APPROVED JOINT MATERIAL OR USE ALTERNATE APPROVED METHOD.			
7	NO WOOD STAKES PERMITTED IN FOUNDATION.			
8	PENDING SITE CONDITIONS, FOUNDATION MAY HAVE TO BE STEPPED DOWN. G.C. TO DETERMINE STEP LOCATIONS IF REQUIRED.			
9	R403.1.4 MINIMUM DEPTH. EXTERIOR FOOTINGS SHALL BE PLACED NOT LESS THAN 12 INCHES BELOW THE FINISHED GRADE OF GROUND SURFACE. WHERE APPLICABLE, THE DEPTH OF FOOTINGS SHALL ALSO CONFORM TO SECTION R403.1.4.1.			
10	MASON TO COORDINATE WITH BUILDER ANY ELECTRICAL REQUIREMENT THROUGH SLAB			
11	PROVIDE 4" STEPDOWN TO SIDEWALK FROM ENTRY			
12	ASSUMED ALLOWABLE SOIL BEARING PRESSURE AFTER COMPACTION: 2000 PSF SEE SOILS REPORT AND SPECIFICATIONS FOR COMPACTION REQUIREMENTS IF SOIL CONDITIONS IN THE PROJECT DO NOT MEET OR EXCEED THE CAPACITY THE GENERAL CONTRACTOR SHALL CONTACT THE ENGINEER PRIOR TO FOUNDATION POUR FOR VERIFICATION OF FOUNDATION DESIGN. SOIL TO BE COMPACTED TO AT LEAST 95% OF MAX. DRY DENSITY AS DETERMINED BY ASTM - 1557 (MODIFIED PROCTOR) THE FOUNDATION SIZES INDICATED ON THE FOUNDATION PLAN HAS BEEN DESIGNED FOR A MINIMUM SOIL BEARING CAPACITY OF 2000 PSF.			

FOOTING SCHEDULE				
MARK	SIZE	DEPTH	REINFORCING	GRAVITY CAP. (lbs)
F1.0	1'-0" X CONT.	1'-0"	2 #5 E.W. BOT.	2000
F2.0	2'-0" X 2'-0"	1'-0"	3 #5 E.W. BOT.	7200
F2.5	2'-6" X 2'-6"	1'-0"	3 #5 E.W. BOT.	11000
F3.0	3'-0" X 3'-0"	1'-0"	4 #5 E.W. BOT.	15600
F3.5	3'-6" X 3'-6"	1'-0"	4 #5 E.W. BOT.	21500
F4.0	4'-0" X 4'-0"	1'-0"	5 #5 E.W. BOT.	28000
F4.5	4'-6" X 4'-6"	1'-4"	5 #5 E.W. BOT.	34500
F5.0	5'-0" X 5'-0"	1'-4"	6 #5 E.W. BOT.	42500
F6.0	6'-0" X 6'-0"	1'-4"	7 #5 E.W. BOT.	61500

LEGEND	
	- INDICATES SINGLE-STORY FOOTING
	- INDICATES TWO-STORY FOOTING
	- INDICATES PAD FOOTING



FOUNDATION PLAN
SCALE: 1/4" = 1'-0"
ELEVATION "A", "B"

COUNTY SEAL

keese
associates
ARCHITECTURE DESIGN
2255 W. Main St., Suite 200
Gainesville, FL 32609
www.keese.com

DAMS HOMES
FLORIDA CONTRACTORS' LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 140
BLK:
SEC:
SUB: Preserve of Laurel Lake
SW Silver Palm Drive
Lake City

Model Name / Number:
1820

Plan Issue Date:
Wednesday, July 24, 2024


KA PROJECT NUMBER:
24-08046

Sheet: 3


FOUNDATION PLAN

Wednesday, July 24, 2024

<p>LOCATION OF BARRIER TO BE 1'-0" IN FRONT OF MECH. OR APP. WHEN REQUIRED</p> <p>MIN. 2'-0" DIA. SCH. 40 STEEL PIPE OR UNWELDED WATER HEATER PROTECTION</p> <p>ELECTRIC</p> <p>(A) 12" x 4" WEDGE ANCHOR BOLTS W/ MIN. MAX. 3" EMBEDMENT</p> <p>MIN. 4" DIA. SCH. 40 STEEL PIPE FILLED W/ CONCRETE FOR GAS WATER HEATER PROTECTION</p> <p>TOP OF SLAB</p> <p>1'-0" DIA. 14" MIN. DIAMETER CONCRETE FOOTING</p> <p>SECTION A-A</p>	<p>N.T.S.</p>
<p>FM24</p>	<p>PROTECTION BARRIER</p> <p>N.T.S.</p>
<p>USE 2 RED HEADS TO ANCHOR WALL</p>	<p>FM24.1</p> <p>ALTERNATIVE PROTECTION BARRIER</p> <p>N.T.S.</p>




VENTILATION CALCULATION		
Formula = SF / 300 / 2 * 144 = net sq inches of venting needed equally for intake and exhaust		
Soffit product provides	4.12	net sq in / sf
Ridge vent provides	18.00	net sq in / lf
Off ridge vent provides	138.00	net sq in / sf
Overhang distance	2.00	ft
S.F. of Area to be vented (SF)	2462	s.f.
Total needed for exhaust for upper 1/3	591	net sq inches
Total needed for intake (soffit area, lower)	591	net sq inches
Number of Off Ridge Vents for upper 1/3 needed	4	
L.F. of Ridge Vent needed (can be used in combo with ORV)	33	
Lineal Feet of Soffit needed to meet required	72	
Lineal S.F. provided by plan	209	



RIGHT ELEVATION "B"

SCALE: 1/4" = 1'-0"




LEFT ELEVATION "B"

SCALE: 1/4" = 1'-0"



REAR ELEVATION

SCALE: 1/4" = 1'-0"



FRONT ELEVATION "B"

SCALE: 1/4" = 1'-0"

COUNTY
SEAL

Wednesday, July 24, 2024

www.FDSEngineers.com

FDSE

ENGINEERING ASSOCIATES

0 (201) 880-2335
288 South Main Lane, Suite 200
Pensacola, Florida 32501

Carl A. Brown, P.E.
Scott A. Lewowski, P.E.
Thien Bao Duong, P.E.

FL # 55126
FL # 78750
FL # 94452

www.keeseearchitect.com

keeseearchitect

ARCHITECTURE | DESIGN

2304 W. Lake Meade, Suite 200
Pensacola, FL 32507
850.880.2335
www.keeseearchitect.com

AA2600319

AB

AD

BD

CD

DE

FE

GE

HE

IE

JE

KE

LE

ME

NE

OE

PE

QE

RE

SE

TE

UE

VE

WE

XE

YE

ZE

DAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY

LOT: 140
BLK:
SEC:
SUB: Preserve of Laurel Lake
SW Silver Palm Drive
Lake City

Model Name / Number:
1820


Plan Issue Date:
Wednesday, July 24, 2024

KA PROJECT NUMBER:
24-08046


Sheet: **5** of:

ELEVATIONS-B


<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;"> </div> <div style="text-align: center;"> <p style="font-size: 24px; margin: 0;">COUNTY</p> <p style="font-size: 24px; margin: 0;">SEAL</p> </div> </div>	
<p style="font-size: 8px;">To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contained within these documents comply with the applicable provisions of the Florida Building Code, and the Engineer is not providing any design services for the structural engineering portions of the following project, leaving it to the Engineer's signature and seal.</p>	<div style="text-align: center;"> <p style="font-weight: bold; margin: 5px 0;">FDS</p> <p style="font-weight: bold; margin: 0 0;">ENGINEERING ASSOCIATES</p> <p style="font-size: 8px;">258 Southlake Avenue, Suite 200 Southlake, Florida 33575-2000 D (231) 972-0451 / F (407) 880-2334</p> <p style="font-size: 8px;">www.fdseng.com</p> </div> <div style="margin-top: 10px;"> <input type="checkbox"/> CARL A. BROWN, P.E. FL # 561126 <input type="checkbox"/> SCOTT A. LEMKOWSKI, PE, FL # 78750 <input type="checkbox"/> THOMAS BLOOMING, PE FL # 94452 </div>
<div style="text-align: center;"> <p style="font-weight: bold; margin: 0;">KEESE</p> <p style="font-weight: bold; margin: 0;">associates</p> <p style="font-weight: bold; margin: 0;">ARCHITECTURE DESIGN </p> <p style="margin: 0;">258 Southlake Lane, Maitland, FL 32751, Suite 200 o (407) 880-2333 g@keese.com</p> </div>	<div style="text-align: right; margin-bottom: 10px;"> <p style="font-size: 8px;">AA28600315</p> </div> <div style="display: flex; justify-content: space-around; align-items: center;"> </div>
<div style="display: flex; align-items: center;"> <p style="margin: 0;">DAMS HOMES</p> </div> <p style="font-size: 8px; margin: 5px 0;">FLORIDA CONTRACTORS' LICENSE NO. CRC1330146</p> <p style="font-weight: bold; margin: 0;">100 WEST GARDEN STREET PENSACOLA FL 32502</p>	
<p style="text-align: center; font-weight: bold; margin: 0;">DIVISION LOCATION:</p> <p style="text-align: center; font-weight: bold; margin: 0;">GAINESVILLE</p>	
<p style="font-size: 8px; margin: 0;">Job Information:</p>	
<p style="font-size: 24px; font-weight: bold; transform: rotate(-90deg); transform-origin: left top;">INVENTORY</p>	<p style="font-size: 18px; margin: 0;">LOT: 140</p> <p style="font-size: 18px; margin: 0;">BLK:</p> <p style="font-size: 18px; margin: 0;">SEC:</p> <p style="font-size: 18px; margin: 0;">SUB: Preserve of Laurel Lake</p> <p style="font-size: 12px; margin: 0;">SW Silver Palm Drive Lake City</p>
<p style="font-size: 8px; margin: 0;">Model Name / Number:</p> <p style="font-weight: bold; margin: 0;">1820</p>	
<p style="font-size: 8px; margin: 0;">Plan Issue Date:</p> <p style="margin: 0;">Wednesday, July 24, 2024</p>	
<p style="font-size: 8px; margin: 0;">KA PROJECT NUMBER:</p> <p style="font-weight: bold; margin: 0;">24-08046</p>	
<p style="font-size: 8px; margin: 0;">Sheet:</p> <p style="font-size: 24px; font-weight: bold; margin: 0;">S-1</p>	<p style="font-size: 8px; margin: 0;">of:</p>
<p style="font-size: 18px; font-weight: bold; margin: 0;">ROOF PLAN A</p>	




TB15 EXTERIOR NON-BEARING WALL DETAIL N.T.S.




WC04 GARAGE HEADER ANCHOR 3/4" = 1'-0"




WC05 SECT. OVERHEAD GAR. DOOR INSTALL N.T.S.




WF64 EXTERIOR NON BRG. WALL DETAIL N.T.S.




WF43 EXTERIOR ANGLED WALL DETAIL N.T.S.




WC03 WALL TO WALL CONN. @ END OF SHEARWALL 1 1/2" = 1'-0"




CD11 COMMON BEAM ATTACHMENT N.T.S.




CD25 BEAM TO WALL CONNECTION N.T.S.




WF66 TYPICAL BEARING WALL N.T.S.




WC09 WALL STEP @ CORNER N.T.S.




WC06 EXTERIOR FRAME CORNER 3/4" = 1'-0"



RD01 VALLEY FLASHING DETAIL N.T.S.



CD26 GIRDER BASE CONNECTION 1/2" = 1'-0"



WF68 CORNER CONNECTION N.T.S.

COUNTY
SEAL

Wednesday, July 24, 2024

FDS ENGINEERING ASSOCIATES
www.fdseng.com
255 Seaboard Lane, Suite 200
Maitland, Florida 32751
407.980.2323
fdseesee.com

Keese Associates
ARCHITECTURE | DESIGN | INTERIORS
2407 N.W. 23rd Ave., Suite 200
Fort Lauderdale, FL 33309
954.566.2004
www.keese.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY
LOT: 140
BLK:
SEC:
SUB: Preserve of Laure Lake
SW Silver Palm Drive
Lake City


Model Name / Number:
1820

Plan Issue Date:
Wednesday, July 24, 2024


KA PROJECT NUMBER:
24-08046

Sheet: **S-2** Of:


TYPICAL FRAMING DETAILS



WF39 TRANSOM DETAIL AT ENTRY 1/2" = 1'-0"



WF09 WALL HEADER DETAIL N.T.S.



WF67 WALL FRAMING 3/4" = 1'-0"

COUNTY SEAL

Wednesday, July 24, 2024

To the best of the Engineer's knowledge, information, and belief, the design and construction of the above project complies with the applicable building codes and standards, and the Engineer is not providing any warranty or guarantee of performance or results, and the Engineer is not responsible for any errors or omissions in the design or construction of the project.

FDS ENGINEERING ASSOCIATES

ARCHITECTURE | DESIGN | CONSTRUCTION

2550 S. GULF BLVD., SUITE 200
FORT MYERS, FL 33901
TEL: 888-280-2344
WWW.FDSENGINEERING.COM

FL # 56126
FL # 78750
FL # 94452

□ CARL A. BROWN, P.E.
□ SCOTT A. LEWIS, P.E.
□ THEN BAO DUONG, P.E.

keesees associates

ARCHITECTURE | DESIGN | CONSTRUCTION

2550 S. GULF BLVD., SUITE 200
FORT MYERS, FL 33901
TEL: 888-280-2344
WWW.KEESEES.COM

FL # 56126
FL # 78750
FL # 94452

□ CARL A. BROWN, P.E.
□ SCOTT A. LEWIS, P.E.
□ THEN BAO DUONG, P.E.

DAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

**100 WEST GARDEN STREET
PENSACOLA FL 32502**

**DIVISION LOCATION:
GAINESVILLE**

INVENTORY

LOT: 140
BLK:
SEC:
SUB: Preserve of Laurel Lake
SW Silver Palm Drive
Lake City


Model Name / Number:
1820

Plan Issue Date:
Wednesday, July 24, 2024


KA PROJECT NUMBER:
24-08046

Sheet: **S-2.1** Of:


TYPICAL FRAMING DETAILS




BD12 TYPICAL WALL SECTION @ WINDOW 3/4" = 1'-0"




WF37 TYPICAL COLUMNS DETAILS N.T.S.




CD24 POST & BEAM DETAIL 1/2" = 1'-0"




BD07 BRICK SHELF DETAIL N.T.S.




WF17 TOP PLATE SPLICE DETAIL 3/4" = 1'-0"




SW01 INTERIOR BEARING SHEARWALL w/UPLIFT N.T.S.




WC08 STEP UP @ CORNER & RAISED BEAM N.T.S.




SE TYPICAL SOFFIT AND EAVE DETAIL 3/4" = 1'-0"



WF63 SECTION AT DOUBLE BEARING N.T.S.



WC07 STEP UP @ CORNER & RAISED BEAM 1/2" = 1'-0"



SW04 INTERIOR SHEARWALL @ TRUSSES 3/4" = 1'-0"

COUNTY
SEAL

Wednesday, July 24, 2024

www.fdsinc.com

FDS
ENGINEERING ASSOCIATES
2201 N. W. 13th Ave., Suite 200
Fort Lauderdale, FL 33304
Tel: 954.333.8800
Fax: 954.333.8801
www.fdsinc.com

Keese Associates
ARCHITECTURE DESIGN
2201 N. W. 13th Ave., Suite 200
Fort Lauderdale, FL 33304
Tel: 954.333.8800
Fax: 954.333.8801
www.keese.com

AA2602116
AIA
BD

FL # 86126
FL # 78750
FL # 94452

CARL A. BROWN, P.E.
SCOTT A. LEWIS, P.E.
THEN BAO DUONG, P.E.

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330148
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY
LOT: 140
BLK:
SEC:
SUB: Preserve of Laurel Lake
SW Silver Palm Drive
Lake City


Model Name / Number:
1820

Plan Issue Date:
Wednesday, July 24, 2024


KA PROJECT NUMBER:
24-08046

Sheet: **S-3** Of:

TYPICAL WALL DETAILS




TB01 TYPICAL CROSS BRACING DETAIL N.T.S.




TB02 TYPICAL CROSS BRACING DETAIL N.T.S.

THE HEIGHT OF THE CHIMNEY SHOULD EXTEND 2' ABOVE THE POINT WHERE THE CHIMNEY IS 10' FROM THE NEAREST BUILDING SURFACE.




CH01 TYPICAL CHIMNEY FRAME DETAIL 3/4" = 1'-0"


RAFTER SIZE	
0'-8" SPAN -	2"x6" W/4-12d EACH END
8'-12" SPAN -	2"x8" W/4-12d EACH END
12'-15" SPAN -	2"x10" W/ SIMPSON A 34 @ EA. END
15'-18" SPAN -	2"x12" W/ SIMPSON A 34 @ EA. END




TB17 CONV. FRAMING & VALLEY FRAMING N.T.S.




TB03 HIP / RIDGE BLOCKING DETAIL N.T.S.



TB04 TRUSS BRACING OVERLAP DETAIL (TYP) N.T.S.






GE04 "T" BRACE CONNECTION @ GABLE END W/ VOLUME CEILING 3/4" = 1'-0"



WF05 DORMER FRAMING DETAIL N.T.S.

TRUSS NOTES:

- WOOD TRUSS ERECTOR SHALL PROVIDE BRACING ACCORDING TO ANSI/TPI-2014 (TRUSS PLATE INSTITUTE) NOTE THAT THE COMBINED WIND AREA IS GREATER BEFORE THE ROOF SHEATHING IS APPLIED, AND BRACING SHALL THEREFORE BE INSTALLED AS THE TRUSSES ARE ERECTED. INADEQUATE BRACING IS THE MOST COMMON CAUSE OF ACCIDENT IN WOOD TRUSS CONSTRUCTION. FULL BUNDLES OF SHEATHING SHALL NOT BE PLACED ON TRUSSES. THIS CONSTRUCTION LOAD SHOULD BE LIMITED TO 8 SHEETS OF SHEATHING ON ANY PAIR OF TRUSSES & SHALL BE LOCATED ADJACENT TO THE SUPPORTS. NO EXCESS CONCENTRATION OF ANY CONSTRUCTION MATERIAL (SUCH AS GRAVEL OR SHINGLES) SHALL BE PLACED ON THE TRUSSES IN ANY ONE AREA THEY SHALL BE SPREAD OUT EVENLY OVER A LARGE AREA SO AS TO AVOID OVERLOADING ANY ONE TRUSS.
- ALL BRACING (DB, CB, BB) SHOWN ABOVE SHALL BE IN ADDITION TO CONTINUOUS LATERAL BRACING SPECIFIED BY THE TRUSS MANUFACTURER. ALL LATERAL BRACING SPECIFIED BY TRUSS MANUF. SHALL HAVE ADDITIONAL DIAGONAL BRACES AT 20'-0" O.C. MAXIMUM.
- ALL BRACES SHALL BE 2x4 NOMINAL DIMENSION LUMBER & SHALL BE ATTACHED W/ (3) 12d NAILS AT EACH TRUSS INTERSECTION.
- ADDITIONAL BOTTOM CHORD BRACING SHALL BE INSTALLED AS REQUIRED BY TRUSS DESIGN WHEREVER ADEQUATE STRUCTURAL CEILING ARE NOT ATTACHED DIRECTLY TO THE BOTTOM CHORD OF THE TRUSS.
- PROVIDE TRUSS BLOCKING AT ALL TRUSS BEARING SUPPORTS WHERE TRUSS DEPTH EXCEEDS STANDARD HEEL HEIGHT. SEE TYP. TRUSS BLOCKING DETAILS.



A-A ALTERNATE BLOCKING DETAIL @ INTERIOR BEARING

TYP. WOOD TRUSS BLOCKING @ RAISED HEEL DETAIL

TB06 BLOCKING AND CONVENTIONAL FRAME DETAILS 3/4" = 1'-0"

COUNTY SEAL

To the best of the Engineer's knowledge, information, and belief, the structure shown on this plan complies with the applicable provisions of the Florida Building Code, and the design and construction of the structure is in accordance with the applicable provisions of the Florida Building Code. The Engineer does not warrant the design or construction of the structure for any other purpose or for any other use than that intended by the owner.

FDS ENGINEERING ASSOCIATES
2540 Silver Palm Lane, Suite 200
Naples, FL 34109
P: 239.438.2304
F: 239.438.2304
www.fdsengineering.com

Keese Associates
ARCHITECTURE | DESIGN | INTERIORS
2540 Silver Palm Lane, Suite 200
Naples, FL 34109
P: 239.438.2304
F: 239.438.2304
www.keeseassociates.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330148
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 140
BLK:
SEC:
SUB: Preserve of Laurel Lake
SW Silver Palm Drive
Lake City

Model Name / Number:
1820


Plan Issue Date:
Wednesday, July 24, 2024

KA PROJECT NUMBER:
24-08046


Sheet: **S-4** Of:

ROOF FRAMING AND BRACING DETAILS


Wednesday, July 24, 2024




GE05 GABLE END BRACING - FRAME WALL N.T.S.




GE22 GABLE END BRACING w/ VOL CEILING 1/2"=1'-0"




GE23 GABLE END BRACING w/o VOLUME CEILING 1/2"=1'-0"




GE24 GABLE @ VAULT N.T.S.




WF72 LEDGER N.T.S.




WF73 KNEEWALL @ DORMER N.T.S.





GE21 SECTION @ DUTCH GABLE 3/4"=1'-0"



LD02 SHEAR TRANSFER EXTERIOR WALL N.T.S.



GE23.1 GABLE END OVERHANG 1/2"=1'-0"



SR01 SECTION AT SHED ROOF 3/4"=1'-0"

COUNTY
SEAL

To the best of the Engineer's knowledge, information, and belief, the design complies with all applicable codes, regulations, and standards, and the Engineer is not providing any warranty or representation regarding the design or the construction of the project.

FDS ENGINEERS ASSOCIATES
ARCHITECTURE DESIGN
22407 SW 23535
Gainesville, FL 32609
www.fdseng.com

Professional Engineer
No. 1251
State of Florida
No. 25751
Date 200

Carl A. Brown, P.E.
Scott A. Lewkowksi, P.E.
Then Bao Clong, P.E.

FL # 89326
FL # 78750
FL # 94152

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC13301148
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 140
BLK:
SEC:
SUB: Preserve of Laurel Lake
SW Silver Palm Drive
Lake City

Model Name / Number:

1820

Plan Issue Date:

Wednesday, July 24, 2024

KA PROJECT NUMBER:

24-08046

Sheet: **S-4.1** Of:

ROOF FRAMING AND BRACING DETAILS

Wednesday, July 24, 2024

