

CAROL CHADWICK, P.E.

Civil Engineer

1208 S.W. Fairfax Glen

Lake City, FL 32025

307.680.1772

ccpewyo@gmail.com

www.carolchadwickpe.com

October 17, 2024

Martin & Rebekah McAlhany

re: ELEVATION LETTER – 460 SW MARYNIK DRIVE, HIGH SPRINGS, FL

As requested, I inspected the building site for the proposed construction at the above referenced site. Per the flood report by SRWMD, there are no wetlands or floodplains on the site. Refer to the attached site plan by others.

The topography of the site drains to the west. The finished floor elevation of the home shall be 12" above the adjacent ground for the entire perimeter of the foundation, except driveways and sidewalks which must be flush with the finished floor elevation. The finished floor of the home will be below required elevation of one foot above the adjacent road.

I certify that the minimum finished floor elevation listed above will protect the structure against water damage from a base flood event, as defined in Article 8 of the Land Development Regulations.

Should you have any questions, please don't hesitate to contact me.

Respectfully,



Digitally signed by Carol Chadwick
DN: c=US, o=Florida,
dnQualifier=A01410D0000018D463
B4E7500032FEE, cn=Carol Chadwick
Date: 2024.10.17 16:34:24 -04'00'

Carol Chadwick, P.E.

attachments: SRWMD Flood Report & site plan sketch

This item has been digitally signed and sealed by Carol Chadwick, P.E. on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

CC Job #FL24515

EFFECTIVE FLOOD INFORMATION REPORT



Location Information

County: **COLUMBIA**
Parcel: **167S1710006213**
Flood Zone: **X**
Flood Risk: **LOW**

1% Annual Chance Base Flood Elev* **Not Applicable**
10% Annual Chance Flood Elev* **Not Applicable**
50% Annual Chance Flood Elev* **Not Applicable**

* Flood Elevations shown on this report are in NAVD 88 and are derived from FEMA flood mapping products, rounded to the nearest tenth of a foot. For more information, please see the note below

Legend with Flood Zone Designations

- | | | | |
|--|----------------------------|-------------------|----------|
| 1% Flood -Floodway (High Risk) | Area Not Included | CrossSections | Wetlands |
| 1% Flood - Zone AE (High Risk) | SFHA Decrease | County Boundaries | |
| 1% Flood - Zone A (HighRisk) | SFHA Increase | FIRM Panel Index | |
| 1% Flood - Zone VE (HighRisk) | Depressions | Parcels | |
| 0.2% Flood-Shaded Zone X (Moderate Risk) | BaseFlood Elevations (BFE) | River Marks | |

Supplemental Information

Watershed	Santa Fe	Map Effective Date	2/4/2009	Special Flood Hazard Area	No
FIRM Panel(s)	12023C0513C				

Anywhere it can rain, it can flood
Know your risk.



www.srwmfloodreport.com

The information herein represents the best available data as of the effective map date shown. The Federal Emergency Management Agency (FEMA) Flood Map Service Center (<https://msc.fema.gov>) maintains the database of Flood Insurance Studies and Digital Flood Insurance Rate Maps, as well as additional information such as how the Base Flood Elevations (BFEs) and/or floodways have been determined and previously issued Letters of Map Change. Requests to revise flood information may be provided to the District during the community review period on preliminary maps, or through the appropriate process with FEMA [Change Your Flood Zone Designation](https://www.floodsmart.com) | [FEMA.gov](https://www.floodsmart.com). Information about flood insurance may be obtained at (<https://www.floodsmart.com>)

Base Flood Elevation (BFE)

The elevation shown on the Flood Insurance Rate Map for Zones AE, AH, A1-A30, AR, AO, V1-V30, and VE that indicates the water surface elevation resulting from a flood that has a one percent chance of equaling or exceeding that level in any given year.

A

Areas with a 1% annual chance of flooding and a 26% chance of flooding over the life of a 30-year mortgage. Because detailed analyses are not performed for such areas; no depths or base flood elevations are shown within these zones.

AE, A1-A30

Areas with a 1% annual chance of flooding and a 26% chance of flooding over the life of a 30-year mortgage. In most instances, base flood elevations derived from detailed analyses are shown at selected intervals within these zones.

AH

Areas with a 1% annual chance of flooding and a 26% chance of flooding over the life of a 30-year mortgage. Usually areas of ponding with flood depths of 1 to 3 feet. Base Flood Elevations are determined.

AO

Areas with a 1% annual chance of flooding and a 26% chance of flooding over the life of a 30-year mortgage. Usually areas of sheet flow on sloping terrain with flood depths of 1 to 3 feet. Base Flood Elevations are determined.

Supplemental Information:

10%-chance flood elevations (10-year flood-risk elevations) and 50%-chance flood elevations (2-year flood-risk elevations), are calculated during detailed flooding studies but are not shown on FEMA Digital Flood Insurance Rate Maps (FIRMs). They have been provided as supplemental information in the Flood Information section of this report.

AE FW (FLOODWAYS)

The channel of a river or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood (1% annual chance flood event). The floodway must be kept open so that flood water can proceed downstream and not be obstructed or diverted onto other properties.

Please note, if you develop within the regulatory floodway, you will need to contact your Local Government and the Suwannee River Water Management District prior to commencing with the activity. Please contact the District at 800.226.1066.

VE

Areas with a 1% annual chance of flooding over the life of a 30-year mortgage with additional hazards due to storm-induced velocity wave action. Base Flood Elevations (BFEs) derived from detailed analyses.

X 0.2 PCT (X Shaded, 0.2 PCT ANNUAL CHANCE FLOOD HAZARD)

Same as Zone X; however, detailed studies have been performed, and the area has been determined to be within the 0.2 percent annual chance floodplain (also known as the 500-year flood zone). Insurance purchase is not required in this zone but is available at a reduced rate and is recommended.

X

All areas outside the 1-percent annual chance floodplain are Zone X. This includes areas of 1% annual chance sheet flow flooding where average depths are less than 1 foot, areas of 1% annual chance stream flooding where the contributing drainage area is less than 1 square mile, or areas protected from the 1% annual chance flood by levees. No Base Flood Elevations or depths are shown within this zone. Insurance purchase is not required in these zones.

LINKS FEMA:

<http://www.fema.gov>

SRWMD:

<http://www.srwmd.state.fl.us>


CONTACT

SRWMD
9225 County Road 49
Live Oak, FL 32060

(386) 362-1001


Toll Free:
(800) 226-1066

RIVER RISE
RESIDENTIAL SUBDIVISION, UNIT 1
PLAT BOOK 8, PAGE 51
LOT 12



* SITE PLAN *

SCALE : 1" = 30'-0"



NEW RESIDENCE
for
MARTIN & REBEKAH
McALHANY

Teena M. Ruffo
2925 SW SR 47
Lake City Florida, 32025
Cell: (386) 867-1191
Email: teenaruffo@gmail.com

PRINTED DATE:
Thursday, May 30, 2024

DRAWN BY: Teena M. Ruffo CHECKED BY:

BUILDING CONTRACTOR

FINAL DATE:

JOB NUMBER:

DRAWING NUMBER

A-1

OF 6 SHEETS