

# **VERIZON WIRELESS** ANTENNA AMENDMENT DRAWINGS

Always call 811 two full business days before you dig



# ATC SITE NAME: LAKE CITY FL SQA

ATC SITE NUMBER: 412243

VERIZON WIRELESS SITE NAME: PHILLIPS LAKE

CITY

**VERIZON WIRELESS SITE NUMBER: 131313 VERIZON WIRELESS FUZE PID: 16276469 VERIZON WIRELESS MDG LOCATION CODE:** 

5000077708

PO BOX 1683

LAKE CITY, FL 32056

PROJECT LOCATION DIRECTIONS

DIRECTIONS: FROM I-75 IN LAKE CITY TAKE EXIT 427 (HWY 90)

WEST CONTINUE WEST FOR 1.8 MILES TO BROWN RD AND TAKE A

RIGHT. FOLLOW BROWN RD TO THE LEFT BESIDE THE RR TRACKS.

GOING RIGHT AT THE FORK TO NASH RD. TAKE A RIGHT. TAKE

NEXT LEFT ONTO NW EDSEL ST. FOLLOW ROAD UPHILL TOWER IN

THE BACK OF PROPERTY SITE ADDRESS DOES NOT MATCH THE

911 ADDRESS, THE SITE ADDRESS IS THE CORRECT ADDRESS

PROFESSIONALS

326 TRYON ROAD

RALEIGH, NC 27603

SITE ADDRESS: 233 N W RANCH COURT LAKE CITY, FL 32055-8079



**LOCATION MAP** 

HTTPS://PMI.VZWSMART.COM

REFER TO MOUNT MODIFICATION DRAWINGS

PAGES FOR VZW SMART KIT APPROVED VENDORS

10231382

131313

\*\*\*PMI AND REQUIREMENTS ALSO EMBEDDED IN MOUNT ANALYSIS REPORT

#### COMPLIANCE CODE PROJECT SUMMARY PROJECT DESCRIPTION SHEET INDEX SITE ADDRESS: VERIZON WIRELESS IS PROPOSING THE FOLLOWING WORK TO BE SHEET NO DESCRIPTION REV: DATE: BY: ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE COMPLETED ON AN EXISTING 300' GUYED TOWER: 233 NORTH WEST RANCH COURT G-001 TITLE SHEET 0 06/21/24 PAP FOLLOWING CODES AS ADOPTED BY THE LOCAL LAKE CITY, FL 32055-8079 GOVERNMENT AUTHORITIES. NOTHING IN THESE PLANS IS REMOVE (3) SECTOR FRAME MOUNT(S), (12) ANTENNA(S), (3) GENERAL NOTES 06/21/24 PAP G-002 TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO COUNTY: COLUMBIA RRU(s), AND (16) 1-5/8" COAX CABLE(S) REGISTERED COORDINATES: C-001 OVERALL SITE PLAN 0 06/21/24 PAP INSTALL (3) SECTOR FRAME MOUNT(S) (9) ANTENNA(S), (6) RRU(s), 2023 FLORIDA BUILDING CODE, 8TH EDITION LATITUDE: 30° 13' 32.60" N NAD 83 PAP (1) OVP(s). AND (1) 6x12 HYBRIFLEX (1-1/4" HYBRIFLEX) CABLE(S). C-101 DETAILED SITE PLAN Ω 06/21/24 ANSI/TIA-222-H 8TH EDITION FLORIDA FIRE PREVENTION CODE LONGITUDE: 82° 43' 29.40" W DETAILED EQUIPMENT LAYOUT 06/21/24 PAP 2020 NATIONAL ELECTRICAL CODE (NFPA 70) C-102 0 GROUND ELEVATION: 465' AMSL REMOVE (1) CDMA CABINET(S), (1) 6201 ODE CABINET(S), (1) EBRE CITY/COUNTY ORDINANCES CABINET(S), (6) RRU(s), (1) 200A PPC(s), (1) ATS(s), (1) 30KW LP PAP C-201 TOWER FLEVATION 0 06/21/24 GEOGRAPHIC COORDINATES: DESIGN CRITERIA FOR STRUCTUAL ANALYSIS BY ATC DATED GENERATOR(S), (1) 250 GAL. PROPANE TANK(S), AND BATTERY(IES) PAP MAY 17, 2024 C-401 ANTENNA INFORMATION & SCHEDULE 06/21/24 LATITUDE: 30.22575, 30° 13' 32.59" N 0 INSTALL (3) HT200ET BATTERY STRING(S), (1) 200A ILC(s), (1) 50KW LONGITUDE: -82.72485, 82° 43' 29.39" W ULTIMATE WIND SPEED: LP GENERATOR(S), (1) 500 GALLON LP TANK(S), (1) BATTERY 119 MPH (3-SECOND GUST) C-501 CONSTRUCTION DETAILS 06/21/24 PAP 0 SERVICE WIND SPEED: CABINET(S), AND (1) CONSOLIDATED CABINET(S). **ZONING INFORMATION:** RISK CATEGORY: CONSTRUCTION DETAILS PAP 06/21/24 INSTALL ROUTER(S), BASEBAND(s), UPCONVERTER(s), AND EXPOSURE CATEGORY: JURISDICTION: COLUMBIA COUNTY TOPOGRAPHIC CATEGORY: SITEBOSS IN PROPOSED CONSOLIDATED CABINET(s) E-101 PANEL SCHEDULES 0 06/21/24 PAP PARCEL ID: 163S1602156002 PAP F-102 ONE-LINE DIAGRAM Ω 06/21/24 PROJECT TEAM F-103 **GROUNDING PLAN & SCHEMATIC** 0 06/21/24 **TOWER OWNER:** APPLICANT: PAP E-104 **GROUNDING PLAN & SCHEMATIC** 06/21/24 AMERICAN TOWER VERIZON WIRELESS **UTILITY COMPANIES** 10 PRESIDENTIAL WAY E-501 GROUNDING DETAILS 06/21/24 PAP POWER COMPANY: FLORIDA POWER & LIGHT **WOBURN, MA 01801** PROJECT NOTES PHONE: (800) 226-3545 R-601 - R-607 SUPPLEMENTAL PROPERTY OWNER: **ENGINEER:** THE FACILITY IS UNMANNED TELEPHONE COMPANY: VERIZON TOWER ENGINEERING REGISTER DANIEL P SR A TECHNICIAN WILL VISIT THE SITE APPROXIMATELY ONCE A CONTRACTOR PMI REQUIREMENTS PHONE: (888) 922-0204

MONTH FOR ROUTINE INSPECTION AND MAINTENANCE

HANDICAP ACCESS IS NOT REQUIRED

CHANGE UNDER CFR § 1.61000 (B)(7).

THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT LAND

NO SANITARY SEWER, POTABLE WATER OR TRASH DISPOSAL

THE PROJECT DEPICTED IN THESE PLANS QUALIFIES AS AN

REVIEW UNDER 47 U.S.C. § 1455(A) AS A MODIFICATION OF AN EXISTING WIRELESS TOWER THAT INVOLVES THE

ELIGIBLE FACILITIES REQUEST ENTITLED TO EXPEDITED

TRANSMISSION EQUIPMENT THAT IS NOT A SUBSTANTIAL

COLLOCATION, REMOVAL, AND/OR REPLACEMENT OF

DISTURBANCE OR EFFECT OF STORM WATER DRAINAGE.

PMI ACCESSED AT:

SMART TOOL VENDOR PROJECT NUMBER

VZW LOCATION CODE (PSLC):

MOUNT MODIFICATION REQUIRED:

VZW APPROVED SMART KIT VENDORS

# AMERICAN TOWER TOWER ENGINEERING PROFESSIONALS ATC SITE NUMBER 412243 ATC SITE NAME: LAKE CITY FL SQA VERIZON WIRELESS SITE NAME: PHILLIPS LAKE CITY SITE ADDRESS: 233 N W RANCH COURT LAKE CITY, FL 32055-8079 DIGITAL/ELECTRONIC SEAL: THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE ELECTRONIC COPIES



326 TRYON ROAD RALEIGH, NC 27603-3530 OFFICE: (919) 661-6351

1	DATE DRAWN:	06/21/24				
	ATC JOB NO:	14857598				
	CUSTOMER NAME:	PHILLIPS LAKE CITY				
	CUSTOMER ID:	131313				

TITLE SHEET

G-001

## **GENERAL CONSTRUCTION NOTES:**

- OWNER FURNISHED MATERIALS, VERIZON "THE COMPANY" WILL PROVIDE AND THE CONTRACTOR WILL INSTALL
- A. BTS EQUIPMENT FRAME (PLATFORM) AND ICEBRIDGE SHELTER (GROUND BUILD/CO-LOCATE ONLY)
- AC/TELCO INTERFACE BOX (PPC)
- ICE BRIDGE (CABLE TRAY WITH COVER) (GROUND BUILD/CO-LOCATE ONLY, GC TO FURNISH AND INSTALL FOR ROOFTOP INSTALLATION)
- D. TOWERS, MONOPOLES
- TOWER LIGHTING
- GENERATORS & LIQUID PROPANE TANK
- ANTENNA STANDARD BRACKETS, FRAMES AND PIPES FOR MOUNTING
- ANTENNAS (INSTALLED BY OTHERS)
- TRANSMISSION LINE
- TRANSMISSION LINE JUMPERS
- TRANSMISSION LINE CONNECTORS WITH WEATHERPROOFING KITS
- TRANSMISSION LINE GROUND KITS
- HANGERS
- HOISTING GRIPS
- O. BTS EQUIPMENT
- THE CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL OTHER MATERIALS FOR THE COMPLETE INSTALLATION OF THE SITE INCLUDING, BUT NOT LIMITED TO, SUCH MATERIALS AS FENCING, STRUCTURAL STEEL SUPPORTING SUB-FRAME FOR PLATFORM, ROOFING LABOR AND MATERIALS GROUNDING RINGS GROUNDING WIRES COPPER-CLAD OR XIT CHEMICAL GROUND ROD(S), BUSS BARS, TRANSFORMERS AND DISCONNECT SWITCHES WHERE APPLICABLE, TEMPORARY ELECTRICAL POWER, CONDUIT LANDSCAPING COMPOUND STONE, CRANES, CORE DRILLING, SI FEPERS AND RUBBER MATTING, REBAR, CONCRETE CAISSONS, PADS AND/OR AUGER MOUNTS, MISCELLANEOUS FASTENERS, CABLE TRAYS, NON-STANDARD ANTENNA FRAMES AND ALL OTHER MATERIAL AND LABOR REQUIRED TO COMPLETE THE JOB ACCORDING TO THE DRAWINGS AND SPECIFICATIONS. IT IS THE POSITION OF VERIZON TO APPLY FOR PERMITTING AND CONTRACTOR RESPONSIBLE FOR PICKUP AND PAYMENT OF REQUIRED
- ALL WORK SHALL CONFORM TO ALL CURRENT APPLICABLE FEDERAL, STATE, AND LOCAL CODES, INCLUDING ANSI/EIA/TIA-222, AND COMPLY WITH ATC CONSTRUCTION
- CONTRACTOR SHALL CONTACT LOCAL 811 FOR IDENTIFICATION OF UNDERGROUND
- CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIRED INSPECTIONS.
- ALL DIMENSIONS TO, OF, AND ON EXISTING BUILDINGS, DRAINAGE STRUCTURES, AND SITE IMPROVEMENTS SHALL BE VERIFIED IN FIELD BY CONTRACTOR WITH ALL DISCREPANCIES REPORTED TO THE ENGINEER.
- DO NOT CHANGE SIZE OR SPACING OF STRUCTURAL ELEMENTS
- DETAILS SHOWN ARE TYPICAL: SIMILAR DETAILS APPLY TO SIMILAR CONDITIONS UNLESS
- THESE DRAWINGS DO NOT INCLUDE NECESSARY COMPONENTS FOR CONSTRUCTION SAFETY WHICH SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR
- CONTRACTOR SHALL BRACE STRUCTURES UNTIL ALL STRUCTURAL ELEMENTS NEEDED FOR STABILITY ARE INSTALLED. THESE ELEMENTS ARE AS FOLLOWS: LATERAL BRACING,
- CONTRACTOR SHALL DETERMINE EXACT LOCATION OF EXISTING UTILITIES, GROUNDS DRAINS, DRAIN PIPES, VENTS, ETC, BEFORE COMMENCING WORK,
- INCORRECTLY FABRICATED, DAMAGED, OR OTHERWISE MISFITTING OR NONCONFORMING MATERIALS OR CONDITIONS SHALL BE REPORTED TO THE VERIZON REP PRIOR TO REMEDIAL OR CORRECTIVE ACTION, ANY SUCH REMEDIAL ACTION SHALL REQUIRE WRITTEN APPROVAL BY THE VERIZON REP PRIOR TO PROCEEDING.
- EACH CONTRACTOR SHALL COOPERATE WITH THE VERIZON REP, AND COORDINATE HIS WORK WITH THE WORK OF OTHERS.
- CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED BY CONSTRUCTION OF THIS PROJECT TO MATCH EXISTING PRE-CONSTRUCTION CONDITIONS TO THE SATISFACTION
- ALL CABLE/CONDUIT ENTRY/EXIT PORTS SHALL BE WEATHERPROOFED DURING 15. INSTALLATION LISING A SILICONE SEALANT
- WHERE EXISTING CONDITIONS DO NOT MATCH THOSE SHOWN IN THIS PLAN SET. CONTRACTOR SHALL NOTIFY THE VERIZON REP AND ENGINEER OF RECORD
- CONTRACTOR SHALL ENSURE ALL SUBCONTRACTORS ARE PROVIDED WITH A COMPLETE AND CURRENT SET OF DRAWINGS AND SPECIFICATIONS FOR THIS PROJECT.
- CONTRACTOR SHALL REMOVE ALL RUBBISH AND DEBRIS FROM THE SITE AT THE END OF
- CONTRACTOR SHALL COORDINATE WORK SCHEDULE WITH AMERICAN TOWER CORPORATION (ATC) AND TAKE PRECAUTIONS TO MINIMIZE IMPACT AND DISRUPTION OF OTHER OCCUPANTS OF THE FACILITY.
- CONTRACTOR SHALL FURNISH VERIZON AND AMERICAN TOWER CORPORATION (ATC) WITH A PDF MARKED UP AS-BUILT SET OF DRAWINGS UPON COMPLETION OF WORK
- PRIOR TO SUBMISSION OF BID, CONTRACTOR SHALL COORDINATE WITH VERIZON REP A. ALL EXTERIOR #6 GREEN GROUND WIRE "DAISY CHAIN" CONNECTIONS ARE TO BE PRIOR TO SUBMISSION OF BID, CONTRACTOR SHALL COUNCIDENT WITH VENICAL REF TO DETERMINE WHAT, IF ANY, ITEMS WILL BE PROVIDED. ALL ITEMS NOT PROVIDED SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR. CONTRACTOR WILL INSTALL

- TO DETERMINE IF ANY PERMITS WILL BE OBTAINED BY CONTRACTOR. ALL REQUIRED PERMITS NOT OBTAINED BY VERIZON MUST BE OBTAINED. AND PAID FOR, BY THE CONTRACTOR.
- 23. CONTRACTOR SHALL INSTALL ALL SITE SIGNAGE IN ACCORDANCE WITH VERIZON
- CONTRACTOR SHALL SUBMIT ALL SHOP DRAWINGS TO VERIZON FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.
- ALL EQUIPMENT SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND LOCATED ACCORDING TO VERIZON SPECIFICATIONS, AND AS SHOWN IN
- THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT.
- 27. CONTRACTOR SHALL NOTIFY VERIZON, REP A MINIMUM OF 48 HOURS IN ADVANCE OF POURING CONCRETE OR BACKFILLING ANY UNDERGROUND UTILITIES, FOUNDATIONS OR SEALING ANY WALL, FLOOR OR ROOF PENETRATIONS FOR ENGINEERING REVIEW AND
- 28 WHEN THE PROJECT SCOPE REQUIRES THE USE OF THE SAFETY CLIMB. THE GENERAL CONTRACTOR SHALL ENSURE THE SAFETY CLIMB IS FREE OF OBSTRUCTIONS, NOT RUBBING ON OR TRAPPED BY ANY INSTALLED CUSTOMER EQUIPMENT, IS VISUALLY TAUT, MEETS MANUFACTURER INSTALLATION SPECIFICATIONS, AND IS FIRMLY SECURED AT ALL CABLE GUIDE LOCATIONS UPON PROJECT COMPLETION.
- COMPLETION OF PROJECT SHALL NOT OBSTRUCT, TRAP, LOOSEN, OR OTHERWISE CALISE FAILURE TO MEET MANUFACTURER INSTALLATION REQUIREMENTS FOR THE SAFETY
- CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SAFETY INCLUDING COMPLIANCE WITH ALL APPLICABLE OSHA STANDARDS AND RECOMMENDATIONS AND SHALL PROVIDE ALL NECESSARY SAFETY DEVICES INCLUDING PPE AND PPM AND CONSTRUCTION DEVICES SUCH AS WELDING AND FIRE PREVENTION, TEMPORARY SHORING, SCAFFOLDING, TRENCH BOXES/SLOPING, BARRIERS, ETC
- 31. THE CONTRACTOR SHALL PROTECT AT HIS OWN EXPENSE, ALL EXISTING FACILITIES AND SUCH OF HIS NEW WORK LIABLE TO INJURY DURING THE CONSTRUCTION PERIOD. ANY DAMAGE CAUSED BY NEGLECT ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, OR BY THE ELEMENTS DUE TO NEGLECT ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, EITHER TO THE EXISTING WORK, OR TO HIS WORK OR THE WORK OF ANY OTHER CONTRACTOR, SHALL BE REPAIRED AT HIS EXPENSE TO THE
- ALL WORK SHALL BE INSTALLED IN A FIRST CLASS, NEAT AND WORKMANLIKE MANNER BY MECHANICS SKILLED IN THE TRADE INVOLVED. THE QUALITY OF WORKMANSHIP SHALL BE SUBJECT TO THE APPROVAL OF THE VERIZON REP. ANY WORK FOUND BY THE VERIZON REP TO BE OF INFERIOR QUALITY AND/OR WORKMANSHIP SHALL BE REPLACED AND/OR REWORKED AT CONTRACTOR EXPENSE UNTIL APPROVAL IS OBTAINED.
- 33 IN ORDER TO ESTABLISH STANDARDS OF QUALITY AND PERFORMANCE, ALL TYPES OF MATERIALS LISTED HEREINAFTER BY MANUFACTURER'S NAMES AND/OR MANUFACTURER'S CATALOG NUMBER SHALL BE PROVIDED BY THESE MANUFACTURERS AS SPECIFIED.
- VERIZON FURNISHED EQUIPMENT SHALL BE PICKED-UP AT THE VERIZON WAREHOUSE, NO LATER THAN 48HR AFTER BEING NOTIFIED INSURED. STORED, LINCRATE, PROTECTED AND INSTALLED BY THE CONTRACTOR WITH ALL APPURTENANCES REQUIRED TO PLACE THE EQUIPMENT IN OPERATION, READY FOR USE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE EQUIPMENT AFTER PICKING IT UP
- 35. VERIZON OR HIS ARCHITECT/ENGINEER RESERVES THE RIGHT TO REJECT ANY EQUIPMENT OR MATERIALS WHICH, IN HIS OWN OPINION ARE NOT IN COMPLIANCE WITH THE CONTRACT DOCUMENTS. EITHER BEFORE OR AFTER INSTALLATION AND THE EQUIPMENT SHALL BE REPLACED WITH EQUIPMENT CONFORMING TO THE REQUIREMENTS OF THE CONTRACT DOCUMENTS BY THE CONTRACTOR AT NO COST TO VERIZON OR THEIR ARCHITECT/ENGINEER

# SPECIAL CONSTRUCTION ANTENNA INSTALLATION NOTES:

- WORK INCLUDED:
- ANTENNA AND COAXIAL/HYBRID CABLES ARE FURNISHED BY VERIZON UNDER A SEPARATE CONTRACT. THE CONTRACTOR SHALL ASSIST ANTENNA INSTALLATION CONTRACTOR IN TERMS OF COORDINATION AND SITE ACCESS. ERECTION SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF PERSONNEL
- INSTALL ANTENNAS AS INDICATED ON DRAWINGS AND VERIZON SPECIFICATIONS.
- INSTALL GALVANIZED STEEL ANTENNA MOUNTS AS INDICATED ON DRAWINGS.
- INSTALL FURNISHED GALVANIZED STEEL OR ALUMINUM WAVEGUIDE.
- INSTALL COAXIAL/HYBRID CABLES AND TERMINATING BETWEEN ANTENNAS AND EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS, WEATHERPROOF ALL CONNECTIONS RETWEEN THE ANTENNA AND FOLIPMENT PER MANUFACTURER'S REQUIREMENTS, TERMINATE ALL COAXIAL/HYBRID CABLE THREE (3) FEET IN EXCESS OF ENTRY PORT LOCATION UNLESS OTHERWISE STATED.
- ANTENNA AND COAXIAL/HYBRID CABLE GROUNDING:
- WEATHER SEALED WITH RFS CONNECTORS/SPLICE WEATHERPROOFING KIT #221213 OR

22. PRIOR TO SUBMISSION OF BID, CONTRACTOR SHALL COORDINATE WITH VERIZON REP B. ALL COAXIAL/HYBRID CABLE GROUNDING KITS ARE TO BE INSTALLED ON STRAIGHT RUNS OF COAXIAL/HYBRID CABLE (NOT WITHIN BENDS)



ALL DISCREPANCIES FROM WHAT IS SHOWN ON THESE CONSTRUCTION DRAWINGS SHALL BE COMMUNICATED TO ATC ENGINEERING IMMEDIATELY FOR CORRECTION OR RE-DESIGN FAILURE TO COMMUNICATE DIRECTLY WITH ATC ENGINEERING OR ANY CHANGES FROM THE DESIGN CONDUCTED WITHOUT PRIOR APPROVAL FROM ATC ENGINEERING SHALL BE THE SOLE RESPONSIBILITY OF THE GENERAL CONTRACTOR.



TOWER ENGINEERING PROFESSIONALS 326 TRYON ROAD RALEIGH, NC 27603-3530 OFFICE: (919) 661-6351 www.tepgroup.net

> FL COA#: 31011 ATC SITE NUMBER

> > 412243

ATC SITE NAME LAKE CITY FL SQA

VERIZON WIRELESS SITE NAME: PHILLIPS LAKE CITY


SITE ADDRESS: 233 N W RANCH COURT

LAKE CITY, FL 32055-8079 DESCRIPTION DATE PRELIMINARY SAS 05/28/24 90% CONSTRUCTION KAG 06/14/24 100% CONSTRUCTION PAP 06/21/24

DIGITAL/ELECTRONIC SEAL:

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.




DATE DRAWN:	06/21/24			
ATC JOB NO:	14857598			
CUSTOMER NAME:	PHILLIPS LAKE CITY			
CUSTOMER ID:	131313			

**GENERAL NOTES** 

SHEET NUMBER:

G-002






326 TRYON ROAD RALEIGH, NC 27603-3530 OFFICE: (919) 661-6351 www.tepgroup.net

REV.	DESCRIPTION	BY	DATE
$\triangle$ _	PRELIMINARY	SAS	05/28/24
<u>/B\</u>	90% CONSTRUCTION	KAG	06/14/24
$\wedge$	100% CONSTRUCTION	PAP	06/21/24
$\overline{\wedge}$			
$\overline{}$			

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.



# verizon /

DATE DRAWN:	06/21/24							
ATC JOB NO:	14857598							
CUSTOMER NAME:	PHILLIPS LAKE CITY							
CUSTOMER ID:	131313							
	ATC JOB NO: CUSTOMER NAME:							

REVISION

0

## SITE PLAN NOTES:


- 1. THIS SITE PLAN REPRESENTS THE BEST PRESENT KNOWLEDGE AVAILABLE TO THE ENGINEER AT THE TIME OF THIS DESIGN. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO CONSTRUCTION AND VERIFY ALL EXISTING CONDITIONS RELATED TO THE SCOPE OF WORK FOR THIS PROJECT.
- 2. ICE BRIDGE, CABLE LADDER, COAX PORT, AND COAX CABLE ARE SHOWN FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM THE EXACT LOCATION OF ALL PROPOSED AND EXISTING EQUIPMENT AND STRUCTURES DEPICTED ON THIS PLAN. BEFORE UTILIZING EXISTING CABLE SUPPORTS, COAX PORTS, INSTALLING NEW PORTS OR ANY OTHER EQUIPMENT, CONTRACTOR SHALL VERIFY ALL ASPECTS OF THE COMPONENTS MEET THE ATC SPECIFICATIONS.


#### LEGEND 8 GROUNDING TEST WELL AUTOMATIC TRANSFER SWITCH ATS BOLLARD CSC CELL SITE CABINET D DISCONNECT ELECTRICAL FIBER GEN **GENERATOR** GENERATOR RECEPTACLE G HH. V HAND HOLE, VAULT ΙB ICE BRIDGE KENTROX BOX K LIGHTING CONTROL LC M METER PB **PULL BOX** POWER POLE TELCO TRN TRANSFORMER

CHAINI INK FENCE

## PROPOSED CABLE NOTES:

- ESTIMATED LENGTH OF PROPOSED CABLE IS 365'.
   ESTIMATED LENGTH OF CABLE WAS PROVIDED BY
   CUSTOMER OR CALCULATED BY ADDING THE RAD
   CENTER AND THE DISTANCE FROM THE SHELTER
   ENTRY PLATE TO THE TOWER (ALONG THE ICE
   BRIDGE) AND A SAFETY FACTOR MEASUREMENT OF
   15% (OF THE TWO PREVIOUS VALUES), CDS DEFER
   TO GREATEST CABLE LENGTH.
- 2. ROUTE PROPOSED CABLES ALONG SAME PATH AS EXISTING CABLES AND IN ACCORDANCE WITH STRUCTURAL ANALYSIS. WHERE POSSIBLE UTILIZE EXISTING CABLE SUPPORT STRUCTURES AS PROVIDED FOR CARRIER TO ADEQUATELY SECURE CABLES, USING EITHER APPROPRIATELY SIZED STAINLESS STEEL SNAP-INS OR MOUNTING HARDWARE AND BRACKETS AS SPECIFIED BY CABLE MANUFACTURER. OTHERWISE, ATTACH CABLES TO HORIZONTAL OR DIAGONAL TOWER MEMBERS USING PROPOSED STAINLESS STEEL ADAPTERS (DO NOT ATTACH TO TOWER LEG).







TOWER ENGINEERING PROFESSIONALS
326 TRYON ROAD
RALEIGH, NC 27603-3530
OFFICE: (919) 661-6351
www.tepgroup.net

FL COA#: 31011

ATC SITE NUMBER: 412243
ATC SITE NAME:

LAKE CITY FL SQA

VERIZON WIRELESS SITE NAME: PHILLIPS LAKE CITY

SITE ADDRESS: 233 N W RANCH COURT LAKE CITY, FL 32055-8079

 REV.
 DESCRIPTION
 BY
 DATE

 A
 PRELIMINARY
 SAS
 05/28/24


 B
 90% CONSTRUCTION
 KAG
 06/14/24

 O
 100% CONSTRUCTION
 PAP
 06/21/24

# DIGITAL/ELECTRONIC SEAL:

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.






DATE DRAWN:	06/21/24
ATC JOB NO:	14857598
CUSTOMER NAME:	PHILLIPS LAKE CITY
CUSTOMER ID:	131313

**DETAILED SITE PLAN** 

SHEET NUMBER:

C-101





326 TRYON ROAD RALEIGH, NC 27603-3530 OFFICE: (919) 661-6351 www.tepgroup.net

FL COA#: 31011

412243


VERIZON WIRELESS SITE NAME:

SITE ADDRESS: 233 N W RANCH COURT

DESCRIPTION **PRELIMINARY** SAS 05/28/24 90% CONSTRUCTION KAG 06/14/24 100% CONSTRUCTION PAP 06/21/24

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.


PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.




	DATE DRAWN:	06/21/24					
	ATC JOB NO:	14857598					
	CUSTOMER NAME:	PHILLIPS LAKE CITY					
	CUSTOMER ID:	131313					

# **DETAILED EQUIPMENT** LAYOUT

C-102





PER MOUNT ANALYSIS COMPLETED BY COLLIERS ENGINEERING AND DESIGN, DATED 17 MAY, 2024. THE EXISTING MOUNT <u>CAN NOT</u> ADEQUATELY SUPPORT THE PROPOSED LOADING. THE MOUNT REPLACEMENT PROPOSED IN THE MOUNT ANALYSIS. INCLUDED AT THE END OF THIS PLAN SET, MUST BE INSTALLED PRIOR TO THE INSTALLATION OF THE PROPOSED ANTENNAS

ATC IS CURRENTLY FILED FOR FAA HEIGHT HIGHER THAN THE TOP OF TOWER.

CONFIRM WITH THE PROJECT MANAGER THAT THEY HAVE THE MOST RECENT VERSION OF THE STRUCTURAL ANALYSIS BEFORE COMMENCING EXISTING AND PROPOSED TOWER APPURTENANCES, MOUNTS, AND ANTENNAS ARE SHOWN BASED ON THE STRUCTURAL ANALYSIS. WHERE APPLICABLE. ALL NEW ANTENNAS EQUIPMENT, MOUNTS, CABLING, ETC. SHALL BE PAINTED/SOCKED TO MATCH EXISTING EQUIPMENT IN ACCORDANCE WITH FAA, JURISDICTION, AND/OR

ROUTE PROPOSED CABLES ALONG SAME PATH AS EXISTING CABLES AND IN ACCORDANCE WITH STRUCTURAL ANALYSIS. WHERE POSSIBLE UTILIZE EXISTING CABLE SUPPORT STRUCTURES AS PROVIDED FOR CARRIER TO ADEQUATELY SECURE

CABLES, USING EITHER APPROPRIATELY SIZED

STAINLESS STEEL SNAP-INS OR MOUNTING HARDWARE AND BRACKETS AS SPECIFIED BY

CABLE MANUFACTURER. OTHERWISE, ATTACH CABLES TO HORIZONTAL OR DIAGONAL TOWER MEMBERS USING PROPOSED STAINLESS STEEL ADAPTERS (DO NOT ATTACH TO TOWER LEG). TOWER ELEVATION DEPICTION MAY NOT REFLECT

ALL EQUIPMENT INCLUDED IN STRUCTURAL

ANALYSIS. REFER TO STRUCTURAL ANALYSIS FOR

OTHER LOCAL REQUIREMENTS.

FULL TOWER LOADING.

AND OTHER EQUIPMENT.

**AMERICAN TOWER** TOWER ENGINEERING PROFESSIONALS 326 TRYON ROAD RALEIGH, NC 27603-3530 OFFICE: (919) 661-6351

FL COA#: 31011

www.tepgroup.net

ATC SITE NUMBER: 412243

# ATC SITE NAME: LAKE CITY FL SQA

VERIZON WIRELESS SITE NAME: PHILLIPS LAKE CITY


> SITE ADDRESS: 233 N W RANCH COURT

LAKE CITY, FL 32055-8079 DESCRIPTION **PRELIMINARY** SAS 05/28/24 90% CONSTRUCTION KAG 06/14/24 100% CONSTRUCTION PAP 06/21/24

## DIGITAL/ELECTRONIC SEAL:

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.



*		
	DATE DRAWN:	06/21/24
	ATC JOB NO:	14857598
	CUSTOMER NAME:	PHILLIPS LAKE CITY
	CUSTOMER ID:	131313

# **TOWER ELEVATION**


SHEET NUMBER:


REVISION:

C-201

0

PROPOSED TOWER ELEVATION SCALE: N.T.S.





				EXIS	STING ANTENNA SCHED	ULE								
LOCATION         ANTENNA SUMMARY         NON ANTENNA SUMM           SECTOR         RAD         AZ         POS         ANTENNA         BAND         MECH/ ELEC D-TILT         STATUS         ADDITIONAL TOWER MOUNTED EQUIPMENT							ARY							
SECTOR	RAD	AZ	POS	ANTENNA	BAND	ELEC	STATUS		STATUS					
			A1	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	(1) RRUS32 B4	RMV					
ALPHA	300'	330°	A2	(1) X7CAP-865-22-IP	-	*	RMV	_	-					
ALPHA	300	330	A3	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	_	-					
								A4	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	_	-
	300'			B1	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	(1) RRUS32 B4	RMV				
BETA		60°	B2	(1) X7CAP-865-22-IP	-	*	RMV	_	-					
BEIA		00	ВЗ	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	_	-					
			B4	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	_	-					
			C1	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	(1) RRUS32 B4	RMV					
CAMMA	300'	195°	C2	(1) X7CAP-865-22-IP	-	*	RMV	_	-					
GAMMA	300	195	C3	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	_	-					
								C4	(1) X7CQAP-86-865-V	LTE 700/LTE AWS	*	RMV	_	_

	NOTES
JS	CONFIRM WITH VERIZON REP     FOR APPLICABLE     UPDATES/REVISIONS AND
,	MOST RECENT RFDS FOR NSN CONFIGURATION (CONFIG). GC TO CAP ALL UNUSED PORTS.
	2. CONFIRM SPACING OF PROPOSED EQUIP DOES NOT CAUSE TOWER CONFLICTS
,	NOR IMPEDE TOWER CLIMBING PEGS.
	3. TEP DID NOT VERIFY THE EXISTING LOADING. LOADING DATA PROVIDED BY ATC AND
	VERIZON.
′	STATUS ABBREVIATIONS
	RMV: TO BE REMOVED  RMN: TO REMAIN

STATUS ABBREVIATIONS
RMV: TO BE REMOVED
RMN: TO REMAIN
REL: TO BE RELOCATED
ADD: TO BE ADDED

CABLE LENGTHS FOR JUMPERS
JUNCTION BOX TO RRU: 15' RRU TO ANTENNA: 10'

\* - SEE RFDS FOR VALUES


,	LC	LOCATION			ANTENNA SUMMARY			NON ANTENNA SUMMARY								
N SC	SECTOR	RAD	AZ	POS	ANTENNA	BAND	MECH/ ELEC D-TILT	STATUS	ADDITIONAL TOWER MOUNTED EQUIPMENT	STATUS						
				A1	MX06FHG865-HG	LTE 700/ 5G 850/LTE 850/ LTE 1900/LTE AWS/ LTE AWS3	*	ADD	(1) RRUS 4490	ADD						
	ALPHA	300'	330°	A2	MX06FHG865-HG	LTE 700/ 5G 850/LTE 850/ LTE 1900/LTE AWS/ LTE AWS3	*	ADD	(1) RRUS 4890	ADD						
IG				А3	AIR6419 N77G	5G L-SUB6	*	ADD	-	-						
				A4	-	-	-	-	-	-						
			' 60°	B1	MX06FHG865-HG	LTE 700/ 5G 850/LTE 850/ LTE 1900/LTE AWS/ LTE AWS3	*	ADD	(1) RRUS 4490	ADD						
	BETA	300'		B2	MX06FHG865-HG	LTE 700/ 5G 850/LTE 850/ LTE 1900/LTE AWS/ LTE AWS3	*	ADD	(1) RRUS 4890	ADD						
										В3	AIR6419 N77G	5G L-SUB6	*	ADD	-	-
				B4	-	-	-	-	-	-						
			D' 195°		C1	MX06FHG865-HG	LTE 700/ 5G 850/LTE 850/ LTE 1900/LTE AWS/ LTE AWS3	*	ADD	(1) RRUS 4490	ADD					
<u> </u>	GAMMA	300'		C2	MX06FHG865-HG	LTE 700/ 5G 850/LTE 850/ LTE 1900/LTE AWS/ LTE AWS3	*	ADD	(1) RRUS 4890	ADD						
				C3	AIR6419 N77G	5G L-SUB6	*	ADD	-	-						
				C4	-	-	-	-	-	-						

FINAL ANTENNA SCHEDULE

EXISTING FIBER DISTRIBUTION/O	/P BOX	EXISTING CA	ABLING SUMMARY	
MODEL NUMBER	COAX	HYBRIFLEX	STATUS	
(1) RXXDC-3315-PF-48	RMN	_	(1) 6X12 [(1) 1-1/4"]	RMN
_	_	(16) 1-5/8"	_	RMV

**EQUIPMENT SCHEDULES** 

FINAL FIBER DISTRIBUTION / O	VP BOX	FINAL CABLING SUMMARY					
MODEL NUMBER	STATUS	COAX	HYBRIFLEX	STATUS			
(1) RXXDC-3315-PF-48	RMN	-	(1) 6X12 [(1) 1-1/4"]	RMN			
(1) RXXDC-3315-PF-48	ADD	·	(1) 6x12 [(1) 1-1/4"]	ADD			



## DIGITAL/ELECTRONIC SEAL:


90% CONSTRUCTION

KAG 06/14/24

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

100% CONSTRUCTION PAP 06/21/24

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.








	DATE DRAWN:	06/21/24
+	ATC JOB NO:	14857598
+	CUSTOMER NAME:	PHILLIPS LAKE CITY
	CUSTOMER ID:	131313

# ANTENNA INFORMATION & SCHEDULE

SHEET NUMBER:	
C-401	








PROPOSED ANTENNA MOUNTING DETAIL

PROPOSED 5G ANTENNA MOUNTING DETAIL

PROPOSED RRU MOUNTING DETAIL




PROPOSED OVP MOUNTING DETAIL

**PROPOSED** CABINET PROPOSED 1/2" HILTI KWIK BOLT CONCRETE PAD

INSTALL HILTI KWIK BOLT ANCHORS STRICTLY PER INSTALLATION INSTRUCTIONS INCLUDED WITH PRODUCT OR FOUND ONLINE AT WWW.US.HILTI.COM. PROPER INSTALLATION IS CRITICAL FOR FULL PERFORMANCE.


CABINET ATTACHMENT DETAIL



NOTE:

INSTALL HILTI KWIK BOLT ANCHORS STRICTLY PER INSTALLATION INSTRUCTIONS INCLUDED WITH PRODUCT OR FOUND ONLINE AT WWW.US.HILTI.COM. PROPER INSTALLATION IS CRITICAL FOR FULL PERFORMANCE

GENERATOR ATTACHMENT DETAIL SCALE: NOT TO SCALE



NOTE:

INSTALL HILTI KWIK BOLT ANCHORS STRICTLY PER INSTALLATION INSTRUCTIONS INCLUDED WITH PRODUCT OR FOUND ONLINE AT WWW.US.HILTI.COM. PROPER INSTALLATION IS CRITICAL FOR FULL PERFORMANCE.

TANK ATTACHMENT DETAIL SCALE: NOT TO SCALE



DIGITAL/ELECTRONIC SEAL:

90% CONSTRUCTION

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.


LAKE CITY, FL 32055-8079 DESCRIPTION PRELIMINARY

100% CONSTRUCTION PAP 06/21/24

SAS 05/28/24

KAG 06/14/24

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.






DATE DRAWN:	06/21/24
ATC JOB NO:	14857598
CUSTOMER NAME:	PHILLIPS LAKE CITY
CUSTOMER ID:	131313

# CONSTRUCTION **DETAILS**

SHEET NUMBER:

C-501





# **FOUNDATION NOTES:**

- FOUNDATION DESIGN BASED ON 2,000 PSF SOIL BEARING CAPACITY.
- 2. CONCRETE SHALL BE 4,000 PSI @ 28 DAYS.
- REINFORCING STEEL Fy = 60,000 PSI.
- ALL BACKFILL SHALL BE THOROUGHLY COMPACTED TO A MINIMUM OF 95% DENSITY USING THE MODIFIED PROCTOR METHOD.
- SURFACE OF FINISHED SLAB SHALL BE LEVEL AND FLAT WITHIN  $\mbox{\it \'{4}}$ ".
- CONTRACTOR SHALL VERIFY WITH MANUFACTURER ACTUAL DIMENSIONS OF EQUIPMENT PRIOR TO LAYING OUT FOUNDATION.
- ALL CONCRETE WORK SHALL BE PERFORMED IN ACCORDANCE WITH ACI 318-14.
- 8. ANCHOR GENERATOR TO PROPOSED PAD PER MANUFACTURER SPECIFICATIONS.





DIGITAL/ELECTRONIC SEAL:

PRELIMINARY


90% CONSTRUCTION KAG 06/14/24

100% CONSTRUCTION PAP 06/21/24

SAS 05/28/24

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.





l	DATE DRAWN:	06/21/24
	ATC JOB NO:	14857598
	CUSTOMER NAME:	PHILLIPS LAKE CITY
	CUSTOMER ID:	131313

# CONSTRUCTION **DETAILS**

SHEET NUMBER:

C-502

0

# **NOTES:**

ALL CONDUCTORS ARE TYPE THWN (75%) COPPER.

MAXIMUM LENGTH OF RUN FOR RECTIFIER CIRCUITS IS 50-FT.


INTERSECT/GENERAC INTEGRATED LOAD CENTER INCLUDES 200A MAIN DISCONNECT AND TRANSFER SWITCH FOR PORTABLE OR PERMANENT GENERATOR.

RECTIFIER LOADS ARE CONSIDERED TO BE NON-CONTINUOUS.

IF ADDITIONAL FUTURE LOADS ARE ADDED WHICH CAUSE TOTAL DEMAND TO EXCEED GENERATOR BREAKER SIZE, BACKUP POWER SYSTEM SHALL BE EVALUATED AND UPGRADED AS NECESSARY.

200A 120/2	40V	1Ø 3	W VI	ERI	ZO	N F	POV	VER	PAN	IEL S	SCHEDULE
LOAD SERVED	UNCOMP VOLT A L1	ENSATED MPERES L2	TRIP	CKT #	PH	ASE	CKT #	TRIP		ENSATED MPERES L2	LOAD SERVED
***RECTIFIER	1140	1140	30A	3	+1+	4	2 4	30A	1140	1140	***RECTIFIER
***RECTIFIER	1140	1140	30A	5 7	71H	4	6 8	30A	1140	1140	***RECTIFIER
***RECTIFIER	1140	1140	30A	9	$_{\perp 1}+$	4	10	30A	0	0	FUTURE RECTIFIER
***RECTIFIER	1140	1140	30A	13 15	¥1\	4	14	_ _	_	_	SPARE SPARE
**BTS	4000	4000	100A	17 19	+1+	4	18	- 20A	-	180	SPARE TELCO RECEPT
SPACE	_		_	21		4	22	20A	180		EEN RECEPT
SPACE		-	-	23		3	24	20A		1000	*GEN BATTERY CHARGER
SPACE	_		_	25		4	26	20A	1500		GEN BLOCK HEATER
SPACE		-	-	27		<b></b>	28	_		_	SPARE
SPACE	_		_	29		$\Delta$	30	-	_		SPARE
VOLT AMPS	8560	8560							3960	3460	VOLT AMPS
	 L1	VOLT A	MPERES	125	520	120	020	L2 VOLT AMPERES			
L1 DEMAND VOLT AMPERES (INCLUDES DEMAND FACTOR)			ACTOR)	15	650	15	025	L2 DEMAND VOLT AMPERES (INLCUDES DEMAND FACTOR			
L1 DEMAND AMPS			D AMPS	130	0.42	12	5.21	L2 DEM	IAND AMI	PS .	
				130.42 125.21		MAX DEMAND AMPS					
					130	).42					

<sup>\*</sup>GEN. BATTERY CHARGED LOAD IS 0 VA DURING GENERATOR OPERATION.



	DATE DRAWN:	06/21/24
	ATC JOB NO:	14857598
	CUSTOMER NAME:	PHILLIPS LAKE CITY
	CUSTOMER ID:	131313

PANEL SCHEDULES


SHEET NUMBER:

REVISION

E-101

<sup>\*\*</sup>LOADING VALUES BASED ON INFORMATION PROVIDED BY LOCAL UTILITY COMPANY.

<sup>\*\*\*</sup>LOADING VALUES BASED ON INFORMATION PROVIDED BY VERIZON WIRELESS.





TOWER ENGINEERING PROFESSIONALS 326 TRYON ROAD

> OFFICE: (919) 661-6351 www.tepgroup.net

FL COA#: 31011

412243

SITE ADDRESS:


233 N W RANCH COURT

LAKE CITY, FL 32055-8079

SAS 05/28/24 90% CONSTRUCTION KAG 06/14/24 100% CONSTRUCTION PAP 06/21/24

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.





	DATE DRAWN:	06/21/24
	ATC JOB NO:	14857598
	CUSTOMER NAME:	PHILLIPS LAKE CITY
	CUSTOMER ID:	131313

**ONE-LINE DIAGRAM** 

REVISION:


0

#### LABEL LIST:

- 1. (1) 3/4" CONDUIT FOR GFI IN THE NEW CONSOLIDATED EQUIPMENT AND POWER CABINET
- 2. (2) 2" CONDUITS FOR THE RECTIFIERS IN THE NEW CONSOLIDATED EQUIPMENT AND POWER CABINET
- 3. (1)-1" CONDUIT FOR GENERATOR AND ILC ALARM FROM ILC TO CONSOLIDATED EQUIPMENT AND POWER
- 4. (1)-1" CONDUIT FOR GENERATOR HEATER & BATTERY CHARGER FROM ILC TO GENERATOR
- 5. (1)-1" CONDUIT FOR ALARM AND CONTROL WIRING FROM ILC TO GENERATOR
- 6. (1)- 21/2" CONDUIT FOR POWER FROM ILC TO GENERATOR
- 7. (1)-2" CONDUIT FOR POWER FROM SERVICE DISCONNECT/CIRCUIT BREAKER TO ILC
- 8. (1)-2" CONDUIT FOR BATTERY CABINET FROM CONSOLIDATED EQUIPMENT AND POWER CABINET TO BATTERY
- (1)-1" CONDUIT FOR BATTERY CABINET FROM ILC TO BATTERY CABINET. CONTRACTOR TO REUSE CONDUIT AND CONDUIT AND CONDUCTORS IF SUFFICIENTLY SIZED.

## NOTES:

- 1. POWER AND TELCO CONDUITS RECEIVING CONDUCTORS BY OTHERS TO HAVE PULL ROPES.
- 2. ALL TELCO CONDUITS ARE TO BE STUBBED IN D-MARC LOCATION.
- 3. ALL POWER CONDUITS ARE TO BE TERMINATED AT THE METER CENTER.
- 4. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES PRIOR TO TRENCHING. ANY DAMAGE CAUSED TO THE EXISTING UTILITIES SHALL BE REPAIRED AT THE CONTRACTORS EXPENSE.
- ALL CONDUITS SHALL BE INSTALLED PRIOR TO FINISH GRADING, GEOFABRIC, AND STONE INSTALLATION.
- 6. CONTRACTOR SHALL INSTALL SWEEPS AT ALL CONDUIT DIRECTION CHANGES UNLESS NOTED OTHERWISE
- RUN CONDUITS FROM ILC TO GENERATOR UNDERGROUND AND STUB UP CONDUITS MINIMUM 6"
  HIGH INSIDE GENERATOR BASE AND TERMINATE WITH MALE ADAPTER AND THREADED BUSHING.
- 8. WHEN ALL RRUS ARE GROUND MOUNTED, OMIT OVPS AND RUN FIBER/POWER FROM CONSOLIDATED EQUIPMENT AND POWER CABINET DIRECTLY TO RRUS.





#### **GROUNDING KEYED NOTES:**

1 BOND TO TOWER GROUND RING


 $\langle$  2  $\rangle$  GROUNDING ELECTRODE CONDUCTOR PER NEC

3 > #2 GROUND RING

4 GROUNDING ELECTRODE (TYP.)

 $\langle$  5  $\rangle$  BOND TO COMPOUND GROUND RING

6 GROUNDING ELECTRODE WITH TEST WELL





TOWER ENGINEERING PROFESSIONALS

326 TRYON ROAD RALEIGH, NC 27603-3530 OFFICE: (919) 661-6351 www.tepgroup.net

FL COA#: 31011

ATC SITE NUMBER: 412243
ATC SITE NAME:

LAKE CITY FL SQA

VERIZON WIRELESS SITE NAME:
PHILLIPS LAKE CITY
SITE ADDRESS:

233 N W RANCH COURT LAKE CITY, FL 32055-8079

 REV.
 DESCRIPTION
 BY
 DATE

 A
 PRELIMINARY
 SAS
 05/28/24


 B
 90% CONSTRUCTION
 KAG
 06/14/24

 0
 100% CONSTRUCTION
 PAP
 06/21/24

DIGITAL/ELECTRONIC SEAL:

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.






	DATE DRAWN:	06/21/24
	ATC JOB NO:	14857598
	CUSTOMER NAME:	PHILLIPS LAKE CITY
	CUSTOMER ID:	131313

GROUNDING PLAN & SCHEMATIC

SHEET NUMBER

E-103

O







TOWER ENGINEERING PROFESSIONALS

326 TRYON ROAD RALEIGH, NC 27603-3530 OFFICE: (919) 661-6351 www.tepgroup.net

FL COA#: 31011

ATC SITE NUMBER: 412243

# ATC SITE NAME: LAKE CITY FL SQA

VERIZON WIRELESS SITE NAME: PHILLIPS LAKE CITY

SITE ADDRESS:


233 N W RANCH COURT LAKE CITY, FL 32055-8079

REV.	DESCRIPTION	BY	DATE
<u> </u>	PRELIMINARY	SAS	05/28/24
<u>/B\</u>	90% CONSTRUCTION	KAG	06/14/24
<u></u>	100% CONSTRUCTION	PAP	06/21/24
$\overline{\wedge}$			
$\overline{\wedge}$			

# DIGITAL/ELECTRONIC SEAL:

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.



# verizon /


	DATE DRAWN:	06/21/24
	ATC JOB NO:	14857598
	CUSTOMER NAME:	PHILLIPS LAKE CITY
	CUSTOMER ID:	131313

# **GROUNDING PLAN &** SCHEMATIC

SHEET NUMBER:


E-104

0



- 1. THIS DETAIL IS INTENDED TO SHOW THE GENERAL GROUNDING REQUIREMENTS. SLIGHT ADJUSTMENTS MAY BE REQUIRED BASED ON EXISTING SITE CONDITIONS. THE CONTRACTOR SHALL MAKE FIELD ADJUSTMENTS AS NEEDED AND INFORM THE CONSTRUCTION MANAGER OF ANY CONFLICTS.
- 2. SITE GROUNDING SHALL COMPLY WITH VERIZON GROUNDING STANDARDS, LATEST EDITION, AND COMPLY WITH VERIZON GROUNDING CHECKLIST, LATEST VERSION. WHEN NATIONAL AND LOCAL GROUNDING CODES ARE MORE STRINGENT THEY SHALL GOVERN.






- GROUND KIT NOTES:

  1. DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.
- 2. CONTRACTOR SHALL PROVIDE WEATHERPROOFING KIT (ANDREW PART NUMBER 221213) AND INSTALL/TAPE PER MANUFACTURER'S SPECIFICATIONS.

CABLE GROUND KIT CONNECTION DETAIL



#### **GROUND BAR NOTES:**

- GROUND BAR KITS COME WITH ALL HARDWARE, NUTS, BOLTS, WASHERS, ETC. EXCEPT THE STRUCTURAL MOUNTING MEMBER(S).
- 2. GROUND BAR TO BE BONDED DIRECTLY TO TOWER.





# DIGITAL/ELECTRONIC SEAL:

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DANIEL P. HAMM, P.E. ON THE DATE ADJACENT TO THE SEAL.

**AMERICAN TOWER** 

FL COA#: 31011

ATC SITE NUMBER:

412243

ATC SITE NAME:

LAKE CITY FL SQA

VERIZON WIRELESS SITE NAME:

PHILLIPS LAKE CITY

SITE ADDRESS:

233 N W RANCH COURT

LAKE CITY, FL 32055-8079

100% CONSTRUCTION PAP 06/21/24

SAS 05/28/24

KAG 06/14/24

DESCRIPTION

PRELIMINARY

90% CONSTRUCTION

TOWER ENGINEERING PROFESSIONALS


326 TRYON ROAD

RALEIGH, NC 27603-3530

OFFICE: (919) 661-6351

www.tepgroup.net

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.






	DATE DRAWN:	06/21/24
	ATC JOB NO:	14857598
	CUSTOMER NAME:	PHILLIPS LAKE CITY
	CUSTOMER ID:	131313

# **GROUNDING DETAILS**


SHEET NUMBER:

E-501

0




ANTENN	IA SPECIFIC	ATIONS		
ANTENNA MODEL	А	В	С	WEIGHT (LBS)
AIR 6419 B77D	30.0"	15.7"	6.7"	70.0
MX06FHG865-HG	95.9"	12.2"	7.5"	51.0




FRONT VIEW

RAYCAP MODEL

RXXDC-3315-PF-48





WEIGHT (LBS)


32.0

С

10.3"



TOP VIEW



RRU	SPECIFICAT	IONS		
RRU MODEL	А	В	С	WEIGHT (LBS)
RRUS 4490	20.6"	15.7"	7.0"	68.4
RRUS 4890	20.6"	15.7"	7.2"	69.5

SUPPLEMENTAL

SHEET NUMBER:

R-601


REVISION:

**EQUIPMENT SPECIFICATIONS** SCALE: NOT TO SCALE

OVP SPECIFICATIONS

19.2"

15.7"




Safety Vent: Low positive pressure, Rating: 190 Ampere-Hours @ 8 hr. rate self-sealing w/ flame arrestor to 1.75 V.P.C. Positive Plate: >98% Pure lead with tin-calcium alloy Float Voltage: 2.25 V.P.C. ± 0.01 V.P.C. @ 77°F (25°C) Range: (13.44V to 13.56V per battery) Negative Plate: Pure lead, calcium alloy Post Seal: Epoxy-sealed Design life: 12 years in float applications @ 77°F (25°C) Case/Cover: Flame-retardant, THT™ -Width - 4.97" (126.3 mm) Height - 12.74" (323.5 mm) UL 94 V-0/>39% L.O.I.

Nominal Voltage: 12-Volts

Volts per Cell (V.P.C.)	1 HR.	2 HR.	3 HR.	4 HR.	5 HR.	8 HR.	12 HR.	20 HR.	24 HR
1.75	144	82.0	57.3	44.4	36.4	23.8	16.3	10.1	8.4
1.80	136	79.1	55.4	43.1	35.4	23.2	16.0	9.9	8.3
1.85	124	73.1	51.9	40.6	33.5	22.1	15.2	9.4	7.9
1.88	113	68.0	48.7	38.3	31.7	21.0	14.5	9.0	7.6
1.90	105	63.9	46.2	36.4	30.1	20.0	13.9	8.6	7.2

Weight: 151 lbs. (68.5 kg)



## INSTALLATION AND OPERATING INSTRUCTIONS

http://www.eastpennmanufacturing.com/wp-content/uploads/Fahrenheit-IO-Manual-2100.pdf

PROPOSITION 65 WARNING: Battery posts, terminals and related accessories contain lead and lead compounds, chemicals known to the State of California to cause cancer and reproductive harm. Batteries also contain other chemicals known to the State of California to cause cancer. WASH HANDS AFTER HANDLING.



**LATF 16949** ISO 14001







www.dekabatteries.com

East Penn Manufacturing Co. Lyon Station, PA 19536-0147 Phone: 610-682-3263 Fax: 610-682-0891 e-mail: reservepowersales@dekabatteries.com

NOTE: THIS SHEET WAS CREATED BY OTHERS AND PROVIDED

AT THE REQUEST OF CUSTOMER WITHOUT EDIT.

E.P.M. Form No. 2201 2/20

© 2020 by EPM Printed in U.S.A.

All data subject to change without notice. No part of this document may be copied or reproduced, electronically or mechanically, without written permission from the company

PROPOSED HT200ET BATTERY DETAILS


SUPPLEMENTAL

SHEET NUMBER:

R-602


50 kW, 63 kVA, 60 Hz PRIME POWER RATING 45 kW, 56 kVA, 60 Hz





#### CODES AND STANDARDS

General products are designed to the following standards



NFPA70, 99, 110, 37



IS09001, 8528, 3046, 7637, Pluses #2b, 4

NEMA ICS10, MG1, 250, ICS6, AB1

SG050 | 6.8L | 50 kW

APPLICATION AND ENGINEERING DATA

ENGINE SPECIFICATIONS

Engine Coverning

Lubrication System

ALTERNATOR SPECIFICATIONS

INDUSTRIAL SPARK-IGNITED GENERATOR SET



ANSI C62.41

oslpd IBC 2009, CBC 2010, IBC 2012, ASCE 7-05, ASCE 7-10, ICC-ES AC-156 (2012)

POWERING AHEAD

Cooling System

Fan Diameter rom (i Coclant Heater Watt

Fuel System

Fuel Type

Battary Size

Engine Electrical System

Goding System Type Water Pump Flow -gal/min (Amin)

For over 50 years, Generac has led the industry with nnovative design and superior manufacturing.

Generaciensures superior quality by designing and manufacturing most of its generator components, including alternators, enclosures and base tanks, control systems and communications software.

Generac's gensets utilize a wide variety of options, configurations and arrangements, allowing us to meet the standby power needs of practically every application.

Generac searched globally to ensure the most reliable engines power our generators. We choose only engines that have already been proven in heavy-duty industrial application under adverse conditions.

GENERAC INDUSTRIAL

Precentized Closed Recovery 38 (144)

Material Sass, Propone Vapor Down Draft

Bill Digital

Generac is committed to ensuring our customers' service support continues after their generator purchase

SG050 | 6.8L | 50 kW INDUSTRIAL SPARK-IGNITED GENERATOR SET

STANDARD FEATURES

ENGINE SYSTEM General

ces erain - Oll Drain Extension 
- Air Cleaner 
- Fan Gland 
- Sandreas Steel Health extract connect 
- Pacting Filled Oll & Contant 
- Pacting Filled Oll & C

Redble fuel lines NFT Connection

 275 Pitch
 Seawed Stator
 Brushlers Excitation
 Soaled Searings
 Amortiseur winding
 Full load capacity alternal Cooling System Closed Goolant Recovery System
 Un/Querre resistant fisces
 Facting Installed Radiator
 Sit/50 Bitiglene glycol antifreeza
 Radiator drain extension

Wrapped Exhaust Plying
 Standard Factory Teating
 Z Year Limited Warranty (Standby rated Units)
 1 Year Warranty (Prime rated units)

GENERAC INDUSTRIAL

Silverser mounted in the discharge hood (exclosed only)

GENERATOR SET

ENCLOSURE (IF SELECTED) Rust-proof facteners with reformwasters to protect finish

princial finish

Migh performance cound-absorbing
material (1.1 & L2)

Gaslebest donor

Stamped air-make lossess

Air discharge hoods for radiator-upward
pointing

Staintess steel #1 off door hinges Stainteas alorel luckable handles
 Rhina Good \* - Testoned polycester provoke conf.

CONTROL SYSTEM



Common Hames

- Digital H Control Panel - Dual 4020 Display

- Programmable Crank Limber

- 7-Day Programmable Exercises

- Special Applications Programmable PLC

- RG-222486

Full System Status

NV Hours, Total & Last Plur

OPERATING DATA

FUEL CONSUMPTION RATES\*

COMBUSTION AIR REQUIREMENT

COOLING

 Didity Monitoring
 Low Fuel Pressure Indicatio
 2-Wire Start Compatible Power Dulput (KW)

SG050 | 6.8L | 50 kW

INDUSTRIAL SPARK-IGNITED GENERATOR SET

Three-Phase 347/800 VAC @0.8pt

Ar Free (over an economission and cane Coolant Row per Minote Coolant System Capacity Heat Rejection to Coolant Max. Operating Air Temp on Radiator

Mor. Operating Ambient Temperature (betwee desate)

Movimum Hadiator Backpressure

Engine Electrical System

Bettery charging elemetor
 Bettery cables
 Bettery tray
 Publica-bouted angine electrical connections

· Solenoid autinoted starter mutor

ALTERNATOR SYSTEM

Real/Resotize/Auparent, Pure
 All Planse Ad Yolinge
 Wil Planse Currents
 Gol Pressure
 Coolant Temperature
 Coolant Temperature
 Engine Speed
 Bullery Voltage
 Fessesser

Frequency Date/Time Fauli History (Event Log)

 Not in Auto (Reshing Light) Auto/OII/Manual Switch E-Stop (Red Masterson-Type) . NFPA110 Level I and II (Programmable

 Customizable Alarms, Warnings, and Events
 Modbus profocol
 Prodetive Mainterance algorithm Sealed Boards

Password parameter adjustment protection

 Single point ground
 15 dharmed data lagging
 0.2 mace high speed data lagging
 Alarm information automatically comes up on the display

Alarins
Oil Pressure (Pre-programmatis Low
Pressure Stationar)
Coulsan Temperature (Pre-programmed
High Temp Stationar)
Condant Level (Pre-programmed Low Level
Stationar)
Low Final Pressure Alarin
Low Final Pressure Alarin

Low Inside Pressure Alarm Personal Over speed Studiourly Personal Over speed Studiourly Restry Morning
 Alarma & wornings time and data stamped Alarma & wornings to transient and stacty ofthe conditions
 Alarma & wornings to transient and stacty ofthe conditions
 Arma phases of key operation parameters during alarma & writings

GENERAC | INDUSTRIAL

Amps: 173 Amps: 150

Natural Ges Amps 208
Amps 173
Amps 150
Amps 75
Amps 80

122 (50)

50 kW

| Albernation | Mov | 10% | 15% | 20% | 20% | 30% | 35% | 10% | 15% | 20% | 20% | 20% | 35% | 10% | 15% | 20% | 20% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35% | 35

SG050 | 6.8L | 50 kW INDUSTRIAL SPARK-IGNITED GENERATOR SET

CONFIGURABLE OPTIONS

ENGINE SYSTEM GENERATOR SET

Gar-Link Communications Software (buylah Daly)
Gar-Link Communications Software (buylah Daly)
Gibenhed Factory Testing (3 Phase Orly)
Gib Colories' Certification
8 Position Load Contex
9 Position Load Conte CL Engine Block Health Congress Bloods Header
 Oil Header
 Oil Header
 Office Restriction Indicator
 Stone Guard (Open Set Only)
 Critical Edinant Sitencer (Open Set Only)
 Standand on Ultra Low Emissions Option)

ENCLOSURE

Standard Enclosure
 Level 1 Sound Attenuation

O Level 2 Sound Attenuation O Stool Emphrouse O Attentionn Employage

O AG/OC Engineura Lighting Kit O. Door Alanu Switch

O 150 MPH Wind Kill O 12 VIDG Enclosure Lighting Kit O 120 VAC Enclosure Lighting Kit

GENERATOR SET

O Special Testing O Batlery Box

ENCLOSURE

O Motorized Dampers O Enclosure Ambient Heaters

Fuel Electrical System O 10A & 2.5A UL bettery charge O Battery Warmer

ALTERNATOR SYSTEM O Afternator Upsizing
O Anti-Condensation Healer
O Tropical Coating
O Permanent Magnet Excitation

CIRCUIT BREAKER O Main Line Circuit Breaker
O 2nd Main Line Circuit Breaker
O Shunt Trip and Auditory Contro
O Electronic Trip Breaker

ENGINEERED OPTIONS

ENGINE SYSTEM O Fluid containment Pans O Godant heater ball valves

ALTERNATOR SYSTEM O 3rd Breaker Systems

CONTROL SYSTEM

O Spare inputs (x4) / outputs (x4) - H Panel Only O Battery Disconnect Switch

RATING DEFINITIONS

Standby - Applicable for a varying emergency food for the duration of a utility power notage with no overhead capability.


nime - Applicable for expelying power to a waying had in lisu of utility for an unfinited amount of moving time. A 10% contrad capacity is excitable for 1 ant of very 12 hours. The Prime Power cytics is only available on International applications. Prover ratings in accordance with ISO 0533-1, Second Edition

SG050 | 6.8L | 50 kW

EPA Certified Stationary Emergency

INDUSTRIAL SPARK-IGNITED GENERATOR SET

DIMENSIONS AND WEIGHTS



L x W x H in (num) 92.9 (2380) x 48 (1815.9) x 75.4 (1914.1)

STANDARD ENCLOSURE

Lx W x H in (num) 111.5 (2839.7) x 10.5 (1027.6) x 55.3 (1406.7)

GENERAC INDUSTRIAL

GENERAC INDUSTRIAL

CONTROL SYSTEM

C 21-Light Resente Ausunciator C Hamole Holay Board (8 or 16)

C Oil Temperature Sender with Indicatio

Asim

Il Remote E-Stop (Birisk Stass-Type, Surface Mount)

Il Remote E-Stop (Red Mushroom-Type, Surface Mount)

Surface Mount)
O Bernote E-Stop (Hed Mushroom-Type,
Flush Mount)
O Bronos Communication - Bridge
O Remote Communication - Ethernet
O 10A Run Palay
O Grand Foot Indication and Protection
Flushchine

LEVEL 1 ACOUSTIC ENCLOSURE Lx Wx H in (num) 129.4 (3287.2) x 40.5 (1027.8 ) x 55.3 (1406.7)

LEVEL 2 ACOUSTIC ENCLOSURE L x W x H in (num) 111.8 (2039.7) x 40.5 (1027.8) x 67.8 (1721.5)

Commun. Passor Bysherns, Inc. | F.O. Rice B. || Windowske, VII Bit 87 P. (182) 544-4011 - 49-2015 General Passor Systems, Inc. All rights reserved. All agreed patients are subject to change without notice.

R-603

SHEET NUMBER:

Derafins — Operational charachefeldra comisider maximum an blent conditions. Desafe tustors may apply under attpicted else conditions. Please consult a Denesa Please Systems Industrial Desilve For additional details. All performance entings in accordance with 1503048, 858514, 808528 and 0108727 students.

PROPOSED 50KW LP GENERATOR DETAILS

Max. Barispossore (Post Turbo) in Fig. (Kpt)

External Temp. (Rated Catput - post sitencer) IF (PC)

External Code: Size (Open Set) mm. (in)

.... -----

NOTE: THIS SHEET WAS CREATED BY OTHERS AND PROVIDED AT THE REQUEST OF CUSTOMER WITHOUT EDIT.

SUPPLEMENTAL

# AA-CL-T-3S PTLC Series

ATS Power Transfer Load Center with an Integrated Telco Cabinet

The AA-CL-T-3S is an outdoor PTLC that features separate The AA-CL-T-3S Series also features a Square D load AC and Telco chambers. The AC chamber includes a 42k AIC main disconnect breaker for normal (utility) power. When the normal power source is not available, an ASCO® Series 300 automatic transfer switch connects to a permanent or temporary alternative power source. Mechanically interlocked 10 kAIC main disconnect breakers allow manual transfer between the permanent and temporary sources.



center: Strikesorb® surge suppression; a utility voltage sensing relay; a Cam-Lok style engine generator connector panel, mounted on the left or right; and a ground fault circuit interrupter (GFCI) circuit breaker wired to a duplex outlet in the Telco chamber.

A double throw, single solenoid transfer mechanism and microprocessor controls in the ASCO Series 300 automatic transfer switch adjust to input from the primary power source or generator, depending on site conditions. The robust ASCO switch is UL 1008 Listed and complies with NFPA 110 for emergency and standby power systems.

To protect connected equipment, the AA-CL-3S PTLC safeguards critical loads from transients and load transfer spikes using Strikesorb® surge suppression. Strikesorb incorporates state of the art technological developments that provide superior protection characteristics, which remain unchanged throughout its long service life. It is designed to withstand repeated surges providing cost-effective and maintenance-free operation in demanding environments. Critical loads are never left unprotected, as Strikesorb will operate to a short circuit and trip the main disconnect breaker in the event of a long duration, potentially catastrophic overvoltage event.

A 42-position Square D load center provides the flexibility to distribute 200 amp, 240/120 single-phase or 208/120 threephase power to a variety of site equipment.

The Telco chamber has a plywood backboard with three knockouts for cable entry centered above the backboard. Included in the Telco chamber is a 20-amp duplex receptacle fed from a GFCI circuit breaker (located in the upper, AC

For more information about the AA-CL-T-3S Series panels, or other PTLC models, e-mail Intersect today at solutions@intersectinc.com.

# Intersect, Inc.

Quality products. Premium customer care. Integrated solutions.

Series Number	Product Configuration
M1220042-3R-CL-T-L	240/120; 1Ø; 200 amp; 42 kAlC; utility and permanent or temporary power sources (3-sources); left-mount Cam Lok-style engine generator connector
AA1220042-3R-CL-T-R	240/120; 1Ø; 200 amp; 42 kAlC; utility and permanent or temporary power sources (3-sources); right-mount Cam Lok-style engine generator connector
AA3320042-3R-CL-T-L	208/120; 3Ø; 200 amp; 42 kAlC; utility and permanent or temporary power sources (3-sources); left-mount Cam-Lok style engine generator connector
AA3320042-3R-CL-T-R	208/120; 3Ø; 200 amp; 42 kAlC; utility and permanent or temporary power sources (3-sources); right-mount Cam-Lok style engine generator connector
Option Number	Description
Opt 11BG	Programmable Engine Exerciser — seven-day electronic time switch provides automatic weekly or bi-weekly testing of the engine generator set either with or without load and offers relay contacts for remote status monitoring.

Other service voltages and amperages are available. Custom panels can be designed to your performance specifications. Contact Intersect: solutions@intersectinc.com

# General Data

# Overall enclosure weight and dimensions

Varies by service voltage, amperage, and enclosure type. Request specific panel drawings for this product information.

#### AC cabinet dimensions (H x W x D) 53 x 29 x 12 inches

Telco cabinet dimensions (H x W x D) 20 x 29 x 12 inches

#### Enclosure type

- · 0.008 aluminum construction
- Service voltage
- 200 amp
- 240/120 208/120

# Voltage sensing relay

. Senses "utility" or normal source voltage · Installed on "line" side of main disconnect breaker

# UL certification

- · UL 67 listed panel
- · Service entrance rated

# Cam-Lok Style Panel

## Model

Micrin or Intersect ICL

- Color coded Cam-Lok Connectors
- Green Ground
- · White Neutral
- Black Line 1 Red — Line 2
- Blue Line 3 **UL** Certification UL 1008 listed

# Load Center

Load center type Square D

Circuit breaker positions 42 circuits

Circuit breaker type

Square D bolt-on or plug-in branch devices

# Telco Cabinet

# Duplex receptacle

• 15 amp GFCI circuit breaker

# Terminal bar

- Insulated
- Ground connection

# AC service connection

Two, 2-inch nonmetallic conduits

# Manual Transfer Switch

- Mechanically interlocked breakers for permanent or alternative power source
- · Enables manual transfer between permanent and temporary power source (10 kA at 240 VAC)

# Square D input breaker

200 amns

Source circuit breaker

Permanent & alternative emergency power Withstand current rating (WCR)

10,000 amps

# Automatic Transfer Switch

ASCO - 300L Series

#### Power transfer mechanism · Single solenoid operation

- Microprocessor controller
- · Double throw operation

# Engine starting contact

Connect signal wires to auto-start engine generator set

#### Source circuit breaker

· Normal (utility power) 200 amp, 60 Hz

## Engine exerciser

- · Built-in, 20-minute exerciser
- See Option 11BG in table for further details

#### Withstand current rating (WCR) 42,000 amps

#### UL certification & other safety compliances

- . UL 1008, standard for transfer switch equipment
- . CSA standard C22.2 for automatic transfer
- . NFPA 110 for emergency and standby power systems
- NEC Articles 700, 701, and 702

# Suppression Technology

# Technology type

Strikesorb 40-A1, 120 V modules

#### Surge Protection Levels Response time

<1 ns

#### Maximum surge current

- . Surge current, imax (8/20) NEMA LS-1:
- Lightning current, limp (10/350) IEC 61643-1:

## Let through voltage level

For surge current 10 kA (8/20) IEEE C62.41-1: 435 V - actual surge current through Strikesorb

#### Long duration surge performance

500 A square waveform 2 ms IEEE C62.11: 250 hits

# Voltage protection rating (VPR) 600 V per UL 1449 3rd edition

Short Circuit Current Rating

- Tested for safe installation behind a 4000 A Class L time delay fuse at available fault current
- · 3-cycle testing at 85 kA

# Standards Compliance

- IEEE C62.41, IEEE C62,45, IEEE C62.11, NEMA LS-1
- IEC 61643-1 ed 2:2005, EN-61642-A11:2005, IEC 61643-12

Intersect, Inc.

All specifications subject to change without notice. ASCO® is a registered trademark of ASCO Power Technologies. Strikesorb® is a registered trademark of Raycap Corporation. © Intersect. Inc. 2007-2011. Rev 050611.

P.O. Box 753 Liberty Lake WA 99019 USA Phone: 509.255.9570 - Fax: 509.255.6034

PROPOSED ILC DETAILS

www.intersectinc.com

NOTE: THIS SHEET WAS CREATED BY OTHERS AND PROVIDED

AT THE REQUEST OF CUSTOMER WITHOUT EDIT

SUPPLEMENTAL

R-604

# UNDERGROUND/ABOVEGROUND TANKS (AG/UG)



# WHY CHOOSE QUALITY STEEL **UNDERGROUND TANKS?**

- 120 1,990 WG CAPACITY
- General Specifications
- . Conforms to the latest edition of ASME Rules for Construction of Pressure Vessels, Section VIII, Division 1.
- Complies with NFPA 58.
- Rated at 250 psig from -20° F to 125° F. All vessels registered with National Board.
- Two service options available:
- Option 1: Ready-to-bury underground option, coated with either powder coated phenolic epoxy finish or liquid applied epoxy primer coat followed by urethane top coat, supplied with composite AG/UG dome
- Option 2: Aboveground option, coated with either powder coated TGIC polyester finish or liquid applied epoxy primer coat followed by urethane top coat, supplied with steel AG/UG dome
- Family & employee owned
- Financing and leasing available
- · Customized delivery programs available

# We want to make it easier for you to do your tank business! 2914 U.S. 61 · Cleveland, MS 38732 · 800-345-2495 · www.propanetank.com

# HOW DO I FIND MY SALES REP?

Visit our website, www.propanetank.com to view a list of our reps. Once on our site you'll be able to choose the Commercial options and from there you'll be taken to a list of US states where you can choose your location and view the contact information for your local sales rep. If you don't see your sales rep. please give us a call at 800-345-2495.

Our manufacturing locations are strategically located to help serve your tank needs.

# OHIO LOCATION 721 Graham Drive Fremont, OH 43420 419-334-2664 UTAH LOCATION HOME OFFICE 5601 Axel Park Rd. 2914 U.S. 61 West Jordan, UT 84081 Cleveland, MS 38732 801-280-1133 800-345-2495



# UNDERGROUND/ABOVEGROUND TANKS (AG/UG)

Consult our dimension and specification chart below to find the tank that best fits your needs. Visit our website at www.propanetank.com for more information.





# APPROXIMATE ABOVEGROUND/UNDEGROUND (AG/UG) VESSEL DIMENSIONS AND SPECIFICATIONS

WATER	DIAMETER	HEAD	OVERALL	OVERALL	LEG*	LEG**	WEIGHT	**QU/	ANTITY
CAPACITY	(OD)	TYPE	LENGTH	HEIGHT	WIDTH	SPACING	(lbs.)	FULL LOAD	PER STACK
*120 wg.	24"	Ellip.	5'-8"	3'	1'-1 1/2"	2'-10 1/2" or 3'-11"	260	108   96	16   12
*250 wg.	30"	Hemi.	7'-10"	3'-8"	1'-5"	4'-11"	480	54	9
*320 wg.	30"	Hemi.	9'-7"	3'-8"	1'-5"	5'	620	45	9
500 wg.	37 1/2"	Hemi.	10'	4'-2"	1'-8"	5'	950	37   30	8   6
1000 wg.	41"	Hemi.	16'	4'-5"	1'-8"	10'-1"	1,800	17   15	6   5
1450 wg.	46 1/2"	Ellip.	17'-4"	4'-11"	1'-9"	11'-7"	2,650	12	4
1990 wg.	46 1/2"	Ellip.	23'-11"	4'-11"	1'-9"	16'	3,520	8	4

Dimensions and specifications shown are approximate. Individual vessels may vary

<sup>\*\*</sup> Full load and stack quantities vary by shipping location. Check with your salesperson for details



HOME OFFICE 2914 U.S.61 Cleveland, MS 38732 800-345-2495

**OHIO LOCATION** 721 Graham Drive Fremont, OH 43420 419-334-2664

**UTAH LOCATION** 5601 Axel Park Rd. West Jordan, UT 84081 801-280-1133

Quality Steel 6/2017 S2


SUPPLEMENTAL

REVISION:

R-605

PROPOSED 500 GAL. LPG TANK DETAIL

<sup>\*</sup> Leg spacing +/- 2". Leg widths and spacing may vary based on mfg. location. Check with your salesperson for details. 120, 250, 320 wg. standard tanks - no holes in legs (one center hole on request). 500 and 1000 wg. standard tanks - 2 holes 16" on center. 1450 wg. and up as shown above.



			PARTS LIST			
ITEM	QTY	PART NO.	PART DESCRIPTION	LENGTH	UNIT WT.	NET WT.
1	2	X-VFAW	SUPPORT ARM		71.41	142.81
2	1	X-HDCAMTBW	CLAMP WELDMENT FOR BCAM-HD		33.86	33.86
3	1	X-MHTPHD	MULTI-HOLE TAPER PLATE WELDMENT		36.24	36.24
4	2	X-VFAPL4	VFA-HD PIVOT PLATE	12 in	15.88	31.77
5	2	X-LCBP4	BENT BACKING PLATE	13 in	20.04	40.09
6	1	X-HDCAMSS	ANGLE ADJUSTMENT WELDMENT FOR BCAM-HD		16.39	16.39
7	4	X-SPTB	SLIDING PIPE TIE BACK PLATE	5 1/2 in	5.87	23.49
8	1	X-HDCAMSP	POSITIONING PLATE WELDMENT FOR BCAM-HD		2.58	2.58
9	4	X-TBCA	TIE BACK CLIP ANGLE	1	2.01	8.02
10	8	SCX2	CROSSOVER PLATE	7 in	4.80	38.37
11	4	MCP	CLAMP HALF 1/2" THICK, 11-5/8" LONG	12 1/16 in	3.59	14.37
12	8	DCP	1/2" THICK, 5-3/4" CNTER TO CENTER CLAMP HALF	8 1/8 in	2.36	18.90
13	2	P2126	2-3/8" X 126" (2" SCH. 40) GALVANIZED PIPE	126 in	40.75	81.50
14	2	P30150	2-7/8" X 150" (2-1/2" SCH. 40) GALVANIZED PIPE	150 in	76.94	153.87
15	4	A34212	3/4" x 2-1/2" UNC HEX BOLT (A325)	2 1/2 in	0.48	1.92
16	4	G34FW	3/4" HDG USS FLATWASHER		0.06	0.24
17	4	G34LW	3/4" HDG LOCKWASHER	1	0.04	0.17
18	4	G34NUT	3/4" HDG HEAVY 2H HEX NUT		0.21	0.85
19	8	G58R-18	5/8" x 18" THREADED ROD (HDG.)		1.57	12.54
20	4	G58R-12	5/8" x 12" THREADED ROD (HDG.)	i e	1.05	4.18
21	4	G58R-8	5/8" x 8" THREADED ROD (HDG.)	İ	0.70	2.79
22	4	X-UB5300	5/8" X 3" X 5-1/4" X 2-1/2" U-BOLT (HDG.)		1.15	4.60
23	8	X-UB5258	5/8" X 2-5/8" X 4-1/2" X 2" U-BOLT (HDG.)		1.00	8.00
24	2	G5807	5/8" x 7" HDG HEX BOLT GR5 FULL THREAD	7 in	0.70	1.41
25	1	G5806	5/8" x 6" HDG HEX BOLT GR5 FULL THREAD	6 in	0.62	0.62
26	8	G5804	5/8" x 4" HDG HEX BOLT GR5		0.44	3.55
27	4	G5802	5/8" x 2" HDG HEX BOLT GR5	1	0.27	1.08
28	8	A582114	5/8" x 2-1/4" HDG A325 HEX BOLT	2 1/4 in	0.31	2.50
29	25	G58FW	5/8" HDG USS FLATWASHER	1/8 in	0.07	1.76
30	66	G58LW	5/8" HDG LOCKWASHER		0.03	1.72
31	71	G58NUT	5/8" HDG HEAVY 2H HEX NUT		0.13	9.22
32	32	X-UB1300	1/2" X 3" X 5" X 2" GALV U-BOLT		0.74	23.64
33	16	X-UB1212	1/2" X 2-1/2" X 4-1/2" X 2" U-BOLT (HDG.)		0.60	9.56
34	64	G12FW	1/2" HDG USS FLATWASHER	3/32 in	0.03	2.18
35	64	G12LW	1/2" HDG LOCKWASHER	1/8 in	0.01	0.89
36	64	G12NUT	1/2" HDG HEAVY 2H HEX NUT		0.07	4.58
					TOTAL WT. #	740.26

					1
D	UPDATED BCAM VERSION 1 TO BCAM VERSION 2		CEK	6/29/2018	1!
С	UPDATED PIN LEG CONNECTION TO B-CAM CONNECTION		CEK	12/7/2017	]'
В	CHANGED TIE-BACK BACK CONNECTION		CEK	7/31/2017	]′
Α	CHANGED TIE-BACK FRONT CONNECTION		CEK	2/2/2017	ľ
REV	DESCRIPTION OF REVISIONS	CPD	BY	DATE	];
	REVISION HISTORY				ľ

# **TOLERANCE NOTES**

TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE: SAWED, SHEARED AND GAS CUT EDGES (± 0.030")

DRILLED AND GAS CUT HOLES (± 0.030") - NO CONING OF HOLES LASER CUT EDGES AND HOLES (± 0.010") - NO CONING OF HOLES BENDS ARE ± 1/2 DEGREE

ALL OTHER MACHINING (± 0.030") ALL OTHER ASSEMBLY (± 0.060")

PROPRIETARY NOTE:
THE DATA AND TECHNIQUES CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF VALIMONT
INDUSTRIES AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT THE CONSENT OF
VALMONT INDUSTRIES IS STRICTLY PROHIBITED.

12' 6" HEAVY DUTY V-FRAME ASSEMBLY WITH TWO STIFF ARMS

DWG. NO.

ENG. APPROVAL

CHECKED BY

BMC 12/13/2017

A valmont **T** COMPANY

Locations: New York, NY Atlanta, GA Los Angeles, CA Plymouth, IN Salem, OR Dallas, TX

VFA12-HD VFA12-HD

**SUPPLEMENTAL** 

SHEET NUMBER:

REVISION:

PROPOSED SECTOR FRAME MOUNT DETAILS

DESCRIPTION

DRAWN BY

CEK 1/25/2017

CUSTOMER

DRAWING USAGE

CPD NO.

81 02





Colliers Engineering & Design 5141 Virginia Way, Suite 420 Brentwood, TN 37027 615.686.2575 ashley.sustek@collierseng.com

# New/Replacement Antenna Mount Analysis Report and PMI Requirements

Mount Analysis-R

SMART Tool Project #: 10234593 Colliers Engineering & Design Project #: 21941226

May 17, 2024

<u>Site Information</u> Site ID: 5000077708-VZW / PHILLIPS LAKE CITY

Site Name: PHILLIPS LAKE CITY
Carrier Name: Verizon Wireless
Address: 233 NW Ranch Court

Lake City, Florida 32056 Columbia County

Latitude: 30.225722° Longitude: -82.724833°

<u>Structure Information</u> Tower T

Tower Type: 300-Ft Guyed Mount Type: 12.50-Ft Sector Frame

FUZE ID # 16276469

# Analysis Results

Sector Frame: 65.7% Pass w/ Mount Replacement\*
((3) Site Pro 1 VFA12-HD)

\*Antennas and equipment to be installed in compliance with PMI Requirements of this mount analysis.

\*\*\*Contractor PMI Requirements:
Included at the end of this MA report
Available & Submitted via portal at https://pmi.vzwsmart.com
For additional questions and support, please reach out to:
pmisupport@colliersengineering.com

Report Prepared By: David Anuka



Mount Structural Analysis Report (3) 12.50-Ft Sector Frame

May 17, 2024 Site ID: 5000077708-VZW / PHILLIPS LAKE CITY Page | 5

# Mount Steel (EPA)a per ANSI/TIA-222-H Section 2.6.11.2:

Ice	Mount Pipes Excluded		Mount Pipes Included		
Thickness (In)	Front (EPA)a (Sq. Ft.)	Side (EPA)a (Sq. Ft.)	Front (EPA)a (Sq. Ft.)	Side (EPA)a (Sq. Ft.)	
0	15.1	6.7	24.2	15.8	
0.5	23.7	12.2	36.6	25.2	
1	31.6	17.2	48.4	34.0	

#### Notes

- (EPA)a values listed above may be used in the absence of more precise information
- (EPA)a values in the table above include 1 sector(s).
- Ka factors included in (EPA)a calculations

# Requirements:

The proposed antenna mounts are **SUFFICIENT** for the final loading configuration (attachment 2) upon completion of the mount replacement (attachment 3) and requirements below.

Refer to document at the end of this form for special instructions. Contact EOR if special instructions are not available.

ANSI/ASSP rigging plan review services compliant with the requirements of ANSI/TIA 322 are available for a Construction Class IV site or other, if required. Separate review fees will apply.

# Attachments:

- 1. Contractor Required Post Installation Inspection (PMI) Report Deliverables
- 2. Antenna Placement Diagrams
- 3. Mount Manufacturer Drawings
- 4. Existing Mount Photos
- 5. Analysis Calculations

SUPPLEMENTAL

SHEET NUMBER:

REVISION:

R-607

MOUNT ANALYSIS

SCALE: N.T.S.

NOTE: THIS SHEET WAS CREATED BY OTHERS AND PROVIDED AT THE REQUEST OF THE CUSTOMER WITHOUT EDIT. PLEASE REFERENCE THE MOUNT ANALYSIS REPORT FOR COMPLETE MOUNT ANALYSIS CALCULATIONS AND DETAILS. SUPPLEMENTAL PAGES INCLUDED IN THE CONSTRUCTION DRAWINGS ARE FOR REFERENCE ONLY. GENERAL CONTRACTOR IS TO VERIFY THEY HAVE THE MOST RECENT MOUNT ANALYSIS PRIOR TO CONSTRUCTION.