

Columbia County Building Permit

PERMIT

DATE 02/20/2007

000025553

This Permit Expires One Year From the Date of Issue

PHONE 752-5152

APPLICANT MARY ANN CRAWFORD

FL 32025

ADDRESS 853 SW SISTERS WELCOME RD

LAKE CITY

OWNER JOHN HOLTON

PHONE 752-2235

ADDRESS 228 SW ROYAL COURT

LAKE CITY

CONTRACTOR STANLEY CRAWFORD

PHONE 752-5152

LOCATION OF PROPERTY 90 EAST, L 247, L 242, L ROYAL COURT, 5TH ON LEFT

TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 92000.00

HEATED FLOOR AREA 1840.00 TOTAL AREA 2680.00 HEIGHT 21.75 STORIES 1

FOUNDATION CONCRETE WALLS FRAMED ROOF PITCH 6/12 FLOOR SLAB

LAND USE & ZONING RSF-2 MAX. HEIGHT 35

Minimum Set Back Requirements: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00

NO. EX.D.U. 0 FLOOD ZONE XPP DEVELOPMENT PERMIT NO.

PARCEL ID 21-4S-16-03081-105 SUBDIVISION KENSINGTON

LOT 5 BLOCK PHASE UNIT TOTAL ACRES 0.50

RG0042896

Culvert Permit No. Culvert Waiver Contractor's License Number

EXISTING 07-00142N BK

Driveway Connection Septic Tank Number

LU & Zoning checked by

Approved for Issuance

JH

N

New Resident

COMMENTS: NOC ON FILE, FLOOR ONE FOOT ABOVE THE ROAD

Check # or Cash 14

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power

Foundation

Monolithic

date/app. by

date/app. by

date/app. by

Under slab rough-in plumbing

Slab

Sheathing/Nailing

date/app. by

Framing

Rough-in plumbing above slab and below wood floor

date/app. by

Columbia County Building Permit Application

For Office Use Only Application # 0702-40 Date Received 2/15/07 By GT Permit # 25553
 Application Approved by - Zoning Official BLK Date 16.02.07 Plans Examiner OKJTH Date 2-16-07
 Flood Zone x pmt Development Permit N/A Zoning RSF-2 Land Use Plan Map Category RES. D.E.
 Comments V.L.

☒ NOC ☒ EH ☐ Deed or PA ☐ Site Plan ☐ State Road Info ☐ Parent Parcel # ☐ Development Permit

Name Authorized Person Signing Permit Mary Ann Crawford Phone (386) 752-5152
 Address 853 S.W. Sisters Welcome Rd. Lake City, FL 32025
 Owners Name John D. Holton Phone (386) 752-2235
 911 Address 228 S.W. Royal Court Lake City, FL 32024
 Contractors Name Stanley Crawford Construction, Inc. Phone (386) 752-5152
 Address 853 S.W. Sisters Welcome Rd. Lake City, FL 32025

Fee Simple Owner Name & Address _____
 Bonding Co. Name & Address _____
 Architect/Engineer Name & Address Mark Disoway - P.O. Box 868 Lake City, FL 32056
 Mortgage Lenders Name & Address First Federal - 4307 US Hwy. 90 West Lake City, FL 32025

Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progressive Energy
 Property ID Number 21-45-16-03081-105 Estimated Cost of Construction \$140,000.00
 Subdivision Name Kensington Lot 5 Block _____ Unit _____ Phase _____
 Driving Directions Hwy 90 East, Turn left on County Rd. 242, Turn left on Co. Rd. 242, turn left on Royal Court - 5th Lot on Left

Type of Construction Residential House Number of Existing Dwellings on Property 0
 Total Acreage 1/2 Acre Lot Size _____ Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
 Actual Distance of Structure from Property Lines - Front 40 Side 30 Side 61 Rear 54
 Total Building Height 20' 1 3/4" Number of Stories 1 Heated Floor Area 1840.8 Roof Pitch 6/12
 TOTAL 2680

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Stanley Crawford
 Owner Builder or Authorized Person by Notarized Letter

STATE OF FLORIDA
 COUNTY OF COLUMBIA



Sworn to (or affirmed) and subscribed before me
 his 14th day of February 2007.
 Personally known ☒ or Produced Identification _____
Janet L. Cheek
 Notary Signature

Stanley Crawford
 Contractor Signature
 Contractors License Number RG-0042896
 Competency Card Number 5627
 NOTARY STAMP/SEAL

THIS INSTRUMENT WAS PREPARED BY:
FIRST FEDERAL SAVINGS BANK OF FLORIDA
4705 WEST U.S. HIGHWAY 90
P.O. BOX 2029
LAKE CITY, FLORIDA 32056

Inst:2007003510 Date:02/13/2007 Time:11:51
D.7 DC, P. DeWitt Cason, Columbia County B:1110 P:1712

PERMIT NO. _____

TAX FOLIO NO. 03681-105

NOTICE OF COMMENCEMENT

STATE OF FLORIDA
COUNTY OF Columbia


The undersigned hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

1. Description of property: Lot 5, Kensington Subdivision
Lake City, Florida Columbia County
2. General description of improvement: Construction of Dwelling
3. Owner information:
 - a. Name and address: John D. Halton
235 SW MARKS DRIVE, Lake City FL 32024
 - b. Interest in property: Fee Simple
 - c. Name and address of fee simple title holder (if other than Owner): NONE
4. Contractor (name and address): Stanly Crawford Construction
5. Surety:
 - a. Name and address: _____
 - b. Amount of bond: _____
6. Lender: **FIRST FEDERAL SAVINGS BANK OF FLORIDA**
4705 WEST U.S. HIGHWAY 90
P. O. BOX 2029
LAKE CITY, FLORIDA 32056
7. Persons within the State of Florida designated by Owner upon whom notices or other document may be served as provided by Section 713.13 (1) (a) 7., Florida Statutes: NONE
8. In addition to himself, Owner designates PAULA HACKER of FIRST FEDERAL SAVINGS BANK OF FLORIDA, 4705 West U.S. Highway 90 / P. O. Box 2029, Lake City, Florida 32056 to receive a copy of the Lienor's Notice as provided in Section 713.13 (1) (b), Florida Statutes.
9. Expiration date of notice of commencement (the expiration date is 1 year from the date of recording unless a different date is specified).

John D. Halton
Borrower Name

Co-Borrower Name

The foregoing instrument was acknowledged before me this 14th day of February, 2007, by John D. Halton who is personally known to me or who has produced driver's license for identification.



Kelly A. Renfro
Notary Public
My Commission Expires:


KELLY A. RENFROE

**Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan**

Permit Application Number: 07-00142N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

HOLTON/CR 06-3848



Site Plan Submitted By Paul L. [Signature] Date 1/19/07
Plan Approved ✓ Not Approved _____

By Salhi Maddy ESII 2-20-07 CPHU


Notes: Colr CHD

Columbia CHD

Construction Permit. Part II Site Plan
Permit Application Number: _____

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

HOLTON/CR 06-3848



Site Plan Submitted By Paul P. [Signature] Date 1/19/07
Plan Approved _____ Not Approved _____
By _____ CPHU

Notes: _____

01/17/2007 15:40

BISHOP REALTY
7547176

386/521284
HOME TOWN TITLE OF N

P. 2
PAGE 01/02

Prepared by and return to:
Sera Shettler

Home Town Title of North Florida
2744 US Highway 90 West
Lake City, FL 32065
386-754-7175
File Number: 2006-3713

Last: 2006070549 Date: 12/20/2006 Time: 15:00
Doc Stamp-Deed : 200.00

MC, P. Bennett Case, Columbia County B:1905 P:600

[Space Above This Line For Recording Date]

Warranty Deed

This Warranty Deed made this 20th day of December, 2006 between Janet Cormier and Kathleen Kane whose post office address is 7744 Highlands Circle, Margate, FL 33063, grantor, and John D. Holton, an unmarried person whose post office address is 236 SW Marks Drive, Lake City, FL 32024, grantee:

(Wherever used herein the terms "grantor" and "grantee" include all the parties to this instrument and the heirs, legal representatives, and assigns of individuals, and the successors and assigns of corporations, trusts and estates)

Witnesseth, that said grantor, for and in consideration of the sum of TEN AND NO/100 DOLLARS (\$10.00) and other good and valuable considerations to said grantor in hand paid by said grantee, the receipt whereof is hereby acknowledged, has granted, bargained, and sold to the said grantee, and grantee's heirs and assigns forever, the following described land, situate, lying and being in Columbia County, Florida to-wit:

Lot 5, Kensington Subdivision, a subdivision according to the plat thereof as recorded in Plat Book 6, pages 193-194 of the public records of Columbia County, Florida.

Parcel Identification Number: 21-45-16-03081-105

The above described property is not the homestead of the grantors herein.

Together with all the tenements, hereditaments and appurtenances thereto belonging or in anywise appertaining.

To Have and to Hold, the same in fee simple forever.


And the grantor hereby covenants with said grantee that the grantor is lawfully seized of said land in fee simple; that the grantor has good right and lawful authority to sell and convey said land; that the grantor hereby fully warrants the title to said land and will defend the same against the lawful claims of all persons whomsoever; and that said land is free of all encumbrances, except taxes accruing subsequent to December 31, 2006.

In Witness Whereof, grantor has hereunto set grantor's hand and seal this day and year first above written.

Signed, sealed and delivered in our presence:

Witness Name: Barbara J. [Signature]Witness Name: Janet Carrier (Seal)
Janet CarrierWitness Name: Barbara J. [Signature]Witness Name: Kathleen Kane (Seal)
Kathleen KaneState of Florida
County of BayardThe foregoing instrument was acknowledged before me this 20th day of December, 2006 by Janet Carrier, who ☐ is personally known or ☒ has produced a driver's license as identification.

(Notary Seal)

Notary Public: Pamela SanchezPrinted Name: Pamela SanchezMy Commission Expires: September 18, 2010Inst: 2006030509 Date: 12/20/2006 Time: 16:00
Doc Stamp-Due: 200.00
DC, P. Hewitt Cason, Columbia County R: 1100 P: 601

FORM 600A-2004R

EnergyGauge® 4.5

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

Project Name: holton	Builder: CRAWFORD
Address:	Permitting Office: Columbia
City, State:	Permit Number: 25553
Owner:	Jurisdiction Number: 221500
Climate Zone: North	

<p>1. New construction or existing New ___</p> <p>2. Single family or multi-family Single family ___</p> <p>3. Number of units, if multi-family 1 ___</p> <p>4. Number of Bedrooms 3 ___</p> <p>5. Is this a worst case? Yes ___</p> <p>6. Conditioned floor area (ft²) 1840 ft² ___</p> <p>7. (Glass type¹ and area: (Label req'd by 13-104.4.5 if not default))</p> <p>a. U-factor: Description Area (or Single or Double DEFAULT) 7a. (Table Default) 257.0 ft² ___</p> <p>b. SHGC: (or Clear or Tint DEFAULT) 7b. (Clear) 257.0 ft² ___</p> <p>8. Floor types</p> <p>a. Slab-On-Grade Edge Insulation R=0.0, 209.0(p) ft² ___</p> <p>b. N/A ___</p> <p>c. N/A ___</p> <p>9. Wall types</p> <p>a. Frame, Wood, Exterior R=13.0, 1065.0 ft² ___</p> <p>b. Frame, Wood, Adjacent R=13.0, 278.0 ft² ___</p> <p>c. N/A ___</p> <p>d. N/A ___</p> <p>e. N/A ___</p> <p>10. Ceiling types</p> <p>a. Under Attic R=30.0, 1840.0 ft² ___</p> <p>b. Under Attic R=30.0, 120.0 ft² ___</p> <p>c. N/A ___</p> <p>11. Ducts</p> <p>a. Sup: Unc. Ret: Unc. AH: Garage Sup. R=6.0, 255.0 ft² ___</p> <p>b. N/A ___</p>	<p>12. Cooling systems</p> <p>a. Central Unit Cap: 36.0 kBtu/hr ___ SEER: 13.00 ___</p> <p>b. N/A ___</p> <p>c. N/A ___</p> <p>13. Heating systems</p> <p>a. Electric Heat Pump Cap: 35.0 kBtu/hr ___ HSPF: 8.00 ___</p> <p>b. N/A ___</p> <p>c. N/A ___</p> <p>14. Hot water systems</p> <p>a. Electric Resistance Cap: 50.0 gallons ___ EF: 0.94 ___</p> <p>b. N/A ___</p> <p>c. Conservation credits (HR-Heat recovery, Solar DHP-Dedicated heat pump)</p> <p>15. HVAC credits (CR-Ceiling fan, CV-Cross ventilation, HT-Whole house fan, PT-Programmable Thermostat, MZ-C-Multizone cooling, MZ-H-Multizone heating)</p>
--	--

Glass/Floor Area: 0.14

Total as-built points: 24549

Total base points: 24587

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: _____

DATE: 2/13/07

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: _____

DATE: _____

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 563.908 Florida Statutes.



BUILDING OFFICIAL: _____

DATE: _____

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.

FORM 600A-2004R

EnergyGauge® 4.5

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: ...

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: 3 cfm/sq. ft. window area; 5 cfm/sq. ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings > 1/8" sealed unless backed by truss or joist members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spas & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

FORM 600A-2004R

EnergyGauge® 4.5

WATER HEATING & CODE COMPLIANCE STATUS**Residential Whole Building Performance Method A - Details**

ADDRESS: , , ,

PERMIT #:

BASE					AS-BUILT					
WATER HEATING										
Number of Bedrooms	X	Multiplier	=	Total	Tank Volume	EF	Number of Bedrooms	X	Tank X Ratio	Credit = Total Multiplier
3		2635.00		7905.0	50.0	0.94	3		1.00	2578.94
					As-Built Total:					7736.8

CODE COMPLIANCE STATUS									
BASE					AS-BUILT				
Cooling Points	+	Heating Points	+	Hot Water Points	=	Total Points	Cooling Points	+	Heating Points
7365		9317		7905		24587	7596		9216
							7737		24549

PASS

FORM 600A-2004R

EnergyGauge® 4.5

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE			AS-BUILT					
Winter Base Points: 16817.6			Winter As-Built Points: 17302.4					
Total Winter X Points	System = Multiplier	Heating Points	Total X Cap X Duct X System X Credit = Heating Component Ratio Multiplier Multiplier Multiplier Points					
			(System - Points) (DM x DSM x AHU)					
			(sys 1: Electric Heat Pump 35000 btuh ,EFF(8.0) Ducts:Unc(S),Unc(R),Gar(AH),R5.0					
16817.6	0.5540	9317.0	17302.4	1.000	(1.069 x 1.169 x 1.00)	0.426	1.000	9216.4
			17302.4	1.00	1.250	0.426	1.000	9216.4

FORM 600A-2004R

EnergyGauge® 4.5

WINTER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BWPM = Points				Overhang							
Floor Area				Type/SC	Omt	Len	Hgt	Area	X WPM	X WOF	= Point
.18	1840.0	29.17	6698.9	1. Double, Clear	N	2.0	6.0	42.0	24.58	1.00	1037.0
				2. Double, Clear	E	2.0	6.0	71.0	18.79	1.06	1415.0
				3. Double, Clear	S	2.0	6.0	22.0	13.30	1.26	368.0
				4. Double, Clear	W	2.0	6.0	122.0	20.73	1.04	2635.0
				As-Built Total: 257.0 6486.0							
WALL TYPES											
Area X BWPM = Points				Type	R-Value		Area X WPM		= Points		
Adjacent	278.0	3.60	1000.8	1. Frame, Wood, Exterior	13.0		1065.0	3.40	3621.0		
Exterior	1065.0	3.70	3940.5	2. Frame, Wood, Adjacent	13.0		278.0	3.30	917.4		
Base Total: 1343.0 4941.3				As-Built Total: 1343.0 4538.4							
DOOR TYPES											
Area X BWPM = Points				Type	R-Value		Area X WPM		= Points		
Adjacent	18.0	11.50	207.0	1. Exterior Insulated			36.0	8.40	302.4		
Exterior	36.0	12.30	442.8	2. Adjacent Insulated			18.0	8.00	144.0		
Base Total: 54.0 649.8				As-Built Total: 54.0 446.4							
CEILING TYPES											
Area X BWPM = Points				Type	R-Value		Area X WPM X WCM		= Points		
Under Attic	1840.0	2.05	3772.0	1. Under Attic	30.0		1840.0	2.05 X 1.00	3772.0		
				2. Under Attic	30.0		120.0	2.05 X 1.00	246.0		
Base Total: 1840.0 3772.0				As-Built Total: 1840.0 4018.0							
FLOOR TYPES											
Area X BWPM = Points				Type	R-Value		Area X WPM		= Points		
Slab	209.0(p)	8.9	1860.1	1. Slab-On-Grade Edge Insulation	0.0		209.0(p)	16.80	3499.2		
Raised	0.0	0.00	0.0								
Base Total: 1860.1				As-Built Total: 209.0 3929.2							
INFILTRATION											
Area X BWPM = Points				Area X WPM		= Points					
1840.0 -0.59 -1085.6				1840.0 -0.59		-1085.6					

FORM 600A-2004R

EnergyGauge® 4.5

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: ...

PERMIT #:

BASE				AS-BUILT						
Summer Base Points: 22661.5				Summer As-Built Points: 23368.1						
Total Summer Points	X Multiplier	= Cooling Points		Total Component (System - Points)	X Cap Ratio (DM x DSM x AHU)	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Cooling Points	
				<small>(eqn 1: Central Unit 36000btuh, SEER/EFP (13.0) Ducts: Uno(S), Uno(R), Gair(AH), R6.0(INS)</small>						
22661.5	0.3250	7365.0		23368.1	1.00	(1.09 x 1.147 x 1.00)	0.260	1.000	7596.0	
				23368.1	1.00	1.250	0.260	1.000	7596.0	

FORM 600A-2004R

EnergyGauge® 4.5

SUMMER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: ...

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BSPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt			Area X SPM X SOF = Points			
.18	1840.0	18.59	6167.0	1.Double, Clear	N	2.0	6.0	42.0	19.20	0.90	725.0
				2.Double, Clear	E	2.0	6.0	71.0	42.06	0.85	2532.0
				3.Double, Clear	S	2.0	6.0	22.0	35.87	0.78	612.0
				4.Double, Clear	W	2.0	6.0	122.0	38.52	0.85	3992.0
				As-Built Total:			257.0			7881.0	
WALL TYPES				Area X BSPM = Points		Type	R-Value		Area X SPM = Points		
Adjacent	278.0	0.70	194.6	1. Frame, Wood, Exterior		13.0		1065.0	1.50	1597.5	
Exterior	1065.0	1.70	1810.5	2. Frame, Wood, Adjacent		13.0		278.0	0.60	166.8	
Base Total:		1343.6	2066.1	As-Built Total:				1343.0	1764.3		
DOOR TYPES				Area X BSPM = Points		Type			Area X SPM = Points		
Adjacent	18.0	2.40	43.2	1.Exterior Insulated				36.0	4.10	147.6	
Exterior	36.0	6.10	219.6	2.Adjacent Insulated				18.0	1.60	28.8	
Base Total:		54.0	262.8	As-Built Total:				54.0	176.4		
CEILING TYPES				Area X BSPM = Points		Type	R-Value		Area X SPM X SCM = Points		
Under Attic	1840.0	1.73	3163.2	1. Under Attic		30.0		1840.0	1.73 X 1.00	3163.2	
				2. Under Attic		30.0		120.0	1.73 X 1.00	207.6	
Base Total:		1840.0	3163.2	As-Built Total:				1860.0	3390.8		
FLOOR TYPES				Area X BSPM = Points		Type	R-Value		Area X SPM = Points		
Slab	209.0(p)	-37.0	-7733.0	1. Slab-On-Grade Edge Insulation		0.0		209.0(p)	-41.20	-8610.8	
Raised	0.0	0.00	0.0								
Base Total:		-7733.0		As-Built Total:				209.0	-8610.8		
INFILTRATION				Area X BSPM = Points				Area X SPM = Points			
		1840.0	10.21	18786.4				1840.0	10.21	18786.4	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 84.5

The higher the score, the more efficient the home.

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 36.0 kBtu/hr
3. Number of units, if multi-family	1		SEER: 13.00
4. Number of Bedrooms	3	b. N/A	
5. Is this a worst case?	Yes	c. N/A	
6. Conditioned floor area (ft ²)	1840 ft ²		
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		13. Heating systems	
a. U-factor:	Description Area	a. Electric Heat Pump	Cap: 35.0 kBtu/hr
(or Single or Double DEFAULT) 7a. (Dble Default) 257.0 ft ²			HSPF: 8.00
b. SHGC:		b. N/A	
(or Clear or Tint DEFAULT) 7b. (Clear) 257.0 ft ²		c. N/A	
8. Floor types		14. Hot water systems	
a. Slab-On-Grade Edge Insulation	R=0.0, 209.0(p) ft	a. Electric Resistance	Cap: 50.0 gallons
b. N/A			EF: 0.94
c. N/A		b. N/A	
9. Wall types		c. Conservation credits	
a. Frame, Wood, Exterior	R=13.0, 1065.0 ft ²	(HR-Heat recovery, Solar	
b. Frame, Wood, Adjacent	R=13.0, 278.0 ft ²	DHP-Dedicated heat pump)	
c. N/A		15. HVAC credits	
d. N/A		(CF-Ceiling fan, CV-Cross ventilation,	
e. N/A		HF-Whole house fan,	
10. Ceiling types		P1-Programmable Thermostat,	
a. Under Attic	R=30.0, 1840.0 ft ²	MZ-C-Multizone cooling,	
b. Under Attic	R=30.0, 120.0 ft ²	MZ-H-Multizone heating)	
c. N/A			
11. Ducts			
a. Sup. Unc. Rot. Unc. AH: Garage	Sup. R=6.0, 255.0 ft		
b. N/A			

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____ Date: _____

Address of New Home: _____ City/FL Zip: _____



*NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStar[®] designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter (film output on pages 2&4).
EnergyGauge[®] (Version: FLRCSB v4.5)

COLUMBIA COUNTY FLORIDA DEPARTMENT OF BUILDING AND ZONING

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 21-4S-16-03081-105

Building permit No. 000025553

Use Classification SFD, UTILITY

Fire: 16.74

Permit Holder STANLEY CRAWFORD

Waste: 50.25

Owner of Building JOHN HOLTON

Total: 66.99

Location: 228 SW ROYAL COURT, LAKE CITY, FL

Date: 07/13/2007

Building Inspector



POST IN A CONSPICUOUS PLACE
(Business Places Only)

Notice of Treatment

12497

Applicator: Florida Pest Control & Chemical Co. (www.flapest.com)

Address: BAYLA AVE
City: CAVE CITY Phone: 752 1703

Site Location: Subdivision KENSINGTON RD
Lot # 5 Block# Permit # 25553
Address

<u>Product used</u>	<u>Active Ingredient</u>	<u>% Concentration</u>
---------------------	--------------------------	------------------------

<input type="checkbox"/> Premise	Imidacloprid	0.1%
----------------------------------	--------------	------

<input type="checkbox"/> Termidor	Fipronil	0.12%
-----------------------------------	----------	-------

<input checked="" type="checkbox"/> Bora-Care	Disodium Octaborate Tetrahydrate	23.0%
---	----------------------------------	-------

Type treatment:

☐ Soil ☒ Wood

<u>Area Treated</u>	<u>Square feet</u>	<u>Linear feet</u>	<u>Gallons Applied</u>
<u>Dwelling</u>	<u>2680</u>	<u>804</u>	<u>7</u>
<u></u>	<u></u>	<u></u>	<u></u>
<u></u>	<u></u>	<u></u>	<u></u>
<u></u>	<u></u>	<u></u>	<u></u>

As per Florida Building Code 104.2.6 – If soil chemical barrier method for termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial this line _____.

3/27/07 1300 Jessie Gummy
Date Time Print Technician's Name

Remarks: _____

Applicator - White

Permit File - Canary

Permit Holder - Pink

10/05

©

Project Summary

Entire House

Touchstone Heating and Air, Inc.

Job: John D Holton
Date: Jan 23, 2007
By: TE

P.O. Box 327, Lake Butler, FL 32054 Phone: 386-486-3487 Fax: 386-486-3147

Project Information

For: Stanley Crawford Construction
1531 SW Commercial Glen, Lake City, FL 32025
Phone: 386-752-5152 Fax: 386-755-2165

Notes:

Design Information

Weather: Gainesville, FL, US

Winter Design Conditions

Outside db	33 °F
Inside db	70 °F
Design TD	37 °F

Summer Design Conditions

Outside db	92 °F
Inside db	75 °F
Design TD	17 °F
Daily range	M
Relative humidity	50 %
Moisture difference	52 gr/lb

Heating Summary

Structure	17123 Btuh
Ducts	6257 Btuh
Central vent (43 cfm)	1725 Btuh
Humidification	0 Btuh
Piping	0 Btuh
Equipment load	25105 Btuh

Sensible Cooling Equipment Load Sizing

Structure	18878 Btuh
Ducts	7797 Btuh
Central vent (43 cfm)	792 Btuh
Blower	0 Btuh

Infiltration

Method	Simplified
Construction quality	Average
Fireplaces	0

	Heating	Cooling
Area (ft²)	1847	1847
Volume (ft³)	17044	17044
Air changes/hour	0.36	0.20
Equiv. AVF (cfm)	108	57

Latent Cooling Equipment Load Sizing

Structure	2397 Btuh
Ducts	1764 Btuh
Central vent (43 cfm)	1498 Btuh
Equipment latent load	5660 Btuh

Equipment total load	30169 Btuh
Req. total capacity at 0.70 SHR	2.9 ton

Heating Equipment Summary

Make Trane
Trade XB13 Weathertron
Model 2TWB3036A1

Efficiency	8 HSPF
Heating input	
Heating output	29000 Btuh @ 47°F
Temperature rise	24 °F
Actual air flow	1100 cfm
Air flow factor	0.047 cfm/Btuh
Static pressure	0.00 in H2O
Space thermostat	

Cooling Equipment Summary

Make Trane
Trade XB13 Weathertron
Cond 2TWB3036A1
Coil 2TXCB036AC3+*UX1B080A9H3

Efficiency	13 SEER
Sensible cooling	23100 Btuh
Latent cooling	9900 Btuh
Total cooling	33000 Btuh
Actual air flow	1100 cfm
Air flow factor	0.045 cfm/Btuh
Static pressure	0.00 in H2O
Load sensible heat ratio	0.82

Printout certified by ACCA to meet all requirements of Manual J 6th Ed.

Right-Suite Residential 6.0.00 RGR28972

Project1.rpt Calc = MJ8 Orientation = N

2007-Jan-23 09:58:18

Page 1



March 6, 2002

Subject: Elk Product Approval Information

All Prestique® and Capstone® products manufactured in Tuscaloosa, AL are certified under the Miami – Dade County Building Code Office (BCCO). These products also meet the requirements for the Florida Building Code since they are MD approved. The following test protocols must be passed by each of the products in order for MD product certification:

ASTM D3462

PA 100 (110 mph uplift and wind driven rain resistance)

PA 107 (Modified ASTM D3161 - 110 mph wind uplift resistance)

The nailing patterns that were used during the PA 100 and PA 107 wind test protocols for the Prestique and Capstone products are listed below. Also listed below are the Miami – Dade Notice of Acceptance Numbers (NOA).

Raised Profile, Prestique High Definition, Prestique 25, or Prestique 30 –

PA 100 = 4 nails

PA 107 = 5 nails

MD NOA# = 01-1226.04

Prestique I 35 or Prestique I* –

PA 100 = 4 nails

PA 107 = 5 nails

MD NOA# = 01-1226.05

Prestique Plus or Prestique Gallery Collection* –

PA 100 = 4 nails

PA 107 = 4 nails

MD NOA# = 01-1226.03

Capstone*

PA 100 = 4 Nails

PA 107 = 4 Nails

MD NOA# = 01-0523.01

* As per the Elk Limited Warranty, six nails are required for the Elk high wind warranty.

If there are any questions please contact:



Mike Reed – Technical Manager
(205) 342-0287

or

Daniel DeJarnette – QA Engineer
(205) 342-0298

**ELK**

ROOFING PRODUCTS SPECIFICATIONS — TUSCALOOSA, AL

**PRESTIQUE®
HIGH DEFINITION®****RAISED PROFILE™****Prestique Plus High Definition
and Prestique Gallery Collection***

Product size 13½" x 39½"
Exposure 5½"
Pieces/Bundle 16
Bundles/Square 4/98.5 sq.ft.
Squares/Pallet 11

50-year limited warranty period:
non-prorated coverage for
shingles and application labor for
the initial 5 years, plus an option
for transferability*; prorated
coverage for application labor and
shingles for balance of limited
warranty period; 5-year limited
wind warranty*.

Raised Profile

Product size 13½" x 38½"
Exposure 5½"
Pieces/Bundle 22
Bundles/Square 3/100 sq.ft.
Squares/Pallet 16

30-year limited warranty period:
non-prorated coverage for
shingles and application labor for
the initial 5 years, plus an option
for transferability*; prorated
coverage for application labor and
shingles for balance of limited
warranty period; 5-year limited
wind warranty*.

Prestique I High Definition

Product size 13½" x 39½"
Exposure 5½"
Pieces/Bundle 16
Bundles/Square 4/98.5 sq.ft.
Squares/Pallet 14

40-year limited warranty period:
non-prorated coverage for
shingles and application labor for
the initial 5 years, plus an option
for transferability*; prorated
coverage for application labor and
shingles for balance of limited
warranty period; 5-year limited
wind warranty*.

HIP AND RIDGE SHINGLES**Seal-A-Ridge® w/FLX®**

Size: 12" x 12"
Exposure: 6½"
Pieces/Bundle: 45
Coverage: 4 Bundles = 100 linear feet

Prestique High Definition

Product size 13½" x 38½"
Exposure 5½"
Pieces/Bundle 22
Bundles/Square 3/100 sq.ft.
Squares/Pallet 16

30-year limited warranty period:
non-prorated coverage for
shingles and application labor for
the initial 5 years, plus an option
for transferability*; prorated
coverage for application labor and
shingles for balance of limited
warranty period; 5-year limited
wind warranty*.

Elk Starter Strip

52 Bundles/Pallet
18 Pallets/Truck
936 Bundles/Truck
19 Pieces/Bundle
1 Bundle = 120.33 linear feet

Available Colors: Antique Slate, Weatheredwood, Shakeswood, Sablewood, Hickory, Barkwood**, Forest Green, Wedgewood**, Birchwood**, Sandalwood.
Gallery Collection: Balsam Forest®, Weathered Sage®, Sienna Sunset®.

All Prestique, Raised Profile and Seal-A-Ridge roofing products contain Elk WindGuard® sealant. WindGuard activates with the sun's heat, bonding shingles into a wind and weather resistant cover that resists blow-offs and leaks.

Check for availability with built-in StainGuard® treatment to inhibit the discoloration of roofing granules caused by the growth of certain types of algae. Not available in Sablewood.

All Prestique and Raised Profile shingles meet UL® Wind Resistant (UL 997) and Class "A" Fire Ratings (UL 790); and ASTM Specifications D 3018, Type-I; D 3161, Type-I; E 108 and the requirements of ASTM D 3462.

All Prestique and Raised Profile shingles meet the latest Metro Dade building code requirements.

*See actual limited warranty for conditions and limitations.

**Check for product availability.

SPECIFICATIONS

SCOPE: Work includes furnishing all labor, materials and equipment necessary to complete installation of (name) shingles specified herein. Color shall be (name of color). Hip and ridge type to be Elk Seal-A-Ridge with formula FLX.

All exposed metal surfaces (flashing, vents, etc.) to be painted with matching Elk roof accessory paint.

PREPARATION OF ROOF DECK: Roof deck to be dry, well-seasoned 1" x 6" (25.4mm x 152.4mm) boards; exterior-grade plywood (exposure 1 rated sheathing) at least 3/8" (9.525mm) thick conforming to the specifications of the American Plywood Association; 7/16" (11.074mm) oriented strandboard; or chipboard. Most fire retardant plywood decks are NOT approved substrates for Elk shingles. Consult Elk Field Service for application specifications over other decks and other slopes.

MATERIALS: Underlayment for standard roof slopes, 4" per foot (101.6/304.8mm) or greater: apply non-perforated No. 15 or 30 asphalt-saturated felt underlayment. For low slopes (4" per foot (101.6/304.8mm) to a minimum of 2" per foot (50.8/304.8mm)), use two plies of underlayment overlapped a minimum of 19". Fasteners shall be of sufficient length and holding power for securing material as required by the application instructions printed on shingle wrapper.

For areas where algae is a problem, shingles shall be (name) with StainGuard treatment, as manufactured by the Elk Tuscaloosa plant. Hip and ridge type to be Seal-A-Ridge with formula FLX with StainGuard treatment.

Complete application instructions are published by Elk and printed on the back of every shingle bundle. All

warranties are contingent upon the correct installation as shown on the instructions. These instructions are the minimum required to meet Elk application requirements. In some areas, building codes may require additional application techniques or methods beyond our instructions. In these cases, the local code must be followed. Under no circumstances will Elk accept application requirements less than those contained in its application instructions.

For specifications in CSI format, call 800.354.SPEC (7732) or e-mail specinfo@elkcorp.com.

**SOUTHEAST &
ATLANTIC OFFICE:**
800.945.5551

CORPORATE HEADQUARTERS:
800.354.7732


PLANT LOCATION:
800.945.5545

ELK
www.elkcorp.com


SSOOT 01/02

DIRECTIONS FOR APPLICATION


Please read carefully. Failure to follow these instructions may void the product warranty. See specific application instructions for Prestique® Plus and Prestique Gallery Collection™ 110 MPH and Prestique I 90 MPH limited wind warranty requirements.




● **VALLEY CONSTRUCTION OPTION** (California Open and California Closed are also acceptable) NOTE: For complete ARMA valley installation details, see ARMA Residential Asphalt Roofing Manual.



VALLEY CENTER LINE



VALLEY CENTER LINE



VALLEY CENTER LINE

DIRECTIONS FOR APPLICATION

These application instructions are the minimum required to meet Elk's application requirements. Your failure to follow these instructions may void the product warranty. In some areas, the building codes may require additional application techniques or methods beyond our instructions. In these cases, the local code must be followed. Under no circumstances will Elk accept application requirements that are less than those printed here. Shingles should not be jammed tightly together. All attics should be properly ventilated. Note: It is not necessary to remove tape on back of shingles.

● DECK PREPARATION

Roof decks should be dry, well-seasoned 1" x 6" boards or exterior grade plywood minimum 3/8" thick and conform to the specifications of the American Plywood Association or 7/16" oriented strandboard, or 7/16" chipboard.

● UNDERLAYMENT

Apply underlayment (Non-Perforated No. 15 or 30 asphalt saturated felt). Cover drip edge at eaves only.

For low slope (2/12 up to 4/12), completely cover the deck with two plies of underlayment overlapping a minimum of 18". Begin by fastening a 1" wide strip of underlayment placed along the eaves. Place a full 36" wide sheet over the starter, horizontally placed along the eaves and completely overlapping the starter strip.

EAVE FLASHING FOR ICE DAMS (ASK A ROOFING CONTRACTOR, REFER TO ARMA MANUAL OR CHECK LOCAL CODES)

For standard slope (4/12 to less than 21/12), use coated roll roofing of no less than 30 pounds over the felt underlayment extending from the eave edge to a point at least 24" beyond the inside wall of the living space below or one layer of a self-adhered eave and flashing membrane.

For low slope (2/12 up to 4/12), use a continuous layer of asphalt plastic cement between the two plies of underlayment from the eave edge up roof to a point at least 24" beyond the inside wall of the living space below or one layer of a self-adhered eave and flashing membrane.

Consult the Elk Field Service Department for application specifications over other decks and other slopes.

● STARTER SHINGLE COURSE

USE AN ELK STARTER STRIP OR A STRIP SHINGLE INVERTED WITH THE HEADLAP APPLIED AT THE EAVE EDGE. With at least 4" trimmed from the end of the first shingle, start at the rake edge overhanging the eave 1/2" to 3/4". Fasten 2" from the lower edge and 1" from each side. Shingles may be applied with a course alignment of 45° on the roof.

● FIRST COURSE

Start at rake and continue course with full shingles laid flush with the starter course.

● SECOND COURSE

Start at the rake with the shingle having 10" trimmed off and continue across roof with full shingles.

● THIRD COURSE

Start at the rake with the shingle having 20" trimmed off and continue across roof with full shingles.

● FOURTH COURSE

Start at the rake and continue with full shingles across roof.

FIFTH AND SUCCEEDING COURSES.

Repeat application as shown for second, third, and fourth courses. Do not rack shingles straight up the roof.

● VALLEY CONSTRUCTION

Open, woven and closed cut valleys are acceptable when applied by Asphalt Roofing Manufacturing Association (ARMA) recommended procedures. For metal valleys, use 36" wide vertical underlayment prior to applying 18" metal flashing (secure edge with nails). No nails are to be within 6" of valley center.

● RIDGE CONSTRUCTION

For ridge construction use Class "A" Seal-A-Ridge™ with formula FLX™ (See ridge package for installation instructions.)

FASTENERS

While nailing is the preferred method for Elk shingles, Elk will accept fastening methods according to the following instructions. Always nail or staple through the fastener line or on products without fastener lines, nail or staple between and in line with sealant dots.

NAILS: Corrosive resistant, 3/8" head, minimum 12-gauge roofing nails. Elk recommends 1-1/4" for new roofs and 1-1/2" for re-roofs. In cases where you are applying shingles to a roof that has an exposed overhang, for new roofs only, 3/4" ring shank nails are allowed to be used from the eave's edge to a point up the roof that is past the outside wall line. 1" ring shank nails allowed for re-roof.

STAPLES: Corrosive resistant, 16-gauge minimum, crown width minimum of 15/16". Note: An improperly adjusted staple gun can result in raised staples that can cause a fish-mouthed appearance and can prevent sealing.

Fasteners should be long enough to obtain 3/4" deck penetration or penetration through deck, whichever is less.


MANSARD APPLICATIONS

Correct fastening is critical to the performance of the roof. For slopes exceeding 60° (or 21/12) use six fasteners per shingle. Locate fasteners in the fastener area 1" from each side edge with the remaining four fasteners equally spaced along the length of the double thickness (laminated) area. Only fastening methods according to the above instructions are acceptable.

LIMITED WIND WARRANTY


• For a Limited Wind Warranty, all Prestique and Raised Profile™ shingles must be applied with 4 properly placed fasteners, or in the case of mansard applications, 6 properly placed fasteners per shingle.

• For a Limited Wind Warranty up to 110 MPH for Prestique Gallery Collection or Prestique Plus or 90 MPH for Prestique I, shingles must be applied with 6 properly placed NAILS per shingle. SHINGLES APPLIED WITH STAPLES WILL NOT QUALIFY FOR THIS ENHANCED LIMITED WIND WARRANTY. Also, Elk Starter Strip shingles must be applied at the eaves and rake edges to qualify Prestique Plus, Prestique Gallery Collection and Prestique I shingles for this enhanced Limited Wind Warranty. Under no circumstances should the Elk Shingles or the Elk Starter Strip overhang the eaves or rake edge more than 3/4" of an inch.



HELP STOP BLOW-OFFS AND CALL-BACKS

A minimum of four fasteners must be driven into the DOUBLE THICKNESS (laminated) area of the shingle. Nails or staples must be placed along – and through – the fastener line or on products without fastener lines, nail or staple between and in line with sealant dots. CAUTION: Do not use fastener line for shingle alignment.



Refer to local codes which in some areas may require specific application techniques beyond those Elk has specified. All Prestique and Raised Profile shingles have a UL® Wind Resistance Rating when applied in accordance with these instructions using nails or staples on re-roofs as well as new construction.

CAUTION TO WHOLESALE: Careless and improper storage or handling can harm fiberglass shingles. Keep these shingles completely covered, dry, reasonably cool, and protected from the weather. Do not store near various sources of heat. Do not store in direct sunlight until applied. Do NOT DOUBLE STACK. Systematically rotate all stock so that the material that has been stored the longest will be the first to be moved out.

© 2002 Elk Corporation of Dallas.

All trademarks, ®, are registered trademarks of Elk Corporation of Dallas, an ELOOR company. Raised Profile, RidgeCrest, Gallery Collection and FLX are trademarks pending registration of Elk Corporation of Dallas. UL is a registered trademark of Underwriters Laboratories, Inc.

ELK
www.elkcorp.com

FLORIDA DEPARTMENT OF Community Affairs



[BCIS Home](#) | [Log In](#) | [Hot Topics](#) | [Submit Surcharge](#) | [Stats & Facts](#) | [Publications](#) | [FBC Staff](#) | [B](#)



Product Approval USER: Public User

[Product Approval Menu](#) > [Product or Application Search](#) > [Application List](#) > [Application Detail](#)

► COMMUNITY PLANNING

► HOUSING & COMMUNITY
DEVELOPMENT

► ECONOMIC DEVELOPMENT

► ENVIRONMENTAL PROTECTION

► EMERGENCY MANAGEMENT

► OFFICE OF THE
SECRETARY

► PUBLIC AFFAIRS

► REGULATORY AFFAIRS

► TECHNICAL AFFAIRS

► TRAINING & EDUCATION

► WORKING WITH THE PUBLIC

► WORKING WITH THE PRIVATE

► WORKING WITH THE STATE

► WORKING WITH THE LOCAL

► WORKING WITH THE FEDERAL

► WORKING WITH THE INDUSTRY

FL #

FL1476-R2

Application Type

Revision

Code Version

2004

Application Status

Approved

Comments

Archived



Product Manufacturer

Elk Corporation

Address/Phone/Email

4600 Stillman Blvd.
Tuscaloosa, AL 35401
(205) 342-0298
daniel.dejarnette@elkcorp.com

Authorized Signature

Daniel DeJarnette
daniel.dejarnette@elkcorp.com

Technical Representative

Daniel DeJarnette

Address/Phone/Email

4600 Stillman Blvd
Tuscaloosa, AL 35401
(205) 342-0298
daniel.dejarnette@elkcorp.com

Quality Assurance Representative

Address/Phone/Email

Category

Roofing

Subcategory

Asphalt Shingles

Compliance Method

Certification Mark or Listing

Certification Agency

Underwriters Laboratories Inc.

Referenced Standard and Year (of Standard)

Standard

ASTM D3462
 TAS 107

Equivalence of Product Standards
 Certified By

Product Approval Method

Method 1 Option A

Date Submitted

09/20/2005

Date Validated

09/27/2005

Date Pending FBC Approval

09/29/2005

Date Approved

10/11/2005

Summary of Products

FL #	Model, Number or Name	Description
1476.1	Elk Prestique Shingles	Laminated Asphalt Shingles
Limits of Use (See Other) Approved for use in HVHZ: Approved for use outside HVHZ: Impact Resistant: Design Pressure: +/- Other: 1) All FBC sections apply except for those pertaining to Miami - Dade and Broward Counties 2) Refer to NOA # 0500706.07 for use in Dade and Broward Counties		Certification Agency Certificate Installation Instruction <u>PTID 1476 R2 I Specs.</u> <u>PTID 1476 R2 I UL Pre</u> Verified By:

Back

Next

DCA Administration

Department of Community Affairs
Florida Building Code Online
Codes and Standards

2555 Shumard Oak Boulevard
 Tallahassee, Florida 32399-2100

(850) 487-1824, Suncom 277-1824, Fax (850) 414-8436

© 2000-2005 The State of Florida. All rights reserved. Copyright and Disclaimer

Product Approval Accepts:




Door Model	Gauge	Decimal
2250/2251	25	.0185
4250/4251	25	.0185
2240/2241	24	.0225
4240/4241	24	.0225
5240/5241	24	.0225

door height	section quantity	strut quantity	trk brkt per side
6'-6" to 7'-0"	4	7	3
7'-6" to 8'-0"	5	8	4
8'-3" to 8'-9"	5	9	4
9'-0" to 10'-6"	6	11	5
10'-9" to 12'-3"	7	13	6
12'-6" to 14'-0"	8	15	7

Refer to Supplemental Instructions for strut placement on doors over 7'-0" high

Track Bracket Chart	door height									
	6'-6"	6'-9"	7'-0"	7'-6"	8'-0"	8'-3"	8'-6"	8'-9"		
D	n/a	n/a	n/a	72"	69"	72"	81"	84"	87"	
C	60"	63"	66"	58"	55"	58"	60"	63"	66"	
B	35"	35"	38"	34"	31"	34"	32"	35"	38"	
A	10"	7"	10"	10"	7"	10"	4"	7"	10"	

Track bracket locations shown above are for doors up to five sections high. Additional door sections may be added for a maximum door height of 14'-0". One track bracket (per track) must be added for each section and spaced at a distance not greater than the corresponding section height.




This door has been tested in accordance with ANSI/DASMA 108-2002
 Design Pressure (DP): 18.5 psf / 20.7 neg
 Test Pressure (TP): 27.8 psf / 31.1 neg
 Per 2004 FBC Table 1609.6E, DP meets or exceeds basic wind speed of:
 V = 110 MPH for Exposure B and mean roof height of 30' or less
 V = 93 MPH for Exposure C and mean roof height of 30' or less
 Maximum door size: 16'-0" wide by 14'-0" tall
 Glazing and door have not been tested for windborne debris.
 Wood buck and supporting structural elements shall be designed by a registered professional engineer for wind loads shown on this drawing.
 If door is not electrically operated, a lock must be installed.

Professional Engineer's seal provided only for verification of windload construction details

John E. Scates, P.E.
 1411 LeMay Street #205
 Carrollton, Texas 75007
 Florida P.E. # 51737


FL 5519

4 3 2 1




The 2x6 vertical wood jambs are to be grade 2 or better southern pine. Fasteners may be countersunk to provide a flush mounting surface.

12 gauge (.095) galvanized steel track bracket fastened to wood jamb with one 5/16" x 1-5/8" wood lag screw per bracket.




2" x .051 min. galvanized steel track fastened to track brackets. Each track bracket attached with one 1/4" x 5/8" track bolt and nut.


2" steel track roller:



Intermediate Hinge
18 gauge (.047) galvanized steel intermediate hinge fastened to section with four 1/4" x 3/4" screws.



12 gauge (.102) galvanized steel bottom bracket manufactured by C.H.I. Each bracket attached with four red 1/4" x 3/4" screws.




Vinyl
Aluminum extrusion
push nut
weatherstrip


12 gauge (.086) galvanized steel flag bracket fastened to wood jamb with three 5/16" x 1-5/8" wood lag screws.

Flag bracket attached to horizontal track with two 1/4" x 5/8" track bolts and nuts.

Flag bracket attached to vertical track with two 1/4" x 5/8" track bolts and nuts.



Each track bracket attached with one 1/4" x 5/8" track bolt and nut. Or two 1/4" x 11/32" rivets.



Design Load: 18.5 pos / 20.7 neg
Test Load: 27.8 pos / 31.1 neg
page 2 of 2

John E. Scates, P.E.
1411 LeMay Street #205
Carrollton, Texas 75007
Florida P.E. # 51737


C.H.I.
Model 2250/51 (16'-0" wide)
C.H.I. Drawing: Z3-1607-01100

4 3 2 1



Clyatt Well Drilling, Inc.
(Established in 1971)
POST OFFICE BOX 180
WORTHINGTON SPRINGS, FLORIDA 32697

Telephone Number (386)496-2488
FAX Number (386)496-4640



June 18, 2002

Columbia County Building Department
Post Office Box 1529
Lake City, Florida 32056

To Whom It May Concern:

As required by building code regulations for Columbia County in order that a building permit can be issued, the following well information is provided with regard to the above-referenced well:


Size of Pump Motor:	1-1/2 Horse Power
Size of Pressure Tank:	220 Gallon Equivalent
Cycle Stop Valve Used:	No

Should you require any additional information, please do not hesitate to contact us.


Respectfully,

CLYATT WELL DRILLING, INC.

K. Melaine "Red" Clyatt
President



Clyatt Well Drilling, Inc.
(Established in 1971)
POST OFFICE BOX 180
WORTHINGTON SPRINGS, FLORIDA 32697



Telephone Number (386)496-2488
FAX Number (386)496-4640

PUMP AND TANK SPECIFICATIONS FOR
STANDARD 4" RESIDENTIAL WELLS

PUMPS

1 Horse Power Submersible Pump
20 Gallons Per Minute
Voltage: 240
Phase: (Single) 1

1.5 Horse Power Submersible Pump
25 Gallons Per Minute
Voltage: 240
Phase: (Single) 1

TANK

WF-255 Captive Air Tank
Capacity 81 Gallons
Equivalent 220 Gallons
Draw Down 25 Gallons


INSTALLATION INSTRUCTIONS ROUGH OPENING

Be sure to Check your window series size for correct call-out size.

FLASHING & INSTALLATION

1. All series of windows rough openings will be call out with exception of series 4300. Series 4300 rough opening requires $\frac{1}{2}$ " added to width and height.
2. **SILL:** Cut weather resistant building material (minimum 6" wide) to fit horizontally immediately below the sill extending 6" past each side of rough opening. Apply sealant to top lip of flashing and fasten across top. Leave bottom of sill flashing loose for further wall treatment.
3. **INSTALL WINDOW:** Apply sealant around interior side of nailing fin and to outside joints at each corner of the window. Use shim blocks as necessary to sit window level and square. Fasten with 1 $\frac{1}{2}$ " galvanized roofing nails or #8 sheet metal screws no less than 3" from corners and maximum 12" apart. Fasteners must be driven straight into wall, not at angle. Do not use power nailers as they may damage and bow nailing fin. Test opening each during process.
4. **JAMBS:** Next, cut and apply sealant to edge of 6" weatherproof building material and fasten over window jamb nailing s. Jamb flashing should extend six inches above head and below sill.
5. **HEAD:** Apply sealant and fasten 6" weatherproof building material over window head nailing fin and extending on each side 6" to cover jamb flashing.
6. **NAILING:** Nailing fin is not a water-moisture barrier.
7. **COOLING - HEATING:** Vents facing windows can cause excessive condensation to form.

FLASHING GUIDE



ATTENTION

Action Window Technology recognizes the California Association of Window Manufacturers (CAWM) Practice of Window Installation in Wood Frame Construction.

Proper flashing, or sealing, is necessary as a secondary barrier to stop water from entering between the window frame and rough opening. It is not Action Window Technology's responsibility to design or recommend a flashing system appropriate to each job condition.

The responsibility for properly installing a flashing system into a weather resistant barrier for the entire building is the responsibility of the General Contractor or his agent.

Action Window Technology guidelines do not supercede Federal, State or local codes.

CONSULT WITH LOCAL BUILDING CODES BEFORE INSTALLATION.

A

Summary of Products		
FL #	Model, Number or Name	Description
2896.1	SERIES 2900 F VINYL	BRICK MOLD
Limits of Use (See Other) Approved for use in HVHZ: Approved for use outside HVHZ: Impact Resistant: Design Pressure: +/- Other: SERIES 2900 F VINYL 44 X 72 R50		Certification Agency Certificate Installation Instructions <u>PTID 2896 R1 I 2900.pdf</u> Verified By:



ETC Laboratories

Measuring Up To Your Standards, And More

Corporate Office / Laboratories
297 Buell Road
Rochester, NY 14624-3102
Tel: (585) 328-7668
Fax: (585) 328-7777
<http://www.etclabs.com>

Insulating Glass Division
Jim Spetz Testing Laboratory
29633 Lakeland Blvd.
Wickliffe, OH 44092-2203
Tel: (440) 944-3665
Fax: (440) 944-3671

Fenestration Structural Test Report

Rendered To:

Action Window Technology, Inc.
1312 W. Crosby Road
Carrollton, TX 75006

Series/Model

2900F Single Hung Oriel (O/X)

Report Number

ETC-04-809-15249.A

Accreditations ~ Recognitions

AAMA - WDMA - NFRC - SIGMA - NAMI - IGCC - SGCC - Dade County - TDI
Laboratories and Offices in New York and Ohio

NOTE: For security purposes, the original of this report has been printed on special paper with a red bar running down the entire right margin

Report Number: ETC-04-809-15249.A
Test Start Date: 03/16/04
Test Finish Date: 03/16/04
Report Date: 03/24/04
Expiration Date: 03/24/08

Fenestration Structural Test Report
Rendered To:

Action Windoor Technology, Inc.
1312 W. Crosby Road
Carrollton, TX 75006

Series/Model
2900F Single Hung Oriel (O/X)

Description: The product tested was a vinyl Single Hung window. The test specimen was glazed with 5/8-inch thick insulating glass units constructed with annealed glass, utilizing double strength glass in the fixed light and single strength glass in the operable sash. The frame size was 44 inches wide by 72 inches high by 2-13/16 inches deep. See Appendix A.

Test Specification: ANSI/AAMA/NWDA 101/I.S.2

Summary of Results

Overall Design Pressure	50.0 psf
Air Leakage Rate	0.15 scfm/ft ²
Maximum Water Pressure Achieved	7.50 psf
Maximum Structural Pressure Achieved	75.0 psf
Forced Entry Resistance – (ASTM)	Grade 10
Product Designation	H-R50 44 x 72

Specifications: The test specimen was evaluated in accordance with ANSI/AAMA/NWDA 101/I.S.2 "Voluntary Specification for Aluminum, Vinyl and Wood Windows and Glass Doors", Sections 1, 2 and 4 only. All performance specifications in this standard shall be met for full compliance to the standard and for product certification, labeling or represented as conforming to this standard.

Referenced Test Reports: ETC-03-034-14092.0, ETC-03-034-14918.0

Note – The test data in any section below with an "RTR" comment have not been obtained from this specimen but from the Referenced Test Report with a specimen of the same or larger size and identical construction.

Design Pressure (DP): The product tested herein has been first evaluated to the Gateway pressure in the referenced specification for the performance class rating achieved.

Gateway Performance Tests

<u>Specification Paragraph</u>	<u>Title of Test</u>	<u>Results</u>	<u>Allowed</u>
2.1.2	<u>Air Infiltration – ASTM E283</u> Test Pressure - 1.57 psf The tested specimen exceeds the performance levels specified in ANSI/AAMA/NWDA 101/I.S.2 for air infiltration.	RTR 0.15 scfm/ft ²	0.30 scfm/ft ²
2.1.3	<u>Water Resistance – ASTM E547</u> 5 gal/hr-ft ² – 4 Test cycles – 24 Minutes Design Pressure - 15.0 psf Test Pressure – 2.86 psf With and Without Screen	RTR Pass	 No Leakage
2.1.4.2	<u>Uniform Structural Load – ASTM E330</u> Design Pressure - 15.0 psf Test Pressure Positive Load – 22.5 psf (150% x DP) Negative Load – 22.5 psf (150% x DP) Note: Measurement taken after load from center of the meeting rail	 0.002 in. 0.017 in.	 0.160 in. 0.160 in.
2.1.7	<u>Corner Weld</u> Frame – 4 Corners Sashes – 4 Corners	RTR Pass Pass	 < 100% < 100%
2.1.8	<u>Forced Entry Resistance – ASTM F588</u> Lock/Tool Manipulation Tests A1 through A7 Lock/Tool Manipulation	Pass Pass Pass	No Entry No Entry No Entry
2.2.1.6.1	<u>Operating Force – No Standardized Method</u> Bottom Sash – Open/Close	14/12 lbf	30 lbf

Gateway Performance Tests

<u>Specification Paragraph</u>	<u>Title of Test</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.2	<u>Deglazing - ASTM E987</u>	RTR	
	Bottom Sash: Left Stile - 50 lbf	0.0%	<100%
	Right Stile - 50 lbf	0.0%	<100%
	Top Rail - 70 lbf	0.0%	<100%
	Bottom Rail - 70 lbf	0.0%	<100%

Optional Performance Tests

The manufacturer specified herein has successfully achieved all the required criteria in Section 2 of the referenced specification for the Gateway size of the achieved Performance Rating and has further successfully tested the product to higher performance levels as indicated below.

Design Pressure (DP): The product tested herein has been additionally evaluated to the Design Pressure referenced below.

<u>Specification Paragraph</u>	<u>Title of Test</u>	<u>Results</u>	<u>Allowed</u>
4.3	<u>Water Resistance - ASTM E547</u>	RTR	
	5 gal/hr-ft ² - 4 Test cycles - 24 Minutes		
	Design Pressure - 50.0 psf		
	Test Pressure - 7.5 psf (15% x DP)		
	With and Without Screen	Pass	No Leakage
4.4	<u>Uniform Structural Load - ASTM E330</u>		
	Design Pressure - 50.0 psf		
	Test Pressure		
	Positive Load - 75.0 psf (150% x DP)	0.111 in.	0.160 in.
	Negative Load - 75.0 psf (150% x DP)	0.102 in.	0.160 in.
	Note: Measurement taken after load from center of the meeting rail		

#

Summary of Products

FL #	Model, Number or Name	Description
7474.1	Series 3180 Vinyl Fixed Window	Series 3180 Vinyl Fixed Window O Configuration Up to 48" x 72"
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +50 /-50 Other:		Certification Agency Certificate FL7474_R0_C_CAC_NI006586.pdf Installation Instructions FL7474_R0_II_FL_00013A.pdf Verified By: Luis R. Lomas P.E. FL 62514


CERTIFIED TESTING LABORATORIES

Architectural Division • 7252 Narcoossee Rd. • Orlando, FL 32822

(407) 384-7744 • Fax (407) 384-7751

Web Site: www.ctlarch.com

E-mail: ctlarch.com



Report Number: CTLA-1038W-2-AWT
Report Date: March 4, 2003

STRUCTURAL PERFORMANCE TEST REPORT

Client: ACTION WINDOOR TECHNOLOGY INC.
1312 W. CROSBY ROAD
CARROLLTON, TX 75006

Product Type and Series: AWT Series 3180 Vinyl Fin Frame Picture Window F-R80 (48"x 72")

Test Specifications: AAMA/NWWDA 101/I.S.2-97 "Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors"

Frame: Vinyl Fin frame measured 47.50" wide x 71.50" high overall. Mitered corner weld construction. Clear lite measured 44.50" wide x 68.50" high.

Ventilator: N/A

Weather Stripping: N/A

Hardware & Location: N/A

Glazing: 3/4" insulated annealed glass consisting of .1875" glass .375" air space with swiggle .1875" glass. Sash exterior glazed. Fixed lite interior glazed adhesive foam strip backbedding and vinyl snap in glazing bead.

Sealant: A silicone type sealant was used at frame corners and to seal specimen to test buck.

Weep System: N/A

Muntins: N/A

Reinforcement: N/A

Additional Description: N/A

Screen: N/A

Installation: Twenty-eight (28) 1.75" roofing nails were used to secure the specimen to the wood test buck. Six (6) were located in head and sill measuring 5.50", 13", 20.625", 28.25", 35.875" and 43.50" from left jamb. Eight (8) were located in each jamb measuring 5.50", 14", 22.75", 31.50", 40", 48.75", 57.75" and 66.50" from sill.

Surface Finish: White Vinyl

Comment: Nominal 2 mil polyethylene film was used to seal against air leakage during structural loads. The film was used in a manner that did not influence the test results.

Performance Test Results

<u>Paragraph No</u>	<u>Title of Test</u>	<u>Method</u>	<u>Measured</u>	<u>Allowed</u>
2.1.2	Air Infiltration @1.57 psf	ASTM E283-91	.02 cfm/ft ²	.34 cfm/ft ²
The tested specimen meets or exceeds the performance levels specified in AAMA/NWWDA 101/I.S.2-97. Results recorded in two (2) decimals at the clients request.				
2.1.3	Water Resistance @ 5.0 gph/ft ²	ASTM E547-93 Four (4) five (5) minute cycles	No Entry	No Entry
	WTP= 13.5 psf	ASTM E331-93 Fifteen (15) minute duration	No Entry	No Entry
2.1.4.2	Uniform Load Structural Permanent Deformation @ 120 psf positive @ 120 psf negative	ASTM E330-90 Ten (10) second load	Neg. Neg.	.192" .192"
2.1.7	Welded Corner Test	AAMA/NWWDA 101/ IS2-97	Passed	
2.1.8	Forced Entry Resistance Test D Window Assemblies This specimen as tested complies to a grade 10-T ¹ =5 minutes Tools used: A spatula (10.1.1.1) and a piece of stiff wire (10.1.3.2)	ASTM F 588-97	Passed	

Test Date January 28, 2003


Test Completion Date: January 28, 2003

Remarks: Detailed drawings were available for laboratory records and comparison to the test specimen at the time of this report. A copy of this report along with representative sections of the test specimen will be retained by CTL for a period of four (4) years. The results obtained apply only to the specimen tested.

This test report does not constitute certification of this product, but only that the above test results were obtained using the designated test methods and they indicate compliance with the performance requirements (paragraphs as listed) of the above referenced specifications.

Certified Testing Laboratories assumes that all information provided by the client is accurate and that the physical and chemical properties of the components are as stated by the manufacturer.

Certified Testing Laboratories, Inc.




James W. Blakely
Vice President
Architectural Division

cc: Action Windoor Technology Inc. (3)
File (1)

★

NAMI NOTICE OF PRODUCT LINE CERTIFICATION



Certification No.: NI006110-Page 1
Date: 07/23/05
Revision Date: _____
Certification Program: Structural
Company: Masonite International
Code: M-703-1

The "Notice of Product Line Certification" is valid only when Administrator's Seal is applied to the upper left hand portion of this form and a certification label is applied to the product. This certification seal represents product conformity to the applicable specification and that all certification criteria has been satisfied.

The products and systems listed below are approved for listing in the Directory of Certified Products at www.NAMICertification.com. Please review, and advise NAMI immediately if data, as shown requires corrections.

Company: Masonite International Corporation
1955 Powis Road
West Chicago, IL 60185

Product Line: Masonite Wood-Edge Steel Side-Hinged Door Units

Test Report: NCTL-210-2929-1/210-2930-1/210-2930-7/210-2930-7/210-3121-1/
210-3123-1/210-3125-1/CTLA-919W

Section 1: General Description of the Products and Systems under this Certification

- 1.1 **Frame:** The frame jambs consist of finger jointed pine with all corners coped, butted, and sealed using three 2" long wire staples (.04375").
- 1.2 **Mullion Construction:** Where used, each mullion constructed of laminated lumber with a pine cap and attached to the header and threshold with three #10 x 3" Philips Flat Head Wood Screws.
- 1.3 **Glazing:** Where used, the overall insulated glass was glazed into a rigid plastic lip-lite frame. Consisted of symmetric monolithic insulated glass with 3mm (0.118) tempered glass.
- 1.4 **Door Leaf Construction:** Each door leaf was constructed from 0.017"(6'8" height) or 0.020"(8'0" height) thick galvanized steel facings.

Section 2: Registered Suppliers

- | | | |
|------------|--------------------|----------------------------------|
| 2.1 | Door Lites: | ODL, Specialty or Trinity |
| 2.2 | Astragal: | Endura Ultimate |

Section 3: Additional Supportive Test or Acceptance Data Provided with Certification Documentation included:

- 3.1 Miami-Dade Building Code Compliance Notice of Acceptance for Lite Frame Material, NOA#02-0429.11; #02-1216.06 and #03-0303.07.**
- 3.2 Surface Burning Characteristics for Foam Filled Door performed by Omega Point Laboratories to ASTM E84-98, "Standard Test Method for Surface Burning Characteristics of Building Materials-Report No. 15977-104313.**
- 3.3 ASTM E1300 Glass Load Resistance Report provided by National Certified Testing Laboratories NCTL-110-9735-1.**
- 3.4 Anchor Calculations for:
Anchor Performance Calculation Report-Performed by Harold E. Rupp, P.E. (Florida No. 15935.)**

See additional Pages of Certification for Certified Product Line Matrix(s) and Installation Details. If you have any questions regarding this certification, please contact NAMI at (757)594-8658.

NOTICE OF PRODUCT CERTIFICATION

Company: Masonite International Corporation
1955 Powis Road
West Chicago, IL 60185

Certification No.: NI006110-Page 3
Certification Date: 07/23/2005
Expiration Date: 12/31/2008

Product: Wood-Edge Opaque Inswing or Outswing Door w/ and w/o Non-Impact Rated Sidelites (w/Wood Frame unless noted)
Specifications Tested To: PA 201-94/202-94/203-94

The "Notice of Product Certification" is only valid if the NAMI Certification Label has been applied to the product as described within this document. The certification label represents product conformity to the applicable specification and that all certification criteria has been satisfied. This product has been approved for listing within NAMI's Certified Product Listing at www.Namincertification.com. NAMI's Certification Program is accredited by The American National Standards Institute (ANSI).

Configuration	Inswing or Outswing	Glazed or Opaque	Maximum Size	Design Pressure Pos/Neg	Missile Impact Rated	Test Report Number Drawing Number & Comments
X Single	I/S	Opaque	3'0" x 6'8"	+76/-76	Yes	NCTL-210-2929-1 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
X Single	O/S	Opaque	3'0" x 6'8"	+76/-76	Yes	NCTL-210-2929-1 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
XX Double	I/S	Opaque	6'0" x 6'8"	+55/-55	Yes	NCTL-210-2930-1 Maximum Panel Size: 3'0" x 6'8"/Sidelite: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
XX Double	O/S	Opaque	6'0" x 6'8"	+55/-55	Yes	NCTL-210-2930-1 Maximum Panel Size: 3'0" x 6'8"/Sidelite: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
XO/OX Single w/Sidelite	I/S	Opaque Door Glazed Sidelite	6'0" x 6'8"	+55/-55	Door-Yes Sidelite-No	NCTL-210-2930-1 Maximum Panel Size: 3'0" x 6'8"/Sidelite: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
XO/OX Single w/Sidelites	O/S	Opaque Door Glazed Sidelite	6'0" x 6'8"	+55/-55	Door-Yes Sidelite-No	NCTL-210-2930-1 Maximum Panel Size: 3'0" x 6'8"/Sidelite: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
OXO Single w/Sidelites	I/S	Opaque Door Glazed Sidelites	9'0" x 6'8"	+55/-55	Door-Yes Sidelites-No	NCTL-210-2930-1 Maximum Panel Size: 3'0" x 6'8"/Sidelite: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
OXO Single w/Sidelites	O/S	Opaque Door Glazed Sidelites	9'0" x 6'8"	+55/-55	Door-Yes Sidelites-No	NCTL-210-2930-1 Maximum Panel Size: 3'0" x 6'8"/Sidelite: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
OXOX Double w/Sidelites	I/S	Opaque Doors Glazed Sidelites	12'4" x 6'8"	+55/-55	Doors-Yes Sidelites-No	NCTL-210-2930-1 Maximum Panel Size: 3'0" x 6'8"/Sidelite: 3'0" x 6'8" Installation Drawings-MA-FL0128-05
OXOX Double w/Sidelites	O/S	Opaque Doors Glazed Sidelites	12'4" x 6'8"	+55/-55	Doors-Yes Sidelites-No	NCTL-210-2930-1 Maximum Panel Size: 3'0" x 6'8"/Sidelite: 3'0" x 6'8" Installation Drawings-MA-FL0128-05

National Accreditation & Management Institute, Inc./11870 Merchants Walk Suite 202/Newport News, VA 23606
Tel-757.594.8658/Fax-757.594.8659

NAMI AUTHORIZED SIGNATURE:

NOTICE OF PRODUCT CERTIFICATION

Company: Masonite International Corporation
1955 Powis Road
West Chicago, IL 60185

Certification No.: NI006110-Page 4
Certification Date: 07/23/2005
Expiration Date: 12/31/2008

Product: Wood-Edge Steel Opaque Inswing or Outswing Door w/ and w/o Non-Impact Rated Sidelites (w/Wood Frame unless noted)
Specifications Tested To: PA201-94/202-94/203-94

The "Notice of Product Certification" is only valid if the NAMI Certification Label has been applied to the product as described within this document. The certification label represents product conformity to the applicable specification and that all certification criteria has been satisfied. This product has been approved for listing within NAMI's Certified Product Listing at www.Namincertification.com. NAMI's Certification Program is accredited by The American National Standards Institute (ANSI).

Configuration	Inswing or Outswing	Glazed or Opaque	Maximum Size	Design Pressure Pos/Neg	Missile Impact Rated	Test Report Number Drawing Number & Comments
X Single	I/S	Opaque	3'0" x 8'0"	+70/-70	Yes	NCTL-210-3121-1/CTLA919W Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
X Single	O/S	Opaque	3'0" x 8'0"	+70/-70	Yes	NCTL-210-3121-1/CTLA919W Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
XX Double	I/S	Opaque	6'0" x 8'0"	+45/-50	Yes	NCTL-210-3123-1 Maximum Panel Size: 3'0" x 8'0"/Sidelite: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
XX Double	O/S	Opaque	6'0" x 8'0"	+50/-45	Yes	NCTL-210-3123-1 Maximum Panel Size: 3'0" x 8'0"/Sidelite: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
XO/OX Single w/Sidelite	I/S	Opaque Door Glazed Sidelite	6'0" x 8'0"	+45/-50	Door-Yes Sidelite-No	NCTL-210-3123-1 Maximum Panel Size: 3'0" x 8'0"/Sidelite: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
XO/OX Single w/Sidelites	O/S	Opaque Door Glazed Sidelite	6'0" x 8'0"	+50/-45	Door-Yes Sidelite-No	NCTL-210-3123-1 Maximum Panel Size: 3'0" x 8'0"/Sidelite: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
OXO Single w/Sidelites	I/S	Opaque Door Glazed Sidelites	9'0" x 8'0"	+45/-50	Door-Yes Sidelites-No	NCTL-210-3123-1 Maximum Panel Size: 3'0" x 8'0"/Sidelite: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
OXO Single w/Sidelites	O/S	Opaque Door Glazed Sidelites	9'0" x 8'0"	+50/-45	Door-Yes Sidelites-No	NCTL-210-3123-1 Maximum Panel Size: 3'0" x 8'0"/Sidelite: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
OXXO Double w/Sidelites	I/S	Opaque Doors Glazed Sidelites	12'4" x 8'0"	+45/-50	Doors-Yes Sidelites-No	NCTL-210-3123-1 Maximum Panel Size: 3'0" x 8'0"/Sidelite: 3'0" x 8'0" Installation Drawings-MA-FL0129-05
OXXO Double w/Sidelites	O/S	Opaque Doors Glazed Sidelites	12'4" x 8'0"	+50/-45	Doors-Yes Sidelites-No	NCTL-210-3123-1 Maximum Panel Size: 3'0" x 8'0"/Sidelite: 3'0" x 8'0" Installation Drawings-MA-FL0129-05

National Accreditation & Management Institute, Inc./11870 Merchants Walk Suite 202/Newport News, VA 23606
Tel-757.594.8658/Fax-757.594.8659

NAMI AUTHORIZED SIGNATURE:

NOTICE OF PRODUCT CERTIFICATION

Company: Masonite International Corporation
1955 Powis Road
West Chicago, IL 60185

Certification No.: NI006110-Page 5
Certification Date: 07/23/2005
Expiration Date: 12/31/2008

Product: Wood-Edge Steel Glazed Inswing or Outswing Door w/ and w/o Non-Impact Rated Sidelites (w/Wood Frame unless noted)
Specifications Tested To: PA 202-94

The "Notice of Product Certification" is only valid if the NAMI Certification Label has been applied to the product as described within this document. The certification label represents product conformity to the applicable specification and that all certification criteria has been satisfied. This product has been approved for listing within NAMI's Certified Product Listing at www.Namincertification.com. NAMI's Certification Program is accredited by The American National Standards Institute (ANSI).

Configuration	Inswing or Outswing	Glazed or Opaque	Maximum Size	Design Pressure Pos/Neg	Missile Impact Rated	Test Report Number Drawing Number & Comments
X Single	I/S	Glazed	3'0" x 6'8"	+50.5/-50.5	No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
X Single	O/S	Glazed	3'0" x 6'8"	+50.5/-50.5	No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
XX Double	I/S	Glazed	6'0" x 6'8"	+50.5/-50.5	No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
XX Double	O/S	Glazed	6'0" x 6'8"	+50.5/-50.5	No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
XO/OX Single w/Sidelite	I/S	Glazed Door Glazed Sidelite	6'0" x 6'8"	+50.5/-50.5	Door-No Sidelite-No	NCTL-210-2930-7 MA-WL0115/16/17/18/19/20/21-02 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
XO/OX Single w/Sidelites	O/S	Glazed Door Glazed Sidelite	6'0" x 6'8"	+50.5/-50.5	Door-No Sidelite-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
OXO Single w/Sidelites	I/S	Glazed Door Glazed Sidelites	9'0" x 6'8"	+50.5/-50.5	Door-No Sidelites-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
OXO Single w/Sidelites	O/S	Glazed Door Glazed Sidelites	9'0" x 6'8"	+50.5/-50.5	Door-No Sidelites-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
OXOX Double w/Sidelites	I/S	Glazed Doors Glazed Sidelites	12'6" x 6'8"	+50.5/-50.5	Doors-No Sidelites-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
OXOX Double w/Sidelites	O/S	Glazed Doors Glazed Sidelites	12'6" x 6'8"	+50.5/-50.5	Doors-No Sidelites-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05

National Accreditation & Management Institute, Inc./11870 Merchants Walk Suite 202/Newport News, VA 23606

Tel-757.594.8658/Fax-757.594.8659

NAMI AUTHORIZED SIGNATURE: 

NOTICE OF PRODUCT CERTIFICATION

Company: Masonite International Corporation
1955 Powis Road
West Chicago, IL 60185

Certification No.: NI006110-Page 5
Certification Date: 07/23/2005
Expiration Date: 12/31/2008

Product: Wood-Edge Steel Glazed Inswing or Outswing Door w/ and w/o Non-Impact Rated Sidelites (w/Wood Frame unless noted)
Specifications Tested To: PA 202-94

The "Notice of Product Certification" is only valid if the NAMI Certification Label has been applied to the product as described within this document. The certification label represents product conformity to the applicable specification and that all certification criteria has been satisfied. This product has been approved for listing within NAMI's Certified Product Listing at www.NamIcertification.com. NAMI's Certification Program is accredited by The American National Standards Institute (ANSI).

Configuration	Inswing or Outswing	Glazed or Opaque	Maximum Size	Design Pressure Pos/Neg	Missile Impact Rated	Test Report Number Drawing Number & Comments
X Single	I/S	Glazed	3'0" x 6'8"	+50.5/-50.5	No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
X Single	O/S	Glazed	3'0" x 6'8"	+50.5/-50.5	No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
XX Double	I/S	Glazed	6'0" x 6'8"	+50.5/-50.5	No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
XX Double	O/S	Glazed	6'0" x 6'8"	+50.5/-50.5	No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
XO/OX Single w/Sidelite	I/S	Glazed Door Glazed Sidelite	6'0" x 6'8"	+50.5/-50.5	Door-No Sidelite-No	NCTL-210-2930-7 MA-WL0115/16/17/18/19/20/21-02 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
XO/OX Single w/Sidelites	O/S	Glazed Door Glazed Sidelite	6'0" x 6'8"	+50.5/-50.5	Door-No Sidelite-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
OXO Single w/Sidelites	I/S	Glazed Door Glazed Sidelites	9'0" x 6'8"	+50.5/-50.5	Door-No Sidelites-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
OXO Single w/Sidelites	O/S	Glazed Door Glazed Sidelites	9'0" x 6'8"	+50.5/-50.5	Door-No Sidelites-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
OXOXO Double w/Sidelites	I/S	Glazed Doors Glazed Sidelites	12'6" x 6'8"	+50.5/-50.5	Doors-No Sidelites-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05
OXOXO Double w/Sidelites	O/S	Glazed Doors Glazed Sidelites	12'6" x 6'8"	+50.5/-50.5	Doors-No Sidelites-No	NCTL-210-2930-7 Maximum Panel Size: 3'0" x 6'8" Installation Drawings-MA-FL0130-05

National Accreditation & Management Institute, Inc./11870 Merchants Walk Suite 202/Newport News, VA 23606

Tel-757.594.8658/Fax-757.594.8659

NAMI AUTHORIZED SIGNATURE:

NOTICE OF PRODUCT CERTIFICATION

Company: Masonite International Corporation

1955 Powis Road

West Chicago, IL 60185

Certification No.: NI006110-Page 6

Certification Date: 07/23/2005

Expiration Date: 12/31/2008

Product:

Wood-Edge Steel Glazed Inswing or Outswing Door w/ and w/o Non-Impact Rated Sidelites (w/Wood Frame unless noted)
Specifications Tested To: PA 202-94

The "Notice of Product Certification" is only valid if the NAMI Certification Label has been applied to the product as described within this document. The certification label represents product conformity to the applicable specification and that all certification criteria has been satisfied. This product has been approved for listing within NAMI's Certified Product Listing at www.Namincertification.com. NAMI's Certification Program is accredited by The American National Standards Institute (ANSI).

Configuration	Inswing or Outswing	Glazed or Opaque	Maximum Size	Design Pressure Pos/Neg	Missile Impact Rated	Test Report Number Drawing Number & Comments
X Single	I/S	Glazed	3'0" x 8'0"	+40/-45	No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
X Single	O/S	Glazed	3'0" x 8'0"	+45/-40	No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
XX Double	I/S	Glazed	6'0" x 8'0"	+40/-45	No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
XX Double	O/S	Glazed	6'0" x 8'0"	+45/-40	No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
XO/OX Single w/Sidelite	I/S	Glazed Door Glazed Sidelite	6'0" x 8'0"	+40/-45	Door-No Sidelite-No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
XO/OX Single w/Sidelites	O/S	Glazed Door Glazed Sidelite	6'0" x 8'0"	+45/-40	Door-No Sidelite-No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
OXO Single w/Sidelites	I/S	Glazed Door Glazed Sidelites	9'0" x 8'0"	+40/-45	Door-No Sidelites-No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
OXO Single w/Sidelites	O/S	Glazed Door Glazed Sidelites	9'0" x 8'0"	+45/-40	Door-No Sidelites-No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
OXXO Double w/Sidelites	I/S	Glazed Doors Glazed Sidelites	12'6" x 8'0"	+40/-45	Doors-No Sidelites-No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05
OXXO Double w/Sidelites	O/S	Glazed Doors Glazed Sidelites	12'6" x 8'0"	+45/-40	Doors-No Sidelites-No	NCTL-210-3125-1 Maximum Panel Size: 3'0" x 8'0" Installation Drawings-MA-FL0131-05

National Accreditation & Management Institute, Inc./11870 Merchants Walk Suite 202/Newport News, VA 23606
Tel-757.594.8658/Fax-757.594.8659

NAMI AUTHORIZED SIGNATURE:



SITE NAVIGATION

PRODUCT APPROVAL

Product Type Detail

Overview Product Search Organization Search Product Application

User: Public User - Not Associated with Organization -

[Need Help ?](#)

Application #: FL4904
 Date Submitted: 07/25/2005
 Code Version: 2004

Product Manufacturer: Masonite International
 Address/Phone/email: One North Dale Mabry
 Suite 950
 Tampa, FL 33609
 (615) 441-4258

Category: Exterior Doors

Subcategory: Swinging

Evaluation Method: Certification Mark or Listing

Referenced Standards from the Florida Building Code:	Section	Standard	Year
		TAS 201	1994
		TAS 202	1994
		TAS 203	1994
		ASTM E1300	1998
		ASTM E1300	2002

Section
 2612 HVHZ
 P1

Certification Agency: National Accreditation & Management Institute,

Quality Assurance Entity:

Validation Entity:

Authorized Signature: Steve Schreiber
 sschreiber@masonite.com



Evaluation/Test Reports Uploaded:
 Installation Documents Uploaded:

[PTID 4904 I Install 68 WE
 Glazed.pdf](#)
[PTID 4904 I Install 68 WE
 Opaque.pdf](#)
[PTID 4904 I Install 80 WE
 Glazed.pdf](#)
[PTID 4904 I Install 80 WE
 Opaque.pdf](#)

Product Approval Method:

Method 1 Option A

Application Status:

Approved

Date Validated:

09/27/2005

Date Approved:

10/06/2005

Date Certified to the 2004 Code:

Page:

Page 1 / 1

App/Seq #	Product Model # or Name	Model Description	Limits of Use
4904.1	Wood-edge Steel Side-Hinged Door Units	6'-8" Opaque I/S and O/S Single Door	Evaluated for use in locations adhering to the Florida Building Code including the High Velocity Hurricane Zone, and where pressure requirements as determined by ASCE 7, Minimum Design Loads for Buildings and Other Structures, does not exceed the design pressures listed. 3'-0" x 6'-8" max nominal size Max DP = +/- 76.0. When large missile impact resistance is required, hurricane protective system is NOT required. See installation drawing DWG-MA-FL0128-05 for additional information.
4904.2	Wood-edge Steel Side-Hinged Door Units	8'-0" Opaque I/S and O/S Single Door	Evaluated for use in locations adhering to the Florida Building Code including the High Velocity Hurricane Zone, and where pressure requirements as determined by ASCE 7, Minimum Design Loads for Buildings and Other Structures, does not exceed the design pressures listed. 3'-0" x 8'-

			0" max nominal size Max DP = +/- 70.0. When large missile impact resistance is required, hurricane protective system is NOT required. See installation drawing DWG-MA-FL0129-05 for additional information.
4904.3	Wood-edge Steel Side-Hinged Door Units	6'-8" Opaque I/S and O/S Door w/ or w/o Sidelites	<p>Evaluated for use in locations adhering to the Florida Building Code including the High Velocity Hurricane Zone, and where pressure requirements as determined by ASCE 7, Minimum Design Loads for Buildings and Other Structures, does not exceed the design pressures listed. 12'-0" x 6'-8" max nominal size. Max DP = +/- 55.0. When large missile impact resistance is required, hurricane protective system is NOT required on opaque panels, but is required on glazed panels. See installation drawing DWG-MA-FL0128-05 for additional information.</p>
4904.4	Wood-edge Steel Side-Hinged Door Units	8'-0" Opaque I/S Door w/ or w/o Sidelites	<p>Evaluated for use in locations adhering to the Florida Building Code including the High Velocity Hurricane Zone, and where pressure requirements as determined by ASCE 7, Minimum Design Loads for Buildings and Other Structures, does not exceed the design pressures listed. 12'-0" x 8'-0" max nominal size. Max DP = + 45.0 / -50.0. When large missile impact resistance is required, hurricane protective system is NOT required on opaque panels, but is required on glazed panels. See installation drawing DWG-MA-FL0129-05 for additional information.</p>
			Evaluated for use in

4904.5	Wood-edge Steel Side-Hinged Door Units	8'-0" Opaque O/S w/ or w/o Sidelites	locations adhering to the Florida Building Code including the High Velocity Hurricane Zone, and where pressure requirements as determined by ASCE 7, Minimum Design Loads for Buildings and Other Structures, does not exceed the design pressures listed. 12'-0" x 8'-0" max nominal size. Max DP = + 50.0 / -45.0. When large missile impact resistance is required, hurricane protective system is NOT required on opaque panels, but is required on glazed panels. See installation drawing DWG-MA-FL0129-05 for additional information.
4904.6	Wood-edge Steel Side-Hinged Door Units	6'-8" Glazed I/S and O/S Door w/ or w/o Sidelites	Evaluated for use in locations adhering to the Florida Building Code including the High Velocity Hurricane Zone, and where pressure requirements as determined by ASCE 7, Minimum Design Loads for Buildings and Other Structures, does not exceed the design pressures listed. 12'-0" x 6'-8" max nominal size. Max DP = +/- 50.5. When large missile impact resistance is required, hurricane protective system is required. See installation drawing DWG-MA-FL0130-05 for additional information.
4904.7	Wood-edge Steel Side-Hinged Door Units	8'-0" Glazed I/S Door w/ or w/o Sidelites	Evaluated for use in locations adhering to the Florida Building Code including the High Velocity Hurricane Zone, and where pressure requirements as determined by ASCE 7, Minimum Design Loads for Buildings and Other Structures, does not exceed the design pressures listed 12'-0" x 8'-0" max nominal size

			<p>Max DP = +40.0 / -45.0. When large missile impact resistance is required, hurricane protective system is required. See installation drawing DWG-MA-FL0131-05 for additional information.</p>
4904 8	Wood-edge Steel Side-Hinged Door Units	8'-0" Glazed O/S Door w/ or w/o Sidelites	<p>Evaluated for use in locations adhering to the Florida Building Code including the High Velocity Hurricane Zone, and where pressure requirements as determined by ASCE 7, Minimum Design Loads for Buildings and Other Structures, does not exceed the design pressures listed. 12'-0" x 8'-0" max nominal size. Max DP = + 45.0 / -40.0. When large missile impact resistance is required, hurricane protective system is required. See installation drawing DWG-MA-FL0131-05 for additional information.</p>

Next



Copyright and Disclaimer: ©2000 The State of Florida. All rights reserved

my


**SIDE-HINGED WOOD-EDGE STEEL DOOR UNIT
6-8" GLAZED DOUBLE DOOR WITH / WITHOUT SIDELITES**

1. EVALUATED FOR USE IN LOCATIONS ADHERING TO THE FLORIDA BUILDING CODE AND WHERE PRESSURE REQUIREMENTS AS DETERMINED BY ASCE 7, MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES, DOES NOT EXCEED THE DESIGN PRESSURES LISTED
2. HURRICANE PROTECTIVE SYSTEM (SHUTTERS) IS REQUIRED
3. POLYURETHANE CORE FLAME SPREAD INDEX OF 50 AND SMOKE DEVELOPED INDEX OF 80 PER ASTM E84
4. PLASTICS TESTING OF LIFE FLAME MATERIAL:

TEST DESCRIPTION	DESIGNATION	RESULT
SELF IGNITION TEMP	ASTM D1929	880 F > 650
RATE OF BURNING	ASTM D635	1.10 IN/MIN
SMOKE DENSITY	ASTM D2943	66.6%
TENSILE STRENGTH*	ASTM D638	7.48K LBF

* COMPARATIVE TENSILE STRENGTH AFTER WEATHERING 4500 HOURS XENON ARC METHOD 1


TEST DESCRIPTION	DESIGNATION	RESULT
SELF IGNITION TEMP	ASTM D19129	680 °F to 650 °F
RATE OF BURNING	ASTM D635	1.10 in/min
SMOKE DENSITY	ASTM D2843	69.62
TENSILE STRENGTH*	ASTM D638	-7.48% DIFF



DOUBLE INSWING UNIT W/SIDELITES

Addendum to NIA

Certification No: NI006110
 Prepared By: [Signature]
 Date Prepared: 8/10/05



SINGLE DOOR UNIT DOUBLE DOOR UNIT

SINGLE DOOR UNIT SINGLE DOOR UNIT
WITH SIDELITE WITH SIDELITE

SINGLE DOOR UNIT W/SIDELITES


DOUBLE DOOR UNIT W/SIDELITES

TABLE OF CONTENTS	
SHEET #	DESCRIPTION
1	TYPICAL ELEVATIONS & GENERAL NOTES
2	ANCHORING LOCATIONS & DETAILS
3	ANCHORING LOCATIONS & DETAILS

CONFIG	MAX WIDTH	DESIGN PRESSURE RATING		WHERE WATER INFILTRATION PERFORMANCE IS REQUIRED TO BE 15% OF DESIGN PRESSURE
		INSURING	OUTSURING	
X	3/5"	+50.5	+50.5	+50.5
XX	7/8"	+50.5	-50.5	+50.5
XX	7/8"	+50.5	+50.5	+50.5
OX or XO	7/5"	+50.5	-50.5	+50.5
OXO	11/25"	+50.5	+50.5	+50.5
OXOX	14/9"	+50.5	-50.5	+50.5
		+50.5	+50.5	+50.5


WHERE WATER INFILTRATION PERFORMANCE IS REQUIRED TO BE 15% OF DESIGN PRESSURE	2 MECHANICAL
INSWING	

DATE: 7/11/05		PRODUCT:	
SCALE: N.T.S.		EXTERIOR DOOR PRODUCT*	
DWG. BY: SMS		DOUBLE 6'8" GLAZED	
CHECK BY:		WOOD-EDGE STEEL DOOR	
DWG. NO. 44A-FLD110-05		PART OR ASSEMBLY:	
REVISION NO.:		TYPICAL ELEVATIONS	
		& GENERAL NOTES	
NO.	DATE	BY	
REVISIONS			



INSWING THRESHOLD

Certification No.: NT006110
 Printed By: _____
 Date Printed: 8/16/05

EXTERIOR  **INTERIOR**

TYPICAL GLAZING DETAIL


PAGE 2 of 3

MASONITE INTERNATIONAL CORP.
7300 REAMES RD.
CHARLOTTE, NC 28216

PRODUCT: EXTERIOR DOOR PRODUCT
PART OR ASSEMBLY: 6'-8" WOOD-DOOR STEEL GLAZED DOUBLE DOOR UNIT
ANCHORING LOCATIONS & DETAILS

NO.	DATE	REVISIONS
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		

DATE: 7/11/05
SCALE: N.T.S.
DWG. BY: SWS
CHK. BY:
DRAWING NO.:
DWG-MA-FL0130-05
SHEET 3 OF 3




ATTACHMENT DETAIL

- ANCHOR ANALYSIS FOR LOADING CONDITIONS PREPARED, SIGNED AND SEALED BY HAROLD E. RUPP, PE (FLORIDA #15935) WITH THE LOWEST (LEAST) FASTENER RATING FROM THE DIFFERENT FASTENERS BEING CONSIDERED FOR USE. JAMB, HEAD, AND THRESHOLD FASTENERS ANALYZED FOR THIS UNIT INCLUDE #10 WOOD SCREWS OR 3/16" TAPCONS. A PHYSICAL SHIM MUST BE PLACED IN SHIM SPACE AT EACH ANCHOR LOCATION.
- THE WOOD SCREW SINGLE SHEAR DESIGN VALUES COME FROM ANSI/AF&PA NDA FOR SOUTHERN PINE LUMBER AND ACHIEVEMENT OF 1-1/2" MINIMUM EMBEDMENT. THE TAPCON MUST ACHIEVE MINIMUM EMBEDMENT OF 1-1/4".
- WOOD BUCKS BY OTHERS MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO STRUCTURE.
- MINIMUM DESIGN VALUE STRENGTH OF ANCHORS 171 LBS.

HARDWARE SCHEDULE

- KWIKSET OR SCHLEGE ANSI/BHMA GRADE 3 OR BETTER CYLINDRICAL AND DEADLOCK HARDWARE TO BE INSTALLED AT 5-1/2" CENTERLINE.
- 4" X 4" FULL MORTISE BUTT HINGES




Approval by: NT006110
Reviewed by: NT006110
Date: 7/11/05



SIDE-HINGED WOOD-EDGE STEEL DOOR UNIT
6'-8" DOUBLE DOOR WITH / WITHOUT SIDELITES

GENERAL NOTES

1. EVALUATED FOR USE IN LOCATIONS ADHERING TO THE FLORIDA BUILDING CODE AND WHERE PRESSURE REQUIREMENTS AS DETERMINED BY ASCE 7, MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES, DOES NOT EXCEED THE DESIGN PRESSURES LISTED
2. HURRICANE PROTECTIVE SYSTEM (SHUTTERS) IS NOT REQUIRED ON OPAQUE PANELS, BUT IS REQUIRED ON GLAZED SIDELITES
3. POLYURETHANE CORE FLAME SPREAD INDEX OF 50 AND SMOKE DEVELOPED INDEX OF 60 PER ASTM E84
4. PLASTICS TESTING OF LITE FRAME MATERIAL:
TEST DESCRIPTION DESIGNATION RESULT
SELF IGNITION TEMP ASTM D1828 680 °F > 650 °F
RATE OF BURNING ASTM D635 1.10 IN./MIN
SMOKE DENSITY ASTM D2843 68.6%
TENSILE STRENGTH* ASTM D638 -7.48% DIF
* COMPARATIVE TENSILE STRENGTH AFTER WEATHERING 4500 HOURS XENON ARC METHOD 1



DOUBLE INSULATING UNIT W/SIDELITES

Assembled by
Nicoletto
Date 11/10/05





TABLE OF CONTENTS	
SHEET #	DESCRIPTION
1	TYPICAL ELEVATIONS & GENERAL NOTES
2	ANCHORING LOCATIONS & DETAILS
3	ANCHORING LOCATIONS & DETAILS

DESIGN PRESSURE RATING		WHERE WATER INFILTRATION PERFORMANCE IS REQUIRED TO BE 15% OF DESIGN PRESSURE	
CONFIG	MAX WIDTH	INSULATING	OUTSWING
X	37.5"	+76.0 / -76.0	+19.0 / -19.0
XX	74"	+55.0 / -55.0	+55.0 / -55.0
OK or XO	75"	+55.0 / -55.0	+55.0 / -55.0
OXO	112.5"	+55.0 / -55.0	+55.0 / -55.0
OXOX	149"	+55.0 / -55.0	+55.0 / -55.0

DATE: 7/11/05	SCALE: N.T.S.	DRG. BY: SWS	CHECK BY:	DATE:
DWG. NO.: 05				
SHEET 1 OF 3				
PRODUCT:	"EXTERIOR DOOR PRODUCT"			
	DOUBLE 6'-8" OPAQUE WOOD-EDGE STEEL DOOR			
PART OR ASSEMBLY:	TYPICAL ELEVATIONS & GENERAL NOTES			
NO.	DATE	BY	REVISIONS	

MASONITE INTERNATIONAL CORP.
7300 REAMES RD.
CHARLOTTE, NC 28216





DATE:	7/11/05	NO.	DATE	REVISIONS
SCALE:	N=1'S.			
DRG. BY:	SMS			
CHEK. BY:				
DRAWING NO.:				
DMG-M4-FL0128-05				
SHEET	3	OF	3	

ITW Building Components Group, Inc.


1950 Marley Drive Haines City, FL 33844
Florida Engineering Certificate of Authorization Number: 567
Florida Certificate of Product Approval # FL1999
Page 1 of 1 Document ID: IT4U8228Z0114080828

Truss Fabricator: Anderson Truss Company
Job Identification: 7-056--Stanley Crawford Construc HOLTON -- , **
Truss Count: 46
Model Code: Florida Building Code 2004 and 2006 Supplement
Truss Criteria: ANSI/TPI-2002(STD)/FBC
Engineering Software: Alpine Software, Version 7.24.
Structural Engineer of Record: The identity of the structural EOR did not exist as of
Address: the seal date per section 61G15-31.003(5a) of the FAC
Minimum Design Loads: Roof - 40.0 PSF @ 1.25 Duration
Floor - N/A
Wind - 110 MPH ASCE 7-02 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR8228

Details: BRCLBSUB-CNBRGBLK-A11015EE-GBLLETIN-MAX DEAD LOAD-PIGBACKA-PIGBACKB-



Seal Date: 02/14/2007

-Truss Design Engineer-
James F. Collins Jr.
Florida License Number: 52212
1950 Marley Drive
Haines City, FL 33844

#	Ref	Description	Drawing#	Date
1	93275--H7A		07045046	02/14/07
2	93276--H9A		07045001	02/14/07
3	93277--H11A		07045002	02/14/07
4	93278--H13A		07045003	02/14/07
5	93279--H15A		07045004	02/14/07
6	93280--H17A		07045005	02/14/07
7	93281--H19A		07045006	02/14/07
8	93282--HM7A		07045035	02/14/07
9	93283--HM9A		07045007	02/14/07
10	93284--H11AT		07045008	02/14/07
11	93285--H13AT		07045009	02/14/07
12	93286--H15AT		07045010	02/14/07
13	93287--H17AT		07045011	02/14/07
14	93288--H19AT		07045012	02/14/07
15	93289--H21AT		07045013	02/14/07
16	93290--H23AT		07045014	02/14/07
17	93291--HM7B		07045036	02/14/07
18	93292--HM9B		07045015	02/14/07
19	93293--HM11B		07045016	02/14/07
20	93294--H13B		07045017	02/14/07
21	93295--H15B		07045018	02/14/07
22	93296--H17B		07045019	02/14/07
23	93297--H5C		07045037	02/14/07
24	93298--C-1		07045038	02/14/07
25	93299--H3D		07045039	02/14/07
26	93300--D-1		07045040	02/14/07
27	93301--F1		07045020	02/14/07
28	93302--F		07045021	02/14/07
29	93303--FGE		07045041	02/14/07
30	93304--HJ5		07045042	02/14/07
31	93305--HJ7		07045043	02/14/07
32	93306--EJ7		07045022	02/14/07
33	93307--J5		07045023	02/14/07
34	93308--J3		07045024	02/14/07
35	93309--J1		07045025	02/14/07
36	93310--EJ7D		07045026	02/14/07

#	Ref	Description	Drawing#	Date
37	93311--EJ7D1		07045027	02/14/07
38	93312--EJ7GE		07045044	02/14/07
39	93313--EJ7H		07045028	02/14/07
40	93314--EJ7S		07045029	02/14/07
41	93315--HJ3S		07045045	02/14/07
42	93316--EJ3S		07045030	02/14/07
43	93317--CJ1S		07045031	02/14/07
44	93318--H21AP		07045032	02/14/07
45	93319--H23AP		07045033	02/14/07
46	93320--AP		07045034	02/14/07





1 OF 1

SPECIAL LOADS
----- (LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)
TC From 62 PLF at -2.00 to 62 PLF at 7.00

TC - From	62 PLF at 17.41 to	62 PLF at 28.75
TC - From	62 PLF at 28.75 to	62 PLF at 34.48
TC - From	62 PLF at 34.48 to	62 PLF at 45.08

BC - From 20 PLF at 0.00 to 20 PLF at 14.42

BC - From	20 PLF at 27.08 to 4 PLF at 43.08	20 PLF at 43.08 to 4 PLF at 45.08
BC - From	4 PLF at 43.08 to	4 PLF at 45.08 to

TC -	182 LB Conc.	Load at 9.06, 11.06, 13.06
BC -	431 LB Conc.	Load at 7.00



R=1225 U=180 W=3.5"

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)

 $Cq/RT=1.00(1.25)/10(0)$

7.24.1230.17

61x:1

FL/-/4/-/-/R/-/

Scale = .125" / Ft.

W. R. COLLINS JR.
JAN 11 1965
LIBRARY

№ 192219

STATE OF

STATE OF
NEW YORK
OFFICE OF THE
ATTORNEY GENERAL
ALBANY



100

REF	R8228- 93275
DATE	02/14/07
DRW	HCSNR8228 07045046
HC-ENG	JB/WHK
SEQN-	9899
JREF-	1T4U8228Z01

Top	chord	2x4	SP	#2	Dense
Bot	chord	2x4	SP	#2	Dense
	webs	2x4	SP	#3	

Deflection meets $L/360$ live and $L/240$ total load. Creep increase factor for dead load is 1.50.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.




Diagram of a continuous beam with four supports. The beam is divided into three spans. The first span is 14-6-12, the second is 10-4-15, and the third is 9-4-0. The total length is 43-1-0. The beam is labeled "Over 3 Supports". The beam is labeled "R=495 U=180 W=3.5\" at the left end and "R=1051 U=180 W=3.5\" at the right end. The beam is labeled "R=2135 U=212 W=3.5\" at the first support.

PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)

7.24.1230 13 QTY:1

FL/-/4/-/-/R/-

Scale = .125" / Ft.

*****WARNING***** FRICES (BUILDING EXISTENT CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING REFER TO GC51 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TROSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WPCA (WOOD TRUSS COUNCIL OF AMERICA, 65000 ENTERPRISE LANE, MADISON, WI, 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

IMPORTANTFURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT

TP1; OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

CONNECTOR PLATES ARE MADE OF 20/18/16GA (M.H/SS/K) ASTM A653 GRADE 40/60 (M. K/H.SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND WELDES STRUCTURE LOCATED ON THIS DESIGN POSITION PER DRAWING 1604 T

ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TP11-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT

DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER. SEE ANCLT/01-1 SEC. 2.

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523</
--	---	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-------

ITW Building Components Group, Inc.
Haines City, FL 33844
FI Certificate of Authorization #

FI Certificate of Authorization # 567

Feb 19 2012

TC LL	20.0 PSF	REF	R8228-93276
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228-07045001
BC LL	0.0 PSF	HC-ENG JB/WHK	
TOT.LD.	40.0 PSF	SEQN-	9890
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1TAU8228Z01


JREF - 1T4U8228Z01

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Wets 2x4 SP #3

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. IW=1.00 Gcpl(+/-)=0.18
In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



2-0-0
11-0-0
14-6-12
10-4-15
7-4-0
14-4-0
43-1-0 Over 3 Supports
R=424 U=180 W=3.5"
R=2243 U=221 W=3.5"
R=1015 U=180 W=3.5"

PLT TYP. 20 Gauge HS.Wave



Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

QTY:1 FL/-/4/-/R/-

Scale = .125" /ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY NDS AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 2018/1604 (A/H/S/A) ASH/ALSO GRADE 40/60 (A, K/M, S) GALV. STEEL. APPLY TO THE TRUSS DESIGN. ANY DEVIATION FROM THIS DESIGN SHALL BE PER ANNEK 43 OF TPI-2002 (SEC. 3). DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITW Building Components Group, Inc.
Haines City, FL 33844
FL Certificate of Authorization # SC7

TC LL	20.0 PSF	REF R8228- 93277
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045002
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9882
DUR. FAC.	1.25	
SPACING	24.0"	

JREF- 1T4U8228201


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCP1(+/-)=0.18

(A) Continuous lateral bracing equally spaced on member.



2'-0"-0
14'-6"-12
13'-0"-0
13'-3"-8
1'-1"-8
10'-4"-15
5'-4"-0
28'-8"-0
14'-4"-0
43'-1"-0 Over 3 Supports
R=488 U=180 W=3.5"
R=2146 U=201 W=3.5"
R=1047 U=180 W=3.5"

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

7.24.1230

0TY:1 FL/-/4/-/-/R/-



Scale = .125"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF HUD (NATIONAL DESIGN SPEC. BY ACPA) AND TPI. ITW BCG CONNECTION PLATES ARE MADE OF 2018/1604 (4 H/55/4) ASTM A553 GRADE 40/60 (4, 6/21/55) GALV. STEEL. APPLY TO ALL TRUSSES. CONNECTIONS SHALL BE LOCATED ON THIS DESIGN. CONNECTION PER DRAWINGS 1604.2, 1604.3, 1604.4, 1604.5, 1604.6, 1604.7, 1604.8, 1604.9, 1604.10, 1604.11, 1604.12, 1604.13, 1604.14, 1604.15, 1604.16, 1604.17, 1604.18, 1604.19, 1604.20, 1604.21, 1604.22, 1604.23, 1604.24, 1604.25, 1604.26, 1604.27, 1604.28, 1604.29, 1604.30, 1604.31, 1604.32, 1604.33, 1604.34, 1604.35, 1604.36, 1604.37, 1604.38, 1604.39, 1604.40, 1604.41, 1604.42, 1604.43, 1604.44, 1604.45, 1604.46, 1604.47, 1604.48, 1604.49, 1604.50, 1604.51, 1604.52, 1604.53, 1604.54, 1604.55, 1604.56, 1604.57, 1604.58, 1604.59, 1604.60, 1604.61, 1604.62, 1604.63, 1604.64, 1604.65, 1604.66, 1604.67, 1604.68, 1604.69, 1604.70, 1604.71, 1604.72, 1604.73, 1604.74, 1604.75, 1604.76, 1604.77, 1604.78, 1604.79, 1604.80, 1604.81, 1604.82, 1604.83, 1604.84, 1604.85, 1604.86, 1604.87, 1604.88, 1604.89, 1604.90, 1604.91, 1604.92, 1604.93, 1604.94, 1604.95, 1604.96, 1604.97, 1604.98, 1604.99, 1604.100.

ANY INSPECTION OF PLATE FABRICATION BY AN INDEPENDENT QUALITY CONTROL FIRM SHALL BE REQUIRED. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITW Building Components Group, Inc.
Haines City, FL 33844

TC LL	20.0 PSF	REF R8228- 93278
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUR8228 07045003
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9891
DUR. FAC.	1.25	
SPACING	24.0"	
JREF	1T4U8228Z01	


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. 1W=1.00 gcpl(+/-)=0.18

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



2.0 0
14-6-12
15-0-0
10-4-15
3-4-0
14-4-0
43-1-0 Over 3 Supports
R=458 U=180 W=3.5"
R=2193 U=227 W=3.5"
R=1031 U=180 W=3.5"

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

7.24.1230

QTY:1 FL/-/4/-/-/R/-



Scale = .125"/ft.

HARRING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 210 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND NCA (NATIONAL COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIAA AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/S) ASTM A653 GRADE 40/50 (W. K/H/SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A, Z. CONNECTION OF PLATES FOLLOWED BY TPI SHALL BE DESIGNER'S RESPONSIBILITY. A SEAL ON THIS DRAWING INDICATES THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ITW Building Components Group, Inc.
Haines City, FL 33844
ITW Certificate of Authorization #567




TC LL	20.0 PSF	REF R8228- 93279
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCURS8228 07045004
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9877
DUR. FAC.	1.25	
SPACING	24.0"	
UREF-	1T4U8228201	

Top chord	2x4	SP	#2	Dense
Bot chord	2x4	SP	#2	Dense
Webs	2x4	SP	#3	

Deflection meets $L/360$ live and $L/240$ total load. Creep increase factor for dead load is 1.50.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC



0
10-10-8
17-0-0
43-1-0 Over 3 Supports
14-4-0
1-4-0
R-390 U=180 W=3.5" R-2030 U=196 W=4.95" R-1262 U=180 W=3.5"

Design Crit: $TPI - 2002(STD) / FBC$ $Cq/RT=1.00(1.25)/10(0)$

7.24.1230

QTY:1


FL/-/4/-/-/R/-/

Scale = .125" / Ft.

WARNING: THESE REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND PACKING. REFER TO HC51 (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY IP1 (TRUSS PLATE INSTITUTE), 210 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314, AND WICA (WOOD TRUSS COUNCIL OF AMERICA), 6500 ENTERPRISE LANE, SUITE 500, ST. LOUIS, MO, 63139 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED CHORD CEILING.

ALPINE

JTW Building Components Group, Inc.
Haines City, FL 33844
FL Certificate of Authorization #



Feb 14 07

TC LL	20.0 PSF	REF	R8228-93280
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCSUR8228 07045005
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT. LD.	40.0 PSF	SEQN-	9883
DUR. FAC.	1.25		
SPACING	24.0"	JREF	174U8228Z01

JREF - 1T4U8228Z01

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3


Wind reactions based on MMFRS pressures.

In lieu of structural panels or rigid ceiling use purlins to
brace TC @ 24' OC, BC @ 24' OC.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not
located within 6.50 ft from roof edge, CAT II, EXP B, wind TC
DL=5.0 psf, wind BC DL=5.0 psf, IW=1.00 Gcpl(+/-)=0.18

(A) Continuous lateral bracing equally spaced on member.

Deflection meets L/360 live and L/240 total load. Creep increase
factor for dead load is 1.50.



2-0-0
8-9-12
19-0-0
9-1-0
15-0-0
2-0-0
43-1-0 Over 3 Supports
R=483 U=180 W=3.5"
R=1787 U=182 W=3.5"
R=1546 U=180 W=3.5"

PLT TYP. Wave


Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

QTY: 4 FL/-/4/-/R/-

Scale = .125"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 210 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22304 AND WICK (WOOD TRUSS COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. BY AFRPA AND TPI. ITW BCG DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. FOR WOOD) AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/R) ASTM A653 GRADE 40/50 (W. K/M/SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A, Z, AND 160B. INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PERFORMED AS OF 11/11/2002 SEC. 3 FOR THE TRUSS COMPONENT AND (2) SHALL BE PERFORMED AS OF 11/11/2002 SEC. 3 FOR THE TRUSS COMPONENT. A SEAL ON THIS DESIGN SHOWS THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITW Building Components Group, Inc.
Haines City, FL 33844
FL Certificate # 567

TC LL	20.0 PSF	REF	R8228-93281
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCU8R8228 07045006
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT. LD.	40.0 PSF	SEON-	9875
DUR. FAC.	1.25		
SPACING	24.0"	UREF-	1T4U8228201

Top chord 2x6 SP #1 Dense :T1, T5 2x4 SP #2 Dense:

Bot chord 2x6 SP #1 Dense

Webs 2x4 SP #3 :W11 2x4 SP #2 Dense:

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. lw=1.00 GCPI(+/-)=0.18

Wind reactions based on MMFRS pressures.

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

2 COMPLETE TRUSSES REQUIRED

Nailing Schedule: (12d Common (0.148"x3.25", min.)_nails)

Top Chord: 1 Row @12.00" o.c.

Bot Chord: 1 Row @12.00" o.c.

Webs : 1 Row @ 4" o.c.


Use equal spacing between rows and stagger nails in each row to avoid splitting.

Right end vertical not exposed to wind pressure.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

#1 hip supports 7'-0" jacks with no webs.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



R-3650 U-319 W-3.5"

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.1230

QTY:1 FL-/4/-/R/-

Scale = .125"/ft.

WARNINGS TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI BUILDING COMPONENTS SAFETY INFORMATION PUBLISHED BY TPI TRUSSES, INC., 6300 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA 22314 AND WICK TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. TPI BCS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE OF THE TRUSS IN COMPLIANCE WITH TPI; OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.


DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY APCA) AND TPI. TPI BCS CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/RS) ASTM A653 GRADE 40/50 (W, K/R, S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS. 16GA, 2.0" MIN. THICKNESS ON PLATE TO COVER OF PROTECT SHALL BE USED. TPI BCS, INC. SHALL BE SOLELY RESPONSIBLE FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

TW Building Components Group, Inc.

Haines City, FL 33844

77 Certificate of Authorization 44-567



TC LL	20.0 PSF	REF	R8228- 93282
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045035
BC LL	0.0 PSF	HC-ENG	JB/MHK
TOT. LD.	40.0 PSF	SEON-	9907
DUR. FAC.	1.25		
SPACING	24.0"	UREF-	1T4U8228201

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

:Lt Splice Block 2x4 SP #3:

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.


110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. 1W=1.00 GCPI(+/-)=0.18

Wind reactions based on MFRS pressures.

Right end vertical not exposed to wind pressure.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

3X6 =



2'-0"

9'-0"

31'-0"

3'-1"

R=1917 U=196 W=3.5"

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.1230

R=1765 U=180 H=Simpson HUS26
W/(4) 10d Common, 0.148"x3.0" nails in Truss
W/(14) 10d Common, 0.148"x3.0" nails in Girder
Girder is (1)2X6 min. So. Pine

Scale = .125"/ft.


PLT TYP. Wave

WARNING THUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO THE MANUFACTURER'S INSTRUCTIONS FOR THE PROPER USE OF THE THUSSES. THE THUSSES ARE NOT TO BE USED IN ANY MANNER OTHER THAN THAT SPECIFIED IN THE INSTRUCTIONS. THE THUSSES ARE NOT TO BE USED IN ANY MANNER OTHER THAN THAT SPECIFIED IN THE INSTRUCTIONS. THE THUSSES ARE NOT TO BE USED IN ANY MANNER OTHER THAN THAT SPECIFIED IN THE INSTRUCTIONS.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR.

ALPINE

ITM Building Components Group, Inc.
Haines City, FL 33844
Tel: 888-444-4444



TC LL	20.0 PSF	REF	R8228- 93283
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045007
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT. LD.	40.0 PSF	SEON-	9910
DUR. FAC.	1.25		
SPACING	24.0"	UREF-	1T4U8228201

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MMFRS pressures.

Calculated horizontal deflection is 0.12" due to live load and 0.19" due to dead load.



In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCPI(+/-)=0.18

Right end vertical not exposed to wind pressure.

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



Note: All Plates Are 3X4 Except As Shown.

PLT TYP. 18 Gauge HS.Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

7.24.1230

QTY:1 FL/-/4/-/R/-

Scale = .125"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSE (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WICA (WOOD TRUSS COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

ALPINE

TW Building Components Group, Inc.
Haines City, FL 33844

Professional Engineer

Feb 14 07

TC LL	20.0 PSF	REF	R8228- 93284
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045008
BC LL	0.0 PSF	HC-ENG	JB/MHK
TOT. LD.	40.0 PSF	SEON-	9913
DUR. FAC.	1.25		
SPACING	24.0"	UREF-	1T4U8228201

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MMFRS pressures.

Calculated horizontal deflection is 0.13" due to live load and 0.20" due to dead load.



In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf, IW=1.00 Gcpl(+/-)=0.18

Right end vertical not exposed to wind pressure.

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



Design Crit: TPI-2002(STD)/FBC

PLT TYP. 18 Gauge HS.Wave

Cq/RT=1.00(1.25)/10(0)

7.24.1230

QTY:1 FL/-/4/-/R/-

Scale = .125"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA. 22314 AND WICA (WOOD TRUSS COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/PA) AND TPI. DESIGN CONFORMS WITH 2018/18 GMA (W/H/SS/RS) ASH 4853 GRADE 40/50 (W, K/H/SS) GALV. STEEL. ITM BCG PLATES EACH OF ALL TRUSSES AND ALL GIRDERS SHALL BE STAMPED OR MARKED WITH THE FOLLOWING INFORMATION PER DRAWING 60612. THIS INFORMATION SHALL BE STAMPED OR MARKED ON EACH OF THE TRUSSES AND GIRDERS. THE STAMPING INDICATES THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

ITM Building Components Group, Inc.

Haines City, FL 33844

PLT TYP. 18 Gauge HS.Wave



Feb 14 07

TC LL	20.0 PSF	REF R8228- 93285
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045009
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT.LD.	40.0 PSF	SECON- 9916
DUR.FAC.	1.25	
SPACING	24.0"	JREF- 1T4U8228201


המחברת מודה לרבות מהמשתתפים במחקר על שיתוף הפעולה והתמיכה.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT 11, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf lw=1.00 GCPI (+/-) -0.18

Right end vertical not exposed to wind pressure.

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

Deflection meets $L/360$ live and $L/240$ total load. Creep increase factor for dead load is 1.50.



Scale = .125" / Ft.

TC LL	20.0 PSF	REF R822
TC DL	10.0 PSF	DATE

[illegible]

OF

TC LL	20.0 PSF	REF	R8228- 93286
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCSR8228 07045010
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEON-	9919
DUR.FAC.	1.25		
SPACING	24.0"	JREF -	1T4U8228Z01

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. Iw=1.00 Gcpi(+/-)=0.18

Right end vertical not exposed to wind pressure.

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.




Scale = .125"/Ft.

R=1765 U-180 H-Simpson HUS26 W/ (4) 10d Common, 0.148"x3.0" nails in Truss W/ (14) 10d Common, 0.148"x3.0" nails in Girder Girder is (1)2X6 min. So.Pine	
QTY:1	FL/-4/-/-R/-
TC LL	20.0 PSF
TC DL	10.0 PSF
REF	R822
DATE	0

BC DL 10.0 PSF

ALPINE



TC LL	20.0 PSF	REF	R8228 - 93287
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045011
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN -	9922
DUR.FAC.	1.25		
SPACING	24.0"	JREF -	1T4U8228Z01

JREF - 1T4U8228Z01

[illegible]


110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. 1w=1.00 Gcpi (+/-)=0.18

Right end vertical not exposed to wind pressure.

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

publication for additional information.

Deflection meets $L/360$ live and $L/240$ total load. Creep increase factor for dead load is 1.50.



Scale = .125" / Ft.


TC LL	20.0 PSF	REF	R8228- 93288
TC DL	10.0 PSF	DATE	02/14/07

BC LL	0.0 PSF
-------	---------


DUR. FAC.

SPACING 24.0" JREF- 1T4U8228Z01

Deflection meets $L/360$ live and $L/240$ total load. Creep increase factor for dead load is 1.50.




CONNECTION PLATES MADE OF 20/218/1654 (A/N-HSS) WITH A655 GRADE OD-60 (R/A-35) GALV. STEEL. APPLY PLATES TO EACH FACE OF THUS AND UNLESS OTHERWISE NOTED ON THIS DESIGN, POSITION PER DRAWING. LOD-2 AN INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMEX AS OF APRIL-2002 SEC.3.
DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE SEAL ON THIS CONNECTION. NO USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/APSI SEC. 2.



TC LL	20.0 PSF	REF	R8228 - 93289
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCSUR8228 07045013
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN -	9928
DUR.FAC.	1.25		
SPACING	24.0"	JREF -	1TAU8228Z01

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{CPI}(+/-)=0.18$



	Top chord	2x4 SP	#2 Dense	:T2, T3	2x6 SP	#1 Dense
Bot	chord	2x6 SP	#1 Dense			
Web	2x4 SP	#3				


TC	From	126 PLF at	0.00 to	126 PLF at	28.6
BC	From	4 PLF at	-2.00 to	4 PLF at	0.00
BC	From	44 PLF at	0.00 to	44 PLF at	28.6

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Wind reactions based on MMFRS pressures.

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

Deflection meets $L/360$ live and $L/240$ total load. Creep increase factor for dead load is 1.50.



R=2446 U=266 W=3.5^m

-28-8-0 Over 2 Supports

R=2437 U-261 H-Simpson HUS26
w/ (6) 10d Common, 0.148"x3.0" nails in Truss
w/ (14) 10d Common, 0.148"x3.0" nails in Girder
Girder is (1)2X6 min. So.Pine

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)

$$Cq/RT=1.00(1.25)/10(0)$$

ATTY:

FL/4/1/1R/1

Scale = .25" / Ft.

WARNING—FRAMES REQUIRING EXTENSIVE CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING REFER TO GC51 (BUILDING COMPONENT SPECIFICATION) - PUBLISHED BY TPI (TRUSS PLATING INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WPCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, MI 48139) FOR TRUSS PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

ALPINE

ITW Building Components Group, Inc.

Haines City, FL 33844
 FI Certificate of Authorization # 567

Feb 14 07

SPACING

1

JREF - 1T4U822BZ01

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MWFRS pressures.

Left end vertical exposed to wind pressure. Deflection meets L/240 criteria for brittle and flexible wall coverings.


In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{CPI}(+/-)=0.18$

Right end vertical not exposed to wind pressure.

H = recommended connection based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



R=1319 U=180 W=3.5*

R=1176 U=180 H=Simpson HUS26
W/ (4) 10d Common, 0.148"x3.0" nails in Truss
W/ (14) 10d Common, 0.148"x3.0" nails in Girder
Girder is (1)2x6 min. So. Pine

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

7-24-1230

QTY:1

FL/-/4/-/R/-

Scale = .25"/ft.


WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA 22314) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. JTW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. JTW BCG CONNECTION PLATES ARE MADE OF 20/18/16GA (N/A/55K) ASTM A653 GRADE 40/80 (K/47/55) GALV. STEEL. APPLY TO ALL TRUSSES. ALL TRUSSES SHALL BE LOCATED ON THIS DESIGN. POSITION PER DRAWINGS. LOADS AND REACTIONS OF TRUSSES SHOWN BY TRUSSES SHALL BE USED BY THE DESIGNER. THE TRUSS COMPONENTS DESIGN INDICATES THE ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENTS DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

JTW Building Components Group, Inc.
Haines City, FL 33844
Professional Engineer
Feb 14 07

PLT TYP. Wave



TC LL	20.0 PSF	REF	R8228 - 93292
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045015
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN-	9934
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	174U8228Z01

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MMFRS pressures.

Left end vertical exposed to wind pressure. Deflection meets L/240
criteria for brittle and flexible wall coverings.


In lieu of structural panels or rigid ceiling use purlins to brace
TC @ 24" OC, BC @ 24" OC.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not
located within 4.50 ft from roof edge, CAT II, EXP B, wind TC
DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{CPI}(+/-)=0.18$

Right end vertical not exposed to wind pressure.

H = recommended connection based on manufacturer tested capacities
and calculations. Conditions may exist that require different
connections than indicated. Refer to manufacturer publication for
additional information.

Deflection meets L/360 live and L/240 total load. Creep increase
factor for dead load is 1.50.



R=1319 U=180 W=3.5*

R=1176 U=180 H=Simpson HUS26
W/(4) 10d Common, 0.148"x3.0" nails in Truss
W/(14) 10d Common, 0.148"x3.0" nails in Girder
Girder is (1)2x6 min. So.Pine

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

7.24.1230.17

QTY:1


FL/-/4/-/R/-

Scale=.25"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING.
REFER TO BCST (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218
NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WICK (WOOD TRUSS COUNCIL OF AMERICA, 6300
ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS
OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE
A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT
BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH
TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.
DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY ASCE/AIA AND TPI. ITM BCG
CONNECTOR PLATES ARE MADE OF 20/10/100A (A/H/SS/A) ASH AREA GRADE 40/60 (A/H/SS) GALV. STEEL. APPLY 7.
NAILING REQUIREMENTS TO BE FOLLOWED. ALL TRUSSES SHALL BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH
TPI-2002 (STD) AND TPI-2002 (FBC). ALL TRUSSES SHALL BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH
DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT
DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE
BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ITW Building Components Group, Inc.
Haines City, FL 33844
Certificate of Authorization # 4527




TC LL	20.0 PSF	REF	R8228- 93293
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045016
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN-	9936
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1T4U8228Z01

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. IW=1.00 Gcpl(+/-)=0.18
In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0)

7.24.123

QTY:1

FL/-/4/-/R/-

Scale = .1875"/ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSS BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY THE TRUSS COUNCIL OF AMERICA, 6300 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA 22314 AND WICA (WOOD TRUSS COUNCIL OF AMERICA), 1000 ENTERPRISE LANE, MADISON, NJ 07719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.


****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. ITW BCG DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY ACPA) AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/RS) ASTM A653 GRADE 40/60 (W. K/H/SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A.2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMER AS OF TPI-2002, SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. SOLELY FOR THE TRUSS COMPONENT BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ITW Building Components Group, Inc.
Haines City, FL 33844
Certificate of Authorization # 547




TC LL	20.0 PSF	REF R8228- 93294
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUR8228 07045017
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9878
DUR. FAC.	1.25	
SPACING	24.0"	UREF- 1T4U8228201

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC



Scale = .25" / Ft.



2230
CITY

JAMES F. COLLINS
LICENSE
No. 8222
STATE OF
FLORIDA
PROFESSIONAL ENGINEER


Feb 14 07

TC LL	20.0 PSF	REF	R8228 - 93295
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUS88228 07045018
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEON-	9863
DUR.FAC.	1.25		
SPACING	24.0"	JREF -	174U8228201

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP 8, wind TC DL=5.0 psf, wind BC DL=5.0 psf. Iw=1.00 gcpi(+/-)=0.18

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



Scale = .25" / ft.

1230 13 QTY: 1

1230 15
JAMES E. COLLINS
NOL 62212
JAN 1962
PTY:

1230 15
JAMES E. COLLINS
LICENSE
No 152212
STATE OF
NY
DTY:

REF	R8228-93296
DATE	02/14/07
DRW	HCSR8228 07045019
HC-ENG	JB/WHK
SEQN-	9886
TOT.LD.	40.0 PSF
DR.FAC.	1.25
SPACING	24.0"
JREF-	1T4U8228Z01

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCPI(+/-)=0.18



Scale = .25" / Ft

ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMNE AS OF TP11-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY FOR THE TRUSS COMPONENTS DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE USER.



FL/-/4/-/-/R/-		Scale=.25"/Ft.
TC LL	20.0 PSF	REF R8228-98297
FC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228-07045037
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT.LD.	40.0 PSF	SECN- 9896
DUR.FAC.	1.25	
SPACING	24.0"	JREF-1T4U8228Z01

Top chord 2x4 SP #2 Dense
Bot chord 2x6 SP #1 Dense
Webs 2x4 SP #3


SPECIAL LOADS

----- (LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)
TC - From 62 PLF at -2.00 to 62 PLF at 5.54
TC - From 62 PLF at 5.54 to 62 PLF at 16.75
TC - From 62 PLF at 16.75 to 62 PLF at 24.29
BC - From 4 PLF at -2.00 to 4 PLF at 0.00
BC - From 20 PLF at 0.00 to 20 PLF at 12.00
BC - From 20 PLF at 12.00 to 20 PLF at 22.29
BC - From 4 PLF at 22.29 to 4 PLF at 24.29
BC - 1765 LB Conc. load at 1.23, 3.23, 5.23, 7.23, 13.23
BC - 1766 LB Conc. load at 9.23, 11.23
BC - 3675 LB Conc. load at 15.17

Wind reactions based on MWFRS pressures.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

+ 8-16d COMMON (.162"x3.5") NAILS OPPOSITE HANGER AFTER THE THIRD PLY IS ATTACHED.



R=10596 U=1019 W=3.5*
R=7540 U=719 W=3.5*

PLT TYP. 20 Gauge HS,Wave

Design Crit: TPI-2002(STD)/FBC
Cq/R=1.00(1.25)/10(0)

7-24-1230

QTY:1

FL/-/4/-/R/-

Scale = .25"/Ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSTI (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

ALPINE

ITW Building Components Group, Inc.
Haines City, FL 33844

For Certificate of Authorization # 4547

3 COMPLETE TRUSSES REQUIRED

Nailing Schedule: (12d Common (0.148"x3.25", min.) nails)


Top Chord: 1 Row @ 12.00" o.c.
Bot Chord: 2 Rows @ 5.00" o.c. (Each Row)
Webs : 1 Row @ 4" o.c.

Repeat nailing as each layer is applied. Use equal spacing between rows and stagger nails in each row to avoid splitting.

Bearing blocks: Nail type: 12d Common (0.148"x3.25", min.) nails
BRG X-LOC #BLOCKS LENGTH/BLK #NAILS/BLK WALL PLATE
1 0.000' 1 12" Rigid Surface
Bearing block to be same size and species as bottom chord.
Refer to drawing CNBRGBLK1103 for additional information.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 6.50 ft from roof edge, CAT 11, EXP B, Wind TC DL=5.0 psf, Wind BC DL=5.0 psf. Iw=1.00 Gcpl(+/-)=0.18

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



TC LL	20.0 PSF	REF	R8228- 98298
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045038
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEON-	9952
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1TAU8228201

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. Iw=1.00 GCPI (+/-)=0.18

In lieu of structural panels or rigid ceiling use purllins to brace TC @ 24" OC, BC @ 24" OC.

Deflection meets $L/360$ live and $L/240$ total load. Creep increase factor for dead load is 1.50.

 $Cq/RT=1.00(1.25)/10(0) \quad 7.24.1230$

FL/-/4/-/-/R/-

Scale = .5" / Ft.

QTY: 1230

QTY: 12301

1230 1
QTY:

12301
QTY:

12301
QTY:

JAMES F. COLLINS JR.
LICENSED
No. 5222
STATE OF FLORIDA
PROFESSIONAL ENGINEER

Feb 14 97

TC LL	20.0 PSF	REF	R8228- 98299
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045039
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN-	9895
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1T4U8228T01


Top chord 2x4 SP #2 Dense
Bot chord 2x6 SP #1 Dense
Webs 2x4 SP #3

SPECIAL LOADS

----- (LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)
TC - From 62 PLF at -2.00 to 62 PLF at 3.25
TC - From 62 PLF at 3.25 to 62 PLF at 8.75
TC - From 62 PLF at 8.75 to 62 PLF at 14.00
BC - From 4 PLF at -2.00 to 4 PLF at 0.00
BC - From 20 PLF at 0.00 to 20 PLF at 12.00
BC - From 4 PLF at 12.00 to 4 PLF at 14.00
BC - 2437 LB Conc. Load at 7.00
BC - 1176 LB Conc. Load at 9.00, 11.00

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

2 COMPLETE TRUSSES REQUIRED
Nailing Schedule: (12d Common (0.148"x3.25", min.)_nails)
Top Chord: 1 Row @12.00" o.c.
Bot Chord: 1 Row @ 4.75" o.c.
Webs : 1 Row @ 4" o.c.
Use equal spacing between rows and stagger nails in each row to avoid splitting.
110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, Wind TC DL=5.0 psf, wind BC DL=5.0 psf. Iw=1.00 Gcpi(+/-)=0.18
Wind reactions based on MMFRS pressures.
Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



2-0-0
3-3-0
5-6-1
12-0-0 Over 2 Supports
2-0-0
R=2011 U=216 W=3.5"
R=4034 U=432 W=3.5"

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)


QTY: 1 FL/-/4/-/R/-

Scale = .5"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. JTW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES. JTW BCG DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIAA) AND TPI. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A, 2.

INSPECTION OF TRUSSES SHALL BE MADE AS SHOWN ON THIS DESIGN. A SEAL ON THIS DRAWING INDICATES THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



JTW Building Components Group, Inc.
Haines City, FL 33844
P.O. Box 1000
Haines City, FL 33844

TC LL	20.0 PSF	REF R8228- 93300
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045040
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9939
DUR.FAC.	1.25	
SPACING	24.0"	JREF- 1T4U8228201

110 mph wind, 15.00 ft mean hg, ASCE 7-02, CLOSED bldg, located anywhere in roof, GAI 11, EXP B, wind TC DL-5.0 psf, wind BC DL-5.0 psf. Iw=1.00 GAI(+/-)=0.18



TC LL	20.0 PSF	REF	R8228 - 93301
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045020
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN-	9862
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1T4U8228Z01



Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{cpl}(+/-)=0.18$

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

QTY:1


FL/-/4/-/1/-/R/-

Scale = .5"/ft.


****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIAA) AND TPI. ITM BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/AS) ASTM A653 GRADE 40/80 (W. K/P/1.55) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS. 16GA. Z-SECTION OF PLATES FOLLOWED BY (1) SHALL BE USED FOR ALL TRUSSES. 11/2002 (EC. 1) FOR THE TRUSS COMPONENTS. DRAWING INDICATES THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITM Building Components Group, Inc.
Haines City, FL 33844
FL Certificate of Authorization #547



TC LL	20.0 PSF	REF	R8228- 93302
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045021
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN-	9880
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1T4U8228Z01

THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF THE ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, AND SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO THE GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.


In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



****IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT**

FI Certificate of Authorization # 667



Feb 14 '07

TC LL	20.0 PSF	REF	R8228 - 93303
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045041
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN -	9947
DUR.FAC.	1.25		
SPACING	24.0"	JREF -	1TAU8228Z01

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense


Wind reactions based on MMFRS pressures.

Hipjack supports 5-0-0 setback jacks with no webs.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf, lw=1.00 Gcp1(+/-)=0.18

In lieu of structural panels or rigid ceiling use purtins to brace TC @ 24" OC, BC @ 24" OC.



PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0)

7-24-1230

QTY: 2


FL/-/4/-/R/-

Scale = .5"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

ALPINE


TW Building Components Group, Inc.
Haines City, FL 33844
P.O. Box 1000, Haines City, FL 33844



TC LL	20.0 PSF	REF R8228- 93304
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045042
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT.LD.	40.0 PSF	SEON- 9894
DUR.FAC.	1.25	
SPACING	24.0"	JREF- 1T4U8228Z01

Hipjack supports 7-0-0 setback jacks with no webs.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCPI(+/-)=0.18



9-10-13 Over 3 Supports \rightarrow
 $R=540$ $U=180$ $W=4.95"$

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)

$$Cq/RT=1.00(1.25)/10(0)$$

7.24.1238:5/ COL/17

QTY:2 FL/-/4/-/-/R/-

Scale = .5" / Ft.

WARNING PROE, BUILDING EXTERIOR CASE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING REFER TO GC51 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY IP1 (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 63000 ENTERPRISE LANE, MADISON, WI, 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.


IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITN BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI-1 OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSEES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AF&A) AND TPI-1.

CONNECTOR PLATES ARE MADE OF 20/18/16GA (M/A/SS/K) ASTM A653 GRADE 40/60 (M, K/P/SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z.

ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMEAS O3 OF TPI-2002 SEC.3.

DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENTS OF THE DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI-1 SEC. 2.




TC LL	20.0 PSF	REF	R8228- 93305
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCU8R8228 07045043
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN-	9898
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1TAU8228Z01

Top chord	2x4	SP	#2	Dense
Bot chord	2x4	SP	#2	Dense

Deflection meets $L/360$ live and $L/240$ total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not
located within 4.50 ft from roof edge, CAT II, Exp B, wind TC
DL=5.0 psf, wind BC DL=5.0 psf. IW=1.00 Gcpi(+/-)0.18
In lieu of structural panels or rigid ceiling use purlins to
brace TC @ 24" OC, BC @ 24" OC



PLT TYP. Wave


Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)

$$Cq/RT=1.00(1.25)/10(0)$$

7.24.1230.17

QTY:22 FL/-/4/-/-/R/-


Scale = .5" / Ft.



ITW Building Components Group, Inc.
Haines City, FL 33844
EI Certificate of Authorization

****WARNING**** *RIGS REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPIING, INSTALLING AND DRACING REFER TO BCG1 (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 212, ALEXANDRIA, VA, 22304) AND WICA (WOOD TRUSS COMPANY OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI, 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT***** *HARNESS A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DETAIL OR FIELDING DESIGNER'S FAILURE TO BUILD THE TRUSSES IN CONFORMANCE WITH TPI: OR FABRICATING/HANDLING, SHIPPING, INSTALLING, OR BRACING OF TRUSSES. ITW BCG HAS NO LIABILITY FOR DESIGN CONFLICTS WITH APPLICABLE PROVISIONS OF NOS (NATIONAL DESIGN SPEC. BY AISC) AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 50/18/16GA U.S./SS/24 ASTM A653 GRADE 40/60 K/A/53 GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. AN INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-1:2002 SEC.3. SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.




TC LL	20.0 PSF	REF	R8228- 93306
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045022
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN-	9865
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1T4U8228Z01

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT 11, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. IW=1.00 Gcpl(+/-)=0.18
In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)


7.24.1230

QTY:12 FL/-/4/-/-/R/-

Scale =.5"/ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENTS SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 210 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22304, AND WICA (WOOD PRES. COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI, 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE OF TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/PA AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/S) ASTM A653 GRADE 40/60 (W, K/H, S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A, Z, AND 160B. INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMER AS OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. ONLY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SEAL IS NOT VALID FOR ANY OTHER USE OR THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



TC LL	20.0 PSF	REF R8228- 93307
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045023
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9873
DUR. FAC.	1.25	
SPACING	24.0"	
UREF-	1T4U8228201	

ITW Building Components Group, Inc.
Haines City, FL 33844
FL Certificate of Authorization #567


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL-5.0 psf, wind BC DL-5.0 psf, $I_w=1.00$ $G_{CPI}(+/-)=0.18$

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



2-0-0

2-5-8
3-0-0 Over 3 Supports
R=317 U=180 W=3.5"

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)


7.24.1230

QTY:8 FL/-/4/-/-/R/-


Scale = .5"/ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314, AND WCA (WOOD TRUSS COUNCIL OF AMERICA), UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/PA & TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/R) ASTM A653 GRADE 40/50 (W, K/H, S) GALV. STEEL. APPLY PLATES EACH SIDE OF TRUSS JOINTS. UNLESS OTHERWISE SPECIFIED ON THIS DESIGN. POSITION PER DRAWING 160A.2. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITW Building Components Group, Inc.
Haines City, FL 33844
ET Certificate of Authorization #567



TC LL	20.0 PSF	REF R8228- 93308
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCURSR8228 07045024
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEQN- 9868
DUR. FAC.	1.25	
SPACING	24.0"	UREF- 1T4U8228201


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{cpl}(+/-)=0.18$

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



R=110 U=180
R=35 U=180



0-10-3



1-0-0 over 3 supports

R=361 U=180 W=3.5"

PLT TYP. Wave

Design Crt: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0)

7.24.1230

DTY:8


FL/-/4/-/R/-

Scale =.5"/ft.


WARNINGS TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY TPI TRUSS PLATE INSTITUTE, 2100 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA. 22314 AND WCA WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES. ITW BCG DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. CONNECTION PLATES ARE MADE OF 20/18/16GA (W/H/SS/RS) ASTM A653 GRADE 40/50 (W, K/M, SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2.

ANY INSPECTION OF PLATES FOLLOWED BY TPI SHALL BE PERFORMED AS OF TPI-2002, SEC. 3. A SEAL ON THIS DRAWING INDICATES THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITW Building Components Group, Inc.
Haines City, FL 33844



Feb 14 07


TC LL	20.0 PSF	REF R8228- 93309
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045025
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9871
DUR. FAC.	1.25	
SPACING	24.0"	
UREF-	1T4U8228Z01	

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{cpl}(+/-)=0.18$
In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



2-0-0
4-0-7
2-11-9
7-0-0 Over 3 Supports
R=441 U=180 W=3.5*

PLT TYP. Wave


Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

QTY: 1 FL/-/4/-/-/R/-


Scale = .5"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST BUILDING COMPONENTS SAFETY INFORMATION, PUBLISHED BY THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 100 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA 22314 AND AISC (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC.), BY ACPA AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/S) ASTM A653 GRADE 40/50 (W. K/H/SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 100-12. ANY INSPECTION OF PLATES FOLLOWED BY IT SHALL BE PER AMEA AS OF 1/11/2002, SEC. 3 FOR THE TRUSS COMPONENT DRAWING INDICATES ACCEPTANCE OF THE DESIGN AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITW Building Components Group, Inc.
Haines City, FL 33844
P.O. Box 1000
Haines City, FL 33844




ITEM	DESCRIPTION	QTY	UNIT	PRICE	TOTAL
1	TRUSS	1	EA	20.0	20.0
2	PLATE	10	EA	10.0	100.0
3	PLATE	10	EA	10.0	100.0
4	PLATE	0	EA	0.0	0.0
5	PLATE	40	EA	0.0	0.0
6	PLATE	1	EA	1.25	1.25
7	PLATE	24	EA	0.0	0.0
8	PLATE	1	EA	9867	9867

REF R8228- 93310
DATE 02/14/07
DRW HCUSR8228 07045026
HC-ENG JB/WHK
SEON- 9867
JREF- 1T4U8228201

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



PLT TYP. Wave


Design Crit: TPI-2002(STD)/FBC

 $Cq/RT=1.00(1.25)/10(0)$

7.24.1230:17 C01/1 QTY:1

QTY:1 FL/-/4/-/-/R/-

Scale = .5" / Ft.




JTW Building Components Group, Inc.
Haines City, FL 33844

MAINING FRAMES REQUIRE EXTREME CARE IN FABRICATING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 63000 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE OPERATIONS. UNLESS OTHERWISE INDICATED FOR CHORD SHAFTS HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID GILLING.

****IMPORTANT*** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TROUS IN CONFORMANCE WITH ITM OR FABRICATING, HANDLING, SHIPPING, INSTALLING BRACING OF TRUSSES.

PLATES TO EACH FLEE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-200. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPII 2002 SEC.3. A SEAL OF THIS SOCIETY DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY FOR THE TRUSS COMPONENTS OF THE DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE



TC LL	20.0 PSF	REF	R8228- 93311
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045027
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT. LD.	40.0 PSF	SEQN -	9889
DUR. FAC.	1.25		
SPACING	24.0"	JREF -	1T4U8228201

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

SPECIAL LOADS

----- (LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)
TC - From 84 PLF at -2.00 to 84 PLF at 1.58
TC - From 84 PLF at 1.58 to 84 PLF at 3.50
TC - From 84 PLF at 3.50 to 84 PLF at 7.00
BC - From 4 PLF at -2.00 to 4 PLF at 0.00
BC - From 20 PLF at 0.00 to 20 PLF at 7.00

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.


110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP 8, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{cpl}(+/-)=0.18$

Wind reactions based on MMFRS pressures.

Right end vertical not exposed to wind pressure.

Dead loads are stated on projected horizontal area basis.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)



QTY: 1 FL/-/4/-/1/-/R/-

Scale = .5"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22304, AND WICK (WOOD TRUSS COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/AIA AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/S) ASTM A653 GRADE 40/50 (W, K/H, S/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A, 2, AND 160B. INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMEAS 2011.11.2002, SEC.3.3. ANY DEVIATION FROM THIS DESIGN SHALL BE INDICATED BY A NOTE. THE TRUSS COMPONENT DESIGN SHOWS THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Alpine Building Components Group, Inc.
Haines City, FL 33844
FL Certificate of Authorization # 547

TC LL	20.0 PSF	REF	R8228- 93312
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045044
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT. LD.	40.0 PSF	SEON-	9866
DUR. FAC.	1.25	REV	
SPACING	24.0"		

JREF- 1T4U8228201


110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. Iw=1.00 GCpl(+/-)=0.18

FL / - / 4 - - / R -		Scale = .5" / Ft.
TC LL	20.0 PSF	REF R8228- 93313
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUR8228 07045028
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT.LD.	40.0 PSF	SEQN- 9888
DUR.FAC.	1.25	
SPACING	24.0"	JREF- 1T4U8228701

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf, Iw=1.00 GCp1(+/-)=0.18

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

In lieu of structural panels on brace TC @ 24" OC, BC @ 24" OC.



Scale = .5" / Ft.

IMPORTANTFURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITH BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH

Haines City, FL 33844
FL Certificate of Authorization

1230 QTY

TC LL	20.0 PSF	REF	R8228- 93314
TC DL	10.0 PSF	DATE	02/14/07
EC DL	10.0 PSF	DRW	HUSR8228 07045029
EC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEGN-	9869
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	174U8228201

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Lt Wedge 2x4 SP #3:

Wind reactions based on MMFRS pressures.


Hipjack supports 3-0-0 setback jacks with no webs.

Top chord overhangs have been checked for loads as indicates. Overhangs not checked for man loads or long-term deflection.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{cpl}(+/-)=0.18$

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



4-2-15 Over 3 Supports →
R=308 U=180 W=4.95"

PLT TYP. Wave

Design Crt: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

7.24.1230

QTY:2 FL/-/4/-/-/R/-


Scale =.5"/ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST (BUILDING COMPONENT SAFETY INFORMATION) PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/S) ASTM A563 GRADE 40/50 (W. K/H/S) GALV. STEEL. ITM BCG PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A, 2, 160B, 160C, 160D, 160E, 160F, 160G, 160H, 160I, 160J, 160K, 160L, 160M, 160N, 160O, 160P, 160Q, 160R, 160S, 160T, 160U, 160V, 160W, 160X, 160Y, 160Z, 160AA, 160AB, 160AC, 160AD, 160AE, 160AF, 160AG, 160AH, 160AI, 160AJ, 160AK, 160AL, 160AM, 160AN, 160AO, 160AP, 160AQ, 160AR, 160AS, 160AT, 160AU, 160AV, 160AW, 160AX, 160AY, 160AZ, 160BA, 160BB, 160BC, 160BD, 160BE, 160BF, 160BG, 160BH, 160BI, 160BJ, 160BK, 160BL, 160BM, 160BN, 160BO, 160BP, 160BQ, 160BR, 160BS, 160BT, 160BU, 160BV, 160BW, 160BX, 160BY, 160BZ, 160CA, 160CB, 160CC, 160CD, 160CE, 160CF, 160CG, 160CH, 160CI, 160CJ, 160CK, 160CL, 160CM, 160CN, 160CO, 160CP, 160CQ, 160CR, 160CS, 160CT, 160CU, 160CV, 160CW, 160CX, 160CY, 160CZ, 160DA, 160DB, 160DC, 160DD, 160DE, 160DF, 160DG, 160DH, 160DI, 160DJ, 160DK, 160DL, 160DM, 160DN, 160DO, 160DP, 160DQ, 160DR, 160DS, 160DT, 160DU, 160DV, 160DW, 160DX, 160DY, 160DZ, 160EA, 160EB, 160EC, 160ED, 160EE, 160EF, 160EG, 160EH, 160EI, 160EJ, 160EK, 160EL, 160EM, 160EN, 160EO, 160EP, 160EQ, 160ER, 160ES, 160ET, 160EU, 160EV, 160EW, 160EX, 160EY, 160EZ, 160FA, 160FB, 160FC, 160FD, 160FE, 160FF, 160FG, 160FH, 160FI, 160FJ, 160FK, 160FL, 160FM, 160FN, 160FO, 160FP, 160FQ, 160FR, 160FS, 160FT, 160FU, 160FV, 160FW, 160FX, 160FY, 160FZ, 160GA, 160GB, 160GC, 160GD, 160GE, 160GF, 160GG, 160GH, 160GI, 160GJ, 160GK, 160GL, 160GM, 160GN, 160GO, 160GP, 160GQ, 160GR, 160GS, 160GT, 160GU, 160GV, 160GW, 160GX, 160GY, 160GZ, 160HA, 160HB, 160HC, 160HD, 160HE, 160HF, 160HG, 160HH, 160HI, 160HJ, 160HK, 160HL, 160HM, 160HN, 160HO, 160HP, 160HQ, 160HR, 160HS, 160HT, 160HU, 160HV, 160HW, 160HX, 160HY, 160HZ, 160IA, 160IB, 160IC, 160ID, 160IE, 160IF, 160IG, 160IH, 160II, 160IJ, 160IK, 160IL, 160IM, 160IN, 160IO, 160IP, 160IQ, 160IR, 160IS, 160IT, 160IU, 160IV, 160IW, 160IX, 160IY, 160IZ, 160JA, 160JB, 160JC, 160JD, 160JE, 160JF, 160JG, 160JH, 160JI, 160JJ, 160JK, 160JL, 160JM, 160JN, 160JO, 160JP, 160JQ, 160JR, 160JS, 160JT, 160JU, 160JV, 160JW, 160JX, 160JY, 160JZ, 160KA, 160KB, 160KC, 160KD, 160KE, 160KF, 160KG, 160KH, 160KI, 160KJ, 160KK, 160KL, 160KM, 160KN, 160KO, 160KP, 160KQ, 160KR, 160KS, 160KT, 160KU, 160KV, 160KW, 160KX, 160KY, 160KZ, 160LA, 160LB, 160LC, 160LD, 160LE, 160LF, 160LG, 160LH, 160LI, 160LJ, 160LK, 160LL, 160LM, 160LN, 160LO, 160LP, 160LQ, 160LR, 160LS, 160LT, 160LU, 160LV, 160LW, 160LX, 160LY, 160LZ, 160MA, 160MB, 160MC, 160MD, 160ME, 160MF, 160MG, 160MH, 160MI, 160MJ, 160MK, 160ML, 160MM, 160MN, 160MO, 160MP, 160MQ, 160MR, 160MS, 160MT, 160MU, 160MV, 160MW, 160MX, 160MY, 160MZ, 160NA, 160NB, 160NC, 160ND, 160NE, 160NF, 160NG, 160NH, 160NI, 160NJ, 160NK, 160NL, 160NM, 160NN, 160NO, 160NP, 160NQ, 160NR, 160NS, 160NT, 160NU, 160NV, 160NW, 160NX, 160NY, 160NZ, 160OA, 160OB, 160OC, 160OD, 160OE, 160OF, 160OG, 160OH, 160OI, 160OJ, 160OK, 160OL, 160OM, 160ON, 160OO, 160OP, 160OQ, 160OR, 160OS, 160OT, 160OU, 160OV, 160OW, 160OX, 160OY, 160OZ, 160PA, 160PB, 160PC, 160PD, 160PE, 160PF, 160PG, 160PH, 160PI, 160PJ, 160PK, 160PL, 160PM, 160PN, 160PO, 160PP, 160PQ, 160PR, 160PS, 160PT, 160PU, 160PV, 160PW, 160PX, 160PY, 160PZ, 160QA, 160QB, 160QC, 160QD, 160QE, 160QF, 160QG, 160QH, 160QI, 160QJ, 160QK, 160QL, 160QM, 160QN, 160QO, 160QP, 160QQ, 160QR, 160QS, 160QT, 160QU, 160QV, 160QW, 160QX, 160QY, 160QZ, 160RA, 160RB, 160RC, 160RD, 160RE, 160RF, 160RG, 160RH, 160RI, 160RJ, 160RK, 160RL, 160RM, 160RN, 160RO, 160RP, 160RQ, 160RR, 160RS, 160RT, 160RU, 160RV, 160RW, 160RX, 160RY, 160RZ, 160SA, 160SB, 160SC, 160SD, 160SE, 160SF, 160SG, 160SH, 160SI, 160SJ, 160SK, 160SL, 160SM, 160SN, 160SO, 160SP, 160SQ, 160SR, 160SS, 160ST, 160SU, 160SV, 160SW, 160SX, 160SY, 160SZ, 160TA, 160TB, 160TC, 160TD, 160TE, 160TF, 160TG, 160TH, 160TI, 160TJ, 160TK, 160TL, 160TM, 160TN, 160TO, 160TP, 160TQ, 160TR, 160TS, 160TT, 160TU, 160TV, 160TW, 160TX, 160TY, 160TZ, 160UA, 160UB, 160UC, 160UD, 160UE, 160UF, 160UG, 160UH, 160UI, 160UJ, 160UK, 160UL, 160UM, 160UN, 160UO, 160UP, 160UQ, 160UR, 160US, 160UT, 160UU, 160UV, 160UW, 160UX, 160UY, 160UZ, 160VA, 160VB, 160VC, 160VD, 160VE, 160VF, 160VG, 160VH, 160VI, 160VJ, 160VK, 160VL, 160VM, 160VN, 160VO, 160VP, 160VQ, 160VR, 160VS, 160VT, 160VU, 160VV, 160VW, 160VX, 160VY, 160VZ, 160WA, 160WB, 160WC, 160WD, 160WE, 160WF, 160WG, 160WH, 160WI, 160WJ, 160WK, 160WL, 160WM, 160WN, 160WO, 160WP, 160WQ, 160WR, 160WS, 160WT, 160WU, 160WV, 160WW, 160WX, 160WY, 160WZ, 160XA, 160XB, 160XC, 160XD, 160XE, 160XF, 160XG, 160XH, 160XI, 160XJ, 160XK, 160XL, 160XM, 160XN, 160XO, 160XP, 160XQ, 160XR, 160XS, 160XT, 160XU, 160XV, 160XW, 160XX, 160XY, 160XZ, 160YA, 160YB, 160YC, 160YD, 160YE, 160YF, 160YG, 160YH, 160YI, 160YJ, 160YK, 160YL, 160YM, 160YN, 160YO, 160YP, 160YQ, 160YR, 160YS, 160YT, 160YU, 160YV, 160YW, 160YX, 160YY, 160YZ, 160ZA, 160ZB, 160ZC, 160ZD, 160ZE, 160ZF, 160ZG, 160ZH, 160ZI, 160ZJ, 160ZK, 160ZL, 160ZM, 160ZN, 160ZO, 160ZP, 160ZQ, 160ZR, 160ZS, 160ZT, 160ZU, 160ZV, 160ZW, 160ZX, 160ZY, 160ZZ

ITW Building Components Group, Inc.
Haines City, FL 33844
PLT Certificate of Authorization # 567



TC LL	20.0 PSF	REF R8228- 93315
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUR8228 07045045
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEQN- 9950
DUR. FAC.	1.25	
SPACING	24.0"	JREF- 1T4U8228201



Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCPI(+/-)=0.18

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0)

7.24.1230


QTY:4

FL-4/-/-/R/-


Scale =.5"/ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 212, ALEXANDRIA, VA, 22314) AND NCCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. BY AREA) AND TPI. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AREA) AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/S/A) ASTM A653 GRADE 40/50 (W. K/M/SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE SPECIFIED ON THIS DESIGN, SECTIONS PER DRAWINGS. A606/2 PLATES SHALL BE 1/4" THICK. UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN INCHES. ALL DIMENSIONS OF TRUSS SHALL BE TO CENTERLINE OF CHORDS. ACCEPTANCE OF PROGRESSIVE ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWS THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITW Building Components Group, Inc.
Haines City, FL 33844
FL Certificate # 1400072200-4-SC2



ITC LL	20.0 PSF	REF R8228- 93316
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045030
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9876
DUR. FAC.	1.25	
SPACING	24.0"	UREF- 1T4U8228201


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, located anywhere in roof, CAT II, EXP 8, wind TC DL=5.0 psf, wind BC DL=5.0 psf. IW=1.00 GCPI(+/-)=0.18

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



2-0-0 Over 3 Supports
R=308 U=180 W=3.5"

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)


7.24.1230

QTY: 4 FL/-/4/-/R/-


Scale = .5"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI BUILDING COMPONENTS SAFETY INFORMATION PUBLISHED BY THE TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES. BY ACPA AND TPI. ITW BCG DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY ACPA) AND TPI. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/T) ASTM A653 GRADE 40/50 (Q. K/P, SSI GALV. STEEL. APPLY PLATES EACH SIDE OF TRUSS JOINTS. BE SURE TO FOLLOW THE CONNECTION PER DRAWING. APPLY 2.5" MIN. OVERLAP OF PLATES. ALL JOINTS SHALL BE WELDED OR BOLTED. ALL JOINTS SHALL BE WELDED OR BOLTED. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. SOLELY FOR THE TRUSS COMPONENTS DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



ITW Building Components Group, Inc.
Haines City, FL 33844
P.O. Certificate # 33844



TC LL	20.0 PSF	REF R8228- 93317
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045031
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT. LD.	40.0 PSF	SEON- 9870
DUR. FAC.	1.25	
SPACING	24.0"	UREF- 1T4U8228201

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3


Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Refer to DWG PIGBACKA1106 or PIGBACKB1106 for piggyback details. PORTION OF TRUSS UNDER PIGGYBACK IS TO BE BRACED @ 24" OC, UNLESS OTHERWISE SPECIFIED.

110 mph wind, 18.35 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. IW=1.00 Gcpl(+/-)=0.18

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



1-0-11 5-1-0 1-0-11
R=350 U=180 W=3.5*
R=350 U=180 W=3.5*

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)



7.24.1230 QTY:2 FL/-/4/-/R/- Scale=.5"/ft.

WARNINGS TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI BUILDING INFORMATION CORPORATION PUBLISHED BY TPI TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA 22314 AND WICKI WOOD TRUSS COMPANY OF AMERICA, 6300 ENTERPRISE LANE, MOULTON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/R) ASTM A653 GRADE 40/50 (W. K/M/SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z.

ANY INSPECTION OF PLATES FOLLOWED BY TPI SHALL BE PER AMES 430 OR TPI-11-2002 SEC.3 FOR A SEAL ON THIS DESIGN. PROVIDES PROFESSIONAL, ENGINEERING RESPONSIBILITY. SOLICIT FOR THE TRUSS COMPONENT DESIGN AND CONSTRUCTION. ANY USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER AMS/TPI 1 SEC. 2.



TC LL	20.0 PSF	REF	R8228- 93318
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCUSR8228 07045032
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEON-	9902
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1T4U8228201

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3


Wind reactions based on MWFRS pressures.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Refer to DWG PIGBACKA1106 or PIGBACKB1106 for piggyback details. PORTION OF TRUSS UNDER PIGGYBACK IS TO BE BRACED @ 24" OC, UNLESS OTHERWISE SPECIFIED.

110 mph wind, 18.85 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf. $I_w=1.00$ $G_{CPI}(+/-)=0.18$

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



R=350 U=180 W=3.5"
9-1-0 Over 2 Supports
3-0-11
1-1-0
3-0-11
R=350 U=180 W=3.5"

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)



QTY:2 FL/-/4/-/R/-

Scale = .5"/ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSJ (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE STRUCTURAL STEEL INSTITUTE, 218 NORTH ZEEB ROAD, PITTSBURGH, PA 15222-1000, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. JTW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/AIA) AND TPI. JTW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/RS) ASTM A653 GRADE 40/60 (W. K/H/SS) GALV. STEEL. APPLY ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER AMER AS OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES THE ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN AND THE QUALITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



IC LL	20.0 PSF	REF R8228- 93319
TC DL	10.0 PSF	DATE 02/14/07
BC DL	10.0 PSF	DRW HCUSR8228 07045033
BC LL	0.0 PSF	HC-ENG JB/WHK
TOT.LD.	40.0 PSF	SEON- 9903
DUR.FAC.	1.25	
SPACING	24.0"	JREF- 1T4U8228Z01

110 mph wind, 18.98 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf Iw=1.00 Gcpi(+/-)=0.18

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Refer to DWG PIGBACKA1106 or PIGBACKB1106 for piggyback details. PORTION OF TRUSS UNDER PIGGYBACK IS TO BE BRACED @ 24" OC, UNLESS OTHERWISE SPECIFIED.




Diagram of a continuous beam with two spans. The left span is 9'-1.0" long, and the right span is 9'-7.3" long. The beam is supported by two supports. The beam is labeled "R=350 U=180 W=3.5" at both ends.

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)

$$Cq/RT=1.00(1.25)/10(0)$$

7.24.1230

QTY: 1

FL/-/4/-/-/R/-

Scale = .5" / Ft.

WARNING PRIORS BEING COUNDED EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING REFER TO AC308 (BUILDING COMPONENT SAFETY INFORMATION). PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND NWC (WOOD TRUSS COUNCIL OF AMERICA, 6500 ROCKY HILL ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED FOR CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID GELING.

****IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITM BCG, INC. SHALL NOT**

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF MDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ITM BCG

PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2

DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT

BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

JTW Building Components Group, Inc.
Haines City, FL 33844
F1 Certificate of Authorization #

Feb 14 07

TC LL	20.0 PSF	REF	R8228- 93320
TC DL	10.0 PSF	DATE	02/14/07
BC DL	10.0 PSF	DRW	HCU8R8228 07045034
BC LL	0.0 PSF	HC-ENG	JB/WHK
TOT.LD.	40.0 PSF	SEQN-	9904
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1T4U8228Z01

THIS DETAIL IS TO BE USED WHEN CONTINUOUS LATERAL BRACING (CLB) IS SPECIFIED ON AN ALPINE TRUSS DESIGN BUT AN ALTERNATIVE WEB BRACING METHOD IS DESIRED.

THIS DETAIL IS ONLY APPLICABLE FOR CHANGING THE SPECIFIED CLB SHOWN ON SINGLE PLY SEALED DESIGNS TO T-BRACING OR SCAB BRACING.


ALTERNATIVE BRACING SPECIFIED IN CHART BELOW MAY BE CONSERVATIVE.
FOR MINIMUM ALTERNATIVE BRACING, RE-RUN DESIGN WITH APPROPRIATE
BRACING.

WEB MEMBER SIZE	SPECIFIED CLB BRACING	ALTERNATIVE T OR L-BRACE	BRACING SCAB BRACE
2X3 OR 2X4	1 ROW	2X4	1-2X4
2X3 OR 2X4	2 ROWS	2X6	2-2X4
2X6	1 ROW	2X4	1-2X6
2X6	2 ROWS	2X6	2-2X4(*)
2X8	1 ROW	2X6	1-2X8
2X8	2 ROWS	2X6	2-2X6(*)


T-BRACE, I-BRACE AND SCAB BRACE TO BE SAME SPECIES AND GRADE OR BETTER THAN WEB MEMBER UNLESS SPECIFIED OTHERWISE ON ENGINEER'S SEALED DESIGN.

(*) CENTER SCAB ON WIDE FACE OF WEB. APPLY (1) SCAB TO EACH FACE OF WEB.

APPLY TO EITHER SIDE OF WEB NARROW FACE
ATTACH WITH 10D BOX OR GUN
(0.128" x 3" MIN) NAILS.
AT 6" O.C. BRACE IS A
MINIMUM 80% OF WEB
MEMBER LENGTH




APPLY SCAB(S) TO WIDE FACE OF WEB
NO MORE THAN (1) SCAB PER FACE.
ATTACH WITH 10d BOX OR GUN
(0.128"x 3", MIN) NAILS.
AT 6" O.C. BRACE IS A MINIMUM
80% OF WEB MEMBER LENGTH




THIS DRAWING REPLACES DRAWING 579,640

TO LL	PSF	REF	CLB SUBST.
TC DL	PSF	DATE	11/1/06
BC DL	PSF	DRWG	BRCLBSUB1106
BC LL	PSF	-ENG	MLH/KAR
TOT	LD.		
DUR. FAC.			
SPACING			



ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS AND THE CONNECTIONS TO THE BUILDING. THE TRUSS SHALL BE DESIGNED TO SUPPORT THE DEAD AND LIVE LOADS AS SPECIFIED IN THE SPECIFICATIONS. THE TRUSS SHALL BE DESIGNED TO RESIST THE EFFECTS OF WIND, SEISMIC, AND OTHER APPLICABLE LOADS. THE TRUSS SHALL BE DESIGNED TO MAINTAIN ITS INTEGRITY AND STABILITY UNDER ALL APPLICABLE LOADS. THE TRUSS SHALL BE DESIGNED TO BE EASILY ASSEMBLED AND DISASSEMBLED FOR TRANSPORT AND ERECTION. THE TRUSS SHALL BE DESIGNED TO BE COMPATIBLE WITH THE BUILDING STRUCTURE AND FINISHES. THE TRUSS SHALL BE DESIGNED TO BE MAINTAINABLE AND ACCESSIBLE FOR INSPECTION AND REPAIR. THE TRUSS SHALL BE DESIGNED TO BE PROTECTED AGAINST CORROSION AND OTHER ENVIRONMENTAL EFFECTS. THE TRUSS SHALL BE DESIGNED TO BE IDENTIFIABLE BY THE BUILDING OWNER AND THE BUILDING DEPARTMENT. THE TRUSS SHALL BE DESIGNED TO BE REMOVED WITHOUT CAUSING DAMAGE TO THE BUILDING STRUCTURE OR FINISHES. THE TRUSS SHALL BE DESIGNED TO BE REUSED OR RECYCLED AT THE END OF ITS SERVICE LIFE. THE TRUSS SHALL BE DESIGNED TO BE COST-EFFECTIVE AND ECONOMICALLY FEASIBLE. THE TRUSS SHALL BE DESIGNED TO BE SAFELY AND SECURELY STORED AND TRANSPORTED. THE TRUSS SHALL BE DESIGNED TO BE EASILY AND SAFELY ERECTED AND DEMOLISHED. THE TRUSS SHALL BE DESIGNED TO BE COMPATIBLE WITH THE BUILDING'S AESTHETIC AND HISTORIC CHARACTER. THE TRUSS SHALL BE DESIGNED TO BE PROTECTED AGAINST VANDALISM AND THEFT. THE TRUSS SHALL BE DESIGNED TO BE MAINTAINABLE AND ACCESSIBLE FOR INSPECTION AND REPAIR. THE TRUSS SHALL BE DESIGNED TO BE PROTECTED AGAINST CORROSION AND OTHER ENVIRONMENTAL EFFECTS. THE TRUSS SHALL BE DESIGNED TO BE IDENTIFIABLE BY THE BUILDING OWNER AND THE BUILDING DEPARTMENT. THE TRUSS SHALL BE DESIGNED TO BE REMOVED WITHOUT CAUSING DAMAGE TO THE BUILDING STRUCTURE OR FINISHES. THE TRUSS SHALL BE DESIGNED TO BE REUSED OR RECYCLED AT THE END OF ITS SERVICE LIFE. THE TRUSS SHALL BE DESIGNED TO BE COST-EFFECTIVE AND ECONOMICALLY FEASIBLE. THE TRUSS SHALL BE DESIGNED TO BE SAFELY AND SECURELY STORED AND TRANSPORTED. THE TRUSS SHALL BE DESIGNED TO BE EASILY AND SAFELY ERECTED AND DEMOLISHED. THE TRUSS SHALL BE DESIGNED TO BE COMPATIBLE WITH THE BUILDING'S AESTHETIC AND HISTORIC CHARACTER. THE TRUSS SHALL BE DESIGNED TO BE PROTECTED AGAINST VANDALISM AND THEFT.




BEARING BLOCK NAIL SPACING DETAIL

MINIMUM SPACING FOR SINGLE BEARING BLOCK IS SHOWN. DOUBLE NAIL SPACINGS AND STAGGER NAILING FOR TWO BLOCKS. GREATER SPACING MAY BE REQUIRED TO AVOID SPLITTING.

- A - EDGE DISTANCE AND SPACING BETWEEN STAGGERED ROWS OF NAILS (6 NAIL DIAMETERS)
- B - SPACING OF NAILS IN A ROW (12 NAIL DIAMETERS)
- C - END DISTANCE (15 NAIL DIAMETERS)

IF NAIL HOLES ARE PREBORED, SOME SPACING MAY BE REDUCED BY THE AMOUNTS GIVEN BELOW:
 • SPACING MAY BE REDUCED BY 50%
 • SPACING MAY BE REDUCED BY 33%

BEARING BLOCK TO BE SAME SIZE AND SPECIES AS BOTTOM CHORD. BLOCKS MAY BE ANY GRADE WITHIN THE SPECIES, PROVIDED THE COMPRESSION PERPENDICULAR TO GRAIN VALUE (Fc-perp) IS AT LEAST THAT OF THE CHORD.




MAXIMUM NUMBER OF NAIL LINES PARALLEL TO GRAIN

NAIL TYPE	CHORD SIZE									
	2X4	2X6	2X8	2X10	2X12					
8d BOX (0.113"X 2.5", MIN)	3	6	9	12	15					
10d BOX (0.128"X 3", MIN)	3	5	7	10	12					
12d BOX (0.128"X 3.25", MIN)	3	5	7	10	12					
16d BOX (0.135"X 3.5", MIN)	3	5	7	10	12					
20d BOX (0.148"X 4", MIN)	2	4	5	6	8					
8d COMMON (0.131"X 2.5", MIN)	3	5	7	10	12					
10d COMMON (0.148"X 3", MIN)	2	4	6	8	10					
12d COMMON (0.148"X 3.25", MIN)	2	4	6	8	10					
16d COMMON (0.162"X 3.5", MIN)	2	4	6	8	10					
GUN (0.120"X 2.5", MIN)	3	6	8	11	14					
GUN (0.131"X 2.5", MIN)	3	5	7	10	12					
GUN (0.120"X 3", MIN)	3	6	8	11	14					
GUN (0.131"X 3", MIN)	3	5	7	10	12					

MINIMUM NAIL SPACING DISTANCES

NAIL TYPE	DISTANCES		
	A	B*	C**
8d BOX (0.113"X 2.5", MIN)	3/4"	1 3/8"	1 3/4"
10d BOX (0.128"X 3", MIN)	7/8"	1 5/8"	2"
12d BOX (0.128"X 3.25", MIN)	7/8"	1 5/8"	2"
16d BOX (0.135"X 3.5", MIN)	7/8"	1 5/8"	2 1/8"
20d BOX (0.148"X 4", MIN)	1"	1 7/8"	2 1/4"
8d COMMON (0.131"X 2.5", MIN)	7/8"	1 5/8"	2"
10d COMMON (0.148"X 3", MIN)	1"	1 7/8"	2 1/4"
12d COMMON (0.148"X 3.25", MIN)	1"	1 7/8"	2 1/4"
16d COMMON (0.162"X 3.5", MIN)	1"	2"	2 1/2"
GUN (0.120"X 2.5", MIN)	3/4"	1 1/2"	1 7/8"
GUN (0.131"X 2.5", MIN)	7/8"	1 5/8"	2"
GUN (0.120"X 3", MIN)	3/4"	1 1/2"	1 7/8"
GUN (0.131"X 3", MIN)	7/8"	1 5/8"	2"

THIS DRAWING REPLACES DRAWING B139 AND CNBRGBLK0699



REF	BEARING BLOCK
DATE	11/1/06
DRWG	CNBRGBLK1106
-ENG	SJP/KAR

ALPINE
 ENGINEERED PRODUCTS, INC.
 POMPANO BEACH, FLORIDA

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BUILDING. REFER TO THE ALPINE TRUSS DESIGN MANUAL FOR DETAILED INSTRUCTIONS. THE TRUSS DESIGNER SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO FOLLOW THE TRUSS DESIGN MANUAL OR THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE TRUSS DESIGNER. THE TRUSS DESIGNER SHALL BE RESPONSIBLE FOR THE STABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.

GROUP A:		
SPRUCE-PINE-FIR		HEM-FIR
#1 / #2	STANDARD	#2
#3	STUD	#3
		STANDARD
DOUGLAS FIR-LARCH		SOUTHERN PINE
#3		#3
STUD		STUD
STANDARD		STANDARD

GROUP B:

HEM-FIR

#1 & BTR

#1

SOUTHERN PINE

#1

#2

DOUGLAS FIR-LARCH

#1


#2

LIVE LOAD DEFLECTION CRITERIA IS $L/240$.
 PROVIDE UPLIFT CONNECTIONS FOR 80 PLF OVER
 CONTINUOUS BEARING (5 PSF TC DEAD LOAD).
 GABLE END SUPPORTS LOAD FROM 4' 0"
 OUTLOOKERS WITH 2' 0" OVERHANG, OR 12"
 PLYWOOD OVERHANG.

* ATTACH EACH "L" BRACE WITH 10d NAILS.
* FOR (1) "L" BRACE: SPACE NAILS AT 2' O.C.
IN 18" END ZONES AND 4' O.C. BETWEEN ZONES.
** FOR (2) "L" BRACES: SPACE NAILS AT 3' O.C.
IN 18" END ZONES AND 8' O.C. BETWEEN ZONES.
"L" BRACING MUST BE A MINIMUM OF 80% OF WEB
MEMBER LENGTH.

CABLE VERTICAL PLATE SIZES	
VERTICAL LENGTH	NO SPLICED
LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0", BUT LESS THAN 11' 6"	2X4
GREATER THAN 11' 6"	2.5X4

+ REFER TO COMMON TRUSS DESIGN FOR
PEAK, SPLICE, AND HEEL PLATES.



DIAGONAL BRACE OPTION:
VERTICAL LENGTH MAY BE
DOUBLED WHEN DIAGONAL
BRACE IS USED. CONNECT
DIAGONAL BRACE FOR 600#
AT EACH END. MAX WEB
TOTAL LENGTH IS 14'.

VERTICAL LENGTH SHOWN
IN TABLE ABOVE.

CONNECT DIAGONAL AT
MIDPOINT OF VERTICAL WEB


REFER TO CHART ABOVE FOR MAX. DABLE VERTICAL LENGTH

ALPINE

ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA

THESE REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST BUILDING COMPONENT SAFETY INTERPRETATION, PUBLISHED BY TPI STEEL PLATE INSTITUTE, 218 NORTH LEE STR., SUITE 314, ALEXANDRIA, VA 22304 AND VISCIO TRUSS COUNCIL OF AMERICA, 6400 OVERVIEW LN, WASHINGTON, VI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.


FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR, ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN, ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS NATIONAL DESIGN SPEC. 40.60 (V/A/K/H/S/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED IN THIS DESIGN, POSITION PER DRAWINGS 1604-2. AN INSPECTION OF PLATES FOLLOWED BY SHALL BE PER ANNEAS OF TPI 1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUSTAINABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.



MAX. SPACING 24.0"

REF	ASCE7-02-CAB11015
DATE	11/1/06
DRWG	A11015EE1106
-ENG	

CABLE DETAIL FOR LET-IN VERTICALS



GABLE VERTICAL PLATE SIZES

VERTICAL LENGTH BETWEEN CHORDS	PLATE SIZE	IF PLATES OVERLAP*
LESS THAN 4' 0"	1X4 OR 2X3	2X8
GREATER THAN 4' 0", BUT LESS THAN 11' 6"	2X4	2X8
GREATER THAN 11' 6"	2.5X4	2.5X8

* REFER TO ENGINEERED TRUSS DESIGN FOR PEAK, SPLICE, WEB AND HEEL PLATES.

* IF GABLE VERTICAL PLATES OVERLAP, USE A SINGLE PLATE TO SPAN THE WEB.

EXAMPLE:

PROVIDE CONNECTIONS FOR UPLIFT SPECIFIED ON THE ENGINEERED TRUSS DESIGN.

ATTACH EACH "T" REINFORCING MEMBER WITH:

10d COMMON (0.148" X 3.125") TOENAILS AT 4" O.C. PLUS

(4) 16d COMMON (0.162" X 3.5") TOENAILS IN TOP AND BOTTOM CHORD.

GUN DRIVEN NAILS:

8d COMMON (0.131" X 2.5") TOENAILS AT 4" O.C. PLUS

(4) TOENAILS IN TOP AND BOTTOM CHORD.

THIS DETAIL TO BE USED WITH THE APPROPRIATE ALPINE GABLE DETAIL FOR ASCE OR SBCCI WIND LOAD.

ASCE 7-93 GABLE DETAIL DRAWINGS

AL1015EN1103, A10015EN1103, A09015EN1103, A08015EN1103, A07015EN1103

AL1030EN1103, A10030EN1103, A09030EN1103, A08030EN1103, A07030EN1103

ASCE 7-98 GABLE DETAIL DRAWINGS

AL1015EC1103, A12015EC1103, A11015EC1103, A08515EC1103


AL1030EC1103, A12030EC1103, A11030EC1103, A08530EC1103

ASCE 7-02 GABLE DETAIL DRAWINGS

AL1015EB0405, A12015EB0405, A11015EB0405, A08515EB0405, A07015EB0405

AL1030EB0405, A12030EB0405, A11030EB0405, A08530EB0405, A07030EB0405

SEE APPROPRIATE ALPINE GABLE DETAIL (ASCE OR SBCCI WIND LOAD) FOR MAXIMUM UNREINFORCED GABLE VERTICAL LENGTH.



TO CONVERT FROM "L" TO "T" REINFORCING MEMBERS, MULTIPLY "T" FACTOR BY LENGTH (BASED ON GABLE VERTICAL SPECIES, GRADE AND SPACING) FOR (1) 2X4 "L" BRACE, GROUP A, OBTAINED FROM THE APPROPRIATE ALPINE GABLE DETAIL FOR ASCE OR SBCCI WIND LOAD.

MAXIMUM ALLOWABLE "T" REINFORCED GABLE VERTICAL LENGTH IS 14' FROM TOP TO BOTTOM CHORD.

WEB LENGTH INCREASE W/ "T" BRACE

WIND SPEED "T" REINFORCED MEMBER SIZE	SBCCI	ASCE
110 MPH 2x4	10 %	10 %
110 MPH 2x6	40 %	50 %
110 MPH 2x4	10 %	10 %
110 MPH 2x6	50 %	50 %
100 MPH 2x4	10 %	10 %
100 MPH 2x6	30 %	50 %
100 MPH 2x4	10 %	10 %
100 MPH 2x6	40 %	40 %
90 MPH 2x4	20 %	10 %
90 MPH 2x6	20 %	10 %
15 FT 2x6	20 %	40 %
90 MPH 2x4	10 %	10 %
90 MPH 2x6	30 %	50 %
80 MPH 2x4	10 %	20 %
80 MPH 2x6	20 %	30 %
30 FT 2x6	10 %	10 %
80 MPH 2x4	20 %	10 %
80 MPH 2x6	20 %	40 %
30 FT 2x6	0 %	20 %
70 MPH 2x4	0 %	20 %
70 MPH 2x6	0 %	20 %
30 FT 2x4	10 %	20 %
30 FT 2x6	10 %	30 %

EXAMPLE:

ASCE WIND SPEED = 100 MPH

MEAN ROOF HEIGHT = 30 FT

GABLE VERTICAL = 24" O.C. SP #3

"T" REINFORCING MEMBER SIZE = 2X4

"T" BRACE INCREASE (FROM ABOVE) = 10% = 1.10

(1) 2X4 "T" BRACE LENGTH = 6' 7"

MAXIMUM "T" REINFORCED GABLE VERTICAL LENGTH 1.10 x 6' 7" = 7' 3"

THIS DRAWING REPLACES DRAWINGS GAB98117 876,719 & HC26294035

ALPINE

ALPINE ENGINEERED PRODUCTS, INC.
POMPAHO BEACH, FLORIDA

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY TPI TRUSS PLATE MANUFACTURER, 2100 NORTH 31ST AVE., SUITE 312, ALEXANDRIA, VA 22304, AND TPI TRUSS PLATE MANUFACTURER, 2100 NORTH 31ST AVE., SUITE 312, ALEXANDRIA, VA 22304, FOR ADDITIONAL INFORMATION ON THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT: FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN, ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPECIFICATION FOR WOOD) AND TPI ALPINE CONNECTIONS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPECIFICATION FOR WOOD). THIS DESIGN IS THE PROPERTY OF ALPINE ENGINEERED PRODUCTS, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. ANY REPRODUCTION OR TRANSMISSION OF THIS DESIGN WITHOUT THE WRITTEN PERMISSION OF ALPINE ENGINEERED PRODUCTS, INC. SHALL BE PER ANNEX A3 OF TPI 1-2008 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE BY A PROFESSIONAL ENGINEER. ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.

JAMES E. COLLINS, JR.

No. 62212

STATE OF FLORIDA

PROFESSIONAL ENGINEER

REF	LET-IN VERT
DATE	11/1/06
DRWG	GBLETTN1106
ENG	DLJ/KAR
MAX TOT. LD.	60 PSF
DUR. FAC.	ANY
MAX SPACING	24.0"

PIGGYBACK DETAIL


100 MPH WIND, 30.00 FT MEAN HGT, ASCE 7-02, CLOSED BLDG,
LOCATED ANYWHERE IN ROOF, CAT II, EXP C,
WIND TC DL=5.0 PSF, WIND BC DL=5.0 PSF.

80 MPH WIND, 30.00 FT MEAN HGT, SBC,
ENCLOSED BLDG, LOCATED ANYWHERE IN ROOF
WIND TC DL=5.0 PSF, WIND BC DL=5.0 PSF.

100 MPH WIND, 30.00 FT MEAN HGT, ASCE 7-98,
CLOSED BLDG, LOCATED ANYWHERE IN ROOF, CAT II,
EXP. C, WIND TC DL=5.0 PSF, WIND BC DL=5.0 PSF.


NOTE: TOP CHORDS OF TRUSSES SUPPORTING PIGGYBACK CAP TRUSSES MUST BE ADEQUATELY BRACED BY SHEATHING OR PURLINS. PROVIDE DIAGONAL BRACING OR OTHER SUITABLE ANCHORAGE TO PERMANENTLY RESTRAIN PURLINS.

DETAIL A




PIGGYBACK CAP TRUSS TOENAILED TO ALL TOP CHORD
BRACING WITH (2) 10d COMMON (0.148"x3") NAILS.
* 12" MIN RIGID SHEATHING OVERLAP WITH 8d COMMON (0.131"x2.5")
OR GUN NAILS IN OVERLAP ZONE SPACED AT 4" O.C.

DETAIL B



PIGGYBACK CAP TRUSS TOENAILED TO ALL TOP
CHORD BRACING WITH (2) 10d COMMON (0.148"x3") NAILS AND
SECURED WITH 2x4 #3 GRADE SCAB (1 SIDE ONLY)
ATTACHED WITH 10d COMMON NAILS AT 4" O.C.

DETAIL C



CAP TRUSS TOENAILED TO TOP CHORD BRACING AND SECURED WITH 3x8 TRULOX PLATES (EACH FACE) AT EACH END AND AT 1/3 POINTS.
CIRCLED NUMBER INDICATES REQUIRED NUMBER OF 0.120" X 1.375" NAILS PER FACE. SEE DRAWING 160TL FOR TRULOX INFORMATION.

IN LIEU OF TRULOX CONNECTORS, ALPINE 62PB SPECIAL
PIGGYBACK CONNECTORS MAY BE USED. SHOP APPLY
TOOTHED PORTION, FIELD ATTACH TO MATING TRUSS
WITH (4) 0.120" X 0.375" NAILS MINIMUM EACH FACE.

(4) 8d COMMON NAILS (0.131"x2.5")

8" X 8" X 1/2" RATED SHEATHING GUSSETS (EACH
FACE) MAY BE USED IN LIEU OF TRULOX PLATES.
ATTACH WITH (8) 8d COMMON NAILS PER GUSSET.
(4) IN CAP BC AND (4) IN BASE TRUSS FLAT TC.


THIS DRAWING REPLACES DRAWINGS 561.670 & 961.860

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND
ERECTING. REFER TO BEST BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY THE TRUSS
INSTITUTE, 1500 ENTERPRISE LN, MADISON, WI, 53719, FOR SAFETY PRACTICES PRIOR TO PERFECTING THESE
FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL
PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED
PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN, ANY FAILURE TO
BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING, SPEC,
BRACING OF TRUSSES. DESIGN CONNECTORS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC,
AT 4.6.4.3) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA. A/H/S/S/20 AS THE 60SS GRADE
STEEL. ALL PLATES SHALL BE TOENAILED TO ALL TOP CHORD BRACING WITH (2) 10d COMMON (0.148"x3") NAILS.
LOCATED ON THIS DESIGN POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FILLED IN BY
FIELD SHALL BE PER ANNEX A3 OF TPI 1-2008 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF
PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE
SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING
DESIGNER, PER ANSI/TPI 1 SEC. 2.

ALPINE

ALPINE ENGINEERED PRODUCTS, INC.
POMPAHO BEACH, FLORIDA



TC IL	PSF	REF	PIGGYBACK
TC DL	PSF	DATE	11/1/06
TC BC	PSF	DRWG	PIGGYBACK1106
TC LT	PSF	-ENG	DLJ/KAR
OT LD	MAX 60 PSF		
DUR. FAC.	1.15		
SPACING	24.0"		

TOP CHORD 2X4 #2 OR BETTER
BOT CHORD 2X4 #2 OR BETTER
WEBS 2X4 #3 OR BETTER

PIGGYBACK DETAIL

REFER TO SEALED DESIGN FOR DASHED PLATES.

SPACE PIGGYBACK VERTICALS AT 4' OC MAX.

TOP AND BOTTOM CHORD SPLICES MUST BE STAGGERED SO THAT ONE SPLICE IS NOT DIRECTLY OVER ANOTHER.

PIGGYBACK BOTTOM CHORD MAY BE OMITTED. ATTACH VERTICAL WEBS TO TRUSS TOP CHORD WITH 1.5X3 PLATE.

ATTACH PURLINS TO TOP OF FLAT TOP CHORD. IF PIGGYBACK IS SOLID LUMBER OR THE BOTTOM CHORD IS OMITTED PURLINS MAY BE APPLIED BENEATH THE TOP CHORD OF SUPPORTING TRUSS.

REFER TO ENGINEER'S SEALED DESIGN FOR REQUIRED PURLIN SPACING.

THIS DETAIL IS APPLICABLE FOR THE FOLLOWING WIND CONDITIONS:

130 MPH WIND, 30' MEAN HGT, ASCE 7-02, CLOSED BLDG, LOCATED ANYWHERE IN ROOF, CAT II, EXP C,

WIND TC DL=5 PSF, WIND BC DL=5 PSF

110 MPH WIND, 30' MEAN HGT, SBC

ENCLOSED BLDG, LOCATED ANYWHERE IN ROOF

WIND TC DL=5 PSF, WIND BC DL=5 PSF

FRONT FACE (E*) PLATES MAY BE OFFSET FROM BACK FACE PLATES AS LONG AS BOTH FACES ARE SPACED 4' OC MAX.

130 MPH WIND, 30' MEAN HGT, ASCE 7-98, CLOSED BLDG, LOCATED ANYWHERE IN ROOF, CAT II, EXP C, WIND TC DL=5 PSF, WIND BC DL=5 PSF


(4) 6d BOX (0.089" X 2" MIN) NAILS.

8" X 8" X 1/2" RATED SHEATHING GUSSETERS (EACH FACE) MAY BE USED IN LIEU OF TRULOX PLATES. ATTACH WITH (8) 6d BOX (0.089" X 2" MIN) NAILS PER GUSSET.

(4) IN CAP BC AND (4) IN BASE TRUSS FLAT TC.


JOINT TYPE	SPANS UP TO			
	30'	34'	38'	52'
A	2X4	2.5X4	2.5X4	3X5
B	4X6	5X6	5X6	5X6
C	1.5X3	1.5X4	1.5X4	1.5X4
D	5X4	5X5	5X5	5X6
E	4X6 OR 3X6 TRULOX AT 4' OC, ROTATED VERTICALLY			

ATTACH TRULOX PLATES WITH (8) 0.120" X 1.375" NAILS, OR EQUAL, PER FACE PER PLY. (4) NAILS IN EACH MEMBER TO BE CONNECTED. REFER TO DRAWING 160 TL FOR TRULOX INFORMATION.



EITHER PLATE LOCATION IS ACCEPTABLE


OPTIONAL SPLICE



*ATTACH PIGGYBACK WITH 3X8 TRULOX OR ALPINE PIGGYBACK SPECIAL PLATE.

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY TPI, CROSS PLATE TRUSS, INC., 1000 N. WILSON AVE., SUITE 300, CHICAGO, IL 60642, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT: FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN, ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF U.S. NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION (NDS) AND THE 2005 INTERNATIONAL RESIDENTIAL CODE (IRC). (ALPINE) GALV. STEEL PLATES TO BE APPLIED TO EACH-2. ANY INSPECTION OF PLATES FOLLOWED BY LOCAL, PER ANNEX A3 OF TPI 1-2008 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.



WEB BRACING CHART		REPLACES DRAWINGS 634,016 634,017 & 647,045	
WEB LENGTH	REQUIRED BRACING	MAX LOADING	REF PIGGYBACK
0' TO 7'9"	NO BRACING	55 PSF AT	DATE 11/1/06
7'9" TO 10'	1x4 "T" BRACE. SAME GRADE, SPECIES AS WEB MEMBER. OR BETTER, AND 80% LENGTH OF WEB MEMBER. ATTACH WITH 8d BOX (0.113" X 2.5" MIN) NAILS AT 4" OC.	1.33 PSF AT FAC.	DRWG PIGBACKB1106
10' TO 14'	2x4 "T" BRACE. SAME GRADE, SPECIES AS WEB MEMBER. OR BETTER, AND 80% LENGTH OF WEB MEMBER. ATTACH WITH 16d BOX (0.135" X 3.5" MIN) NAILS AT 4" OC.	50 PSF AT	-ENG DLJ/KAR
* PIGGYBACK SPECIAL PLATE		47 PSF AT	
ATTACH TEETH TO THE PIGGYBACK AT THE TIME OF FABRICATION. ATTACH TO SUPPORTING TRUSS WITH (4) 0.120" X 1.375" NAILS PER FACE PER PLY. APPLY PIGGYBACK SPECIAL PLATE TO EACH TRUSS FACE AND SPACE 4' OC OR LESS.		1.15 DUR. FAC.	
SPACING 24.0"			

Notice of Intent for Preventative Treatment for Termites

(As required by Florida Building Code 104.2.6)

Date: 2/14/07

lot 5 Kensington - 228 S.W. Royal Court

(Address of Treatment or Lot/Block of Treatment)

Lake City, FL
City 32024

Florida Pest Control & Chemical Co.

www.flapest.com

Product to be used: Bora-Care Termiticide (Wood Treatment)

Chemical to be used: 23% Disodium Octaborate Tetrahydrate

Application will be performed onto structural wood at dried-in stage of construction. Bora-Care Termiticide application shall be applied according to EPA registered label directions as stated in the Florida Building Code Section 1816.1

(Information to be provided to local building code offices prior to concrete foundation installation.)

6/05 ©