

FOUNDATION PLAN  
SCALE: 3/16" = 1'-0"

INTERIOR BEARING WALLS:  
IT IS THE BUILDING CONTRACTOR'S RESPONSIBILITY TO VERIFY WITH THE TRUSS ENGINEERING ANY AND ALL INTERIOR BEARING WALL LOCATIONS AND FURNISH THE ENGINEER OR ARCHITECT OF RECORD TRUSS INFO SO THICKENED FOOTING'S CAN BE SIZED AND LOCATED ON THE FOUNDATION PLAN.

ALL CONCRETE 3,000 PSI  
COMPRESSIVE STRENGTH  
AT 28 DAYS

ALL MESH 6X6-10/10  
WELDED WIRE MESH

6-MIL POLY VAPOR BARRIER  
DOUBLE MESH ALONG EDGE -  
24" WIDE - FULL PERIMETER  
2 - # 5'S, CONTINUOUS

SECTION  
SCALE: 3/4" = 1'-0

C  
S.1

NOTE: ALL DRAWINGS NOT TO BE SCALED, WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS

NOTE:  
THE DESIGN WIND SPEED FOR THIS  
PROJECT IS 130 MPH PER 2017 PER R301.2.1.1  
AND LOCAL JURISDICTION REQUIREMENTS


NOTE:  
ADDED FILL SHALL BE APPLIED IN 8" LIFTS -  
EA. LIFT SHALL BE COMPACTED TO 98% DRY  
COMPACTION PER THE "MODIFIED PROCTOR"  
METHOD.

NOTE:  
PLUMBING CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP  
DRAWINGS INDICATING ALL PLUMBING WORK, INCLUDING ALL  
PLUMBING LINE LOCATIONS AND RISER DIAGRAM - CONTR  
SHALL PROVIDE 1 COPY OF AS-BUILT DWGS TO OWNER AND  
1 COPY TO THE PERMIT ISSUING AUTHORITY.

NOTE:  
H.V.A.C. CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP  
DRAWINGS INDICATING ALL H.V.A.C. WORK, INCLUDING ALL  
DUCTWORK LOC., SIZES, LINES, EQUIPMENT SCH. & BALANCING  
REPORT - CONTR SHALL PROVIDE 1 COPY OF AS-BUILT DWGS  
TO OWNER & 1 COPY TO THE PERMIT ISSUING AUTHORITY.


## CONCRETE / MASONRY / METALS GENERAL NOTES:

- DESIGN SOIL BEARING PRESSURE: 1000 PSF.
- EXPANSIVE SOILS: WHERE DIRECTED BY THE SOILS ENGINEER, SOIL AUGMENTATION PER THE SOILS ENGINEER'S SPECIFICATIONS SHALL BE IMPLEMENTED PRIOR TO PLACING ANY FOUNDATIONS - TESTS AS SPECIFIED SHALL BE PREFORMED TO DETERMINE THE SUITABILITY OF THE SUB-GRADE TO SUPPORT THE DESIGN LOADS.
- CLEAN SAND FILL OVER STRIPPED AND COMPACTED EXISTING GD. SHALL BE PLACED IN 12" LIFTS. BOTH SUB-SOIL AND FILL COMPACTION SHALL BE NOT LESS THAN 98% AS MEASURED BY A MODIFIED PROCTOR TEST AT THE RATE OF ONE TEST FOR EACH 1500 SF OF BUILDING PAD AREA, OR FRACTION THEREOF, FOR EACH 12" LIFT.
- REINFORCING STEEL SHALL BE GRADE 60 AND MEET THE REQUIREMENTS OF ASTM A615, ALL BENDS SHALL BE MADE COLD.
- WELDED WIRE MESH SLAB REINFORCING SHALL MEET THE REQUIREMENTS OF ASTM A185 - MIN. YIELD STRESS = 85 KSI.
- CONCRETE SHALL BE STANDARD MIX F<sub>c</sub> = 3000 PSI FOR ALL FTGS, SLABS, COLUMNS AND BEAMS OR SHALL BE STANDARD PUMP MIX F<sub>c</sub> = 3000 PSI. STRENGTH SHALL BE ATTAINED WITHIN 28 DAYS OF PLACEMENT. MIXING, PLACING AND FINISHING SHALL BE AS PER ACI STANDARDS.
- CONCRETE BLOCK SHALL BE AS PER MANUFACTURER'S PRODUCT GUIDE FOR ASTM C-90 REQUIREMENTS WITH MEDIUM SURFACE FINISH - F<sub>m</sub> = 1500 PSI.
- MORTAR SHALL BE TYPE "M" OR "N" FOR ALL MASONRY UNITS.
- STRUCTURAL STEEL SHALL CONFORM TO ASTM A36 STANDARDS FOR STRENGTH. BOLTS SHALL BE ASTM A307 / GRADE 1 OR A325, AS PER PLAN REQUIREMENTS.
- WELDS SHALL BE AS PER "AMERICAN WELDING SOCIETY" STANDARDS FOR STRUCTURAL STEEL APPLICATIONS.
- 2X4 P/T WOOD SILL, CONT., ALL AROUND, W/ 5/8"~ A.B. W/ 3" SQ. X 1/4" PLATE WASHERS WITHIN 6" FROM EACH CORNER, EA. WAY, & WITHIN 6" FROM ALL WALL OPENINGS / ENDS - 1/2"~ A.B. W/ 2" SQ. WASHERS ALONG EACH RUN @ 48" O.C., MAX. - ALL ANCHOR BOLTS SHALL HAVE A MINIMUM OF 8" EMBEDMENT INTO THE CONCRETE.



SECTION  
SCALE: 3/4" = 1'-0

B  
S.1



SECTION (optional)  
SCALE: 3/4" = 1'-0

A  
S.1

| REVISIONS | October 14, 2020 |
|-----------|------------------|
|           |                  |
|           |                  |
|           |                  |

FOUNDATION PLAN  
SCALE: 1/4" = 1'-0"

A CUSTOM HOME DESIGN FOR:  
**AL & SERANA OTERO**  
PROJECT ADDRESS: LOT 6, West Paces S/D, Lake City, Florida (Parcel: 32-35-16-02431-206)

AROOTOOS  
Digitally signed by: N. P. GEISLER  
DN: cn = N. P. GEISLER C = US  
O = AR0007005 OU = ARCHITECT  
Date: 2020.11.02 09:23:10 -0500

**NICHOLAS PAUL GEISLER ARCHITECT**  
N.C.A.R.B. Certified  
1758 NW Brown Rd.  
Lake City, FL 32055  
(386) 365-4355

JOB NUMBER  
20200320

SHEET NUMBER  
**S.1**  
OF 4 SHEETS



FLORIDA BUILDING CODE

Compliance Summary

TYPE OF CONSTRUCTION

Roof: Gable Construction, Wood Trusses @ 24" O.C.  
Walls: 2x 4 Wood Studs @ 16" O.C.  
Floor: 4" Thk. Concrete Slab W/ #4 rebar @ 24" O.C. ea. way.  
Foundation: Continuous monolithic footing or /Stem Wall foundation system

ROOF DECKING

Material: 5/8" CD Plywood or O.S.B.  
Sheet Size: 48"x96" Sheets Perpendicular to Roof Framing  
Fasteners: 8d Common or ring-shank nails per schedule on sheet S.4

SHEARWALLS

Material: 1/2" CD Plywood or 7/16" O.S.B.  
Sheet Size: 48"x96" Sheets Placed Vertical, stagger each sheet.  
Fasteners: 8d Common Nails @ 4" O.C. Edges & 8" O.C. Interior  
Dragstrut: Double Top Plate (S.Y.P.) W/16d Nails @ 12" O.C.  
Wall Studs: 2x4 Wood Studs @ 16" O.C.

HURRICANE UPLIFT CONNECTORS

Truss Anchors: SIMPSON H2.5A (OR EQUIVALENT), W/ 6 - 10d NAILS  
Wall Tension: Wall Sheathing Nailing is Adequate - 8d @ 4" O.C. Top & Bot.  
Anchor Bolts: 1/2" A307 Bolts @ 48" O.C. - 1st Bolt 6" from corner  
Corner Hold-down Device: (1) DTT2Z (or equiv.) @ each corner  
Porch Column Base Connector: Simpson ABU66/ABU66 @ each column  
Porch Column to Beam Connector: Simpson EPC66/PC66 @ each column

FOOTINGS AND FOUNDATIONS

Footing: 20"x 12" Cont. W/ (2) #5 Bars Cont. on chairs or (1) #3 Transverse @ 24" O.C.  
Stemwall: 8" C.M.U. W/ #5 Vertical Dowel @ 48" O.C.

STRUCTURAL DESIGN CRITERIA:

1. THE DESIGN COMPLIES WITH THE REQUIREMENTS OF THE 2017 FLORIDA BUILDING CODE - PER FBC 1602.2.1.1 AND OTHER REFERENCED CODES AND SPECIFICATIONS. ALL CODES AND SPECIFICATIONS SHALL BE LATEST EDITION AT TIME OF PERMIT.

2. WIND LOAD CRITERIA: RISK CATEGORY: 2, EXPOSURE: "C"  
BASED ON ANSI/AISC 1-10, 2017 FBC 1609-A WIND VELOCITY: V<sub>ULT</sub> = 130 MPH  
V<sub>ASD</sub> = 101 MPH

3. ROOF DESIGN LOADS:  
SUPERIMPOSED DEAD LOADS: 20 PSF  
SUPERIMPOSED LIVE LOADS: 20 PSF

4. FLOOR DESIGN LOADS:  
SUPERIMPOSED DEAD LOADS: 25 PSF  
SUPERIMPOSED LIVE LOADS: 40 PSF  
RESIDENTIAL BALCONIES: 60 PSF

5. WIND NET UPLIFT: ARE AS INDICATED ON PLANS

FRAMING ANCHOR SCHEDULE

| APPLICATION                  | MANUF'R/MODEL                                   | CAP.      |
|------------------------------|---|-----------|
| TRUSS TO WALL:               | SIMPSON H2.5A (OR EQUIVALENT), W/ 6 - 10d NAILS | 960#      |
| GIRDER TRUSS TO POST/HEADER: | SIMPSON LGT, W/ 28 - 16d NAILS                  | 1785#     |
| HEADER TO KING STUD(S):      | SIMPSON ST22                                    | 1370#     |
| PLATE TO STUD:               | SIMPSON SP2                                     | 1065#     |
| STUD TO SILL:                | SIMPSON SP1                                     | 585#      |
| PORCH BEAM TO POST:          | SIMPSON PC44/EPC44                              | 1700#     |
| PORCH POST TO FND.:          | SIMPSON ABU44                                   | 2200#     |
| MISC. JOINTS                 | SIMPSON A34                                     | 315#/240# |


NOTE:  
ALL ANCHORS SHALL BE SECURED W/ NAILS AS PRESCRIBED BY THE MANUFACTURER FOR MAXIMUM JOINT STRENGTH, UNLESS NOTED OTHERWISE.

NOTE:  
REFER TO THE INCLUDED STRUCTURAL DETAILS FOR ADDITIONAL ANCHORS/ JOINT REINFORCEMENT AND FASTENERS.

NOTE:  
ALL UNLISTED JOINTS IN THE LOAD PATH SHALL BE REINFORCED WITH SIMPSON A34 FRAMING ANCHORS, TYPICAL T.O.

NOTE:  
"SEMCO" PRODUCT APPROVAL:  
MIAMI/DADE COUNTY REPORT #95-0818.15

NOTE:  
"SEMCO" PRODUCT APPROVALS:  
MIAMI/DADE COUNTY REPORT #97-0107.05, #96-1126.11, #99-0623.04  
SBCC1 NER-443, NER-393



PENETRATIONS

SOFFIT/DROPPED CLG.


FIREBLOCKING NOTES:

FIREBLOCKING SHALL BE INSTALLED IN WOOD FRAME CONSTRUCTION IN THE FOLLOWING LOCATIONS:

- IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS INCLUDING FURRED SPACES AT CEILING AND FLOOR LEVELS.
- AT ALL INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS OCCUR AT SOFFITS, DROP CEILINGS, COVE CEILINGS, ETC.
- AT OPENINGS AROUND VENTS, PIPES, DUCTS, CHIMNEYS AND FIREPLACES AT CEILING AND FLOOR LEVELS WITH "PYROPANEL MULTIFLEX SEALANT"
- AT ALL INTERCONNECTIONS BETWEEN CONCEALED VERTICAL STUD WALL OR PARTITION SPACES AND CONCEALED SPACES CREATED BY AN ASSEMBLY OF FLOOR JOISTS, FIREBLOCKING SHALL BE PROVIDED FOR THE FULL DEPTH OF THE JOISTS AT THE ENDS AND OVER THE SUPPORTS.

Fire Stopping DETAILS

SCALE: NONE



Typical Stair DETAIL

SCALE: 3/4" = 1'-0"

| BUILDING COMPONENTS & CLADDING LOADS<br>MEAN BUILDING HEIGHT = 30.0', EXPOSURE "B"<br>ROOF ANGLE 21° TO 45° |          |                     |              |              |              |
|---|----------|---------------------|--------------|--------------|--------------|
| BLDG HEIGHT   | EXPOSURE | WIND VELOCITY (MPH) |              |              |              |
|   |          | 10                  | 15           | 20           | 30           |
| 1   | 10       | 19.9 / -21.8        | 23.1 / -25.9 | 27.8 / -30.4 | 32.3 / -35.9 |
|   | 15       | 19.4 / -21.2        | 22.6 / -24.6 | 27.0 / -29.9 | 31.4 / -33.5 |
|   | 20       | 18.6 / -19.2        | 22.2 / -22.8 | 26.0 / -26.8 | 30.2 / -31.1 |
|   | 25       | 18.1 / -18.7        | 21.8 / -22.4 | 25.6 / -26.4 | 29.8 / -30.8 |
|   | 30       | 17.7 / -18.3        | 21.4 / -22.0 | 25.2 / -26.0 | 29.4 / -30.4 |
|   | 35       | 17.3 / -17.9        | 21.0 / -21.6 | 24.8 / -25.6 | 29.0 / -30.0 |
| 2   | 10       | 19.9 / -25.5        | 23.1 / -30.3 | 27.8 / -35.6 | 32.3 / -41.2 |
|   | 15       | 19.4 / -24.9        | 22.6 / -29.7 | 27.0 / -34.0 | 31.4 / -39.4 |
|   | 20       | 18.6 / -22.9        | 22.2 / -27.2 | 26.0 / -32.0 | 30.2 / -37.1 |
|   | 25       | 18.1 / -22.4        | 21.8 / -27.0 | 25.6 / -31.6 | 29.8 / -36.7 |
|   | 30       | 17.7 / -22.0        | 21.4 / -26.6 | 25.2 / -31.2 | 29.4 / -36.3 |
|   | 35       | 17.3 / -21.6        | 21.0 / -26.2 | 24.8 / -30.8 | 29.0 / -35.9 |
| 3   | 10       | 19.9 / -25.5        | 23.1 / -30.3 | 27.8 / -35.6 | 32.3 / -41.2 |
|   | 15       | 19.4 / -24.9        | 22.6 / -29.7 | 27.0 / -34.0 | 31.4 / -39.4 |
|   | 20       | 18.6 / -22.9        | 22.2 / -27.2 | 26.0 / -32.0 | 30.2 / -37.1 |
|   | 25       | 18.1 / -22.4        | 21.8 / -27.0 | 25.6 / -31.6 | 29.8 / -36.7 |
|   | 30       | 17.7 / -22.0        | 21.4 / -26.6 | 25.2 / -31.2 | 29.4 / -36.3 |
|   | 35       | 17.3 / -21.6        | 21.0 / -26.2 | 24.8 / -30.8 | 29.0 / -35.9 |
| 4   | 10       | 21.8 / -23.6        | 25.9 / -34.1 | 30.4 / -33.0 | 35.3 / -38.2 |
|   | 15       | 20.8 / -22.6        | 24.7 / -26.9 | 29.0 / -31.6 | 33.7 / -36.7 |
|   | 20       | 19.5 / -21.3        | 23.2 / -25.4 | 27.2 / -29.8 | 31.6 / -34.6 |
|   | 25       | 18.8 / -20.6        | 22.5 / -24.7 | 26.5 / -29.1 | 30.9 / -33.9 |
|   | 30       | 18.1 / -19.9        | 21.8 / -24.0 | 25.8 / -28.4 | 30.2 / -33.2 |
|   | 35       | 17.4 / -19.2        | 21.1 / -23.3 | 25.1 / -27.7 | 29.5 / -32.5 |

| HEIGHT & EXPOSURE ADJUSTMENT COEFFICIENTS<br>FOR BUILDING COMPONENTS & CLADDING |              |              |              |
|---|--------------|--------------|--------------|
| BLDG HEIGHT   | EXPOSURE "B" | EXPOSURE "C" | EXPOSURE "D" |
| 15  | 1.00         | 1.21         | 1.41         |
| 20  | 1.00         | 1.28         | 1.55         |
| 25  | 1.00         | 1.35         | 1.61         |
| 30  | 1.00         | 1.40         | 1.66         |

| BUILDING COMPONENTS & CLADDING LOADS<br>MEAN BUILDING HEIGHT = 30.0', EXPOSURE "B"<br>ROOF ANGLE 1° TO 21° |          |                     |              |              |              |
|--|----------|---------------------|--------------|--------------|--------------|
| BLDG HEIGHT  | EXPOSURE | WIND VELOCITY (MPH) |              |              |              |
|  |          | 10                  | 15           | 20           | 30           |
| 1  | 10       | 12.0 / -19.9        | 14.9 / -23.1 | 17.5 / -27.8 | 20.3 / -32.3 |
|  | 15       | 11.4 / -19.4        | 13.6 / -23.0 | 16.0 / -27.0 | 18.5 / -31.4 |
|  | 20       | 10.0 / -18.6        | 11.9 / -22.2 | 13.9 / -26.0 | 16.1 / -30.2 |
|  | 25       | 9.5 / -18.1         | 11.4 / -21.7 | 13.4 / -25.5 | 15.6 / -29.7 |
|  | 30       | 9.0 / -17.6         | 10.9 / -21.2 | 12.9 / -25.0 | 15.1 / -29.2 |
|  | 35       | 8.5 / -17.1         | 10.4 / -20.7 | 12.4 / -24.5 | 14.6 / -28.7 |
| 2  | 10       | 12.5 / -34.1        | 14.9 / -41.3 | 17.5 / -48.4 | 20.3 / -56.2 |
|  | 15       | 11.4 / -31.9        | 13.6 / -38.0 | 16.0 / -44.6 | 18.5 / -51.7 |
|  | 20       | 10.0 / -28.2        | 11.9 / -33.6 | 13.9 / -39.4 | 16.1 / -45.1 |
|  | 25       | 9.5 / -27.7         | 11.4 / -33.1 | 13.4 / -38.9 | 15.6 / -44.6 |
|  | 30       | 9.0 / -27.2         | 10.9 / -32.6 | 12.9 / -38.4 | 15.1 / -44.1 |
|  | 35       | 8.5 / -26.7         | 10.4 / -32.1 | 12.4 / -37.9 | 14.6 / -43.6 |
| 3  | 10       | 12.5 / -51.3        | 14.9 / -61.0 | 17.5 / -71.6 | 20.3 / -83.1 |
|  | 15       | 11.4 / -47.9        | 13.6 / -57.1 | 16.0 / -67.0 | 18.5 / -77.1 |
|  | 20       | 10.0 / -43.5        | 11.9 / -51.8 | 13.9 / -60.8 | 16.1 / -70.5 |
|  | 25       | 9.5 / -43.0         | 11.4 / -51.3 | 13.4 / -60.3 | 15.6 / -70.0 |
|  | 30       | 9.0 / -42.5         | 10.9 / -50.8 | 12.9 / -59.8 | 15.1 / -69.5 |
|  | 35       | 8.5 / -42.0         | 10.4 / -50.3 | 12.4 / -59.3 | 14.6 / -69.0 |
| 4  | 10       | 21.8 / -23.6        | 25.9 / -34.1 | 30.4 / -33.0 | 35.3 / -38.2 |
|  | 15       | 20.8 / -22.6        | 24.7 / -26.9 | 29.0 / -31.6 | 33.7 / -36.7 |
|  | 20       | 19.5 / -21.3        | 23.2 / -25.4 | 27.2 / -29.8 | 31.6 / -34.6 |
|  | 25       | 18.8 / -20.6        | 22.5 / -24.7 | 26.5 / -29.1 | 30.9 / -33.9 |
|  | 30       | 18.1 / -19.9        | 21.8 / -24.0 | 25.8 / -28.4 | 30.2 / -33.2 |
|  | 35       | 17.4 / -19.2        | 21.1 / -23.3 | 25.1 / -27.7 | 29.5 / -32.5 |

| HEIGHT & EXPOSURE ADJUSTMENT COEFFICIENTS<br>FOR BUILDING COMPONENTS & CLADDING |              |              |              |
|---|--------------|--------------|--------------|
| BLDG HEIGHT   | EXPOSURE "B" | EXPOSURE "C" | EXPOSURE "D" |
| 15  | 1.00         | 1.21         | 1.41         |
| 20  | 1.00         | 1.28         | 1.55         |
| 25  | 1.00         | 1.35         | 1.61         |
| 30  | 1.00         | 1.40         | 1.66         |

General Roofing NOTES:

DECK REQUIREMENTS:  
ASPHALT SHINGLES SHALL BE FASTENED TO SOLIDLY SHEATHED DECKS.

SLOPE:  
ASPHALT SHINGLES SHALL BE USED ONLY ON ROOF SLOPES OF 2:12 OR GREATER. FOR ROOF SLOPES FROM 2:12 TO 4:12, DBL. UNDERLAYMENT IS REQUIRED.

UNDERLAYMENT:  
UNLESS OTHERWISE NOTED, UNDERLAYMENT SHALL CONFORM W/ ASTM D 226, TYPE 1, OR ASTM D 4869, TYPE 1.

SELF-ADHERING POLYMER MODIFIED BITUMEN SHEET:  
SELF ADHERING POLYMER MODIFIED BITUMEN SHALL COMPLY W/ ASTM D 1970.

ASPHALT SHINGLES:  
ASPHALT SHINGLES SHALL HAVE SELF SEAL STRIPS OR BE INTERLOCKING, AND COMPLY WITH ASTM D 225 OR ASTM D 3462.

FASTENERS:  
FASTENERS FOR ASPHALT SHINGLES SHALL BE GALVANIZED, STAINLESS STEEL, ALUMINUM OR COPPER ROOFING NAILS, MINIMUM 12 GAUGE SHANK WITH A MINIMUM 3/8 INCH DIAMETER HEAD, OF A LENGTH TO PENETRATE THROUGH THE ROOFING MATERIAL AND A MINIMUM 3/4" INTO THE ROOF SHEATHING. WHERE THE SHEATHING IS LESS THAN 3/4" THICK, THE NAILS SHALL PENETRATE THROUGH THE SHEATHING.

ATTACHMENT:  
ASPHALT SHINGLES SHALL BE SECURED TO THE ROOF WITH NOT LESS THAN FOUR FASTENERS PER STRIP SHINGLE OR TWO FASTENERS PER INDIVIDUAL SHINGLE. WHERE ROOFS LOCATED IN BASIC WIND SPEED OF 110 MPH OR GREATER, SPECIAL METHODS OF FASTENING ARE REQUIRED. UNLESS OTHERWISE NOTED, ATTACHMENT OF ASPHALT SHINGLES SHALL CONFORM WITH ASTM D 3161 OR M-DC PA 107-95.

UNDERLAYMENT APPLICATION:  
FOR ROOF SLOPES FORM 2:12 TO 4:12, UNDERLAYMENT SHALL BE A MINIMUM OF TWO LAYERS APPLIED AS FOLLOWS:  
1. STARTING AT THE EAVE, A 19 INCH STRIP OF UNDERLAYMENT SHALL BE APPLIED PARALLEL WITH THE EAVE AND FASTENED SUFFICIENTLY TO STAY IN PLACE.

2. STARTING AT THE EAVE, 36 INCH WIDE STRIPS OF UNDERLAYMENT FELT SHALL BE APPLIED OVERLAPPING SUCCESSIVE SHEETS 19 INCHES AND FASTENED SUFFICIENTLY TO STAY IN PLACE.

FOR ROOF SLOPED 4:12 AND GREATER, UNDERLAYMENT SHALL BE A MINIMUM OF ONE LAYER OF UNDERLAYMENT FELT APPLIED AS FOLLOWS:  
STARTING AT THE EAVE, UNDERLAYMENT SHALL BE APPLIED SHINGLE FASHION PARALLEL TO THE EAVE, LAPPED 2 INCHES, AND FASTENED SUFFICIENTLY TO STAY IN PLACE.

BASE AND CAP FLASHINGS:  
BASE AND CAP FLASHING SHALL BE INSTALLED IN ACCORDANCE W/ MFG'S INSTALLATION INSTRUCTIONS. BASE FLASHING SHALL BE OF EITHER CORROSION RESISTANT METAL OF MINIMUM NOMINAL THICKNESS 0.019 INCH OR MINERAL SURFACE ROLL ROOFING WEIGHING A MINIMUM OF 77 LBS PER 100 SQUARE FEET. CAP FLASHING SHALL BE CORROSION RESISTANT METAL OF MINIMUM NOMINAL THICKNESS OF 0.019 INCH.

VALLEYS:  
VALLEY LININGS SHALL BE INSTALLED IN ACCORDANCE W/ MANUFACTURER'S INSTALLATION INSTRUCTIONS BEFORE APPLYING ASPHALT SHINGLES. VALLEY LININGS OF THE FOLLOWING TYPES SHALL BE PERMITTED.

- FOR OPEN VALLEYS LINED WITH METAL, THE VALLEY LINING SHALL BE AT LEAST 16" WIDE AND OF ANY OF THE CORROSION RESISTANT METALS IN FBC TABLE 1507.3.9.2.
- FOR OPEN VALLEYS, VALLEY LINING OF TWO PLYS OF MINERAL SURFACE ROLL ROOFING SHALL BE PERMITTED. THE BOTTOM LAYER SHALL BE 18 INCHES AND THE TOP LAYER A MINIMUM OF 36 INCHES WIDE.
- FOR CLOSED VALLEYS VALLEY LINING SHALL BE ONE OF THE FOLLOWING:  
1. BOTH TYPES 1 AND 2 ABOVE, COMBINED.  
2. ONE PLY OF SMOOTH ROLL ROOFING AT LEAST 36 INCHES WIDE AND COMPLYING WITH ASTM D 224.  
3. SPECIALTY UNDERLAYMENT AT LEAST 36 INCHES WIDE AND COMPLYING WITH ASTM D 1970.

NOTE !!!  
ROOF SHINGLES SHALL BE AS MANUFACTURED BY "TAMKO ROOFING PRODUCTS" OF THE FOLLOWING MODELS:

GLASS-SEAL AR  
ELITE GLASS-SEAL AR  
HERITAGE 30 AR  
HERITAGE 40 AR  
HERITAGE 50 AR

THESE SHINGLES MEET THE REQUIREMENTS OF ASTM D-3161 TYPE 1 MODIFIED TO 110 MPH WINDS & FBC TAS 100, USING 4 NAILS/SHINGLE

| REVISIONS | October 27, 2020 |
|-----------|------------------|
|           |                  |
|           |                  |
|           |                  |
|           |                  |

SOFTPLAN  
ARCHITECTURAL DESIGN SOFTWARE

DETAILS SHEET  
SCALE: 1/4" = 1'-0"

A CUSTOM HOME DESIGN FOR:

AL & SERANA OTERO

PROJECT ADDRESS: LOT 6, West Paces S/D, Lake City, Florida (Parcel: 32-3S-16-02431-206)

ARCOOT005


Digitally signed by: N. P. GEISLER  
DN: cn = N. P. GEISLER c = US  
o = ARCOOT005 ou = ARCHITECT  
Date: 2020.11.02 09:21:07 -0500

NICHOLAS PAUL GEISLER ARCHITECT  
N.C.A.R.B. Certified (386) 365-4355  
759 NW Brown Rd.  
Lake City, FL 32055

JOB NUMBER  
20200320

SHEET NUMBER  
S.3  
OF 4 SHEETS


NOTE: ALL DRAWINGS NOT TO BE SCALED, WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS



### GABLE END GYPSUM DIAPHRAGM HOLDOWN CONNECTOR

SCALE: NONE

A.1




### END WALL BRACING FOR CEILING DIAPHRAGM

NTS (ALTERNATIVE TO BALLOON FRAMING)

NOTE: ALL WOOD TO BE NUMBER 2 GRADE SOUTHERN YELLOW PINE

A

| BUILDING COMPONENTS & CLADDING LOADS<br>MEAN BUILDING HEIGHT = 30.0', EXPOSURE "B" |      |      |                 |                 |                 |                 |
|--|------|------|-----------------|-----------------|-----------------|-----------------|
|  | ZONE | AREA | Vult<br>110 MPH | Vult<br>120 MPH | Vult<br>130 MPH | Vult<br>140 MPH |
| ROOF 7' TO 27'   | 1    | 10   | 12.0 / -19.9    | 14.9 / -23.7    | 17.5 / -27.8    | 20.3 / -32.3    |
|  | 1    | 20   | 11.4 / -19.4    | 13.6 / -23.0    | 16.0 / -27.0    | 18.5 / -31.4    |
|  | 1    | 50   | 10.0 / -18.6    | 11.9 / -22.2    | 13.9 / -26.0    | 16.1 / -30.2    |
|  | 2    | 10   | 12.5 / -34.7    | 14.9 / -41.3    | 17.5 / -48.4    | 20.3 / -56.2    |
|  | 2    | 20   | 11.4 / -31.9    | 13.6 / -38.0    | 16.0 / -44.6    | 18.5 / -51.7    |
|  | 2    | 50   | 10.0 / -28.2    | 11.9 / -33.6    | 13.9 / -39.4    | 16.1 / -45.7    |
| WALL   | 4    | 10   | 21.8 / -23.6    | 25.9 / -34.7    | 30.4 / -33.0    | 35.3 / -38.2    |
|  | 4    | 20   | 20.8 / -22.6    | 24.7 / -26.9    | 29.0 / -31.6    | 33.7 / -36.7    |
|  | 4    | 50   | 19.5 / -21.3    | 23.2 / -25.4    | 27.2 / -29.8    | 31.6 / -34.6    |
|  | 5    | 10   | 21.8 / -29.1    | 25.9 / -34.7    | 30.4 / -40.7    | 35.3 / -47.2    |
|  | 5    | 20   | 20.8 / -27.2    | 24.7 / -32.4    | 29.0 / -38.0    | 33.7 / -44.0    |
|  | 5    | 50   | 19.5 / -24.6    | 23.2 / -29.3    | 27.2 / -34.3    | 31.6 / -39.8    |




### Garage End Wall DETAIL

SCALE: NTS


G

| ROOF SHEATHING FASTENINGS |                              |  |   |
|---------------------------|------------------------------|--|---|
| NAILING ZONE              | SHEATHING TYPE               | FASTENER   | SPACING   |
| 1                         | 7/16" O.S.B.<br>OR 15/32 CDX | 8d COMMON OR<br>8d RING-SHANK<br>GALVANIZED<br>BOX NAILS | 6 in. o.c. EDGE<br>12 in. o.c. FIELD  |
| 2                         |                              |  | 6 in. o.c. EDGE<br>6 in. o.c. FIELD   |
| 3                         |                              |  | 4 in. o.c. @ GABLE ENDWALL<br>OR GABLE TRUSS<br>6 in. o.c. EDGE<br>6 in. o.c. FIELD |

| HEIGHT & EXPOSURE ADJUSTMENT COEFFICIENTS<br>FOR BUILDING COMPONENTS & CLADDING |              |              |              |
|---|--------------|--------------|--------------|
| BLDG HEIGHT   | EXPOSURE "B" | EXPOSURE "C" | EXPOSURE "D" |
| 15  | 1.00         | 1.21         | 1.47         |
| 20  | 1.00         | 1.29         | 1.55         |
| 25  | 1.00         | 1.35         | 1.61         |
| 30  | 1.00         | 1.40         | 1.66         |



ROOF SHEATHING NAILING ZONES  
(HIP ROOF)




ROOF SHEATHING NAILING ZONES  
(GABLE ROOF)

## Roof Nail Pattern DET.


SCALE: NONE

B


| HEADER SPANS FOR EXTERIOR BEARING WALLS |             |                     |         |        |         |         |         |
|---|-------------|---------------------|---------|--------|---------|---------|---------|
| HEADERS SUPPORTING:                     | HEADER SIZE | BUILDING WIDTH (FT) |         |        |         |         |         |
|   |             | 20'                 |         | 28'    |         | 36'     |         |
|   |             | SPAN                | # JACKS | SPAN   | # JACKS | SPAN    | # JACKS |
| ROOF, CEILING                           | 2-2x4       | 3'-6"               | 1       | 3'-2"  | 1       | 2'-10"  | 1       |
|   | 2-2x6       | 5'-5"               | 1       | 4'-8"  | 1       | 4'-2"   | 1       |
|   | 2-2x8       | 6'-10"              | 1       | 5'-11" | 2       | 5'-4"   | 1       |
|   | 2-2x10      | 8'-5"               | 2       | 7'-3"  | 2       | 6'-6"   | 2       |
|   | 2-2x12      | 9'-9"               | 2       | 8'-5"  | 2       | 7'-6"   | 2       |
|   | 3-2x8       | 8'-4"               | 1       | 7'-5"  | 1       | 6'-8"   | 1       |
|   | 3-2x10      | 10'-6"              | 1       | 9'-1"  | 2       | 8'-2"   | 1       |
|   | 3-2x12      | 12'-2"              | 2       | 10'-7" | 2       | 9'-5"   | 2       |
|   | 4-2x8       | 9'-2"               | 1       | 8'-4"  | 1       | 9'-2"   | 1       |
|   | 4-2x10      | 11'-8"              | 1       | 10'-6" | 1       | 9'-5"   | 1       |
|   | 4-2x12      | 14'-1"              | 1       | 12'-2" | 2       | 10'-11" | 1       |




WALL CORNER




WALL INTERSECTION




NON-BEARING WALL HEADER



TYPICAL WINDOW HEADER



OPENINGS 6' OR GREATER  
REQUIRE DBL. JACK STUDS




BEARING WALL HEADER

## Wall Framing/Header DETAILS

SCALE: NONE

F




## Girder Truss Column DET.

SCALE: 1/2" = 1'-0"

"WindSTORM" ALT. SHEATHING METHOD:  
ALTERNATIVE METHOD FOR ANCHORING THE TOP WALL PLATE TO THE FOUNDATION IN LIEU OF THE SP1/SP2 OR SPA STRAPS INDICATED IN THE CONSTRUCTION DOCUMENTS FOR THIS PROJECT SHALL ALLOWED AS FOLLOWS:  
1. APPLY VERTICALLY, "WindSTORM" 7/16" OSB 48" X 97", 109", 121" OR 145" SHEATHING. FASTEN TO THE TOP PLATE AND THE SILL PLATE WITH EITHER 6d COMMONS @ 7" O.C. OR 6d COMMONS @ 4" O.C., FASTEN TO EACH STUD WITH EITHER 6d COMMONS @ 6" O.C. OR 8d COMMONS @ 8" O.C.

Alternate "Titan" bolt concrete anchor system  
ANCHOR SILL PLATE WITH 5/8" TITAN ANCHOR BOLT, PLACED AT 40" O.C. AROUND PERIMETER OF SLAB AND ALL INTERIOR BEARING WALLS



### TYP. PERMANENT TRUSS BRACING DIA.


NTS

NOTE: ALL WOOD TO BE NUMBER 2 GRADE SOUTHERN YELLOW PINE

## Truss Bracing DETAILS

SCALE: AS NOTED

D



- SHEARWALL NOTES:**
- ALL SHEARWALLS SHALL BE TYPE 2 SHEARWALLS AS DEFINED BY STD 10-97 SBC01 305.4.3.
  - THE WALL SHALL BE ENTIRELY SHEATHED WITH 7/16" O.S.B. INCLUDING AREAS ABOVE AND BELOW OPENING S
  - ALL SHEATHING SHALL BE ATTACHED TO FRAMING ALONG ALL FOUR EDGES WITH JOINTS FOR ADJACENT PANELS OCCURRING OVER COMMON FRAMING MEMBERS OR ALONG BLOCKING.
  - NAIL SPACING SHALL BE 4" O.C. EDGES AND 8" O.C. IN THE FIELD.
  - TYPE 2 SHEARWALLS ARE DESIGNED FOR THE OPENING IT CONTAINS. MAXIMUM HEIGHT OF OPENING SHALL BE 96 TIMES THE WALL HEIGHT. THE MINIMUM DISTANCE BETWEEN OPENINGS SHALL BE THE WALL HEIGHT/3.5 FOR 6'-0" WALLS (2'-3").

| OPENING WIDTH  | SILL PLATES        | 16d TOE NAILS EACH END |
|----------------|--------------------|------------------------|
| UP TO 6'-0"    | (1) 2x4 OR (1) 2x6 | 1                      |
| > 6' TO 9'-0"  | (3) 2x4 OR (1) 2x6 | 2                      |
| > 9' TO 12'-0" | (5) 2x4 OR (2) 2x6 | 3                      |

## Shear Wall DETAILS

SCALE: NONE

E

| REVISIONS        |  |
|------------------|--|
| October 27, 2020 |  |

SOFTPLAN  
ARCHITECTURAL DESIGN SOFTWARE

DETAILS SHEET  
SCALE: 1/4" = 1'-0"

A CUSTOM HOME DESIGN FOR:  
**AL & SERANA OTERO**  
PROJECT ADDRESS: LOT 6, West Paces SD, Lake City, Florida (Parcel: 32-3S-16-02431-206)

Digitally signed by: N. P. GEISLER  
DN: cn = N. P. GEISLER, o = US  
o = AR0007005 OU = ARCHITECT  
Date: 2020.11.02 09:20:21 -0500

**NICHOLAS PAUL GEISLER ARCHITECT**  
N.C.A.R.B. Certified (386)  
1758 NW Brown Rd.  
Lake City, FL 32055  
365-4355

JOB NUMBER  
20200320

SHEET NUMBER  
**S.4**  
OF 4 SHEETS

NOTE: ALL DRAWINGS NOT TO BE SCALED, WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS