


ALL WIND LOADS ARE IN ACCORDANCE WITH SECTION 1609, FLORIDA BUILDING CODE 6TH EDITION (2017)		
FLOOR AND ROOF LIVE LOADS		
UNINHABITABLE ATTICS:	20 PSF	
HABITABLE ATTICS, BEDROOM:	30 PSF	
ALL OTHER ROOMS:	40 PSF	
GARAGE:	40 PSF	
ROOFS:	20 PSF UNIFORM	
WIND DESIGN DATA		
ULTIMATE WIND SPEED:	130 MPH	
NOMINAL (BASIC) WIND SPEED:	101 MPH	
RISK CATEGORY:	II	
WIND EXPOSURE:	B	
ENCLOSURE CLASSIFICATION:	ENCLOSED	
INTERNAL PRESSURE COEFFICIENT:	0.18 +/-	
COMPONENTS AND CLADDING		
ROOFING ZONE 1:	16.8 PSF MAX.	-18.4 PSF MIN.
ROOFING ZONE 2:	16.8 PSF MAX.	-21.5 PSF MIN.
ROOFING ZONE 3:	16.8 PSF MAX.	-21.5 PSF MIN.
ROOFING AT ZONE 2 OVERHANGS:	-31.1 PSF MIN.	
ROOFING AT ZONE 3 OVERHANGS:	-31.1 PSF MIN.	
STUCCO, CLADDING, DOORS AND WINDOWS		
ROOFING ZONE 4:	18.4 PSF MAX.	-19.9 PSF MIN.
ROOFING ZONE 5:	18.4 PSF MAX.	-24.6 PSF MIN.
9' WIDE O/H DR.:	16.1 PSF MAX.	-18.3 PSF MIN.
16' WIDE O/H DR.:	16.0 PSF MAX.	-17.3 PSF MIN.



a: 10% of least horizontal dim. or 0.4h, whichever is smaller, but not less than either 4% of least horizontal dimension or 3 ft.  
h: mean roof height, in feet.


COMPONENTS AND CLADDING

STRUCTURAL DESIGN CRITERIA

<b>CODES:</b>	FLORIDA BUILDING CODE 6TH EDITION (2017) BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE (ACI 318-14) SPECIFICATIONS FOR STRUCTURAL CONCRETE BUILDINGS (ACI 301-16) BUILDING CODE REQUIREMENTS FOR MASONRY STRUCTURES (ACI 530-13) NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION, 2015 EDITION APA PLYWOOD DESIGN SPECIFICATION	
<b>LIVE LOADS:</b>	ROOF RESIDENTIAL FLOOR, UNLESS OTHERWISE INDICATED BALCONIES STAIRS LIGHT PARTITIONS (DEAD LOAD), U.N.O.	20 PSF (REDUCIBLE) 40 PSF 40 PSF 40 PSF 20 PSF
<b>WIND LOADS: (F.B.C.)</b>	WIND LOADS BASED ON FBC, SECTION 1609 WIND VELOCITY: 120 M.P.H., USE FACTOR: 1.0	
<b>CONCRETE STRENGTH @ 28 DAYS</b>	ALL CONCRETE UNLESS OTHERWISE INDICATED PEA GRAVEL CONCRETE FOR MASONRY CELLS ONLY (DO NOT USE FOR CONCRETE COLUMNS OR TIE BEAMS)	2500 PSI 3000 PSI
<b>REINFORCING:</b>	WELDED WIRE FABRIC SHALL CONFORM TO ALL REINFORCING BARS ALL STIRRUPS AND TIES	ASTM A185 ASTM A615-40 40,000 PSI ASTM A615-40 40,000 PSI
<b>CONCRETE MASONRY UNITS:</b>	ASTM C90-99b, STANDARD WEIGHT UNITS, fm=1500 PSI MORTAR TYPE "S", 1800 PSI CONCRETE GROUT: 3000 PSI CONTINUOUS MASONRY INSPECTION IS REQUIRED DURING CONSTRUCTION	
<b>STRUCTURAL STEEL:</b>	ALL STRUCTURAL AND MISCELLANEOUS STEEL A36 36,000 PSI, U.N.O. SHOP AND FIELD WELDS: E70XX ELECTRODES ALL BOLTS CAST IN CONCRETE: ASTM A36 OR ASTM A-307	
<b>WOOD FRAMING:</b>	BEAMS, RAFTERS, JOIST PLATES, ETC. U.N.O. NO. 2 SOUTHERN YELLOW PINE (19% M.C.) ROOF DECK: PLYWOOD C-C-C-D, EXTERIOR, or OSB FLOOR SHEATHING: T&G A-C GROUP 1 APA RATED (48/24) WALL SHEATHING: PLYWOOD C-C-C-D, EXTERIOR OR OSB VERSA LAM BEAM Fb = 2900 PSI (2.0E) WOOD COLS. PARALLAM 2.0E U.N.O.	
<b>WOOD ROOF TRUSSES:</b>	DESIGN LOADS: TOP CHORD LIVE AND DEAD LOAD: 30 PSF BOTTOM CHORD LIVE AND DEAD LOAD: 10 PSF TOTAL: 40 PSF  SEE DRAWINGS FOR SPECIAL CONCENTRATED LOADS. DESIGN FOR NEW WIND UPLIFT AS PER SPECIFIED CODES, DEDUCTING A MAXIMUM OF 5 P.S.F. DEAD LOAD, BUT NOT EXCEEDING ACTUAL DEAD LOAD.	
<b>SOIL BEARING VALUE:</b>	ASSUMED ALLOWABLE SOIL BEARING PRESSURE AFTER COMPACTION: 1,500 PSF SEE SOILS REPORT AND SPECIFICATIONS FOR COMPACTION REQUIREMENTS IF SOIL CONDITIONS IN THE PROJECT DO NOT MEET OR EXCEED THE CAPACITY THE GENERAL CONTRACTOR SHALL CONTACT THE ENGINEER PRIOR TO FOUNDATION POUR FOR VERIFICATION OF FOUNDATION DESIGN.	



PROJECT LOCATION




JONES RESIDENCE

ABBREVIATIONS

A.B.	Anchor Bolt	Fir.	Floor	Plt. Ht.	Plate Height
Abv.	Above	Fdn.	Foundation	Plt Sh.	Plant Shelf
A/C	Air-Conditioner	Fir. Sys.	Floor System	PSF	Pounds per square foot
Adj.	Adjustable	F.Pl.	Fireplace	P.T.	Pressure Treated
A.F.F.	Above Finished Floor	Ft.	Foot / Feet	Pwd.	Powder Room
A.H.U.	Air Handler Unit	Ftg.	Footing	Rad.	Radius
ALT.	Alternate	FX	Fixed	Ref.	Refrigerator
B.C.	Base Cabinet	Galv.	Galvanized	Req'd.	Required
B.F.	Bifold Door	G.C.	General Contractor	Rm.	Room
Bk Sh	Book Shelf	G.F.I.	Ground Fault Interrupter	Rnd.	Round
Bm.	Beam	G.T.	Girder Truss	R/Sh	Rod and Shelf
BOT.	Bottom	Hdr.	Header	SD.	Smoke Detector
B.P.	Bypass door	Hgt.	Height	S.F.	Square Ft.
Brg.	Bearing	HB	Hose Bibb	Sh.	Shelves
Cir.	Circle	Int.	Interior	SHT	Sheet
Clg.	Ceiling	K/Wall	Kneewall	S.L.	Side Lights
Col.	Column	K.S.	Knee Space	S.P.F.	Spruce Pine Fir
Comp.	A/C Compressor	Laun.	Laundry	Sq.	Square
C.T.	Ceramic Tile	Lav.	Lavatory	S.Y.P.	Southern Yellow Pine
D.	Dryer	L.F.	Linear FL	Temp.	Tempered
Dec.	Decorative	L.T.	Laundry Tub	Thik'n.	Thicken
Ded.	Dedicated Outlet	Mas.	Masonry	T.O.B.	Top of Block
Dbl.	Double	Max	Maximum	T.O.M.	Top of Masonry
Dia.	Diameter	M.C.	Medicine Cabinet	T.O.P.	Top of Plate
Disp.	Disposal	MDP	Master Distribution Panel	Trans.	Transom Window
Dist.	Distance	Mfr.	Manufacturer	Typ.	Typical
D.S.	Drawer Stack	Micro.	Microwave	UCL	Under Cabinet Lighting
D.V.	Dryer Vent	Min	Minimum	U.N.O.	Unless Noted Otherwise
D.W.	Dishwasher	M.L.	Microalum	VB	Vanity Base
Ea.	Each	Mir.	Mirror	Vert.	Vertical
E.W.	Each Way	VL.	Versalium	V.L.	Versalium
Elec.	Electrical	N.T.S.	Not to Scale	VTR	Vent through Roof
Elev.	Elevation	Opn'g.	Opening	W	Washer
Ext.	Exterior	Opt.	Optional	W/	With
Exp.	Expansion	Pc.	Piece	W/C	Water Closet
F.B.C.	Florida Bldg. Code	Ped.	Pedestal	W.A.	Wedge Anchor
Fir.	Finished Floor	PL	Parallam	Wd	Wood
F.G.	Fixed Glass	PLF	Pounds per linear foot	WP	Water Proof


INDEX OF SHEETS

SHEET	DESCRIPTION
A-1	COVER SHEET
A-2	FLOOR PLAN
A-3	ELEVATIONS FRONT AND REAR
A-4	ELEVATIONS SIDES
A-5	FOUNDATION PLAN
A-6	ROOF PLAN
A-7	ELECTRICAL PLAN
A-8	SECTIONS AND FRAMING DETAILS
A-9	SHEARWALL DETAILS




REVISIONS			DESIGN BY:	CERTIFIED GENERAL CONTRACTOR CGC1514780	 <b>CES</b> Crews Engineering Services, LLC	CERTIFICATE OF AUTHORIZATION NO. 28022  349 SW CREWS FARM TERRACE LAKE CITY, FL 32025 PHONE: 386.623.4303	 Digitally signed by Brett A. Crews Date: 2020.10.13 09:10:49-04'00'  Brett A. Crews, P.E. 65592	DRAWN BY:  <b>TM</b>  APPROVED BY:  <b>BC</b>	<i><b>JONES RESIDENCE</b></i>	PROJECT NO.:  R20.004
DATE	BY	DESCRIPTION							 <b>TRADEMARK</b> Construction Group, Inc.	750 SW MAIN BLVD. LAKE CITY, FL. 32025 (386)755-5254






AREA SUMMARY	
HEATED	2,407 SF
GARAGE	682 SF
FRONT PORCH	248 SF
REAR PATIO	268 SF
TOTAL	3,605 SF




**BEAM/WALL CONNECTION**  
MAX. CAPACITY - 3640# DOWN; 1810# UPLIFT NOT TO SCALE




**CORNER POST**  
NTS

**FIREBLOCKING NOTES:**


- FIREBLOCKING SHALL BE INSTALLED IN WOOD FRAME CONSTRUCTION IN THE FOLLOWING LOCATIONS:
- IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS INCLUDING FURRED SPACES AT CEILING AND FLOOR LEVELS.
  - AT ALL INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS OCCUR AT SOFFITS, DROP CEILINGS, COVE CEILINGS, ETC.
  - IN CONCEALED SPACES BETWEEN STAIR STRINGERS AT THE TOP AND BOTTOM OF THE RUN.
  - AT OPENINGS AROUND VENTS, PIPES, DUCTS, CHIMNEYS AND FIREPLACES AT CEILING AND FLOOR LEVELS WITH PYROPANEL MULTIFLEX SEALANT
  - AT ALL INTERCONNECTIONS BETWEEN CONCEALED VERTICAL STUD WALL OR PARTITION SPACES AND CONCEALED SPACES CREATED BY AN ASSEMBLY OF FLOOR JOISTS, FIREBLOCKING SHALL BE PROVIDED FOR THE FULL DEPTH OF THE JOISTS AT THE ENDS AND OVER THE SUPPORTS.




**PENETRATIONS**




**SOFFIT/DROPPED CLG.**



**TOP PLATE SPLICE DETAILS**  
SCALE: 1/2" = 1'-0"



**Simpson ABU66**



**PLATFORM FRAMING**

REVISIONS		
DATE	BY	DESCRIPTION

DESIGN BY:  
**TRADEMARK**  
Construction Group, Inc.

CERTIFIED GENERAL CONTRACTOR  
CGC1514780  
  
750 SW MAIN BLVD.  
LAKE CITY, FL. 32025  
(386)755-5254

**CES**  
Crews Engineering Services, LLC



CERTIFICATE OF AUTHORIZATION  
NO. 28022  
  
349 SW CREWS FARM TERRACE  
LAKE CITY, FL 32025  
PHONE: 386.623.4303

Brett A. Crews, P.E. 65592

DRAWN BY:  
**TM**  
  
APPROVED BY:  
**BC**


**JONES RESIDENCE**  
  
**FLOOR PLAN**

PROJECT NO.:  
R20.004  
  
SHEET:  
**A-2**



REVISIONS			DESIGN BY:	CERTIFIED GENERAL CONTRACTOR CGC1514780	<b>CES</b> Crews Engineering Services, LLC	CERTIFICATE OF AUTHORIZATION NO. 28022	349 SW CREWS FARM TERRACE LAKE CITY, FL 32025 PHONE: 386.623.4303	Digitally signed by Brett A. Crews Date: 2020.10.13 09:42:47-04'00' Brett A. Crews, P.E. 65592	DRAWN BY: <b>TM</b> APPROVED BY: <b>BC</b>	<b>JONES RESIDENCE</b>	PROJECT NO.: R20.004
DATE	BY	DESCRIPTION									
			<b>TRADEMARK</b> Construction Group, Inc.	750 SW MAIN BLVD. LAKE CITY, FL. 32025 (386)755-5254						ELEVATIONS FRONT AND REAR	SHEET: A-3






LEFT ELEVATION  
SCALE: 1/4" = 1'-0"



RIGHT ELEVATION  
SCALE: 1/4" = 1'-0"



REVISIONS		
DATE	BY	DESCRIPTION

DESIGN BY:

**TRADEMARK**  
Construction Group, Inc.

CERTIFIED GENERAL CONTRACTOR  
CGC1514780

750 SW MAIN BLVD.  
LAKE CITY, FL. 32025  
(386)755-5254

**CES**  
Crews Engineering Services, LLC

CERTIFICATE OF AUTHORIZATION  
NO. 28022

349 SW CREWS FARM TERRACE  
LAKE CITY, FL 32025  
PHONE: 386.623.4303

Drawn by: **TM**

Approved by: **BC**












Brett A. Crews, P.E. 65592

PROJECT NO.: R20.004

SHEET: A-4

**JONES RESIDENCE**

ELEVATIONS SIDES



REVISIONS		
DATE	BY	DESCRIPTION

DESIGN BY:

**TRADEMARK**  
Construction Group, Inc.

CERTIFIED GENERAL CONTRACTOR  
CGC1514780

750 SW MAIN BLVD.  
LAKE CITY, FL. 32025  
(386)755-5254

**CES**  
Crews Engineering Services, LLC

CERTIFICATE OF AUTHORIZATION  
NO. 28022

349 SW CREWS FARM TERRACE  
LAKE CITY, FL 32025  
PHONE: 386.623.4303

Digitally signed  
by Brett A. Crews  
Date: 2020.10.13  
09:13:44-04'00'

Brett A. Crews, P.E. 65592

DRAWN BY:  
**TM**

APPROVED BY:  
**BC**


**JONES RESIDENCE**

FOUNDATION PLAN

PROJECT NO.:  
R20.004


SHEET:  
**A-5**





### END WALL BRACING FOR CEILING DIAPHRAGM

NTS NOTE: ALL WOOD TO BE NUMBER 2 GRADE SOUTHERN YELLOW PINE




### ROOF INTERSECTION CONNECTION DETAIL

NTS


ROOF SHEATHING FASTENERS			
NAILING ZONE	SHEATHING TYPE	FASTENER	SPACING
1	1/2" OSB	8D GALV. RING SHANK NAILS	6" O.C. EDGE 12" O.C. FIELD
2			6" O.C. EDGE 6" O.C. FIELD
3 (N/A)			4" O.C. @ GABLES 6" O.C. EDGE 6" O.C. FIELD

### ROOF SHEATHING FASTENING




### RIDGE VENT DETAIL


NOTE:  
VENTING SHALL BE PROVIDED SUCH THAT TOTAL  
NET FREE VENTILATING AREA SHALL NOT BE  
LESS THAN 1/150 OF THE AREA OF THE SPACE  
VENTILATED



### ROOF SHEATHING NAILING ZONES (GABLE ROOF)



### ROOF SHEATHING NAILING ZONES (HIP ROOF)



Digitally signed  
by Brett A. Crews  
Date: 2020.10.13  
09:14:20-0400'

Brett A. Crews, P.E. 65592

DRAWN BY:

TM

APPROVED BY:

BC

DESIGN BY:

**TRADEMARK**  
Construction Group, Inc.

CERTIFIED GENERAL CONTRACTOR  
CGC1514780

750 SW MAIN BLVD.  
LAKE CITY, FL. 32025  
(386)755-5254

**CES**  
Crews Engineering Services, LLC

CERTIFICATE OF AUTHORIZATION  
NO. 28022

349 SW CREWS FARM TERRACE  
LAKE CITY, FL 32025  
PHONE: 386.623.4303

**JONES RESIDENCE**

ROOF PLAN

PROJECT NO.:

R20.004

SHEET:

A-6



WIRING NOTES:

WIRING, DISTRIBUTION EQUIPMENT AND DEVICES  
A. CONDUCTORS: COPPER, IN ACCORDANCE WITH ASTM STANDARDS, SIZE REFERENCE AWG. CONDUCTORS NO. 10 AND SMALLER SIZE SOLID, NO. 8 AND LARGER, STRANDED. INSULATION OF CONDUCTOR THERMOPLASTIC, TYPE THHN (MIN. SIZE NO. 12) ANY WIRE INSTALLED OUTSIDE, UNDERGROUND, IN SLABS OR EXPOSED TO MOISTURE SHALL HAVE THWN INSULATION.  
B. RACEWAYS: RIGID STEEL CONDUIT, FULL WEIGHT PIPE GALVANIZED, THREADED, AND MINIMUM 1/2 INCH EXCEPT AS NOTED OR REQUIRED FOR WIRING. ELECTRICAL METALLIC TUBING (EMT), THIN WALL PIPE, GALVANIZED, THREADED, COMPRESSION FITTINGS, AND MINIM 1/2" SIZE EXCEPT AS NOTED OR REQUIRED FOR WIRING. FLEXIBLE STEEL CONDUIT: CONTINUOUS SINGLE STRIP, GALVANIZED, AND MINIMUM 1/2" SIZE EXCEPT AS NOTED OR REQUIRED FOR WIRING. PVC CONDUIT, HEAVY DUTY TYPE, SIZE AS INDICATED. SEPARATE RACEWAYS SHALL BE USED FOR EACH VOLTAGE SYSTEM.  
C. DISCONNECT SWITCHES: GENERAL DUTY, HORSEPOWER RATED FOR MOTOR LOADS 250 VOLT RATING, FUSED OR NON-FUSED AS NOTED; NUMBER OF POLES AS INDICATED. ENCLOSURE NEMA 1 FOR INDOOR USE AND NEMA 3R FOR WEATHERPROOF APPLICATIONS. SWITCH TO BE SQUARE "D" OR EQUAL.  
D. CIRCUIT BREAKERS: MOLDED CASE, THERMAL-MAGNETIC, QUICK MAKE, QUICK BREAK, BOLT-ON TYPE WITH MANUALLY OPERATED INSULATED TRIP-FREE HANDLE. MULT-POLE TYPES WITH INTERNAL COMMON TRIP BAR. TERMINALS SUITABLE FOR COPPER OR ALUMINUM CONDUCTORS. INTERRUPTING CAPACITY MINIMUM 10,000 RMS SYMMETRICAL AMPERES CIRCUIT CIRCUIT BREAKERS TO BE SQUARE "D", SIEMENS OR EQUAL, TYPE AS REQUIRED.  
E. PANELBOARDS: VOLTAGE, PHASING, AND AMPERE RATINGS AS INDICATED, CIRCUIT BREAKER TYPE AS INDICATED, BUSS BARS OF HARD DRAWN COPPER, MINIMUM 98% CONDUCTIVITY, GALVANIZED STEEL BACK BOX, DOOR AND TRIM. ALL CORNERS LAPPED AND WELDED, HARDWARE CHROME PLATED WITH FLUSH LOCK AND CATCH. HINGES SEMI-CONCEALED, 5 KNUCKLES STEEL WITH NONFERREROUS PINS. 180 DEGREE OPENINGS. MINIMUM GUTTER SPACE 5-3/4" SIDES, TOP AND BOTTOM. INCREASE SIZE WHERE REQUIRED BY CODE. DIRECTORY HOLDER COMPLETE WITH CLEAR PLASTIC TRANSPARENT COVER INDICATING TYPWRITTEN LIST OF FEEDER CABLES, CONDUIT SIZES, CIRCUIT NUMBER, OUTLETS OF EQUIPMENT SUPPLIED, AND THEIR LOCATION. CIRCUIT BREAKER TYPE PANELBOARDS TO BE SQUARE "D" TYPE NQOD OR I-LINE, OR EQUAL. A PLASTIC LABEL SHALL BE LOCATED ON EXTERIOR OF PANELBOARD IDENTIFYING THE SYSTEM VOLTAGE, PHASE, AND CURRENT RATING.  
F. WIRING DEVICES: ALL DEVICES THEIR PRODUCT OF THE SAME MANUFACTURER. WALL SWITCHES AND RECEPTACLES TO BE 20 AMP, 125 VOLT, UNLESS NOTED OTHERWISE. COLOR TO BE SELECTED BY ARCHITECT.  
G. DEVICE PLATES: PROVIDE FOR ALL OUTLETS WHERE DEVICES ARE INSTALLED. PROVIDE ENGRAVED MARKING FOR SPECIAL OUTLETS (WHERE NOTED). PROVIDE BLANK PLATES FOR EMPTY OR FUTURE OUTLET BOXES. DEVICE AND DEVICE PLATE COLORS TO BE VERIFIED WITH ARCHITECT AND OWNER.

GROUNDING SYSTEM:

A. EQUIPMENT: GROUND NON-CURRENT CARRYING METAL PARTS OF PANEL BOARD, RACEWAYS AND ALL LIGHTING FIXTURES. ALL CONDUIT SHALL HAVE EQUIPMENT GROUNDING CONDUCTORS.  
INSTALLATION:  
A. SECURE ALL SUPPORTS TO BUILDING STRUCTURE AS SPECIFIED UNDER RACEWAYS. SUPPORT HORIZONTAL RUNS OF METALLIC CONDUIT NOT MORE THAN 10 FEET APART. RUN EXPOSED RACEWAYS PARALLEL WITH OR AT RIGHT ANGLES TO WALLS.  
B. PASS RACEWAYS OVER WATER, STEAM OR OTHER PIPING WHEN PULL BOXES ARE NOT REQUIRED. NO RACEWAY WITHIN 3 INCHES OF STEAM OR HOT WATER PIPES, OR APPLIANCES. EXPECT CROSSING WHERE THE RACEWAY SHALL BE AT LEAST 2 INCHES FROM PIPE COVER.  
C. CUT CONDUIT ENDS SQUARE, REAM SMOOTH. PAINT MALE THREADS OF FIELD THREADED CONDUIT WITH GRAPHITE BASED PIP COMPOUND. DRAW UP TIGHT WITH CONDUIT COUPLINGS.  
D. LEAVE WIRE SUFFICIENTLY LONG TO PERMIT MAKING FINAL CONNECTIONS. IN RACEWAY OVER 50 FEET IN WHICH WIRING IS NOT INSTALLED. FURNISH PULL WIRE.  
E. VERIFY LOCATIONS OF OUTLETS AND SWITCHES.  
F. SUPPORT PANEL, JUNCTION AND PULL BOXES INDEPENDENTLY TO BUILDING STRUCTURE WITH NO WEIGHT BEARING ON CONDUITS.  
G. CONNECT CONDUIT TO MOTOR CONDUIT TERMINAL BASES WITH FLEXIBLE CONDUIT; MINIMUM 18 INCHES IN LENGTH AND 50% SLACK. DO NOT TERMINATE IN OR FASTEN RACEWAYS TO MOTOR FOUNDATION.  
H. THIS CONTRACTOR SHALL PROVIDE A TEMPORARY ELECTRICAL DISTRIBUTION SYSTEM AS REQUIRED; 120/208 VOLT, 1 PHASE, 100 AMP. FOR NEW CONSTRUCTION. ALL TEMPORARY WORK SHALL BE INSTALLED IN A NEAT AND SAFE MANNER.  
I. CONTRACTOR TO REMOVE AND SALVAGE ALL ABANDONED ELECTRICAL EQUIPMENT.  
J. THIS CONTRACTOR SHALL WARRANT ALL LABOR AND MATERIALS FOR ONE YEAR FROM DATE OF FINAL WRITTEN ACCEPTANCE.

ELECTRICAL PLAN NOTES

WIRE ALL APPLIANCES, HVAC UNITS AND OTHER EQUIPMENT PER MANUF. SPECIFICATIONS.

CONSULT THE OWNER FOR THE NUMBER OF SEPERATE TELEPHONE LINES TO BE INSTALLED.

INSTALLATION SHALL BE PER NAT'L. ELECTRIC CODE.


ALL SMOKE DETECTORS SHALL BE 120V W/ BATTERY BACKUP OF THE PHOTOELECTRIC TYPE, AND SHALL BE INTERLOCKED TOGETHER. INSTALL INSIDE AND NEAR ALL BEDROOMS.

TELEPHONE, TELEVISION AND OTHER LOW VOLTAGE DEVICES OR OUTLETS SHALL BE AS PER THE OWNER'S DIRECTIONS, & IN ACCORDANCE W/ APPLICABLE SECTIONS OF NEC-LATEST EDITION.

ELECTRICAL CONTR SHALL PREPARE "AS-BUILT" SHOP DWGS INDICATING ALL ELECTRICAL WORK, INCLUDING ANY CHANGES TO THE ELEC. PLAN, ADDNS TO THE ELEC. PLAN, RISER DIAGRAM, AS-BUILT PANEL SCHEDULE W/ ALL CKTS IDENTIFIED W/ CKT Nr., DESCRIPTION & BRKR, SERVICE ENT. & ALL UNDERGROUND WIRE LOCATIONS/ROUTING/DEPTH. RISER DIA. SHALL INCLUDE WIRE SIZES/TYPE & EQUIPMENT TYPE W/ RATINGS & LOADS. CONTRACTOR SHALL PROVIDE 1 COPY OF AS-BUILT DWGS TO OWNER & 1 COPY TO THE PERMIT ISSUING AUTHORITY.

ELECTRICAL LEGEND		
ELECTRICAL	COUNT	SYMBOL
ceiling fan 4 bladed 01	6	
48in LED LINEAR LIGHT	5	
can light blnd	31	
ceiling lumi mode 02	1	
pendant globe	3	
exterior light 02	4	
spotlight double with motion detector	4	
MOTOR	1	
NON-FUSED DISCONNECT	1	
electrical meter	1	
electrical panel	2	
co detector	1	
fan 50 CFM	3	
light	12	
outlet	38	
outlet 220v	4	
outlet gfi	11	
outlet wp	6	
smoke detector	4	
switch	35	
switch 3 way	10	
vanity wall mount	2	
wall mounted 03 1 light	2	

FIXTURE LAYOUT  
SCALE: 1/4" = 1'-0"



Digitally signed  
by Brett A. Crews  
Date: 2020.10.13  
09:14:53-04'00'  
Brett A. Crews, P.E. 65592

DRAWN BY:  
**TM**  
APPROVED BY:  
**BC**

**JONES RESIDENCE**

**ELECTRICAL PLAN**

PROJECT NO.:  
R20.004

SHEET:  
A-7

REVISIONS		
DATE	BY	DESCRIPTION

DESIGN BY:  
**TRADEMARK**  
Construction Group, Inc.  
750 SW MAIN BLVD.  
LAKE CITY, FL. 32025  
(386)755-5254

CERTIFIED GENERAL CONTRACTOR  
CGC1514780



CERTIFICATE OF AUTHORIZATION  
NO. 28022  
349 SW CREWS FARM TERRACE  
LAKE CITY, FL 32025  
PHONE: 386.623.4303







- RULES:
1. One all-thread rod at each corner.
  2. One all-thread rod at each end of opening headers.
  3. One all-thread rod at each end of opening headers greater than 3'-0"
  4. Check sub-sheathing to top plate connection for horizontal transfer capability.
  5. If necessary, add all-thread rods to girders individually to exclude the from average uplift plf.
  6. Check sole plate to slab connection, additional anchors may be required for lateral and shear load transfer.

ALLOWABLE VALUES	
Connection Type	Allowable Value
Foundation / S.Y.P. Top Plate	3840 lbs.
Foundation / Spruce-Pine-Fir Top Plate	3840 lbs.
Lintel or Bond Beam / S.Y.P. Top Plate	3840 lbs.
Lintel or Bond Beam / Spruce-Pine-Fir Top Plate	3840 lbs.

Placement at slab level:

**Corners**  
When presetting the all-thread rod at a building corner, the rod should be placed 8 to 12 inches away from the corner so it does not set under the corner framing members. When a all-thread rod is specified at a building corner, it may be placed on either side of the corner.

**Header ends**  
When presetting the all-thread rod at a header end, the rod should be placed 8 to 12 inches away from the header end so it does not fall under the stud pack framing members.

**Top Connections**  
Top connections made at corners and header ends shall be made within 2 inches of the framing pack. A nut and 3X3 washer shall be applied to the top plates and tightened securely.

**Intermediate Coupler Connections**  
When using the rod coupler, care should be taken to ensure full and equal thread engagement. This is easily achieved by threading the coupler all the way onto the rod, then standing the two rods end to end, then threading the coupler back over the rod joint so each rod is halfway into the coupler.

**Retro-fits**  
In the case of an all thread rod misplacement, the rod may be epoxied into the concrete.


**Sole plate to slab connection:**  
The slab level sole plate shall be connected to the slab with the connectors specified and at the spacing specified within the design documents. All-thread rods shall be placed as per the design specifications. All-thread rods with a nut and washer at the sole plate will qualify as a sole plate connection but may require other anchors intermediate of the all-thread rod locations to qualify the specified spacing requirements.

**System Tightening:**  
On multiple story applications, the all-thread rod system shall be rechecked for proper tension just before the walls are veneered. This will allow the all-thread rod system to compensate for the buildings dead load compression.

SHEARWALL NOTES:

1. ALL SHEARWALLS SHALL BE TYPE 2 SHEARWALLS AS DEFINED BY STD 10-99 305.4.3.
2. THE WALL SHALL BE ENTIRELY SHEATHED WITH 7/16" O.S.B. INCLUDING AREAS ABOVE AND BELOW OPENINGS.
3. ALL SHEATHING SHALL BE ATTACHED TO FRAMING ALONG ALL FOUR EDGES WITH JOINTS FOR ADJACENT PANELS OCCURING OVER COMMON FRAMING MEMBERS OR ALONG BLOCKING.
4. NAIL SPACING SHALL BE 6" O.C. EDGES AND 12" O.C. IN THE FIELD.
5. TYPE 2 SHEARWALLS ARE DESIGNED FOR THE OPENING IT CONTAINS. MAXIMUM HEIGHT OF OPENING SHALL BE 5/6 TIMES THE WALL HEIGHT. THE MINIMUM DISTANCE BETWEEN OPENINGS SHALL BE THE WALL HEIGHT/3.5 ie. FOR 8'-0" WALLS - (2'-3").


OPENING WIDTH	SILL PLATES	16d TOE NAILS EACH END
UP TO 6'-0"	(1) 2x4 OR (1) 2x6	1
> 6' TO 9'-0"	(3) 2x4 OR (1) 2x6	2
> 9' TO 12'-0"	(5) 2x4 OR (2) 2x6	3



DOUBLE NAIL EDGE SPACING  
TOP AND BOTTOM PLATE

UPLIFT CAPACITY = 474 plf  
(TABLE 305S1 SSTD10-99)


NOTE:  
ALL WALL SHEATHING SHALL BE WINDSTORM  
1 1/8" FULL HEIGHT SHEATHING-  
SEE DETAIL 1 FOR NAILING



SHEARWALL DETAILS

SCALE: 1/2" = 1'-0"

NOTE:  
VERIFY GIRDER TRUSS LOCATION  
ON TRUSS LAYOUT FOR REQ'D  
ALL THREAD AT GIRDER LOCATION



ALL THREAD @ PORCH BEAM


NTS

ALLOWABLE DEFLECTION OF STRUCTURAL MEMBERS

STRUCTURAL MEMBER	ALLOWABLE DEFLECTION
rafters having slopes greater than 2/12 with no finished ceiling attached to rafters	L/180
interior walls and partitions	H/180
floors and plastered ceilings	L/360
all other structural members	L/240
exterior walls with plaster or stucco finish	H/360
exterior walls - wind loads with brittle finishes	L/240
exterior walls - wind loads with flexible finishes	L/120



OPENING CONNECTION REQUIREMENTS				
CLEAR OPENING WIDTH	HEADER SIZE #2 GRADE OR BETTER	END BEARING	CONNECTOR AT EACH END OF OPENING	ANCHORAGE TO FOUNDATION @ EACH END OF OPENING
0' - 3'	(2) 2x8	1.5"	N/A	N/A
>3' - 6'	(2) 2x10	3"	1/2" ALL THREAD ROD	1/2" ALL THREAD ROD
>6' - 9'	(2) 2x12	3"	1/2" ALL THREAD ROD	1/2" ALL THREAD ROD
>9' - 12'	(2) 1 3/4" x 11 1/4" LVL - 2.0E	3"	1/2" ALL THREAD ROD	1/2" ALL THREAD ROD
>12' - 15'	(2) 1 3/4" x 11 1/4" LVL - 2.0E	3"	1/2" ALL THREAD ROD	1/2" ALL THREAD ROD
>15' - 18'	(2) 1 3/4" x 11 1/4" LVL - 2.0E	4.5"	1/2" ALL THREAD ROD	1/2" ALL THREAD ROD

NOTE:  
A SOLID MEMBER OF EQUAL OR GREATER SIZE THAN MULTIPLE MEMBERS MAY BE USED.  
IF RATED SHEATHING IS APPLIED TO NARROW EDGES, NAILED TO EACH STUD AT 12" O.C. MAXIMUM, THE LAMINATION NAILING SHOWN HERE IS NOT REQUIRED.



GIRDER COLUMN DETAIL

SCALE: 1/2" = 1'-0"





ALL THREAD DETAIL

● ALL THREAD LOCATION


REVISIONS			DESIGN BY:	CERTIFIED GENERAL CONTRACTOR	CERTIFICATE OF AUTHORIZATION	DRAWN BY:	APPROVED BY:	PROJECT NO.:
DATE	BY	DESCRIPTION						
			<b>TRADEMARK</b> Construction Group, Inc.	CGC1514780	<b>CES</b> Crews Engineering Services, LLC	TM	BC	R20.004
			750 SW MAIN BLVD. LAKE CITY, FL. 32025 (386)755-5254		349 SW CREWS FARM TERRACE LAKE CITY, FL 32025 PHONE: 386.623.4303			SHEET: A-9





That certain land situate in Columbia County, Florida, in Section 32, Township 4 South, Range 17 East; Commence at the intersection of the East line of the Northwest 1/4 of the Northwest 1/4, and South Right of Way Line of the existing County graded road and run thence East along the South Right of Way Line of said County graded road 521 feet; thence run Southwesterly 915 feet; thence run Northwesterly 521 feet to the East line of said Northwest 1/4 of Northwest 1/4; thence run North along said West line of Northwest 1/4 of Northwest 1/4 800 feet to the Point of Beginning.

PARCEL: 32-4S-17-08925-002



REVISIONS			DESIGN BY:	CERTIFIED GENERAL CONTRACTOR CGC1514780	<div>CES</div> <div>Crews Engineering Services, LLC</div>	CERTIFICATE OF AUTHORIZATION NO. 28022  P.O. BOX 970 LAKE CITY, FL 32056 PHONE: 386.754.4085	<div> <div>           Brett A. Crews           <div>             Digitally signed by Brett A. Crews              Date: 2020.10.13 09:18:16-04'00'           </div> </div>           Brett A. Crews, P.E. 65592         </div>	DRAWN BY: <b>TM</b>  APPROVED BY: <b>BC</b>	<b>JONES RESIDENCE</b>  SITE PLAN	PROJECT NO.:
DATE	BY	DESCRIPTION								R20.004
			<div>TRADEMARK</div> <div>Construction Group, Inc.</div>	750 SW MAIN BLVD. LAKE CITY, FL. 32025 (386)755-5254						SHEET: S-1