



Lumber design values are in accordance with ANSI/TPI 1 section 6.3  
These truss designs rely on lumber values established by others.

RE: 4177528 - IC CONST. - LIPPI RES.

MiTek, Inc.  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200

**Site Information:**

Customer Info: IC CONSTRUCTION Project Name: Lippi Res. Model: Custom  
Lot/Block: N/A Subdivision: N/A  
Address: TBD, TBD  
City: Columbia Cty State: FL

**Name Address and License # of Structural Engineer of Record, If there is one, for the building.**

Name: License #:  
Address:  
City: State:

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: FBC2023/TPI2014 Design Program: MiTek 20/20 8.7  
Wind Code: ASCE 7-22 Wind Speed: 130 mph  
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 65 individual, Truss Design Drawings and 0 Additional Drawings.

With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	T34843208	CJ01	8/27/24	15	T34843222	EJ03	8/27/24
2	T34843209	CJ02	8/27/24	16	T34843223	EJ04	8/27/24
3	T34843210	CJ02A	8/27/24	17	T34843224	EJ05	8/27/24
4	T34843211	CJ03	8/27/24	18	T34843225	EJ06	8/27/24
5	T34843212	CJ03A	8/27/24	19	T34843226	EJ06G	8/27/24
6	T34843213	CJ03B	8/27/24	20	T34843227	HJ02	8/27/24
7	T34843214	CJ04	8/27/24	21	T34843228	HJ03	8/27/24
8	T34843215	CJ04A	8/27/24	22	T34843229	HJ09	8/27/24
9	T34843216	CJ04B	8/27/24	23	T34843230	HJ09A	8/27/24
10	T34843217	CJ04C	8/27/24	24	T34843231	HJ11	8/27/24
11	T34843218	CJ05	8/27/24	25	T34843232	PB01	8/27/24
12	T34843219	CJ06	8/27/24	26	T34843233	PB01A	8/27/24
13	T34843220	EJ01	8/27/24	27	T34843234	PB02	8/27/24
14	T34843221	EJ02	8/27/24	28	T34843235	PB02G	8/27/24

This item has been digitally signed and sealed by ORegan, Philip, PE on the date adjacent to the seal.


Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies

The truss drawing(s) referenced above have been prepared by  
MiTek USA, Inc. under my direct supervision based on the parameters  
provided by Builders FirstSource-Lake City, FL.

Truss Design Engineer's Name: ORegan, Philip

My license renewal date for the state of Florida is February 28, 2025.

**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

ORegan, Philip

1 of 2





RE: 4177528 - IC CONST. - LIPPI RES.

MiTek, Inc.  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200

**Site Information:**


Customer Info: IC CONSTRUCTION   Project Name: Lippi Res.   Model: Custom  
Lot/Block: N/A   Subdivision: N/A  
Address: TBD, TBD  
City: Columbia Cty   State: FL

No.	Seal#	Truss Name	Date
29	T34843236	PB03	8/27/24
30	T34843237	T01	8/27/24
31	T34843238	T01G	8/27/24
32	T34843239	T02	8/27/24
33	T34843240	T02G	8/27/24
34	T34843241	T03	8/27/24
35	T34843242	T04	8/27/24
36	T34843243	T05	8/27/24
37	T34843244	T06	8/27/24
38	T34843245	T07	8/27/24
39	T34843246	T08	8/27/24
40	T34843247	T09	8/27/24
41	T34843248	T10	8/27/24
42	T34843249	T11	8/27/24
43	T34843250	T12	8/27/24
44	T34843251	T13	8/27/24
45	T34843252	T14	8/27/24
46	T34843253	T15	8/27/24
47	T34843254	T16	8/27/24
48	T34843255	T17	8/27/24
49	T34843256	T18	8/27/24
50	T34843257	T19	8/27/24
51	T34843258	T20	8/27/24
52	T34843259	T20G	8/27/24
53	T34843260	T21	8/27/24
54	T34843261	T22	8/27/24
55	T34843262	T22G	8/27/24
56	T34843263	T23	8/27/24
57	T34843264	T24	8/27/24
58	T34843265	T24G	8/27/24
59	T34843266	T25	8/27/24
60	T34843267	T25G	8/27/24
61	T34843268	T26	8/27/24
62	T34843269	T26G	8/27/24
63	T34843270	T27	8/27/24
64	T34843271	T27G	8/27/24
65	T34843272	T28	8/27/24



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843208
4177528	CJ01	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:24 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-1M?o9JMcMfWKaU4Iliaj8oTS5u1zPGcdSQGkGuyjwA9



Scale = 1:11.2

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.28	Vert(LL) 0.00	5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.06	Vert(CT) 0.00	5	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR					Weight: 8 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=47(LC 12)  
Max Uplift 5=68(LC 12), 3=-44(LC 1), 4=-35(LC 1)  
Max Grav 5=228(LC 1), 3=10(LC 16), 4=10(LC 16)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com








Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843210
4177528	CJ02A	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:25 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-VZZAMfNE7zfBBefUrQ5yh?0cjlNB8jsnh4?HoLyjwA8



Scale = 1:15.4

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.35	Vert(LL)	0.00	5	>999	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.07	Vert(CT)	0.00	5	>999		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MR					Weight: 11 lb	FT = 20%
	Code FBC2023/TPI2014							

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 1-5-13 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=73(LC 12)  
Max Uplift 5=-28(LC 12), 3=-31(LC 12), 4=-16(LC 9)  
Max Grav 5=204(LC 1), 3=18(LC 10), 4=19(LC 10)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843211
4177528	CJ03	Jack-Open	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:26 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-\_I7Ya?OtuHn2poEhP7cBDDYmThj0t96wvklrKnyjwA7



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.35	Vert(LL) 0.00	5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.09	Vert(CT) 0.00	5	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.01	3	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR					Weight: 12 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 2-0-4 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=89(LC 12)  
Max Uplift 5=-22(LC 12), 3=-48(LC 12), 4=-15(LC 12)  
Max Grav 5=204(LC 1), 3=33(LC 19), 4=27(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 1-11-8 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)


**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843212
4177528	CJ03A	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:26 2024 Page 1  
ID:21HcZI??AfwO44VTxHlsYnzam3y-\_l7Ya?OtuHn2poEhP7cBDDYmThh8t96wvklrKnyjwA7



Scale = 1:22.1

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.35	Vert(LL) 0.01	4-5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.21	Vert(CT) -0.01	4-5	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.02	3	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR					Weight: 16 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-1-1 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=123(LC 12)  
Max Uplift 5=-14(LC 12), 3=-78(LC 12), 4=-18(LC 12)  
Max Grav 5=226(LC 1), 3=71(LC 19), 4=49(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 3-0-5 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843213
4177528	CJ03B	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),


Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:26 2024 Page 1

ID:21HcZl??AfWo44VTxHlsYnzam3y-\_l7Ya?OtuHn2poEhP7cBDDYnbhiJt96wvklrKnyjwA7



Scale = 1:18.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.28	Vert(LL)	0.01	4-5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.14	Vert(CT)	-0.01	4-5	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014		Matrix-MR						Weight: 15 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-2-5 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=102(LC 12)  
Max Uplift 5=-43(LC 12), 3=-63(LC 12), 4=-7(LC 12)  
Max Grav 5=229(LC 1), 3=69(LC 19), 4=51(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 3-1-9 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843214
4177528	CJ04	Jack-Open	1	1	Job Reference (optional)	


Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:27 2024 Page 1

ID:21HcZl??AfWo44VTxHlsYnzam3y-SxhwnLPVfavvRyptzr7QmQ5xC509ccM48NUOsDyjwA6



Scale = 1:24.3



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.35	Vert(LL) 0.02	4-5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.29	Vert(CT) 0.02	4-5	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.03	3	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR					Weight: 18 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-7-7 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=140(LC 12)  
Max Uplift 5=-12(LC 12), 3=-92(LC 12), 4=-19(LC 12)  
Max Grav 5=241(LC 1), 3=88(LC 19), 4=60(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 3-6-11 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024


**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843215
4177528	CJ04A	Jack-Open	1	1	Job Reference (optional)	



<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 20.0	Plate Grip DOL 1.25	TC 0.28	Vert(LL) 0.02 4-5 >999 240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.27	Vert(CT) -0.03 4-5 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.03 3 n/a n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR		Weight: 19 lb	FT = 20%

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=133(LC 12)  
Max Uplift 5=-44(LC 12), 3=-89(LC 12), 4=-9(LC 12)  
Max Grav 5=265(LC 1), 3=105(LC 19), 4=75(LC 3)

**NOTES-**

- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCdL=4.2psf; BCdL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpI=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 4-4-1 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying approved roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27, 2024



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Components Association ([www.sbsccomponents.com](http://www.sbsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843216
4177528	CJ04B	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:27 2024 Page 1

ID:21HcZl?AfWo44VTxHlsYnzam3y-SxhwnLPVfavRyptzr7QmQ5yK50NccM48NUOsDyJwA6



Scale = 1:22.5




Plate Offsets (X,Y)--		[3:0-5-12,0-1-5]			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.28	Vert(LL) 0.02 6 >999 240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.28	Vert(CT) -0.03 5-6 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) 0.01 5 n/a n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR		Weight: 22 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-4-13 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
6-7: 2x4 SP No.3	
WEBS 2x6 SP No.2	

REACTIONS. (size) 8=0-3-8, 4=Mechanical, 5=Mechanical  
Max Horz 8=133(LC 12)  
Max Uplift 8=-37(LC 12), 4=-72(LC 12), 5=-24(LC 12)  
Max Grav 8=288(LC 1), 4=94(LC 19), 5=88(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-8=-252/185

- NOTES-
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 4-4-1 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 4, 5.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843217
4177528	CJ04C	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:28 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-w8FJ?hP7Qu1l25O3XYffJee6yVMvL3cDN1EyPfyjwA5



Scale = 1:24.3




Plate Offsets (X,Y)--		[2:0-1-12,0-2-4]			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.35	Vert(LL) -0.01 6 >999 240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.26	Vert(CT) -0.01 6 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.01 3 n/a n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR		Weight: 22 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-7-7 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

REACTIONS. (size) 7=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 7=140(LC 12)  
Max Uplift 7=-4(LC 12), 3=-76(LC 12), 4=-32(LC 12)  
Max Grav 7=268(LC 1), 3=81(LC 19), 4=83(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 3-6-11 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 3, 4.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.
4177528	CJ05	Jack-Open	1	1	T34843218


Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:28 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-w8FJ?hP7Qu1I25O3XYffJee56VJrL3cDN1EyPfyjwA5



Scale = 1:28.7



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.41	Vert(LL) 0.05	4-5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.45	Vert(CT) -0.04	4-5	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.06	3	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR					Weight: 21 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-8-4 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=175(LC 12)  
Max Uplift 5=-8(LC 12), 3=-119(LC 12), 4=-21(LC 12)  
Max Grav 5=274(LC 1), 3=120(LC 19), 4=81(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 4-7-8 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 4 except (jt=lb) 3=119.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843219
4177528	CJ06	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:29 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-OKphC1QIAC9cgFzF4GAurAFxvgb4WsMbhZVx6yiwA4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.46	Vert(LL)	0.06	4-5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.42	Vert(CT)	-0.08	4-5	>788	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.05	3	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014		Matrix-MR						Weight: 23 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-8-5 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=166(LC 12)  
Max Uplift 5=-47(LC 12), 3=-116(LC 12), 4=-10(LC 12)  
Max Grav 5=308(LC 1), 3=141(LC 19), 4=99(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-259/212

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 5-7-9 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 4 except (jt=lb) 3=116.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843220
4177528	EJ01	Jack-Partial	5	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),
Lake City, FL - 32055,
8.730 s Aug 15 2024 MiTek Industries, Inc.
Mon Aug 26 16:45:29 2024
Page 1
ID:21HcZI??AfWo44VTxHlsYnzam3y-OKphC1QlAC9cgFzF4GAurrAJFvfy4VkMbhZVx6jywA4



Scale: 3/8"=1'



LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.25	Vert(LL)	-0.08	6-7	>957	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.46	Vert(CT)	-0.17	6-7	>472	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.07	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014		Matrix-MS						Weight: 40 lb	FT = 20%

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 *Except* 2-7: 2x6 SP No.2		

**REACTIONS.** (size) 4=Mechanical, 5=Mechanical, 7=0-3-8  
Max Horz 7=193(LC 12)  
Max Uplift 4=-54(LC 12), 5=-85(LC 12), 7=-55(LC 12)  
Max Grav 4=87(LC 19), 5=174(LC 19), 7=354(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 6-11-4 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 5, 7.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843221
4177528	EJ02	Jack-Partial	4	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:29 2024 Page 1  
ID:21HcZl??AfWo44VTxHlsYnzam3y-OKphC1QlAC9cgFzF4GAurrAHRvhK4VIMbhzVx6jywA4




Plate Offsets (X,Y)--		[3:0-2-0,0-0-15]			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.37	Vert(LL) -0.06 7-8 >999 240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.37	Vert(CT) -0.13 7-8 >631 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.07	Horz(CT) 0.04 6 n/a n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS		Weight: 36 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
8-9: 2x4 SP No.3	6-0-0 oc bracing: 9-10.
WEBS 2x6 SP No.2 *Except*	
4-7: 2x4 SP No.3	

REACTIONS.	(size) 10=0-3-8, 5=Mechanical, 6=Mechanical
Max Horz	10=193(LC 12)
Max Uplift	10=-55(LC 12), 5=-39(LC 12), 6=-100(LC 12)
Max Grav	10=354(LC 1), 5=61(LC 19), 6=200(LC 19)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-10=-326/187

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 6-11-4 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10, 5 except (jt=lb) 6=100.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843222
4177528	EJ03	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:30 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-sWM3QNRNxVHTIPYSezh7O3jTaJ5Rpz5WqLj2TYjwA3



Scale = 1:15.3



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.28	Vert(LL)	0.00	4-5	>999	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.06	Vert(CT)	0.00	5	>999		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MR					Weight: 12 lb	FT = 20%
	Code FBC2023/TPI2014							

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 2-2-8 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=77(LC 12)  
Max Uplift 5=-46(LC 12), 3=-39(LC 12), 4=-4(LC 9)  
Max Grav 5=206(LC 1), 3=36(LC 19), 4=31(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 2-1-12 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.
4177528	EJ04	Jack-Open	2	1	T34843223

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:30 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-sWM3QNRNxVHTIPYSezh7O3jSSJ41pzcWqLj2TYjwA3



Scale = 1:17.6




Plate Offsets (X,Y)--		[2:0-1-11,0-2-0]			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.35	Vert(LL) 0.00 7 >999 240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.09	Vert(CT) -0.00 7 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.03	Horz(CT) 0.00 n/a n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS		Weight: 15 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2 *Except* 3-6: 2x4 SP No.3	

REACTIONS. (size) 7=0-3-8, 5=Mechanical  
Max Horz 7=89(LC 12)  
Max Uplift 7=-22(LC 12), 5=-61(LC 12)  
Max Grav 7=203(LC 1), 5=36(LC 10)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone; end vertical left exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 5.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.
4177528	EJ05	Jack-Open	2	1	T34843224

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:30 2024 Page 1

ID:21HcZI??AFWo44VTxHlsYnzam3y-sWM3QNRNxBHTIPYSezh7O3jSbJ?dpx5WqLj2TYjywA3



Scale = 1:36.7

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.34	Vert(LL)	-0.07	7-8	>999	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.43	Vert(CT)	-0.14	7-8	>513		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.13	Horz(CT)	-0.00	7	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP					Weight: 48 lb	FT = 20%
	Code FBC2023/TPI2014							

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-8: 2x6 SP No.2	

**REACTIONS.** (size) 7=Mechanical, 8=0-3-8  
Max Horz 8=226(LC 12)  
Max Uplift 7=-186(LC 12)  
Max Grav 7=250(LC 19), 8=322(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-8=-203/409, 2-3=-89/277  
WEBS 3-8=-349/62

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 1-6-0 to 1-6-0, Zone1 1-6-0 to 6-4-0 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=186.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843225
4177528	EJ06	Jack-Closed	6	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:31 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-KiwRdjS?ipPKwZ7eChCMwGFa2iL0YHO3?Sc?\_yJwA2




Plate Offsets (X,Y)--		[4:0-0-1,0-1-8]			
<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) I/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 20.0	Plate Grip DOL 1.25	TC 0.55	Vert(LL) -0.05 7-8 >999 240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.42	Vert(CT) -0.11 7-8 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.64	Horz(CT) 0.01 7 n/a n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS		Weight: 55 lb	FT = 20%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

**REACTIONS.** (size) 7=Mechanical, 2=0-3-8  
Max Horz 2=206(LC 12)  
Max Uplift 7=137(LC 12), 2=124(LC 8)  
Max Grav 7=376(LC 1), 2=462(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-937/55, 4-7=-170/251  
BOT CHORD 2-8=-317/898, 7-8=-325/884  
WEBS 3-7=-877/305

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 10-4-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=137, 2=124.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843226
4177528	EJ06G	Jack-Closed Structural Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:31 2024 Page 1  
ID:21HcZI??AfWo44VTxHsYnzam3y-KiwRdjS?ipPKwZ7eChCMwGFYiin6YQXf3?Sc?\_yJwA2




Plate Offsets (X,Y)--		[2:0-3-8,Edge], [2:0-5-12,Edge], [4:0-2-12,0-1-12], [5:0-0-11,0-1-8]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.70
TCDL 7.0	Lumber DOL	1.25	BC 0.29
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.05
BCDL 10.0	Code	FBC2023/TPI2014	Matrix-MS
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.04 6-7 >999 240
			Vert(CT) -0.08 6-7 >960 180
			Horz(CT) -0.00 6 n/a n/a
			PLATES GRIP
			MT20 244/190
			Weight: 70 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD 2-0-0 oc purlins (6-0-0 max.), except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

**REACTIONS.** All bearings 4-3-8 except (jt=length) 6=Mechanical.  
(lb) - Max Horz 2=244(LC 12)  
Max Uplift All uplift 100 lb or less at joint(s) 7 except 2=130(LC 8), 6=157(LC 12)  
Max Grav All reactions 250 lb or less at joint(s) 2, 6, 2 except 7=424(LC 1), 7=424(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 5-6=-169/308  
WEBS 4-7=-293/169

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 10-2-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 4) Gable studs spaced at 2-0-0 oc.
  - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 6) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 7) Refer to girder(s) for truss to truss connections.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7 except (jt=lb) 2=130, 6=157, 2=130.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)


**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843227
4177528	HJ02	Diagonal Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:32 2024 Page 1  
ID:21HcZI??Afw044VTxHlsYnzam3y-ovUpq2SdT6XBjxhmqOjbTUomu6lsHtbpIfC9YRyjwA1



LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 2-0-0	TC 0.48	Vert(LL) 0.00	4-5	>999	240		MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.19	Vert(CT) 0.01	4-5	>999	180			
BCLL 0.0 *	Rep Stress Incr NO	WB 0.00	Horz(CT) -0.02	3	n/a	n/a			
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR						Weight: 13 lb	FT = 20%

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD 2x4 SP No.2		TOP CHORD	Structural wood sheathing directly applied or 2-3-4 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2		BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SP No.2			

**REACTIONS.** (size) 5=0-4-11, 3=Mechanical, 4=Mechanical  
Max Horz 5=85(LC 8)  
Max Uplift 5=85(LC 8), 3=-37(LC 21), 4=-42(LC 21)  
Max Grav 5=272(LC 1), 3=14(LC 25), 4=19(LC 33)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 61 lb down and 123 lb up at 0-10-7 on top chord, and 7 lb down and 55 lb up at 0-10-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-2=-54, 2-3=-54, 4-5=-20

Concentrated Loads (lb)

Vert: 6=31(B) 7=24(B)

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843228
4177528	HJ03	Jack-Open Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),

Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:32 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-ovUpq2SdT6XBXjhqmOjbTUojE6lRHtbpIfC9YRyjwA1




Plate Offsets (X,Y)-- [2:0-3-15,0-0-10]											
LOADING (psf)	SPACING-		CSI.		DEFL.		PLATES		GRIP		
	TCLL	20.0	Plate Grip DOL	1.25	TC	0.65	MT20		244/190		
	TCDL	7.0	Lumber DOL	1.25	BC	0.15					
	BCLL	0.0 *	Rep Stress Incr	NO	WB	0.00					
	BCDL	10.0	Code	FBC2023/TPI2014	Matrix-MR				Weight: 16 lb FT = 20%		

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-1-8 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x6 SP No.2		

**REACTIONS.** (size) 5=0-4-11, 3=Mechanical, 4=Mechanical  
Max Horz 5=88(LC 12)  
Max Uplift 5=91(LC 12), 3=-45(LC 12), 4=-24(LC 9)  
Max Grav 5=313(LC 1), 3=35(LC 1), 4=45(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-260/271

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -2-4-13 to 0-7-3, Zone1 0-7-3 to 3-0-12 zone; end vertical left exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843229
4177528	HJ09	Diagonal Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:33 2024 Page 1  
ID:21HcZl??AFWo44VTxHlsYnzam3y-G52C2OTGEQf29tG1J5Eq0hLxdW2i0lFyWJxi4tyjwA0



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.48	Vert(LL) 0.04	6-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.34	Vert(CT) -0.05	6-7	>999	180		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.17	Horz(CT) -0.00	5	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS					Weight: 49 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except*	
2-8: 2x6 SP No.2	

**REACTIONS.** (size) 8=0-4-11, 4=Mechanical, 5=Mechanical  
Max Horz 8=180(LC 8)  
Max Uplift 8=182(LC 8), 4=79(LC 10), 5=151(LC 8)  
Max Grav 8=459(LC 1), 4=101(LC 35), 5=233(LC 35)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-8=-441/197, 2-3=-398/156  
BOT CHORD 6-7=-225/283  
WEBS 2-7=-187/368, 3-6=-359/285

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 8=182, 5=151.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 87 lb down and 41 lb up at 2-0-5, 81 lb down and 56 lb up at 3-3-12, and 112 lb down and 110 lb up at 5-2-12, and 96 lb down and 108 lb up at 5-10-8 on top chord, and 13 lb down and 13 lb up at 2-0-5, 20 lb down and 20 lb up at 3-3-12, and 40 lb down and 20 lb up at 5-2-12, and 38 lb down and 28 lb up at 5-10-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-2=-54, 2-4=-54, 5-8=-20

Concentrated Loads (lb)

Vert: 11=-5(B) 12=-3(F) 13=10(B) 14=9(F) 15=-9(B) 16=-4(F)

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.


Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843230
4177528	HJ09A	Diagonal Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:33 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-G52C2OTGEQf2t9tG1J5Eq0hLxdW?L0GYyWJxi4tyjwA0



LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.48	Vert(LL) 0.08	6-7	>999	240		MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.56	Vert(CT) -0.11	6-7	>875	180			
BCLL 0.0 *	Rep Stress Incr NO	WB 0.28	Horz(CT) 0.01	5	n/a	n/a			
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS						Weight: 52 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 *Except* 3-8: 2x4 SP No.3	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-9: 2x6 SP No.2	

**REACTIONS.** (size) 4=Mechanical, 5=Mechanical, 9=0-4-11  
Max Horz 9=180(LC 29)  
Max Uplift 4=-81(LC 10), 5=-144(LC 8), 9=-180(LC 8)  
Max Grav 4=112(LC 1), 5=238(LC 35), 9=468(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-9=-409/221, 2-3=-583/285  
BOT CHORD 3-7=-120/256, 6-7=-442/573  
WEBS 2-7=-269/529, 3-6=-607/469

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=144, 9=180.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 87 lb down and 41 lb up at 2-0-5, 81 lb down and 56 lb up at 3-3-12, and 104 lb down and 92 lb up at 5-2-12, and 85 lb down and 92 lb up at 5-10-8 on top chord, and 13 lb down and 13 lb up at 2-0-5, 20 lb down and 20 lb up at 3-4-6, and 57 lb down and 38 lb up at 5-2-12, and 60 lb down and 44 lb up at 5-10-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25  
Uniform Loads (plf)  
Vert: 1-2=-54, 2-4=-54, 8-9=-20, 5-7=-20  
Concentrated Loads (lb)  
Vert: 8=9(B) 11=-5(F) 12=-2(B) 13=10(F) 14=-24(F) 15=-15(B)

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843231
4177528	HJ11	Diagonal Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),

Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:34 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-IHcaFkUu?knvn1rDtpI3Yvt5iwKAjB6lzhGcJyJwA?



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.53	Vert(LL) 0.09	6-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.59	Vert(CT) -0.13	6-7	>926	180		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.31	Horz(CT) -0.00	5	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS					Weight: 57 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-8: 2x6 SP No.2	

**REACTIONS.** (size) 8=0-4-11, 4=Mechanical, 5=Mechanical  
Max Horz 8=203(LC 8)  
Max Uplift 8=-264(LC 8), 4=-121(LC 10), 5=-222(LC 8)  
Max Grav 8=539(LC 1), 4=142(LC 1), 5=311(LC 35)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-8=-515/273, 2-3=-505/275  
BOT CHORD 6-7=-346/389  
WEBS 2-7=-295/507, 3-6=-478/426

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=264, 4=121, 5=222.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 68 lb down and 85 lb up at 2-5-8, 98 lb down and 78 lb up at 3-8-2, 92 lb down and 92 lb up at 5-0-4, and 123 lb down and 142 lb up at 6-10-9, and 106 lb down and 140 lb up at 7-7-0 on top chord, and 18 lb down and 48 lb up at 2-5-8, 27 lb down and 14 lb up at 3-8-2, 32 lb down and 24 lb up at 5-0-4, and 55 lb down and 27 lb up at 6-10-9, and 50 lb down and 34 lb up at 7-7-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)	Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25	
Uniform Loads (plf)	Vert: 1-2=-54, 2-4=-54, 5-8=-20
Concentrated Loads (lb)	Vert: 7=3(B) 9=18(B) 12=-39(F) 13=-30(B) 15=2(F) 16=-27(F) 17=-20(B)

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843232
4177528	PB01	Piggyback	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),

Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:34 2024 Page 1  
ID:21HcZl??AfWo44VTxHlsYnzam3y-IHcaFkUu?knvn1rDtpl3YvtDbwT9ln06lzhGcJyywA?




Plate Offsets (X,Y)--		[2:0-2-1,0-1-0], [4:0-2-1,0-1-0]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL 1.25		TC 0.02		Vert(LL) 0.00	4	n/r	120	MT20	244/190
TCDL 7.0		Lumber DOL 1.25		BC 0.01		Vert(CT) 0.00	4	n/r	120		
BCLL 0.0 *		Rep Stress Incr YES		WB 0.01		Horz(CT) 0.00	4	n/a	n/a		
BCDL 10.0		Code FBC2023/TPI2014		Matrix-P						Weight: 10 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-3-3 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

**REACTIONS.** (size) 2=1-11-12, 4=1-11-12, 6=1-11-12  
Max Horz 2=-29(LC 10)  
Max Uplift 2=-27(LC 12), 4=-30(LC 13), 6=-2(LC 12)  
Max Grav 2=66(LC 1), 4=66(LC 1), 6=58(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4, 6.
  - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843233
4177528	PB01A	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:35 2024 Page 1

ID:21HcZI??AfWo44VTxHsYnzam3y-DUAYt4VWm1vmOAPRWHI56QNmKo6UEfF\_dQp9lyjwA\_  
9-3-10  
9-3-10

Scale = 1:18.2



9-3-10  
9-3-10

Plate Offsets (X,Y)--		[2:0-2-1,0-1-0], [3:0-2-0,0-1-13]							
LOADING (psf)		SPACING- 2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL 1.25	TC 0.12	Vert(LL) 0.00	1	n/r	120	MT20	244/190
TCDL 7.0		Lumber DOL 1.25	BC 0.09	Vert(CT) 0.00	1	n/r	120		
BCLL 0.0 **		Rep Stress Incr YES	WB 0.04	Horz(CT) -0.00	7	n/a	n/a		
BCDL 10.0		Code FBC2023/TPI2014	Matrix-S					Weight: 30 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3		

**REACTIONS.** All bearings 8-7-14.  
(lb) - Max Horz 2=39(LC 12)  
Max Uplift All uplift 100 lb or less at joint(s) 7, 2, 9, 8, 10  
Max Grav All reactions 250 lb or less at joint(s) 7, 2, 10 except 9=272(LC 1), 8=270(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 0-2-14 to 1-5-10, Zone2 1-5-10 to 5-8-9, Zone1 5-8-9 to 9-1-14 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 4) Provide adequate drainage to prevent water ponding.
  - 5) All plates are 2x4 MT20 unless otherwise indicated.
  - 6) Gable requires continuous bottom chord bearing.
  - 7) Gable studs spaced at 4-0-0 oc.
  - 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 9) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 2, 9, 8, 10.
  - 11) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843234
4177528	PB02	Piggyback	14	1	Job Reference (optional)	




Plate Offsets (X,Y)--		[3:0-3-0,Edge]									
LOADING	(psf)	SPACING-		CSL.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC 0.02	Vert(LL)	-0.00	4	n/r	120	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC 0.02	Vert(CT)	-0.00	4	n/r	120		
BCLL	0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	4	n/a	n/a		
BCDL	10.0	Code	FBC2023/TPI2014	Matrix-P						Weight: 7 lb	FT = 20%

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 2=1-5-12, 4=1-5-12  
 Max Horz 2=-20(LC 10)  
 Max Uplift 2=-27(LC 12), 4=-27(LC 13)  
 Max Grav 2=81(LC 1), 4=81(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.
  - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
 MiTek Inc. DBA MiTek USA FL Cert 6634  
 16023 Swingley Ridge Rd. Chesterfield, MO 63017  
 Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
 16023 Swingley Ridge Rd.  
 Chesterfield, MO 63017  
 314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843235
4177528	PB02G	PIGGYBACK	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:36 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-hgkKgQW8XL1d0K?c?EoXdKzZ2j8nDhaOCHANgCjyw9z



Scale = 1:6.0

										1-11-6		
Plate Offsets (X,Y)-- [2:0-3-7,0-0-0]										1-11-6		
<b>LOADING</b> (psf)		<b>SPACING-</b> 2-0-0		<b>CSI.</b>		<b>DEFL.</b> in (loc) l/defl L/d				<b>PLATES</b>	<b>GRIP</b>	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.02	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.00	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code FBC2023/TPI2014		Matrix-P						Weight: 3 lb	FT = 20%	

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 1-11-6 oc purlins.
	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
<b>REACTIONS.</b> (size) 1=1-11-6, 3=1-11-6	
Max Horz 1=11(LC 9)	
Max Uplift 1=17(LC 12), 3=17(LC 13)	
Max Grav 1=38(LC 1), 3=38(LC 1)	

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Gable requires continuous bottom chord bearing.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843236
4177528	PB03	Piggyback	3	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:36 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-hgkKgQW8XL1d0K?c?EoXdKzZ?j8YDhROCHANGCjyw9z



LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 2-0-0	TC 0.03	Vert(LL) 0.00	4	n/r	120		MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.02	Vert(CT) 0.00	4	n/r	120			
BCLL 0.0 *	Rep Stress Incr YES	WB 0.01	Horz(CT) 0.00	4	n/a	n/a			
BCDL 10.0	Code FBC2023/TPI2014	Matrix-P						Weight: 12 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

**REACTIONS.** (size) 2=2-5-13, 4=2-5-13, 6=2-5-13  
Max Horz 2=-28(LC 10)  
Max Uplift 2=-33(LC 12), 4=-36(LC 13), 6=-5(LC 12)  
Max Grav 2=79(LC 1), 4=79(LC 1), 6=78(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4, 6.
  - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843237
4177528	T01	Common	2	1	Job Reference (optional)	


Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:36 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-hgkKgQW8XL1d0K?c?EoXdKzUfj4lDgGOCHANgCjw9z

-1-6-01-6-06-0-06-0-012-0-012-0-013-6-013-6-0

1-6-06-0-06-0-06-0-06-0-06-0-06-0-0

Scale = 1:37.9



LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 2-0-0	TC 0.37	Vert(LL)	-0.02	7-8	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.29	Vert(CT)	-0.05	7-8	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.08	Horz(CT)	0.00	6	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS						Weight: 76 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-8,4-6: 2x6 SP No.2	

**REACTIONS.** (size) 8=0-3-8, 6=0-3-8  
Max Horz 8=193(LC 11)  
Max Uplift 8=137(LC 12), 6=137(LC 13)  
Max Grav 8=520(LC 1), 6=520(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-397/166, 3-4=-397/168, 2-8=-469/293, 4-6=-469/297  
BOT CHORD 7-8=-213/285

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 6-0-0, Zone2 6-0-0 to 10-2-15, Zone1 10-2-15 to 13-6-0 zone; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=137, 6=137.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843238
4177528	T01G	Common Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:37 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-9sHiumWmIf9UeUaoYxJmAXVhD7UVy8xYRxvwCeyjw9y  
-1-6-0 6-0-0 12-0-0 13-6-0  
1-6-0 6-0-0 6-0-0 1-6-0  
4x4 =  
Scale = 1:36.4




Plate Offsets (X,Y)--		[2:0-2-12,0-3-8], [10:0-2-12,0-3-8]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.25	Vert(LL)	-0.01	11	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.03	Vert(CT)	-0.02	11	n/r	120		
BCLL 0.0 **	Rep Stress Incr	YES	WB 0.06	Horz(CT)	0.00	12	n/a	n/a		
BCDL 10.0	Code	FBC2023/TPI2014	Matrix-S						Weight: 85 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	2-0-0 oc purlins (6-0-0 max.), except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x6 SP No.2 *Except*		
	2-17,10-13: 2x4 SP No.3		
OTHERS	2x4 SP No.3		

**REACTIONS.** All bearings 12-0-0.  
(lb) - Max Horz 18=-177(LC 10)  
Max Uplift All uplift 100 lb or less at joint(s) 18, 12 except 16=-110(LC 12), 17=-122(LC 12), 14=-110(LC 13), 13=-117(LC 13)  
Max Grav All reactions 250 lb or less at joint(s) 18, 12, 15, 16, 17, 14, 13

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 18, 12 except (jt=lb) 16=110, 17=122, 14=110, 13=117.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843239
4177528	T02	Common	3	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:38 2024 Page 1  
ID:21HcZl??AfWo44VTxHlsYnzam3y-d3r556XO3yHLFe9\_6fq?jI2oKXh7hOmghbfTk4yvw9x




Plate Offsets (X,Y)--		[3:0-3-12,0-3-0], [5:0-3-12,0-3-0]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL	1.25	TC 0.49		Vert(LL)	-0.10 9-11	>999	240	MT20	244/190
TCDL 7.0		Lumber DOL	1.25	BC 0.58		Vert(CT)	-0.19 9-11	>999	180		
BCLL 0.0 *		Rep Stress Incr	NO	WB 0.85		Horz(CT)	0.02 8	n/a	n/a		
BCDL 10.0		Code	FBC2023/TPI2014	Matrix-MS						Weight: 188 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-4-13 oc purlins, except end verticals.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-12,6-8: 2x6 SP No.2	WEBS 1 Row at midpt 3-12, 5-8

**REACTIONS.** (size) 12=0-3-8, 8=0-3-8  
Max Horz 12=317(LC 11)  
Max Uplift 12=-320(LC 12), 8=-320(LC 13)  
Max Grav 12=1396(LC 19), 8=1365(LC 20)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-424/230, 3-4=-1484/486, 4-5=-1447/486, 5-6=-424/230, 2-12=-465/262, 6-8=-465/262  
BOT CHORD 11-12=-287/1266, 9-11=-84/893, 8-9=-172/1135  
WEBS 4-9=-330/863, 5-9=-207/291, 4-11=-330/895, 3-11=-202/291, 3-12=-1248/219, 5-8=-1297/218

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 12-2-0, Zone2 12-2-0 to 16-4-15, Zone1 16-4-15 to 25-10-0 zone; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 12=320, 8=320.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25  
Uniform Loads (plf)  
Vert: 1-2=-54, 2-4=-54, 4-6=-54, 6-7=-54, 11-12=-20, 9-11=-80(F=-60), 8-9=-20

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843241
4177528	T03	Common	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:39 2024 Page 1  
ID:21HcZl??AfWo44VTxHlsYnzam3y-5FPTISY0qGPCtokAgMLEFybzEx1LQmrvFO1HXjyw9w




Plate Offsets (X,Y)--		[3:0-3-12,0-3-0], [5:0-4-0,0-3-0]										
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.48	Vert(LL)	-0.10	8-10	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.59	Vert(CT)	-0.19	8-10	>999	180		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.87	Horz(CT)	0.02	7	n/a	n/a		
BCDL	10.0	Code FBC2023/TP12014		Matrix-MS							Weight: 185 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-5-13 oc purlins, except end verticals.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-11,6-7: 2x6 SP No.2	WEBS 1 Row at midpt 3-11, 5-7

REACTIONS. (size) 11=0-3-8, 7=0-3-8  
Max Horz 11=269(LC 9)  
Max Uplift 11=-319(LC 12), 7=-275(LC 13)  
Max Grav 11=1367(LC 19), 7=1275(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-414/237, 3-4=-1440/487, 4-5=-1449/491, 5-6=-385/185, 2-11=-458/266, 6-7=-341/182  
BOT CHORD 10-11=-330/1208, 8-10=-118/845, 7-8=-216/1085  
WEBS 4-8=-336/874, 5-8=-220/299, 4-10=-332/862, 3-10=-206/292, 3-11=-1248/229, 5-7=-1264/268

- NOTES-
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 12-2-0, Zone2 12-2-0 to 16-4-15, Zone1 16-4-15 to 24-1-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 11=319, 7=275.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard  
1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25  
Uniform Loads (plf)  
Vert: 1-2=-54, 2-4=-54, 4-6=-54, 10-11=-20, 8-10=-80(F=-60), 7-8=-20

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843242
4177528	T04	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:39 2024 Page 1  
ID:21HcZI??AfWo44VTxHsYnzam3y-5FPTISY0qGPCtokAgMLEFyb?Qx57QzNrvFO1HXjyw9w




Plate Offsets (X,Y)--		[3:0-3-0,0-3-0], [4:0-6-4,0-2-0], [5:0-2-0,0-1-13]
LOADING (psf)	SPACING-	2-0-0
TCLL 20.0	Plate Grip DOL	1.25
TCDL 7.0	Lumber DOL	1.25
BCLL 0.0 *	Rep Stress Incr	YES
BCDL 10.0	Code	FBC2023/TPI2014
	CSI.	TC 0.34
		BC 0.34
		WB 0.38
		Matrix-MS
	DEFL.	in (loc) l/defl L/d
	Vert(LL)	-0.03 13-14 >999 240
	Vert(CT)	-0.07 13-14 >999 180
	Horz(CT)	0.02 8 n/a n/a
	PLATES	GRIP
	MT20	244/190
	Weight: 191 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-5-2 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except*	WEBS 1 Row at midpt 4-10
2-14,7-8: 2x6 SP No.2	

**REACTIONS.** (size) 14=0-3-8, 8=0-3-8  
Max Horz 14=248(LC 9)  
Max Uplift 14=-247(LC 12), 8=-204(LC 13)  
Max Grav 14=980(LC 1), 8=880(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-987/237, 3-4=-771/293, 4-5=-518/272, 5-6=-774/295, 6-7=-988/234, 2-14=-923/264, 7-8=-823/219  
BOT CHORD 13-14=-276/321, 12-13=-226/719, 10-12=-87/519, 9-10=-117/687  
WEBS 3-12=-313/236, 4-12=-155/290, 5-10=-148/282, 6-10=-326/245, 2-13=-51/576, 7-9=-83/575

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 1-6-0 to 1-6-0, Zone1 1-6-0 to 11-0-13, Zone3 11-0-13 to 13-3-3, Zone2 13-3-3 to 17-6-2, Zone1 17-6-2 to 24-4-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 14=247, 8=204.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com







Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843244
4177528	T06	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:41 2024 Page 1  
ID:21HcZI??AfW044VTxHlsYnzam3y-1eXDj7ZHMTgv65tZnnNiKngCMkkNupZ7MZt8LPyiw9u




Plate Offsets (X,Y)--		[2:0-2-4,0-1-8], [3:0-4-4,0-2-0]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC	0.95	Vert(LL)	-0.09 12-13	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.55	Vert(CT)	-0.19 12-13	>999	180		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.59	Horz(CT)	0.02 8	n/a	n/a		
BCDL	10.0	Code	FBC2023/TP12014	Matrix-MS						Weight: 186 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-10-5 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 8-1-7 oc bracing: 12-13.
WEBS 2x4 SP No.3 *Except* 2-13: 2x6 SP No.2	

REACTIONS.	(size) 8=0-3-8, 13=0-3-8
	Max Horz 13=297(LC 12)
	Max Uplift 8=228(LC 13), 13=245(LC 12)
	Max Grav 8=999(LC 2), 13=1050(LC 19)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-1049/219, 3-4=-720/259, 4-5=-801/253, 5-6=-841/273, 6-7=-727/177, 7-8=-863/243, 2-13=-924/268
BOT CHORD	12-13=-528/495, 10-12=-257/781, 9-10=-182/738
WEBS	3-12=-18/367, 4-10=-505/265, 5-10=-252/848, 6-10=-289/125, 6-9=-529/216, 7-9=-250/1009, 2-12=-122/529

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 7-10-6, Zone3 7-10-6 to 11-2-6, Zone1 11-2-6 to 13-10-0, Zone3 13-10-0 to 17-6-12, Zone1 17-6-12 to 24-2-4 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=228, 13=245.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:41 2024 Page 1  
 ID:21HcZl??AfWo44VtXsHsYnzam3y-1eXDj7ZHMTgv65tZnnNiKngKkkk2uqh7MzI8LPjw9u  
 -1-6-0 6-3-3 9-7-3 13-10-0 15-11-9 20-0-1 24-4-0  
 1-6-0 6-3-3 3-4-0 4-2-13 2-1-9 4-0-7 4-3-15



<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-3-11 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2		
WEBS	2x4 SP No.3 *Except*	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
	2-14: 2x6 SP No.2		8-9-13 oc bracing: 13-14.
		WEBS	1 Row at midpt                      8-9, 6-10

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**TOP CHORD** 2-3=-1087/212, 3-4=-773/235, 4-5=-876/213, 5-6=-833/256, 6-7=-457/107,  
7-8=-457/107, 8-9=-933/251, 2-14=-969/253

**BOT CHORD** 13-14=-450/318, 11-13=-338/929, 10-11=-190/680

**WEBS** 3-13=-26/442, 4-13=-304/67, 4-11=-500/267, 5-11=-193/871, 6-10=-512/186,  
7-10=-264/149, 8-10=-226/969, 2-13=-74/623

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCFL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., Gcpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 1-6-0 to 1-6-0, Zone1 1-6-0 to 6-3-3, Zone3 6-3-3 to 9-7-3, Zone1 9-7-3 to 13-10-0, Zone3 13-10-0 to 15-11-9, Zone1 15-11-9 to 24-2-4 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 4) Provide adequate drainage to prevent water ponding.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=243. 14=237.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27, 2024




Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Components Association ([www.sbsccomponents.com](http://www.sbsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843246
4177528	T08	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:42 2024 Page 1  
ID:21HcZl?AfWo44VTxHlsYnzam3y-Wq5bxTav7BomkFSILUvxtbDUZ86DdF?HbDdhryjw9t  
-1-6-0 4-8-0 8-0-0 13-10-0 14-4-6 19-2-7 24-4-0  
1-6-0 4-8-0 3-4-0 5-10-0 0-6-6 4-10-1 5-1-9  
4x4 = Scale = 1:60.0





Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843247
4177528	T09	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:42 2024 Page 1

ID:21HcZl??AfWo44VTxHlsYnzam3y-Wq5bxTav7BomkFSILUvxtbDTI80rdGyHbDdhtryjw9t




Plate Offsets (X,Y)--		[3:0-6-4,0-2-0], [6:0-2-0,0-1-13]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL	1.25	TC 0.46		Vert(LL)	-0.31 9-10	>937	240	MT20	244/190
TCDL 7.0		Lumber DOL	1.25	BC 0.79		Vert(CT)	-0.47 9-10	>609	180		
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.58		Horz(CT)	0.02 9	n/a	n/a		
BCDL 10.0		Code	FBC2023/TP12014	Matrix-MS						Weight: 191 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-2-10 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2 *Except*	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
	9-11: 2x4 SP No.1	WEBS	1 Row at midpt 8-9, 5-10, 7-9
WEBS	2x4 SP No.3 *Except*		
	2-14: 2x6 SP No.2		

**REACTIONS.** (size) 9=0-3-8, 14=0-3-8  
Max Horz 14=400(LC 12)  
Max Uplift 9=266(LC 9), 14=215(LC 12)  
Max Grav 9=1033(LC 2), 14=1071(LC 2)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-982/179, 3-4=-1332/221, 4-5=-1829/390, 5-6=-830/178, 6-7=-586/186,  
2-14=-1006/226  
BOT CHORD 13-14=-378/228, 12-13=-444/751, 10-12=-353/876, 9-10=-111/357  
WEBS 3-12=-74/930, 4-12=-1282/346, 5-12=-291/1008, 5-10=-566/314, 6-10=-24/326,  
7-10=-196/650, 7-9=-853/273, 2-13=-72/745

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 1-6-0 to 1-6-0, Zone1 1-6-0 to 3-0-13, Zone3 3-0-13 to 6-4-13, Zone1 6-4-13 to 14-10-13, Zone2 14-10-13 to 19-1-12, Zone1 19-1-12 to 24-2-4 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=266, 14=215.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843248
4177528	T10	Piggyback Base Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:43 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-\_Of\_8pbXtVwdMP1yvCQAQolftYR9MfWQptMEQlyjw9s




Plate Offsets (X,Y)--		[3:0-6-4,0-2-0], [6:0-6-4,0-2-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.43
TCDL 7.0	Lumber DOL	1.25	BC 0.40
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.88
BCDL 10.0	Code	FBC2023/TP12014	Matrix-MS
		DEFL.	in (loc) l/defl L/d
		Vert(LL)	-0.07 13-14 >999 240
		Vert(CT)	-0.12 13-14 >999 180
		Horz(CT)	0.02 9 n/a n/a
		PLATES	GRIP
		MT20	244/190
		Weight: 222 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-6-11 oc purlins, except end verticals.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-16: 2x6 SP No.2	WEBS 1 Row at midpt 8-9, 6-10, 7-10

**REACTIONS.** (size) 9=0-3-8, 16=0-3-8  
Max Horz 16=405(LC 8)  
Max Uplift 9=269(LC 5), 16=240(LC 8)  
Max Grav 9=1009(LC 2), 16=1060(LC 35)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-805/164, 3-4=-1633/289, 4-5=-1245/187, 5-6=-767/170, 6-7=-365/106, 7-8=-365/106, 8-9=-912/277, 2-16=-1063/252  
BOT CHORD 15-16=-356/144, 14-15=-463/663, 13-14=-628/1765, 11-13=-393/982, 10-11=-194/540  
WEBS 3-15=-325/52, 3-14=-185/1284, 4-14=-626/141, 4-13=-844/254, 5-13=-68/537, 5-11=-704/315, 6-11=-210/718, 6-10=-499/225, 7-10=-282/168, 8-10=-262/902, 2-15=-137/714

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=269, 16=240.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 65 lb down and 35 lb up at 2-7-11 on top chord, and 21 lb down and 72 lb up at 1-5-10, and 19 lb down and 8 lb up at 2-7-11 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25  
Uniform Loads (plf)  
Vert: 1-2=-54, 2-3=-54, 3-4=-54, 4-6=-54, 6-8=-54, 9-16=-20

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843248
4177528	T10	Piggyback Base Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:43 2024 Page 2  
ID:21HcZI??AfWo44VTxHlsYnzam3y-\_Of\_8pbXtVwdMP1yvCQAQolftYR9MfWQptMEQljw9s

**LOAD CASE(S)** Standard  
Concentrated Loads (lb)  
Vert: 15=25(B) 18=8(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / [MiTek-US.com](http://MiTek-US.com)



**Standard**  
**WARNING:** Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. This design is for use on a truss member and is not valid for use on a truss end or a truss web. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinet.org](http://www.tpinet.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

**MiTek®**  
 16023 Swingley Ridge Rd.  
 Chesterfield, MO 63017  
 314.434.1200 / [MiTek-US.com](http://MiTek-US.com)



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843249
4177528	T11	Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:44 2024 Page 2  
ID:21HcZI?AfWo44VTxHIsYnzam3y-SDDMM9c9eo2UzZc8TvxPy0lpwyc56ca2X6oykyjw9r

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)  
Vert: 1-2=-54, 2-3=-54, 3-8=-54, 8-10=-54, 10-11=-54, 18-21=-20, 14-17=-20, 12-13=-20
- Concentrated Loads (lb)  
Vert: 3=-26(B) 6=-7(B) 8=-7(B) 20=-296(B) 19=-136(B) 4=-26(B) 15=-323(B) 22=-26(B) 23=-26(B) 24=-26(B) 25=-7(B) 26=-7(B) 27=-136(B) 28=-136(B) 29=-136(B)  
30=-159(B) 31=-159(B) 32=-159(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

MiTek®

16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843250
4177528	T12	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:44 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-SDDMM9c9eo2UzZc8TvxPy0lpUye45Efa2X6oykyjw9r




Plate Offsets (X,Y)--		[2:0-1-0,0-1-8], [3:0-6-4,0-2-0], [5:0-6-4,0-2-0]										
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	20.0	Plate Grip DOL	1.25	TC	0.51	Vert(LL)	-0.07	13-14	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	1.00	Vert(CT)	-0.15	13-14	>999	180		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.31	Horz(CT)	0.12	8	n/a	n/a		
BCDL	10.0	Code	FBC2023/TPI2014	Matrix-MS							Weight: 177 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-9-4 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2 *Except*	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS	2x4 SP No.3 *Except*		1-7-8 oc bracing: 9-10.
	2-15,7-8: 2x6 SP No.2		

**REACTIONS.** (size) 15=0-3-8, 8=0-3-8  
Max Horz 15=201(LC 9)  
Max Uplift 15=-293(LC 12), 8=-249(LC 13)  
Max Grav 15=1066(LC 1), 8=967(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1099/285, 3-4=-1149/339, 4-5=-1150/339, 5-6=-1220/331, 6-7=-951/256,  
2-15=-1005/311, 7-8=-1049/282  
BOT CHORD 14-15=-272/358, 4-12=-402/231, 11-12=-191/874, 10-11=-297/1032  
WEBS 12-14=-239/690, 3-12=-213/566, 5-12=-212/441, 5-11=-33/297, 2-14=-223/582,  
7-9=-204/748

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 6-10-13, Zone2 6-10-13 to 11-1-11, Zone1 11-1-11 to 19-9-3, Zone2 19-9-3 to 24-0-2, Zone1 24-0-2 to 26-5-4 zone; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 15=293, 8=249.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843251
4177528	T13	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),	Lake City, FL - 32055,	8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:45 2024 Page 1
-1-6-0	4-4-12	ID:21HcZI??AfWo44VTxHlsYnzam3y-wPmkZVcnP6ALbjBK0dSeVDr?gM0oqbniHBrLUAyiw9q
1-6-0	4-4-12	18-2-0
	4-1-4	4-2-0
		24-4-8
		6-2-8
		2-3-8



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.42	Vert(LL)	-0.12 15-16 >999 240	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.84	Vert(CT)	-0.25 15-16 >999 180				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.64	Horz(CT)	0.12 9 n/a n/a				
BCDL	10.0	Code FBC2023/TP12014		Matrix-MS							
								Weight: 192 lb		FT = 20%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-11-12 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2 *Except*	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS	2x4 SP No.3 *Except*		9-11-5 oc bracing: 11-12
	2-16,8-9: 2x6 SP No.2		6-0-0 oc bracing: 10-11.

REACTIONS.	
(size)	9=0-3-8, 16=0-3-8
Max Horz	16=234(LC 9)
Max Uplift	9=243(LC 13), 16=287(LC 12)
Max Grav	9=967(LC 1), 16=1066(LC 1)

FORCES.	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	3-4=-988/317, 4-5=-913/306, 5-6=-913/304, 6-7=-1165/305, 7-8=-952/253, 2-16=-298/173, 8-9=-1046/274
BOT CHORD	15-16=-270/726, 5-13=-297/176, 12-13=-152/804, 11-12=-352/1121, 10-11=-264/96
WEBS	13-15=-205/670, 4-13=-150/396, 6-13=-177/287, 6-12=-42/320, 7-12=-398/303, 3-16=-941/184, 8-10=-234/778

NOTES-	
1) Unbalanced roof live loads have been considered for this design.	
2) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 1-6-0 to 1-6-0, Zone1 1-6-0 to 8-6-0, Zone2 8-6-0 to 12-8-15, Zone1 12-8-15 to 18-2-0, Zone2 18-2-0 to 22-4-15, Zone1 22-4-15 to 26-5-4 zone; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60	
3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.	
4) Provide adequate drainage to prevent water ponding.	
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.	
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.	
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=243, 16=287.	

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:


August 27,2024

<p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TP1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcsccomponents.com)</p>	<p><b>MiTek®</b></p> <p>16023 Swingley Ridge Rd. Chesterfield, MO 63017 314.434.1200 / MiTek-US.com</p>
---	---



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843252
4177528	T14	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:45 2024 Page 1  
ID:21HcZl??AFWo44VTxHlsYnzam3y-wPmkZVcnP6ALbjBK0dSeVDrzrM7QqhAjHBrLUAYjw9q



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.53	Vert(LL)	-0.07 10-12 >999 240	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.41	Vert(CT)	-0.12 10-12 >999 180				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.30	Horz(CT)	0.02 8 n/a n/a				
BCDL	10.0	Code FBC2023/TP12014		Matrix-MS							
								Weight: 189 lb FT = 20%			

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-3-4 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 *Except*	WEBS	1 Row at midpt 4-10
	2-14,7-8: 2x6 SP No.2		

REACTIONS.	
(size)	14=0-3-8, 8=0-3-8
Max Horz	14=267(LC 9)
Max Uplift	14=-279(LC 12), 8=-236(LC 13)
Max Grav	14=1143(LC 2), 8=1057(LC 2)

FORCES.	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	2-3=-1170/272, 3-4=-1020/312, 4-5=-727/303, 5-6=-1015/315, 6-7=-1169/271, 2-14=-1058/292, 7-8=-972/248
BOT CHORD	13-14=-268/282, 12-13=-241/947, 10-12=-176/768, 9-10=-142/849
WEBS	3-12=-265/201, 4-12=-109/437, 5-10=-95/394, 6-10=-280/207, 2-13=-75/781, 7-9=-98/770

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 10-1-3, Zone2 10-1-3 to 14-4-2, Zone1 14-4-2 to 16-6-13, Zone2 16-6-13 to 20-9-11, Zone1 20-9-11 to 26-5-4 zone; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 14=279, 8=236.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843253
4177528	T15	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:46 2024 Page 1

ID:21HcZI??AfWo44VTxHsYnzam3y-ObK6mrdPAQICDtmXaKzt1RNBIIUDZ7stWrbv0dyjw9p




Plate Offsets (X,Y)--		[3:0-3-0,0-3-0], [4:0-6-4,0-2-0], [5:0-2-4,0-2-0]
LOADING (psf)	SPACING-	2-0-0
TCLL 20.0	Plate Grip DOL	1.25
TCDL 7.0	Lumber DOL	1.25
BCLL 0.0 *	Rep Stress Incr	YES
BCDL 10.0	Code	FBC2023/TP12014
	CSI.	TC 0.36
		BC 0.38
		WB 0.33
		Matrix-MS
	DEFL.	in (loc) l/defl L/d
	Vert(LL)	-0.03 12-13 >999 240
	Vert(CT)	-0.07 12-13 >999 180
	Horz(CT)	0.02 8 n/a n/a
	PLATES	GRIP
	MT20	244/190
	Weight: 202 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except*	WEBS 1 Row at midpt 3-12, 4-10, 6-10
2-14,7-8: 2x6 SP No.2	

**REACTIONS.** (size) 14=0-3-8, 8=0-3-8  
Max Horz 14=300(LC 11)  
Max Uplift 14=-271(LC 12), 8=-227(LC 13)  
Max Grav 14=1066(LC 1), 8=967(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1100/264, 3-4=-876/313, 4-5=-591/301, 5-6=-879/314, 6-7=-1102/262, 2-14=-1010/287, 7-8=-910/242  
BOT CHORD 13-14=-313/351, 12-13=-239/810, 10-12=-127/590, 9-10=-117/776  
WEBS 3-12=-326/246, 4-12=-151/312, 5-10=-144/306, 6-10=-338/254, 2-13=-62/674, 7-9=-91/670

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 1-6-0 to 1-6-0, Zone1 1-6-0 to 11-8-6, Zone3 11-8-6 to 14-11-10, Zone2 14-11-10 to 19-2-8, Zone1 19-2-8 to 26-5-4 zone; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 14=271, 8=227.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843254
4177528	T16	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:47 2024 Page 1  
ID:21HcZl??AfWo44VTxHlsYnzam3y-snuU\_Be2xjQ3q0Lj82U6aewM19qSla60kVKSZ3yiw9o




Plate Offsets (X,Y)--		[3:0-3-0,0-3-0], [4:0-6-4,0-2-0], [5:0-2-4,0-2-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.36
TCDL 7.0	Lumber DOL	1.25	BC 0.38
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.33
BCDL 10.0	Code	FBC2023/TP12014	Matrix-MS
DEFL.	in (loc)	I/defl	L/d
Vert(LL)	-0.03 12-13	>999	240
Vert(CT)	-0.07 12-13	>999	180
Horz(CT)	0.02 8	n/a	n/a
PLATES	GRIP		
MT20	244/190		
Weight: 202 lb		FT = 20%	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-14,7-8: 2x6 SP No.2	WEBS 1 Row at midpt 3-12, 4-10, 6-10

**REACTIONS.** (size) 14=0-3-8, 8=0-3-8  
Max Horz 14=300(LC 9)  
Max Uplift 14=-271(LC 12), 8=-227(LC 13)  
Max Grav 14=1066(LC 1), 8=967(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1100/264, 3-4=-876/313, 4-5=-591/301, 5-6=-879/314, 6-7=-1102/262, 2-14=-1010/287, 7-8=-910/242  
BOT CHORD 13-14=-313/351, 12-13=-239/810, 10-12=-127/590, 9-10=-117/776  
WEBS 3-12=-326/246, 4-12=-151/312, 5-10=-144/306, 6-10=-338/254, 2-13=-62/674, 7-9=-91/670

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 1-6-0 to 1-6-0, Zone1 1-6-0 to 11-8-6, Zone3 11-8-6 to 14-11-10, Zone2 14-11-10 to 19-2-8, Zone1 19-2-8 to 26-5-4 zone; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 14=271, 8=227.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843255
4177528	T17	Piggyback Base Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:47 2024 Page 2  
ID:21HcZl??AfWo44VTxHlsYnzam3y-snuU\_Be2xjQ3q0Lj82U6aewK59palZO0kVKSZ3yiw9o

**LOAD CASE(S)** Standard  
Concentrated Loads (lb)  
Vert: 16=-695(F) 17=-695(F)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / [MiTek-US.com](http://MiTek-US.com)



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843256
4177528	T18	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:48 2024 Page 1  
ID:21HcZlI?AfWo44VTxHlsYnzam3y-K\_SsBXfgi1YwSAwvii?L6sTUrZA211z9z94?5Vjyw9n



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.55	Vert(LL)	-0.04	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.35	Vert(CT)	-0.09				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.36	Horz(CT)	0.01				
BCDL	10.0	Code	FBC2023/TPI2014	Matrix-MS							
								Weight: 169 lb		FT = 20%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 *Except* 1-11: 2x6 SP No.2	WEBS	1 Row at midpt 2-8, 3-7, 4-7

REACTIONS.	
(size)	11=0-3-8, 6=0-3-8
Max Horz	11=248(LC 12)
Max Uplift	11=-165(LC 12), 6=-209(LC 12)
Max Grav	11=763(LC 1), 6=763(LC 1)

FORCES.	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	1-2=-844/182, 2-3=-595/215, 3-4=-317/204, 4-5=-514/192, 1-11=-710/180, 5-6=-707/225
BOT CHORD	10-11=-313/271, 8-10=-309/615, 7-8=-126/372
WEBS	2-8=-361/262, 3-8=-162/327, 3-7=-258/156, 1-10=-27/487, 5-7=-105/415

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 0-2-12 to 3-2-12, Zone1 3-2-12 to 11-8-6, Zone3 11-8-6 to 14-11-10, Zone2 14-11-10 to 19-2-8, Zone1 19-2-8 to 20-10-4 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 11=165, 6=209.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843257
4177528	T19	Piggyback Base	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:48 2024 Page 1  
ID:21HcZl??AFWo44VTxHlsYnzam3y-K\_SsBXfgi1YwSAwwil?L6sTVGZ7V1uU9z9475Vyyw9n




Plate Offsets (X,Y)--		[2:0-3-8,0-1-12], [3:0-3-12,0-2-0], [7:0-7-8,Edge], [9:0-8-12,0-2-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.46
TCDL 7.0	Lumber DOL	1.25	BC 0.52
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.90
BCDL 10.0	Code	FBC2023/TPI2014	Matrix-MS
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.07 9-15 >999 240
			Vert(CT) -0.12 9-15 >999 180
			Horz(CT) 0.03 7 n/a n/a
			PLATES GRIP
			MT20 244/190
			Weight: 172 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD 2-0-0 oc purlins (5-6-2 max.), except end verticals, and sheathed or
BOT CHORD 2x4 SP No.2 *Except*	6-0-0 oc purlins: 2-3.
5-10: 2x6 SP No.2	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 3-11, 1-12, 2-12
SLIDER Right 2x6 SP No.2 1-11-8	

**REACTIONS.** (size) 12=Mechanical, 7=0-3-8  
Max Horz 12=-353(LC 13)  
Max Uplift 12=-273(LC 13), 7=-169(LC 13)  
Max Grav 12=821(LC 20), 7=914(LC 20)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-335/160, 3-5=-1009/361, 5-7=-920/147  
BOT CHORD 11-12=-97/306, 5-9=-401/346, 7-9=0/712  
WEBS 2-11=-253/661, 3-11=-372/250, 9-11=-25/348, 3-9=-353/798, 2-12=-691/269

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 0-1-12 to 6-0-8, Zone2 6-0-8 to 10-3-7, Zone1 10-3-7 to 21-0-8 zone; end vertical right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 12=273, 7=169.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843259
4177528	T20G	GABLE Gable I Gable COMMON	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:50 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-HMadcCgwEeohU3lpA2pCHYoSNpEVtqSQSZ69Oyjw9l




Plate Offsets (X,Y)--	[2:0-6-11,0-0-4], [4:0-3-0,0-3-4], [5:0-3-12,0-2-0], [6:0-4-4,0-2-4], [7:0-3-0,0-3-4], [11:0-5-12,Edge], [11:0-3-8,Edge], [25:0-1-10,0-1-0]
-----------------------	---

LOADING (psf)	SPACING-		CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.67	Vert(LL) -0.10 21-44	>999	240	MT20	244/190		
TCDL 7.0	Lumber DOL 1.25	BC 0.50	Vert(CT) -0.17 21-44	>844	180				
BCLL 0.0 *	Rep Stress Incr YES	WB 0.59	Horz(CT) -0.03 2	n/a	n/a				
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS						Weight: 309 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD 2-0-0 oc purlins (5-9-11 max.).
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2x4 SP No.3	6-0-0 oc bracing: 15-17,11-13.
OTHERS 2x4 SP No.3	WEBS 1 Row at midpt 5-20, 6-18, 7-18
SLIDER Left 2x6 SP No.2 1-11-8	

REACTIONS.	All bearings 9-7-8 except (jt=length) 2=0-3-8, 20=0-3-8, 15=0-3-8, 15=0-3-8.
(lb) - Max Horz 2=-284(LC 10)	
Max Uplift All uplift 100 lb or less at joint(s) 14 except 11=-158(LC 9), 2=-242(LC 12), 20=-130(LC 13), 13=-243(LC 9), 15=-243(LC 13)	
Max Grav All reactions 250 lb or less at joint(s) 11, 14, 11 except 2=683(LC 27), 20=1134(LC 2), 13=500(LC 2), 15=904(LC 20), 15=818(LC 1)	

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-586/450, 4-5=-280/389, 5-6=-396/366, 6-7=-575/351, 7-8=-856/311	
BOT CHORD 2-21=-277/604, 20-21=-277/605, 18-20=-69/407, 17-18=-143/675	
WEBS 4-21=-146/313, 4-20=-575/377, 5-20=-656/57, 5-18=-125/561, 7-18=-449/259, 8-17=-201/832, 8-15=-834/289, 8-13=-264/104	

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 1-6-0 to 2-6-6, Zone1 2-6-6 to 15-6-0, Zone3 15-6-0 to 17-11-11, Zone2 17-11-11 to 23-8-2, Zone1 23-8-2 to 41-10-0 zone; end vertical left exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14 except (jt=lb) 11=158, 2=242, 20=130, 13=243, 15=243, 11=158.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843260
4177528	T21	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:51 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-lZ8?qYhY?ywVJeeUNiZ2kU4\_jm9ZEK8cf6lfiqyjw9k

1-6-0 7-10-0 15-6-0 18-6-0 25-1-4 31-8-7 35-6-0 40-4-0 41-10-0  
1-6-0 7-10-0 7-8-0 3-0-0 6-7-3 6-7-3 3-9-9 4-10-0 1-6-0



LOADING (psf)	SPACING-		CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25		TC 0.64	Vert(LL)	-0.10 20-23	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25		BC 0.49	Vert(CT)	-0.18 20-23	>816	180		
BCLL 0.0 *	Rep Stress Incr YES		WB 0.59	Horz(CT)	0.03 2	n/a	n/a		
BCDL 10.0	Code FBC2023/TP12014		Matrix-MS					Weight: 250 lb	FT = 20%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-4-12 oc purlins, except
BOT CHORD 2x4 SP No.2	2-0-0 oc purlins (6-0-0 max.): 6-7.
WEBS 2x4 SP No.3	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
SLIDER Left 2x6 SP No.2 1-11-8	6-0-0 oc bracing: 11-13.
	WEBS 1 Row at midpt 6-19, 7-17, 8-17

**REACTIONS.** All bearings 0-3-8.  
(lb) - Max Horz 2=-285(LC 10)  
Max Uplift All uplift 100 lb or less at joint(s) except 2=-242(LC 12), 19=-148(LC 13), 13=-363(LC 13), 11=-205(LC 9)  
Max Grav All reactions 250 lb or less at joint(s) 11 except 2=674(LC 27), 19=1239(LC 2), 13=1363(LC 2)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-570/449, 5-6=-269/388, 6-7=-438/378, 7-8=-619/373, 8-9=-987/346, 9-10=-131/482, 10-11=-26/338  
BOT CHORD 2-20=-273/586, 19-20=-273/586, 17-19=-65/415, 16-17=-162/781, 14-16=-90/577, 13-14=-85/586, 11-13=-277/60  
WEBS 5-20=-147/304, 5-19=-571/377, 6-19=-740/70, 6-17=-130/618, 8-17=-569/282, 8-16=0/268, 9-16=-76/251, 9-13=-1417/383, 10-13=-342/221

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 2-6-6, Zone1 2-6-6 to 15-6-0, Zone3 15-6-0 to 18-6-0, Zone2 18-6-0 to 24-2-7, Zone1 24-2-7 to 41-10-0 zone; end vertical left exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 242 lb uplift at joint 2, 148 lb uplift at joint 19, 363 lb uplift at joint 13 and 205 lb uplift at joint 11.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024








Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843262
4177528	T22G	GABLE II	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:53 2024 Page 1  
ID:21HcZl??AfWo44VTxHlsYnzam3y-hxFIEEjoXZACYxotUibWpvAMKarniFdv7Qnmmyjw9i  
1-6-0, 7-10-0, 12-3-8, 15-6-0, 17-11-11, 21-6-0, 26-8-0, 31-8-7, 35-6-0, 40-4-0, 41-10-0  
1-6-0, 7-10-0, 4-5-8, 3-2-8, 2-5-11, 3-6-5, 5-2-0, 5-0-7, 3-9-9, 4-10-0, 1-6-0

Scale = 1:79.0



		7-10-0		12-0-0		12-3-8		17-11-11		21-6-0		26-8-0		30-8-8		35-6-0		40-4-0	
		7-10-0		4-2-0		0-3-8		5-8-3		3-6-5		5-2-0		4-0-8		4-9-8		4-10-0	
Plate Offsets (X,Y)--		[2:0-6-11,0-0-8],		[4:0-3-0,0-3-0],		[6:0-3-12,0-2-0],		[7:0-3-12,0-2-0],		[10:0-1-6,0-1-0],		[14:0-3-8,Edge],		[14:0-5-12,Edge],		[18:0-3-0,0-2-4],		[22:0-6-4,0-2-12]	
LOADING	(psf)	SPACING-		2-0-0		CSI.		DEFL.		in (loc)		I/defl		L/d		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL		1.25		TC 0.50		Vert(LL)		-0.10 23-43		>999		240		MT20		244/190	
TCDL	7.0	Lumber DOL		1.25		BC 0.51		Vert(CT)		-0.19 23-43		>774		180					
BCLL	0.0 *	Rep Stress Incr		YES		WB 0.52		Horz(CT)		0.07 18		n/a		n/a					
BCDL	10.0	Code FBC2023/TPI2014				Matrix-MS										Weight: 300 lb		FT = 20%	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD 2-0-0 oc purlins (6-0-0 max.).
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 5-22, 6-22, 7-21
OTHERS 2x4 SP No.3	
SLIDER Left 2x6 SP No.2 1-11-8	

**REACTIONS.** All bearings 9-7-8 except (jt=length) 2=0-3-8, 22=0-3-8.  
(lb) - Max Horz 2=-284(LC 10)  
Max Uplift All uplift 100 lb or less at joint(s) 17 except 14=-160(LC 9), 2=-260(LC 12), 22=-120(LC 13), 18=-291(LC 13), 16=-253(LC 9)  
Max Grav All reactions 250 lb or less at joint(s) 14, 17, 14 except 2=633(LC 27), 22=1153(LC 2), 18=1088(LC 2), 18=1043(LC 1), 16=281(LC 28)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-4=-501/427, 4-5=-210/343, 5-6=-174/405, 6-7=-330/334, 7-8=-839/496, 8-10=-881/358, 10-11=-662/236  
BOT CHORD 2-23=-309/498, 22-23=-309/498, 21-22=-123/397, 20-21=-77/497, 19-20=-105/617, 18-19=-798/249, 17-18=-352/103, 16-17=-352/103  
WEBS 4-23=-152/337, 4-22=-522/312, 6-22=-673/5, 6-21=-22/542, 7-21=-394/54, 7-20=-250/775, 8-20=-274/220, 10-19=-423/178, 11-19=-314/1233, 11-18=-781/257, 11-16=-38/256

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 2-6-6, Zone1 2-6-6 to 15-6-0, Zone3 15-6-0 to 17-11-11, Zone2 17-11-11 to 23-8-2, Zone1 23-8-2 to 41-10-0 zone; end vertical left exposed; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - Provide adequate drainage to prevent water ponding.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 17 except (jt=lb) 14=160, 2=260, 22=120, 18=291, 16=253, 14=160.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)


**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843263
4177528	T23	Piggyback Base	5	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:53 2024 Page 1  
ID:21HcZl??AfWo44VTxHIsYnzam3y-hxFIEEjoXZACYxotUlbWpvAHvapii8lv7Qnmmjyiw9i  
1-6-0 7-10-0 12-3-8 15-6-0 18-6-0 21-6-0 26-8-0 31-8-7 35-6-0 40-4-0 41-10-0  
1-6-0 7-10-0 4-5-8 3-2-8 3-0-0 3-0-0 5-2-0 5-0-7 3-9-9 4-10-0 1-6-0

Scale = 1:75.5





Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843263
4177528	T23	Piggyback Base	5	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:53 2024 Page 2  
ID:21HcZI??AfWo44VTxHlsYnzam3y-hxFIEEjoXZACYxotUlbWpvAHvapii8lv7Qnmmyjyw9i

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-6=-54, 6-7=-54, 7-8=-54, 8-10=-154, 10-31=-154, 13-31=-54, 19-21=-20, 17-19=-20, 15-17=-20, 15-25=-20

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / [MiTek-US.com](http://MiTek-US.com)




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843264
4177528	T24	Roof Special	2	1	Job Reference (optional)	


Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:54 2024 Page 1  
ID:21HcZl??AfWo44VTxHlsYnzam3y-98p8SajRltI3A5N3206IM7iVj\_9mRhX2L4XKJ9yJw9h

1-6-0 7-10-0 12-3-8 15-6-0 21-6-0 26-8-0 31-0-0 32-6-0  
1-6-0 7-10-0 4-5-8 3-2-8 6-0-0 5-2-0 4-4-0 1-6-0






**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843265
4177528	T24G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:55 2024 Page 2  
ID:21HcZI??AfWo44VTxHIsYnzam3y-dKNWfwk33BQwoFyFcje\_vKFeTOWpA2dBakGtrbjw9g

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)
- Vert: 1-7=-54, 7-14=-54, 2-18=-20, 16-18=-20, 16-36=-20
- Concentrated Loads (lb)
- Vert: 40=19(B) 41=7(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / [MiTek-US.com](http://MiTek-US.com)



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843266
4177528	T25	Common	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:56 2024 Page 1  
ID:21HcZI??AfWo44VTxHlsYnzam3y-5WxutGIhqUYnPPXSAR9DRYouqnr2vc8LpO0QN2yJw9f




Plate Offsets (X,Y)--		[1:0-3-8,Edge], [9:0-4-0,0-3-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.42
TCDL 7.0	Lumber DOL	1.25	BC 0.54
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.54
BCDL 10.0	Code	FBC2023/TPI2014	Matrix-MS
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.05 9-10 >999 240
			Vert(CT) -0.11 9-10 >999 180
			Horz(CT) 0.03 7 n/a n/a
			PLATES GRIP
			MT20 244/190
			Weight: 147 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-9-7 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	
SLIDER Left 2x6 SP No.2 1-11-8	

REACTIONS.	(size) 1=0-3-8, 7=Mechanical
	Max Horz 1=212(LC 9)
	Max Uplift 1=221(LC 12), 7=211(LC 13)
	Max Grav 1=907(LC 1), 7=907(LC 1)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-3=-1163/292, 3-4=-834/282, 4-5=-836/287, 5-6=-969/236, 6-7=-862/222
BOT CHORD	1-10=-315/940, 9-10=-315/940, 8-9=-147/757
WEBS	3-9=-425/269, 4-9=-159/510, 5-9=-252/207, 6-8=-147/763

NOTES-	
1) Unbalanced roof live loads have been considered for this design.	
2) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 0-0-0 to 3-0-0, Zone1 3-0-0 to 13-1-0, Zone2 13-1-0 to 17-3-15, Zone1 17-3-15 to 24-6-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60	
3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.	
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.	
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.	
6) Refer to girder(s) for truss to truss connections.	
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 221 lb uplift at joint 1 and 211 lb uplift at joint 7.	

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**

16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843267
4177528	T25G	GABLE	1	1	Job Reference (optional)	




Plate Offsets (X,Y)--	[2:0-6-0,0-2-12], [4:0-5-0,0-0-12], [7:0-2-0,0-1-8], [8:0-5-0,0-0-12], [9:0-4-12,0-3-0], [10:Edge,0-3-8], [11:0-3-8,0-4-8], [12:0-5-0,0-6-0]
-----------------------	--

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.96	Vert(LL)	0.12 12-13	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.25	Vert(CT)	-0.15 11-12	>999	180	MT20HS	187/143
BCLL 0.0 *	Rep Stress Incr NO	WB 0.97	Horz(CT)	0.02 10	n/a	n/a		
BCDL 10.0	Code FBC2023/TP12014	Matrix-MS					Weight: 235 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD 2-0-0 oc purlins (2-11-12 max.), except end verticals.
BOT CHORD 2x8 SP 2400F 2.0E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 6-12, 8-12
OTHERS 2x4 SP No.3	
SLIDER Left 2x6 SP No.2 1-3-5	

**REACTIONS.** (size) 2=0-3-8, 10=Mechanical  
Max Horz 2=222(LC 26)  
Max Uplift 2=952(LC 8), 10=1167(LC 9)  
Max Grav 2=1997(LC 1), 10=2834(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-4=2758/1398, 4-6=2241/1132, 6-8=2242/1130, 8-9=3115/1310, 9-10=2453/1032  
BOT CHORD 2-13=1237/2282, 12-13=1235/2274, 11-12=1044/2564  
WEBS 4-13=301/405, 4-12=655/524, 6-12=1088/2044, 8-12=999/438, 8-11=269/796, 9-11=1036/2543

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TP1 1.
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - All plates are MT20 plates unless otherwise indicated.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 952 lb uplift at joint 2 and 1167 lb uplift at joint 10.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 481 lb down and 460 lb up at 8-3-8, 212 lb down and 206 lb up at 10-4-12, 188 lb down and 177 lb up at 12-4-12, 356 lb down and 157 lb up at 14-4-12, 356 lb down and 157 lb up at 16-4-12, 356 lb down and 157 lb up at 18-4-12, 356 lb down and 157 lb up at 20-4-12, and 356 lb down and 157 lb up at 22-10-6 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

Continue on Page 6 CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843267
4177528	T25G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:56 2024 Page 2  
ID:21HcZI??AfWo44VTxHIsYnzam3y-5WxutGlhqUYnPPXSAR9DRYolMnwXvVPLpO0QN2yiw9f

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)  
Vert: 1-6=-54, 6-9=-54, 2-10=-20
- Concentrated Loads (lb)  
Vert: 22=-436(B) 23=-191(B) 24=-182(B) 25=-356(B) 26=-356(B) 27=-356(B) 28=-356(B) 29=-356(B) 30=-356(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / [MiTek-US.com](http://MiTek-US.com)




Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843268
4177528	T26	Common	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:57 2024 Page 1

ID:21HcZI??AfWo44VTxHlsYnzam3y-ZjVG4bmJaohe1Z6ej8gS\_IK3dBEeeANU12I\_vUyjiw9e



LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 2-0-0	TC 0.42	Vert(LL)	-0.03	6-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.32	Vert(CT)	-0.06	6-7	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.09	Horz(CT)	0.00	6	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MS						Weight: 80 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 2-8,4-6: 2x6 SP No.2	

**REACTIONS.** (size) 8=0-3-8, 6=0-3-8  
Max Horz 8=-200(LC 10)  
Max Uplift 8=-143(LC 12), 6=-143(LC 13)  
Max Grav 8=545(LC 1), 6=545(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-425/169, 3-4=-425/169, 2-8=-491/292, 4-6=-491/292  
BOT CHORD 7-8=-231/309

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 6-4-0, Zone2 6-4-0 to 10-6-15, Zone1 10-6-15 to 14-2-0 zone; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 143 lb uplift at joint 8 and 143 lb uplift at joint 6.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843269
4177528	T26G	Common Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:58 2024 Page 1  
ID:21HcZl??AfWo44VTxHlsYnzam3y-2v3elxnxL6pVfjhqHrBhWztG1bflNd\_eGiVXSwyJw9d





Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843270
4177528	T27	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:58 2024 Page 1  
ID:21HcZI??AfW044VTxHlsYnzam3y-2v3elxnxL6pVfjqHrBhWztCxbWfNZdeGivXSwyiw9d




Plate Offsets (X,Y)-- [5:0-3-8,Edge]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d					PLATES GRIP	
TCLL	20.0	Plate Grip DOL 1.25		TC	0.51	Vert(LL)	-0.08	8-10	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL 1.25		BC	0.59	Vert(CT)	-0.18	8-10	>999	180		
BCLL	0.0 *	Rep Stress Incr YES		WB	0.35	Horz(CT)	0.03	7	n/a	n/a		
BCDL	10.0	Code FBC2023/TPI2014		Matrix-MS							Weight: 90 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-4-6 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 8-2-7 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midpt 3-8

**REACTIONS.** (size) 2=0-3-8, 7=0-3-8  
Max Horz 2=187(LC 11)  
Max Uplift 2=-200(LC 12), 7=-170(LC 13)  
Max Grav 2=692(LC 1), 7=701(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1786/565, 3-4=-626/242, 4-5=-642/247, 5-7=-649/358  
BOT CHORD 2-10=-505/1720, 8-10=-512/1711  
WEBS 3-8=-1327/536, 4-8=-78/425, 5-8=-97/336

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 10-4-0, Zone2 10-4-0 to 14-6-15, Zone1 14-6-15 to 18-2-0 zone; end vertical right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=200, 7=170.

This item has been digitally signed and sealed by ORegan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843271
4177528	T27G	Roof Special Structural Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:45:59 2024 Page 1

ID:21HcZl??AfWo44VTxHlsYnzam3y-W5d1VHnZ6PxMGsG0rZiw3AQNg?xK64unVME5\_MyJw9c




Plate Offsets (X,Y)--		[2:0-3-8,Edge], [2:0-5-12,Edge], [4:0-2-12,0-1-12]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL	1.25	TC 0.51		Vert(LL)	-0.03 8-9	>999	240	MT20	244/190
TCDL 7.0		Lumber DOL	1.25	BC 0.31		Vert(CT)	-0.06 8-9	>999	180		
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.09		Horz(CT)	0.00 8	n/a	n/a		
BCDL 10.0		Code	FBC2023/TPI2014	Matrix-MS						Weight: 93 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD 2-0-0 oc purlins (6-0-0 max.), except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 6-8: 2x6 SP No.2	

**REACTIONS.** All bearings 4-3-8 except (jt=length) 8=0-3-8.  
(lb) - Max Horz 2=187(LC 11)  
Max Uplift All uplift 100 lb or less at joint(s) except 2=147(LC 8), 11=180(LC 12), 8=146(LC 13)  
Max Grav All reactions 250 lb or less at joint(s) 2, 2 except 11=619(LC 1), 11=619(LC 1), 8=550(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 4-5=-432/178, 5-6=-431/181, 6-8=-495/312  
WEBS 4-11=-498/252

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-6-0, Zone1 1-6-0 to 10-4-0, Zone2 10-4-0 to 14-6-15, Zone1 14-6-15 to 18-2-0 zone; end vertical right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 147 lb uplift at joint 2, 180 lb uplift at joint 11, 146 lb uplift at joint 8 and 147 lb uplift at joint 2.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

August 27,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com



Job	Truss	Truss Type	Qty	Ply	IC CONST. - LIPPI RES.	T34843272
4177528	T28	Roof Special Girder	1	2	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Aug 15 2024 MiTek Industries, Inc. Mon Aug 26 16:46:00 2024 Page 2  
ID:21HcZI??AfWo44VTxHlsYnzam3y-\_JAPidoBtj3Du0qDPGD9cOyZsPGHrLKwk0\_eWpyjw9b

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)
- Vert: 1-3=-54, 3-5=-54, 5-8=-54, 2-13=-20
- Concentrated Loads (lb)
- Vert: 10=-2814(F) 13=-895(F) 19=-887(F) 20=-887(F)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcsccomponents.com](http://www.sbcsccomponents.com))


MiTek®

16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MiTek-US.com




## Symbols

### PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

—  
This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in MITek software or upon request.

### PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

### LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

### BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.


#### Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.  
DSB-22: Design Standard for Bracing.  
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

## Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)

1 2 3 Joint ID typ.



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

## Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282  
ESR-4722, ESL-1388

## Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

# MITek®

MITek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023

## General Safety Notes

**Failure to Follow Could Cause Property Damage or Personal Injury**

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.