



Alpine, an ITW Company 6750 Forum Drive, Suite 305 Orlando, FL 32821 Phone: (800)755-6001 www.alpineitw.com

Site Information:

Customer: W. B. Howland Company, Inc.

Job Number: 21-5152

Job Description: CJ Customs-Curtis Jones-Spec House

Address: LAKE CITY, FL

Job Engineering Criteria:				
Design Code: FBC 7th Ed. 2020 Res	IntelliVIEW Version: 20.01.01A			
	JRef #: 1X542150016			
Wind Standard: ASCE 7-16 Wind Speed (mph): 130	Design Loading (psf): 40.00			
Building Type: Closed				

This package contains general notes pages, 26 truss drawing(s) and 5 detail(s).

Item	Drawing Number	Truss
1	124.21.1601.55752	A01
3	124.21.1601.55909	A03
5	124.21.1601.55564	A05
7	124.21.1601.55736	A07
9	124.21.1601.55392	A09
11	124.21.1601.55908	C01
13	124.21.1601.55767	C03
15	124.21.1601.55424	E01
17	124.21.1605.38967	G01
19	124.21.1605.44113	PB01
21	124.21.1605.48970	PB03
23	124.21.1601.55363	PB05
25	124.21.1601.55940	PB07
27	A14015ENC160118	
29	BRCLBSUB0119	
31	PB160160118	

Item	Drawing Number	Truss
2	124.21.1601.55720	A02
4	124.21.1601.55971	A04
6	124.21.1601.55970	A06
8	124.21.1605.21647	A08
10	124.21.1601.55721	B01
12	124.21.1601.55425	C02
14	124.21.1601.56002	C04
16	124.21.1601.55690	E02
18	124.21.1601.55830	J01
20	124.21.1601.55362	PB02
22	124.21.1601.55691	PB04
24	124.21.1601.55393	PB06
26	124.21.1601.55394	PB08
28	A14030ENC160118	
30	GBLLETIN0118	

### **General Notes**

### Truss Design Engineer Scope of Work, Design Assumptions and Design Responsibilities:

The design responsibilities assumed in the preparation of these design drawings are those specified in ANSI/TPI 1, Chapter 2; and the National Design Standard for Metal Plate Connected Wood Truss Construction, by the Truss Plate Institute. The truss component designs conform to the applicable provisions of ANSI/TPI 1 and NDS, the National Design Specification for Wood Construction by AWC. The truss component designs are based on the specified loading and dimension information furnished by others to the Truss Design Engineer. The Truss Design Engineer has no duty to independently verify the accuracy or completeness of the information provided by others and may rely on that information without liability. The responsibility for verification of that information remains with others neither employed nor controlled by the Truss Design Engineer. The Truss Design Engineer's seal and signature on the attached drawings, or cover page listing these drawings, indicates acceptance of professional engineering responsibility solely for the truss component designs and not for the technical information furnished by others which technical information and consequences thereof remain their sole responsibility.

The suitability and use of these drawings for any particular structure is the responsibility of the Building Designer in accordance with ANSI/TPI 1 Chapter 2. The Building Designer is responsible for determining that the dimensions and loads for each truss component match those required by the plans and by the actual use of the individual component, and for ascertaining that the loads shown on the drawings meet or exceed applicable building code requirements and any additional factors required in the particular application. Truss components using metal connector plates with integral teeth shall not be placed in environments that will cause the moisture content of the wood in which plates are embedded to exceed 19% and/or cause corrosion of connector plates and other metal fasteners.

The Truss Design Engineer shall not be responsible for items beyond the specific scope of the agreed contracted work set forth herein, including but not limited to: verifying the dimensions of the truss component, calculation of any of the truss component design loads, inspection of the truss components before or after installation, the design of temporary or permanent bracing and their attachment required in the roof and/or floor systems, the design of diaphragms or shear walls, the design of load transfer connections to and from diaphragms and shear walls, the design of load transfer to the foundation, the design of connections for truss components to their bearing supports, the design of the bearing supports, installation of the truss components, observation of the truss component installation process, review of truss assembly procedures, sequencing of the truss component installation, construction means and methods, site and/or worker safety in the installation of the truss components and/or its connections.

This document may be a high quality facsimile of the original engineering document which is a digitally signed electronic file with third party authentication. A wet or embossed seal copy of this engineering document is available upon request.

### **Temporary Lateral Restraint and Bracing:**

Temporary lateral restraint and diagonal bracing shall be installed according to the provisions of BCSI chapters B1, B2, B7 and/or B10 (Building Component Safety Information, by TPI and SBCA), or as specified by the Building Designer or other Registered Design Professional. The required locations for lateral restraint and/or bracing depicted on these drawings are only for the permanent lateral support of the truss members to reduce buckling lengths, and do not apply to and may not be relied upon for the temporary stability of the truss components during their installation.

### Permanent Lateral Restraint and Bracing:

The required locations for lateral restraint or bracing depicted on these drawings are for the permanent lateral support of the truss members to reduce buckling lengths. Permanent lateral support shall be installed according to the provisions of BCSI chapters B3, B7 and/or B10, or as specified by the Building Designer or other Registered Design Professional. These drawings do not depict or specify installation/erection bracing, wind bracing, portal bracing or similar building stability bracing which are parts of the overall building design to be specified, designed and detailed by the Building Designer.

### **Connector Plate Information:**

Alpine connector plates are made of ASTM A653 or ASTM A1063 galvanized steel with the following designations, gauges and grades: W=Wave, 20ga, grade 40; H=High Strength, 20ga, grade 60; S=Super Strength, 18ga, grade 60. Information on model code compliance is contained in the ICC Evaluation Service report ESR-1118, available on-line at www.icc-es.org.

### Fire Retardant Treated Lumber:

Fire retardant treated lumber must be properly re-dried and maintained below 19% or less moisture level through all stages of construction and usage. Fire retardant treated lumber may be more brittle than untreated lumber. Special handling care must be taken to prevent breakage during all handling activities.

### **General Notes** (continued)

### **Key to Terms:**

Information provided on drawings reflects a summary of the pertinent information required for the truss design. Detailed information on load cases, reactions, member lengths, forces and members requiring permanent lateral support may be found in calculation sheets available upon written request.

BCDL = Bottom Chord standard design Dead Load in pounds per square foot.

BCLL = Bottom Chord standard design Live Load in pounds per square foot.

CL = Certified lumber.

Des Ld = total of TCLL, TCDL, BCLL and BCDL Design Load in pounds per square foot.

FRT = Fire Retardant Treated lumber.

FRT-DB = D-Blaze Fire Retardant Treated lumber.

FRT-DC = Dricon Fire Retardant Treated lumber.

FRT-FP = FirePRO Fire Retardant Treated lumber.

FRT-FL = FlamePRO Fire Retardant Treated lumber.

FRT-FT = FlameTech Fire Retardant Treated lumber.

FRT-PG = PYRO-GUARD Fire Retardant Treated lumber.

g = green lumber.

HORZ(LL) = maximum Horizontal panel point deflection due to Live Load, in inches.

HORZ(TL) = maximum Horizontal panel point long term deflection in inches, due to Total Load, including creep adjustment.

HPL = additional Horizontal Load added to a truss Piece in pounds per linear foot or pounds.

Ic = Incised lumber.

FJ = Finger Jointed lumber.

L/# = user specified divisor for limiting span/deflection ratio for evaluation of actual L/defl value.

L/defl = ratio of Length between bearings, in inches, divided by the vertical Deflection due to creep, in inches, at the referenced panel point. Reported as 999 if greater than or equal to 999.

Loc = Location, starting location of left end of bearing or panel point (joint) location of deflection.

Max BC CSI = Maximum bending and axial Combined Stress Index for Bottom Chords for of all load cases.

Max TC CSI = Maximum bending and axial Combined Stress Index for Top Chords for of all load cases.

Max Web CSI= Maximum bending and axial Combined Stress Index for Webs for of all load cases.

NCBCLL = Non-Concurrent Bottom Chord design Live Load in pounds per square foot.

PL = additional Load applied at a user specified angle on a truss Piece in pounds per linear foot or pounds.

PLB = additional vertical load added to a Bottom chord Piece of a truss in pounds per linear foot or pounds

PLT = additional vertical load added to a Top chord Piece of a truss in pounds per linear foot or pounds.

PP = Panel Point.

R = maximum downward design Reaction, in pounds, from all specified gravity load cases, at the indicated location (Loc).

-R = maximum upward design Reaction, in pounds, from all specified gravity load cases, at the identified location (Loc).

Rh = maximum horizontal design Reaction in either direction, in pounds, from all specified gravity load cases, at the indicated location (Loc).

RL = maximum horizontal design Reaction in either direction, in pounds, from all specified non-gravity (wind or seismic) load cases, at the indicated location (Loc).

Rw = maximum downward design Reaction, in pounds, from all specified non-gravity (wind or seismic) load cases, at the identified location (Loc).

TCDL = Top Chord standard design Dead Load in pounds per square foot.

TCLL = Top Chord standard design Live Load in pounds per square foot.

U = maximum Upward design reaction, in pounds, from all specified non-gravity (wind or seismic) load cases, at the indicated location (Loc).

VERT(CL) = maximum Vertical panel point deflection in inches due to Live Load and Creep Component of Dead Load in inches.

VERT(CTL) = maximum Vertical panel point deflection ratios due to Live Load and Creep Component of Dead Load, and maximum long term Vertical panel point deflection in inches due to Total load, including creep adjustment.

VERT(LL) = maximum Vertical panel point deflection in inches due to Live Load.

VERT(TL) = maximum Vertical panel point long term deflection in inches due to Total load, including creep adjustment. W = Width of non-hanger bearing, in inches.


Refer to ASCE-7 for Wind and Seismic abbreviations.

Uppercase Acronyms not explained above are as defined in TPI 1.

### References:

- 1. AWC: American Wood Council; 222 Catoctin Circle SE, Suite 201; Leesburg, VA 20175; www.awc.org.
- 2. ICC: International Code Council; www.iccsafe.org.
- 3. Alpine, a division of ITW Building Components Group Inc.: 514 Earth City Expressway, Suite 242, Earth City, MO 63045; <a href="https://www.alpineitw.com">www.alpineitw.com</a>.
- 4. TPI: Truss Plate Institute, 2670 Crain Highway, Suite 203, Waldorf, MD 20601; www.tpinst.org.
- 5. SBCA: Wood Truss Council of America, 6300 Enterprise Lane, Madison, WI 53719; www.sbcindustry.com.

SEQN: 372018 / GABL Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T2 / FROM: CDM Qty: 1 DrwNo: 124.21.1601.55752 CJ Customs-Curtis Jones-Spec House Truss Label: A01 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria	4
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#	١.
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.013 C 999 240	L
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.025 C 999 180	1
	Risk Category: II	Snow Duration: NA	HORZ(LL): -0.005 J	١v
Dec 1 4: 40 00	EXP: C Kzt: NA		HORZ(TL): 0.010 J	F
NCBCLL: 10.00	Mean Height: 15.00 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0	E
Soffit: 2.00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.209	١
l	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.150	
Spacing: 24.0 "	C&C Dist a: 3.40 ft	Rep Fac: Yes	Max Web CSI: 0.122	
_	Loc. from endwall: not in 4.50 ft	FT/RT:20(0)/10(0)		
	GCpi: 0.18	Plate Type(s):		1
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11	
Lumber		Additional Notes		-

#### ▲ Maximum Reactions (lbs), or \*=PLF Gravity Non-Gravity Loc R+ /R /Rw /U /RL AJ\* 93 /50 Wind reactions based on MWFRS AJ Brg Width = 408 Min Req = -Bearing B is a rigid surface. Members not listed have forces less than 375#

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3; Stack Chord: SC1 2x4 SP #2; Stack Chord: SC2 2x4 SP #2;

#### **Bracing**

(a) Continuous lateral restraint equally spaced on member.

### **Plating Notes**

All plates are 2X4 except as noted.

#### Loading

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

#### Wind


Wind loads based on MWFRS with additional C&C member design.

Right end vertical not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

See DWGS A14015ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Stacked top chord must NOT be notched or cut in area (NNL). Dropped top chord braced at 24" oc intervals. Attach stacked top chord (SC) to dropped top chord in notchable area using 3x4 tie-plates 24" oc. Center plate on stacked/dropped chord interface, plate length perpendicular to chord length. Splice top chord in notchable area using 3x6.



05/04/2021


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372019 / COMN Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T1 / FROM: CDM DrwNo: 124.21.1601.55720 Qty: 5 CJ Customs-Curtis Jones-Spec House Truss Label: A02 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria	14	
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#	١.	
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.209 N 999 240	L	
DCLL. 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.429 N 946 180	ΙE	
10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.054 J	J	
Dec 1 d · 40 00	EXP: C Kzt: NA		HORZ(TL): 0.111 J	١V	
NCBCLL: 10.00	Mean Height: 15.00 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0	E	
Soffit: 2.00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.614	ļ	
l	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.882	E	
Spacing: 24.0 "	C&C Dist a: 3.40 ft	Rep Fac: Yes	Max Web CSI: 0.963	N	
' '	Loc. from endwall: Any	FT/RT:20(0)/10(0)		٦"	
	GCpi: 0.18	Plate Type(s):		] <del>`</del>	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11	E	
Lumber					

#### ▲ Maximum Reactions (lbs) Gravity Non-Gravity Loc R+ /Rh /Rw /U /RL В 1508 /-/929 /265 /350 1534 /-/-/905 /243 /-Wind reactions based on MWFRS Brg Width = 4.0В Min Req = 1.8Brg Width = 4.0 Min Req = 1.8Bearings B & J are a rigid surface. Members not listed have forces less than 375# Maximum Top Chord Forces Per Ply (lbs) Chords Tens.Comp. Chords Tens. Comp. 1161 - 3537 630 - 1452 C - D 978 - 2843 F-G 609 - 1524 D-E 796 - 2153 G-H 554 - 1870

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

#### **Bracing**

(a) Continuous lateral restraint equally spaced on

### Wind


Wind loads based on MWFRS with additional C&C


Right end vertical not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

### Additional Notes

The overall height of this truss excluding overhang is 10-8-7.





FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372020 / COMN Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T3 / FROM: CDM CJ Customs-Curtis Jones-Spec House DrwNo: 124.21.1601.55909 Qty: 1 Truss Label: A03 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.037 L 999 240
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.077 L 999 180
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.014 E
Des Ld: 40.00	EXP: C Kzt: NA		HORZ(TL): 0.029 E
NCBCLL: 10.00	Mean Height: 15.00 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
Soffit: 2.00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.724
Load Duration: 1.25	MWFRS Parallel Dist: h/2 to h	TPI Std: 2014	Max BC CSI: 0.645
Spacing: 24.0 "	C&C Dist a: 3.40 ft	Rep Fac: Yes	Max Web CSI: 0.451
-	Loc. from endwall: not in 9.00 ft	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11
Louis			

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

#### **Bracing**

(a) Continuous lateral restraint equally spaced on

### Wind


Wind loads based on MWFRS with additional C&C

Right end vertical not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

### Additional Notes

The overall height of this truss excluding overhang is



В 374 /186 /350 1557 /-/-/974 /271 /-1168 /-/740 /178 Wind reactions based on MWFRS Brg Width = 4.0 Min Req = 1.5 Brg Width = 4.0Min Req = 1.6 Brg Width = 4.0 Min Rea = 1.5Bearings B, O, & J are a rigid surface. Members not listed have forces less than 375# Maximum Top Chord Forces Per Ply (lbs) Chords Tens.Comp. Chords Tens. Comp.

/Rh

Non-Gravity

/RL

/Rw / U

Gravity

D - E F-G 285 - 1071 298 - 950 E-F 315 -879 G - H 245 - 1333

### Maximum Bot Chord Forces Per Ply (lbs)

Cilolus	16113.0	onip.	Cilolus	i ciis. C	onip.
O - N	822	-83	M - L	784	-66
N - M	821	-84	L-K	973	- 53

### Maximum Web Forces Per Ply (lbs)

Webs	Tens.Comp.	Webs	Tens. Comp.
C-O	265 - 431	L-G	205 - 425
O - D	296 - 1523	K - H	895 - 19
F-L	634 - 218	H - J	272 - 1114



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372021 / FROM: CDM


GABL

Ply: 1 Qty: 1

Job Number: 21-5152 Truss Label: A04

CJ Customs-Curtis Jones-Spec House

Cust: R 215 JRef: 1X542150016 T9 / DrwNo: 124.21.1601.55971 05/04/2021 / YK



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.042 I 999 240
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.086 I 999 180
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): -0.024 J
Des Ld: 40.00	EXP: C Kzt: NA Mean Height: 15.00 ft		HORZ(TL): 0.049 J
NCBCLL: 10.00	TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
Soffit: 2.00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.671
Load Duration: 1.25	MWFRS Parallel Dist: h/2 to h	TPI Std: 2014	Max BC CSI: 0.588
Spacing: 24.0 "	C&C Dist a: 4.60 ft	Rep Fac: Yes	Max Web CSI: 0.746
	Loc. from endwall: not in 6.50 ft	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11
I complete		A dalista and Massa	

#### Lumber **Additional Notes**

See DWGS A14015ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Stacked top chord must NOT be notched or cut in area (NNL). Dropped top chord braced at 24" oc intervals. Attach stacked top chord (SC) to dropped top chord in notchable area using 3x4 tie-plates 24" oc. Center plate on stacked/dropped chord interface, plate length perpendicular to chord length. Splice top chord in notchable area using 3x6.

WARNING: Furnish a copy of this DWG to installation contractor. Special care trushbe during handling, shipping and installation on See "WARNING" note below. The overall height of this truss 10-8-7.

AR 1193 /808 /211 /-/-AS\*130 /71 /0 Wind reactions based on MWFRS Brg Width = 4.0 Min Req = 1.5AR Brg Width = 4.0 Min Req = 1.5 AS Brg Width = 228 Min Rea = -Bearings B, AR, & AN are a rigid surface. Members not listed have forces less than 375# Maximum Top Chord Forces Per Ply (lbs) Chords Tens.Comp. Chords Tens. Comp.

Non-Gravity

/RL

/342

/Rw /U

/249

▲ Maximum Reactions (lbs), or \*=PLF

/Rh

Gravity

Loc R+

В 406

D-E 352 - 695 G - N 265 - 597 E-F 379 - 466 U - Z 376 -54

Maximum Bot Chord Forces Per Ply (lbs) Chords Tens.Comp. Chords Tens. Comp.

AR-AQ 483 598 - 186 AP-AO - 156 AQ-AP 596 - 187

Maximum Web Forces Per Ply (lbs) Webs Tens.Comp. Webs Tens. Comp. C-AR - 428 AO- N 406 - 81 AR- D 355 - 988 N-AN 432 - 983

#### Loading

member

**Plating Notes** 

requirements.

Top chord: 2x4 SP #2;

Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

Stack Chord: SC1 2x4 SP #2;

All plates are 2X4 except as noted.

Gable end supports 8" max rake overhang. Top chord must not be cut or notched.

(a) Continuous lateral restraint equally spaced on

(\*\*) 2 plate(s) require special positioning. Refer to

scaled plate plot details for special positioning

Wind loads based on MWFRS with additional C&C member design.

Right end vertical not exposed to wind pressure. Wind loading based on both gable and hip roof types.


#### FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.





Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.079 H 999 240
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.159 H 999 180
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.080 N
Des Ld: 40.00	EXP: C Kzt: NA		HORZ(TL): 0.161 N
NCBCLL: 10.00	Mean Height: 15.00 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
Soffit: 2.00	BCDL: 2.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.798
Load Duration: 1.25	MWFRS Parallel Dist: h/2 to h	TPI Std: 2014	Max BC CSI: 0.824
Spacing: 24.0 "	C&C Dist a: 4.60 ft	Rep Fac: Yes	Max Web CSI: 0.715
' "	Loc. from endwall: not in 6.50 ft	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11

#### Lumber

Top chord: 2x4 SP #2; T5 2x4 SP M-31; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

#### **Bracing**

(a) Continuous lateral restraint equally spaced on

### **Plating Notes**

All plates are 2X4 except as noted.

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

### Wind

Wind loads based on MWFRS with additional C&C member design.


Wind loading based on both gable and hip roof types.

## **Additional Notes**

Negative reaction(s) of -671# MAX. from a non-wind load case requires uplift connection. See Maximum Reactions.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.

10-6-4.



#### Gravity Non-Gravity Loc R+ /Rh /Rw /U В 333 /157 1759 /-/1083 /178

/RL

/360

/-

/1608 /-

/553

/-671 /-/179 Wind reactions based on MWFRS

Ν 2791

Brg Width = 4.0 Min Req = 1.5 Brg Width = 4.0Min Req = 1.7 Min Req = 3.3 Brg Width = 4.0 Ν Brg Width = 4.0 Min Req = 1.5

Bearings B, V, N, & L are a rigid surface. Members not listed have forces less than 375#

Maximum Top Chord Forces Per Ply (lbs) Chords Tens.Comp. Chords Tens. Comp. B - C 445 - 104 - 1014 G-H 88

C - D 598 - 107 H - I 88 - 1010 D - E 324 - 1148 I - J O - 1149 E-F 226 - 979 K-L 1483 0 F-G 193 - 792

Maximum Bot Chord Forces Per Ply (lbs)

Chords	Tens.Comp.		ords Tens.Comp. Chords		Tens. Comp.		
B - V	77	- 391	Q-P	1460	0		
V - U	858	- 79	O - N	0	- 1476		
U - T	833	- 66	N - L	0	- 1112		
R-Q	997	-4					

Maximum Web Forces Per Ply (lbs)

Tens.Comp.	Webs	Tens. Comp.
285 - 439	G-Q	376 0
182 - 1861	P - J	1480 0
540 0	O - J	0 - 1193
1068 - 14	0 - K	1240 0
0 -442	N - K	0 - 1710
	285 - 439 182 - 1861 540 0 1068 - 14	285 -439 G - Q 182 -1861 P - J 540 0 O - J 1068 -14 O - K

FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372023 / COMN Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T6 / FROM: CDM DrwNo: 124.21.1601.55970 Qty: 1 CJ Customs-Curtis Jones-Spec House Truss Label: A06 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Deti/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.050 L 999 240
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.090 L 999 180
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.019 D
Des Ld: 40.00	EXP: C Kzt: NA Mean Height: 15.00 ft		HORZ(TL): 0.034 D
NCBCLL: 10.00	TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
Soffit: 2.00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.757
Load Duration: 1.25	MWFRS Parallel Dist: h to 2h	TPI Std: 2014	Max BC CSI: 0.757
Spacing: 24.0 "	C&C Dist a: 3.45 ft	Rep Fac: Yes	Max Web CSI: 0.624
	Loc. from endwall: not in 9.00 ft	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11
Lumber			

# Wind reactions based on MWFRS Bearings B & N are a rigid surface. Members not listed have forces less than 375#

**Maximum Top Chord Forces Per Ply (lbs)** Chords Tens.Comp. Chords Tens. Comp. C-D F-G - 688 444 - 271 295

/Rh

/-

Non-Gravity

/178

/268

/-

/Rw / U

/202

/598

/1017 /131

Min Req = 1.5

Min Req = 1.8

Min Rea =

Gravity

Brg Width = 4.0

Brg Width = 4.0

Brg Width = -

Loc R+

1771 /-

1314 /-

В 357

#### D-E 290 - 1361 G - H 295 - 687 E-F 346 - 1124

Top chord: 2x4 SP #2;

Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

(a) Continuous lateral restraint equally spaced on

### Loading

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

#### **Purlins**

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

### Wind

Wind loads based on MWFRS with additional C&C member design.

Right end vertical not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

#### **Additional Notes**

Refer to DWG PB160160118 for piggyback details. The overall height of this truss excluding overhang is 10-6-4.

## Maximum Bot Chord Forces Per Ply (lbs)

Chords	Tens.C	comp.	Chords	Tens. (	Comp.
N - M	1025	- 362	L-K	844	- 312
M - L	963	- 371			

#### Maximum Web Forces Per Ply (lbs)

webs	rens.comp.	vvebs	rens. Comp.
C - N	276 - 437	G-K	415 - 461
N - D	496 - 1891	K - H	1151 - 458
F-L	543 - 34	H-J	529 - 1154



FL REG# 278, Yoonhwak Kim, FL PE #86367


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372024 / SPEC Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T8 / FROM: CDM Qty: 1 CJ Customs-Curtis Jones-Spec House DrwNo: 124.21.1601.55736 Truss Label: A07 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria	4
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#	١.
	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.065 D 999 240	۱L
DCLL. 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.116 D 999 180	В
	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.018 D	J
Doe   d⋅ /0 00	EXP: C Kzt: NA		HORZ(TL): 0.033 D	۷
NCBCLL: 10.00	Mean Height: 15.00 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0	B
Soffit: 2.00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.791	١Ž
l	MWFRS Parallel Dist: h to 2h	TPI Std: 2014	Max BC CSI: 0.804	B
Spacing: 24.0 "	C&C Dist a: 3.45 ft	Rep Fac: Yes	Max Web CSI: 0.668	I N
	Loc. from endwall: not in 9.00 ft	FT/RT:20(0)/10(0)		ا". د
	GCpi: 0.18	Plate Type(s):		]∸
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11	B
		L.		٠(

▲ Ma	▲ Maximum Reactions (lbs), or *=PLF						
Gravity				N	on-Grav	vity	
Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL	
B* 2	241	/-	/-	/142	/12	/32	
J 1	1372	/-	/-	/631	/183	/-	
Wind	l reac	tions bas	sed on	MWFRS			
В	Brg W	/idth = 1	00	Min Re	q = -		
J	Brg W	/idth = -		Min Reg = -			
		is a rigio			•		
Mem	bers	not listed	have	forces les	s than 3	375#	
Maxi	mum	Top Ch	ord F	orces Per	Ply (lb	s)	
Chor	ds T	ens.Con	np.	Chords	Tens.	Comp.	
B - C	:	500 -:	328	E-F	356	- 1226	
1 C - D		212 - 14			295	-	
D-F		383 - 1	-	G-H	205	_	

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

#### Bracing

(a) Continuous lateral restraint equally spaced on

### **Plating Notes**

All plates are 2X4 except as noted.


Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

Wind loads based on MWFRS with additional C&C member design.


Right end vertical not exposed to wind pressure. Wind loading based on both gable and hip roof types.

#### **Additional Notes**

The overall height of this truss excluding overhang is 10-6-4.



Tens. Comp. Webs Tens.Comp. Webs N-C 556 - 1668 F-L 666 -58 C - M G - K 1754 - 420 404 - 461 M - D 306 -831 K - H 1220 - 458 M - E 435 - 92 H-J 525 - 1213 148 - 379



\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!


\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.

PRUMA PRUMA



SEQN: 372153 COMN Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T11 DrwNo: 124.21.1605.21647 FROM: CDM Qty: 10 CJ Customs-Curtis Jones-Spec House Truss Label: A08 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	DefI/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.047 J 999 240
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.088 J 999 180
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.016 C
Des Ld: 40.00	EXP: C Kzt: NA		HORZ(TL): 0.030 C
NCBCLL: 10.00	Mean Height: 15.00 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
Soffit: 2.00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.587
Load Duration: 1.25	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.776
Spacing: 24.0 "	C&C Dist a: 3.00 ft	Rep Fac: Yes	Max Web CSI: 0.640
' -	Loc. from endwall: Any	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11
Lumber		Loading	

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

#### **Bracing**

(a) Continuous lateral restraint equally spaced on member.

### Hangers / Ties

Simpson Construction Hardware is specified based on the most current information provided by Simpson Strong-Tie. Please refer to the most recent Simpson Strong-Tie catalog for additional information.

Recommended hanger connections are based on manufacturer tested capacities and calculations. Conditions may exist that require different connections than indicated. Refer to manufacturer publication for additional information.

Hanger specified assumes connection to supporting chord is located a minimum of five times the depth of the supporting chord from any unsupported end, unless unsupported chord end has 85% plating

Bearing at location x=26'3" uses the following

support conditions: 26'3"

Bearing H (26'3", 9'1"2) HUS26

Supporting Member: (2)2x6 SP 2400f-2.0E (14) 0.148"x3" nails into supporting

member,
(4) 0.148"x3" nails into supported member

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

#### Wind

Wind loads based on MWFRS with additional C&C member design.

End verticals not exposed to wind pressure.

Wind loading based on both gapte and hip hop types.

### **Additional Notes**

The overall height

ichnes exchir

## ▲ Maximum Reactions (lbs)

	Gravity			Non-Gravity			
Loc	R+	/ R-	/ Rh	/ Rw	/U	/ RL	
L	1318	/-	/-	/817	/24	/376	
Н	1351	/-	/-	/672	/-	/-	
Wi	Wind reactions based on MWFRS						

Brg Width = 4.0Min Reg = 1.6

Brg Width = -Min Reg = -Bearing L is a rigid surface.

Members not listed have forces less than 375# Maximum Top Chord Forces Per Ply (lbs)

Chords Tens.Comp. Chords Tens. Comp. 50 - 1548

67 - 1208 -714

Chords

Tens. Comp.

257 - 497 863 - 117 K-J 1147 - 350

Maximum Bot Chord Forces Per Ply (lbs)

### Maximum Web Forces Per Ply (lbs)

Chords Tens.Comp.

Webs	Tens.Comp.	Webs	Tens. Comp.
B-L	174 - 1262	E-I	0 -488
B - K	1067 0	I-F	1197 0
C - J	307 - 375	F-H	0 - 1197
D-J	473 - 139		

FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372026 / FROM: CDM


GABL

Ply: 1 Qty: 1 Job Number: 21-5152

CJ Customs-Curtis Jones-Spec House

Truss Label: A09

Cust: R 215 JRef: 1X542150016 T5 / DrwNo: 124.21.1601.55392 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria	•
TCLL: 20.00 TCDL: 10.00 BCLL: 0.00 BCDL: 10.00 Des Ld: 40.00 NCBCLL: 10.00 Soffit: 2.00 Load Duration: 1.25 Spacing: 24.0 "	Wind Std: ASCE 7-16 Speed: 130 mph Enclosure: Closed Risk Category: II EXP: C Kzt: NA Mean Height: 15.00 ft TCDL: 5.0 psf BCDL: 2.0 psf MWFRS Parallel Dist: 0 to h/2 C&C Dist a: 3.00 ft Loc. from endwall: Any GCpi: 0.18	Pg: NA Ct: NA CAT: NA Pf: NA Ce: NA Lu: NA Cs: NA Snow Duration: NA  Building Code: FBC 7th Ed. 2020 Res. TPI Std: 2014 Rep Fac: Yes FT/RT:20(0)/10(0) Plate Type(s):	PP Deflection in loc L/defl L/# VERT(LL): 0.001 K 999 240 VERT(CL): 0.003 K 999 180 HORZ(LL): 0.001 R HORZ(TL): 0.002 R Creep Factor: 2.0 Max TC CSI: 0.206 Max BC CSI: 0.036 Max Web CSI: 0.130	L SVSB
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11	]
Lumbor		Additional Notes		

▲ Maximum Reactions (lbs), or \*=PLF Gravity Non-Gravity Loc R+ /Rw /U /RL S\* 89 /-/-/48 Wind reactions based on MWFRS Brg Width = 317 Min Req = -Bearing B is a rigid surface. Members not listed have forces less than 375#

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3; Stack Chord: SC1 2x4 SP #2;

(a) Continuous lateral restraint equally spaced on member

#### **Plating Notes**

All plates are 2X4 except as noted.

### **Purlins**

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Wind loads based on MWFRS with additional C&C member design.

End verticals not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

See DWGS A14030ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Stacked top chord must NOT be notched or cut in area (NNL). Dropped top chord braced at 24" oc intervals. Attach stacked top chord (SC) to dropped top chord in notchable area using 3x4 tie-plates 24" oc. Center plate on stacked/dropped chord interface, plate length perpendicular to chord length. Splice top chord in notchable area using 3x6

Refer to DWG PB160160116 for piggy pack details. The overall height of this trus excluding overnal to 5-9.

FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.

Alpine, a division of ITW Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, installation and bracing of trusses. A seal on this drawing or cover page listing this drawing, indicates acceptance of professional engineering responsibility solely for the design shown. The suitability and use of this drawing for any structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec.2.

For more information see these web sites: Alpine: alpineitw.com; TPI: tpinst.org; SBCA: sbcindustry.com; ICC: iccsafe.org; AWC: awc.org

6750 Forum Drive Suite 305 Orlando FL, 32821 SEQN: 372051 / FLAT Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T17 / FROM: CDM Qty: 1 DrwNo: 124.21.1601.55721 CJ Customs-Curtis Jones-Spec House Truss Label: B01 / YK 05/04/2021 5'6" 11 5'6" 5'6" =3X4 **∥2X4** =3X4- 1'9"8 -D E ≡3X10 **∥**2X4 **∥2X4** 5'6" 5'6" 5'6" 11'

Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	DefI/CSI Criteria	▲ Maximum Reactions (lbs)
TCLL: 20.00 TCDL: 10.00 BCLL: 0.00 BCDL: 10.00 Des Ld: 40.00 NCBCLL: 10.00 Soffit: 2.00 Load Duration: 1.25 Spacing: 24.0 "	Wind Std: ASCE 7-16 Speed: 130 mph Enclosure: Closed Risk Category: II EXP: C Kzt: NA Mean Height: 15.00 ft TCDL: 5.0 psf BCDL: 5.0 psf MWFRS Parallel Dist: 0 to h/2 C&C Dist a: 3.00 ft Loc. from endwall: Any GCpi: 0.18 Wind Duration: 1.60	Pg: NA Ct: NA CAT: NA Pf: NA Ce: NA Lu: NA Cs: NA Snow Duration: NA  Building Code: FBC 7th Ed. 2020 Res. TPI Std: 2014 Rep Fac: Varies by Ld Case FT/RT:20(0)/10(0) Plate Type(s): WAVE	PP Deflection in loc L/defl L/# VERT(LL): 0.028 B 999 240 VERT(CL): 0.052 B 999 180 HORZ(LL): 0.003 A HORZ(TL): 0.007 A Creep Factor: 2.0 Max TC CSI: 0.252 Max BC CSI: 0.264 Max Web CSI: 0.292  VIEW Ver: 20.01.01A.0724.11	Gravity Non-G
Lumber Top chord: 2v4 SP #2				Maximum Web Forces Per Ply (lbs)

<b>▲</b> M	axim	um Rea	ctions	(lbs)		
	(	Gravity		No	on-Grav	vity
Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL
F	364	/-	/-	/-	/133	/-
D	364	/-	/-	/-	/133	/-
Win	d rea	ctions b	ased o	n MWFRS		
F	Brg \	Width =	4.0	Min Re	q = 1.5	;
D	Brg \	Width =	4.0	Min Req = 1.5		
Bea	rings	F&Da	re a rig	jid surface.		
Men	nbers	not liste	ed have	e forces les	s than 3	375#
Maximum Top Chord Forces Per Ply (lbs)					s)	
Cho	rds	Tens.Co	omp.	Chords	Tens.	Comp.
A - I	В	269	- 758	B-C	269	- 758

Webs

Tens. Comp.

- 272

766

Webs

Tens.Comp.

766 - 272

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

#### **Special Loads**

---(Lumber Dur.Fac.=1.25 / Plate Dur.Fac.=1.25) TC: From 30 plf at 0.00 to 0.00 to 30 plf at 11.00 10 plf at 11.00 BC: From 10 plf at 15 lb Conc. Load at 0.06, 2.06, 4.06, 5.50 6.94, 8.94, 10.94 26 lb Conc. Load at 0.06, 2.06, 4.06, 5.50 6.94, 8.94,10.94


### **Purlins**

The TC of this truss shall be braced with attached spans at 24" oc in lieu of structural sheathing.

Wind loads and reactions based on MWFRS. End verticals not exposed to wind pressure.

### **Additional Notes**

Truss must be installed as shown with top chord up. The overall height of this truss excluding overhang is 1-9-8.



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372027 / FROM: CDM


GABL

Ply: 1 Qty: 1 Job Number: 21-5152

CJ Customs-Curtis Jones-Spec House

Truss Label: C01

Cust: R 215 JRef: 1X542150016 T7 / DrwNo: 124.21.1601.55908 05/04/2021 / YK



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	DefI/CSI Criteria	
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#	
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.127 Z 999 240	
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.273 Z 498 180	
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.114 R	
Des Ld: 40.00	EXP: C Kzt: NA Mean Height: 15.22 ft		HORZ(TL): 0.248 R	
NCBCLL: 10.00	TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0	
Soffit: 2.00	BCDL: 2.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.392	
Load Duration: 1.25	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.775	
Spacing: 24.0 "	C&C Dist a: 3.00 ft	Rep Fac: Yes	Max Web CSI: 0.531	
	Loc. from endwall: Any	FT/RT:20(0)/10(0)		
	GCpi: 0.18	Plate Type(s):		
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11	

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3; Stack Chord: SC1 2x4 SP #2; Stack Chord: SC2 2x4 SP #2;

#### **Bracing**

(a) Continuous lateral restraint equally spaced on member.

Fasten rated sheathing to one face of this frame.

### **Plating Notes**

All plates are 2X4 except as noted.

(\*\*) 4 plate(s) require special positioning. Refer to scaled plate plot details for special positioning requirements.

### Loading

Gable end supports 8" max rake overhang. Top chord must not be cut or notched.

In lieu of rigid ceiling use purlins to brace BC @ 24"

#### Wind

Wind loads based on MWFRS with additional C&C member design.

End verticals not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

## **Additional Notes**

Negative reaction(s) of -230# MAX. from a non-wind load case requires uplift connection. See Maximum Reactions.

See DWGS A14030ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Stacked top chord must NOT be notched or cut in area (NNL). Attach stacked top chord (SC) to dropped top chord in notchable area using 3x4 tie-plates 24" oc. Center plate on stacked/dropped chord interface, plate length perpehilikular to chord length. Splice top chord involchable area using 3x6
Refer to DWG PB160100118 for piggyback details.

The overall height of this truss excluding overhal 12-0-0.



▲ Maximum Reactions (lbs), or \*=PLF Gravity Non-Gravity

Loc R+ /Rh /Rw /U /RL AF 569 /335 /87 AF\* 30 /-37 /3 /-AG 651 /400 /-/-/-AH\*94 /55 /-AI 565 /-/334 AC /-219

Wind reactions based on MWFRS

AF Brg Width = 4.0 Min Rea = 1.5AF Brg Width = 74.0 Min Req = AG Brg Width = 4.0 Min Req = 1.5Min Req = AH Brg Width = 76.0 Al Brg Width = 6.0 Min Req = 1.5

Bearings AF, AF, AG, AH, & AI are a rigid surface.

110 -400

K - P

Members not listed have forces less than 375# Maximum Top Chord Forces Per Ply (lbs) Chords Tens.Comp. Chords Tens. Comp.

P - R

0 - 632

Maximum Bot Chord Forces Per Ply (lbs)

Chords Tens.Comp. Chords Tens. Comp. AF- Z 847 Z - T 422

Maximum Gable Forces Per Ply (lbs)

Gables Tens.Comp. Gables Tens. Comp. 150 - 491 0

FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.




Ply: 1 Qty: 7 Job Number: 21-5152

CJ Customs-Curtis Jones-Spec House

Truss Label: C02

Cust: R 215 JRef: 1X542150016 T24 / DrwNo: 124.21.1601.55425 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	DefI/CSI Criteria			
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#			
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.599 G 480 240			
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.979 G 294 180			
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.405 D			
Des Ld: 40.00	EXP: C Kzt: NA		HORZ(TL): 0.717 D			
NCBCLL: 10.00	Mean Height: 15.15 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0			
Soffit: 2.00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.691			
Load Duration: 1.25	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.986			
Spacing: 24.0 "	C&C Dist a: 3.00 ft	Rep Fac: Varies by Ld Case	Max Web CSI: 0.952			
' '	Loc. from endwall: Any	FT/RT:20(0)/10(0)				
	GCpi: 0.18	Plate Type(s):				
	Wind Duration: 1.60	WAVE, HS	VIEW Ver: 20.01.01A.0724.11			
Lumban		Additional Natas				

Top chord: 2x4 SP M-31; T4 2x4 SP #2; Bot chord: 2x4 SP M-31; Webs: 2x4 SP #3; W27 2x4 SP #2;

#### **Special Loads**

· •							
(Lumber Dur.Fac.=1.25 / Plate Dur.Fac.=1.25)							
TC: From	40 plf at	-1.50 to	40 plf at	25.50			
TC: From	28 plf at	-1.50 to	28 plf at	25.50			
PLT: From	20 plf at	4.50 to	20 plf at	19.50			
PLT: From	80 plf at	4.50 to	80 plf at	19.50			
BC: From	6 plf at	-1.50 to	6 plf at	0.00			
BC: From	20 plf at	0.00 to	20 plf at	24.00			
BC: From	6 plf at	24.00 to	6 plf at	25.50			
BC: 111 lb	Conc. Loa	nd at 4.50					
BC: 90 lb	Conc. Loa	d at 19.50					

### **Plating Notes**

All plates are 2X4 except as noted.

(\*\*) 1 plate(s) require special positioning. Refer to scaled plate plot details for special positioning requirements.

Collar-tie braced with continuous lateral bracing at 24" oc. or rigid ceiling.


Wind loads based on MWFRS with additional C&C member design.

End verticals not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is



FL REG# 278, Yoonhwak Kim, FL PE 05/04/2021

▲ Maximum Reactions (lbs)									
		G	ravity		N	Non-Gravity			
5	Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL		
)		028		/-		/135			
	AM 2			/		/133	/-		
	-				n MWFRS				
			/idth =						
	AM E	3rg W	/idth =	6.0	Min Req = 1.7				
	Beari	ngs \	/ & AM	are a i	rigid surfac	e.			
	Memb	oers	not liste	ed have	e forces les	s than 3	375#		
	Maxii	mum	Top C	hord F	orces Pe	Ply (lb	s)		
	Chord	ds T	ens.Co	mp.	Chords	Tens.	Comp.		
	B-C		567 -	1046	I - J	220	- 766		
_	l C - D		576	- 979	J - K	622	- 1002		

#### Maximum Bot Chord Forces Per Ply (lbs)

211 - 766

Choras	rens.comp.	Choras	rens.	Comp.
Y - X	2715 - 1982	T - S	6948	- 699
X - W	4786 - 2185	S - R	5756	- 835
W - V	6343 - 1352	R - Q	3793	- 1107
V - U	7249 - 677	Q - P	1408	- 508
U - T	7448 - 646	P - O	248	- 383

613 - 1069

### Maximum Web Forces Per Ply (lbs)

Webs	Tens.Comp.	Webs `	Ťens. Comp.	
B-Z	385 - 923	AF- I	483 - 908	
Y - Z	389 - 939	AG-AH	899 - 6896	
Y -AA	541 - 2771	T -AH	689 - 555	
Z -AA	968 - 604	AH-AI	963 - 6314	
AA- X	1097 - 127	S-AI	1364 - 542	
AA-AB	1331 - 2300	Al- R	155 - 618	
X -AC	361 - 2266	AI-AJ	1358 - 5042	
D -AB	571 - 600	R -AK	2040 - 282	
AB-AC	1435 - 2302	AJ- J	604 - 642	
AC- W	980 - 234	AJ-AK	1254 - 5042	
AC-AD	1517 - 4589	AK- Q	309 - 889	
W -AD	547 - 1517	AK-AL	1686 - 2999	
AD- V	612 - 197	Q -AL	2372 - 570	
AD-AE	996 - 5977	AL- P	153 - 1023	
V -AE	524 - 819	AL- N	1148 - 1254	
E-AF	483 - 907	P - N	1724 - 233	
AE-AG	919 - 6780	N - L	410 - 924	
#86367	396 - 287	N - O	277 - 2002	
"11-AG	596 - 632			

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372029 / FROM: CDM

Page 1 of 2


COMN

Ply: 1 Qty: 2 Job Number: 21-5152

CJ Customs-Curtis Jones-Spec House

Truss Label: C03

Cust: R 215 JRef: 1X542150016 T27 / DrwNo: 124.21.1601.55767 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	DefI/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.338 D 454 240
DCLL. 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.549 D 279 180
10.00 I	Risk Category: II	Snow Duration: NA	HORZ(LL): -0.377 D
Dec 1 4: 40 00	EXP: C Kzt: NA		HORZ(TL): 0.491 H
INCOCIL, 40 00	Mean Height: 15.68 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
0 - 46:4 0 00	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.912
	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.818
Spacing: 24.0 "	C&C Dist a: 3.00 ft	Rep Fac: Yes	Max Web CSI: 0.940
-	Loc. from endwall: Any	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11

▲ M	▲ Maximum Reactions (lbs)						
	G	ravity	-	No	on-Grav	/ity	
Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL	
W	1200	/-	/-	/689	/165	/1243	
R	3140	/-	/-	/519	/187	/-	
ΑK	980	/-	/-	/568	/97	/-	
Win	d reac	tions b	ased on I	MWFRS			
W	Brg W	/idth =	4.0	Min Re	q = 1.5	;	
R	Brg W	/idth =	4.0	Min Re	q = 3.3		
ΑK	Brg W	/idth =	6.0	Min Re	q = 1.5	;	
Bearings W, R, & AK are a rigid surface.							
Members not listed have forces less than 375#							
Maximum Top Chord Forces Per Ply (lbs)							
Cho	Chords Tens.Comp. Chords Tens.Comp.						

#### Lumber

Top chord: 2x4 SP #2; T5 2x4 SP M-31;

Bot chord: 2x4 SP #2; Webs: 2x4 SP #3; W13 2x4 SP #2;

### **Plating Notes**

All plates are 2X4 except as noted.

#### Loading

Attic room loading from 4-6-0 to 19-6-0: Live Load: 40 PSF. Dead Load: 10 PSF Ceiling: 10 PSF, Kneewalls: 10 PSF

#### **Purlins**

In lieu of rigid ceiling use purlins to brace BC @ 24"

Collar-tie braced with continuous lateral bracing at 24" oc. or rigid ceiling.

#### Wind

Wind loads based on MWFRS with additional C&C member design.

End verticals not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

### **Additional Notes**

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is 11-10-3



## Maximum Bot Chord Forces Per Ply (lbs)

A - B

B - C

C-D

619 - 990

628 - 923

215 -642

Chords	Tens.Comp.	Chords	Tens. Comp.
W - V	2319 - 1917	R - Q	545 - 1209
V - U	2823 - 2148	Q-P	1754 - 1014
U - T	2349 - 1324	P - O	1892 - 1389
T-S	875 - 757	O - N	803 - 607
S - R	571 - 2499		

J - K

219

674

665 - 1011

- 644

- 945

### Maximum Web Forces Per Ply (lbs)

		Webs	Tens.Comp.	Webs	Tens. Comp.
	No. 86367 💃	A - X	417 - 730	AD- H	395 - 449
<b>*</b>		🌭 🟯 W - X	426 - 737	AE- R	260 - 1662
~ ;	values (Mar collect	🤼 👺 W - Y	541 - 1790	AE-AF	3323 - 550
41		≽- <b>≛</b> X-Y	901 - 569	R -AF	445 - 2713
1	<ul> <li>STATE OF € €</li> </ul>	7 <b>- Y</b> - V	626 - 65	AF- Q	998 - 216
6	100	Y-Z	1320 - 1528	AF-AG	1355 - 1129
	Con Opinh	🦿 / V-AA	236 - 1192	Q -AG	538 - 1687
00		° C.Z	573 - 704	AG- P	431 - 149
	15 SIONING ENTER	Z-AA	1424 - 1635	AG-AH	1779 - 1919
	MAL	/ AA- U	391 - 415	P -AI	386 - 571
		AA-AB	1533 - 2563	AH- I	591 - 731
		U -AB	1008 - 794	AH-AI	1674 - 1812
		/ AB- T	298 - 511	Al- O	382 - 449
		/ AB-AC	734 - 2069	Al-AJ	1907 - 2149
		/ T-AC	1868 - 634	O -AJ	1109 - 750
FL	REG# 278, Yoonhwak Kim, F	L PE # <b>8646</b> 7	393 - 422	AJ- N	186 - 451
	05/04/2021	AC-S	294 - 1033	AJ- L	1198 - 1111
	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	AC-AE	737 - 451	N - L	786 - 296

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372029 / CO	NMC	Ply: 1	Job Number: 21-5152	Cust: R 2	215 J	Ref: 1X542150016	T27 /
FROM: CDM		Qty: 2	CJ Customs-Curtis Jones-Spec House	DrwNo:	124.2	1.1601.55767	
Page 2 of 2			Truss Label: C03	/	ΥK	05/04/2021	
			F-AD 390	- 295	1 -	K 437 -	- 732


S-AE

2913 - 604

L - M

99

- 968



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall flave properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372047 / FROM: CDM


COMN

Ply: 1 Qty: 1 Job Number: 21-5152

CJ Customs-Curtis Jones-Spec House

Truss Label: C04

Cust: R 215 JRef: 1X542150016 T20 / DrwNo: 124.21.1601.56002 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria			
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#			
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.143 Q 999 240			
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.311 D 926 180			
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.141 D			
NCBCLL: 10.00 Soffit: 2.00	EXP: C Kzt: NA Mean Height: 15.68 ft TCDL: 5.0 psf BCDL: 5.0 psf MWFRS Parallel Dist: h to 2h C&C Dist a: 3.00 ft Loc. from endwall: not in 9.00 ft	Building Code: FBC 7th Ed. 2020 Res. TPI Std: 2014 Rep Fac: Varies by Ld Case FT/RT:20(0)/10(0) Plate Type(s):	HORZ(TL): 0.324 D Creep Factor: 2.0  Max TC CSI: 0.570  Max BC CSI: 0.454  Max Web CSI: 0.528			
	GCpi: 0.18 Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11			

#### Lumber

Top chord: 2x4 SP #2; T1,T7 2x6 SP 2400f-2.0E; T3.T6 2x4 SP M-31: Bot chord: 2x4 SP #2; B2 2x4 SP M-31; Webs: 2x4 SP #3; W13 2x4 SP M-31; W14 2x6 SP 2400f-2.0E;

### **Special Loads**

(Lumber Dur.Fac.=1.25 / Plate Dur.Fac.=1.25)							
TC: From	40 plf at	0.00 to	40 plf at	24.00			
TC: From		0.00 to	28 plf at	24.00			
PLT: From	10 plf at	4.50 to	10 plf at	19.50			
PLT: From	40 plf at	4.50 to	40 plf at	19.50			
BC: From	20 plf at	0.00 to	20 plf at	24.00			
BC: 56 lb			-				
BC: 45 lb	Conc Loa	d at 19 50					

### **Plating Notes**

All plates are 3X4 except as noted.

(\*\*) 1 plate(s) require special positioning. Refer to scaled plate plot details for special positioning requirements.

Collar-tie braced with continuous lateral bracing at 24" oc. or rigid ceiling.

Wind loads based on MWFRS with additional C&C member design.

End verticals not exposed to wind pressure.


Wind loading based on both gable and hip roof types.

## **Additional Notes**

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is

05/04/2021



#### Gravity Non-Gravity Loc R+ /Rh /Rw /U /RL ٧ 1488 /-/619 /322 AL 1482 /619 /-Wind reactions based on MWFRS Brg Width = 4.0Min Rea = 1.8AL Brg Width = 6.0 Min Req = 1.5 Bearings V & AL are a rigid surface. Members not listed have forces less than 375# Maximum Top Chord Forces Per Ply (lbs) Chords Tens.Comp. Chords Tens. Comp. 90 - 1548 B - C 152 - 1487 H - I 167 - 1086 C-D 212 - 1279 I-J 0 - 1085 D-E 0 -430 J - K 0 - 1251 - 514 E-F 0

▲ Maximum Reactions (lbs)

### Maximum Bot Chord Forces Per Ply (lbs)

Cnoras	i ens.c	omp.	Cnoras	rens.	Jomp.
V - U	494	- 182	Q-P	2286	- 182
U - T	1021	- 238	P - O	2154	- 359
T-S	1491	- 437	O - N	1587	- 515
S - R	1612	- 595	N - M	565	- 185
R - Q	2109	- 213			

### Maximum Web Forces Per Ply (lbs)

Webs	Tens.Comp.	Webs	Tens. Comp.
A - V	81 - 1262	R -AF	250 - 805
A - W	1020 - 23	AE- G	709 - 69
V - X	47 - 530	AE- H	365 - 871
W - X	1011 -20	AF-AG	231 - 1540
X - Y	444 - 14	Q -AG	295 - 387
U - Z	63 - 539	AG-AH	313 - 1547
Y - Z	475 0	P -AH	388 - 313
C -AB	221 - 426	AH-AI	504 - 1379
T -AA	200 -412	O-AJ	763 - 151
AA-AB	306 - 598	AI-AJ	498 - 1377
D -AC	311 - 412	AJ-AK	593 - 843
AB-AC	763 - 111	N -AK	1026 - 312
AB-AD	462 - 930	AK- M	159 - 428
AC-AE	309 - 394	AK- K	400 - 219
AD- R	532 - 92	M - K	629 - 196
<del>&amp;B</del> - <b>A</b> F	554 - 1098	K-L	90 - 1470

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372031 / FROM: CDM


SPEC

Ply: 1 Qty: 1 Job Number: 21-5152

CJ Customs-Curtis Jones-Spec House

Truss Label: E01

Cust: R 215 JRef: 1X542150016 T26 / DrwNo: 124.21.1601.55424 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	DefI/CSI Criteria	T.
TCLL: 20.00 TCDL: 10.00 BCLL: 0.00 BCDL: 10.00 Des Ld: 40.00 NCBCLL: 10.00 Soffit: 2.00 Load Duration: 1.25 Spacing: 24.0 "	Wind Std: ASCE 7-16 Speed: 130 mph Enclosure: Closed Risk Category: II EXP: C Kzt: NA Mean Height: 15.76 ft TCDL: 5.0 psf BCDL: 5.0 psf MWFRS Parallel Dist: h to 2h C&C Dist a: 3.00 ft Loc. from endwall: not in 9.00 ft GCpi: 0.18 Wind Duration: 1.60	Pg: NA Ct: NA CAT: NA Pf: NA Ce: NA Lu: NA Cs: NA Snow Duration: NA  Building Code: FBC 7th Ed. 2020 Res. TPI Std: 2014 Rep Fac: Yes FT/RT:20(0)/10(0) Plate Type(s): WAVE	PP Deflection in loc L/defl L/# VERT(LL): 0.219 C 711 240 VERT(CL): 0.484 C 322 180 HORZ(LL): 0.504 C HORZ(TL): 0.504 C Creep Factor: 2.0 Max TC CSI: 0.850 Max BC CSI: 0.401 Max Web CSI: 0.925  VIEW Ver: 20.01.01A.0724.11	
Lumber				

<b>▲</b> M	axim	um Rea	ctions (II	bs)		
	(	Gravity	•	No	on-Grav	vity
Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL
L	574	/-	/-	/331	/-	/265
G	574	/-	/-	/475	/183	/-
Win	d rea	ctions b	ased on N	<b>MWFRS</b>		
L	Brg \	Width =	4.0	Min Re	q = 1.5	;
G	Brg \	Width =	4.0	Min Re	q = 1.5	;
Bea	rings	L&Ga	re a rigid	surface.	-	
Mer	nbers	not list	ed have fo	orces less	than 3	375#
Max	timur	n Top C	Chord For	rces Per	Ply (lb	s)
Cho	rds	Tens.Co	omp.		•	•
A - I	В	232	- 522			

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2:

Webs: 2x4 SP #3; W15 2x4 SP #2;

#### **Bracing**

(a) Continuous lateral restraint equally spaced on

### **Plating Notes**

All plates are 3X4 except as noted.

### **Purlins**

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

#### Wind


Wind loads based on MWFRS with additional C&C member design.

End verticals not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

### **Additional Notes**

Refer to DWG PB160160118 for piggyback details. The overall height of this truss excluding overhang is



### Maximum Bot Chord Forces Per Ply (lbs)

Jilolus	rens.comp.	Cilolus	i ciis. v	Jonnp.	
K ( - J	1150 - 1261 1650 - 1617	J - I I - H	1162 672	- 916 - 374	

### Maximum Web Forces Per Ply (lbs)

webs	Tens.Comp.	webs	Tens. (	Jomp.
L - N M - N	697 - 1081 545 - 215	J-Q Q-R	487 790	- 675 - 1070
N - O	1222 - 1167	I-R	529	- 525
K - P	358 - 548	R-F	253	- 610
B - O	574 - 479	D - S	577	- 469
O - P	1235 - 1177	H - F	814	- 600
P - Q	1467 - 1558	F-G	539	- 545

FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372032 / SPEC Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T21 / FROM: CDM DrwNo: 124.21.1601.55690 Qty: 1 CJ Customs-Curtis Jones-Spec House Truss Label: E02 / YK 05/04/2021



Loading Criteria (psf)   TCLL: 20.00   TCDL: 10.00   BCLL: 0.00   BCDL: 10.00   Des Ld: 40.00   NCBCLL: 10.00   Soffit: 2.00   Load Duration: 1.25   Spacing: 24.0   "	Wind Criteria Wind Std: ASCE 7-16 Speed: 130 mph Enclosure: Closed Risk Category: II EXP: C Kzt: NA Mean Height: 15.97 ft TCDL: 5.0 psf BCDL: 2.0 psf MWFRS Parallel Dist: h to 2h C&C Dist a: 3.00 ft Loc. from endwall: not in 9.00 ft GCpi: 0.18 Wind Duration: 1.60	Snow Criteria (Pg,Pf in PSF) Pg: NA Ct: NA CAT: NA Pf: NA Ce: NA Lu: NA Cs: NA Snow Duration: NA  Building Code: FBC 7th Ed. 2020 Res. TPI Std: 2014 Rep Fac: Yes FT/RT:20(0)/10(0) Plate Type(s): WAVE	Defi/CSI Criteria PP Deflection in loc L/defl L/# VERT(LL): 0.001 B 999 240 VERT(CL): 0.003 B 999 180 HORZ(LL): -0.004 C HORZ(TL): 0.005 C Creep Factor: 2.0 Max TC CSI: 0.412 Max BC CSI: 0.229 Max Web CSI: 0.223  VIEW Ver: 20.01.01A.0724.11	■ Maximu G Loc R+ E* 95 Wind read E Brg V Bearing H Members Maximum Chords 1 F - E
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11	
Lumbor				

num Reactions (lbs), or \*=PLF Gravity Non-Gravity /R /Rw /U /RL /-/actions based on MWFRS Width = 156Min Req = -H is a rigid surface. rs not listed have forces less than 375# m Bot Chord Forces Per Ply (lbs) Tens.Comp. 452 - 181

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

(a) Continuous lateral restraint equally spaced on

### Loading

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

#### **Purlins**

In lieu of rigid ceiling use purlins to brace BC @ 24"

### Wind

Wind loads based on MWFRS with additional C&C member design.

End verticals not exposed to wind pressure.

Wind loading based on both gable and hip roof types.

#### **Additional Notes**

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!


\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372155 FLAT Ply: 2 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T28 Qty: 1 FROM: CDM DrwNo: 124.21.1605.38967 CJ Customs-Curtis Jones-Spec House Page 1 of 2 Truss Label: G01 / YK 05/04/2021

#### 2 Complete Trusses Required



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.026 K 999 240
DCLL. 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.051 K 999 180
10.00 I	Risk Category: II	Snow Duration: NA	HORZ(LL): -0.015 A
Dec 1 4: 40 00	EXP: C Kzt: NA Mean Height: 19.01 ft		HORZ(TL): 0.029 A
NODOLL, O OO	TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
0 - 40:4	BCDL: 5.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.110
	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.478
Spacing: 24.0 "	C&C Dist a: 3.00 ft	Rep Fac: No	Max Web CSI: 0.540
	Loc. from endwall: not in 25.00 ft	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11

#### Lumber

Top chord: 2x6 SP 2400f-2.0E; Bot chord: 2x6 SP 2400f-2.0E;

Webs: 2x4 SP #3; W1,W9 2x6 SP 2400f-2.0E;

(a) Continuous lateral restraint equally spaced on

### Nailnote

Nail Schedule:0.128"x3", min. nails Top Chord: 1 Row @12.00" o.c. Bot Chord: 2 Rows @ 4.50" o.c. (Each Row)
Webs : 1 Row @ 4" o.c. Use equal spacing between rows and stagger nails in each row to avoid splitting.


### **Special Loads**

(Lumber	Dur.Fac.=1	.25 / Plate [	Dur.Fac.=1.2	25)
TC: From	60 plf at	0.00 to	60 plf at	<b>25.50</b>
BC: From	20 plf at	0.00 to	20 plf at	0.46
BC: From	60 plf at	0.46 to	60 plf at	3.63
BC: From	20 plf at	3.63 to	20 plf at	6.22
BC: From	60 plf at	6.22 to	60 plf at	9.49
BC: From	20 plf at	9.49 to	20 plf at	14.51
BC: From	60 plf at	14.51 to	60 plf at	17.78
BC: From	20 plf at	17.78 to	20 plf at	20.37
BC: From	60 plf at	20.37 to	60 plf at	23.54
BC: From	20 plf at	23.54 to	20 plf at	24.00
BC: From	4 plf at	24.00 to	4 plf at	25.50
BC: 1314 lb	Conc. Load	at 0.27		
BC: 1372 lb	Conc. Load	at 2.27		
BC: 1351 lb	Conc. Load	lat 3.94, 5.	.94, 7.94, 9.	94
11.94,13.94,	15.94,17.94,	19.94,21.94	1	

## **Purlins**

The TC of this truss shall be braced with attached spans at 24" oc in lieu of structural sheathing.

Wind loads and reactions based on MWFRS. End verticals not exposed to wind pressure. Left cantilever is exposed to wind



FL REG# 278, Yoonhwak Kim, FL PE #86367

#### ▲ Maximum Reactions (lbs), or \*=PLF Gravity Non-Gravity Loc R+ /Rh /Rw / U /RL 1159 /137 /29 /-G 235 /-402 Wind reactions based on MWFRS Brg Width = 194 Min Req = -Brg Width = 4.0 Min Req = 1.5 Bearings L & G are a rigid surface. Members not listed have forces less than 375# Maximum Top Chord Forces Per Ply (lbs) Chords Tens.Comp. Chords Tens. Comp.

C-D

445

### Maximum Bot Chord Forces Per Ply (lbs) Chords Tens.Comp.

83 - 605

619 -86

445 - 79

A - B

B - C

### Maximum Web Forces Per Ply (lbs)

Webs	rens.comp.	webs	rens. (	Jonnp.
A - K	919 - 100	I - D	89	- 428
A - J	163 - 1166	H - E	63	- 409
J-B	114 - 481			

05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372155 FLAT Ply: 2 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T28 DrwNo: 124.21.1605.38967 FROM: CDM Qty: 1 CJ Customs-Curtis Jones-Spec House Page 2 of 2 Truss Label: G01 / YK 05/04/2021

### **Additional Notes**

WARNING: 20 psf additional bottom chord live load check has been modified

Truss must be installed as shown with top chord up. The overall height of this truss excluding overhang is 9-11-0.

#### WIND LOAD CASE MODIFIED!

It is the responsibility of the Building Designer and Truss Fabricator to review this drawing prior to cutting lumber to verify that all data, including dimensions and loads, conform to the architectural plans/specifications and fabricators truss layout.




FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!


\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.





SEQN: 372049 / **EJAC** Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T19 / FROM: CDM DrwNo: 124.21.1601.55830 Qty: 7 CJ Customs-Curtis Jones-Spec House Truss Label: J01 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00 TCDL: 10.00 BCLL: 0.00 BCDL: 10.00 Des Ld: 40.00 NCBCLL: 10.00 Soffit: 2.00 Load Duration: 1.25 Spacing: 24.0 "	Wind Std: ASCE 7-16 Speed: 130 mph Enclosure: Closed Risk Category: II EXP: C Kzt: NA Mean Height: 15.00 ft TCDL: 5.0 psf BCDL: 5.0 psf MWFRS Parallel Dist: 0 to h/2 C&C Dist a: 3.00 ft Loc. from endwall: Any GCpi: 0.18 Wind Duration: 1.60	Pg: NA Ct: NA CAT: NA Pf: NA Ce: NA Lu: NA Cs: NA Snow Duration: NA  Building Code: FBC 7th Ed. 2020 Res. TPI Std: 2014 Rep Fac: Yes FT/RT:20(0)/10(0) Plate Type(s): WAVE	PP Deflection in loc L/defl L/# VERT(LL): NA VERT(CL): NA HORZ(LL): -0.001 D HORZ(TL): 0.001 D Creep Factor: 2.0 Max TC CSI: 0.316 Max BC CSI: 0.059 Max Web CSI: 0.000  VIEW Ver: 20.01.01A.0724.11
Lumber		•	

▲ Maximum Reactions (Ibs)						
	G	ravity		No	on-Gra	vity
Loc	R+	/ R-	/ Rh	/ Rw	/U	/ RL
В	246	/-	/-	/198	/33	/80
D	26	/-	/-	/22	/5	/-
С	15	/-	/-	/31	/21	/-
Win	d read	ctions b	ased on I	MWFRS		
В	Brg V	Vidth =	3.5	Min Re	q = 1.5	5
D	Brg V	Vidth =	1.5	Min Re	q = -	
С	Brg V	Vidth =	1.5	Min Re	q = -	
Bearing B is a rigid surface.						
Mer	nbers	not list	ed have f	orces les	s than	375#

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2;

Wind loads based on MWFRS with additional C&C

Wind loading based on both gable and hip roof types.

#### **Additional Notes**

The overall height of this truss excluding overhang is 1-9-8.



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS


Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.

Alpine, a division of ITW Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, installation and bracing of trusses. A seal on this drawing or cover page listing this drawing, indicates acceptance of professional engineering responsibility solely for the design shown. The suitability and use of this drawing for any structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec.2.

For more information see these web sites: Alpine: alpineitw.com; TPI: tpinst.org; SBCA: sbcindustry.com; ICC: iccsafe.org; AWC: awc.org

6750 Forum Drive Suite 305 Orlando FL, 32821

SEQN: 372159 GABL Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T15 FROM: CDM Qty: 1 CJ Customs-Curtis Jones-Spec House DrwNo: 124.21.1605.44113 Truss Label: PB01 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	DefI/CSI Criteria
TCLL: 20.00 TCDL: 10.00 BCLL: 0.00 BCDL: 10.00 Des Ld: 40.00 NCBCLL: 10.00 Soffit: 2.00	Wind Std: ASCE 7-16 Speed: 130 mph Enclosure: Closed Risk Category: II EXP: C Kzt: NA Mean Height: 21.92 ft TCDL: 5.0 psf BCDL: 2.0 psf MWFRS Parallel Dist: 0 to h/2 C&C Dist a: 3.00 ft Loc. from endwall: not in 6.50 ft	Pg: NA Ct: NA CAT: NA Pf: NA Ce: NA Lu: NA Cs: NA Snow Duration: NA  Building Code: FBC 7th Ed. 2020 Res. TPI Std: 2014 Rep Fac: Varies by Ld Case FT/RT:20(0)/10(0)	Defl/CSI Criteria PP Deflection in loc L/defl L/# VERT(LL): 0.002 F 999 240 VERT(CL): 0.003 F 999 180 HORZ(LL): -0.002 F HORZ(TL): 0.004 F Creep Factor: 2.0 Max TC CSI: 0.401 Max BC CSI: 0.140 Max Web CSI: 0.038
	GCpi: 0.18 Wind Duration: 1.60	Plate Type(s): WAVE	VIEW Ver: 20.01.01A.0724.11
Lumban			

	▲ Maximum Reactions (lbs), or *=PLF						
ŧ		G	ravity		No	on-Gra	vity
40	Loc	: R+	/ R-	/ Rh	/ Rw	/ U	/ RL
30	Α	-	/-224	/-	/115	/22	/-
-	В*	122	/-	/-	/26	/57	/-
-	Е	-	/-224	/-	/115	/22	/-
	В		/-274				
	D		/-274				
	Wii	nd read	tions ba	sed on M	IWFRS		
	Α	Brg V	/idth = 5	5.5	Min Re	q = 1.5	5
	В	Brg V	/idth = 1	29	Min Re	q = -	
	Ε	Brg V	/idth = 5	5.5	Min Re	q = 1.5	5
	Bea	arings /	A, B, & E	are a rig	gid surfa	ce.	
	Ме	mbers	not liste	d have fo	rces less	than:	375#

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

#### **Special Loads**

l	(Lumber	Dur.Fac.=1	.25 / Plate D	Dur.Fac.=1.2	25)
l	TC: From	65 plf at	-0.68 to	65 plf at	11.46
l	TC: From	65 plf at	20.79 to	65 plf at	26.82
l	TC: From	65 plf at	26.85 to	65 plf at	32.92
l	BC: From	4 plf at	-0.71 to	4 plf at	-0.68
l	BC: From	9 plf at	-0.68 to	9 plf at	11.46
l	BC: From	4 nlf at	11 46 to	4 nlf at	45 20

### **Plating Notes**

All plates are 2X4(A1) except as noted.

Wind loads based on MWFRS with additional C&C member design.

Wind loading based on both gable and hip roof types.

### **Additional Notes**

Negative reaction(s) of -224# MAX. from a non-wind load case requires uplift connection. See Maximum

Refer to DWG PB160160118 for piggyback details. The overall height of this truss excluding overhang is

WIND LOAD CASE MODIFIED!



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372034 / GABL Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T10 / FROM: CDM Qty: 10 CJ Customs-Curtis Jones-Spec House DrwNo: 124.21.1601.55362 Truss Label: PB02 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.002 F 999 240
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.004 F 999 180
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.003 F
Des Ld: 40.00	EXP: C Kzt: NA		HORZ(TL): 0.004 F
NCBCLL: 10.00	Mean Height: 22.07 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
Soffit: 2.00	BCDL: 2.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.417
Load Duration: 1.25	MWFRS Parallel Dist: h/2 to h	TPI Std: 2014	Max BC CSI: 0.194
Spacing: 24.0 "	C&C Dist a: 3.31 ft	Rep Fac: Yes	Max Web CSI: 0.048
' •	Loc. from endwall: not in 6.50 ft	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11
	•	•	•

	▲ Maximum Reactions (lbs), or *=PLF							
/#		G	ravity		No	on-Grav	vity	
240	Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL	
180	Α	_	/-267	/-	/219	/361	/148	
-	В*	121	/-	/-	/91	/52	/-	
-	Е	-	/-267	/-	/182	/272	/-	
	В		/-229					
	D		/-182					
	Wii	nd read	tions ba	sed on I	MWFRS			
	Α	Brg V	Vidth = 5	5.5	Min Re	q = 1.5	5	
	В	Brg V	Vidth = 1	139	Min Re	q = -		
	Е	Brg V	Vidth = 5	5.5	Min Re	q = 1.5	5	
	Bea	arings .	A, B, & E	are a r	igid surfa	ce.		
					orces less		375#	

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

### **Plating Notes**

All plates are 2X4(A1) except as noted.

#### Loading

Gable end supports 8" max rake overhang. Top chord must not be cut or notched.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

#### Wind

Wind loads based on MWFRS with additional C&C member design.

Wind loading based on both gable and hip roof types.

### **Additional Notes**

Negative reaction(s) of -267# MAX. from a non-wind load case requires uplift connection. See Maximum

See DWGS A14030ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is 15-5-1.



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372163 SPEC Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T18 FROM: CDM Qty: 1 CJ Customs-Curtis Jones-Spec House DrwNo: 124.21.1605.48970 Truss Label: PB03 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria	Ī
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#	
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.002 F 999 240	
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.004 F 999 180	
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): -0.002 F	
Des Ld: 40.00	EXP: C Kzt: NA		HORZ(TL): 0.004 F	
NCBCLL: 10.00	Mean Height: 22.07 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0	
Soffit: 2.00	BCDL: 2.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.480	
Load Duration: 1.25	MWFRS Parallel Dist: h/2 to h	TPI Std: 2014	Max BC CSI: 0.134	
Spacing: 24.0 "	C&C Dist a: 3.00 ft	Rep Fac: Varies by Ld Case	Max Web CSI: 0.049	
-	Loc. from endwall: not in 9.00 ft	FT/RT:20(0)/10(0)		
	GCpi: 0.18	Plate Type(s):		1
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11	ı
Lumber	•	•	•	_

▲ Ma	▲ Maximum Reactions (lbs), or *=PLF								
	Gravity Non-Gravity								
Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL			
Α	-	/-266	/-	/143	/28	/-			
B*	120	/-	/-	/26	/62	/-			
E	-	/-266	/-	/143	/28	/-			
Win	d reac	tions ba	sed on I	MWFRS					
A Brg Width = 5.5 Min Req = 1.5									
В	Brg W	/idth = 1	39	Min Re	q = -				
E Brg Width = 5.5 Min Req = 1.5									
Bearings A, B, & E are a rigid surface.									
Men	Members not listed have forces less than 375#								

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

#### **Special Loads**

--(Lumber Dur.Fac.=1.25 / Plate Dur.Fac.=1.25) TC: From BC: From 65 plf at 4 plf at -0.68 to 65 plf at 4 plf at 12 33

#### **Plating Notes**

All plates are 2X4(A1) except as noted.

Wind loads based on MWFRS with additional C&C member design.

Wind loading based on both gable and hip roof types.

### **Additional Notes**

Negative reaction(s) of -266# MAX. from a non-wind load case requires uplift connection. See Maximum

Refer to DWG PB160160118 for piggyback details. The overall height of this truss excluding overhang is 4-10-13.

WIND LOAD CASE MODIFIED!



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372035 / GABL Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T4 / FROM: CDM Qty: 10 DrwNo: 124.21.1601.55691 CJ Customs-Curtis Jones-Spec House Truss Label: PB04 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.002 F 999 240
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.004 F 999 180
BCDL: 10.00	Risk Category: II EXP: C Kzt: NA	Snow Duration: NA	HORZ(LL): 0.003 F
Des Ld: 40.00	Mean Height: 22.05 ft		HORZ(TL): 0.004 F
NCBCLL: 10.00	TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
Soffit: 2.00	BCDL: 2.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.430
Load Duration: 1.25	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.165
Spacing: 24.0 "	C&C Dist a: 3.00 ft	Rep Fac: Yes	Max Web CSI: 0.050
	Loc. from endwall: Any	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11

▲ N	laxim	um Read	ctions (I	bs), or *=	:PLF	
	G	Gravity		No	on-Grav	/ity
Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL
A	_	/-275	/-	/220	/345	/141
B*	121	/-	/-	/83	/57	/-
E	-	/-275	/-	/200	/260	/-
D		/-181				
Wir	nd rea	ctions ba	sed on I	MWFRS		
Α	Brg \	Vidth = 5	5.5	Min Re	q = 1.5	;
В		Vidth = 1	41	Min Re	q = -	
E	Brg V	Vidth = 5	5.5	Min Re	q = 1.5	,
Bea	arings	A, B, & E	are a r	igid surfa	ce.	
Mei	mbers	not liste	d have f	orces less	s than 3	375#

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

### **Plating Notes**

All plates are 2X4(A1) except as noted.

#### Loading

Gable end supports 8" max rake overhang. Top chord must not be cut or notched.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

#### Wind

Wind loads based on MWFRS with additional C&C member design.

Wind loading based on both gable and hip roof types.

### **Additional Notes**

Negative reaction(s) of -275# MAX. from a non-wind load case requires uplift connection. See Maximum

See DWGS A14030ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is 15-5-1.



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!


\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



SEQN: 372036 / GABL Ply: 1 Job Number: 21-5152 Cust: R 215 JRef: 1X542150016 T12 / FROM: CDM CJ Customs-Curtis Jones-Spec House Qty: 1 DrwNo: 124.21.1601.55363 Truss Label: PB05 / YK 05/04/2021





Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
TCDL: 10.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.000 E 999 240
BCLL: 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.001 F 999 180
BCDL: 10.00	Risk Category: II	Snow Duration: NA	HORZ(LL): 0.001 F
Des Ld: 40.00	EXP: C Kzt: NA		HORZ(TL): 0.002 F
NCBCLL: 10.00	Mean Height: 21.95 ft	Building Code:	Creep Factor: 2.0
Soffit: 2.00	TCDL: 5.0 psf BCDL: 2.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.042
Load Duration: 1.25	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.024
Spacing: 24.0 "	C&C Dist a: 3.00 ft	Rep Fac: Yes	Max Web CSI: 0.033
	Loc. from endwall: Any	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11

	▲ Maximum Reactions (lbs), or *=PLF								
A 9 /- /- /94 /84 /1: B* 73 /- /- /57 /24 /- I 9 /- /- /11 /0 /- Wind reactions based on MWFRS A Brg Width = 5.5 Min Req = 1.5		Gr	avity		No	n-Grav	ity		
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	Loc	R+	/ R-	/ Rh	/ Rw	/ U	/RL		
I 9 /- /- /11 /0 /- Wind reactions based on MWFRS A Brg Width = 5.5 Min Req = 1.5	Α	9	/-	/-	/94	/84	/136		
Wind reactions based on MWFRS A Brg Width = 5.5 Min Req = 1.5	B*	73	/-	/-	/57	/24	/-		
A Brg Width = 5.5 Min Req = 1.5	1	9	/-	/-	/11	/0	/-		
•	Wind reactions based on MWFRS								
B Brg Width = 135 Min Req = -	A Brg Width = 5.5 Min Req = 1.5								
	B Brg Width = 135 Min Req = -								
I Brg Width = 5.5 Min Req = 1.5									
Bearings A, B, & I are a rigid surface.									
Members not listed have forces less than 375#		_		_			75#		

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

### **Plating Notes**

All plates are 2X4 except as noted.

#### Loading

Gable end supports 8" max rake overhang. Top chord must not be cut or notched.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

#### Wind

Wind loads based on MWFRS with additional C&C


Wind loading based on both gable and hip roof types.

### **Additional Notes**

See DWGS A14030ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is 15-2-14.



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021


\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!


\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



Cust: R 215 JRef: 1X542150016 T25 / 05/04/2021





Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
10LL. 20.00	Wind Std: ASCE 7-16	Pg: NA Ct: NA CAT: NA	PP Deflection in loc L/defl L/#
1.0220.00	Speed: 130 mph	Pf: NA Ce: NA	VERT(LL): 0.000 C 999 240
DCLL. 0.00	Enclosure: Closed	Lu: NA Cs: NA	VERT(CL): 0.001 C 999 180
10.00	Risk Category: II EXP: C Kzt: NA	Snow Duration: NA	HORZ(LL): 0.000 F
Dec 1 d · 40 00			HORZ(TL): 0.001 F
NODOLL, 40 00	Mean Height: 21.78 ft TCDL: 5.0 psf	Building Code:	Creep Factor: 2.0
0.00	BCDL: 2.0 psf	FBC 7th Ed. 2020 Res.	Max TC CSI: 0.016
	MWFRS Parallel Dist: 0 to h/2	TPI Std: 2014	Max BC CSI: 0.010
1	C&C Dist a: 3.00 ft	Rep Fac: Yes	Max Web CSI: 0.002
	Loc. from endwall: Any	FT/RT:20(0)/10(0)	
	GCpi: 0.18	Plate Type(s):	
	Wind Duration: 1.60	WAVE	VIEW Ver: 20.01.01A.0724.11

#### ▲ Maximum Reactions (lbs) Gravity Non-Gravity Loc R+ /Rh /Rw /U /RL Α 96 /-/74 /-96 /20 Wind reactions based on MWFRS Brg Width = 4.7 Min Reg = 1.5Brg Width = 4.7 Min Req = 1.5 Bearings A & E are a rigid surface. Members not listed have forces less than 375#

#### Lumber

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

### **Plating Notes**

All plates are 2X4(A1) except as noted.

#### Loading

Gable end supports 8" max rake overhang. Top chord must not be cut or notched.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

#### Wind

Wind loads based on MWFRS with additional C&C


Wind loading based on both gable and hip roof types.

### **Additional Notes**

See DWGS A14030ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is 13-4-3.



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.

Alpine, a division of ITW Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, installation and bracing of trusses. A seal on this drawing or cover page listing this drawing, indicates acceptance of professional engineering responsibility solely for the design shown. The suitability and use of this drawing for any structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec. 2. For more information see these web sites: Alpine: alpineitw.com; TPI: tpinst.org; SBCA: sbcindustry.com; ICC: iccsafe.org; AWC: awc.org

6750 Forum Drive Suite 305 Orlando FL, 32821 SEQN: 372038 / FROM: CDM


GABL

Ply: 1 Qty: 11 Job Number: 21-5152

CJ Customs-Curtis Jones-Spec House

Truss Label: PB07

Cust: R 215 JRef: 1X542150016 T23 / DrwNo: 124.21.1601.55940 / YK 05/04/2021



Loading Criteria (psf)	Wind Criteria	Snow Criteria (Pg,Pf in PSF)	Defl/CSI Criteria
TCLL: 20.00 TCDL: 10.00 BCLL: 0.00 BCDL: 10.00 Des Ld: 40.00 NCBCLL: 10.00 Soffit: 2.00 Load Duration: 1.25 Spacing: 24.0 "	Wind Std: ASCE 7-16 Speed: 130 mph Enclosure: Closed Risk Category: II EXP: C Kzt: NA Mean Height: 21.91 ft TCDL: 5.0 psf BCDL: 2.0 psf MWFRS Parallel Dist: 0 to h/2 C&C Dist a: 3.00 ft Loc. from endwall: Any GCpi: 0.18 Wind Duration: 1.60	Pg: NA Ct: NA CAT: NA Pf: NA Ce: NA Lu: NA Cs: NA Snow Duration: NA  Building Code: FBC 7th Ed. 2020 Res. TPI Std: 2014 Rep Fac: Yes FT/RT:20(0)/10(0) Plate Type(s):	PP Deflection in loc L/defl L/# VERT(LL): 0.001 C 999 240 VERT(CL): 0.002 C 999 180 HORZ(LL): 0.001 F HORZ(TL): 0.001 F Creep Factor: 2.0 Max TC CSI: 0.042 Max BC CSI: 0.018 Max Web CSI: 0.001  VIEW Ver: 20.01.01A.0724.11
Lumbor	Willa Baration. 1.00	WAVE	VIEW Vel. 20.01.01A.0724.11

#### ▲ Maximum Reactions (lbs) Gravity Non-Gravity Loc R+ /Rh /Rw /U /RL 137 /103 /57 /-/-/93 /-137 Wind reactions based on MWFRS Brg Width = 4.7 Min Reg = 1.5Brg Width = 4.7 Min Req = 1.5 Bearings A & E are a rigid surface. Members not listed have forces less than 375#

#### Lumbei

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

### **Plating Notes**

All plates are 2X4(A1) except as noted.

#### Loading

Gable end supports 8" max rake overhang. Top chord must not be cut or notched.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

#### Wind

Wind loads based on MWFRS with additional C&C

Wind loading based on both gable and hip roof types.

### **Additional Notes**

See DWGS A14030ENC160118 & GBLLETIN0118 for gable wind bracing and other requirements.

Refer to DWG PB160160118 for piggyback details.

The overall height of this truss excluding overhang is 13-9-2.



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.

Alpine, a division of ITW Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, installation and bracing of trusses. A seal on this drawing or cover page listing this drawing, indicates acceptance of professional engineering responsibility solely for the design shown. The suitability and use of this drawing for any structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec.2.


For more information see these web sites: Alpine: alpineitw.com; TPI: tpinst.org; SBCA: sbcindustry.com; ICC: iccsafe.org; AWC: awc.org

6750 Forum Drive Suite 305 Orlando FL, 32821 Ply: 1 Qty: 2 Job Number: 21-5152

CJ Customs-Curtis Jones-Spec House

Truss Label: PB08

Cust: R 215 JRef: 1X542150016 T22 / DrwNo: 124.21.1601.55394 / YK 05/04/2021



▲ Maximum Reactions (lbs), or *=PLF							
	G	avity		No	on-Gra	vity	
Loc	R+	/ R-	/ Rh	/ Rw	/ U	/ RL	
Α	10	/-	/-	/43	/29	/46	
В*	92	/-	/-	/88	/15	/-	
Win	d read	ctions b	ased on I	MWFRS			
Α	Brg V	Vidth =	4.7	Min Re	q = 1.5	5	
B Brg Width = 22.7 Min Req = -							
Bearings A & B are a rigid surface.							
Members not listed have forces less than 375#							

#### Lumbe

Top chord: 2x4 SP #2; Bot chord: 2x4 SP #2; Webs: 2x4 SP #3;

### **Plating Notes**

All plates are 2X4(A1) except as noted.

(\*\*) 1 plate(s) require special positioning. Refer to scaled plate plot details for special positioning requirements.

#### **Purlins**

In lieu of rigid ceiling use purlins to brace BC @ 24"


### Wind

Wind loads based on MWFRS with additional C&C member design.

Right end vertical not exposed to wind pressure. Wind loading based on both gable and hip roof types.

#### **Additional Notes**

Refer to DWG PB160160118 for piggyback details. The overall height of this truss excluding overhang is 13-9-2.



FL REG# 278, Yoonhwak Kim, FL PE #86367 05/04/2021

\*\*WARNING\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING!

\*\*IMPORTANT\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS

Trusses require extreme care in fabricating, handling, shipping, installing and bracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid ceiling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7, or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. Refer to job's General Notes page for additional information.



## Gable Stud Reinforcement Detail


ASCE 7-16: 140 mph Wind Speed, 15' Mean Height, Enclosed, Exposure C, Kzt = 1.00

Dr: 120 mph Wind Speed, 15' Mean Height, Partially Enclosed, Exposure C, Kzt = 1.00

Dr: 120 mph Wind Speed, 15' Mean Height, Enclosed, Exposure D, Kzt = 1.00

Or: 100 mph Wind Speed, 15' Mean Height, Partially Enclosed, Exposure D. Kzt = 1.00

		2x4 Vertica	Brace	No	(1) 1×4 *L	" Brace *	(1) 2×4 *L	" Brace *	(2) 2×4 *L	* Brace **	(1) 2×6 *L	" Brace *	(2) 2x6 L	Brace **
	Spacing	Species	Grade	Braces	Group A	Group B	Group A	Group B	Group A	Group B	Group A	Group B	Group A	Group B
💠		ر ر	#1 / #2	4′ 3″	7′ 3″	7′ 7″	8′ 7 <b>″</b>	8′ 11 <b>″</b>	10′ 3 <b>″</b>	10′ 8″	13′ 6″	14' 0"	14' 0"	14′ 0″
ˈo	1 1	SPF	#3	4′ 1″	6′ 7 <b>″</b>	7′ 1″	8′ 6 <b>″</b>	8′ 10 <b>″</b>	10′ 1″	10′ 6″	13′ 4″	13′ 10″	14′ 0″	14′ 0″
21	Ų	HF	Stud	4′ 1″	6′ 7 <b>″</b>	7′ 0 <b>″</b>	8′ 6 <b>″</b>	8′ 10 <b>′</b>	10′ 1″	10′ 6″	13′ 4″	13′ 10″	14′ 0″	14′ 0″
>	0	1 11	Standard	4′ 1″	5′ 8 <b>″</b>	6′ 0 <b>″</b>	7′ 7″	8′ 1 <b>″</b>	10′ 1″	10′ 6″	11′ 10″	12′ 8″	14′ 0″	14′ 0″
o			#1	4′ 6″	7′ 4″	7′ 8 <b>″</b>	8′ 8 <b>″</b>	9′ 0″	10′ 4″	10′ 9″	13′ 8″	14′ 0″	14′ 0″	14′ 0″
-	*	SP	#2	4′ 3″	7′ 3″	7′ 7″	8′ 7 <b>″</b>	8′ 11 <b>″</b>	10′ 3″	10′ 8″	13′ 6″	14′ 0″	14′ 0″	14′ 0″
	4	ъ	#3	4′ 2″	6′ 0″	6′ 4″	7′ 11″	8′ 6 <b>″</b>	10′ 2″	10′ 7″	12′ 5 <b>″</b>	13′ 4″	14′ 0″	14′ 0″
b	$\Omega$	DFL	Stud	4′ 2″	6′ 0″	6′ 4″	7′ 11″	8′ 6 <b>″</b>	10′ 2″	10′ 7″	12′ 5 <b>″</b>	13′ 4″	14′ 0″	14′ 0″
II			Standard	4′ 0″	5′ 3 <b>″</b>	5′ 7 <b>″</b>	7′ 0 <b>″</b>	7′ 6″	9′ 6″	10′ 2″	11′ 0″	11′ 10″	14′ 0″	14′ 0″
II <u>.</u>		SPF	#1 / #2	4′ 11″	8′ 4″	8′ 8 <b>″</b>	9′ 10″	10′ 3″	11′ 8″	12′ 2″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
+>		761	#3	4′ 8 <b>″</b>	8′ 1 <b>″</b>	8′ 8 <b>″</b>	9′ 8″	10′ 1″	11′ 7″	12′ 1″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
	Ō	HF	Stud	4′ 8″	8′ 1″	8′ 6″	9′ 8″	10′ 1″	11′ 7″	12′ 1″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
امَا	Ō	1 11	Standard	4′ 8 <b>″</b>	6′ 11″	7′ 5″	9′ 3 <b>″</b>	9′ 11″	11′ 7″	12′ 1″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
$\parallel$	0		#1	5′ 1 <b>″</b>	8′ 5 <b>″</b>	8′ 9 <b>″</b>	9′ 11″	10′ 4″	11′ 10″	12′ 4″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
/		SP	#2	4′ 11″	8′ 4″	8′ 8 <b>″</b>	9′ 10″	10′ 3″	11′ 8″	12′ 2 <b>″</b>	14′ 0″	14′ 0″	14′ 0″	14′ 0″
	. ^	·	#3	4′ 9″	7′ 4″	7′ 9″	9′ 9″	10′ 2″	11′ 8″	12′ 1″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
ושו	16	DFL	Stud	4′ 9″	7′ 4″	7′ 9″	9′ 9″	10′ 2″	11′ 8″	12′ 1″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
			Standard	4′ 8″	6′ 5 <b>″</b>	6′ 10 <b>″</b>	8′ 7 <b>″</b>	9′ 2″	11′ 7″	12′ 1″	13′ 6″	14′ 0″	14′ 0″	14′ 0″
ᄓᆇᆝ		SPF	#1 / #2	5′ 5 <b>″</b>	9′ 2″	9′ 6 <b>″</b>	10′ 10 <b>″</b>	11′ 3″	11′ 8″	13′ 5 <b>″</b>	14′ 0″	14′ 0″	14′ 0″	14′ 0″
ơ			#3	5′ 1 <b>″</b>	9′ 0″	9′ 4″	10′ 8″	11′ 1″	12′ 9″	13′ 3″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
0	Ō	HF	Stud	5′ 1 <b>″</b>	9′ 0″	9′ 4″	10′ 8″	11′ 1″	12′ 9″	13′ 3″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
	Ō	1 11	Standard	5′ 1 <b>′</b>	8′ 0 <b>″</b>	8′ 6 <b>″</b>	10′ 8″	11′ 1″	12′ 9″	13′ 3″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
$   \times  $	0	00	#1	5′ 8 <b>″</b>	9′ 3″	9′ 8″	10′ 11″	11′ 4″	13′ 0″	13′ 6 <b>″</b>	14′ 0″	14′ 0″	14′ 0″	14′ 0″
6	*	SP	#2	5′ 5″	9′ 2″	9′ 6″	10′ 10″	11′ 3″	12′ 11″	13′ 5″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
$  \breve{\Sigma} $	ù	DC:	#3	5′ 3 <b>″</b>	8′ 5 <b>″</b>	9′ 0″	10′ 9″	11′ 2″	12′ 10 <b>″</b>	13′ 4″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
	Ţ	DFL	Stud	5′ 3 <b>″</b>	8′ 5 <b>″</b>	9′ 0″	10′ 9″	11′ 2″	12′ 10 <b>″</b>	13′ 4″	14′ 0″	14′ 0″	14′ 0″	14′ 0″
			Standard	5′ 1 <b>″</b>	7′ 5 <b>″</b>	7′ 11″	9′ 11″	10′ 7″	12′ 9″	13′ 3″	14′ 0″	14′ 0″	14′ 0″	14′ 0″



1x4 Braces shall be SRB (Stress-Rated Board) \*\*For 1x4 So. Pine use only Industrial 55 or Industrial 45 Stress-Rated Boards, Group B values may be used with these grades.


Gable Truss Detail Notes: Wind Load deflection criterion is L/240.

Provide uplift connections for 55 plf over continuous bearing (5 psf TC Dead Load).


Gable end supports load from 4' 0" outlookers with 2' 0" overhang, or 12" plywood overhang.

Attach "L" braces with 10d (0.128"x3.0" min) nails. \* For (1) "L" brace: space nails at 2" o.c. in 18" end zones and 4" o.c. between zones. ₩¥For (2) "L" braces: space nails at 3" o.c. in 18" end zones and 6" o.c. between zones.

"L" bracing must be a minimum of 80% of web member length.



Refer to the Building Designer for conditions not addressed by this detail.



\*\*\*VARNINGI\*\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWINGI \*\*\*\*IMPORTANT\*\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS.

Trusses require extreme care in fabricating, handling, shipping, installing and macing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI unless noted otherwise, top chord shall have properly attached structural sheathing and botton chord shall have a properly attached rigid celling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7 or B10, as applicable. Applicable to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions.

Alpine, a division of ITV Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, installation & bracing of trusses.

A seal on this drawing or cover page listing this drawing, indicates acceptance of professional engineering responsibility solely for the design shown. The suitability and use of this drawing for any structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec.2.

For more information see this job's general notes page and these web sites 04/2021 ALPINE: www.alpineitw.com, TPI: www.tpinst.org, SBCA: www.sbcindustry.org, ICC: www.cesterorg, 278 Yoonhwak Kim, FL PE #86367

ASCE7-16-GAB14015 |DATE 01/26/2018 

MAX, TOT, LD, 60 PSF

MAX. SPACING 24.0"

## Gable Stud Reinforcement Detail

ASCE 7-16: 140 mph Wind Speed, 30' Mean Height, Enclosed, Exposure C, Kzt = 1.00


Dr: 120 mph Wind Speed, 30' Mean Height, Partially Enclosed, Exposure C, Kzt = 1.00

Or: 120 mph Wind Speed, 30' Mean Height, Enclosed, Exposure D, Kzt = 1.00

Or: 100 mph wind speed, 30' Mean Height Portiolly Enclosed Exposure D, Kzt = 1.00

	100 mph wind speed, 30' Mean Height, Partially Enclosed, Exposure D, Kzt = 1.00														
		2×4 · Vertica	Brace	No	(1) 1×4 "L	" Brace *	(1) 2×4 "L	" Brace *	(2) 2×4 L	" Brace **	(1) 2×6 *L	" Brace *	(2) 2x6 <b>1</b> L	Brace **	ı
_	Spacing	Species	Grade	Braces	Group A	Group B	Group A	Group B	Group A	Group B	Group A	Group B	Group A	Group B	
1		CDE	#1 / #2	4′ 1″	6′ 11″	7′ 2″	8′ 2 <b>″</b>	8′ 6″	9′ 9″	10′ 2″	12′ 10″	13′ 4″	14′ 0″	14′ 0″	ıl
	1	SPF	#3	3′ 10″	6′ 2″	6′ 7″	8′ 1″	8′ 5 <b>″</b>	9′ 8″	10′ 0″	12′ 8″	13′ 2″	14′ 0″	14′ 0″	ıl
Ó	ΙŲ	HF	Stud	3′ 10″	6′ 2″	6′ 6″	8′ 1″	8′ 5″	9′ 8″	10′ 0″	12′ 8″	13′ 2″	14′ 0″	14′ 0″	ıl
Ϊ́	10	ПГ	Standard	3′ 10″	5′ 3″	5′ 7 <b>″</b>	7′ 0″	7′ 6″	9′ 6″	10′ 0″	11′ 0″	11′ 10″	14′ 0″	14′ 0″	ıl
به	_		#1	4′ 2 <b>″</b>	7′ 0 <b>″</b>	7′ 3″	8′ 3″	8′ 7″	9′ 10″	10′ 3″	13′ 0″	13′ 6″	14′ 0″	14′ 0″	ıl
$\parallel$ $\perp$	*	I SP	#2	4′ 1″	6′ 11″	7′ 2″	8′ 2 <b>″</b>	8′ 6″	9′ 9″	10′ 2″	12′ 10″	13′ 4″	14′ 0″	14′ 0″	ıl
	4		#3	4′ 0 <b>″</b>	5′ 7″	5′ 11 <b>″</b>	7′ 5″	7′ 11″	9′ 8″	10′ 1″	11′ 7″	12′ 5″	14′ 0″	14′ 0″	ıl
d		IDFLI	Stud	4′ 0″	5′ 7″	5′ 11 <b>″</b>	7′ 5″	7′ 11″	9′ 8″	10′ 1″	11′ 7″	12′ 5″	14′ 0″	14′ 0″	ıl
			Standard	3′ 9″	4′ 11″	5′ 13 <b>″</b>	6′ 6″	7′ 0 <b>″</b>	8′ 10 <b>″</b>	9′ 6″	10′ 3″	11′ 0″	13′ 11″	14′ 0″	ıl
$\cup$	tic  :	SPF	#1 / #2	4′ 8 <b>″</b>	7′ 11″	8′ 3 <b>″</b>	9′ 4″	9′ 9″	11′ 2″	11′ 7″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ıl
1			#3	4′ 5 <b>″</b>	7′ 6″	8′ 3″	9′ 3″	9′ 7″	11′ 0″	11′ 6″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ıl
	U	HF	Stud	4′ 5 <b>″</b>	7′ 6″	8′ 0 <b>″</b>	9′ 3″	9′ 7″	11′ 0″	11′ 6″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ıl
ا د	Ιō	1 11	Standard	4′ 5 <b>″</b>	6′ 5″	6′ 10 <b>″</b>	8′ 7 <b>″</b>	9′ 2″	11′ 0″	11′ 6″	13′ 6″	14′ 0″	14′ 0″	14′ 0″	ıl
			#1	4′ 10″	8′ 0 <b>″</b>	8′ 4″	9′ 6″	9′ 10″	11′ 3″	11′ 9″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ıl
>		SP	#2	4′ 8 <b>″</b>	7′ 11″	8′ 3″	9′ 4″	9′ 9″	11′ 2″	11′ 7″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ıΙ
	9	l	#3	4′ 7″	6′ 10 <b>″</b>	7′ 3″	9′ 1″	9′ 8″	11′ 1″	11′ 6″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ıl
Ι ω	1	IDFLI	Stud	4′ 7″	6′ 10 <b>″</b>	7′ 3″	9′ 1″	9′ 8″	11′ 1″	11′ 6″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ıl
			Standard	4′ 5 <b>″</b>	6′ 0 <b>″</b>	6′ 5″	8′ 0″	8′ 7 <b>″</b>	10′ 10″	11′ 6″	12′ 7″	13′ 15″	14′ 0″	14′ 0″	ıl
Gabl		SPF	#1 / #2	5′ 2 <b>″</b>	8′ 9″	9′ 1″	10′ 4″	10′ 9″	11′ 2″	12′ 9″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ן וַ
	l . <del>.</del>		#3	4′ 10″	8′ 7″	8′ 11 <b>″</b>	10′ 2″	10′ 7″	12′ 2″	12′ 8″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ı
10		HF	Stud	4′ 10 <b>″</b>	8′ 7″	8′ 11 <b>″</b>	10′ 2″	10′ 7″	12′ 2″	12′ 8 <b>″</b>	14′ 0″	14′ 0″	14′ 0″	14′ 0″	, '
	Ιō	1 11	Standard	4′ 10″	7′ 5″	7′ 11″	9′ 11″	10′ 7″	12′ 2″	12′ 8″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	
M X X	~		#1	5′ 4″	8′ 10 <b>″</b>	9′ 2″	10′ 5 <b>″</b>	10′ 10″	12′ 5 <b>″</b>	12′ 11″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ı
18		SP	#2	5′ 2 <b>″</b>	8′ 9″	9′ 1″	10′ 4″	10′ 9″	12′ 3″	12′ 9″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	. (
Ι <del>Σ</del>	l ù	المحا	#3	5′ 0″	7′ 10″	8′ 4″	10′ 3″	10′ 8″	12′ 2″	12′ 8″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ı
		IDFLI	Stud	5′ 0″	7′ 10 <b>″</b>	8′ 4″	10′ 3″	10′ 8″	12′ 2″	12′ 8″	14′ 0″	14′ 0″	14′ 0″	14′ 0″	ı

9' 3"



1x4 Braces shall be SRB (Stress-Rated Board). \*\*\*\*For 1x4 So. Pine use only Industrial 55 or Industrial 45 Stress-Rated Boards. Group B values may be used with these grades.

Gable Truss Detail Notes: Wind Load deflection criterion is L/240.

Provide uplift connections for 100 plf over continuous bearing (5 psf TC Dead Load).

Gable end supports load from 4' 0" outlookers with 2' 0" overhang, or 12" plywood overhang.

Attach "L" braces with 10d (0.128"x3.0" min) nails.

# For (1) "L" brace: space nails at 2" o.c.
in 18" end zones and 4" o.c. between zones.

##For (2) "L" braces: space nails at 3" o.c.
in 18" end zones and 6" o.c. between zones.

"L" bracing must be a minimum of 80% of web member length.

Gable Vertical Plate Sizes						
Vertical Length	No Splice					
Less than 4' 0"	2X4					
Greater than 4' 0", but less than 11' 6"	3X4					
Greater than 11' 6"	4X4					
+ Refer to common truss design for						

Refer to the Building Designer for conditions not addressed by this detail.

|DATE 01/26/2018

ASCE7-16-GAB14030

Diagonal brace option: vertical length may be doubled when diagonal brace is used. Connect diagonal brace for 525# at each end. Max web "L" Brace End total length is 14'. Zones, typ. 2x6 DF-L #2 or better diagonal brace; single Vertical length shown or double cut in table above. (as shown) at upper end. Constituous Bearing Connect diagonal at Refer to chart above son mai midpoint of vertical web.

9' 10"

Symm C About C

12' 2"

12' 8"

14' 0"

14' 0"

ak Kim EL DE #86367

14' 0"

14' 0"

\*\*\*VARNING\*\*\* READ AND FOLLOV ALL NOTES ON THIS DRAVING \*\*\*IMPORTANT\*\*\* FURNISH THIS DRAVING TO ALL CONTRACTORS INCLUDING THE INSTALLERS.

7′ 4″

6' 11"

Trusses require extreme care in fabricating, handling, shipping, installing of bracing, Refer to and follow the latest edition of BCSI (Building Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and botton chord shall have a properly attached rigid celling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7 or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise.

Refer to drawings 160A-Z for standard plate positions.

Alpine, a division of ITV Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, installation & bracing of trusses.

A seal on this drawing or cover page listing this drawing, indicates acceptance of professional

A seal on this drawing or cover page listing this drawing, indicates acceptance of professione regineering responsibility solely for the design shown. The suitability and use of this drawing for any structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec.2.

structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec.2.

For nore information see this job's general notes page and these web sites;

ALPINE: www.alpineitw.com; TPI: www.tpinst.org; SBCA; www.sbcindustry.org; ICC; www.alpis.be/ap/ag/1/7/2

MAX. TOT. LD. 60 PSF
MAX. SPACING 24.0"

ALPINE AN ITW COMPANY

Standard

4' 10"

Gable Truss

# CLR Reinforcing Member Substitution

This detail is to be used when a Continuous Lateral Restraint (CLR) is specified on a truss design but an alternative web reinforcement method is desired.

### Notes:

This detail is only applicable for changing the specified CLR shown on single ply sealed designs to T-reinforcement or L-reinforcement or scab reinforcement.


Alternative reinforcement specified in chart below may be conservative. For minimum alternative reinforcement, re-run design with appropriate reinforcement type.

Use scabs instead of L- or T- reinforcement on webs with intersecting truss joints, such as K-web joints, that may interfere with proper application along the narrow face of the web.


Web Member	Specified CLR	Alternative Reir	
Size	Restraint	T- or L- Reinf.	
2x3 or 2x4	1 row	2×4	1-2×4
2x3 or 2x4	2 rows	2×6	2-2×4
2×6	1 row	2×4	1-2×6
2×6	2 rows	2×6	2-2×4( <b>米</b> )
5×8	1 row	2×6	1-2×8
5×8	2 rows		2-2×6( <del>*/</del> )

T-reinforcement, L-reinforcement, or scab reinforcement to be same species and grade or better than web member unless specified otherwise on Engineer's sealed design.

(\*\*) Center scab on wide face of web. Apply (1) scab to each face of web.



No. 86367



\*\*\*WARNING\*\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING \*\*\*\*IMPORTANT\*\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS.

Trusses require extreme care in fabricating, handling, shipping, installing and inclinations of the installing and process. Trusses require extreme care in fabricating, handling, shipping, installing and pracing. Refer to and follow the latest edition of BCSI (Buldling Component Safety Information, by TPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and botton chord shall have a properly attached rigid celling. Locations shown for pernanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7 or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions.

Alpine, a division of ITV Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, installation & bracing of trusses.

A seal on this drawing or cover page listing this drawing, indicates acceptance of professional

structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec.2. For more information see this job's general notes page and these web sites 10.424.12 278, Yoonhwak Kim, FL PE #86367 ALPINE; www.abjneitw.com, TPI; www.tpinst.org, SBCA; www.sbcindustry.org, ICC; www.iccssfeb.ng; Yoonhwak Kim, FL PE #86367

TC LL PSF REF CLR Subst.

TC DL PSF DATE 01/02/19

BC DL PSF DRWG BRCLBSUB0119

BC LL PSF DUR. FAC.

SPACING

ALPINE ANTW COMPANY

## Gable Detail For Let-in Verticals Gable Truss Plate Sizes Refer to appropriate Alpine gable detail for minimum plate sizes for vertical studs. (+) Refer to Engineered truss design for peak, splice, web, and heel plates. \*If gable vertical plates overlap, use a single plate that covers the total area of the overlapped plates to span the web. Gable Example: Length typ.

Provide connections for uplift specified on the engineered truss design.

Attach each "T" reinforcing member with

End Driven Nails:

10d Common (0.148"x 3.", min) Nails at 4" o.c. plus

(4) nails in the top and bottom chords.

10d Common (0.148"x3".min) Toenails at 4" o.c. plus

(4) toenails in the top and bottom chords.

This detail to be used with the appropriate Alpine gable detail for ASCE wind load.

ASCE 7-05 Gable Detail Drawings

A13015051014, A12015051014, A11015051014, A10015051014, A14015051014, A13030051014, A12030051014, A11030051014, A10030051014, A14030051014

ASCE 7-10 & ASCE 7-16 Gable Detail Drawings A11515ENC100118, A12015ENC100118, A14015ENC100118, A14015ENC100118,


A18015ENC100118, A12015ENC100118, A12015ENC100118, A12015ENC100118, A120015ENC100118, A120015ENC100118, A120015ENC100118, A120015ENC100118, A12003ENC100118, A12003ENC100118, A120030ENC100118, A120030ENC100118,

\$18015ENC100118, \$20015ENC100118, \$20015END100118, \$20015PED100118

\$11530ENC100118, \$12030ENC100118, \$14030ENC100118, \$16030ENC100118) \$18030ENC100118, \$20030ENC100118, \$20030END100118, \$20030PED100118

See appropriate Alpine gable detail for maximum unreinforced gable vertical

#### "T" Reinforcement Attachment Detail



To convert from "L" to "T" reinforcing members, multiply "T" increase by length (based on appropriate Alpine gable detail).

Maximum allowable "T" reinforced gable vertical length is 14' from top to bottom chord.

"T" reinforcing member material must match size, specie, and grade of the "L" reinforcing member.

#### Web Length Increase w/ "T" Brace

"T" Reinf.	"T"
Mbr. Size	Increase
2×4	30 %
2x6	20 %

Example:

ASCE 7-10 Wind Speed = 120 mph Mean Roof Height = 30 ft, Kzt = 1.00 Gable Vertical = 24°o.c. SP #3 "T" Reinforcing Member Size = 2x4

"T" Brace Increase (From Above) = 30% = 1.30

(1) 2x4 "L" Brace Length = 8' 7"

Maximum "T" Reinforced Gable Vertical Length  $1.30 \times 8' \ 7'' = 11' \ 2''$ 

\*\*\*VARNINGI\*\*\* READ AND FOLLOW ALL NOTES ON THIS DRAWING \*\*\*IMPORTANT\*\*\* FURNISH THIS DRAWING TO ALL CONTRACTORS INCLUDING THE INSTALLERS.

Trusses require extreme care in fabricating, shaping, shipping, installing and pracing. Refer to and follow the latest edition of BCSI (Building Component Safety Information, br PI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and bottom chord shall have a properly attached rigid celling. Locations shown for permanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7 or B10, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise.

Refer to drawings 160A-Z for standard plate positions.

Alpine, a division of ITV Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, nstallation 8 bracing of trusses.

A seal on this drawing or cover page listing this drawing, indicates acceptance of professional

engineering responsibility solely for the design shown. The sultability and use of this for any structure is the responsibility of the Building Designer per ANSI/TPI 1 Sec.2.

For more information see this job's general notes page and these web sites ALPINE: www.alpineitw.com; TPI: www.tpinst.org; SBCA: www.sbcindustry.org; ICC: www.fpsace onbwak Kim EL PE #86367 IREF LET-IN VERT DATE 01/02/2018 DRWG GBLLETIN0118

MAX. TOT. LD. 60 PSF DUR. FAC. ANY

MAX. SPACING 24.0"



Rigid Sheathing

Ceiling

4 Nails

Nails

Spaced At

4 Nails

Reinforcing Member

Gable

Truss

## Piggyback Detail - ASCE 7-16: 160 mph, 30' Mean Height, Enclosed, Exposure C, Kzt=1.00


160 mph Wind, 30.00 ft Mean Hgt, ASCE 7-16, Enclosed Bldg. located anywhere in roof, Exp C, Wind DL= 5.0 psf (min), Kzt=1.0. Dr 140 mph wind, 30.00 ft Mean Hgt, ASCE 7-16, Enclosed Bldg. located anywhere in roof, Exp D, wind DL= 5.0 psf (min), Kzt=1.0.

Note: Top chords of trusses supporting piggyback cap trusses must be adequately braced by sheathing or purlins. The building Engineer of Record shall provide diagonal bracing or any other suitable anchorage to permanently restrain purlins, and lateral bracing for out of plane loads over gable ends.

Maximum truss spacing is 24' o.c. detail is not applicable if cap supports additional loads such as cupola, steeple, chimney or drag strut loads.

\*\* Refer to Engineer's sealed truss design drawing for piggyback and base truss specifications.

## Detail A: Purlin Spacing = 24" o.c. or less



Piggyback cap truss slant nailed to all top chord purlin bracing with (2) 16d box nails (0.135"x3.5") and secure top chord with 2x4 #3 grade scab (1 side only at each end) attached with 2 rows of 10d box nails (0.128"x3") at 4" o.c.


Attach purlin bracing to the flat top chord using (2) 16d box nails (0.135"x3.5").

The top chord #3 grade 2x4 scab may be replaced with either of the following: (1) 3X8 Trulox plate attached with (8) 0.120"x1.375" nalls, (4) into cap TC & (4) into base truss TC or (1) 28PB wave piggyback plate plated to the piggyback truss TC and attached to the base truss TC with (4) 0.120"x1.375" nails. Note: Nailing thru holes of wave plate is acceptable.

## Detail B: Purlin Spacing > 24" o.c.

Piggyback cap truss slant nailed to all top chord purlin bracing with (2) 16d box nails (0.135"x3.5") and secure top chord with 2x4 #3 grade scab (1 side only at each end) attached with 2 rows of 10d box nails (0.128"x3") at 4" o.c.

Attach purlin bracing to the flat top chord using a minimum of (2) 16d box nails (0.135"x3.5").



Note: If purlins or sheathing are not specified on the flat top of the bose  $\mathfrak{I}$ truss, purlins must be installed at 24" o.c. max. and use Detail A.

\* In addition, provide connection with one of the following methods:

Use 3X8 Trulox plates for 2x4 chord member, and 3X10 Trulox plates for 2x6 and larger chord members. Attach to each face @ 8' o.c. with (4) 0.120"x1.375" nails into cap bottom chord and (4) in base truss top chord. Trulox plates may be staggered 4' o.c. front to back faces.

#### APA Rated Gusset

8'x8'x7'16' (min) APA rated sheathing gussets (each face). Attach @ 8' o.c. with (8) 6d common (0.13'x2') nalls per gusset, (4) in cap bottom chord and (4) in base truss top chord. Gussets may be staggered 4' o.c. front to back faces.

#### 2x4 Vertical Scabs

2x4 SPF #2, full chord depth scabs (each face). Attach @ 8' o.c. with (6) 10d box nails (0.128"x3") per scab, (3) in cap bottom chord and (3) in base truss top chord. Scabs may be staggered 4' o.c. front to back faces.

#### 28PB Wave Piggyback Plate

Dine 28PB wave piggyback plate to each face 8 8' o.c. Attach teeth to piggyback at time of fabrication. Attach to supporting truss with (4) 0.120'x1.375' nails per face per ply.
Piggyback plates may be staggered 4' o.c. front to back faces.

## 

Trusses require extreme care in fabricating, handling, shipping, installing and internacing. Refer to and follow the latest edition of BCSI (Buldling Component Safety Information, by FPI and SBCA) for safety practices prior to performing these functions. Installers shall provide temporary bracing per BCSI. Unless noted otherwise, top chord shall have properly attached structural sheathing and botton chord shall have a properly attached rigid celling. Locations shown for pernanent lateral restraint of webs shall have bracing installed per BCSI sections B3, B7 or BIO, as applicable. Apply plates to each face of truss and position as shown above and on the Joint Details, unless noted otherwise. Refer to drawings 160A-Z for standard plate positions. 13,05/ONAL

Alpine, a division of ITV Building Components Group Inc. shall not be responsible for any deviation from this drawing, any failure to build the truss in conformance with ANSI/TPI 1, or for handling, shipping, installation & bracing of trusses.

A seal on this drawing or cover page listing this drawing, indicates acceptance of professional AN ITW COMPANY

engineering responsibility solely for the design shown. The suitability and use of this drawing for any structure is the responsibility of the Bullding Designer per ANSI/TPI 1 Sec.2. For more information see this job's general notes page and these web sites, ALPINE: www.alpineitw.com; TPI: www.tpinst.org; SBCA: www.sbcindustry.org; ICC: www.desage.general

DATE 01/02/2018 DRWG PB160160118

PIGGYBACK

SPACING 24.0"

13723 Riverport Drive Suite 200 Maryland Heights, MO 63043

nhwak Kim EL PE #86367