

Florida Building Code, Sixth Edition (2017) - Energy Conservation

EnergyGauge Summit® Fla/Com-2017, Effective Date: Dec 31, 2017

IECC 2015 - Total Building Performance Compliance Option

Check List

Applications for compliance with the Florida Building Code, Energy Conservation shall include:

- ☒ This Checklist
- ☒ The full compliance report generated by the software that contains the project summary, compliance summary, certifications and detailed component compliance reports.
- ☒ The compliance report must include the full input report generated by the software as contiguous part of the compliance report.
- ☒ Boxes appropriately checked in the Mandatory Section of the compliance report.

WARNING: INPUT REPORT NOT GENERATED.

To include input report in final submission, go to the Project Form, Settings Tab and check the box - "Append Input Report to Compliance Output Report"
Then rerun your calculation



PROJECT SUMMARY

Short Desc: Office

Description: I-75 Truck Stop Repair Center

Owner: I-75 Truck Stop Repair Center

Address1: 14197 S US 441

City: Ellisville

Address2:

State: FL

Zip: 32024

Type: Office

Class: New Finished building

Jurisdiction: COLUMBIA COUNTY, COLUMBIA COUNTY, FL (221000)

Conditioned Area: 2373 SF

Conditioned & UnConditioned Area: 2373 SF

No of Stories: 1

Area entered from Plans 2373 SF

Permit No: 0

Max Tonnage 6

If different, write in: _____

Compliance Summary

Component	Design	Criteria	Result
Gross Energy Cost (in \$)	1,489.0	1,516.0	PASSED
LIGHTING CONTROLS			PASSES
EXTERNAL LIGHTING			No Entry
HVAC SYSTEM			PASSES
PLANT			No Entry
WATER HEATING SYSTEMS			PASSES
PIPING SYSTEMS			PASSES
Met all required compliance from Check List?			Yes/No/NA
IMPORTANT MESSAGE Info 5009 -- -- -- An input report of this design building must be submitted along with this Compliance Report			

CERTIFICATIONS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code

Prepared By: Ronald Miller

Building Official: _____

Date: 12/9/19

Date: _____

I certify that this building is in compliance with the FLorida Energy Efficiency Code

Owner Agent: _____

Date: _____

If Required by Florida law, I hereby certify (*) that the system design is in compliance with the Florida Energy Efficiency Code

Architect: Nicholas Paul Geisler

Reg No: AR0007005

Electrical Designer: Nicholas Paul Geisler

Reg No: AR0007005

Lighting Designer: Nicholas Paul Geisler

Reg No: AR0007005

Mechanical Designer: Nicholas Paul Geisler

Reg No: AR0007005

Plumbing Designer: Nicholas Paul Geisler

Reg No: AR0007005

(*) Signature is required where Florida Law requires design to be performed by registered design professionals. Typed names and registration numbers may be used where all relevant information is contained on signed/sealed plans.


Certified Energy Rater #1494

Project: Office
 Title: I-75 Truck Stop Repair Center
 Type: Office
 (WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Building End Uses

	1) Proposed	2) Baseline
Total	92.20	111.50
	\$1,489	\$1,784
ELECTRICITY(MBtu/kWh/\$)	92.20	111.50
	26983	32665
	\$1,489	\$1,784
AREA LIGHTS	13.40	17.10
	3920	5012
	\$216	\$274
MISC EQUIPMT	12.40	12.40
	3619	3619
	\$200	\$198
PUMPS & MISC	0.20	0.10
	48	38
	\$3	\$2
SPACE COOL	36.80	36.50
	10774	10680
	\$595	\$583
SPACE HEAT	17.30	13.60
	5075	3987
	\$280	\$218
VENT FANS	12.10	31.80
	3547	9329
	\$196	\$509

Credits Applied: None

Passing Criteria = 1516

Design (including any credits) = 1489

Passing requires Proposed Building cost to be at most 85% of
 Baseline cost. This Proposed Building is at 83.5%

PASSES

External Lighting Compliance						
Description	Category	Tradable?	Allowance (W/Unit)	Area or Length or No. of Units (Sqft or ft)	ELPA (W)	CLP (W)
						None

Project: Office
 Title: I-75 Truck Stop Repair Center
 Type: Office
 (WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Lighting Controls Compliance						
Acronym	Ashrae ID	Description	Area (sq.ft)	Design CP	Min CP	Compliance
Handicap RR 1	6	Toilet and Washroom	42	1	1	PASSES
Handicap RR 2	6	Toilet and Washroom	42	1	1	PASSES
Handicap RR 3	6	Toilet and Washroom	42	1	1	PASSES
Parts Manager	17	Office - Enclosed	75	1	1	PASSES
Locker Room	23	Locker Room	82	1	1	PASSES
Parts Warehouse	3	Storage & Warehouse - Bulky Active Storage	1,331	1	1	PASSES
Reception/Bill pay	29,003	Terminal - Ticket Counter	42	1	1	PASSES
Service Manager	17	Office - Enclosed	104	1	1	PASSES
Customer Lounge	9	Food Service - Bar/Lounge	613	1	1	PASSES
						PASSES

Project: Office
Title: I-75 Truck Stop Repair Center
Type: Office
(WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

System Report Compliance

Pr0Sy2	System 2	Constant Volume Packaged System	No. of Units 1
--------	----------	---------------------------------	-------------------

Component	Category	Capacity	Design Eff	Eff Criteria	Design IPLV	IPLV Criteria	Compliance
Cooling System	Air Conditioners Air Cooled 65000 to 135000 Btu/h Cooling Capacity	71500	11.50	11.20	12.90	12.90	PASSES
Heating System	Electric Furnace	51195	1.00	1.00			PASSES
Air Handling System -Supply	Air Handler (Supply) - Constant Volume	2400	0.42	0.82			PASSES
Air Distribution System (Sup)	Not in Check list - Compliance Ignored		6.00	6.00			N/A

PASSES

Plant Compliance	
------------------	--

Description	Installed No	Size	Design Eff	Min Eff	Design IPLV	Min IPLV	Category	Comp liance
-------------	-----------------	------	---------------	------------	----------------	-------------	----------	----------------

None

Project: Office
 Title: I-75 Truck Stop Repair Center
 Type: Office
 (WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Water Heater Compliance

Description	Type	Category	Design Eff	Min Eff	Design Loss	Max Loss	Compliance
Water Heater 1	Electric water heater	<= 12 [kW]	0.97	0.97			PASSES
							PASSES

Project: Office
 Title: I-75 Truck Stop Repair Center
 Type: Office
 (WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Piping System Compliance

Category	Pipe Dia [inches]	Is Runout?	Operating Temp [F]	Ins Cond [Btu-in/hr .SF.F]	Ins Thick [in]	Req Ins Thick [in]	Compliance
Heating System (Steam, Steam Condensate, & Hot Water)	0.50	False	110.00	0.28	1.00	0.50	PASSES
							PASSES

Mandatory Requirements (as applicable)

Mandatory requirements compiled by US Department of Energy and Pacific Northwest National Laboratory. Adopted with permission

Topic	Section	Component	Description	Yes	N/A	Exempt
1. To be checked by Designer or Engineer						
Insulation	C303.2	Envelope	Below-grade wall insulation installed per manufacturer's instructions.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Insulation	C303.2	Envelope	Slab edge insulation installed per manufacturer's instructions.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Insulation	C303.2	Envelope	Above-grade wall insulation installed per manufacturer's instructions.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C402.3	Envelope	High-albedo roofs satisfy one of the following: 3-year-aged solar reflectance ≥ 0.55 and thermal emittance ≥ 0.75 or 3-year-aged solar reflectance index ≥ 64.0 .	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Fenestration	C402.4.4	Envelope	U-factor of opaque doors associated with the building thermal envelope meets requirements.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.12.1	Mechanical	HVAC fan systems at design conditions do not exceed allowable fan system motor nameplate hp or fan system bhp.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.12.2	Mechanical	HVAC fan motors not oversized beyond allowable limits.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.3(8) Table	Mechanical	Heat Rejection Equipment: Minimum Efficiency Requirement meet those listed in Table C403.2.3(8)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.7	Mechanical	Exhaust air energy recovery on systems meeting Table C403.2.7(1) and C403.2.7(2).	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.3	Mechanical	Air economizers provided where required, meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off, integrated economizer control, and provide a means to relieve excess outside air during operation.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.3.2	Mechanical	Economizer operation will not increase heating energy use during normal operation.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.3.4, C403.3.4.1, C403.3.4.2, C403.3.1	Mechanical	Water economizers provided where required, meet the requirements for design capacity, maximum pressure drop and integrated economizer control.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.2.1	Mechanical	Three-pipe hydronic systems using a common return for hot and chilled water are not used.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.2.3.1	Mechanical	Hydronic heat pump systems connected to a common water loop meet heat rejection and heat addition requirements.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.3.4	Mechanical	Open-circuit cooling towers having water cooled chiller systems and multiple or variable speed condenser pumps, are designed so that tower cells can run in parallel with larger of flow criteria.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.2	Mechanical	Service water heating equipment meets efficiency requirements.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Wattage	C405.3	Interior Lighting	Exit signs do not exceed 5 watts per face.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. To be checked by Plan Reviewer						
Plan Review	C103.2	Envelope	Plans and/or specifications provide all information with which compliance can be determined for the building envelope and document where exceptions to the standard are claimed.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Plan Review	C103.2	Mechanical	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering st	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Plan Review	C103.2	Mechanical	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the service water heating systems and equipment and document where exceptions to the standard are claimed. Hot water system sized per manufact	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Plan Review	C103.2	Interior Lighting	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the interior lighting and electrical systems and equipment and document where exceptions to the standard are claimed. Information provided shoul	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Plan Review	C103.2	Exterior Lighting	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the exterior lighting and electrical systems and equipment and document where exceptions to the standard are claimed. Information provided shoul	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C402.2.5	Envelope	Slab edge insulation depth/length. Slab insulation extending away from building is covered by pavement or ≥ 10 inches of soil.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C402.2.6	Project	Radiant heating systems panels insulated to $\geq R-3.5$ on face opposite space being heated.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C402.2.6	Mechanical	Thermally ineffective panel surfaces of sensible heating panels have insulation $\geq R-3.5$.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C402.2.6	Envelope	Radiant panels and associated components, designed for heat transfer from the panel surfaces to the occupants or indoor space are insulated with a minimum of R-3.5.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.7	Envelope	Vestibules are installed on all building entrances. Doors have self-closing devices.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.12.3	Mechanical	Fans have efficiency grade (FEG) ≥ 67 . The total efficiency of the fan at the design point of operation $\leq 15\%$ of maximum total efficiency of the fan.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.13	Mechanical	Unenclosed spaces that are heated use only radiant heat.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.4.2	Mechanical	Each zone equipped with setback controls using automatic time clock or programmable control system.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.4.4	Mechanical	Zone isolation devices and controls installed where applicable.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.4.7	Mechanical	Fault detection and diagnostics installed with air-cooled unitary DX units having economizers.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.5	Mechanical	Hot water boilers supplying heat via one- or two-pipe systems include outdoor setback control.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.6.1	Mechanical	Demand control ventilation provided for spaces >500 ft ² and >25 people/1000 ft ² occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow $>3,000$ cfm.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.1.1	Mechanical	Hydronic and multizone HVAC system controls are VAV fans driven by mechanical or electrical variable speed drive per Table C403.4.1.1.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.1.3	Mechanical	Reset static pressure setpoint for DDC controlled VAV boxes reporting to central controller based on the zones requiring the most pressure.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.2	Mechanical	Temperature reset by representative building loads in pumping systems for chiller and boiler systems $>500,000$ Btu/h.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

SYSTEM_SPECIFIC	C403.4.2.3.2.1	Mechanical	Closed-circuit cooling tower within heat pump loop have either automatic bypass valve or lower leakage positive closure dampers. Open-circuit tower within heat pump loop have automatic valve to bypass all heat pump water flow around the tower. Open- or cl	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.2.4	Mechanical	Hydronic systems greater than 500,000 Btu/h designed for variable fluid flow.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.2.5	Mechanical	System turndown requirement met through multiple single-input boilers, one or more modulating boilers, or a combination of single-input and modulating boilers.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.2.6	Mechanical	Boiler input between 1.0 MBtu/h and 5 MBtu/h has 3:1 turndown ratio, boiler input between 5.0 Chilled water plants with multiple chillers have capability to reduce flow automatically through the chiller plant when a chiller is shut down. Boiler plants with multiple boilers have the capability to reduce flow automatically through the boiler plant	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.3, C403.4.3.2	Mechanical	Fan systems with motors ≥ 7.5 hp associated with heat rejection equipment to have capability to operate at 2/3 of full-speed and auto speed controls to control the leaving fluid temperature or condensing temp/pressure of heat rejection device.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.4.5	Mechanical	Multiple zone HVAC systems have supply air temperature reset controls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.4.6	Mechanical	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.2.1	Mechanical	Gas-fired water-heating equipment installed in new buildings: where a singular piece of water-heating equipment $\geq 1,000$ kBtu/h serves the entire building, thermal efficiency ≥ 90 Et. Where multiple pieces of water-heating equipment serve the building wi	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.4	Mechanical	All piping insulated in accordance with section details and Table C403.2.10.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.5, C404.5.1, C404.5.2	Mechanical	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.6.3	Mechanical	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to ≤ 5 minutes after end of heating cycle.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.7	Mechanical	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Wattage	C405.5.1	Exterior Lighting	Exterior lighting power is consistent with what is shown on the approved lighting plans, demonstrating proposed watts are less than or equal to allowed watts.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Plan Review	C405.6	Project	Group R-2 dwelling units have separate electrical meters.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Plan Review	C406	Project	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the additional energy efficiency package options.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C408.2.2.2	Mechanical	HVAC hydronic heating and cooling coils have means to balance and have pressure test connections.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C408.2.2.2	Mechanical	HVAC hydronic heating and cooling coils have means to balance and have pressure test connections.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

3. To be checked by Inspector

Insulation	C303.1	Envelope	Roof insulation installed per manufacturer's instructions. Blown or poured loose-fill insulation is installed only where the roof slope is ≤ 3 in 12.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C303.1	Envelope	Building envelope insulation is labeled with R-value or insulation certificate providing R-value and other relevant data.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Fenestration	C303.1.3	Envelope	Fenestration products rated in accordance with NFRC.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Fenestration	C303.1.3	Envelope	Fenestration products are certified as to performance labels or certificates provided.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C303.2, C402.2.4	Envelope	Floor insulation installed per manufacturer's instructions. Cavity or structural slab insulation installed in permanent contact with underside of decking or structural slabs.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C303.2.1	Envelope	Exterior insulation protected against damage, sunlight, moisture, wind, landscaping and equipment maintenance activities.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C303.2.1	Envelope	Exterior insulation is protected from damage with a protective material. Verification for exposed foundation insulation may need to occur during Foundation Inspection.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C402.1.3	Envelope	Non-swinging opaque doors have R-4.75 insulation.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C402.2.2	Envelope	Skylight curbs are insulated to the level of roofs with insulation above deck or R-5.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Insulation	C402.2.2	Envelope	Insulation intended to meet the roof insulation requirements cannot be installed on top of a suspended ceiling. Mark this requirement compliant if insulation is installed accordingly.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5	Envelope	Building envelope contains a continuous air barrier that has been tested and deemed to limit air leakage ≤ 0.40 cfm/ft ² .	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.1	Envelope	The building envelope contains a continuous air barrier that is sealed in an approved manner and either constructed or tested in an approved manner. Air barrier penetrations are sealed in an approved manner.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.1.1	Envelope	All sources of air leakage in the building thermal envelope are sealed, caulked, gasketed, weather stripped or wrapped with moisture vapor-permeable wrapping material to minimize air leakage.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.1.2.1	Envelope	The building envelope contains a continuous air barrier that is sealed in an approved manner and material permeability ≤ 0.004 cfm/ft ² . Air barrier penetrations are sealed in an approved manner.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.1.2.2	Envelope	The building envelope contains a continuous air barrier that is sealed in an approved manner and average assembly air leakage ≤ 0.04 cfm/ft ² . Air barrier penetrations are sealed in an approved manner.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.2, C402.5.4	Envelope	Factory-built fenestration and doors are labeled as meeting air leakage requirements.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.3	Envelope	Where open combustion air ducts provide combustion air to open combustion fuel burning appliances, the appliances and combustion air opening are located outside the building thermal envelope or enclosed in a room, isolated from inside the thermal envelope.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.5, C403.2.4.3	Envelope	Stair and elevator shaft vents have motorized dampers that automatically close.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.5, C403.2.4.3	Envelope	Outdoor air and exhaust systems have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Check gravity dampers where allowed.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Air Leakage	C402.5.6	Envelope	Weatherseals installed on all loading dock cargo doors.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Air Leakage	C402.5.8	Envelope	Recessed luminaires in thermal envelope to limit infiltration and be IC rated and labeled. Seal between interior finish and luminaire housing.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.1	Mechanical	HVAC systems and equipment design loads calculated in accordance with ANSI/ASHRAE/ACCA Standard 183 or by an approved equivalent computational procedure	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.10	Mechanical	HVAC piping insulation thickness. Where piping is installed in or under a slab, verification may need to occur during Foundation Inspection.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.3	Mechanical	HVAC equipment efficiency verified.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.3	Mechanical	PTAC and PTHP with sleeves 16 in. by 42 in. labeled for replacement only as per Footnote b to Table C403.2.3(3).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.4.1	Mechanical	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.4.1.1	Mechanical	Heat pump controls prevent supplemental electric resistance heat from coming on when not needed.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.4.1.2	Mechanical	Thermostatic controls have a 5 °F deadband.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.4.1.2	Mechanical	Thermostatic controls have a 5 °F deadband.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.4.1.3	Mechanical	Temperature controls have setpoint overlap restrictions.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.4.2.1, C403.2.4.2.2	Mechanical	Automatic Controls: Setback to 55°F (heat) and 85°F (cool); 7-day clock, 2-hour occupant override, 10-hour backup	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.4.2.3	Mechanical	Systems include optimum start controls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.4.5, C403.2.4.6	Mechanical	Snow/ice melting system sensors for future connection to controls. Freeze protection systems have automatic controls installed.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.6.2	Mechanical	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C403.2.9	Mechanical	HVAC ducts and plenums insulated. Where ducts or plenums are installed in or under a slab, verification may need to occur during Foundation Inspection.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.2.9.1.3	Mechanical	Ductwork operating >3 in. water column requires air leakage testing.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.1.2	Mechanical	VAV fans have static pressure sensors located so controller setpoint ≤1.2 w.c..	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.2.2	Mechanical	Two-pipe hydronic systems using a common distribution system have controls to allow a deadband ≥15°F, allow operation in one mode for at least 4 hrs before changeover, and have reset controls to limit heating and cooling supply temperature to ≤30 °F.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.2.3.3	Mechanical	Two-position automatic valve interlocked to shut off water flow when hydronic heat pump with pumping system >10 hp is off.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.4.5, C403.4.4.5.1-4	Mechanical	Zone controls can limit simultaneous heating and cooling and sequence heating and cooling to each zone.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.5	Mechanical	Condenser heat recovery system that can heat water to 85°F or provide 60% of peak heat rejection is installed for preheating of service hot water.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C403.4.6	Mechanical	Hot gas bypass limited to: ≤240 kBtu/h - 50% capacity, >240 kBtu/h - 25% capacity	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.3	Mechanical	Heat traps installed on non-circulating storage water tanks.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

SYSTEM_SPECIFIC	C404.3	Mechanical	Heat traps installed on supply and discharge piping of non-circulating systems.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.3	Mechanical	Heat traps installed on supply and discharge piping of non-circulating systems.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.6.1	Mechanical	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank. System return pipe is a dedicated return pipe or a cold water supply pipe.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.6.1, C404.6.2	Mechanical	Automatic time switches installed to automatically switch off the recirculating hot-water system or heat trace.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.9.1	Mechanical	Pool heaters are equipped with on/off switch and no continuously burning pilot light.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.9.2	Mechanical	Time switches are installed on all pool heaters and pumps.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.9.2	Mechanical	Time switches are installed on all pool heaters and pumps.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SYSTEM_SPECIFIC	C404.9.3	Mechanical	Vapor retardant pool covers are provided for heated pools and permanently installed spas.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.1	Interior Lighting	Lighting controls installed to uniformly reduce the lighting load by at least 50%.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.1	Interior Lighting	Occupancy sensors installed in required spaces.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.1, C405.2.2.3	Interior Lighting	Independent lighting controls installed per approved lighting plans and all manual controls readily accessible and visible to occupants.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.2.1	Interior Lighting	Automatic controls to shut off all building lighting installed in all buildings.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.3	Interior Lighting	Daylight zones provided with individual controls that control the lights independent of general area lighting.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.3, C405.2.3.1, C405.2.3.2	Interior Lighting	Primary sidelighted areas are equipped with required lighting controls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.3, C405.2.3.1, C405.2.3.3	Interior Lighting	Enclosed spaces with daylight area under skylights and rooftop monitors are equipped with required lighting controls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.4	Interior Lighting	Separate lighting control devices for specific uses installed per approved lighting plans.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Wattage	C405.2.4	Interior Lighting	Additional interior lighting power allowed for special functions per the approved lighting plans and is automatically controlled and separated from general lighting.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Controls	C405.2.5	Exterior Lighting	Automatic lighting controls for exterior lighting installed. Controls will be daylight controlled, set based on business operation time-of-day, or reduce connected lighting > 30%.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Wattage	C405.4.1	Interior Lighting	Interior installed lamp and fixture lighting power is consistent with what is shown on the approved lighting plans, demonstrating proposed watts are less than or equal to allowed watts.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Mandatory Additional	C406.4	Project	Enhanced digital lighting controls efficiency package: Interior lighting has following enhanced lighting controls in accordance with Section C405.2.2: Luminaires capable of continuous dimming and being addressed individually, <= 8 luminaires controlled in	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Mandatory Additional	C406.6	Project	Dedicate outdoor air system efficiency package: Buildings with hydronic and/or multiple-zone HVAC systems are equipped with an independent ventilation system designed to provide >= 100-percent outdoor air to each individual occupied space, as specified by	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Mandatory Additional	C406.7, C406.7.1	Project	Enhanced Service Water Heat System efficiency package. One of the following SWH system enhancements must satisfy 60 percent of hot water requirements, or 100 percent if the building otherwise complies with heat recovery per Section C403.4.5: Waste heat re	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C408.2.2.1	Mechanical	Air outlets and zone terminal devices have means for air balancing.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC	C408.2.2.1	Mechanical	Air outlets and zone terminal devices have means for air balancing.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Testing	C408.2.3.2	Mechanical	HVAC control systems have been tested to ensure proper operation, calibration and adjustment of controls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. To be checked by Inspector at Project Completion and Prior to Issuance of Certificate of Occupancy						
Post Construction	C303.3, C408.2.5.2	Interior Lighting	Furnished O&M instructions for systems and equipment to the building owner or designated representative.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C303.3, C408.2.5.3	Mechanical	Furnished O&M manuals for HVAC systems within 90 days of system acceptance.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Fenestration	C402.4.2.2	Envelope	Skylights in office, storage, automotive service, manufacturing, non-refrigerated warehouse, retail store, and distribution/sorting area have a measured haze value > 90 percent unless designed to exclude direct sunlight.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.2.1	Mechanical	Commissioning plan developed by registered design professional or approved agency.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.2.3.1	Mechanical	HVAC equipment has been tested to ensure proper operation.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.2.3.3	Mechanical	Economizers have been tested to ensure proper operation.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.2.4	Mechanical	Preliminary commissioning report completed and certified by registered design professional or approved agency.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.2.5.1	Mechanical	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.2.5.1	Interior Lighting	Furnished as-built drawings for electric power systems within 90 days of system acceptance.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.2.5.3	Mechanical	An air and/or hydronic system balancing report is provided for HVAC systems.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.2.5.4	Mechanical	Final commissioning report due to building owner within 90 days of receipt of certificate of occupancy.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Post Construction	C408.3	Interior Lighting	Lighting systems have been tested to ensure proper calibration, adjustment, programming, and operation.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

EnergyGauge Summit® v6.10
INPUT DATA REPORT

Project Information

Project Name: Office

Project Title: I-75 Truck Stop Repair Center

Address: 14197 S US 441

State: FL

Zip: 32024

Owner: I-75 Truck Stop Repair Center

Orientation: 0 Deg Clockwise. Walls & Windows will
be rotated accordingly

Building Type: Office

Building Classification: New Finished building

No.of Stories: 1

GrossArea: 2373 SF

Zones

No	Acronym	Description	Type	Area [sf]	Multiplier	Total Area [sf]	
1	Office	Office	CONDITIONED	2373.0	1	2373.0	<input type="checkbox"/>

Spaces

No	Acronym	Description	Type	Depth [ft]	Width [ft]	Height [ft]	Multi plier	Total Area [sf]	Total Volume [cf]
----	---------	-------------	------	---------------	---------------	----------------	----------------	--------------------	----------------------

In Zone: Office										
1	Handicap RR 1	Handicap RR 1	Toilet and Washroom	1.00	42.00	10.00	1	42.0	420.0	<input type="checkbox"/>
2	Handicap RR 2	Handicap RR 2	Toilet and Washroom	1.00	42.00	10.00	1	42.0	420.0	<input type="checkbox"/>
3	Handicap RR 3	Handicap RR 3	Toilet and Washroom	1.00	42.00	10.00	1	42.0	420.0	<input type="checkbox"/>
4	Parts Manager	Parts Manager	Office - Enclosed	1.00	75.00	10.00	1	75.0	750.0	<input type="checkbox"/>
5	Locker Room	Locker Room	Locker Room	1.00	82.00	10.00	1	82.0	820.0	<input type="checkbox"/>
6	Parts Warehouse	Parts Warehouse	Storage & Warehouse - Bulky Active Storage	1.00	1331.00	20.00	1	1331.0	26620.0	<input type="checkbox"/>
7	Reception/Bill	Reception/Bill Pay	Terminal - Ticket Counter	1.00	42.00	10.00	1	42.0	420.0	<input type="checkbox"/>
8	Service Manag	Service Manager	Office - Enclosed	1.00	104.00	10.00	1	104.0	1040.0	<input type="checkbox"/>
9	Customer Lour	Customer Lounge	Food Service - Bar/Lounge	1.00	613.00	10.00	1	613.0	6130.0	<input type="checkbox"/>

Lighting									
No	Type	Category	No. of Luminaires	Watts per Luminaire	Power [W]	Control Type	No. of Ctrl pts		
In Zone: Office									
In Space:	Handicap RR 1								
1	LED	General Lighting	1	40	40	Occupancy sensor without Daylighting	1		<input type="checkbox"/>
In Space:	Handicap RR 2								
1	LED	General Lighting	1	40	40	Occupancy sensor without Daylighting	1		<input type="checkbox"/>
In Space:	Handicap RR 3								
1	LED	General Lighting	1	40	40	Occupancy sensor without Daylighting	1		<input type="checkbox"/>
In Space:	Parts Manager								
1	LED	General Lighting	1	40	40	Occupancy sensor without Daylighting	1		<input type="checkbox"/>
In Space:	Locker Room								
1	LED	General Lighting	1	40	40	Occupancy sensor without Daylighting	1		<input type="checkbox"/>
In Space:	Parts Warehouse								
1	LED	General Lighting	12	40	480	Occupancy sensor without Daylighting	1		<input type="checkbox"/>

In Space:	Reception/Bill pay									
1	LED	General Lighting	1	40	40	Occupancy sensor without Daylighting	1	<input type="checkbox"/>		
In Space:	Service Manager									
1	LED	General Lighting	2	40	80	Occupancy sensor without Daylighting	1	<input type="checkbox"/>		
In Space:	Customer Lounge									
1	LED	General Lighting	12	40	480	Occupancy sensor without Daylighting	1	<input type="checkbox"/>		

Walls (Walls will be rotated clockwise by building rotation value)

No	Description	Type	Width [ft]	H (Effect) [ft]	Multiplier	Area [sf]	Orientation	Conductance [Btu/hr. sf. F]	Heat Capacity [Btu/sf.F]	Dens. [lb/cf]	R-Value [h.s.f./Btu]	
In Zone: Office												
1	Pr0Zo1Wal	Metal siding/2x4@24"+R1 1Batt/5/8"Gyp	25.33	10.00	1	253.3	North	0.0920	1.072	19.38	10.9	<input type="checkbox"/>
2	Pr0Zo1Wal	Metal siding/2x4@24"+R1 1Batt/5/8"Gyp	93.67	10.00	1	936.7	North	0.0920	1.072	19.38	10.9	<input type="checkbox"/>
3	Pr0Zo1Wal	Metal siding/2x4@24"+R1 1Batt/5/8"Gyp	93.67	10.00	1	936.7	East	0.0920	1.072	19.38	10.9	<input type="checkbox"/>
4	South	Metal siding/2x4@24"+R1 1Batt/5/8"Gyp	25.33	20.00	1	506.6	South	0.0920	1.072	19.38	10.9	<input type="checkbox"/>

Windows (Windows will be rotated clockwise by building rotation value)

No	Description	Orientation	Shaded	U [Btu/hr sf F]	SHGC	Vis.Tra	W [ft]	H (Effect) [ft]	Multiplier	Total Area [sf]	
In Zone: Office											
In Wall: North											
1	Pr0Zo1WalWi1	North	No	0.6000	0.59	0.64	20.00	9.00	1	180.0	<input type="checkbox"/>

Doors												
No	Description	Type	Shaded?	Width [ft]	H (Effec [ft]	Multi plier	Area [sf]	Cond. [Btu/hr. sf. F]	Dens. [lb/cf]	Heat Cap. [Btu/sf. F]	R-Value [h.sf.F/Btu]	
In Zone: Office												
In Wall: West												
1	Pr0Zo1Wa2Dr1	Solid core flush (2.25)	No	3.00	6.67	2	20.0	0.3504	0.00	0.00	2.85	<input type="checkbox"/>
In Wall: East												
1	Pr0Zo1Wa2Dr1	Solid core flush (2.25)	No	3.00	6.67	2	20.0	0.3504	0.00	0.00	2.85	<input type="checkbox"/>
In Wall: South												
1	Pr0Zo1Wa4Dr1	Solid core flush (2.25)	No	12.00	16.00	1	192.0	0.3504	0.00	0.00	2.85	<input type="checkbox"/>
2	Pr0Zo1Wa4Dr2	Solid core flush (2.25)	No	3.00	6.67	1	20.0	0.3504	0.00	0.00	2.85	<input type="checkbox"/>

Roofs												
No	Description	Type	Width [ft]	H (Effec [ft]	Multi plier	Area [sf]	Tilt [deg]	Cond. [Btu/hr. Sf. F]	Heat Cap [Btu/sf. F]	Dens. [lb/cf]	R-Value [h.sf.F/Btu]	
In Zone: Office												
1	Pr0Zo1Rf1	Mtl Bldg Roof/R-19 Batt	25.33	93.67	1	2372.7	0.00	0.0492	1.34	9.49	20.3	<input type="checkbox"/>

Skylights											
No	Description	Type	U [Btu/hr sf F]	SHGC	Vis.Trans	W [ft]	H (Effec [ft]	Multiplier	Area [Sf]	Total Area [Sf]	
In Zone: In Roof:											

Floors										
No	Description	Type	Width [ft]	H (Effec [ft]	Multi plier	Area [sf]	Cond. [Btu/hr. sf. F]	Heat Cap. [Btu/sf. F]	Dens. [lb/cf]	R-Value [h.s.f.F/Btu]
In Zone: Office										
1	Pr0Zo1FI1	1 ft. soil, concrete floor, carpet and rubber pad	25.33	93.67	1	2372.7	0.2681	34.00	113.33	3.73

Systems										
Pr0Sy2	System 2		Constant Volume Packaged System						No. Of Units	1
Component	Category		Capacity		Efficiency		IPLV			
1	Cooling System		71500.00		11.50		12.90			
2	Heating System		51195.00		1.00					
3	Air Handling System -Supply		2400.00		0.42					
4	Air Distribution System (Sup)				6.00					

Plant					
Equipment	Category	Size	Inst.No	Eff.	IPLV

Water Heaters										
W-Heater Description		CapacityCap.Unit	I/P Rt.		Efficiency		Loss			
1	Electric water heater	[Gal]	3 [kW]		0.9700 [Ef]		[Btu/h]			

Ext-Lighting						
Description	Category	No. of Luminaires	Watts per Luminaire	Area/Len/No. of units [sf/ft/No]	Control Type	Wattage [W]
<input type="checkbox"/>						

Piping						
No	Type	Operating Temperature [F]	Insulation Conductivity [Btu-in/h.sf.F]	Nominal pipe Diameter [in]	Insulation Thickness [in]	Is Runout?
1	Heating System (Steam, Steam Condensate, & Hot Water)	110.00	0.28	0.50	1.00	No <input type="checkbox"/>

Fenestration Used					
Name	Glass Type	No. of Panels	Glass Conductance [Btu/h.sf.F]	SHGC	VLT
ASHULDbIClrW d-Vy-Fg frm	User Defined	2	0.6000	0.5900	0.6400 <input type="checkbox"/>

Materials Used								
Mat No	Acronym	Description	Only R-Value Used	RValue [h.sf.F/Btu]	Thickness [ft]	Conductivity [Btu/h.ft.F]	Density [lb/cf]	SpecificHeat [Btu/lb.F]
187	Mat187	GYP OR PLAS BOARD, 1/2IN	No	0.4533	0.0417	0.0920	50.00	0.2000 <input type="checkbox"/>
178	Mat178	CARPET W/RUBBER PAD	Yes	1.2300				<input type="checkbox"/>
265	Mat265	Soil, 1 ft	No	2.0000	1.0000	0.5000	100.00	0.2000 <input type="checkbox"/>

48	Matl48	6 in. Heavyweight concrete	No	0.5000	0.5000	1.0000	140.00	0.2000	<input type="checkbox"/>
23	Matl23	6 in. Insulation	No	20.0000	0.5000	0.0250	5.70	0.2000	<input type="checkbox"/>
4	Matl4	Steel siding	No	0.0002	0.0050	26.0000	480.00	0.1000	<input type="checkbox"/>
271	Matl271	2x4@24" oc + R11 Batt	No	10.4179	0.2917	0.0280	7.11	0.2000	<input type="checkbox"/>
279	Matl279	Solid core flush (2.25")	Yes	2.8537					<input type="checkbox"/>
94	Matl94	BUILT-UP ROOFING, 3/8IN	No	0.3366	0.0313	0.0930	70.00	0.3500	<input type="checkbox"/>

Constructs Used

No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1055	Metal siding/2x4@24"+R11Batt/5/8"Gyp	No	No	0.09	1.07	19.38	10.9	<input type="checkbox"/>
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	4	Steel siding	0.0050	0.000			<input type="checkbox"/>
	2	271	2x4@24" oc + R11 Batt	0.2917	0.000			<input type="checkbox"/>
	3	187	GYP OR PLAS BOARD, 1/2IN	0.0417	0.000			<input type="checkbox"/>
No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1056	Mtl Bldg Roof/R-19 Batt	No	No	0.05	1.34	9.49	20.3	<input type="checkbox"/>
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	94	BUILT-UP ROOFING, 3/8IN	0.0313	0.000			<input type="checkbox"/>
	2	23	6 in. Insulation	0.5000	0.000			<input type="checkbox"/>

No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1057	1 ft. soil, concrete floor, carpet and rubber pad	No	No	0.27	34.00	113.33	3.7	<input type="checkbox"/>
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	265	Soil, 1 ft	1.0000	0.000			<input type="checkbox"/>
	2	48	6 in. Heavyweight concrete	0.5000	0.000			<input type="checkbox"/>
	3	178	CARPET W/RUBBER PAD		0.000			<input type="checkbox"/>
No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1058	Solid core flush (2.25)	No	Yes	0.35			2.9	<input type="checkbox"/>
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	279	Solid core flush (2.25")		0.000			<input type="checkbox"/>

I-75 TRUCK STOP - REPAIR CENTER

Location	ELLISVILLE FL 32024
Building owner	I-75 TRUCK STOP
Program user	Ron Miller
Company	Go Green Engineering
Comments	

By	Go Green Engineering LLC
Dataset name	C:\PROJECTS\PROJECTS\GREEN ENGINEERING SOLUTIONS\2019\TRUCK STOP\TRUCK STOP.TRC

Calculation time	06:30 AM on 11/26/2019
TRACE® 700 version	6.3.4

Location	Gainesville, Florida
Latitude	29.0 deg
Longitude	82.0 deg
Time Zone	5
Elevation	155 ft
Barometric pressure	29.7 in. Hg
Air density	0.0756 lb/cu ft
Air specific heat	0.2444 Btu/lb·°F
Density-specific heat product	1.1087 Btu/h·cfm·°F
Latent heat factor	4,880.3 Btu·min/h·cu ft
Enthalpy factor	4.5356 lb·min/hr·cu ft
Summer design dry bulb	96.2 °F
Summer design wet bulb	77.2 °F
Winter design dry bulb	31.0 °F
Summer clearness number	0.95
Winter clearness number	0.95
Summer ground reflectance	0.20
Winter ground reflectance	0.20
Carbon Dioxide Level	400 ppm
Design simulation period	January - December
Cooling load methodology	TETD-TA1
Heating load methodology	UATD



System Checksums

By Go Green Engineering LLC

AHU-1

Constant Volume

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16					Mo/Hr: 6 / 15					Mo/Hr: Heating Design							
Outside Air: OADBWB/HR: 96 / 77 / 113					OADB: 94					OADB: 31							
Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total		Space Sensible	Percent Of Total				Space Peak	Coil Peak	Percent Of Total			Cooling	Heating	
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)				Space Sens	Tot Sens	(%)					
Envelope Loads					Envelope Loads					Envelope Loads							
Skyline Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	SADB	54.9	76.2
Skyline Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Ra Plenum	79.9	68.2
Roof Cond	0	9,662	9,662	14	0	0	0	0	0	0	-3,963	15.80	0	0	Return	79.9	68.2
Glass Solar	5,863	0	5,863	8	6,876	15	8	6,876	15	0	0	0.00	0	0	Ret/OA	81.1	65.1
Glass/Door Cond	5,225	0	5,225	7	4,768	10	7	4,768	10	0	-9,556	38.09	0	0	Fn MtrTD	0.0	0.0
Wall Cond	2,617	876	3,493	5	2,577	6	5	2,577	6	0	-4,351	17.34	0	0	Fn BldTD	0.0	0.0
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Fn Frict	0.0	0.0
Floor	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Sub Total ==>	13,705	10,538	24,243	34	14,221	31	31	14,221	31	-12,714	-17,871	71.22	71.22	71.22			
Internal Loads					Internal Loads					Internal Loads							
Lights	12,434	3,109	15,543	22	12,434	27	27	12,434	27	0	0	0.00	0	0			
People	11,500	0	11,500	16	5,750	13	13	5,750	13	0	0	0.00	0	0			
Misc	9,672	0	9,672	14	9,672	21	21	9,672	21	0	0	0.00	0	0			
Sub Total ==>	33,607	3,109	36,715	52	27,857	61	61	27,857	61	0	0	0.00	0	0			
Ceiling Load	3,507	-3,507	0	0	3,493	8	8	3,493	8	-1,325	0	0.00	0	0			
Ventilation Load	0	0	9,517	14	0	0	0	0	0	0	-7,221	28.78	28.78	28.78			
Adj Air Trans Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Dehumid. Ov Sizing	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Ov/Undr Sizing	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Exhaust Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Sup. Fan Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Ret. Fan Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Duct Heat Pkup	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Underflr Sup Ht Pkup	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Supply Air Leakage	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Grand Total ==>	50,819	10,139	70,475	100.00	45,571	100.00	100.00	45,571	100.00	-14,039	-25,092	100.00	100.00	100.00			

COOLING COIL SELECTION										AREAS			HEATING COIL SELECTION				
Total Capacity	ion	MBh	Sens Cap.	Coil Airflow	Enter DB/WH/HR	Leave DB/WH/HR				Gross Total	Glass		Capacity/Coil	Airflow	Ent	Lvg	
			MBh	cfm	°F	°F	gr/lb				ft²	(%)	MBh	cfm	°F	°F	
Main Clg	5.9	70.5	59.0	2,048	81.1	64.0	62.5	54.9	52.4	2,277	0	0	Main Htg	-25.1	2,048	65.1	76.2
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0	0	0	Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0	0	0	Preheat	0.0	0	0.0	0.0
Total	5.9	70.5								2,277	0	0	Humidif	0.0	0	0.0	0.0
										2,276	510	22	Opt Vent	0.0	0	0.0	0.0
										232	0	0	Total	-25.1			

COOLING COIL SELECTION										AREAS			HEATING COIL SELECTION				
Total Capacity	ion	MBh	Sens Cap.	Coil Airflow	Enter DB/WH/HR	Leave DB/WH/HR				Gross Total	Glass		Capacity/Coil	Airflow	Ent	Lvg	
			MBh	cfm	°F	°F	gr/lb				ft²	(%)	MBh	cfm	°F	°F	
Main Clg	5.9	70.5	59.0	2,048	81.1	64.0	62.5	54.9	52.4	2,277	0	0	Main Htg	-25.1	2,048	65.1	76.2
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0	0	0	Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0	0	0	Preheat	0.0	0	0.0	0.0
Total	5.9	70.5								2,277	0	0	Humidif	0.0	0	0.0	0.0
										2,276	510	22	Opt Vent	0.0	0	0.0	0.0
										232	0	0	Total	-25.1			

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 1 of 1

Room Checksums

By Go Green Engineering LLC

Handicap Restroom

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16 Outside Air: OADBWB/HR: 96 / 77 / 113					Mo/Hr: 8 / 16 OADB: 96					Mo/Hr: Heating Design OADB: 31							
Space Sens. + Lat. Btu/h	Plenum Sens. + Lat. Btu/h	Net Total Btu/h	Percent Of Total (%)		Space Sensible Btu/h	Percent Of Total (%)				Space Peak Space Sens Btu/h	Coil Peak Tot Sens Btu/h	Percent Of Total (%)			Cooling	Heating	
Envelope Loads					Envelope Loads					Envelope Loads					AIRFLOWS		
SkyLite Solar	0	0	0	0	0	0	0	SkyLite Solar	0	0	0	0.00			Cooling	Heating	
SkyLite Cond	0	0	0	0	0	0	0	SkyLite Cond	0	0	0	0.00			20	20	
Roof Cond	0	178	178	28	0	0	0	Roof Cond	0	-73	24.44				20	20	
Glass Solar	0	0	0	0	0	0	0	Glass Solar	0	0	0	0.00			20	20	
Glass/Door Cond	83	0	83	13	83	19		Glass/Door Cond	-154	-154	51.55				20	20	
Wall Cond	65	22	87	14	65	15		Wall Cond	-80	-111	37.04				0	0	
Partition/Door	0	0	0	0	0	0		Partition/Door	0	0	0	0.00			0	0	
Floor	0	0	0	0	0.00	0		Floor	0	0	0	0.00			0	0	
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		Adjacent Floor	0.00	0.00	0.00	0.00			0	0	
Infiltration	0	0	0	0	0	0		Infiltration	0	0	0	0.00			0	0	
Sub Total ==>	148	200	348	55	148	33		Sub Total ==>	-234	-338	113.03				0	0	
Internal Loads					Internal Loads					Internal Loads					ENGINEERING CKS		
Lights	229	57	287	45	229	52		Lights	0	0	0	0.00			Cooling	Heating	
People	0	0	0	0	0	0		People	0	0	0	0.00			% OA	0.0	0.0
Misc	0	0	0	0	0	0		Misc	0	0	0	0.00			cfm/ft²	0.47	0.47
Sub Total ==>	229	57	287	45	229	52		Sub Total ==>	0	0	0	0.00			cfm/ton	376.71	
Ceiling Load	65	-65	0	0	65	15		Ceiling Load	-24	0	0	0.00			ft³/ton	793.60	
Ventilation Load	0	0	0	0	0	0		Ventilation Load	0	0	0	0.00			Btu/hr-ft²	15.12	-7.12
Adj Air Trans Heat	0	0	0	0	0	0		Adj Air Trans Heat	0	0	0	0			No. People	0.0	0.0/1000 ft²
Dehumid. Ov Sizing	0	0	0	0	0	0		Ov/Undr Sizing	0	0	0	0.00					
Ov/Undr Sizing	0	0	0	0	0	0		Exhaust Heat	0	0	0	0.00					
Exhaust Heat	0	0	0	0	0	0		OA Preheat Diff.	0	0	0	0.00					
Sup. Fan Heat	0	0	0	0	0	0		RA Preheat Diff.	0	0	0	0.00					
Ret. Fan Heat	0	0	0	0	0	0		Additional Reheat	0	0	0	0.00					
Duct Heat Pkup	0	0	0	0	0	0		System Plenum Heat	39	-13.03							
Underflr Sup Ht Pkup	0	0	0	0	0	0		Underflr Sup Ht Pkup	0	0	0	0.00					
Supply Air Leakage	0	0	0	0	0	0		Supply Air Leakage	0	0	0	0.00					
Grand Total ==>	442	193	635	100.00	442	100.00		Grand Total ==>	-259	-299	100.00						

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 1 of 9

Room Checksums

By Go Green Engineering LLC

Handi-Cap Restroom

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time:		Mo/Hr: 6 / 16			Mo/Hr: 6 / 17		Mo/Hr: Heating Design						Cooling			Heating	
Outside Air:		OADBWB/HR: 94 / 75 / 103			OADB: 92		OADB: 31						SADB			Ra Plenum	
													Return			Ret/OA	
													Fn MtrTD			Fn BldTD	
													Fn Frict				

Room Checksums

By Go Green Engineering LLC

Handicap RR

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 6 / 16 Outside Air: OADBWB/HR: 94 / 75 / 103					Mo/Hr: 6 / 17 OADB: 92					Mo/Hr: Heating Design OADB: 31							
Space Sens. + Lat. Btu/h	Plenum Sens. + Lat. Btu/h	Net Total Btu/h	Percent Of Total (%)		Space Sensible Btu/h	Percent Of Total (%)				Space Peak Space Sens Btu/h	Coil Peak Tot Sens Btu/h	Percent Of Total (%)			SADB	Cooling	Heating
Envelope Loads								Envelope Loads							Ra Plenum	55.0	77.7
Skyllite Solar	0	0	0	0	0	0	0	Skyllite Solar	0	0	0	0.00			Return	79.9	68.2
Skyllite Cond	0	0	0	0	0	0	0	Skyllite Cond	0	0	0	0.00			Ret/OA	79.9	68.2
Roof Cond	0	180	180	30	0	0	0	Roof Cond	0	-73	38.26				Fn MtrTD	0.0	0.0
Glass Solar	0	0	0	0	0	0	0	Glass Solar	0	0	0.00				Fn BldTD	0.0	0.0
Glass/Door Cond	0	0	0	0	0	0	0	Glass/Door Cond	0	0	0.00				Fn Frict	0.0	0.0
Wall Cond	104	22	126	21	109	27		Wall Cond	-130	-161	84.13						
Partition/Door	0	0	0	0	0	0		Partition/Door	0	0	0.00						
Floor	0	0	0	0	0.00	0		Floor	0	0	0.00						
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		Adjacent Floor	0.00	0.00	0.00						
Infiltration	0	0	0	0	0	0		Infiltration	0	0	0.00						
Sub Total ==>	104	202	306	52	109	27		Sub Total ==>	-130	-234	122.39						
Internal Loads								Internal Loads									
Lights	229	57	287	48	229	57		Lights	0	0	0.00						
People	0	0	0	0	0	0		People	0	0	0.00						
Misc	0	0	0	0	0	0		Misc	0	0	0.00						
Sub Total ==>	229	57	287	48	229	57		Sub Total ==>	0	0	0.00						
Ceiling Load	65	-65	0	0	63	16		Ceiling Load	-24	0	0.00						
Ventilation Load	0	0	0	0	0	0		Ventilation Load	0	0	0.00						
Adj Air Trans Heat	0	0	0	0	0	0		Adj Air Trans Heat	0	0	0						
Dehumid. Ov Sizing	0	0	0	0	0	0		Ov/Undr Sizing	0	0	0.00						
Ov/Undr Sizing	0	0	0	0	0	0		Exhaust Heat	0	0	0.00						
Exhaust Heat	0	0	0	0	0	0		OA Preheat Diff.	0	0	0.00						
Sup. Fan Heat	0	0	0	0	0	0		RA Preheat Diff.	0	0	0.00						
Ret. Fan Heat	0	0	0	0	0	0		Additional Reheat	0	0	0.00						
Duct Heat PkUp	0	0	0	0	0	0		System Plenum Heat	43	-22.39							
Underflr Sup Ht PkUp	0	0	0	0	0	0		Underflr Sup Ht PkUp	0	0	0.00						
Supply Air Leakage	0	0	0	0	0	0		Supply Air Leakage	0	0	0.00						
Grand Total ==>	399	194	593	100.00	401	100.00		Grand Total ==>	-154	-191	100.00						

COOLING COIL SELECTION										AREAS			HEATING COIL SELECTION				
Total Capacity ton	Capacity MBh	Sens Cap. MBh	Coil Airflow cfm	Enter DB/WB/HR °F °F gr/lb	Leave DB/WB/HR °F °F gr/lb					Gross Total	Glass ft² (%)		Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F	
Main Clg	0.1	0.6	0.6	18	79.9	58.8	40.8	55.0	46.3	33.1			Main Htg	-0.2	18	68.2	77.7
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0			Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0			Preheat	0.0	0	0.0	0.0
Total	0.1	0.6											Humidif	0.0	0	0.0	0.0
													Opt Vent	0.0	0	0.0	0.0
													Total	-0.2			

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 3 of 9

Room Checksums

By Go Green Engineering LLC

Lockeroom

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 6 / 16					Mo/Hr: 6 / 17					Mo/Hr: Heating Design							
Outside Air: OADB/WB/HR: 94 / 75 / 103					OADB: 92					OADB: 31							
Space Sens. + Lat. Btu/h	Plenum Sens. + Lat. Btu/h	Net Total Btu/h	Percent Of Total (%)		Space Sensible Btu/h	Percent Of Total (%)				Space Peak Btu/h	Coil Peak Tot Sens Btu/h	Percent Of Total (%)			SADB	Cooling	Heating
Envelope Loads					Envelope Loads					Envelope Loads							
Skylite Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00	Ra Plenum	55.0	75.9
Skylite Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00	Return	79.9	68.2
Roof Cond	0	352	352	33	0	0	0	0	0	0	-143	52.44	0	0.00	Rot/OA	79.9	68.2
Glass Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00	Fn MtrTD	0.0	0.0
Glass/Door Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00	Fn BldTD	0.0	0.0
Wall Cond	128	27	156	15	134	19	0	0	0	-160	-198	72.70	0	0.00	Fn Frict	0.0	0.0
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Floor	0	0	0	0	0.00	0	0	0	0	0	0	0.00	0	0.00			
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Sub Total ==>	128	379	507	48	134	19				-160	-341	125.14					
Internal Loads					Internal Loads					Internal Loads							
Lights	448	112	560	52	448	64	0	0	0	0	0	0.00	0	0.00			
People	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Misc	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Sub Total ==>	448	112	560	52	448	64				0	0	0.00					
Ceiling Load	127	-127	0	0	122	17	0	0	0	-48	0	0.00	0	0.00			
Ventilation Load	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Adj Air Trans Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Dehumid. Ov Sizing	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Ov/Undr Sizing	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Exhaust Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Sup. Fan Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Ret. Fan Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Duct Heat Pkup	0	0	0	0	0	0	0	0	0	0	68	-25.14	0	0.00			
Underflr Sup Ht Pkup	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Supply Air Leakage	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Grand Total ==>	703	364	1,067	100.00	704	100.00				-208	-272	100.00					

AIRFLOWS		
	Cooling	Heating
Diffuser	32	32
Terminal	32	32
Main Fan	32	32
Sec Fan	0	0
Nom Vent	0	0
AHU Vent	0	0
Infil	0	0
MinStop/Rh	0	0
Return	32	32
Exhaust	0	0
Rm Exh	0	0
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	0.0	0.0
cfm/ft²	0.39	0.39
cfm/ton	357.06	
ft³/ton	922.32	
Btu/hr-ft²	13.01	-3.32
No. People	0.0	0.0/1000 ft²

COOLING COIL SELECTION										AREAS			HEATING COIL SELECTION				
Total Capacity ton	MBh	Sens Cap. MBh	Coil Airflow cfm	Enter DB/°F	WB/°F	HR gr/lb	Leave DB/°F	WB/°F	HR gr/lb	Gross Total	Glass ft²	(%)	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F	
Main Clg	0.1	1.1	1.1	32	79.9	58.8	40.8	55.0	46.0	31.9	Floor	82	Main Htg	-0.3	32	68.2	75.9
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Part	0	Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Int Door	0	Preheat	0.0	0	0.0	0.0
											ExFlr	0					
Total	0.1	1.1									Roof	82	Humidif	0.0	0	0.0	0.0
											Wall	80	Opt Vent	0.0	0	0.0	0.0
											Ext Door	0	Total	-0.3			

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 4 of 9

Room Checksums

By Go Green Engineering LLC

Parts Manager

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16					Mo/Hr: 6 / 17					Mo/Hr: Heating Design							
Outside Air: OADB/WB/HR: 96 / 77 / 113					OADB: 92					OADB: 31							
Space Sens. + Lat. Btu/h	Plenum Sens. + Lat. Btu/h	Net Total Btu/h	Percent Of Total (%)		Space Sensible Btu/h	Percent Of Total (%)				Space Peak Space Sens Btu/h	Coil Peak Tot Sens Btu/h	Percent Of Total (%)			SADB	Cooling	Heating
Envelope Loads					Envelope Loads					Envelope Loads					Ra Plenum	53.3	75.6
Skyline Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Return	79.9	68.2
Skyline Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Ret/OA	83.9	58.6
Roof Cond	0	318	318	15	0	0	0	0	0	0	-131	17.77	0	0	Fn MtrTD	0.0	0.0
Glass Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Fn BldTD	0.0	0.0
Glass/Door Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Fn Frict	0.0	0.0
Wall Cond	162	34	196	9	167	18	0	0	0	-200	-247	33.66	0	0	AIRFLOWS		
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Floor	0	0	0	0	0.00	0	0	0	0	0	0	0.00	0	0	Diffuser	39	39
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0.00	0.00	0.00	0	0	Terminal	39	39
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Main Fan	39	39
Sub Total ==>	162	352	514	25	167	18	0	0	0	-200	-378	51.43	0	0	Sec Fan	0	0
Internal Loads					Internal Loads					Internal Loads					Nom Vent	10	10
Lights	410	102	512	25	410	44	0	0	0	0	0	0.00	0	0	AHU Vent	10	10
People	500	0	500	24	250	27	0	0	0	0	0	0.00	0	0	Infil	0	0
Misc	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	MinStop/Rh	0	0
Sub Total ==>	910	102	1,012	48	660	70	0	0	0	0	0	0.00	0	0	Return	29	29
Ceiling Load	116	-116	0	0	112	12	0	0	0	-44	0	0.00	0	0	Exhaust	0	0
Ventilation Load	0	0	563	27	0	0	0	0	0	0	-432	58.85	0	0	Rm Exh	10	10
Adj Air Trans Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Auxiliary	0	0
Dehumid. Ov Sizing	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Leakage Dwn	0	0
Ov/Undr Sizing	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Leakage Ups	0	0
Exhaust Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	ENGINEERING CKS		
Sup. Fan Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Ret. Fan Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	% OA	25.7	25.7
Duct Heat Pkup	0	0	0	0	0	0	0	0	0	0	76	-10.28	0	0	cfm/ft²	0.52	0.52
Underflr Sup Ht Pkup	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	cfm/ton	223.72	
Supply Air Leakage	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	ft²/ton	430.82	
Grand Total ==>	1,187	339	2,089	100.00	939	100.00	0	0	0	-243	-735	100.00	0	0	Btu/hr-ft²	27.85	-9.80
COOLING COIL SELECTION					AREAS					HEATING COIL SELECTION					No. People		
Total Capacity ton	MBh	Sens Cap. MBh	Coil Airflow cfm	Enter DB/WB/HR °F °F gr/lb	Leave DB/WB/HR °F °F gr/lb	Gross Total	Glass ft² (%)			Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F				
Main Clg	0.2	2.1	1.5	39	83.9 68.0 77.7	Floor	75			Main Htg	-0.7	39	58.6	75.6			
Aux Clg	0.0	0.0	0.0	0	0.0 0.0 0.0	Part	0			Aux Htg	0.0	0	0.0	0.0			
Opt Vent	0.0	0.0	0.0	0	0.0 0.0 0.0	Int Door	0			Preheat	0.0	0	0.0	0.0			
Total	0.2	2.1				ExFlr	0			Humidif	0.0	0	0.0	0.0			
						Roof	75	0	0	Opt Vent	0.0	0	0.0	0.0			
						Wall	100	0	0	Total	-0.7						
						Ext Door	0	0	0								

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 5 of 9

Room Checksums

By Go Green Engineering LLC

Parts Warehouse

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16 Outside Air: OADB/WB/HR: 96 / 77 / 113					Mo/Hr: 8 / 16 OADB: 96					Mo/Hr: Heating Design OADB: 31							
Space Sens. + Lat. Btu/h	Plenum Sens. + Lat. Btu/h	Net Total Btu/h	Percent Of Total (%)		Space Sensible Btu/h	Percent Of Total (%)				Space Peak Space Sens Btu/h	Coil Peak Tot Sens Btu/h	Percent Of Total (%)			Cooling	Heating	
Envelope Loads					Envelope Loads					Envelope Loads							
Skyline Solar	0	0	0	0	0	0	0	Skyline Solar	0	0	0	0.00			SADB	55.0	74.9
Skyline Cond	0	0	0	0	0	0	0	Skyline Cond	0	0	0	0.00			Ra Plenum	79.9	68.2
Roof Cond	0	4,894	4,894	25	0	0	0	Roof Cond	0	-2,009	42.08				Return	79.9	68.2
Glass Solar	0	0	0	0	0	0	0	Glass Solar	0	0	0.00				Ret/OA	79.9	68.2
Glass/Door Cond	799	0	799	4	799	6	6	Glass/Door Cond	-1,480	-1,480	31.00				Fn MtrTD	0.0	0.0
Wall Cond	1,131	329	1,460	7	1,131	8	8	Wall Cond	-1,318	-1,747	36.59				Fn BldTD	0.0	0.0
Partition/Door	0	0	0	0	0	0	0	Partition/Door	0	0	0.00				Fn Frict	0.0	0.0
Floor	0	0	0	0	0.00	0	0	Floor	0	0	0.00						
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00						
Infiltration	0	0	0	0	0	0	0	Infiltration	0	0	0.00						
Sub Total ==>	1,929	5,224	7,153	37	1,929	14		Sub Total ==>	-2,798	-5,235	109.66						
Internal Loads					Internal Loads					Internal Loads							
Lights	6,302	1,575	7,877	40	6,302	44	44	Lights	0	0	0.00				AIRFLOWS		
People	500	0	500	3	250	2	2	People	0	0	0.00				Cooling	Heating	
Misc	3,939	0	3,939	20	3,939	28	28	Misc	0	0	0.00				Diffuser	640	640
Sub Total ==>	10,740	1,575	12,316	63	10,490	74		Sub Total ==>	0	0	0.00				Terminal	640	640
Ceiling Load	1,777	-1,777	0	0	1,777	13	13	Ceiling Load	-672	0	0.00				Main Fan	640	640
Ventilation Load	0	0	0	0	0	0	0	Ventilation Load	0	0	0.00				Sec Fan	0	0
Adj Air Trans Heat	0	0	0	0	0	0	0	Adj Air Trans Heat	0	0	0.00				Nom Vent	0	0
Dehumid. Ov Sizing	0	0	0	0	0	0	0	Dehumid. Ov Sizing	0	0	0.00				AHU Vent	0	0
Ov/Undr Sizing	0	0	0	0	0	0	0	Ov/Undr Sizing	0	0	0.00				Infil	0	0
Exhaust Heat	0	0	0	0	0	0	0	Exhaust Heat	0	0	0.00				MinStop/Rh	0	0
Sup. Fan Heat	0	0	0	0	0	0	0	OA Preheat Diff.	0	0	0.00				Return	640	640
Ret. Fan Heat	0	0	0	0	0	0	0	RA Preheat Diff.	0	0	0.00				Exhaust	0	0
Duct Heat Pkup	0	0	0	0	0	0	0	Additional Reheat	0	0	0.00				Rm Exh	0	0
Underfir Sup Ht Pkup	0	0	0	0	0	0	0	System Plenum Heat	461	-9.66					Auxiliary	0	0
Supply Air Leakage	0	0	0	0	0	0	0	Underfir Sup Ht Pkup	0	0	0.00				Leakage Dwn	0	0
Supply Air Leakage	0	0	0	0	0	0	0	Supply Air Leakage	0	0	0.00				Leakage Ups	0	0
Grand Total ==>	14,447	5,022	19,469	100.00	14,197	100.00		Grand Total ==>	-3,470	-4,774	100.00				ENGINEERING CKS		
COOLING COIL SELECTION					AREAS					HEATING COIL SELECTION							
Total Capacity ton	MBh	Sens Cap. MBh	Coil Airflow cfm	Enter DB/WB/HR °F °F gr/lb	Leave DB/WB/HR °F °F gr/lb		Gross Total	Glass ft² (%)		Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F				
Main Clg	1.6	19.5	19.2	640	79.9 61.0	50.5	55.0 50.1	46.2	Floor	1,154	-4.8	640	68.2	74.9	Main Htg	-4.8	640
Aux Clg	0.0	0.0	0.0	0	0.0 0.0	0.0	0.0 0.0	0.0	Part	0	0.0	0	0.0	0.0	Aux Htg	0.0	0
Opt Vent	0.0	0.0	0.0	0	0.0 0.0	0.0	0.0 0.0	0.0	Int Door	0	0.0	0	0.0	0.0	Preheat	0.0	0
Total	1.6	19.5							ExFlr	0	0.0	0	0.0	0.0	Humidif	0.0	0
									Roof	1,154	0.0	0	0.0	0.0	Opt Vent	0.0	0
									Wall	708	0.0	0	0.0	0.0	Total	-4.8	
									Ext Door	192	0.0	0	0.0	0.0			

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 6 of 9

Room Checksums

By Go Green Engineering LLC

Reception/Bill Pay

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 15 Outside Air: OADB/WB/HR: 96 / 77 / 111					Mo/Hr: 6 / 15 OADB: 94					Mo/Hr: Heating Design OADB: 31							
Space Sens. + Lat. Btu/h	Plenum Sens. + Lat. Btu/h	Net Total Btu/h	Percent Of Total (%)		Space Sensible Btu/h	Percent Of Total (%)				Space Peak Space Sens Btu/h	Coil Peak Tot Sens Btu/h	Percent Of Total (%)			Cooling	Heating	
Envelope Loads					Envelope Loads					Envelope Loads							
Skyline Solar	0	0	0	0	0	0	0	Skyline Solar	0	0	0	0.00			SADB	55.0	78.1
Skyline Cond	0	0	0	0	0	0	0	Skyline Cond	0	0	0	0.00			Ra Plenum	79.8	68.2
Roof Cond	0	519	519	9	0	0	0	Roof Cond	0	-214	8.26				Return	79.8	68.2
Glass Solar	1,256	0	1,256	22	1,402	34		Glass Solar	0	0	0.00				Ret/OA	81.0	65.6
Glass/Door Cond	865	0	865	15	777	19		Glass/Door Cond	-1,584	-1,584	61.11				Fn MtrTD	0.0	0.0
Wall Cond	15	44	59	1	15	0		Wall Cond	-20	-87	3.34				Fn BldTD	0.0	0.0
Partition/Door	0	0	0	0	0	0		Partition/Door	0	0	0.00				Fn Frict	0.0	0.0
Floor	0	0	0	0	0.00	0		Floor	0	0	0.00						
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00		Adjacent Floor	0.00	0.00	0.00						
Infiltration	0	0	0	0	0	0		Infiltration	0	0	0.00						
Sub Total ==>	2,137	563	2,700	48	2,195	53		Sub Total ==>	-1,604	-1,885	72.72						
Internal Loads					Internal Loads					Internal Loads							
Lights	672	168	840	15	672	16		Lights	0	0	0.00				AIRFLOWS		
People	500	0	500	9	250	6		People	0	0	0.00				Cooling	Heating	
Misc	840	0	840	15	840	20		Misc	0	0	0.00				Diffuser	187	187
Sub Total ==>	2,011	168	2,179	38	1,761	42		Sub Total ==>	0	0	0.00				Terminal	187	187
Ceiling Load	188	-188	0	0	189	5		Ceiling Load	-72	0	0.00				Main Fan	187	187
Ventilation Load	0	0	785	14	0	0		Ventilation Load	0	-562	21.69				Sec Fan	0	0
Adj Air Trans Heat	0	0	0	0	0	0		Adj Air Trans Heat	0	0	0.00				Nom Vent	13	13
Dehumid. Ov Sizing	0	0	0	0	0	0		Ov/Undr Sizing	0	0	0.00				AHU Vent	13	13
Ov/Undr Sizing	0	0	0	0	0	0		Exhaust Heat	0	0	0.00				Infil	0	0
Exhaust Heat	0	0	0	0	0	0		OA Preheat Diff.	0	0	0.00				MinStop/Rh	0	0
Sup. Fan Heat	0	0	0	0	0	0		RA Preheat Diff.	0	0	0.00				Return	174	174
Ret. Fan Heat	0	0	0	0	0	0		Additional Reheat	0	0	0.00				Exhaust	0	0
Duct Heat PkUp	0	0	0	0	0	0		System Plenum Heat	-145	5.60					Rm Exh	13	13
Underflr Sup Ht PkUp	0	0	0	0	0	0		Underflr Sup Ht PkUp	0	0	0.00				Auxiliary	0	0
Supply Air Leakage	0	0	0	0	0	0		Supply Air Leakage	0	0	0.00				Leakage Dwn	0	0
Grand Total ==>	4,336	543	5,664	100.00	4,145	100.00		Grand Total ==>	-1,676	-2,592	100.00				Leakage Ups	0	0
COOLING COIL SELECTION					AREAS					HEATING COIL SELECTION					ENGINEERING CKS		
Total Capacity ton	MBh	Sens Cap. MBh	Coil Airflow cfm	Enter DB/WB/HR °F °F gr/lb	Leave DB/WB/HR °F °F gr/lb		Gross Total	Glass ft² (%)		Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F		Cooling	Heating	
Main Clg	0.5	5.7	4.9	187	81.0 63.7	61.3	Floor	123		Main Htg	-2.6	187	65.6	78.1	% OA	7.0	7.0
Aux Clg	0.0	0.0	0.0	0	0.0 0.0	0.0	Part	0		Aux Htg	0.0	0	0.0	0.0	cfm/ft²	1.52	1.52
Opt Vent	0.0	0.0	0.0	0	0.0 0.0	0.0	Int Door	0		Preheat	0.0	0	0.0	0.0	cfm/ton	396.04	
Total	0.5	5.7					ExFlr	0		Humidif	0.0	0	0.0	0.0	ft²/ton	260.59	
							Roof	123	0 0	Opt Vent	0.0	0	0.0	0.0	Btu/hr-ft²	46.05	-21.07
							Wall	140	104 74	Total	-2.6				No. People	1.0	8.1/1000 ft²
							Ext Door	0	0 0								

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 7 of 9

Room Checksums

By Go Green Engineering LLC

Service Manager

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16 Outside Air: OADB/WB/HR: 96 / 77 / 113					Mo/Hr: 6 / 15 OADB: 94					Mo/Hr: Heating Design OADB: 31							
Space Sens. + Lat.		Plenum Sens. + Lat	Net Total	Percent Of Total	Space Sensible		Percent Of Total	Space Peak		Coil Peak		Percent Of Total	SADB	Cooling	Heating		
Btu/h	Btu/h	Btu/h	(%)	Btu/h	(%)	Btu/h	(%)	Space Sens Btu/h	Space Sens Btu/h	Tot Sens Btu/h	Percent Btu/h	(%)	Ra Plenum	55.0	77.9		
Envelope Loads																	
Skylite Solar	0	0	0	0	0	0	0	Skylite Solar	0	0	0.00	0	0.00	0	0		
Skylite Cond	0	0	0	0	0	0	0	Skylite Cond	0	0	0.00	0	0.00	0	0		
Roof Cond	0	441	441	10	0	0	0	Roof Cond	0	-181	9.03	0	0.00	0	0		
Glass Solar	635	0	635	14	755	24	419	Glass Solar	0	0	0.00	0	0.00	0	0		
Glass/Door Cond	468	0	468	10	419	14	237	Glass/Door Cond	-853	-853	42.54	0	0.00	0	0		
Wall Cond	254	78	331	7	0	0	0	Wall Cond	-313	-421	20.98	0	0.00	0	0		
Partition/Door	0	0	0	0	0	0	0	Partition/Door	0	0	0.00	0	0.00	0	0		
Floor	0	0	0	0	0.00	0	0	Floor	0	0	0.00	0	0.00	0	0		
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0	0		
Infiltration	0	0	0	0	0	0	0	Infiltration	0	0	0.00	0	0.00	0	0		
Sub Total ==>	1,357	519	1,876	41	1,410	46	46	Sub Total ==>	-1,166	-1,455	72.54	72.54					
Internal Loads																	
Lights	568	142	710	16	568	18	18	Lights	0	0	0.00	0	0.00	0	0		
People	500	0	500	11	250	8	8	People	0	0	0.00	0	0.00	0	0		
Misc	710	0	710	16	710	23	23	Misc	0	0	0.00	0	0.00	0	0		
Sub Total ==>	1,778	142	1,920	42	1,528	49	49	Sub Total ==>	0	0	0.00	0	0.00	0	0		
Ceiling Load	160	-160	0	0	160	5	5	Ceiling Load	-61	0	0.00	0	0.00	0	0		
Ventilation Load	0	0	730	16	0	0	0	Ventilation Load	0	-519	25.87	25.87					
Adj Air Trans Heat	0	0	0	0	0	0	0	Adj Air Trans Heat	0	0	0	0					
Dehumid. Ov Sizing	0	0	0	0	0	0	0	Ov/Undr Sizing	0	0	0.00	0	0.00	0	0		
Ov/Undr Sizing	0	0	0	0	0	0	0	Exhaust Heat	0	0	0.00	0	0.00	0	0		
Exhaust Heat	0	0	0	0	0	0	0	OA Preheat Diff.	0	0	0.00	0	0.00	0	0		
Sup. Fan Heat	0	0	0	0	0	0	0	RA Preheat Diff.	0	0	0.00	0	0.00	0	0		
Ret. Fan Heat	0	0	0	0	0	0	0	Additional Reheat	0	0	0.00	0	0.00	0	0		
Duct Heat Pkup	0	0	0	0	0	0	0	System Plenum Heat	-32	1.59	0.00	1.59					
Underflr Sup Ht Pkup	0	0	0	0	0	0	0	Underflr Sup Ht Pkup	0	0	0.00	0	0.00	0	0		
Supply Air Leakage	0	0	0	0	0	0	0	Supply Air Leakage	0	0	0.00	0	0.00	0	0		
Grand Total ==>	3,295	500	4,525	100.00	3,098	100.00	100.00	Grand Total ==>	-1,226	-2,005	100.00	100.00					

COOLING COIL SELECTION								AREAS				HEATING COIL SELECTION					
Total Capacity		Sens Cap.	Coil Airflow	Enter DB/WB/HR		Leave DB/WB/HR		Gross Total		Glass		Capacity		Coil Airflow	Ent	Lvg	
ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb	ft²	(%)	MBh	cfm	°F	°F		
Main Clg	0.4	4.5	3.8	140	81.2	64.3	63.6	55.0	53.4	58.8		Main Htg	-2.0	140	65.0	77.9	
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		Aux Htg	0.0	0	0.0	0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0		Preheat	0.0	0	0.0	0.0	
Total	0.4	4.5										Humidif	0.0	0	0.0	0.0	
												Opt Vent	0.0	0	0.0	0.0	
												Total	-2.0				

AIRFLOWS		
	Cooling	Heating
Diffuser	140	140
Terminal	140	140
Main Fan	140	140
Sec Fan	0	0
Nom Vent	12	12
AHU Vent	12	12
Infil	0	0
MinStop/Rh	0	0
Return	128	128
Exhaust	0	0
Rm Exh	12	12
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	8.6	8.6
cfm/ft²	1.34	1.34
cfm/ton	370.50	
ft³/ton	275.79	
Btu/hr-ft²	43.51	-19.28
No. People	1.0	9.6/1000 ft²

COOLING COIL SELECTION										AREAS			HEATING COIL SELECTION				
Total Capacity ton	MBh	Sens Cap. MBh	Coil Airflow cfm	Enter DB/WB/HR °F °F gr/lb	Leave DB/WB/HR °F °F gr/lb					Gross Total	Glass ft² (%)		Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F	
Main Clg	0.4	4.5	3.8	140	81.2 64.3	63.6	55.0 53.4	58.8		Floor	104		Main Htg	-2.0	140	65.0	77.9
Aux Clg	0.0	0.0	0.0	0	0.0 0.0	0.0	0.0 0.0	0.0		Part	0		Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0 0.0	0.0	0.0 0.0	0.0		Int Door	0		Preheat	0.0	0	0.0	0.0
										ExFlr	0						
Total	0.4	4.5								Roof	104	0 0	Humidif	0.0	0	0.0	0.0
										Wall	227	56 25	Opt Vent	0.0	0	0.0	0.0
										Ext Door	0	0 0	Total	-2.0			

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 8 of 9

Room Checksums

By Go Green Engineering LLC

Trucker Lounge / Customer Waiting

COOLING COIL PEAK				CLG SPACE PEAK				HEATING COIL PEAK				TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16				Mo/Hr: 6 / 15				Mo/Hr: Heating Design						
Outside Air: OADBWB/HR: 96 / 77 / 113				OADB: 94				OADB: 31						
Space Sens. + Lat. Btu/h	Plenum Sens. + Lat. Btu/h	Net Total Btu/h	Percent Of Total (%)	Space Sensible Btu/h	Percent Of Total (%)	Space Peak Btu/h	Coil Peak Btu/h	Percent Of Total (%)	Space Sens Btu/h	Coil Peak Btu/h	Percent Of Total (%)	SADB	Cooling	Heating
Envelope Loads				Envelope Loads				Envelope Loads				AIRFLOWS		
Skyline Solar	0	0	0	0	0	0	0	0.00	0	0	0.00	Diffuser	955	955
Skyline Cond	0	0	0	0	0	0	0	0.00	0	0	0.00	Terminal	955	955
Roof Cond	0	2,600	2,600	0	0	0	-1,067	7.60	0	-1,067	7.60	Main Fan	955	955
Glass Solar	3,972	0	3,972	4,719	22	0	0	0.00	0	0	0.00	Sec Fan	0	0
Glass/Door Cond	3,009	0	3,009	2,690	13	-5,485	-5,485	39.09	0	-5,485	39.09	Nom Vent	132	132
Wall Cond	654	297	951	611	3	-807	-1,220	8.69	0	-1,220	8.69	AHU Vent	132	132
Partition/Door	0	0	0	0	0	0	0	0.00	0	0	0.00	Infil	0	0
Floor	0	0	0	0.00	0	0	0	0.00	0	0	0.00	MinStop/Rh	0	0
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	Return	823	823
Infiltration	0	0	0	0	0	0	0	0.00	0	0	0.00	Exhaust	0	0
Sub Total ==>	7,635	2,897	10,532	29	8,020	38	-6,293	55.39	0	-7,772	55.39	Rm Exh	132	132
Internal Loads				Internal Loads				Internal Loads				ENGINEERING CKS		
Lights	3,347	837	4,184	12	3,347	16	0	0.00	0	0	0.00	% OA	13.8	13.8
People	9,500	0	9,500	27	4,750	22	0	0.00	0	0	0.00	cfm/ft²	1.56	1.56
Misc	4,184	0	4,184	12	4,184	20	0	0.00	0	0	0.00	cfm/ton	319.63	
Sub Total ==>	17,032	837	17,869	50	12,282	58	0	0.00	0	0	0.00	ft³/ton	205.25	
Ceiling Load	944	-944	0	0	943	4	-357	0.00	0	0	0.00	Btu/hr-ft²	58.47	-22.89
Ventilation Load	0	0	7,439	21	0	0	0	-5,707	40.67	0	0.00	No. People	19.0	31.0/1000 ft²
Adj Air Trans Heat	0	0	0	0	0	0	0	0	0	0	0.00			
Dehumid. Ov Sizing	0	0	0	0	0	0	0	0.00	0	0	0.00			
Ov/Undr Sizing	0	0	0	0	0	0	0	0.00	0	0	0.00			
Exhaust Heat	0	0	0	0	0	0	0	0.00	0	0	0.00			
Sup. Fan Heat	0	0	0	0	0	0	0	0.00	0	0	0.00			
Ret. Fan Heat	0	0	0	0	0	0	0	0.00	0	0	0.00			
Duct Heat Pkup	0	0	0	0	0	0	-553	3.94	0	0	0.00			
Underflr Sup Ht Pkup	0	0	0	0	0	0	0	0.00	0	0	0.00			
Supply Air Leakage	0	0	0	0	0	0	0	0.00	0	0	0.00			
Grand Total ==>	25,611	2,789	35,839	100.00	21,244	100.00	-6,649	14.032	100.00	-14,032	100.00			
COOLING COIL SELECTION				AREAS				HEATING COIL SELECTION						
Total Capacity ton	Sens Cap. MBh	Coil Airflow cfm	Enter DB/WB/HR °F °F gr/lb	Gross Total	Glass ft² (%)	Capacity MBh	Coil Airflow cfm	Ent °F	Lvg °F					
Main Clg	3.0	35.8	26.7	955	82.0 66.3 72.0	54.9 54.0 61.3				Main Htg	-14.0	955	63.0	76.3
Aux Clg	0.0	0.0	0.0	0	0.0 0.0 0.0	0.0 0.0 0.0				Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0 0.0 0.0	0.0 0.0 0.0				Preheat	0.0	0	0.0	0.0
Total	3.0	35.8								Humidif	0.0	0	0.0	0.0
										Opt Vent	0.0	0	0.0	0.0
										Total	-14.0			

Project Name: I-75 TRUCK STOP - REPAIR CENTER
Dataset Name: TRUCK STOP.TRC

TRACE® 700 v6.3.4 calculated at 06:30 AM on 11/26/2019
Alternative - 1 System Checksums Report Page 9 of 9

Florida Building Code, Sixth Edition (2017) - Energy Conservation

EnergyGauge Summit® Fla/Com-2017, Effective Date: Dec 31, 2017

IECC 2015 - Total Building Performance Compliance Option

Check List

Applications for compliance with the Florida Building Code, Energy Conservation shall include:

- ☒ This Checklist
- ☒ The full compliance report generated by the software that contains the project summary, compliance summary, certifications and detailed component compliance reports.
- ☒ The compliance report must include the full input report generated by the software as contiguous part of the compliance report.
- ☒ Boxes appropriately checked in the Mandatory Section of the compliance report.

WARNING: INPUT REPORT NOT GENERATED.

To include input report in final submission, go to the Project Form, Settings Tab and check the box - "Append Input Report to Compliance Output Report"
Then rerun your calculation

PROJECT SUMMARY

Short Desc: Office

Description: I-75 Truck Stop Repair Center

Owner: I-75 Truck Stop Repair Center

Address1: 14197 S US 441

City: Ellisville

Address2:

State: FL

Zip: 32024

Type: Office

Class: New Finished building

Jurisdiction: COLUMBIA COUNTY, COLUMBIA COUNTY, FL (221000)

Conditioned Area: 2373 SF

Conditioned & UnConditioned Area: 2373 SF

No of Stories: 1

Area entered from Plans 2373 SF

Permit No: 0

Max Tonnage 6

If different, write in: _____