

DATE 12/24/2008

Columbia County Building Permit
This Permit Must Be Prominently Posted on Premises During Construction

PERMIT
000027543

APPLICANT ROGER BONIFANT PHONE 904 296-1490
ADDRESS 6800 SOUTHPOINT PARKWAY JACKSONVILLE FL 32216
OWNER MARONDA HOMES PHONE 904 296-1490
ADDRESS 135 SW BLACK MAPLE CT LAKE CITY FL 32024
CONTRACTOR TED BROCK PHONE 904 296-1490

LOCATION OF PROPERTY 90W, TL 247S, TR ON 252B, TL ON TIMBE RIDGE, TR ON
BLACK MAPLE, 2ND LOT ON RIGHT

TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 154800.00

HEATED FLOOR AREA 2527.00 TOTAL AREA 3096.00 HEIGHT STORIES 1

FOUNDATION CONC WALLS FRAMED ROOF PITCH FLOOR SLAB

LAND USE & ZONING RSF-2 MAX. HEIGHT

Minimum Set Back Requirments: STREET-FRONT 25.00 REAR 15.00 SIDE 10.00

NO. EX.D.U. 0 FLOOD ZONE X PP DEVELOPMENT PERMIT NO.

PARCEL ID 10-4S-16-02856-114 SUBDIVISION TIMBERLANDS

LOT 14 BLOCK PHASE UNIT TOTAL ACRES 0.56

000001699 CBC1256382

Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
CULVERT 08-735 BK WR Y
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: MFE AT 106.5', NEED ELEVATION CONFIRMATION LETTER AT SLAB, NOC
ON FILE

Check # or Cash 959521

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power Foundation Monolithic
date/app. by date/app. by date/app. by
Under slab rough-in plumbing Slab Sheathing/Nailing
date/app. by date/app. by date/app. by
Framing Rough-in plumbing above slab and below wood floor
date/app. by date/app. by
Electrical rough-in Heat & Air Duct Peri. beam (Lintel)
date/app. by date/app. by date/app. by
Permanent power C.O. Final Culvert
date/app. by date/app. by date/app. by
M/H tie downs, blocking, electricity and plumbing Pool
date/app. by date/app. by
Reconnection Pump pole Utility Pole
date/app. by date/app. by date/app. by
M/H Pole Travel Trailer Re-roof
date/app. by date/app. by date/app. by

BUILDING PERMIT FEE \$ 775.00 CERTIFICATION FEE \$ 15.48 SURCHARGE FEE \$ 15.48

MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$

FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ 25.00 TOTAL FEE 905.96

INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED TO BE IN ACTIVE PROGRESS WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Columbia County Building Permit Application

For Office Use Only Application # 0812-23 Date Received 12/14/08 By G Permit # 1699/27543
 Zoning Official BLK Date 12-12-08 Flood Zone X plat Land Use Res. Low Density Zoning RSF-2
 FEMA Map # N/A Elevation N/A MFE 106.5' River N/A Plans Examiner (initials) Date 12/14/08
 Comments Elevation Confirmation letter required at slab.
☒ NOC ☒ EH ☐ Deed or PA ☐ Site Plan ☐ State Road Info ☐ Parent Parcel # _____
☐ Dev Permit # _____ ☐ In Floodway ☐ Letter of Auth. from Contractor ☐ F W Comp. letter
 IMPACT FEES: EMS \$29.88 Fire \$78.63 Corr \$40.16 Road/Code \$1,046.00/210
 School \$1,500.00 = TOTAL \$3,063.67

Septic Permit No. 08-735 Fax 904 332-6375
 Name Authorized Person Signing Permit THEODORE BROCK / ROGER BONIFANT Phone 904 296-1490
 Address 6800 SOUTHPOINT PKWY #300 JACKSONVILLE FL 32216
 Owners Name MARONDA HOMES INC. OF FLORIDA Phone 904 296-1490
 911 Address 135 SW BLACK MAPLE CT, LAKE CITY FL 32024
 Contractors Name THEODORE C. BROCK Phone 904 296-1490
 Address 6800 SOUTHPOINT PKWY #300 JACKSONVILLE FL 32216
 Fee Simple Owner Name & Address FREE SIMPLE
 Bonding Co. Name & Address N/A
 Architect/Engineer Name & Address THOMAS PONCE 4005 MARONDA WAY
SANFORD FL 32771
 Mortgage Lenders Name & Address BANK OF AMERICA
250 SOUTH PARK AVE. #400 WINTER PARK FL 32789
 Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progress Energy
 Property ID Number 10-45-16-02856-114 Estimated Cost of Construction \$116,100
 Subdivision Name TIMBER LANDS Lot 14 Block / Unit / Phase 1
 Driving Directions HWY 90, LEFT ON 247 SOUTH, RIGHT ON 252 B, LEFT ON TIMBER RIDGE, TR BLACK MAPLE, 2nd lot on right.
 Number of Existing Dwellings on Property 0
 Construction of RESIDENTIAL SINGLE FAMILY DWELLING Total Acreage .56 Lot Size
 Do you need a Culvert Permit or Culvert Waiver or Have an Existing Drive Total Building Height
 Actual Distance of Structure from Property Lines - Front 25.2 Side 25.4 Side 44.5 Rear 15.2
 Number of Stories 1 Heated Floor Area 2527 Total Floor Area 3096 Roof Pitch VARIABLES

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

Columbia County Building Permit Application

TIME LIMITATIONS OF APPLICATION: An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment

According to Florida Law, those who work on your property or provide materials, and are not paid-in-full, have a right to enforce their claim for payment against your property. This claim is known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look to your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

NOTICE OF RESPONSIBILITY TO BUILDING PERMITEE:

YOU ARE HEREBY NOTIFIED as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that result in ponding of water, or other damage to roadway and other public infrastructure facilities caused by you or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

OWNERS CERTIFICATION: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning. I further understand the above written responsibilities in Columbia County for obtaining this Building Permit.

Owners Signature

Steve Hagg

CONTRACTORS AFFIDAVIT: By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit.

Contractor's Signature (Permitee)

Theodore C. Brock

Contractor's License Number

CBC1256382

Columbia County

Competency Card Number

Affirmed under penalty of perjury to by the Contractor and subscribed before me this 12th day of December 2011.

Personally known X or Produced Identification

State of Florida Notary Signature (For the Contractor)

SEAL:





STATE OF FLORIDA
DEPARTMENT OF
ON-SITE SEWAGE
APPLICATION FOR

✓ 5/6 3388133

08-735-N

PERMIT NO. AP 903226
DATE PAID: 11/25/08
FEE PAID: 425.00
RECEIPT #: 12172-1081812

W/LOT
14
Permit Request

APPLICATION FOR:

[X] New System [] Exist. [] Holding Tank [] Innovative
[] Repair [] Abandon [] Temporary []

APPLICANT: Maronda Homes Inc of Florida

AGENT: Melissa McKague

TELEPHONE: (904) 290-1490 ext

MAILING ADDRESS: 1800 Southpoint Pkwy # 300 Jacksonville, FL 32210

TO BE COMPLETED BY APPLICANT OR APPLICANT'S AUTHORIZED AGENT. SYSTEMS MUST BE CONSTRUCTED BY A PERSON LICENSED PURSUANT TO 489.105(3)(M) OR 489.552, FLORIDA STATUTES.

PROPERTY INFORMATION

LOT: 14 BLOCK: 1 SUBDIVISION: Timberlands PLATTED: Yes 1996

PROPERTY ID #: 10-45-16-02856-114 ZONING: SFR I/M OR EQUIVALENT: [Y / N]

PROPERTY SIZE: 50 ACRES WATER SUPPLY: [] PRIVATE PUBLIC [X] <=2000GPD [] >2000GPD

IS SEWER AVAILABLE AS PER 381.0065, FS? [Y / N] DISTANCE TO SEWER: 0 FT

PROPERTY ADDRESS: 135 SW BLACK MAPLE CT. LAKE CITY, FL 32024

DIRECTIONS TO PROPERTY: US 90 West, left on 247, right on CR 252B, left on SW Timber Ridge Drive 14th LOT ON RIGHT

BUILDING INFORMATION

[X] RESIDENTIAL [] COMMERCIAL

Unit No	Type of Establishment	No. of Bedrooms	Building Area Sqft	Commercial/Institutional System Design Table 1, Chapter 64E-6, FAC
1	SFR	4	2527	Under Air
2			3096	SF
			TOTAL	
3	12/3/08 owner ready			
4	to meet @ site			

[] Floor/Equipment Drains [] Other (Specify)

SIGNATURE: [Signature]

DATE: 11/21/08



STATE OF FLORIDA
DEPARTMENT OF HEALTH

APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Permit Application Number 08-135N

----- PART II - SITE PLAN -----

Scale: Each block represents 5 feet and 1 inch = 50 feet.

See Attached
Plot Plan

Notes: _____

Site Plan submitted by [Signature] _____

Signature

Title

Plan Approved ☒ _____ Not Approved ☐ _____ Date 12-3-08

By [Signature] _____ Columbia County Health Department

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT

08-735

PROPOSED BUILDING LAYOUT

IN SECTION 10, TOWNSHIP 4 SOUTH, RANGE 16 EAST, COLUMBIA COUNTY, FLORIDA



LEGAL DESCRIPTION:
LOT 14 OF "RANGERS" AS PER PLAT THEREOF AS RECORDED IN PLAT BOOK "9", PAGE 27 OF THE PUBLIC RECORDS OF COLUMBIA COUNTY, FLORIDA.


CERTIFIED TO:
1) MARIONA HOMES

BUILDING SETBACK NOTE:
BUILDING SETBACK INFORMATION FOR THIS PROJECT IS AS FOLLOWS: FRONT 25', REAR 15', SIDE 10'

BENCHMARK NOTE:
ELEVATIONS SHOWN HEREON ARE BASED UPON A BENCHMARK SET IN A 6" PIPE AT THE INTERSECTION OF THE CENTERLINE OF R.T. 15 AND THE CENTERLINE OF R.T. 16. THIS INFORMATION WAS PROVIDED TO THIS SURVEYOR BY BRIT SURVEYING (PLATTING SURVEYOR) DATUM UNKNOWN.

SURVEYOR NOTES:
1) TO THE BEST OF MY KNOWLEDGE, THERE ARE NO ENCROACHMENTS, BOUNDARY LINE DISPUTES, EASEMENTS, OR CLAIMS OF EASEMENTS, OTHER THAN ARE DEPICTED ON THIS DRAWING.
2) ALL UTILITIES AND OR IMPROVEMENTS, IF ANY, MAY NOT BE SHOWN ON THIS DRAWING.
3) IN THE OPINION OF THIS SURVEYOR THE BOUNDARY HEREON REPRESENTS THE BEST ESTIMATION OF THE TRUE BOUNDARY IN RELATION TO THE DESCRIPTION AND THOSE PROPERTY CORNERS FOUND TO BE ACCEPTABLE TO THIS SURVEYOR.
4) BUILDING SETBACK LINES DEPICTED HEREON ARE SHOWN AS PER THE RECORD PLAT, BUT ARE SUBJECT TO CHANGE PRIOR TO ANY NEW CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SETBACK REQUIREMENTS.
5) THIS MAP OF SURVEY REFLECTS CONDITIONS LOCATED AS OF THE DATE OF FIELD WORK COMPLETION (SEE TITLE BLOCK).
6) AREAS OF ENVIRONMENTAL CONCERN HAVE NOT BEEN DEPICTED HEREON.

FLOOD NOTE:
IN THE OPINION OF THIS SURVEYOR, ACCORDING TO THE NATIONAL FLOOD INSURANCE PROGRAM, FLOOD INSURANCE RATE MAP COMMUNITY PANEL NO. 120070-0175-B, DATED 1-4-88, THE PROPERTY IS IN FLOOD ZONE V. THE FLOOD INSURANCE RATE MAP INFORMATION FROM THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAPS, SHOWN ON THIS MAP, WAS CURRENT AS OF THE REFERENCED DATE. MAP REVISIONS AND AMENDMENTS ARE PERIODICALLY MADE BY LETTER AND MAY NOT BE REFLECTED ON THE MOST CURRENT MAP.



- ABBREVIATIONS:**
- ASPT - ASPHALT
 - ASPC - ASPHALT CALCULATED FROM MEASURED
 - CAV - CONCRETE VULNERABLE
 - CLB - CONCRETE BLOCK
 - CLF - CHAIN LINK FENCE
 - CM - CONCRETE MONUMENT
 - CONC - CONCRETE
 - ELEC - ELECTRIC
 - ELEV - ELEVATION
 - FNC - FENCE
 - FS - FENCED SURVEYOR BUSINESS
 - LB - LICENSED SURVEYOR BUSINESS
 - MB - MEASURED
 - MI - MEASURED
 - OUL - OVERHEAD UTILITIES
 - PL - PLAT
 - PLB - PLAT BOOK
 - PUB - PUBLIC UTILITIES EASEMENT
 - TRANS - TRANSFORMER
 - TYP - TYPICAL
 - WM - WATER METER
 - WV - WATER VALVE

THIS IS NOT A BOUNDARY SURVEY
CERTIFICATE OF SURVEYOR:
NOT VALID WITHOUT THE SIGNATURE AND THE ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER. ADDITIONS OR CHANGES TO THIS MAP BY ANYONE OTHER THAN THIS SURVEYOR IS PROHIBITED.

I HEREBY CERTIFY THAT THE SURVEY DATA SHOWN HEREON, IS A TRUE AND CORRECT REPRESENTATION OF A SURVEY PERFORMED UNDER MY SUPERVISION OF THE HEREON DESCRIBED PROPERTY AND I AM NOT PROVIDING ANY GUARANTEE OR WARRANTY OF ANY KIND, INCLUDING BUT NOT LIMITED TO THE MINIMUM TECHNICAL STANDARDS SET FORTH BY THE FLORIDA SURVEYING AND MAPPING ACT, PURSUANT TO SECTION 472.027, FLORIDA STATUTES, AND CHAPTER 110-12-8, FLORIDA ADMINISTRATIVE CODE.

BY: *James Brinkman* JAMES BRINKMAN, PSM - FLA. CERT# 5582
DATE: 11/24/08

BRINKMAN SURVEYING & MAPPING INC.
4607 NW 8th STREET SUITE C, GAINESVILLE, FL 32609
PHONE: (352) 374-7707 FAX: (352) 374-8757

SCALE: 1" = 30'	THE BENCHMARK IN QUALITY SERVICE	DRAWN BY: ZL
DATE: 11/5/2008		CHECKED BY: J.B.
FELD WORK COMPLETED ON ***	FELDBOOK #, PAGE **	
PREPARED FOR: MARIONA	DRAWING NUMBER	166-08

TITLE NOTE:
THIS SURVEY IS SUBJECT TO ANY FACTS THAT MAY BE DISCOVERED BY FULL AND ACCURATE TITLE SEARCH. THIS SURVEYOR HAS NOT PERFORMED A SEARCH OF THE PUBLIC RECORDS ON THIS PARCEL FOR ANY CLAIMS OF TITLE, EASEMENTS, OR RESTRICTIONS THAT MAY EFFECT THIS PARCEL. THE PRESENCE OR ABSENCE OF ANY SUCH CLAIMS ARE NOT CERTIFIED HEREON.

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

14/1

Project Name: DAVENPORT NORTH Address: City, State: Owner: ELECTRIC Climate Zone: North	Builder: MARONDA HOMES Permitting Office: Columbia Permit Number: 27543 Jurisdiction Number: 221000
--	--

1. New construction or existing New ☐ 2. Single family or multi-family Single family ☐ 3. Number of units, if multi-family 1 ☐ 4. Number of Bedrooms 4 ☐ 5. Is this a worst case? Yes ☐ 6. Conditioned floor area (ft²) 2527 ft² ☐ 7. Glass type¹ and area: (Label reqd. by 13-104.4.5 if not default) <table style="width: 100%;"> <tr> <td style="width: 30%;">a. U-factor:</td> <td style="width: 30%;">Description</td> <td style="width: 40%;">Area</td> </tr> <tr> <td>(or Single or Double DEFAULT)</td> <td>7a. (Dble Default)</td> <td>237.0 ft²</td> </tr> <tr> <td>b. SHGC:</td> <td></td> <td></td> </tr> <tr> <td>(or Clear or Tint DEFAULT)</td> <td>7b. (Clear)</td> <td>237.0 ft²</td> </tr> </table> 8. Floor types <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Slab-On-Grade Edge Insulation</td> <td style="width: 30%;">R=0.0, 211.0(p) ft</td> <td style="width: 40%;"></td> </tr> <tr> <td>b. N/A</td> <td></td> <td></td> </tr> <tr> <td>c. N/A</td> <td></td> <td></td> </tr> </table> 9. Wall types <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Concrete, Int Insul, Exterior</td> <td style="width: 30%;">R=4.1, 1173.0 ft²</td> <td style="width: 40%;"></td> </tr> <tr> <td>b. Frame, Wood, Adjacent</td> <td>R=13.0, 326.0 ft²</td> <td></td> </tr> <tr> <td>c. N/A</td> <td></td> <td></td> </tr> <tr> <td>d. N/A</td> <td></td> <td></td> </tr> <tr> <td>e. N/A</td> <td></td> <td></td> </tr> </table> 10. Ceiling types <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Under Attic</td> <td style="width: 30%;">R=30.0, 2650.0 ft²</td> <td style="width: 40%;"></td> </tr> <tr> <td>b. N/A</td> <td></td> <td></td> </tr> <tr> <td>c. N/A</td> <td></td> <td></td> </tr> </table> 11. Ducts <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Sup: Unc. Ret: Con. AH(Sealed):Interior</td> <td style="width: 30%;">Sup. R=6.0, 250.0 ft</td> <td style="width: 40%;"></td> </tr> <tr> <td>b. N/A</td> <td></td> <td></td> </tr> </table>	a. U-factor:	Description	Area	(or Single or Double DEFAULT)	7a. (Dble Default)	237.0 ft ²	b. SHGC:			(or Clear or Tint DEFAULT)	7b. (Clear)	237.0 ft ²	a. Slab-On-Grade Edge Insulation	R=0.0, 211.0(p) ft		b. N/A			c. N/A			a. Concrete, Int Insul, Exterior	R=4.1, 1173.0 ft ²		b. Frame, Wood, Adjacent	R=13.0, 326.0 ft ²		c. N/A			d. N/A			e. N/A			a. Under Attic	R=30.0, 2650.0 ft ²		b. N/A			c. N/A			a. Sup: Unc. Ret: Con. AH(Sealed):Interior	Sup. R=6.0, 250.0 ft		b. N/A			12. Cooling systems <table style="width: 100%;"> <tr> <td style="width: 50%;">a. Central Unit</td> <td style="width: 50%;">Cap: 47.5 kBtu/hr</td> </tr> <tr> <td></td> <td>SEER: 13.00</td> </tr> <tr> <td>b. N/A</td> <td></td> </tr> <tr> <td>c. N/A</td> <td></td> </tr> </table> 13. Heating systems <table style="width: 100%;"> <tr> <td style="width: 50%;">a. Electric Heat Pump</td> <td style="width: 50%;">Cap: 47.5 kBtu/hr</td> </tr> <tr> <td></td> <td>HSPF: 8.00</td> </tr> <tr> <td>b. N/A</td> <td></td> </tr> <tr> <td>c. N/A</td> <td></td> </tr> </table> 14. Hot water systems <table style="width: 100%;"> <tr> <td style="width: 50%;">a. Electric Resistance</td> <td style="width: 50%;">Cap: 50.0 gallons</td> </tr> <tr> <td></td> <td>EF: 0.90</td> </tr> <tr> <td>b. N/A</td> <td></td> </tr> <tr> <td>c. Conservation credits (HR-Heat recovery, Solar DHP-Dedicated heat pump)</td> <td></td> </tr> </table> 15. HVAC credits PT, ☐ (CF-Ceiling fan, CV-Cross ventilation, HF-Whole house fan, PT-Programmable Thermostat, MZ-C-Multizone cooling, MZ-H-Multizone heating)	a. Central Unit	Cap: 47.5 kBtu/hr		SEER: 13.00	b. N/A		c. N/A		a. Electric Heat Pump	Cap: 47.5 kBtu/hr		HSPF: 8.00	b. N/A		c. N/A		a. Electric Resistance	Cap: 50.0 gallons		EF: 0.90	b. N/A		c. Conservation credits (HR-Heat recovery, Solar DHP-Dedicated heat pump)	
a. U-factor:	Description	Area																																																																										
(or Single or Double DEFAULT)	7a. (Dble Default)	237.0 ft ²																																																																										
b. SHGC:																																																																												
(or Clear or Tint DEFAULT)	7b. (Clear)	237.0 ft ²																																																																										
a. Slab-On-Grade Edge Insulation	R=0.0, 211.0(p) ft																																																																											
b. N/A																																																																												
c. N/A																																																																												
a. Concrete, Int Insul, Exterior	R=4.1, 1173.0 ft ²																																																																											
b. Frame, Wood, Adjacent	R=13.0, 326.0 ft ²																																																																											
c. N/A																																																																												
d. N/A																																																																												
e. N/A																																																																												
a. Under Attic	R=30.0, 2650.0 ft ²																																																																											
b. N/A																																																																												
c. N/A																																																																												
a. Sup: Unc. Ret: Con. AH(Sealed):Interior	Sup. R=6.0, 250.0 ft																																																																											
b. N/A																																																																												
a. Central Unit	Cap: 47.5 kBtu/hr																																																																											
	SEER: 13.00																																																																											
b. N/A																																																																												
c. N/A																																																																												
a. Electric Heat Pump	Cap: 47.5 kBtu/hr																																																																											
	HSPF: 8.00																																																																											
b. N/A																																																																												
c. N/A																																																																												
a. Electric Resistance	Cap: 50.0 gallons																																																																											
	EF: 0.90																																																																											
b. N/A																																																																												
c. Conservation credits (HR-Heat recovery, Solar DHP-Dedicated heat pump)																																																																												

Glass/Floor Area: 0.09

Total as-built points: 28994

Total base points: 32964

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: Wayne Campbell**DATE:** Wayne Campbell

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: Melina Mucaghe**DATE:** Melina Mucaghe

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

**BUILDING OFFICIAL:** _____**DATE:** _____

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BSPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X SPM X SOF = Points				
.18	2527.0	18.59	8456.0	1.Double, Clear	W	1.0	6.0	71.0	38.52	0.97	2654.0
				2.Double, Clear	S	1.0	6.0	16.0	35.87	0.94	539.0
				3.Double, Clear	E	1.0	6.0	78.0	42.06	0.97	3176.0
				4.Double, Clear	W	1.0	8.0	40.0	38.52	0.99	1524.0
				5.Double, Clear	N	1.0	6.0	32.0	19.20	0.97	598.0
				As-Built Total:		237.0			8491.0		
WALL TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Adjacent	326.0	0.70	228.2	1. Concrete, Int Insul, Exterior	4.1		1173.0	1.13		1331.4	
Exterior	1173.0	1.70	1994.1	2. Frame, Wood, Adjacent	13.0		326.0	0.60		195.6	
Base Total: 1499.0 2222.3				As-Built Total:		1499.0			1527.0		
DOOR TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Adjacent	18.0	2.40	43.2	1.Exterior Wood			20.0	6.10		122.0	
Exterior	38.0	6.10	231.8	2.Adjacent Wood			18.0	2.40		43.2	
				3.Exterior Wood			18.0	6.10		109.8	
Base Total: 56.0 275.0				As-Built Total:		56.0			275.0		
CEILING TYPES Area X BSPM = Points				Type	R-Value		Area X SPM X SCM = Points				
Under Attic	2527.0	1.73	4371.7	1. Under Attic	30.0		2650.0	1.73 X 1.00		4584.5	
Base Total: 2527.0 4371.7				As-Built Total:		2650.0			4584.5		
FLOOR TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Slab	211.0(p)	-37.0	-7807.0	1. Slab-On-Grade Edge Insulation	0.0		211.0(p)	-41.20		-8693.2	
Raised	0.0	0.00	0.0								
Base Total: -7807.0				As-Built Total:		211.0			-8693.2		
INFILTRATION Area X BSPM = Points				Area X SPM = Points							
2527.0 10.21 25800.7				2527.0 10.21 25800.7							

SUMMER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT						
Summer Base Points: 33318.7				Summer As-Built Points:						31984.9
Total Summer Points	X System Multiplier	=	Cooling Points	Total Component (System - Points)	X Cap Ratio (DM x DSM x AHU)	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	=	Cooling Points
33318.7	0.3250		10828.6	(sys 1: Central Unit 47500btuh ,SEER/EFF(13.0) Ducts:Unc(S),Con(R),Int(AH),R6.0(INS) 31985 1.00 (1.08 x 1.147 x 0.86) 0.260 0.950 8468.3 31984.9 1.00 1.072 0.260 0.950 8468.3						

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X WPM X WOF = Points				
.18	2527.0	20.17	9175.0	1.Double, Clear	W	1.0	6.0	71.0	20.73	1.01	1483.0
				2.Double, Clear	S	1.0	6.0	16.0	13.30	1.03	218.0
				3.Double, Clear	E	1.0	6.0	78.0	18.79	1.02	1489.0
				4.Double, Clear	W	1.0	8.0	40.0	20.73	1.00	831.0
				5.Double, Clear	N	1.0	6.0	32.0	24.58	1.00	786.0
				As-Built Total:				237.0	4807.0		
WALL TYPES											
Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	326.0	3.60	1173.6	1. Concrete, Int Insul, Exterior	4.1		1173.0	6.42		7530.7	
Exterior	1173.0	3.70	4340.1	2. Frame, Wood, Adjacent	13.0		326.0	3.30		1075.8	
Base Total:				1499.0		5513.7		As-Built Total:		1499.0	
										8606.5	
DOOR TYPES											
Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	18.0	11.50	207.0	1.Exterior Wood			20.0	12.30		246.0	
Exterior	38.0	12.30	467.4	2.Adjacent Wood			18.0	11.50		207.0	
				3.Exterior Wood			18.0	12.30		221.4	
Base Total:				56.0		674.4		As-Built Total:		56.0	
										674.4	
CEILING TYPES											
Area X BWPM = Points				Type	R-Value		Area X WPM X WCM = Points				
Under Attic	2527.0	2.05	5180.4	1. Under Attic	30.0		2650.0	2.05 X 1.00		5432.5	
Base Total:				2527.0		5180.4		As-Built Total:		2650.0	
										5432.5	
FLOOR TYPES											
Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Slab	211.0(p)	8.9	1877.9	1. Slab-On-Grade Edge Insulation	0.0		211.0(p)	18.80		3966.8	
Raised	0.0	0.00	0.0								
Base Total:				1877.9		As-Built Total:		211.0		3966.8	
INFILTRATION											
Area X BWPM = Points								Area X WPM = Points			
2527.0 -0.59 -1490.9								2527.0 -0.59 -1490.9			

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE			AS-BUILT						
Winter Base Points: 20930.4			Winter As-Built Points: 21996.2						
Total Winter Points	X System Multiplier	= Heating Points	Total Component (System - Points)	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Heating Points	
20930.4	0.5540	11595.5	(sys 1: Electric Heat Pump 47500 btuh ,EFF(8.0) Ducts:Unc(S),Con(R),Int(AH),R6.0 21996.2	1.000	(1.060 x 1.169 x 0.88)0.426	0.950	0.950	9751.3	
			21996.2	1.00	1.095	0.426	0.950	9751.3	

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT						
WATER HEATING										
Number of Bedrooms	X	Multiplier	= Total	Tank Volume	EF	Number of Bedrooms	X	Tank X Ratio	Multiplier X Credit	= Total Multiplier
4		2635.00	10540.0	50.0	0.90	4		1.00	2693.56	1.00 10774.2
				As-Built Total: 10774.2						

CODE COMPLIANCE STATUS											
BASE						AS-BUILT					
Cooling Points	+	Heating Points	+	Hot Water Points	= Total Points	Cooling Points	+	Heating Points	+	Hot Water Points	= Total Points
10829		11595		10540	32964	8468		9751		10774	28994

PASS

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	✓
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	✓
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	✓
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	✓
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	✓
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	✓
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	✓

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	✓
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	✓
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	✓
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	✓
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	✓
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	✓

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 86.9

The higher the score, the more efficient the home.

ELECTRIC, , , ,

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 47.5 kBtu/hr
3. Number of units, if multi-family	1		SEER: 13.00
4. Number of Bedrooms	4	b. N/A	
5. Is this a worst case?	Yes	c. N/A	
6. Conditioned floor area (ft ²)	2527 ft ²		
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		13. Heating systems	
a. U-factor:	Description Area	a. Electric Heat Pump	Cap: 47.5 kBtu/hr
(or Single or Double DEFAULT)	7a. (Dble Default) 237.0 ft ²		HSPF: 8.00
b. SHGC:		b. N/A	
(or Clear or Tint DEFAULT)	7b. (Clear) 237.0 ft ²	c. N/A	
8. Floor types		14. Hot water systems	
a. Slab-On-Grade Edge Insulation	R=0.0, 211.0(p) ft	a. Electric Resistance	Cap: 50.0 gallons
b. N/A			EF: 0.90
c. N/A		b. N/A	
9. Wall types		c. Conservation credits	
a. Concrete, Int Insul, Exterior	R=4.1, 1173.0 ft ²	(HR-Heat recovery, Solar	
b. Frame, Wood, Adjacent	R=13.0, 326.0 ft ²	DHP-Dedicated heat pump)	
c. N/A		15. HVAC credits	PT,
d. N/A		(CF-Ceiling fan, CV-Cross ventilation,	
e. N/A		HF-Whole house fan,	
10. Ceiling types		PT-Programmable Thermostat,	
a. Under Attic	R=30.0, 2650.0 ft ²	MZ-C-Multizone cooling,	
b. N/A		MZ-H-Multizone heating)	
c. N/A			
11. Ducts			
a. Sup: Unc. Ret: Con. AH(Sealed):Interior Sup. R=6.0, 250.0 ft			
b. N/A			

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: [Signature]
Address of New Home: 135 S.W. BLACK MAPLE CT.

Date: 11/25/08
City/FL Zip: LAKE CITY, FL 32024



*NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStarTM designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.
EnergyGauge® (Version: FLRCSB v4.5)



Project Summary
Entire House
Maronda Homes

Job:
Date:
By: G. Carmack

4005 Maronda Way, Sanford, FL 32771 Phone: 407-321-3913 Fax: 407-321-0064

Project Information

For: DAVENPORT

Notes:

Design Information

Weather: Jacksonville, Int'l AP, FL, US

Winter Design Conditions

Outside db	32 °F
Inside db	70 °F
Design TD	38 °F

Summer Design Conditions

Outside db	93 °F
Inside db	75 °F
Design TD	18 °F
Daily range	M
Relative humidity	50 %
Moisture difference	51 gr/lb

Heating Summary

Structure	35160 Btuh
Ducts	5770 Btuh
Central vent (100 cfm)	4175 Btuh
Humidification	0 Btuh
Piping	0 Btuh
Equipment load	45105 Btuh

Sensible Cooling Equipment Load Sizing

Structure	20194 Btuh
Ducts	12342 Btuh
Central vent (100 cfm)	1934 Btuh
Blower	0 Btuh
Use manufacturer's data	n
Rate/swing multiplier	0.98
Equipment sensible load	33642 Btuh

Infiltration

Method	Simplified
Construction quality	Average
Fireplaces	0

	Heating	Cooling
Area (ft²)	2527	2527
Volume (ft³)	20216	20216
Air changes/hour	0.32	0.16
Equiv. AVF (cfm)	108	54

Latent Cooling Equipment Load Sizing

Structure	1879 Btuh
Ducts	2839 Btuh
Central vent (100 cfm)	3485 Btuh
Equipment latent load	8204 Btuh

Equipment total load	41846 Btuh
Req. total capacity at 0.76 SHR	3.7 ton

Heating Equipment Summary

Make TEMPSTAR
Trade HEAT PUMP
Model N4H348AKB

Efficiency	8 HSPF
Heating input	0 Btuh @ 47°F
Heating output	0 °F
Temperature rise	0 cfm
Actual air flow	0.000 cfm/Btuh
Air flow factor	0.60 in H2O
Static pressure	
Space thermostat	

Cooling Equipment Summary

Make	TEMPSTAR
Trade	HEAT PUMP
Cond	N4H348AKB
Coil	FSU4X4800A
Efficiency	13 SEER
Sensible cooling	36100 Btuh
Latent cooling	11400 Btuh
Total cooling	47500 Btuh
Actual air flow	1460 cfm
Air flow factor	0.045 cfm/Btuh
Static pressure	0.60 in H2O
Load sensible heat ratio	0.81

Bold/italic values have been manually overridden

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.



wrightsoft

Right-Suite Residential 6.0.90 RSR21115

C:\Documents and Settings\gcarmack\My Documents\Man J Calcs 2007\JACKSONVILLE\DAVENPORT 13.rpt Ca

2008-Sep-22 13:45:49

Page 1

Project Information

For: DAVENPORT

Design Conditions

Location:

Jacksonville, Int'l AP, FL, US
Elevation: 30 ft
Latitude: 31°N

Outdoor:

Dry bulb (°F)
Daily range (°F)
Wet bulb (°F)
Wind speed (mph)

Heating

32
-
-
15.0

Cooling

93
18 (M)
77
7.5

Indoor:

Indoor temperature (°F)
Design TD (°F)
Relative humidity (%)
Moisture difference (gr/lb)

Heating

70
38
30
11.5

Cooling

75
18
50
51.3


Infiltration:

Method
Construction quality
Fireplaces

Simplified
Average
0


Heating

Component	Btuh/ft²	Btuh	% of load
Walls	4.5	7210	16.0
Glazing	48.3	6998	15.5
Doors	14.8	830	1.8
Ceilings	1.9	4731	10.5
Floors	17.9	10888	24.1
Infiltration	2.5	4502	10.0
Ducts		5770	12.8
Piping		0	0.0
Humidification		0	0.0
Ventilation		4175	9.3
Adjustments		0	
Total		45105	100.0



Cooling

Component	Btuh/ft²	Btuh	% of load
Walls	2.4	3883	11.3
Glazing	46.4	6722	19.5
Doors	11.8	660	1.9
Ceilings	2.6	6686	19.4
Floors	0.0	0	0.0
Infiltration	0.6	1043	3.0
Ducts		12342	35.8
Ventilation		1934	5.6
Internal gains		1200	3.5
Blower		0	0.0
Adjustments		0	
Total		34469	100.0



Overall U-value = 0.163 Btuh/ft²-°F

Data entries checked.

Duct System Summary

Entire House

Maronda Homes

Job: DAVENPORT

Date:

By: G. Carmack

4005 Maronda Way, Sanford, FL 32771 Phone: 407-321-3913 Fax: 407-321-0064

Project Information

For: DAVENPORT

	Heating	Cooling
External static pressure	0.60 in H2O	0.60 in H2O
Pressure losses	0.00 in H2O	0.00 in H2O
Available static pressure	0.60 in H2O	0.60 in H2O
Supply / return available pressure	0.46 / 0.14 in H2O	0.46 / 0.14 in H2O
Lowest friction rate	0.100 in/100ft	0.100 in/100ft
Actual air flow	1460 cfm	1460 cfm
Total effective length (TEL)	26 ft	

Supply Branch Detail Table

Name	Design (Btuh)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	Rect Size (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
MASTER BDR	h 626 5	240	240	0.100	8	x00	VIFx	5.0	0.0	st1
MASTER BATH	h 294 7	75	75	0.100	6	x00	VIFx	10.0	0.0	st1
MASTER TOILET	h 111 6	25	25	0.100	4	x00	VIFx	20.0	0.0	st1
LIVING ROOM	h 310 7	155	155	0.100	7	x00	VIFx	5.0	0.0	st1
FAMILY ROOM	c 413 9	165	165	0.100	7	x00	VIFx	5.0	0.0	st1
DINING ROOM	h 434 1	125	125	0.100	6	x00	VIFx	5.0	0.0	st1
NOOK	h 265 3	125	125	0.100	6	x00	VIFx	20.0	0.0	st1
KITCHEN	c 262 7	100	100	0.100	6	x00	VIFx	10.0	0.0	st1
BDR #4	h 325 2	130	130	0.100	6	x00	VIFx	10.0	0.0	ST2
bDR #3	h 198 4	90	90	0.100	6	x00	VIFx	5.0	0.0	ST2
BATH	h 867	20	20	0.100	4	x00	VIFx	15.0	0.0	ST2
BDR #2	c 410 9	160	160	0.100	7	x00	VIFx	15.0	0.0	ST2
UTILITY	h 907	50	50	0.100	4	x00	VIFx	10.0	0.0	ST3

Supply Trunk Detail Table

Name	Trunk Type	Htg (cfm)	Clg (cfm)	Design FR	Veloc (fpm)	Diam (in)	Rect Duct Size (in)	Duct Material	Trunk
st1	Peak AVF	1010	1010	0.100	590	16	0 x 0	VinIFlx	
ST2	Peak AVF	400	400	0.100	517	10	0 x 0	VinIFlx	
ST3	Peak AVF	50	50	0.100	284	4	0 x 0	VinIFlx	

Bold/italic values have been manually overridden

Return Branch Detail Table

Name	Grill Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	RectSize (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb1	0x0	1460	1460	6.0	2.308	669	18	x0 0		VlFx	

NOTICE OF COMMENCEMENT

County Clerk's Office Stamp or Seal

Tax Parcel Identification Number 10-45-16-02856-114

THE UNDERSIGNED hereby gives notice that improvements will be made to certain real property, and in accordance with Section 713.13 of the Florida Statutes, the following information is provided in this NOTICE OF COMMENCEMENT.

1. Description of property (legal description): LOT 14, TIMBERLANDS
a) Street (job) Address: 135 SW BLACK MAPLE CT. LAKE CITY FL 32024
2. General description of improvements: SINGLE FAMILY
NEW CONSTRUCTION
3. Owner Information
a) Name and address: MARONDA HOMES INC. OF FLORIDA 6800 SOUTHPOINT PKYW
b) Name and address of fee simple titleholder (if other than owner) _____
c) Interest in property: OWNER #300
JAX FL 32216
4. Contractor Information
a) Name and address: MARONDA HOMES INC. OF FL
b) Telephone No.: 904 296-1490 Fax No. (Opt.) 904 332-6375
5. Surety Information
a) Name and address: _____
b) Amount of Bond: _____
c) Telephone No.: _____ Fax No. (Opt.) _____
6. Lender
a) Name and address: _____
b) Phone No.: _____
7. Identity of person within the State of Florida designated by owner upon whom notices or other documents may be served:
a) Name and address: STEEL CITY TITLE INC. 851 TRAFALGAR CT #1328 MAITLAND FL
b) Telephone No.: 407 660-4422 Fax No. (Opt.) 407 660-4208 32751
8. In addition to himself, owner designates the following person to receive a copy of the Lienor's Notice as provided in Section 713.13(1)(b), Florida Statutes:
a) Name and address: _____
b) Telephone No.: _____ Fax No. (Opt.) _____
9. Expiration date of Notice of Commencement (the expiration date is one year from the date of recording unless a different date is specified): _____

WARNING TO OWNER: ANY PAYMENTS MADE BY THE OWNER AFTER THE EXPIRATION OF THE NOTICE OF COMMENCEMENT ARE CONSIDERED IMPROPER PAYMENTS UNDER CHAPTER 713, PART I, SECTION 713.13, FLORIDA STATUTES, AND CAN RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY; A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT YOUR LENDER OR AN ATTORNEY BEFORE COMMENCING WORK OR RECORDING YOUR NOTICE OF COMMENCEMENT.


STATE OF FLORIDA
COUNTY OF COLUMBIA

10. _____
Signature of Owner or Owner's Authorized Office/Director/Partner/Manager
Steve Hogg
Print Name

The foregoing instrument was acknowledged before me, a Florida Notary, this 12 day of DECEMBER, 2008, by:
STEVE HOGG AS DIVISION MANAGER (type of authority, e.g. officer, trustee, attorney
fact) for MARONDA HOMES INC. OF FLORIDA (name of party on behalf of whom instrument was executed).


Personally Known ☒ OR Produced Identification _____ Type _____

Notary Signature Nancy P. O'Leary Notary Stamp or Seal: _____



11. Verification pursuant to Section 92.525, Florida Statutes. Under penalties of perjury, I declare that I have read the foregoing and that the facts stated in it are true to the best of my knowledge and belief.

Nancy P. O'Leary



Signature of Natural Person Signing (in line #10 above.) STEVE HOGG


**Columbia County Building Department
Culvert Permit**

**Culvert Permit No.
000001699**

DATE 12/24/2008 PARCEL ID # 10-4S-16-02856-114
APPLICANT ROGER BONIFANT PHONE 904 296-1490
ADDRESS 6800 SOUTHPPOINT PARKWAY JACKSONVILLE FL 32216
OWNER MARONDA HOMES PHONE 904 296-1490
ADDRESS 135 SW BLACK MAPLE CT LAKE CITY FL 32024
CONTRACTOR TED BROCK PHONE 904 296-1490
LOCATION OF PROPERTY 90W, TL ON 247S, TR ON 252B, TL ON TIMBER RIDGE, TR BLACK
MAPLE, 2ND LOT ON RIGHT

SUBDIVISION/LOT/BLOCK/PHASE/UNIT TIMBERLANDS 14

SIGNATURE



INSTALLATION REQUIREMENTS



Culvert size will be 18 inches in diameter with a total length of 32 feet, leaving 24 feet of driving surface. Both ends will be mitered 4 foot with a 4 : 1 slope and poured with a 4 inch thick reinforced concrete slab.

INSTALLATION NOTE: Turnouts will be required as follows:

- a) a majority of the current and existing driveway turnouts are paved, or;
 - b) the driveway to be served will be paved or formed with concrete.
- Turnouts shall be concrete or paved a minimum of 12 feet wide or the width of the concrete or paved driveway, whichever is greater. The width shall conform to the current and existing paved or concreted turnouts.



Culvert installation shall conform to the approved site plan standards.



Department of Transportation Permit installation approved standards.



Other _____

**ALL PROPER SAFETY REQUIREMENTS SHOULD BE FOLLOWED
DURING THE INSTALLATION OF THE CULVERT.**

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160

Amount Paid 25.00



Design Check List for Screen / Vinyl Room (Page 1 of 2)

I. Design Statement:

These plans have been designed in accordance with the Aluminum Structures Design Manual by Lawrence E. Bennett and are in compliance with the 2004 Florida Building Code Edition with 2006 Supplements, Chapter 20, ASMS and The 2005 Aluminum Design Manual Part I-A & II-A; Exposure 'B' ☒ or 'C' ☐ or 'D' ☐; Importance Factor 0.87 for 100 MPH and 0.77 for 110 MPH and higher; 120 MPH or _____ MPH for 3 second wind gust velocity load; Basic Wind Pressure _____; Design Pressures for Screen / Vinyl Rooms can be found on page 3A-ii:

- a. "B" exposure = 13.0 PSF for Roofs & 15.0 PSF for Walls
 b. "C" exposure = _____ PSF for Roofs & _____ PSF for Walls
 c. "D" exposure = _____ PSF for Roofs & _____ PSF for Walls
 Negative I.P.C. 0.18

For "C" or "D" exposure design loads, multiply "B" exposure loads by factors in table 3A-C on page 3iii.

II. Host Structure Adequacy Statement:

I have inspected and verify that the host structure is in good repair and attachments made to the structure will be solid.

Peter Wojtas Phone: 407-322-8122
 Contractor / Authorized Rep* Name (please print)

Peter Wojtas Date: 12/11/08
 Contractor / Authorized Rep* Signature

135 SW Black Maple CT. LAKE CITY, FL
 Job Name & Address 32024

Note: Projection of room from host structure shall not exceed 16".

III. Building Permit Application Package contains the following:

- A. Project name & address on plans ☒ Yes ☐ No
 B. Site plan or survey with enclosure location ☒ Yes ☐ No
 C. Contractor's / Designer's name, address, phone number, & signature on plans ☒ Yes ☐ No
 D. Site exposure form completed ☒ Yes ☐ No
 E. Proposed project layout drawing @ 1/8" or 1/10" scale with the following:
 1. Plan view with host structure area of attachment, enclosure length, and projection from host structure ☒ Yes ☐ No
 2. Front and side elevation views with all dimensions & heights ☒ Yes ☐ No
 3. Beam span, spacing, & size (Select beam size from appropriate 3A.1 series tables) ☒ Yes ☐ No
 4. Upright height, spacing, & size (Select uprights from appropriate 3A.2 series tables) (Check Table 3A.3 for minimum upright size) ☒ Yes ☐ No
 5. Chair rail or girts size, length, & spacing (Select chair rails from appropriate 3A.2 series tables) ☒ Yes ☐ No
 6. Knee braces length, location, & size (Check Table 3A.3 for knee brace size) ☐ Yes ☒ No

IV. Highlight details from Aluminum Structures Design Manual:

- A. Beam & purlin tables w/ sizes, thickness, spacing, & spans / lengths. Indicate Section 3A tables used: 3A.1.1-120

Beam allowable span conversions from 120 MPH wind zone, "B" Exposure to _____ MPH wind zone and/or "C" or "D" Exposure for load width _____:
 Look up span on 120-MPH table and apply the following formula:

$$\text{Span / Height @ 120 MPH} \times \text{Wind Zone Multiplier **} = \text{Required Span @ _____ MPH}$$

$$0.00 (b \text{ or } d) \times 1.00 (b \text{ or } d) \times 1.00 (b \text{ or } d) = \text{Exposure Multiplier **}$$

* Must have attended Engineer's Continuing Education Class within the past two years.
 ** Appropriate multiplier from page 3A-ii and page 3A-iii.

Design Check List for Screen / Vinyl Room (Page 2 of 2)

B. Upright tables w/ sizes, thickness, spacing, & heights ☒ ☐
 (Tables 3A.2.1, 3A.2.2, or 3A.2.3)

Upright or wall member allowable height / span conversions from 120 MPH
 wind zone, 'B' Exposure to _____ MPH wind zone and/or 'C' Exposure for load
 width _____:

Look up span on 120 MPH table and apply the following formula:

$$\begin{array}{c} \text{Span / Height} \\ \text{@ 120 MPH} \end{array} \downarrow \quad \begin{array}{c} \text{Required Span} \\ \text{@ _____ MPH} \end{array} \downarrow$$

$$\frac{0.00}{\text{Wind Zone Multiplier}^{**}} (b \text{ or } d) \times \frac{1.00}{\text{Exposure Multiplier}^{**}} (b \text{ or } d) \times \frac{1.00}{\text{Exposure Multiplier}^{**}} (b \text{ or } d) = \underline{\hspace{2cm}}$$

C. Table 3A.3 with beam & upright combination if applicable ☒ ☐


D. Connection details to be used such as:

- | | Yes | No |
|---|-------------------------------------|-------------------------------------|
| 1. Beam to upright | ☒ | ☐ |
| 2. Beam to wall | ☒ | ☐ |
| 3. Beam to beam | ☐ | ☒ |
| 4. Chair rail, purlins, & knee braces to beams & uprights | ☐ | ☒ |
| 5. Extruded gutter connection | ☐ | ☒ |
| 6. U-clip, angles and/or sole plate to deck | ☐ | ☒ |

E. Foundation detail type & size ☒ ☐


Notes:

** Appropriate multiplier from page 3A-ii and 3A-iii.



TYPICAL SLOPED SOLID ROOF ENCLOSURE

SCALE: N.T.S.



TYPICAL GABLE SOLID ROOF ENCLOSURE

SCALE: N.T.S.



Lawrence E. Bennett, P.E. FL # 16644
 CIVIL & STRUCTURAL ENGINEERING
 P.O. Box 214368, South Daytona, FL 32121
 Telephone #: (386) 767-4774 Fax #: (386) 767-6556
 Email: lebpe@bellsouth.net

PAGE

3A-1

SECTION 3A

SCREEN, ACRYLIC & VINYL ROOMS



NOTES:

1. ANCHOR 1" x 2" OPEN BACK EXTRUSION W/ 1/4" x 2-1/4" CONCRETE FASTENER MAX. OF 2'-0" O.C. AND W/ IN 6" EACH SIDE OF UPRIGHT ANCHOR 1" x 2" TO WOOD WALL W/ #10 x 2-1/2" S.M.S. W/ WASHERS OR #10 x 2-1/2" WASHER HEADED SCREW 2'-0" O.C. ANCHOR BEAM AND COLUMN INTERNALLY OR W/ ANCHOR CLIPS AND (2) #8 SCREWS W/ WASHERS @ EACH POINT OF CONNECTION.
2. SELECT FRONT WALL BEAM FROM TABLE USING LARGER LOAD WIDTH VALUE OF P/2 OR P/2 + O.H.
3. SELECT SCREEN ROOM FORTH WALL BEAM FROM TABLES 3A.1.3
4. ANCHORS BASED ON 123 MPH WIND VELOCITY. FOR HIGHER WIND ZONES USE THE FOLLOWING CONVERSION:

100-123	130	140	150
#8	#10	#12	#12

TYPICAL SCREEN ROOM

SCALE: 3/16" = 1'-0"

Lawrence E. Bennett, P.E. FL # 16644

CIVIL & STRUCTURAL ENGINEERING

P.O. Box 274368, South Daytona, FL 32121

Telephone #: (386) 767-4774 Fax #: (386) 767-8556


Email: lebpo@bellsouth.net

SECTION 3A

SCREEN, ACRYLIC & VINYL ROOMS

EDGE BEAM


1" x 2" OPEN BACK ATTACHED
TO FRONT POST W/
#10 x 1-1/2" S.M.S. MAX. 6"
FROM EACH END OF POST
AND 24" O.C.



ALTERNATE CONNECTION:
(2) #10 x 1-1/2" S.M.S.
THROUGH SPLINE GROOVES

SIDE WALL HEADER
ATTACHED TO 1" x 2" OPEN
BACK W/ MIN. (2) #10 x 1-1/2"
S.M.S.


FRONT WALL GIRT



SIDE WALL GIRT ATTACHED TO
1" x 2" OPEN BACK W/ MIN. (3)
#10 x 1-1/2" S.M.S. IN SCREW
BOSSSES

1" x 2" OPEN BACK ATTACHED
TO FRONT POST W/
#10 x 1-1/2" S.M.S. MAX. 6"
FROM EACH END OF POST
AND 24" O.C.

1"
MIN.



FRONT AND SIDE BOTTOM
RAILS ATTACHED TO
CONCRETE W/ 1/4" x 2-1/4"
CONCRETE / MASONRY
ANCHORS @ 6" FROM EACH
POST AND 24" O.C. MAX. AND
WALLS MIN. 1" FROM EDGE OF
CONCRETE

TYPICAL & ALTERNATE CORNER DETAIL

SCALE: 3" = 1'-0"

Lawrence E. Bennett, P.E. FL # 16644

CIVIL & STRUCTURAL ENGINEERING

P.O. Box 214368, South Daytona, FL 32121

Telephone #: (386) 767-4774 Fax #: (386) 767-5556

Email: lebpe@bellsouth.net

© COPYRIGHT 2005

NOT TO BE REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF LAWRENCE E. BENNETT, P.E.


ALTERNATE CONNECTION
DETAIL 1" x 2" WITH
(3) #10 x 1-1/2" S.M.S. INTO
SCREW BOSS

(2) #10 x 1 1/2" S. M. S. INTO
SCREW BOSS

ANCHOR 1" x 2" PLATE TO
CONCRETE W/ 1/4" x 2-1/2"
CONCRETE ANCHORS WITHIN
6" OF EACH SIDE OF EACH
POST AND 24" O.C. MAX.

MIN. 3-1/2" SLAB 2500 PSI
CONC. 6 x 6 - 10 x 10 W.W.M.
OR FIBER MESH

VAPOR BARRIER UNDER
CONCRETE



ANGLE CLIPS MAY BE
SUBSTITUTED FOR INTERNAL
SCREW SYSTEMS

MIN. (3) #10 x 1 1/2" S.M.S.
INTO SCREW BOSS

1" x 2" EXTRUSION

1-1/8" MIN. IN CONCRETE


**ALTERNATE HOLLOW UPRIGHT TO BASE AND
HOLLOW UPRIGHT TO BEAM DETAIL**

SCALE: 3" = 1'-0"

ANCHOR 1" x 2" CHANNEL TO
CONCRETE WITH
1/4" x 2-1/4" CONCRETE
ANCHORS WITHIN 6" OF EACH
SIDE OF EACH POST AT 24"
O.C. MAX. OR THROUGH
ANGLE AT 24" O.C. MAX.

MIN. 3-1/2" SLAB 2500 PSI
CONC. 6x6-10x10 W.W.M. OR
FIBER MESH

VAPOR BARRIER UNDER
CONCRETE



HEADER BEAM

(4) #10 x 1/2" S.M.S. EACH SIDE
OF POST

H-BAR OR GUSSET PLATE

2" x 2" OR 2" x 3" OR 2" S.M.B.
POST

MIN. (4) #10 x 1/2" S.M.S. @
EACH POST

1" x 2" EXTRUSION

1-1/8" MIN. IN CONCRETE

**ALTERNATE PATIO SECTION TO UPRIGHT AND
PATIO SECTION TO BEAM DETAIL**

SCALE: 3" = 1'-0"

Lawrence E. Bennett, P.E. FL # 16644

CIVIL & STRUCTURAL ENGINEERING

P.O. Box 214368, South Daytona, FL 32121

Telephone #: (386) 767-4774 Fax #: (386) 767-5336

Email: lebpc@bellsouth.net

COMPOSITE ROOF PANELS:
(4) 1/4" x 4" LAG BOLTS W/
1-1/4" FENDER WASHERS PER
4'-0" PANEL ACROSS THE
FRONT AND 24" O.C. ALONG
SIDES

RISER PANELS ATTACHED PER
CHAPTER 7

2" x 2" OR 2" x 3" HOLLOW

HEADER ATTACHED TO POST
W/ MIN. (3) #10 x 1-1/2" S.M.S.
IN SCREW BOSSES

GIRT AND KICK PLATE 2" x 2"
HOLLOW RAIL

2" x 2", 2" x 3" OR 3" x 2"
HOLLOW (SEE SPAN TABLES)

FOR SNAP EXTRUSIONS GIRT
ATTACHED TO POST WITH
MIN. (3) #10 x 1/2" S.M.S. IN
SCREW BOSSES

POST ATTACHED TO BOTTOM
W/ MIN. (3) #10 x 1-1/2"
S.M.S. IN SCREW BOSSES

1" x 2" OPEN BACK BOTTOM
RAIL

1/4" x 2-1/4" MASONRY
ANCHOR @ 6" FROM EACH
POST AND 24" O.C. (MAX.)

TYPICAL UPRIGHT DETAIL

SCALE: 3" = 1'-0"

Lawrence E. Bennett, P.E. FL # 16644

CIVIL & STRUCTURAL ENGINEERING

P.O. Box 214368, South Daytona, FL 32121

Telephone #: (386) 767-4774 Fax #: (386) 767-8556

Email: lebpe@bellsouth.net

SCREEN, ACRYLIC & VINYL ROOMS

SECTION 3A

Table 3A.1.1-120 Allowable Edge Beam Spans - Hollow Extrusions
For Screen or Vinyl Rooms

For 3 second wind gust at 120 MPH velocity; using design load of 15 #/SF (43 #/SF for Max. Cantilever)

2" x 2" x 0.044"					2" x 2" x 0.055"				
Load Width (ft.)	Max. Span 'L' / (bending 'b' or deflection 'd')				Load Width (ft.)	Max. Span 'L' / (bending 'b' or deflection 'd')			
	1 & 2 Span	3 Span	4 Span	Max. Cantilever		1 & 2 Span	3 Span	4 Span	Max. Cantilever
5	5'-1" d	6'-3" d	6'-4" d	1'-0" d	5	5'-4" d	6'-7" d	6'-9" d	1'-1" d
6	4'-9" d	5'-10" d	5'-11" b	0'-11" d	6	5'-0" d	6'-3" d	6'-4" d	1'-0" d
7	4'-6" d	5'-7" d	5'-6" b	0'-11" d	7	4'-9" d	5'-11" d	5'-11" b	0'-11" d
8	4'-4" d	5'-4" b	5'-1" b	0'-10" d	8	4'-7" d	5'-8" d	5'-7" b	0'-11" d
9	4'-2" d	5'-11" b	4'-10" b	0'-10" d	9	4'-5" d	5'-5" d	5'-3" b	0'-10" d
10	4'-0" d	4'-9" b	4'-7" b	0'-10" d	10	4'-3" d	5'-2" b	5'-0" b	0'-10" d
11	3'-11" d	4'-6" b	4'-4" b	0'-9" d	11	4'-1" d	4'-11" b	4'-9" b	0'-10" d
12	3'-9" d	4'-4" b	4'-2" b	0'-9" d	12	3'-11" d	4'-9" b	4'-7" b	0'-10" d
3" x 2" x 0.045"					3" x 2" x 0.070"				
Load Width (ft.)	Max. Span 'L' / (bending 'b' or deflection 'd')				Load Width (ft.)	Max. Span 'L' / (bending 'b' or deflection 'd')			
	1 & 2 Span	3 Span	4 Span	Max. Cantilever		1 & 2 Span	3 Span	4 Span	Max. Cantilever
5	5'-8" d	7'-1" d	7'-2" d	1'-2" d	5	6'-5" d	7'-11" d	8'-1" d	1'-3" d
6	5'-4" d	6'-8" d	6'-9" d	1'-1" d	6	6'-0" d	7'-5" d	7'-7" d	1'-2" d
7	5'-1" d	6'-4" d	6'-5" d	1'-0" d	7	5'-9" d	7'-1" d	7'-3" d	1'-2" d
8	4'-11" d	6'-0" d	6'-2" b	0'-11" d	8	5'-6" d	6'-9" d	6'-11" d	1'-1" d
9	4'-8" d	5'-10" d	5'-9" b	0'-11" d	9	5'-3" d	6'-6" d	6'-8" d	1'-1" d
10	4'-6" d	5'-7" d	5'-6" b	0'-11" d	10	5'-1" d	6'-3" d	6'-5" d	1'-0" d
11	4'-5" d	5'-5" b	5'-3" b	0'-10" d	11	4'-11" d	6'-1" d	6'-3" d	0'-11" d
12	4'-3" d	5'-2" b	5'-0" b	0'-10" d	12	4'-9" d	5'-11" d	5'-11" b	0'-11" d
2" x 3" x 0.045"					2" x 3" x 0.050"				
Load Width (ft.)	Max. Span 'L' / (bending 'b' or deflection 'd')				Load Width (ft.)	Max. Span 'L' / (bending 'b' or deflection 'd')			
	1 & 2 Span	3 Span	4 Span	Max. Cantilever		1 & 2 Span	3 Span	4 Span	Max. Cantilever
5	7'-1" d	8'-9" d	8'-9" b	1'-5" d	5	9'-2" d	11'-4" d	11'-2" b	1'-10" d
6	6'-8" d	8'-3" d	7'-11" b	1'-4" d	6	8'-8" d	10'-7" b	10'-3" b	1'-9" d
7	6'-4" d	7'-8" b	7'-5" b	1'-3" d	7	8'-2" d	9'-9" b	9'-5" b	1'-8" d
8	6'-1" d	7'-2" b	6'-11" b	1'-2" d	8	7'-10" d	9'-2" b	8'-10" b	1'-7" d
9	5'-10" d	6'-9" b	6'-6" b	1'-2" d	9	7'-6" d	8'-8" b	8'-4" b	1'-6" d
10	5'-7" d	6'-5" b	6'-2" b	1'-1" d	10	7'-3" d	8'-2" b	7'-11" b	1'-5" d
11	5'-5" d	6'-1" b	5'-11" b	1'-1" d	11	6'-11" b	7'-10" b	7'-7" b	1'-5" d
12	5'-3" b	5'-10" b	5'-8" b	1'-1" d	12	6'-8" b	7'-6" b	7'-3" b	1'-4" d

Notes:

- Above spans do not include length of knee brace. Add horizontal distance from upright to center of brace to beam connection to the above spans for total beam spans.
- Spans may be interpolated.

Lawrence E. Bennett, P.E. FL # 16644

CIVIL ENGINEER - DEVELOPMENT CONSULTANT
P.O. BOX 214368, SOUTH DAYTONA, FL 32121
TELEPHONE: (386) 767-4774
FAX: (386) 767-6556

SECTION 3A

SCREEN, ACRYLIC & VINYL ROOMS

Table 3A.2.1 Allowable Upright Heights, Chair Rail Spans or Header Spans
for Screen, Acrylic or Vinyl Rooms.
Aluminum Alloy 6063 T-5

or 3 second wind gust at 110 MPH velocity; using design load of 11 #/SF

Sections		Tributary Load Width 'W' = Purlin Spacing								
		3'-0"	3'-6"	4'-0"	4'-6"	5'-0"	5'-6"	6'-0"	6'-6"	7'-0"
		Allowable Height 'H' / bending 'b' or deflection 'd'								
2" x 2" x 0.044"	Hollow	9'-5" b	8'-9" b	8'-2" b	7'-8" b	7'-4" b	6'-11" b	6'-8" b	6'-5" b	6'-2" b
2" x 2" x 0.055"	Hollow	10'-3" b	9'-6" b	8'-11" b	8'-5" b	7'-11" b	7'-7" b	7'-3" b	6'-11" b	6'-9" b
2" x 2" x 0.045"	Hollow	11'-3" b	10'-5" b	9'-9" b	9'-3" b	8'-9" b	8'-4" b	7'-11" b	7'-8" b	7'-5" b
2" x 2" x 0.070"	Hollow	12'-9" d	12'-2" d	11'-7" d	10'-11" b	10'-5" b	9'-11" b	9'-6" b	9'-2" b	8'-10" b
2" x 3" x 0.045"	Hollow	12'-9" b	11'-9" b	11'-0" b	10'-5" b	9'-10" b	9'-5" b	8'-11" b	8'-8" b	8'-4" b
2" x 4" x 0.050"	Hollow	16'-3" b	15'-1" b	14'-1" b	13'-3" b	12'-7" b	12'-0" b	11'-6" b	11'-0" b	10'-8" b
2" x 4" x 0.046"	S.M.B.	19'-1" b	17'-8" b	16'-6" b	15'-7" b	14'-9" b	14'-1" b	13'-6" b	12'-11" b	12'-6" b
2" x 5" x 0.050"	S.M.B.	23'-7" b	21'-10" b	20'-5" b	19'-3" b	18'-3" b	17'-5" b	16'-8" b	16'-0" b	15'-5" b
2" x 6" x 0.050"	S.M.B.	26'-1" b	24'-2" b	22'-7" b	21'-3" b	20'-2" b	19'-3" b	18'-5" b	17'-9" b	17'-1" b
2" x 2" x 0.044"	Snap	11'-3" b	10'-5" b	9'-9" b	9'-2" b	8'-8" b	8'-3" b	7'-11" b	7'-7" b	7'-4" b
2" x 3" x 0.045"	Snap	14'-4" b	13'-4" b	12'-5" b	11'-9" b	11'-2" b	10'-7" b	10'-2" b	9'-9" b	9'-5" b
2" x 4" x 0.045"	Snap	17'-7" b	16'-3" b	15'-3" b	14'-4" b	13'-7" b	12'-11" b	12'-5" b	11'-11" b	11'-8" b


or 3 second wind gust at 120 MPH velocity; using design load of 13 #/SF

Sections		Tributary Load Width 'W' = Purlin Spacing								
		3'-0"	3'-6"	4'-0"	4'-6"	5'-0"	5'-6"	6'-0"	6'-6"	7'-0"
		Allowable Height 'H' / bending 'b' or deflection 'd'								
2" x 2" x 0.044"	Hollow	8'-8" b	8'-0" b	7'-6" b	7'-1" b	6'-8" b	6'-5" b	6'-1" b	5'-11" b	5'-8" b
2" x 2" x 0.055"	Hollow	9'-5" b	8'-9" b	8'-2" b	7'-9" b	7'-4" b	6'-11" b	6'-8" b	6'-5" b	6'-2" b
2" x 2" x 0.045"	Hollow	10'-5" b	9'-7" b	8'-11" b	8'-6" b	8'-0" b	7'-8" b	7'-4" b	7'-1" b	6'-10" b
2" x 2" x 0.070"	Hollow	12'-1" d	11'-5" d	10'-8" b	10'-1" b	9'-7" b	9'-2" b	8'-9" b	8'-5" b	8'-1" b
2" x 3" x 0.045"	Hollow	12'-10" b	11'-11" b	11'-2" b	10'-6" b	9'-11" b	9'-6" b	9'-1" b	8'-9" b	8'-5" b
2" x 4" x 0.050"	Hollow	14'-11" b	13'-10" b	12'-11" b	12'-2" b	11'-7" b	11'-0" b	10'-7" b	10'-2" b	9'-9" b
2" x 4" x 0.046"	S.M.B.	17'-6" b	16'-3" b	15'-2" b	14'-4" b	13'-7" b	12'-11" b	12'-5" b	11'-11" b	11'-8" b
2" x 5" x 0.050"	S.M.B.	21'-8" b	20'-1" b	18'-9" b	17'-9" b	16'-10" b	16'-0" b	15'-4" b	14'-9" b	14'-2" b
2" x 6" x 0.050"	S.M.B.	23'-11" b	22'-2" b	20'-9" b	19'-7" b	18'-7" b	17'-9" b	16'-11" b	16'-3" b	15'-8" b
2" x 2" x 0.044"	Snap	10'-4" b	9'-7" b	8'-11" b	8'-5" b	7'-11" b	7'-7" b	7'-4" b	7'-0" b	6'-9" b
2" x 3" x 0.045"	Snap	13'-3" b	12'-3" b	11'-5" b	10'-9" b	10'-3" b	9'-9" b	9'-4" b	8'-11" b	8'-8" b
2" x 4" x 0.045"	Snap	16'-2" b	14'-11" b	14'-0" b	13'-2" b	12'-6" b	11'-11" b	11'-5" b	10'-11" b	10'-7" b

- Notes:
1. Above spans do not include length of knee brace. Add horizontal distance from upright to center of brace to beam connection to the above spans for total beam spans.
 2. Spans may be interpolated.

Lawrence E. Bennett, P.E. FL # 16644

CIVIL ENGINEER - DEVELOPMENT CONSULTANT
P.O. BOX 214368, SOUTH DAYTONA, FL 32121
TELEPHONE: (386) 767-4774
FAX: (386) 767-6556

**ALTERNATE ROOF PANEL TO WALL DETAIL**

SCALE: 3" = 1'-0"

ROOF PANELS SHALL BE ATTACHED TO THE HEADER W/ (3) EACH #8 x 1/2" LONG CORROSION RESISTANT S.M.S. W/ 1/2" WASHERS. ALL SCREW HEADS SHALL BE CAULKED OR SHALL HAVE NEOPRENE GASKET BETWEEN THE WASHER AND THE PAN. PAN RIBS SHALL RECEIVE (1) EACH #8 x 1/2" SCREW EACH. THE PANS MAY BE ANCHORED THROUGH BOXED PAN W/ (3) EACH #8 x 1" OF THE ABOVE SCREW TYPES AND THE ABOVE SPECIFIED RIB SCREW.

Lawrence E. Bennett, P.E. FL # 16644

CIVIL ENGINEER - DEVELOPMENT CONSULTANT

P.O. BOX 214368, SOUTH DAYTONA, FL 32121

TELEPHONE: (386) 767-4774

FAX: (386) 767-6556

SECTION 7

SOLID ROOF PANEL PRODUCTS

Table 7.2.1

Allowable Spans for Elite Composite Roof Panels for Various Loads
 Elite Aluminum Corporation
 Statewide Product Approval #FL1049

Manufacturers' Proprietary Products: Aluminum Alloy 3105 H-14 or H-25 Foam Core E.P.S. #1 Density
 3" x 48" x 0.024" Panels Foam Core E.P.S. #1 Density

Wind Region	Open Structures Mono-Sloped Roof			Screen Rooms & Attached Covers			Glass & Modular Rooms Enclosed			Overhang / Cantilever All Roofs
	1&2 span	3 span	4 span	1&2 span	3 span	4 span	1&2 span	3 span	4 span	
100 MPH	21'-4"	23'-10"	23'-0"	20'-4"	22'-9"	21'-11"	15'-1"	17'-9"	16'-3"	4'-0"
110 MPH	21'-4"	23'-10"	23'-0"	18'-8"	20'-11"	20'-2"	13'-9"	15'-4"	14'-10"	4'-0"
120 MPH	20'-4"	22'-9"	21'-11"	17'-5"	19'-5"	18'-10"	12'-6"	13'-11"	13'-6"	4'-0"
123 MPH	19'-6"	21'-10"	21'-1"	15'-11"	18'-11"	18'-3"	11'-8"	13'-8"	13'-2"	4'-0"
130 MPH	18'-0"	20'-2"	19'-5"	15'-1"	17'-9"	16'-3"	11'-1"	12'-11"	12'-6"	4'-0"
140 MPH	12'-4"	13'-9"	13'-3"	12'-4"	13'-9"	13'-3"	10'-3"	11'-6"	11'-1"	4'-3"
150 MPH	12'-4"	13'-9"	13'-3"	12'-4"	13'-9"	13'-3"	9'-6"	10'-8"	10'-4"	3'-11"

3" x 48" x 0.030" Panels Foam Core E.P.S. #1 Density

Wind Region	Open Structures Mono-Sloped Roof			Screen Rooms & Attached Covers			Glass & Modular Rooms Enclosed			Overhang / Cantilever All Roofs
	1&2 span	3 span	4 span	1&2 span	3 span	4 span	1&2 span	3 span	4 span	
100 MPH	24'-11"	27'-11"	27'-0"	23'-10"	26'-8"	25'-9"	18'-8"	20'-10"	20'-2"	4'-0"
110 MPH	24'-11"	27'-11"	27'-0"	21'-11"	24'-6"	23'-8"	16'-2"	19'-3"	18'-8"	4'-0"
120 MPH	23'-10"	26'-8"	25'-9"	20'-5"	22'-10"	22'-1"	14'-8"	17'-8"	15'-10"	4'-0"
123 MPH	22'-11"	25'-7"	24'-9"	19'-10"	22'-2"	21'-5"	14'-4"	16'-0"	15'-6"	4'-0"
130 MPH	21'-2"	23'-7"	22'-10"	18'-8"	20'-10"	20'-2"	13'-7"	15'-2"	14'-8"	4'-0"
140 MPH	14'-5"	16'-2"	15'-7"	14'-5"	16'-2"	15'-7"	12'-8"	14'-2"	13'-8"	4'-0"
150 MPH	14'-5"	16'-2"	15'-7"	14'-5"	16'-2"	15'-7"	11'-2"	13'-2"	12'-9"	4'-0"

4" x 48" x 0.024" Panels Foam Core E.P.S. #1 Density

Wind Region	Open Structures Mono-Sloped Roof			Screen Rooms & Attached Covers			Glass & Modular Rooms Enclosed			Overhang / Cantilever All Roofs
	1&2 span	3 span	4 span	1&2 span	3 span	4 span	1&2 span	3 span	4 span	
100 MPH	23'-5"	26'-2"	25'-3"	22'-3"	24'-11"	24'-1"	17'-5"	19'-6"	18'-10"	4'-0"
110 MPH	23'-5"	26'-2"	25'-3"	20'-6"	22'-11"	22'-2"	15'-1"	18'-0"	17'-5"	4'-0"
120 MPH	22'-3"	24'-1"	24'-1"	19'-1"	21'-4"	20'-7"	13'-9"	15'-4"	14'-10"	4'-0"
123 MPH	21'-5"	23'-11"	23'-2"	18'-6"	20'-9"	20'-0"	13'-5"	14'-11"	14'-6"	4'-0"
130 MPH	19'-9"	22'-1"	21'-4"	17'-5"	19'-6"	18'-10"	12'-8"	14'-2"	13'-8"	4'-0"
140 MPH	13'-6"	15'-1"	14'-7"	13'-6"	15'-1"	14'-7"	11'-3"	13'-3"	12'-9"	4'-0"
150 MPH	13'-6"	15'-1"	14'-7"	13'-6"	15'-1"	14'-7"	10'-5"	12'-4"	11'-4"	4'-0"

4" x 48" x 0.030" Panels Foam Core E.P.S. #1 Density

Wind Region	Open Structures Mono-Sloped Roof			Screen Rooms & Attached Covers			Glass & Modular Rooms Enclosed			Overhang / Cantilever All Roofs
	1&2 span	3 span	4 span	1&2 span	3 span	4 span	1&2 span	3 span	4 span	
100 MPH	26'-11"	30'-1"	29'-1"	25'-8"	28'-9"	27'-9"	20'-1"	22'-5"	21'-8"	4'-0"
110 MPH	26'-11"	30'-1"	29'-1"	23'-8"	26'-5"	25'-6"	18'-7"	20'-9"	20'-1"	4'-0"
120 MPH	25'-8"	28'-9"	27'-9"	21'-11"	24'-7"	23'-9"	15'-10"	19'-1"	18'-5"	4'-0"
123 MPH	24'-8"	27'-7"	26'-8"	21'-4"	23'-11"	23'-1"	15'-5"	18'-6"	17'-11"	4'-0"
130 MPH	22'-9"	25'-5"	24'-7"	20'-1"	22'-5"	21'-8"	14'-7"	17'-5"	15'-9"	4'-0"
140 MPH	15'-7"	17'-5"	16'-10"	15'-7"	17'-5"	16'-10"	13'-8"	15'-3"	14'-9"	4'-0"
150 MPH	15'-7"	17'-5"	16'-10"	15'-7"	17'-5"	16'-10"	12'-9"	14'-9"	13'-11"	4'-0"

Note: Total roof panel width = room width + w

Lawrence E. Bennett, P.E. FL

CIVIL ENGINEER - DEVELOPMENT CON

P.O. BOX 214368, SOUTH DAYTON

TELEPHONE: (386) 7

FAX: (386) 7

OF LAWRENCE E. BENNETT, P.E.
 FL 33309
 Fax: (954) 491-1433

Table 9.1 Allowable Loads for Concrete Anchors

Table 9.1 Allowable Loads for Concrete				
Screw Size d = diameter	Embedment Depth (in.)	Min. Edge Dist. & Anchor Spacing 5d (in.)	Allowable Loads	
			Tension	Shear
ZAMAC NAILIN (Drive Anchors)				
1/4"	1-1/2"	1-1/4"	273#	236#
	2"	1-1/4"	316#	236#
TAPPER (Concrete Screws)				
3/16"	1-1/4"	15/16"	288#	167#
	1-3/4"	15/16"	371#	259#
1/4"	1-1/4"	1-1/4"	427#	200#
	1-3/4"	1-1/4"	544#	216#
3/8"	1-1/2"	1-7/8"	511#	402#
	1-3/4"	3-3/8"	703#	455#
POWER BOLT (Expansion Bolt)				
1/4"	2"	1-1/4"	624#	261#
5/16"	3"	1-7/8"	936#	751#
3/8"	3-1/2"	1-7/8"	1,575#	1,425#
1/2"	5"	2-1/2"	2,332#	2,220#
POWER STUD (Wedge Anchor)				
1/4"	2-3/4"	1-1/4"	812#	326#
3/8"	4-1/4"	1-7/8"	1,358#	921#
1/2"	6"	2-1/2"	2,271#	1,218#
5/8"	7"	2-1/4"	3,288#	2,202#

Notes:

- Concrete screws are limited to 2" embedment by manufacturers.
- Values listed are allowed loads with a safety factor of 4 applied.
- Products equal to rawl may be substituted.
- Anchors receiving loads perpendicular to the diameter are in tension.
- Allowable loads are increased by 1.00 for wind load.
- Minimum edge distance and center to center spacing shall be 5d.
- Anchors receiving loads parallel to the diameter are shear loads.
- A 133% increase has been applied because wind uplift is only load.

Example:

Determine the number of concrete anchors required for a pool enclosure by dividing the uplift load by the anchor allowed load.
For a 2" x 6" beam with: spacing = 7'-0" O.C.,
allowed span = 20'-5" (Table 1.1)

$$\text{UPLIFT LOAD} = 1/2(\text{BEAM SPAN}) \times \text{BEAM \& UPRIGHT SPACING}$$

$$\text{NUMBER OF ANCHORS} = \frac{1/2(20.42') \times 7' \times 10\# / \text{Sq. Ft.}}{\text{ALLOWED LOAD ON ANCHOR}}$$

$$\text{NUMBER OF ANCHORS} = \frac{714.70\#}{427\#} = 1.67$$

Therefore, use 2 anchors, one (1) on each side of upright.

Table is based on Rawl Products' allowable loads for 2,500 p.s.i. concrete.

Allowable Load Conversion Multipliers
for Edge Distances More Than 5d

Edge Distance	Multipliers	
	Tension	Shear
5d	1.00	1.00
6d	1.04	1.20
7d	1.08	1.40
8d	1.11	1.60
9d	1.14	1.80
10d	1.18	2.00
11d	1.21	-
12d	1.25	-

Lawrence E. Bennett, P.E. FL # 16644

CIVIL ENGINEER - DEVELOPMENT CONSULTANT
P.O. BOX 214368, SOUTH DAYTONA, FL 32121
TELEPHONE: (386) 767-4774
FAX: (386) 767-6556

Maronda Systems

4005 Maronda Way

(407) 321-0064

Fax (407) 321-3913

367 Medallion PL.

FL PE # 50068,



Design: Matrix Analysis

PLAN JOB #	LOT	ADDRESS	DIV/SUB	MODEL	DAVENPORT A-M
9TM01401	14-1	135SW BLACK MAPLE CT	JAX-9TM	DVPM4 LEFT	

This structure was designed in accordance with, and meets the requirements of TPI standards and the FLORIDA 2004 BUILDING CODE for 125 M.P.H. Wind Zone. Truss loading is in accordance with ASCE 7-02. These trusses are designed for an enclosed building.

The Truss Engineering package for the above referenced site was generated by the Truss Designer/Architect/MiTek/Trenco.

I, **Tomas Ponce, P.E.** the Architect/Engineer of Record for the above referenced lot
Have reviewed the package and confirmed that it matches the physical and structural
Parameters found on the set of permit drawings.

Truss ID	Run Date	Drawing Reviewed	Truss ID	Run Date	Drawing Reviewed	No. of Eng. Dwgs:	46
Layout	10/18/07	10/15/08	J	10/10/08	10/15/08	Roof Loads-	
V	07/27/05	10/15/08	JS	10/10/08	10/15/08	TC Live:	16.0 psf
HIP	11/02/06	10/15/08	JSA	10/10/08	10/15/08	TC Dead:	7.0 psf
S1	10/10/08	10/15/08	J1	10/10/08	10/15/08	BC Live:	10.0 psf
HS1	10/10/08	10/15/08	JS1	10/10/08	10/15/08	BC Dead:	10.0 psf
HS2	10/10/08	10/15/08	J2	10/10/08	10/15/08	Total	43.0 psf
HS3	10/10/08	10/15/08	JS2	10/10/08	10/15/08	DurFac- Lbr: 1.25 DurFac- Plt: 1.25 O.C. Spacing: 24.0"	
HS4	10/10/08	10/15/08	J3	10/10/08	10/15/08		
HS5	10/10/08	10/15/08	JS3	10/10/08	10/15/08	 DATE: OCT 29 2008	
HS6S	10/10/08	10/15/08	V1S	10/10/08	10/15/08		
HS7S	10/10/08	10/15/08	V2S	10/10/08	10/15/08		
HS8S	10/10/08	10/15/08	V3S	10/10/08	10/15/08		
HSGRD1S	10/10/08	10/15/08	V4S	10/10/08	10/15/08		
H1S	10/10/08	10/15/08	V6	10/10/08	10/15/08		
H2S	10/10/08	10/15/08	V7	10/10/08	10/15/08		
H3S	10/10/08	10/15/08	V8	10/10/08	10/15/08		
H4S	10/10/08	10/15/08					
H5S	10/10/08	10/15/08					
B1	10/10/08	10/15/08					
BGRD1	10/10/08	10/15/08					
GRD1	10/10/08	10/15/08					
T1	10/10/08	10/15/08					
G1	10/10/08	10/15/08					
H6	10/10/08	10/15/08					
HGRD1	10/10/08	10/15/08					
GRD2	10/10/08	10/15/08					
T2	10/10/08	10/15/08					
G2	10/10/08	10/15/08	INV #	DESC	QNTY	 DATE: OCT 29 2008	
JGRD1	10/10/08	10/15/08	50060.0048	THD26	15		
JSGRD1	10/10/08	10/15/08	50060.0047	THD28			
			50060.0050	THDH28-3	1		
			50060.0110	JUS26			
			50060.0058	THJ26	3		
			50060.0049	THD28-2	2		
						DATE:	
			SEAT PLATES			150	

HARDWARE LEGEND


- 1 HUS26
- 2 HUS28
- 3 JUS26
- 4 MP6F
- 5 MPA1 & MPA1F
- 6 SKH26 L/R
- 7 SKHH26 L/R
- 8 SUS26
- 9 SUS28
- 10 THD26
- 11 THD28
- 12 THD28-2
- 13 THDH28-3
- 14 THD48
- 15 THJ26**
- 16 LTW12

HARDWARE MANUFACTURED
BY USP

* HARDWARE MANUFACTURED
BY SIMPSON

** HARDWARE MANUFACTURED
BY CLEVELAND

OCT 29 2008



DAVENPORT ELEVATION "A" "M"-FL

GARAGE : LEFT

DESIGNER: WCA
CHECKER: MIKE

SCALE: 1/8" = 1'-0"
DATE: 10/18/2007


LOADING-FBC2004/TPI2002

TC LIVE	1600	SNOW LOAD	0.00
TC DEAD	700	LUMBER DOL	1.25
BC LIVE	1000	PLATE DOL	1.25
BC DEAD	1000	WIND	125
TOTAL	43.00	SPACING	2'-0"



COPYRIGHT © 2007 MARONDA HOMES

14071 321-0064 4005 MARONDA WAY SANFORD, FLORIDA



MITEK 2000
LUMBER
1800 848.3387 • mitek@itek.com

GENERAL NOTES

Trusses are not marked in any way to identify the frequency or location of temporary lateral restraint and diagonal bracing. Follow the recommendations for handling, installing and temporary restraining and bracing of trusses. Refer to BCSI Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for more detailed information.

Truss Design Drawings may specify locations of permanent lateral restraint or reinforcement for individual truss members. Refer to the BCSI-B3 Summary Sheet - Permanent Restraint/Bracing of Chords & Web Members for more information. All other permanent bracing design is the responsibility of the Building Designer.

Warning! The consequences of improper handling, erecting, installing, restraining and bracing can result in a collapse of the structure, or worse, serious personal injury or death.


El resultado de un manejo, levantamiento, instalación, restricción y arrioste incorrecto puede ser la caída de la estructura o aún peor, heridos o muertos.

Warning! Banding and truss plates have sharp edges. Wear gloves when handling and safety glasses when cutting banding.

"Empaques y placas de metal tienen bordes afilados. Use guantes y lentes protectores cuando corte los empaques."


HANDLING — MANEJO

Warning! Avoid lateral bending. — Evite la flexión lateral.



Warning! The contractor is responsible for properly receiving, unloading and storing the trusses at the jobsite.

El contratista tiene la responsabilidad de recibir, descargar y almacenar adecuadamente los trusses en la obra.



Warning! If trusses are to be stored horizontally, place blocking of sufficient height beneath the stack of trusses at 8' to 10' on center.

For trusses stored for more than one week, cover bundles to prevent moisture gain but allow for ventilation.

Refer to BCSI Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for more detailed information pertaining to handling and jobsite storage of trusses.

Si los trusses estarán guardados horizontalmente, ponga bloqueando de altura suficiente detrás de la pila de los trusses.



Para trusses guardados por más de una semana, cubra los paquetes para prevenir aumento de humedad pero permita ventilación.

Vea el folleto BCSI Guía de Buena Práctica para el Manejo, Instalación, Restricción y Arriostres de los Trusses de Madera Conectados con Placas de Metal para información más detallada sobre el manejo y almacenamiento de los trusses en área de trabajo.

NOTAS GENERALES


Los trusses no están marcados de ningún modo que identifique la frecuencia o localización de restricción lateral y arrioste diagonal temporales. Use las recomendaciones de manejo, instalación, restricción y arrioste temporal de los trusses. Vea el folleto BCSI Guía de Buena Práctica para el Manejo, Instalación, Restricción y Arrioste de los Trusses de Madera Conectados con Placas de Metal para información más detallada.

Los dibujos de diseño de los trusses pueden especificar las localizaciones de restricción lateral permanente o refuerzo en los miembros individuales del truss. Vea la hoja resumen BCSI-B3 - Restricción/Arrioste Permanente de Cuerdas y Miembros Secundarios para más información. El resto de los diseños de arriostres permanentes son la responsabilidad del Diseñador del Edificio.



Warning! Use special care in windy weather or near power lines and airports.

Utilice cuidado especial en días ventosos o cerca de cables eléctricos o de aeropuertos.




Warning! Use proper rigging and hoisting equipment.

Use equipo apropiado para levantar e improvisar.



Warning! Do not store unbraced bundles upright.

No almacene verticalmente los trusses sueltos.




Warning! Do not store on uneven ground.

No almacene en tierra desigual.



HOISTING RECOMMENDATIONS FOR TRUSS BUNDLES RECOMENDACIONES PARA LEVANTAR PAQUETES DE TRUSSES.

Warning! Don't overload the crane.
¡Advertencia! No sobrecargue la grúa!
Warning! Never use banding alone to lift a bundle.
Do not lift a group of individually banded bundles.
Nunca use sólo los empaques para levantar un paquete.
No levante un grupo de empaques individuales.



Warning! A single lift point may be used for bundles with trusses up to 45'.
Two lift points may be used for bundles with trusses up to 60'.
Use at least 3 lift points for bundles with trusses greater than 60'.


Puede usar un solo lugar de levantar para paquetes de trusses hasta 45 pies.
Puede usar dos puntos de levantar para paquetes más de 60 pies.
Use por lo menos tres puntos de levantar para paquetes más de 60 pies.

Warning! Do not over load supporting structure with truss bundle.
¡Advertencia! No sobrecargue la estructura apoyada con el paquete de trusses.


Warning! Place truss bundles in stable position.
Puse paquetes de trusses en una posición estable.

INSTALLATION OF SINGLE TRUSSES BY HAND INSTALACIÓN POR LA MANO DE TRUSSES INDIVIDUALES

Warning! Trusses 20' or less, support at peak.
Levante del pico los trusses de 20 pies o menos.



Warning! Trusses 30' or less, support at quarter points.
Levante de los cuartos de tramo los trusses de 30 pies o menos.



HOISTING OF SINGLE TRUSSES — LEVANTAMIENTO DE TRUSSES INDIVIDUALES

Warning! Hold each truss in position with the erection equipment until top chord temporary lateral restraint is installed and the truss is fastened to the bearing points.

Sostenga cada truss en posición con equipo de grúa hasta que la restricción lateral temporal de la cuerda superior esté instalada y el truss está asegurado en los soportes.




Warning! Using a single pick-point at the peak can damage the truss.

¡Advertencia! El uso de un solo lugar para levantar en el pico puede hacer daño al truss.



HOISTING RECOMMENDATIONS FOR SINGLE TRUSSES

RECOMENDACIONES PARA LEVANTAR TRUSSES INDIVIDUALES




TEMPORARY RESTRAINT & BRACING RESTRICCIÓN Y ARRIOSTRE TEMPORAL

Warning! Refer to BCSI-B2 Summary Sheet - Truss Installation & Temporary Restraint/Bracing for more information.

Vea el resumen BCSI-B2 - Restricción/Arrioste Temporal y Instalación de los Trusses para más información.


Warning! Locate ground braces for first truss directly in line with all rows of top chord temporary lateral restraint (see table in the next column).

Coloque los arriostres de tierra para el primer truss directamente en línea con cada una de las filas de restricción lateral temporal de la cuerda superior (vea la tabla en la próxima columna).



Warning! Do not walk on unbraced trusses.

No camine en trusses sueltos.



EL MANEJO, INSTALACION, RESTRICCIÓN Y ARRIOSTRE DE LOS TRUSSES (2006 EDICIÓN)

Maronda Systems

MARONDA SYSTEMS

4005 Maronda Way

Sanford, FL 32771

(407) 321-0064

Fax (407) 321-3913

Date: November 1, 2006

To: Building Department


From: Maronda Systems
Tomas Ponce
Professional Engineer
State of Florida #0050068

Subject: Valley Trusses

All valley trusses labeled V-1 through 100 are covered under the general valley sheet provided in the truss package signed and sealed by the engineer of record. The connections are noted on the structural info sheet of the plans. All criteria of the valley trusses are noted on the general sheet.

If you have any questions please feel free to call at 407-321-0064.

Sincerely,



Tomas Ponce, P.E.

Date: 11/1/06

STRONGBACKING PROVISIONS

Strongbacking is intended to enhance the performance of the truss by helping to limit differential deflection between adjacent trusses and to reduce vibration. Strongbacking is generally attached near the bottom of vertical webs or scabs at specified intervals and locations indicated on the Truss Design Drawing (TDD). ANSI/TPI 1 provides the following provisions for using strongbacking:

- ✓ The Building Designer specifies if strongbacking is required.
- ✓ Use a minimum 2x6 (nominal) lumber oriented with the depth vertical.
- ✓ Attach the strongbacking to each truss with a minimum of three (3) 16d common nails (0.162x3.5"). Shim the joint between the strongback and truss to ensure a solid connection.
- ✓ The strongbacking shall be as continuous as possible. When required to be cut, removed, or modified to allow for the installation of mechanical and/or plumbing lines, the continuity at the adjoining floor sections shall be maintained as specified by the Truss Designer.
- ✓ Spacing between strongbacking shall not exceed 10'.
- ✓ When specified to control vibration in floor assemblies, locate the strongbacking as stipulated on the Truss Design Drawing unless otherwise specified by the Building Designer.
- ✓ When specified to control deflection in floor assemblies, unless otherwise specified by the Truss Designer, install one strongback near the centerline of the truss clear span when the deflection due to live load exceeds 0.67" and install two strongbacks near the centerline of the clear span, or near the third points of the truss span, when the live load deflection exceeds 0.85".
- ✓ Floor trusses with ceilings attached that meet span/480 live load deflection criteria do not require strongbacking, unless required for a specific fire-rated assembly or specified in the Construction Documents.




FIGURE B7-12




FIGURE B7-14

- ✓ Attach the ends of each row of strongbacks to a wall or another secure end restraint.
- ✓ Many Truss Manufacturers will also include a supplemental tag, such as the one shown above, to further assist the erection/installation Contractor in correctly installing strongbacking.

LATERAL RESTRAINT & DIAGONAL BRACING ARE VERY IMPORTANT!



FIGURE B7-15

⊘ DO NOT WALK ON UNBRACED TRUSSES




FIGURE B7-13

This design is for an individual building component and has been based on information provided by the client. The designer disclaims any responsibility for damages as a result of faulty or incorrect information, specifications and/or designs furnished to the user designer by the client and the correctness or accuracy of this information as it

only relate to a specific project and accepts no responsibility or exercises no control with regard to fabrication, handling, shipment and installation of Unistrut. This strut has been designed as an individual building component in accordance with ANSI/PTI 1-1995 and NDS-97 to be incorporated as part of the building design by a building Designer (registered architect or professional engineer). When reviewed for approval by the building designer, the design loadings shown must be used. The design loadings shown are in agreement with the best building codes, local/national, required for steel or masonry walls. The design loadings are applied loads. Unistrut shows, strut has not been designed for storage or occupancy loads. The design assumes compression chords (top or bottom) are continuously braced by sheathing unless otherwise specified. Where bottom chords in tension are not fully braced laterally by a properly applied rafter ceiling, they should be braced at a maximum spacing of 10'-0". Also, connector plates shall be manufactured from 20 gauge hot galvanized steel, meeting ASTM A 652, Grade 40, unless otherwise shown.

Prior to fabrication, use fabricator mail review this drawing to verify that this drawing is in conformance with the fabricator's plans and to realize a continuing responsibility for plan verification. Any discrepancies are to be put in writing before cutting or fabrication. Plates shall not be installed over blemishes, holes or distorted grain. Members shall be cut for tight fitting to wood framing. Connector plates shall be flared on both faces of the joist. The minimum thickness of the plates shall be the joist ultimate allowable stress. A 54k plate is 1/2" thick. The joist ultimate allowable stress is 54k. (Point load) The joist ultimate allowable stress is 54k. A 64k plate is 3/4" thick. A 64k plate is 3/4" thick. Double cut on web members to the plate length specified. Double cut on web members shall meet at the centroid of the webs unless otherwise shown. Connector plate sizes are minimum sizes based on the forces shown and may need to be increased for certain handling and/or erection stresses. This steel is not to be fabricated with fire retardant treated lumber unless otherwise shown. For additional information, refer to the National Quality Center web site.

1/2001

ANSI/ITPA

All breeding and erection recommendations are to be followed in accordance with "Handling, Lashing and Securing," HB-91. Trusses are to be handled with particular care during breeding and delivery, and installation for avoid damage. Temporary and permanent bracing to hold trusses in a upright and plumb position and for resisting lateral forces shall be designed and installed by others. Careful handling is essential and trusses are to be protected from damage. Normal precautionary erection bracing is always required. Normal precautionary action for trusses requires such temporary bracing and shoring as may be necessary to prevent buckling and to maintain the trusses in the desired position. The use of temporary bracing shall be determined by the engineer in charge of the erection. The use of temporary bracing shall be approved by the engineer in charge of the erection. The use of temporary bracing shall be approved by the engineer in charge of the erection. If needed, Concentration of construction loads greater than the design loads shall not be applied to trusses at any time. No loads other than the weight of the trusses shall be applied to trusses until after all fastening and bracing is completed.

TOP CHORDS: 2X4 SP #2
BOT CHORDS: 2X4 SP #2
WEBS: 2X4 SP #3

T/C MUST BE CONTINUOUSLY BRACED
BY ROOF SHEATHING UNLESS NOTED
OTHERWISE.

VALLEY MEMBERS TO BE SET
PERPENDICULAR TO TRUSSES BELOW.

IT IS NOT REQUIRED TO SHEATH TRUSSES
BELOW VALLEY SET. VALLEY MEMBERS
PROVIDE ALL NECESSARY TOP CHORD
BRACING.

WHEN VALLEY MEMBERS ARE NAILED DIRECTLY TO TRUSS TOP CHORDS USE (2) 16D NAILS PER INTERSECTION, OR TWO FEET ON CENTER.

WHEN BELOW TRUSSES ARE SHEATHED FIRST USE (2) 10d NAILS OR (1) 16d NAIL PER INTERSECTION, OR TWO FEET ON CENTER.

2x4 TRANSVERSE BRACING NAILED FLAT TO EDGE OF WEB WITH 12d NAILS AT 8" O.C. OR A SCAB OF THE SAME DIMENSION AND GRADE AS WEB; NAILED TO FACE (S) OF WEB WITH 10d NAILS STAGGERED 16" O.C. SCAB OR TRANSVERSE BRACING TO EXTEND FOR 30% OF WEB LENGTH. 2x8 BRACE REQUIRED ON ANY WEB EXCEEDING 14'.

... denotes ONE edge or one face
... denotes BOTH edges or Both faces

(1) ONE BRACE REQUIRED ON WEBS $\geq 94.0'$ LONG
(2) TWO BRACES REQ'D ON WEBS $\geq 128.0'$ LONG. "

VALLEY TRUSSES ARE ACCEPTABLE TO BE
CANTILEVERED UP TO TWO FEET.

[illegible]

T
F LESS THEN 3.0-0 THEN MOVE
DIAGONAL WEB TO NEXT PANEL.

DIAGONAL WEBS REQUIRED WITH SPANS GREATER THAN 28-0-0

VALLEY MEMBERS AT
24 * O.C. (TYP)

COMMON TRUSSES (TYP.)

* VALLEY STRAPPING TO TRÜBS BELOW

4' 0.0.

WO: VALLEY SET

6.2540

6.2540

2X4 TRANSVERSE BRACING NAILED FLAT TO EDGE OF WEB WITH 12d NAILS AT 8" O.C. OR A SCAB OF THE SAME DIMENSION AND GRADE AS WEB: NAILED TO FACE (S) OF WEB WITH 10d NAILS STAGGERED 8" O.C. SCAB OR TRANSVERSE BRACING TO EXTEND FOR 30% OF WEB LENGTH. 2X8 BRACE REQUIRED ON ANY WEB EXCEEDING 14'. COMMON

U
U
U
C
E
O
E
E
O
O

(1) ONE BRACE REQUIRED ON WEBS $\geq 94.0'$ LONG
(2) TWO BRACES REQ'D ON WEBS $\geq 128.0'$ LONG. "

VALLEY TRUSSES ARE ACCEPTABLE TO BE
CANTILEVERED UP TO TWO FEET.

VALLEY TRUSSES (TYP.)

SUPPORTING TRUSSES

MONO VALLEY

RED UP TO TWO FEET.

T
F LESS THEN 3.0-0 THEN MOVE
DIAGONAL WEB TO NEXT PANEL.

DIAGONAL WEBS REQUIRED WITH SPANS GREATER THAN 28-0-0

VALLEY MEMBERS AT
24 * O.C. (TYP)

COMMON TRUSSES (TYP.)

* VALLEY STRAPPING TO TRÜBS BELOW

4' 0, 0,

DEC 17 2005

EXCEPT AS SHOWN PLATES ARE TL20 GA TESTED PER ANSI/TPI 1-1995

Cont. Support Studs @ 6'-0" O.C.

WARNING:

[illegible]

Maronda Systems

4005 MARONDA WAY

Sanford, FL 32771
(407) 321-0064 Fnx (407) 321-3913
TOMAS PONCE P.E. LICENSE #0050068
1005 VANNESSA DR. OVIEDO FL 32766

Design: Matrix Analysis

Profile Path: C:\TEE-LOX\work\Jobs\MARONDA SYSTEMS\VT.PRJ

Eng Job:	WO: VALLEY SET		
Dwg:	TI: V		
Dsgn: RTLY	Chk:	7/27/2005	
TC Live	16.0	psf	Lbr DF: 1.25
TC Dead	7.0	psf	Plt DF: 1.25
BC Live	10.0	psf	O.C.: 2 - 0 - 0
BC Dead	2.0	psf	TPI-02/FBC-04
TOTAL	35.0	psf	Code: FLA
			V4.7.214355

DESIGN INFORMATION

This design is for an individual building component and has been based on information provided by the client. The engineer disclaims any responsibility for damages as a result of faulty or incorrect information, specifications and/or designs furnished to the team designer by the client and the correctness or accuracy of this information as it may relate to a specific project and accepts no responsibility or warranties no controls with regard to

[illegible]

FABRICATION NOTES—

Prior to fabrication, the fabricator shall review this drawing to verify that all drawings in a consultation with the architect's plans are consistent in detailing. The fabricator shall verify that all dimensions and tolerances are within the manufacturer's tolerances. Fabricators shall not be liable for variations in board or equipment size and shall not be furnished over finished or damaged panels. Members shall be cut for light fitting used to wood grain. Members shall be cut to fit the wall faces of the trim with mill-finish inboard and shall be cut to fit the joint between members. A 5/4 inch (12.7 mm) x 4" long, A fast piece is 6" wide x 1/2" long. Double cut on members shall meet at the perimeter of the glass unit. All members shall meet at the perimeter of the glass unit. Members shall be cut to fit the wall faces of the trim with mill-finish inboard and shall be cut to fit the joint between members. A 5/4 inch (12.7 mm) x 4" long, A fast piece is 6" wide x 1/2" long. Double cut on members shall meet at the perimeter of the glass unit. All members shall meet at the perimeter of the glass unit. Members shall be cut to fit the wall faces of the trim with mill-finish inboard and shall be cut to fit the joint between members. A 5/4 inch (12.7 mm) x 4" long, A fast piece is 6" wide x 1/2" long. Double cut on members shall meet at the perimeter of the glass unit. All members shall meet at the perimeter of the glass unit.

PRECAUTIONARY NOTES

All breeding and erection recommendations are to be followed in accordance with accepted industry publications. Trusses are to be handled with particular care during bundling and bundling, delivery and installation to avoid damage. Temporary and permanent bracing for holding trusses in a straight and plumb position and for retaining lateral forces shall be designed and installed by others. Careful handling is essential and erection bracing is always required. Normal precambering for trusses requires cast temporary bracing during installation between trusses to avoid toppling and dismounting. The supervision of erection of trusses shall be under the control of persons experienced in the installation of trusses. Precautionary advice shall be sought if needed. Consumption of construction loads greater than the design loads shall not be applied to trusses at any time. No load other than the weight of the erections shall be applied to trusses until after all bracing and bracing is completed.



HIP TRUSS BLOCKING REQUIREMENTS

APA-FORM NO. TT-083

SPAN RATING AND BLOCKING RECOMMENDATIONS FOR USE OVER HIP-ROOFS SUPPORT AT 24" O.C.

Roof Slope	Panel Span Rating			48/24
	24/18	32/18	40/20	
≤ 1:12	OK	OK	OK	OK
≤ 2:12	OK	OK	OK	OK
≤ 3:12	OK	OK	OK	OK
≤ 4:12	OK	OK	OK	OK
≤ 5:12	OK	OK	OK	OK
≤ 6:12	OK	OK	OK	OK
≤ 8:12	OK	OK	OK	OK
≤ 7:12	OK	OK	OK	OK
≤ 8:12	OK	OK	OK	OK
≤ 9:12	OK	OK	OK	OK
≤ 10:12	OK	OK	OK	OK
≤ 11:12	OK	OK	OK	OK
≤ 12:12	OK	OK	OK	OK
≤ 13:12	OK	OK	OK	OK
≤ 14:12	OK	OK	OK	OK

NOTE: SHADED AREA REPRESENTS LUMBER BLOCKING BETWEEN TRUSS AT UN SUPPORTED PANTEL. EDGES IN HTT BOOE ATTACH



NOTE: NO BLOCKING IS REQUIRED ON 4/12 AND BELOW PITCHED ROOFS

Maronda Systems
4005 MARONDA WAY
Sanford, FL 32771
(407) 321-0064 Fax (407) 321-3913
TOMAS PONCE P.E. LICENSE #0050068
367 Medallion Pl. Chula Vista, FL 32766

WARNING:
READ ALL NOTES ON THIS SHEET. A COPY OF THIS DRAWING TO BE GIVEN TO
ERECTING CONTRACTORS. BRACING WARNING.
Bracing shown on this drawing is not section bracing, wall bracing, portal bracing or similar bracing which is a part of the building design and which must be considered by the building designer. Bracing shown is for lateral support of truss members only to reduce buckling length. Provisions must be made to anchor lateral bracing at ends and specified locations determined by the building designer. Additional bracing of the overall structure may be required. (See HBH-91
171 for details.) For contact building designer (Truss Panel Institute, 171 E. Second St.,
Oshkosh, Wis., Madison, Wisconsin 53101).
Component Engineering, Truss Engineering Co., P.A., 818 Southside Rd., Education, NC 27922

Eng Job:	WO: HRPDETAIL		
Dwg:	TI: HIP		
Dsgnr: TLY	Chk:	11/2/2006	
TC Live	16.0	psf	Lbr DF: 1.25
TC Dead	7.0	psf	Plt DF: 1.25
BC Live	10.0	psf	O.C.: 2 - 0 - 0
BC Dead	10.0	psf	TPI-02/FBC-04
			Code: FLA
TOTAL	43.0	psf	V4.7.32-0

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
 DAVENPORT S1 SPECIAL 8 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
 7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:53 2008 Page 1

1-0-0 6-6-4 12-0-6 16-11-1 23-0-0 26-0-0 32-1-7 39-0-0 46-0-0 47-0-0
 1-0-0 6-6-4 5-6-2 4-10-11 6-0-15 3-0-0 6-1-7 6-10-9 7-0-0 1-0-0
 Scale = 1/78.3




Plate Offsets (X,Y): [4:0-3-0,Edge], [10:0-3-0,Edge], [12:0-3-4,0-2-0], [14:0-5-0,0-4-8], [17:0-5-0,0-4-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.77	Vert(LL)	-0.38 14-15	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.95	Vert(TL)	-0.76 14-15	>616	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.87	Horz(TL)	-0.32 18	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)					Weight: 276 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 6 SYP No.2
 WEBS 2 X 4 SYP No.2 *Except*
 W7 2 X 4 SYP No.1D

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-6-8 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 5-4-2 oc bracing.
 WEBS 1 Row at midpt 5-18

REACTIONS

(lb/size) 2=-625/0-8-0, 18=3055/0-8-6, 12=1596/0-8-6
 Max Horz 12=162(LC 6)
 Max Uplift 2=-653(LC 11), 18=-583(LC 6), 12=-390(LC 7)
 Max Grav 2=64(LC 7), 18=3055(LC 1), 12=1596(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/14, 2-3=-618/2149, 3-4=-466/2002, 4-5=-455/2090, 5-6=-1386/469, 6-7=-2057/686, 7-8=-2021/710, 8-9=-2886/854, 9-10=-4276/1198, 10-11=-4337/1186, 11-12=-4570/1410, 12-13=0/11
 BOT CHORD 2-18=-1893/647, 17-18=-41/727, 16-17=-240/1600, 15-16=-401/2605, 14-15=-845/3528, 12-14=-1191/4183
 WEBS 3-18=-391/323, 5-18=-3513/938, 5-17=-131/1055, 6-17=-799/305, 6-16=-61/470, 7-16=-356/1318, 8-16=-1616/451, 8-15=-306/1593, 9-15=-930/458, 9-14=-54/797, 11-14=-176/331


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 653 lb uplift at joint 2, 583 lb uplift at joint 18 and 390 lb uplift at joint 12.

LOAD CASE(S) Standard

[Signature]

OCT 15 2008



Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001


DAVENPORT HS1 SPECIAL 2 1

Job Reference (optional)

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:32 2008 Page 1

Maronda Homes Inc., Sanford, Florida

-1-0-0 6-8-6 13-10-3 21-0-0 25-0-0 31-10-13 38-9-11 46-0-0 47-0-0
1-0-0 6-8-6 7-1-13 7-1-13 4-0-0 6-10-13 6-10-13 7-2-5 1-0-0
Scale = 1/79.6



6-4-3 6-8-6 13-10-3 21-0-0 26-0-0 35-10-4 46-0-0
6-4-3 0-4-3 7-1-13 7-1-13 5-0-0 9-10-4 10-1-12

Plate Offsets (X,Y): [4:0-3-0,Edge], [6:0-5-12,0-2-8], [7:0-3-0,0-2-4], [9:0-3-0,Edge], [11:0-3-5,0-2-0], [13:0-5-0,0-4-8], [14:0-2-12,0-3-12], [15:0-5-0,0-4-8], [17:0-5-0,0-0-13]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.76	Vert(LL)	-0.36 13-14	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.92	Vert(TL)	-0.73 13-14	>645	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.70	Horz(TL)	-0.27 17	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 269 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-6-5 oc purlins.
BOT CHORD Rigid ceiling directly applied or 5-0-0 oc bracing.

REACTIONS

(lb/size) 2=-672/0-8-0, 17=3124/0-8-6, 11=1575/0-8-6
Max Horz 11=150(LC 6)
Max Uplift2=-714(LC 11), 17=-554(LC 6), 11=-379(LC 7)
Max Grav2=48(LC 7), 17=3124(LC 1), 11=1575(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=0/14, 2-3=-616/2280, 3-4=-1171/387, 4-5=-1055/399, 5-6=-1961/681, 6-7=-2375/825, 7-8=-2796/861, 8-9=-4155/1221, 9-10=-4268/1210, 10-11=-4501/1408, 11-12=0/11
BOT CHORD 2-17=-2010/643, 16-17=-2191/709, 15-16=-132/1059, 14-15=-239/1785, 13-14=-849/3418, 11-13=-1187/4120
WEBS 3-17=-2404/857, 3-16=-828/3234, 5-16=-992/452, 5-15=-127/848, 6-15=-267/127, 6-14=-227/1020, 8-14=-913/473, 8-13=-73/834, 10-13=-173/316, 7-14=-126/831

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearing at joint(s) 11 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 714 lb uplift at joint 2, 554 lb uplift at joint 17 and 379 lb uplift at joint 11.

LOAD CASE(S) Standard

OCT 15 2008




Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
DAVENPORT HS2 SPECIAL 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:33 2008 Page 1

-1-0-0 6-8-6 12-10-3 19-0-0 27-0-0 33-2-13 39-5-11 46-0-0 47-0-0
1-0-0 6-8-6 6-1-13 6-1-13 8-0-0 6-2-13 6-2-13 6-6-5 1-0-0
Scale = 1.79 6



6-4-3 6-8-6 12-10-3 19-0-0 26-0-0 35-10-4 46-0-0
6-4-3 0-4-3 6-1-13 6-1-13 7-0-0 9-10-4 10-1-12

Plate Offsets (X,Y): [4:0-3-0,Edge], [6:0-5-4,0-2-4], [7:0-3-8,0-2-4], [9:0-3-0,Edge], [10:0-0-0,0-0-0], [11:0-3-4,0-2-0], [13:0-5-0,0-4-8], [15:0-5-0,0-4-8], [17:0-5-0,0-0-13]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.74	Vert(LL)	-0.36 13-14	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.94	Vert(TL)	-0.72 13-14	>652	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.90	Horz(TL)	-0.28 17	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 265 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-8-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 4-9-11 oc bracing.

REACTIONS

(lb/size) 17=3204/0-8-6, 2=-741/0-8-0, 11=1563/0-8-6
Max Horz 11=137(LC 6)
Max Uplift 17=-566(LC 5), 2=-799(LC 11), 11=-368(LC 7)
Max Grav 17=3204(LC 1), 2=45(LC 7), 11=1563(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 7-8=-2819/907, 8-9=-4161/1218, 9-10=-4224/1208, 10-11=-4432/1437, 11-12=0/11, 6-7=-2705/902,
1-2=0/14, 2-3=-678/2453, 3-4=-846/279, 4-5=-785/297, 5-6=-1817/661
BOT CHORD 13-14=-911/3564, 11-13=-1217/4053, 16-17=-2355/768, 15-16=-43/758, 14-15=-261/1669,
2-17=-2169/701
WEBS 10-13=-135/314, 8-13=-7/660, 8-14=-977/423, 7-14=-48/744, 6-14=-293/1348, 6-15=-423/217,
5-15=-253/1105, 5-16=-1173/481, 3-16=-813/3094, 3-17=-2463/873


NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearing at joint(s) 11 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 566 lb uplift at joint 17, 799 lb uplift at joint 2 and 368 lb uplift at joint 11.

LOAD CASE(S) Standard

[Signature]

OCT 15 2008




Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT HS3 SPECIAL 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:34 2008 Page 1

-1-0-0 6-8-6 12-10-3 19-0-0 25-1-8 33-2-13 39-5-11 46-0-0 47-0-0
1-0-0 6-8-6 6-1-13 6-1-13 6-1-8 8-1-5 6-2-13 6-6-5 1-0-0
Scale = 1:79.6



6-4-3 6-8-6 12-10-3 19-0-0 25-1-8 26-10-8 36-3-8 46-0-0
6-4-3 0-4-3 6-1-13 6-1-13 6-1-8 1-9-0 9-5-0 9-8-8

Plate Offsets (X,Y): [4:0-3-0,Edge], [6:0-5-12,0-2-8], [8:0-3-0,0-2-4], [10:0-3-0,Edge], [11:0-0-0,0-0-0], [12:0-3-4,0-2-0], [14:0-5-0,0-4-8], [15:0-5-4,0-3-12], [17:0-5-0,0-4-8], [19:0-5-0,0-0-13]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.76	Vert(LL)	-0.35 14-15	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.94	Vert(TL)	-0.70 14-15	>669	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.67	Horz(TL)	-0.27 19	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 277 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-8-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 4-9-13 oc bracing.

REACTIONS

(lb/size) 19=3199/0-8-6, 2=-736/0-8-0, 12=1564/0-8-6
Max Horz 12=137(LC 6)
Max Uplift 19=-566(LC 5), 2=-794(LC 11), 12=-368(LC 7)
Max Grav 19=3199(LC 1), 2=43(LC 7), 12=1564(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 8-9=-2923/925, 9-10=-4197/1239, 10-11=-4260/1228, 11-12=-4448/1424, 12-13=0/11, 6-7=-2553/893,
7-8=-2666/906, 1-2=0/14, 2-3=-677/2443, 3-4=-850/282, 4-5=-790/301, 5-6=-1819/656
BOT CHORD 14-15=-923/3558, 12-14=-1205/4064, 15-16=-479/2539, 18-19=-2345/768, 17-18=-47/763,
16-17=-252/1655, 2-19=-2160/701
WEBS 11-14=-110/286, 9-14=-19/668, 9-15=-901/435, 7-15=-129/388, 7-16=-525/187, 6-16=-311/1240,
6-17=-393/209, 5-17=-239/1091, 5-18=-1177/483, 3-18=-816/3092, 3-19=-2457/872, 8-15=-180/893


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 566 lb uplift at joint 19, 794 lb uplift at joint 2 and 368 lb uplift at joint 12.


LOAD CASE(S) Standard

[Signature]

OCT 15 2008



Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001				
DAVENPORT	HS4	SPECIAL	1	1	Job Reference (optional)				
Maronda Homes Inc., Sanford, Florida					7.030 s Mar 11 2008 MITek Industries, Inc. Fri Oct 10 14:33:34 2008 Page 1				
-1-0-0	6-8-6	11-10-3	17-0-0	23-1-8	29-0-0	34-6-13	40-1-11	46-0-0	47-0-0
1-0-0	6-8-6	5-1-13	5-1-13	6-1-8	5-10-8	5-6-13	5-6-13	5-10-5	1-0-0
Scale = 1:79.6									



6-4-3	6-8-6	11-10-3	17-0-0	23-1-8	28-10-8	37-3-8	46-0-0
6-4-3	0-4-3	5-1-13	5-1-13	6-1-8	5-9-0	8-5-0	8-8-8

Plate Offsets (X,Y): [4:0-3-0,Edge], [6:0-5-12,0-2-8], [8:0-3-0,0-2-4], [10:0-3-0,Edge], [11:0-0-0,0-0-0], [12:0-3-4,0-2-0], [14:0-5-0,0-4-8], [17:0-5-0,0-4-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.77	Vert(LL)	-0.34 14-15	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.95	Vert(TL)	-0.67 14-15	>693	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.54	Horz(TL)	-0.27 19	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
									Weight: 271 lb

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 2-9-7 oc purlins.
BOT CHORD 2 X 6 SYP No.2	BOT CHORD Rigid ceiling directly applied or 4-7-1 oc bracing.
WEBS 2 X 4 SYP No.2	

REACTIONS (lb/size) 19=3305/0-8-6, 2=-827/0-8-0, 12=1549/0-8-6
 Max Horz 12=124(LC 6)
 Max Uplift 19=-628(LC 5), 2=-901(LC 11), 12=-355(LC 7)
 Max Grav 19=3305(LC 1), 2=38(LC 7), 12=1549(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 8-9=-3175/1032, 9-10=-4217/1270, 10-11=-4265/1258, 11-12=-4383/1417, 12-13=0/11, 6-7=-2617/938,
 7-8=-2910/1002, 1-2=0/14, 2-3=-757/2667, 3-4=-442/154, 4-5=-388/169, 5-6=-1536/586
 BOT CHORD 14-15=-988/3655, 12-14=-1201/3993, 15-16=-578/2633, 18-19=-2557/845, 17-18=0/384,
 16-17=-217/1399, 2-19=-2365/775
 WEBS 11-14=-26/232, 9-14=-3/525, 9-15=-748/361, 7-15=-148/400, 6-16=-445/1571, 6-17=-619/282,
 5-17=-346/1325, 5-18=-1381/527, 3-18=-794/2940, 3-19=-2530/891, 8-15=-169/945, 7-16=-532/304


NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 628 lb uplift at joint 19, 901 lb uplift at joint 2 and 355 lb uplift at joint 12.

LOAD CASE(S) Standard

[Signature]


OCT 15 2008



Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:35 2008 Page 1

1-0-0 6-8-6 10-10-3 15-0-0 21-1-8 26-0-12 31-0-0 38-4-4 46-0-0 47-0-0
1-0-0 6-8-6 4-1-13 4-1-13 6-1-8 4-11-4 4-11-4 7-4-4 7-7-12 1-0-0
Scale = 1:79.7



6-4-3	6-8-6	15-0-0	21-1-8	30-10-8	38-4-4	46-0-0
6-4-3	0-4-3	8-3-10	6-1-8	9-9-0	7-5-12	7-7-12

Plate Offsets (X,Y): [3:0-3-0,Edge], [6:0-5-12,0-2-8], [9:0-3-0,0-2-4], [11:0-3-0,Edge], [13:0-1-11,0-3-0], [13:0-0-0,0-0-0], [17:0-5-4,0-3-8]

LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase 1.25	TC 0.81	Vert(LL) -0.35 16-17	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.76	Vert(TL) -0.72 16-17	>654	180		
BCLL 10.0	Rep Stress Incr YES	WB 0.65	Horz(TL) -0.30 19	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002	(Matrix)				Weight: 269 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2
SLIDER Right 2 X 4 SYP No.2 4-0-13

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 4-9-3 oc bracing.
WEBS	1 Row at midpt 5-19

REACTIONS

(lb/size) 13=1561/0-8-6, 19=3296/0-8-6, 2=-831/0-8-0
Max Horz 13=112(LC 6)
Max Uplift 13=-345(LC 7), 19=-666(LC 5), 2=-929(LC 11)
Max Grav 13=1561(LC 1), 19=3296(LC 1), 2=49(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 9-10=-3594/1160, 10-11=-4335/1394, 11-12=-4362/1386, 12-13=-4430/1377, 13-14=0/11,
6-7=-2803/1009, 7-8=-2802/1009, 8-9=-3309/1137, 1-2=0/14, 2-3=-784/2564, 3-4=-760/2617,
4-5=-636/2529, 5-6=-1283/508

BOT CHORD 15-16=-1167/4071, 13-15=-1164/4050, 16-17=-842/3157, 18-19=-201/111, 17-18=-178/1179,
2-19=-2325/800


WEBS 10-15=0/27, 8-16=-85/230, 8-17=-492/213, 6-17=-602/1970, 6-18=-844/365, 5-18=-348/1509,
5-19=-3271/1034, 4-19=-407/315, 7-17=-270/252, 9-16=-163/1024, 10-16=-722/349

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDF=4.2psf; BCDL=6.0psf; Category II; Exp B; **enclosed**; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearing at joint(s) 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 345 lb uplift at joint 13, 666 lb uplift at joint 19 and 929 lb uplift at joint 2.

LOAD CASE(S) Standard

OCT 15 2008



Job Reference (optional)

7-0-0 13-1-8 20-0-12 33-4-4 40-0-0 41-0-0

7-0-0 6-1-8 6-11-4 13-3-8 6-7-12 1-0-0

Scale = 1:68.4



Plate Offsets (X,Y): [2:0-5-12,0-2-8], [4:0-4-0,0-3-0], [5:0-3-0,0-2-4], [8:0-0-0,0-0-0], [8:0-0-11,0-4-4], [11:0-5-4,0-3-12], [13:0-5-4,0-3-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.72	Vert(LL)	-0.46 11-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.82	Vert(TL)	-0.91 11-12	>522	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.68	Horz(TL)	-0.42 15	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)					Weight: 262 lb	

TOP CHORD	2 X 4 SYP No.2 *Except*
	T4 2 X 4 SYP No.1D
BOT CHORD	2 X 6 SYP No.2 *Except*
	F1 2 X 4 SYP No.2
WEBS	2 X 4 SYP No.2
SLIDER	Right 2 X 4 SYP No.2 3-2-6

TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-1-12 oc bracing.
JOINTS	1 Brace at Jt(s): 14

(lb/size) 8=1764/0-8-6, 15=1698/0-3-8
Max Horz 8=-174(LC 7)
Max Uplift 8=-352(LC 5), 15=-328(LC 5)

TOP CHORD	5-6=-4644/1622, 6-7=-5044/1691, 7-8=-5096/1680, 8-9=0/11, 2-3=-4312/1587, 3-4=-4312/1587, 4-5=-4311/1567, 1-2=-2478/875, 1-15=-1576/614
BOT CHORD	10-11=-1609/4680, 8-10=-1600/4653, 12-13=-1652/4884, 11-12=-1652/4883, 14-15=-69/137, 13-14=-736/2255
WEBS	6-10=0/167, 6-11=-340/245, 4-11=-811/246, 4-12=0/278, 4-13=-677/223, 2-13=-838/2415, 2-14=-546/351, 1-14=-685/2174, 3-13=-304/268, 5-11=-332/1419

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); $h=25ft$; $TCDL=4.2psf$; $BCDL=6.0psf$; Category II; Exp B; **enclosed**; MWFRS (low-rise) and C-C Interior(1) zone; Lumber $DOL=1.60$ plate grip $DOL=1.60$. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearing at joint(s) 8, 15 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 352 lb uplift at joint 8 and 328 lb uplift at joint 15.


LOAD CASE(S) Standard

OCT 15 2008



5-0-0	11-1-8	20-0-12	29-0-0	34-4-4	40-0-0	41-0-0
5-0-0	6-1-8	8-11-4	8-11-4	5-4-4	5-7-12	1-0-0

Scale = 1.684



5-0-0	11-1-8	20-0-12	28-10-8	34-4-4	40-0-0
5-0-0	6-1-8	8-11-4	8-9-12	5-5-12	5-7-12

Plate Offsets (X,Y): [2:0-6-12,0-2-12], [7:0-0-0,0-0-0]

LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase 1.25	TC 0.56	Vert(LL) -0.51 11-12	>934	240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.80	Vert(TL) -1.01 11-12	>468	180		
BCLL 10.0	Rep Stress Incr YES	WB 0.73	Horz(TL) -0.41 14	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002	(Matrix)					
						Weight: 279 lb	

LUMBER

TOP CHORD 2 X 6 SYP No.2
BOT CHORD 2 X 6 SYP No.2 *Except*
B4 2 X 6 SYP No.1D, F1 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-1-3 oc bracing.
JOINTS	1 Brace at Jt(s) : 13

REACTIONS

(lb/size) 7=1766/0-8-6, 14=1698/Mechanical
Max Horz 7=-164(LC 7)
Max Uplift 7=-373(LC 5), 14=-353(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD	6-7=-5276/1802, 7-8=0/16, 2-3=-4740/1736, 3-4=-5880/2139, 4-5=-5880/2139, 5-6=-5881/2139, 1-2=-2140/770, 1-14=-1611/612
BOT CHORD	7-9=-1682/4875, 11-12=-1663/4775, 10-11=-1655/4823, 9-10=-1655/4823, 13-14=-23/73, 12-13=-658/1954
WEBS	6-11=-409/1363, 5-11=-410/365, 3-11=-401/1190, 2-12=-1100/3134, 2-13=-790/404, 1-13=-683/2007, 3-12=-731/459, 6-9=-176/1241

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDF=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 373 lb uplift at joint 7 and 353 lb uplift at joint 14.

LOAD CASE(S) Standard

OCT 15 2008




Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
 DAVENPORT HS8S SPECIAL 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
 7.030 s Mar 11 2008 MITek Industries, Inc. Fri Oct 10 14:33:38 2008 Page 1

3-0-0 9-1-8 16-5-0 23-8-8 31-0-0 35-4-4 40-0-0 41-0-0
 3-0-0 6-1-8 7-3-8 7-3-8 7-3-8 4-4-4 4-7-12 1-0-0
 Scale = 1:68.1



3-0-0 9-1-8 16-5-0 23-8-8 30-10-8 40-0-0
 3-0-0 6-1-8 7-3-8 7-3-8 7-2-0 9-1-8

Plate Offsets (X,Y): [2:0-7-4,0-2-12], [9:0-0-0,0-0-0], [11:0-4-0,0-4-4], [13:0-5-0,0-5-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.38	Vert(LL)	-0.60 13-14	>790	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.80	Vert(TL)	-1.19 13-14	>398	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.84	Horz(TL)	-0.45 17	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 276 lb	

LUMBER

TOP CHORD 2 X 6 SYP No.2 *Except*
 T2 2 X 6 SYP No.1D, T2 2 X 6 SYP No.1D
 BOT CHORD 2 X 6 SYP No.1D *Except*
 B1 2 X 4 SYP No.2, F1 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-2 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-6-1 oc bracing.
 JOINTS 1 Brace at Jt(s): 15, 16

REACTIONS

(lb/size) 9=1745/0-8-6, 17=1699/Mechanical
 Max Horz 9=-140(LC 7)
 Max Uplift 9=-372(LC 5), 17=-378(LC 5)

FORCES (lb)

- Maximum Compression/Maximum Tension
 TOP CHORD 8-9=-5394/1884, 9-10=0/8, 2-3=-4787/1754, 3-4=-6560/2397, 4-5=-6954/2537, 5-6=-6954/2537,
 6-7=-6952/2535, 7-8=-6265/2286, 1-2=-1542/560, 1-17=-1672/609
 BOT CHORD 9-11=-1775/4974, 14-15=-1726/4839, 13-14=-2340/6560, 12-13=-2229/6265, 11-12=-1751/4935,
 16-17=-6/28, 15-16=-489/1408
 WEBS 3-15=-972/509, 2-15=-1315/3682, 2-16=-1073/510, 1-16=-620/1759, 4-14=-433/312, 3-14=-667/1873,
 6-13=-267/252, 4-13=-150/432, 7-12=-559/273, 7-13=-278/814, 8-11=-213/1139, 8-12=-530/1644


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 372 lb uplift at joint 9 and 378 lb uplift at joint 17.

LOAD CASE(S) Standard

[Signature]

OCT 15 2008




Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	HSGRD1S	SPECIAL	1	3	Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:39 2008 Page 1

1-0-0	5-6-0	10-0-0	11-1-6	16-7-0	22-0-11	27-6-5	33-0-0	36-2-7	40-0-0	41-0-0
1-0-0	4-6-0	4-6-0	1-1-6	5-5-11	5-5-11	5-5-11	5-5-11	3-2-7	3-9-9	1-0-0

Scale = 1:68.4



5-6-0	10-0-0	11-1-6	16-7-0	22-0-11	27-6-5	32-7-8	36-2-7	40-0-0
5-6-0	4-6-0	1-1-6	5-5-11	5-5-11	5-5-11	5-1-3	3-6-15	3-9-9

Plate Offsets (X,Y): [2:0-5-12,0-2-8], [11:0-3-0,0-2-4], [13:0-0-0,0-0-0], [18:0-5-0,0-4-8], [21:0-6-0,0-3-8]

LOADING (psf)	SPACING	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase 1.25	TC 0.52	Vert(LL) 0.67	18-19	>711	240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.89	Vert(TL) -1.31	18-19	>361	180		
BCLL 10.0	Rep Stress Incr NO	WB 0.50	Horz(TL) -0.36	24	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002	(Matrix)						
							Weight: 732 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-9-5 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 13=2856/0-8-6, 24=2901/Mechanical
Max Horz 13=-64(LC 6)
Max Uplift 13=-1416(LC 6), 24=-1181(LC 5)
Max Grav 13=2856(LC 1), 24=2923(LC 9)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 11-12=-9708/4864, 12-13=-8367/4164, 13-14=0/3, 2-25=-4439/1851, 25-26=-4439/1851, 3-26=-4439/1851, 3-4=-7307/3141, 4-27=-7307/3141, 5-27=-7307/3141, 5-28=-11743/5108, 6-28=-11743/5108, 6-29=-11743/5108, 29-30=-11743/5108, 7-30=-11743/5108, 7-31=-14903/6806, 8-31=-14903/6806, 8-32=-14903/6806, 9-32=-14903/6806, 9-33=-14903/6806, 33-34=-14903/6806, 34-35=-14903/6806, 10-35=-14903/6806, 10-36=-9587/4804, 36-37=-9587/4804, 11-37=-9587/4804, 1-2=-1102/453, 1-24=-2820/1153
BOT CHORD 16-38=-3872/7642, 15-38=-3791/7534, 13-15=-3776/7503, 20-39=-6576/14760, 39-40=-6576/14760, 19-40=-6576/14760, 19-41=-6576/14760, 41-42=-6576/14760, 42-43=-6576/14760, 18-43=-6576/14760, 18-44=-6277/13314, 44-45=-6277/13314, 45-46=-6277/13314, 17-46=-6277/13314, 17-47=-6277/13314, 47-48=-6277/13314, 16-48=-6277/13314, 21-49=-3678/8640, 20-49=-3674/8702, 23-24=-49/120, 23-50=-350/867, 50-51=-350/867, 22-51=-350/867, 22-52=-1846/4438, 52-53=-1847/4440, 21-53=-1848/4441
WEBS 12-15=-183/105, 12-16=-814/1621, 10-16=-4017/1598, 10-17=0/415, 10-18=-572/1715, 9-18=-386/364, 7-18=-239/152, 7-19=-57/590, 7-20=-3213/1568, 6-20=-247/302, 5-20=-3597/8135, 5-21=-6757/2891, 3-21=-1552/3450, 3-22=-2249/918, 2-23=-2116/806, 1-23=-973/2432, 2-22=-1813/4322, 11-16=-1599/3423

NOTES

- 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2 X 6 - 2 rows at 0-8-0 oc.
Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

OCT 15 2008



Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	HSGRD1S	SPECIAL	1	3	Job Reference (optional)
Maronda Homes Inc., Sanford, Florida			7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:40 2008 Page 2		

NOTES

- 4) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) Refer to girder(s) for truss to truss connections.
- 8) Bearing at joint(s) 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1416 lb uplift at joint 13 and 1181 lb uplift at joint 24.
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 119 lb down and 114 lb up at 33-0-0, 108 lb down and 122 lb up at 30-11-4, 108 lb down and 122 lb up at 28-11-4, 108 lb down and 122 lb up at 26-11-4, 108 lb down and 122 lb up at 24-11-4, 108 lb down and 122 lb up at 22-11-4, 108 lb down and 122 lb up at 20-11-4, 108 lb down and 122 lb up at 18-11-4, 108 lb down and 122 lb up at 16-11-4, 108 lb down and 122 lb up at 14-11-4, 108 lb down and 122 lb up at 12-11-4, 108 lb down and 122 lb up at 10-11-4, 86 lb down and 1 lb up at 8-11-4, 86 lb down and 1 lb up at 6-11-4, 86 lb down and 1 lb up at 4-11-4, and 86 lb down and 1 lb up at 2-11-4, and 118 lb down and 1 lb up at 1-0-0 on top chord, and 690 lb down and 518 lb up at 33-0-0, 98 lb down at 30-11-4, 98 lb down at 28-11-4, 98 lb down at 26-11-4, 98 lb down at 24-11-4, 98 lb down at 22-11-4, 98 lb down at 20-11-4, 98 lb down at 18-11-4, 98 lb down at 16-11-4, 98 lb down at 14-11-4, 98 lb down at 12-11-4, 98 lb down at 10-11-4, 105 lb down and 84 lb up at 8-11-4, 105 lb down and 84 lb up at 6-11-4, 105 lb down and 84 lb up at 4-11-4, and 105 lb down and 84 lb up at 2-11-4, and 105 lb down and 84 lb up at 0-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard


- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 11-14=-23, 2-11=-23, 1-2=-23, 13-16=-20, 16-20=-20, 20-21=-20, 21-24=-20

Concentrated Loads (lb)

Vert: 11=-119(B) 8=-108(B) 2=-86(B) 16=-90(B) 4=-86(B) 23=-105(B) 25=-86(B) 26=-86(B) 27=-86(B) 28=-108(B) 29=-108(B) 30=-108(B) 31=-108(B) 32=-108(B) 33=-108(B) 34=-108(B) 35=-108(B) 36=-108(B) 37=-108(B) 38=-599(B) 39=-98(B) 40=-98(B) 41=-98(B) 42=-98(B) 43=-98(B) 44=-98(B) 45=-98(B) 46=-98(B) 47=-98(B) 48=-98(B) 49=-98(B) 50=-105(B) 51=-105(B) 52=-105(B) 53=-105(B)



OCT 15 2008

5-5-8 11-0-0 17-0-0 23-0-0 28-5-8 33-11-1 40-0-0
 5-5-8 5-6-8 6-0-0 6-0-0 5-5-9 5-5-9 6-0-15

Scale = 1:67.3




Plate Offsets (X,Y): [3:0-3-0,0-2-4], [5:0-3-0,0-2-4], [9:0-0-1,0-1-11]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.59	Vert(LL)	-0.26 10-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.91	Vert(TL)	-0.54 10-12	>889	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.56	Horz(TL)	-0.15 17	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 236 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2
 WEDGE
 Right: 2 X 4 SYP No.3


BRACING
 TOP CHORD Structural wood sheathing directly applied or 2-8-8 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-9-8 oc bracing.
 WEBS 1 Row at midpt 4-12, 4-15

REACTIONS (lb/size) 9=1711/Mechanical, 17=1711/Mechanical
 Max Horz 9=-184(LC 7)
 Max Uplift 9=-306(LC 7), 17=-281(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 5-6=-2548/946, 6-7=-3318/1112, 7-8=-3371/1095, 8-9=-3545/1185, 3-4=-1897/782, 4-5=-2323/922,
 1-2=-1799/620, 2-3=-2091/796, 1-17=-1604/584
 BOT CHORD 16-17=-287/1, 15-16=-515/1617, 14-15=-718/2305, 13-14=-718/2305, 12-13=-718/2305,
 11-12=-934/2788, 10-11=-934/2788, 9-10=-1137/3198
 WEBS 8-10=-191/234, 6-10=-67/578, 6-12=-646/304, 5-12=-125/690, 4-12=-129/87, 4-13=0/217, 4-15=-725/235,
 3-15=-67/521, 2-15=-72/431, 2-16=-593/330, 1-16=-550/1744

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Provide adequate drainage to prevent water ponding.
 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 5) Refer to girder(s) for truss to truss connections.
 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 306 lb uplift at joint 9 and 281 lb uplift at joint 17.

LOAD CASE(S) Standard



OCT 15 2008

4-7-12 9-0-0 17-0-0 25-0-0 32-4-11 40-0-0
 4-7-12 4-4-4 8-0-0 8-0-0 7-4-11 7-7-5

Scale = 1:67.3




Plate Offsets (X,Y): [3:0-5-12,0-2-8], [5:0-5-4,0-2-4], [6:0-3-0,0-3-0], [7:0-0-1,0-1-11], [9:0-3-0,0-3-4], [11:0-3-0,0-3-4]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/dell	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.69	Vert(LL)	-0.26	9-10	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.93	Vert(TL)	-0.54	9-10	>880	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.56	Horz(TL)	-0.16	12	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 218 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2
 WEDGE
 Right: 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-7-4 oc purlins, **except** end verticals.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
 WEBS 1 Row at midpt 6-9, 2-12

REACTIONS

(lb/size) 7=1711/Mechanical, 12=1711/Mechanical
 Max Horz 7=-171(LC 7)
 Max Uplift 7=-290(LC 7), 12=-306(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 5-6=-2797/1008, 6-7=-3576/1172, 3-4=-2636/1039, 4-5=-2636/1039, 1-2=-187/52, 2-3=-2079/777, 1-12=-177/100
 BOT CHORD 11-12=-496/1421, 10-11=-586/1892, 9-10=-819/2534, 8-9=-1112/3222, 7-8=-1112/3222
 WEBS 6-8=0/334, 6-9=-773/323, 5-9=-37/622, 5-10=-72/290, 4-10=-392/356, 3-10=-360/1012, 3-11=-160/201, 2-11=-134/717, 2-12=-1873/721

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 290 lb uplift at joint 7 and 306 lb uplift at joint 12.

LOAD CASE(S) Standard



OCT 15 2008


Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
DAVENPORT H3S HIP 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:12 2008 Page 1

8-0-0 14-0-0 20-0-0 26-0-0 32-10-11 40-0-0
8-0-0 6-0-0 6-0-0 6-0-0 6-10-11 7-1-5

Scale = 1:67.3



8-0-0 14-0-0 20-0-0 26-0-0 32-10-11 40-0-0
8-0-0 6-0-0 6-0-0 6-0-0 6-10-11 7-1-5

Plate Offsets (X,Y): [1:0-3-0,0-1-8], [2:0-5-0,0-2-4], [3:0-4-0,0-3-0], [5:0-5-12,0-2-8], [7:0-0-1,0-1-11]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.58	Vert(LL)	-0.24	8-9	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.89	Vert(TL)	-0.50	8-9	>962	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.64	Horz(TL)	-0.16	15	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 224 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
WEDGE
Right: 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-9-9 oc purlins, **except** end verticals.
BOT CHORD Rigid ceiling directly applied or 5-8-13 oc bracing.
WEBS 1 Row at midpt 3-14

REACTIONS (lb/size)

7=1711/Mechanical, 15=1711/Mechanical
Max Horz 7=-165(LC 7)
Max Uplift 7=-285(LC 4), 15=-319(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 5-6=-2878/1039, 6-7=-3603/1188, 2-3=-1864/755, 3-4=-2849/1105, 4-5=-2849/1105, 1-2=-2079/747, 1-15=-1545/618
BOT CHORD 14-15=-63/161, 13-14=-860/2586, 12-13=-860/2586, 11-12=-860/2586, 10-11=-861/2611, 9-10=-861/2611, 8-9=-1132/3246, 7-8=-1132/3246
WEBS 6-8=0/318, 6-9=-714/298, 5-9=-44/548, 5-11=-128/467, 4-11=-288/255, 3-11=-129/401, 3-12=0/223, 3-14=-1102/372, 2-14=0/524, 1-14=-571/1791

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 285 lb uplift at joint 7 and 319 lb uplift at joint 15.

LOAD CASE(S) Standard



OCT 15 2008

6-0-0 13-4-9 20-7-7 28-0-0 33-10-11 40-0-0
 6-0-0 7-4-9 7-2-13 7-4-9 5-10-11 6-1-5

Scale = 1:67.3




Plate Offsets (X,Y): [2:0-4-0,0-1-13], [6:0-5-12,0-2-8], [8:0-0-1,0-1-11], [13:0-3-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.43	Vert(LL)	-0.30 10-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.82	Vert(TL)	-0.61 10-12	>786	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.50	Horz(TL)	-0.18 15	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 216 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2
 WEDGE
 Right: 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-11-12 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-8-12 oc bracing.
 WEBS 1 Row at midpt 3-14

REACTIONS

(lb/size) 8=1711/Mechanical, 15=1711/Mechanical
 Max Horz 8=-152(LC 7)
 Max Uplift 8=-303(LC 4), 15=-344(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 6-7=-3074/1107, 7-8=-3625/1212, 2-3=-1729/692, 3-4=-3325/1265, 4-5=-3325/1265, 5-6=-3325/1265,
 1-2=-1908/692, 1-15=-1599/615
 BOT CHORD 14-15=-28/72, 13-14=-1023/2963, 12-13=-1023/2963, 11-12=-958/2806, 10-11=-958/2806,
 9-10=-1160/3263, 8-9=-1160/3263
 WEBS 7-9=0/255, 7-10=-519/223, 6-10=-12/485, 6-12=-235/748, 5-12=-346/317, 3-12=-157/467, 3-13=0/292,
 3-14=-1559/549, 2-14=0/456, 1-14=-606/1813

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 303 lb uplift at joint 8 and 344 lb uplift at joint 15.


LOAD CASE(S) Standard



OCT 15 2008

5-0-0	11-0-14	17-0-0	22-11-2	29-0-0	34-4-11	40-0-0
5-0-0	6-0-14	5-11-2	5-11-2	6-0-14	5-4-11	5-7-5

Scale = 1:67.3



5-0-0	11-0-14	17-0-0	22-11-2	29-0-0	34-4-11	40-0-0
5-0-0	6-0-14	5-11-2	5-11-2	6-0-14	5-4-11	5-7-5

Plate Offsets (X,Y): [2:0-3-0,0-2-4], [4:0-3-0,0-3-0], [6:0-3-0,0-2-4], [8:0-0-1,0-1-11], [10:0-2-12,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.36	Vert(LL)	-0.31 11-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.78	Vert(TL)	-0.62 11-12	>773	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.78	Horz(TL)	-0.19 16	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 222 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 3-0-9 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 5-8-12 oc bracing.
WEBS 2 X 4 SYP No.2	WEBS 1 Row at midpt 3-15
WEDGE	
Right: 2 X 4 SYP No.3	


REACTIONS (lb/size) 8=1711/Mechanical, 16=1711/Mechanical
Max Horz 8=-146(LC 7)
Max Uplift 8=-312(LC 4), 16=-356(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 6-7=-3162/1137, 7-8=-3636/1224, 2-3=-1600/638, 3-4=-3504/1324, 4-5=-3504/1324, 5-6=-2876/1094, 1-2=-1759/642, 1-16=-1616/615
BOT CHORD 15-16=-20/52, 14-15=-1003/2871, 13-14=-1003/2871, 12-13=-1003/2871, 11-12=-1232/3515, 10-11=-1232/3515, 9-10=-1176/3271, 8-9=-1176/3271
WEBS 7-9=0/229, 7-10=-438/200, 6-10=-199/928, 5-10=-904/296, 5-11=0/241, 5-12=-29/59, 4-12=-269/251, 3-12=-290/827, 3-14=0/240, 3-15=-1662/592, 2-15=-10/451, 1-15=-597/1755

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 312 lb uplift at joint 8 and 356 lb uplift at joint 16.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
 DAVENPORT B1 SPECIAL 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
 7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:03 2008 Page 1

6-8-0 13-4-0 20-0-0 26-8-0 33-4-0 40-0-0
 6-8-0 6-8-0 6-8-0 6-8-0 6-8-0 6-8-0

Scale = 1/67.5




Plate Offsets (X,Y): [3:0-4-0,0-3-0], [5:0-4-0,0-3-0], [10:0-3-0,0-3-0], [12:0-3-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.70	Vert(LL)	-0.40 11-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.83	Vert(TL)	-0.80 11-12	>597	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.86	Horz(TL)	0.18 8	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 223 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-9-2 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-4-0 oc bracing.
 WEBS 1 Row at midpt 3-13, 5-9

REACTIONS (lb/size) 14=1707/Mechanical, 8=1707/Mechanical
 Max Uplift 14=-418(LC 4), 8=-418(LC 4)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-14=-1577/646, 1-2=-2415/872, 2-3=-2415/872, 3-4=-4336/1565, 4-5=-4336/1565, 5-6=-2415/872, 6-7=-2415/872, 7-8=-1577/646
 BOT CHORD 13-14=-25/68, 12-13=-1393/3856, 11-12=-1393/3856, 10-11=-1393/3856, 9-10=-1393/3856, 8-9=-25/68
 WEBS 1-13=-992/2749, 2-13=-307/297, 3-13=-1677/606, 3-12=0/266, 3-11=-201/559, 4-11=-306/288, 5-11=-201/559, 5-10=0/266, 5-9=-1677/606, 6-9=-307/297, 7-9=-992/2749

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Provide adequate drainage to prevent water ponding.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 418 lb uplift at joint 14 and 418 lb uplift at joint 8.

LOAD CASE(S) Standard




[Signature]

OCT 15 2008

Scale = 1:67.5

1.5.3




LOADING (psf)	SPACING	1-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.83	Vert(LL)	0.75 12-13	>635	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.82	Vert(TL)	-1.10 12-13	>432	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.87	Horz(TL)	0.18 10	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 410 lb	

TOP CHORD	Structural wood sheathing directly applied or 3-7-14 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-2-0 oc bracing.
WEBS	1 Row at midpt 8-10

TOP CHORD	1-15=-2676/1670, 1-16=-6079/3645, 16-17=-6079/3645, 17-18=-6079/3645, 2-18=-6079/3645, 2-3=-6079/3645, 3-19=-6079/3645, 19-20=-6079/3645, 4-20=-6079/3645, 4-21=-9072/5440, 5-21=-9072/5440, 5-22=-9072/5440, 6-22=-9072/5440, 6-23=-9072/5440, 23-24=-9072/5440, 7-24=-9072/5440, 7-8=-9072/5440, 8-25=-228/137, 25-26=-228/137, 26-27=-228/137, 9-27=-228/137, 9-10=-250/195
BOT CHORD	15-28=-137/229, 28-29=-137/229, 29-30=-137/229, 14-30=-137/229, 14-31=-5446/9081, 31-32=-5446/9081, 32-33=-5446/9081, 13-33=-5446/9081, 13-34=-5446/9081, 34-35=-5446/9081, 35-36=-5446/9081, 12-36=-5446/9081, 12-37=-3644/6078, 37-38=-3644/6078, 38-39=-3644/6078, 11-39=-3644/6078, 11-40=-3644/6078, 40-41=-3644/6078, 41-42=-3644/6078, 10-42=-3644/6078
WEBS	1-14=-3778/6301, 2-14=-569/466, 4-14=-3225/1934, 4-13=-243/603, 4-12=-9/6, 6-12=-574/463, 8-12=-1930/3216, 8-11=-235/595, 8-10=-6301/3777

- 1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 Bottom chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
- 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the **LOAD CASE(S)** section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 3) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; **enclosed**; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 4) Provide adequate drainage to prevent water ponding.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (or others) of truss to bearing plate capable of withstanding 1833 lb uplift at joint 15 and 1697 lb uplift at joint 10.



OCT 15 2008

NOTES

8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 98 lb down and 83 lb up at 0-1-12, 98 lb down and 83 lb up at 2-2-4, 98 lb down and 83 lb up at 4-2-4, 98 lb down and 83 lb up at 6-2-4, 98 lb down and 83 lb up at 8-2-4, 98 lb down and 83 lb up at 10-2-4, 98 lb down and 83 lb up at 12-2-4, 98 lb down and 83 lb up at 14-2-4, 98 lb down and 83 lb up at 16-2-4, 98 lb down and 83 lb up at 18-2-4, 98 lb down and 83 lb up at 20-2-4, 98 lb down and 83 lb up at 22-2-4, 98 lb down and 83 lb up at 24-2-4, 98 lb down and 83 lb up at 26-2-4, 98 lb down and 83 lb up at 28-2-4, 98 lb down and 83 lb up at 30-2-4, 98 lb down and 83 lb up at 32-2-4, 98 lb down and 83 lb up at 34-2-4, and 98 lb down and 83 lb up at 36-2-4, and 98 lb down and 83 lb up at 38-2-4 on top chord, and 110 lb down and 72 lb up at 0-1-12, 110 lb down and 72 lb up at 2-2-4, 110 lb down and 72 lb up at 4-2-4, 110 lb down and 72 lb up at 6-2-4, 110 lb down and 72 lb up at 8-2-4, 110 lb down and 72 lb up at 10-2-4, 110 lb down and 72 lb up at 12-2-4, 110 lb down and 72 lb up at 14-2-4, 110 lb down and 72 lb up at 16-2-4, 110 lb down and 72 lb up at 18-2-4, 110 lb down and 72 lb up at 20-2-4, 110 lb down and 72 lb up at 22-2-4, 110 lb down and 72 lb up at 24-2-4, 110 lb down and 72 lb up at 26-2-4, 110 lb down and 72 lb up at 28-2-4, 110 lb down and 72 lb up at 30-2-4, 110 lb down and 72 lb up at 32-2-4, 110 lb down and 72 lb up at 34-2-4, and 110 lb down and 72 lb up at 36-2-4, and 110 lb down and 72 lb up at 38-2-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-9=-23, 10-15=-20

Concentrated Loads (lb)

Vert: 15=-110(F) 1=-98(F) 3=-98(F) 14=-110(F) 2=-98(F) 4=-98(F) 13=-110(F) 6=-98(F) 12=-110(F) 11=-110(F) 8=-98(F) 5=-98(F) 7=-98(F) 16=-98(F) 17=-98(F) 18=-98(F) 19=-98(F) 20=-98(F) 21=-98(F) 22=-98(F) 23=-98(F) 24=-98(F) 25=-98(F) 26=-98(F) 27=-98(F) 28=-110(F) 29=-110(F) 30=-110(F) 31=-110(F) 32=-110(F) 33=-110(F) 34=-110(F) 35=-110(F) 36=-110(F) 37=-110(F) 38=-110(F) 39=-110(F) 40=-110(F) 41=-110(F) 42=-110(F)



A handwritten signature in black ink, appearing to be "TP" or similar initials, written over the seal area.

OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
DAVENPORT GRD1 COMMON 2 3

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:08 2008 Page 1

4-4-7 7-1-8 9-4-0 14-3-9 18-8-0
4-4-7 2-9-1 2-2-8 4-11-9 4-4-7

Scale = 1:30.0




Plate Offsets (X,Y): [7:Edge,0-2-14], [9:0-3-8,0-4-0], [10:0-5-0,0-6-0], [11:0-3-8,0-4-0]

LOADING (psf)	SPACING	1-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.57	Vert(LL)	-0.16	9	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.87	Vert(TL)	-0.29	9	>736	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.57	Horz(TL)	0.06	7	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 371 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 8 SYP No.1D
WEBS 2 X 4 SYP No.2 *Except*
W3 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-10-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 1=6166/0-8-6, 7=10143/0-8-6
Max Horz 1=-30(LC 6)
Max Uplift 1=-2521(LC 5), 7=-3632(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-13584/5585, 2-3=-14213/5864, 3-4=-12490/4956, 4-5=-12494/4957, 5-6=-15481/5858, 6-7=-19008/6918
BOT CHORD 1-12=-5069/12296, 11-12=-5069/12296, 10-11=-5386/13101, 10-13=-5360/14279, 9-13=-5360/14279, 9-14=-6252/17227, 8-14=-6252/17227, 8-15=-6252/17227, 15-16=-6252/17227, 7-16=-6252/17227
WEBS 2-12=-375/177, 4-10=-3664/9255, 5-10=-4577/1407, 6-8=-1210/3974, 3-11=-1521/2862, 2-11=-418/1024, 3-10=-2579/1412, 5-9=-1506/4936, 6-9=-3574/1088

NOTES

- 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2 X 8 - 4 rows at 0-4-0 oc.
Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2521 lb uplift at joint 1 and 3632 lb uplift at joint 7.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 4002 lb down and 2065 lb up at 7-1-8, 1826 lb down and 789 lb up at 9-0-12, 1910 lb down and 622 lb up at 11-0-12, 1932 lb down and 608 lb up at 12-0-12, 1943 lb down and 627 lb up at 14-0-12, and 1945 lb down and 637 lb up at 15-0-12, and 1976 lb down and 656 lb up at 17-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.



OCT 15 2008

Job	Truss	Truss Type
DAVENPORT	GRD1	COMMON

Qty Ply DAVENPORT_125_9TM04001

2

3

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:08 2008 Page 2

LOAD CASE(S) Standard


1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-23, 4-7=-23, 1-7=-20

Concentrated Loads (lb)

Vert: 10=-1826(F) 8=-1943(F) 11=-4002(F) 13=-1910(F) 14=-1932(F) 15=-1945(F) 16=-1976(F)



A handwritten signature in black ink, appearing to be "TP" or "T. Ponce", written over a horizontal line.

OCT 15 2008

Job Truss Truss Type
DAVENPORT T1 COMMON

Qty Ply DAVENPORT_125_9TM04001

6 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:53 2008 Page 1

-1-0-0 4-9-5 9-4-0 13-10-11 18-8-0 19-8-0
1-0-0 4-9-5 4-6-11 4-6-11 4-9-5 1-0-0
Scale = 1:33.2




Plate Offsets (X,Y): [2:0-0-1,0-0-15], [6:0-0-1,0-0-15], [8:0-4-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.27	Vert(LL)	-0.13	6-8	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.62	Vert(TL)	-0.30	6-8	>713	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.11	Horz(TL)	0.03	6	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 82 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-1-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 2=838/0-8-6, 6=838/0-8-6
Max Horz 2=73(LC 6)
Max Uplift 2=-230(LC 6), 6=-230(LC 7)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/10, 2-3=-1276/426, 3-4=-1056/313, 4-5=-1056/313, 5-6=-1276/426, 6-7=0/10
BOT CHORD 2-8=-293/1131, 6-8=-293/1131
WEBS 3-8=-246/193, 4-8=-37/573, 5-8=-246/193

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 230 lb uplift at joint 2 and 230 lb uplift at joint 6.

LOAD CASE(S) Standard



OCT 15 2008




Plate Offsets (X,Y): [14:0-3-0,0-3-0]										
LOADING (psf)		SPACING 2-0-0		CSI	DEFL in (loc)		I/defl	L/d	PLATES	GRIP
TCLL	16.0	Plates Increase	1.25	TC 0.10	Vert(LL)	0.00 1	n/r	120	MT20	244/190
TCDL	7.0	Lumber Increase	1.25	BC 0.09	Vert(TL)	0.01 1	n/r	120		
BCLL	10.0	Rep Stress Incr	NO	WB 0.03	Horz(TL)	0.00 10	n/a	n/a		
BCDL	10.0	Code FBC2004/TPI2002		(Matrix)						
Weight: 85 lb										

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2 X 4 SYP No.2	

REACTIONS (lb/size) 10=121/18-8-0, 2=179/18-8-0, 14=160/18-8-0, 15=183/18-8-0, 16=132/18-8-0, 17=277/18-8-0, 13=185/18-8-0, 12=125/18-8-0, 11=293/18-8-0
 Max Horz 2=93(LC 6)
 Max Uplift 10=32(LC 7), 2=-115(LC 6), 15=-102(LC 6), 16=-82(LC 6), 17=-151(LC 6), 13=-104(LC 7), 12=-71(LC 7), 11=-176(LC 7)
 Max Grav 10=121(LC 1), 2=179(LC 1), 14=160(LC 1), 15=187(LC 10), 16=132(LC 1), 17=277(LC 10), 13=188(LC 11), 12=125(LC 11), 11=293(LC 11)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/10, 2-3=-76/34, 3-4=-32/89, 4-5=-24/122, 5-6=-26/179, 6-7=-26/180, 7-8=-24/120, 8-9=-33/70, 9-10=-46/33
 BOT CHORD 2-17=0/83, 16-17=0/83, 15-16=0/83, 14-15=0/83, 13-14=0/83, 12-13=0/83, 11-12=0/83, 10-11=0/83
 WEBS 6-14=-83/0, 5-15=-101/137, 4-16=-72/119, 3-17=-145/197, 7-13=-101/139, 8-12=-69/112, 9-11=-153/213

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 32 lb uplift at joint 10, 115 lb uplift at joint 2, 102 lb uplift at joint 15, 82 lb uplift at joint 16, 151 lb uplift at joint 17, 104 lb uplift at joint 13, 71 lb uplift at joint 12 and 176 lb uplift at joint 11.

LOAD CASE(S) Standard



OCT 15 2008

-1-0-0 4-7-5 9-0-0 9-8-0 14-0-11 18-8-0 19-8-0
 1-0-0 4-7-5 4-4-11 0-8-0 4-4-11 4-7-5 1-0-0
 Scale = 1:33.7




Plate Offsets (X,Y): [2:0-0-1,0-0-15], [4:0-2-0,0-2-11], [6:0-2-0,0-2-11], [8:0-0-1,0-0-15], [10:0-4-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.27	Vert(LL)	-0.13	8-10	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.62	Vert(TL)	-0.30	8-10	>720	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.18	Horz(TL)	0.03	8	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						Weight: 82 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-2-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 2=838/0-8-6, 8=838/0-8-6
 Max Horz 2=71(LC 6)
 Max Uplift 2=227(LC 6), 8=227(LC 7)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/10, 2-3=-1278/432, 3-4=-1059/317, 4-5=-937/332, 5-6=-937/332, 6-7=-1059/317, 7-8=-1278/432, 8-9=0/10
 BOT CHORD 2-10=-299/1133, 8-10=-299/1133
 WEBS 3-10=-244/191, 7-10=-244/191, 5-10=-26/558

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 227 lb uplift at joint 2 and 227 lb uplift at joint 8.

LOAD CASE(S) Standard



[Signature]

OCT 15 2008

-1-0-0 3-9-12 7-0-0 11-8-0 14-10-4 18-8-0 19-8-0
 1-0-0 3-9-12 3-2-4 4-8-0 3-2-4 3-9-12 1-0-0
 Scale = 1:33.7




Plate Offsets (X,Y): [2:0-4-4,0-1-8], [4:0-5-4,0-2-4], [7:0-4-4,0-1-8], [11:0-3-8,0-3-0]									
LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.44	Vert(LL)	0.13 9-11	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.59	Vert(TL)	-0.22 9-11	>999	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.17	Horz(TL)	0.06 7	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						Weight: 102 lb

LUMBER
 TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 6 SYP No.2
 WEBS 2 X 4 SYP No.2


BRACING
 TOP CHORD Structural wood sheathing directly applied or 3-1-7 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 6-2-8 oc bracing.

REACTIONS (lb/size) 2=1807/0-8-6, 7=1807/0-8-6
 Max Horz 2=61(LC 7)
 Max Uplift2=-855(LC 7), 7=-855(LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/14, 2-3=-3481/1661, 3-4=-3522/1704, 4-12=-3288/1623, 12-13=-3288/1623, 5-13=-3288/1623,
 5-6=-3519/1702, 6-7=-3480/1660, 7-8=0/14
 BOT CHORD 2-11=-1478/3082, 10-11=-1541/3291, 10-14=-1541/3291, 14-15=-1541/3291, 9-15=-1541/3291,
 7-9=-1417/3081
 WEBS 3-11=-115/296, 4-11=-389/931, 4-9=-73/67, 5-9=-388/929, 6-9=-114/294

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 855 lb uplift at joint 2 and 855 lb uplift at joint 7.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 98 lb down and 83 lb up at 7-0-0, 98 lb down and 83 lb up at 9-0-12, and 98 lb down and 83 lb up at 9-7-4, and 98 lb down and 83 lb up at 11-8-0 on top chord, and 663 lb down and 404 lb up at 7-0-0, 110 lb down and 72 lb up at 9-0-12, and 110 lb down and 72 lb up at 9-7-4, and 663 lb down and 404 lb up at 11-7-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-4=-46, 4-5=-46, 5-8=-46, 2-7=-40



[Signature]

OCT 15 2008

Job	Truss	Truss Type
DAVENPORT	HGRD1	HIP

Qty	Ply	DAVENPORT_125_9TM04001
1	1	


Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:28 2008 Page 2

LOAD CASE(S) Standard

Concentrated Loads (lb)

Vert: 4=-98(B) 5=-98(B) 11=-663(B) 9=-663(B) 12=-98(B) 13=-98(B) 14=-110(B) 15=-110(B)



A handwritten signature in black ink, appearing to be "T. Ponce", written over the seal area.

OCT 15 2008

3-9-12 7-0-0 10-2-4 14-0-0
 3-9-12 3-2-4 3-2-4 3-9-12

Scale = 1:22.5




Plate Offsets (X,Y): [7:0-4-0,0-4-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.16	Vert(LL)	-0.06	7	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.41	Vert(TL)	-0.11	7	>999	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.34	Horz(TL)	0.03	5	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 147 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 6 SYP No.2
 WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-11-12 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 1=2430/0-8-6, 5=2430/0-8-6
 Max Horz 1=46(LC 5)
 Max Uplift 1=807(LC 5), 5=807(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-5038/1699, 2-3=-5098/1792, 3-4=-5098/1792, 4-5=-5038/1700
 BOT CHORD 1-8=-1526/4479, 7-8=-1526/4479, 6-7=-1481/4479, 5-6=-1481/4479
 WEBS 2-8=0/72, 2-7=-154/360, 3-7=-1276/3707, 4-7=-156/360, 4-6=0/73


NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 Bottom chords connected as follows: 2 X 6 - 2 rows at 0-3-0 oc.
 Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 807 lb uplift at joint 1 and 807 lb uplift at joint 5.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 3714 lb down and 1394 lb up at 6-9-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25

OCT 15 2008



Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	GRD2	COMMON	1	2	

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:08 2008 Page 2


LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-3=-46, 3-5=-46, 1-5=-40

Concentrated Loads (lb)

Vert: 7=-3714(F)



A handwritten signature in black ink, appearing to be "T. Ponce", written over a horizontal line.

OCT 15 2008

Job Truss Truss Type
DAVENPORT T2 COMMON

Qty Ply DAVENPORT_125_9TM04001

2 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:54 2008 Page 1

7-0-0

14-0-0

15-0-0

7-0-0

7-0-0

1-0-0

Scale: 1/2"=1'




Plate Offsets (X,Y): [1:0-0-1,0-1-3], [3:0-0-1,0-1-3]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.31	Vert(LL)	-0.08	1-5	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.53	Vert(TL)	-0.15	1-5	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.06	Horz(TL)	0.02	3	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 50 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 1=570/0-8-6, 3=641/0-8-6
Max Horz 1=-63(LC 7)
Max Uplift 1=-109(LC 6), 3=-193(LC 7)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-862/266, 2-3=-877/269, 3-4=0/10
BOT CHORD 1-5=-137/746, 3-5=-137/746
WEBS 2-5=0/332

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 109 lb uplift at joint 1 and 193 lb uplift at joint 3.

LOAD CASE(S) Standard



[Signature]


OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
DAVENPORT G2 GABLE 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:07 2008 Page 1

7-0-0 14-0-0 15-0-0
7-0-0 7-0-0 1-0-0
Scale: 1/2"=1'



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.10	Vert(LL)	0.00	8	n/r	120	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.07	Vert(TL)	0.00	8	n/r	120		
BCLL 10.0	Rep Stress Incr	NO	WB 0.03	Horz(TL)	0.00	7	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 59 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 1=109/14-0-0, 7=169/14-0-0, 11=180/14-0-0, 12=137/14-0-0, 13=266/14-0-0, 10=143/14-0-0, 9=249/14-0-0
Max Horz 1=-76(LC 7)
Max Uplift 1=-39(LC 7), 7=-138(LC 7), 12=-78(LC 6), 13=-161(LC 6), 10=-88(LC 7), 9=-131(LC 7)
Max Grav 1=109(LC 1), 7=169(LC 1), 11=180(LC 1), 12=141(LC 10), 13=266(LC 1), 10=147(LC 11), 9=249(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-48/42, 2-3=-32/98, 3-4=-26/151, 4-5=-26/152, 5-6=-31/96, 6-7=-37/26, 7-8=0/10
BOT CHORD 1-13=0/75, 12-13=0/75, 11-12=0/75, 10-11=0/75, 9-10=0/75, 7-9=0/75
WEBS 4-11=-92/23, 3-12=-79/122, 2-13=-138/210, 5-10=-82/129, 6-9=-131/193

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 39 lb uplift at joint 1, 138 lb uplift at joint 7, 78 lb uplift at joint 12, 161 lb uplift at joint 13, 88 lb uplift at joint 10 and 131 lb uplift at joint 9.

LOAD CASE(S) Standard



[Signature]

OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT JGRD1 MONO TRUSS

2 1 Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:44 2008 Page 1

-1-5-0 5-2-11 9-10-1
1-5-0 5-2-11 4-7-6

Scale = 1:18.5
3x4
4




Plate Offsets (X,Y): [2:0-0-1,0-0-6], [2:0-0-13,0-10-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.27	Vert(LL)	-0.03	2-6	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.32	Vert(TL)	-0.06	5-6	>999	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.29	Horz(TL)	0.01	5	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 47 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
WEDGE
Left: 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 9-3-13 oc bracing.

REACTIONS (lb/size) 5=565/Mechanical, 2=498/1-0-10
Max Horz 2=141(LC 3)
Max Uplift 5=-305(LC 7), 2=-233(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=0/11, 2-7=-928/362, 7-8=-927/364, 8-9=-898/386, 3-9=-865/365, 3-10=-117/63, 4-10=-63/3,
4-5=-125/158
BOT CHORD 2-11=-450/852, 11-12=-450/852, 12-13=-450/852, 6-13=-450/852, 6-14=-450/852, 5-14=-450/852
WEBS 3-6=0/283, 3-5=-840/432

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCCL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 305 lb uplift at joint 5 and 233 lb uplift at joint 2.
- 5) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 44 lb up at 4-4-12, 44 lb up at 4-4-12, 50 lb down and 117 lb up at 7-2-11, 50 lb down and 117 lb up at 7-2-11, and 44 lb down at 1-6-12, and 44 lb down at 1-6-12 on top chord, and 22 lb up at 1-6-12, 22 lb up at 1-6-12, 12 lb down at 4-4-12, 12 lb down at 4-4-12, and 52 lb down at 7-2-11, and 52 lb down at 7-2-11 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 6) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-2=-46, 2-7=-14, 4-7=-46, 2-11=-20, 5-11=-40



[Signature]

OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	JGRD1	MONO TRUSS	2	1	


Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:44 2008 Page 2

LOAD CASE(S) Standard

Concentrated Loads (lb)

Vert: 9=6(F=3, B=3) 10=-101(F=-50, B=-50) 12=43(F=22, B=22) 13=-24(F=-12, B=-12) 14=-104(F=-52, B=-52)



A handwritten signature in black ink, appearing to be "T. Ponce", written over the seal area.

OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT JSGRD1 SPECIAL

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:48 2008 Page 1

-1-5-0

5-2-7

9-10-1

1-5-0

5-2-7

4-7-10

Scale = 1:18.6




Plate Offsets (X,Y): [2:0-2-0,0-7-6], [6:0-2-0,0-1-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.32	Vert(LL)	-0.04	6-7	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.39	Vert(TL)	-0.08	6-7	>999	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.24	Horz(TL)	0.02	8	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 50 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2 *Except*
W4 2 X 6 SYP No.2
SLIDER Left 2 X 4 SYP No.2 2-7-11

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-6-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 7-5-5 oc bracing.

REACTIONS

(lb/size) 2=550/0-11-14, 8=562/Mechanical
Max Horz 2=133(LC 3)
Max Uplift 2=273(LC 7), 8=334(LC 7)

FORCES (lb)

- Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/6, 2-9=-1307/640, 3-9=-1272/657, 3-10=-1272/658, 4-10=-1241/632, 4-11=-348/215, 5-11=-288/149, 5-6=-169/462
BOT CHORD 2-12=-703/1201, 12-13=-697/1208, 7-13=-697/1222, 7-14=-706/1203, 6-14=-701/1227
WEBS 4-7=0/254, 4-6=-913/501, 5-8=-596/368, 6-8=-172/203

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 273 lb uplift at joint 2 and 334 lb uplift at joint 8.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 11 lb down and 65 lb up at 4-4-12, 11 lb down and 65 lb up at 4-4-12, 61 lb down and 132 lb up at 7-2-11, 61 lb down and 132 lb up at 7-2-11, and 43 lb down at 1-6-13, and 43 lb down at 1-6-13 on top chord, and 21 lb up at 1-6-13, 21 lb up at 1-6-13, 18 lb down at 4-4-12, 18 lb down at 4-4-12, and 58 lb down at 7-2-11, and 58 lb down at 7-2-11 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard



OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	JSGRD1	SPECIAL	1	1	

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:48 2008 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-5=-46, 2-6=-40

Concentrated Loads (lb)

Vert: 10=-22(F=-11, B=-11) 11=-121(F=-61, B=-61) 12=41(F=21, B=21) 13=-36(F=-18, B=-18) 14=-116(F=-58, B=-58)



A handwritten signature in black ink, appearing to be "T. Ponce", written over a horizontal line.

OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	J	MONO TRUSS	29	1	Job Reference (optional)
Maronda Homes Inc., Sanford, Florida			7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:40 2008 Page 1		




Plate Offsets (X,Y): [2:0-0-0,0-0-15], [2:0-0-14,0-6-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.39	Vert(LL)	-0.12	2-6	>639	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.44	Vert(TL)	-0.26	2-6	>309	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.02	Horz(TL)	0.01	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 28 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2
 WEDGE
 Left: 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=132/Mechanical, 2=355/0-8-6, 5=145/Mechanical
 Max Horz 2=143(LC 6)
 Max Uplift 4=-19(LC 6), 2=-127(LC 6), 5=-72(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/10, 2-3=-106/26, 3-4=-17/48
 BOT CHORD 2-6=0/0, 5-6=0/0
 WEBS 3-6=-17/165

NOTES (5)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 4, 127 lb uplift at joint 2 and 72 lb uplift at joint 5.
- 5) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 4 and 5.

LOAD CASE(S) Standard



OCT 15 2008

-1-0-0 7-0-0
 1-0-0 7-0-0 Toe-Nail (See note below) 4

Scale = 1:16.5




Plate Offsets (X,Y): [2:0-1-13,0-5-2]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.47	Vert(LL)	-0.12	2-5	>690	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.45	Vert(TL)	-0.30	2-5	>276	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.02	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 29 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 SLIDER Left 2 X 4 SYP No.2 3-9-9

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=154/Mechanical, 2=351/0-8-6, 5=138/Mechanical
 Max Horz 2=141(LC 6)
 Max Uplift 4=140(LC 6), 2=109(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/6, 2-3=-88/0, 3-4=-78/47
 BOT CHORD 2-5=-18/18

NOTES (6)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 4 and 109 lb uplift at joint 2.
- 6) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 4 and 5.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type
DAVENPORT JSA SPECIAL

Qty Ply DAVENPORT_125_9TM04001

1 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:48 2008 Page 1

-1-0-0

7-0-0

1-0-0

7-0-0

Scale = 1:18.0




Plate Offsets (X,Y): [2:0-2-1,0-5-2], [4:Edge,0-3-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.42	Vert(LL)	-0.10	2-5	>816	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.40	Vert(TL)	-0.24	2-5	>326	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.01	Horz(TL)	0.00	5	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 34 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
SLIDER Left 2 X 4 SYP No.2 3-5-13

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 2=335/0-8-6, 5=276/Mechanical
Max Horz 2=134(LC 6)
Max Uplift 2=-107(LC 6), 5=-93(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/6, 2-3=-85/0, 3-4=-74/44
BOT CHORD 2-5=-17/17
WEBS 4-5=-146/165

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 107 lb uplift at joint 2 and 93 lb uplift at joint 5.


LOAD CASE(S) Standard



[Signature]

OCT 15 2008

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:41 2008 Page 1

OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT JS1 SPECIAL

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:46 2008 Page 1

-1-0-0

1-0-0

5-0-0

5-0-0

Toe-Nail (See note below)

Scale = 1:12.3




Plate Offsets (X,Y): [2:0-1-13,0-5-2]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.22	Vert(LL)	-0.03	2-5	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.23	Vert(TL)	-0.08	2-5	>772	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.01	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 21 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
SLIDER Left 2 X 4 SYP No.2 2-8-9

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=107/Mechanical, 2=267/0-8-6, 5=98/Mechanical
Max Horz 2=106(LC 6)
Max Uplift 4=98(LC 6), 2=98(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/6, 2-3=-64/0, 3-4=-55/32
BOT CHORD 2-5=-13/13

NOTES (6)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 98 lb uplift at joint 4 and 98 lb uplift at joint 2.
- 6) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 4 and 5.

LOAD CASE(S) Standard



OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	J2	JACK	4	1	Job Reference (optional)
Maronda Homes Inc., Sanford, Florida			7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:41 2008 Page 1		




Plate Offsets (X,Y): [2:0-0-0,0-0-15], [2:0-0-14,0-6-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.14	Vert(LL)	-0.00	2-4	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.06	Vert(TL)	-0.01	2-4	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 12 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEDGE
Left: 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS (lb/size) 3=43/Mechanical, 2=193/0-8-6, 4=52/Mechanical
Max Horz 2=74(LC 6)
Max Uplift 3=38(LC 6), 2=112(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/10, 2-3=-37/15
BOT CHORD 2-4=0/0

NOTES (5)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 38 lb uplift at joint 3 and 112 lb uplift at joint 2.
- 5) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 3 and 4.

LOAD CASE(S) Standard



OCT 15 2008




Plate Offsets (X,Y): [2-0-1-13,0-5-2]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.08	Vert(LL)	-0.00	2-5	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.08	Vert(TL)	-0.01	2-5	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 14 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 SLIDER Left 2 X 4 SYP No.2 1-7-9

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=57/Mechanical, 2=185/0-8-6, 5=58/Mechanical
 Max Horz 2=72(LC 6)
 Max Uplift 4=53(LC 6), 2=88(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/6, 2-3=-42/0, 3-4=-28/16
 BOT CHORD 2-5=-8/8

NOTES (6)


- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 53 lb uplift at joint 4 and 88 lb uplift at joint 2.
- 6) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 4 and 5.

LOAD CASE(S) Standard



OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	J3	JACK	4	1	Job Reference (optional)
Maronda Homes Inc., Sanford, Florida			7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:42 2008 Page 1		



LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase 1.25	TC 0.02	Vert(LL) -0.00	2	>999	240		MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.01	Vert(TL) -0.00	2	>999	180			
BCLL 10.0	Rep Stress Incr YES	WB 0.00	Horz(TL) -0.00	3	n/a	n/a			
BCDL 10.0	Code FBC2004/TPI2002	(Matrix)							Weight: 7 lb

LUMBER	BRACING
TOP CHORD 2 X 6 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=86/0-8-6, 4=18/Mechanical, 3=8/Mechanical
Max Horz 2=32(LC 6)
Max Uplift 2=62(LC 6), 3=11(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/7, 2-3=-17/2
BOT CHORD 2-4=0/0

- NOTES** (6)
- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 62 lb uplift at joint 2 and 11 lb uplift at joint 3.
 - 5) SEE MiTek STANDARD PIGGYBACK TRUSS CONNECTION DETAIL FOR CONNECTION TO BASE TRUSS
 - 6) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 3 and 4.

LOAD CASE(S) Standard



[Signature]

OCT 15 2008


Job Truss Truss Type
DAVENPORT JS3 SPECIAL

Qty Ply DAVENPORT_125_9TM04001

2 1 Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:47 2008 Page 1



LOADING (psf)	SPACING	2-0-0	CSI	0-8-6(0-1-8)	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.05		Vert(LL)	-0.00	2	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.01		Vert(TL)	-0.00	2	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00		Horz(TL)	-0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)								
										Weight: 7 lb	

LUMBER

TOP CHORD 2 X 6 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=19/Mechanical, 2=84/0-8-6, 3=11/Mechanical
Max Horz 2=29(LC 6)
Max Uplift 2=54(LC 6), 3=14(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/2, 2-3=-18/4
BOT CHORD 2-4=-3/3

NOTES (7)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 2 and 14 lb uplift at joint 3.
- 6) SEE MiTek STANDARD PIGGYBACK TRUSS CONNECTION DETAIL FOR CONNECTION TO BASE TRUSS
- 7) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 3 and 4.

LOAD CASE(S) Standard



[Signature]


OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
 DAVENPORT V1S VALLEY 1 1 Job Reference (optional)
 Maronda Homes Inc., Sanford, Florida 7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:56 2008 Page 1

0-2-8 2-5-0
 0-2-8 2-2-8

Scale = 1/5/6

5.00 12



LOADING (psf)		SPACING		CSI		DEFL		I/d		PLATES		GRIP	
TCLL	16.0	Plates Increase	1.25	TC	0.02	Vert(LL)	n/a	-	n/a	999	MT20	244/190	
TCDL	7.0	Lumber Increase	1.25	BC	0.02	Vert(TL)	n/a	-	n/a	999			
BCLL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(TL)	0.00	2	n/a	n/a			
BCDL	10.0	Code FBC2004/TPI2002		(Matrix)									Weight: 7 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-5-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 3=66/2-5-0, 2=66/2-5-0
 Max Horz 3=-27(LC 7)
 Max Uplift 3=-22(LC 7), 2=-11(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-3=-35/40, 1-2=-20/11
 BOT CHORD 2-3=-0/33


NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 3 and 11 lb uplift at joint 2.

LOAD CASE(S) Standard

[Signature]

OCT 15 2008




Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V2S VALLEY 1 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:57 2008 Page 1



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.13	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.12	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	0.00	2	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						Weight: 14 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-5-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 3=152/4-5-0, 2=152/4-5-0
Max Horz 3=-61(LC 7)
Max Uplift 3=-50(LC 7), 2=-25(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-3=-81/92, 1-2=-46/25
BOT CHORD 2-3=-0/76

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 3 and 25 lb uplift at joint 2.

LOAD CASE(S) Standard

OCT 15 2008



Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V3S GABLE 1 1


Maronda Homes Inc., Sanford, Florida

Job Reference (optional)

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:57 2008 Page 1

0-2-8 6-5-0
0-2-8 6-2-8

Scale = 1:15.4



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.10	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.08	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr	YES	WB 0.03	Horz(TL)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 23 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, **except** end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size)

5=48/6-5-0, 3=118/6-5-0, 4=310/6-5-0
Max Horz 5=-96(LC 7)
Max Uplift 5=-16(LC 7), 4=-102(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-5=-26/29, 1-2=-28/6, 2-3=-99/36
BOT CHORD 4-5=-0/117, 3-4=-0/117
WEBS 2-4=-166/184


NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; **enclosed**; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 16 lb uplift at joint 5 and 102 lb uplift at joint 4.

LOAD CASE(S) Standard

[Signature]

OCT 15 2008




Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V4S GABLE 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:58 2008 Page 1



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/dell	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.07	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr	YES	WB 0.02	Horz(TL)	0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 33 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 7=80/8-2-8, 4=113/8-2-8, 6=166/8-2-8, 5=273/8-2-8
Max Horz 7=-127(LC 7)
Max Uplift 7=-26(LC 7), 6=-54(LC 7), 5=-90(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-7=-43/46, 1-2=-25/13, 2-3=-68/12, 3-4=-139/33
BOT CHORD 6-7=-0/152, 5-6=-0/152, 4-5=-0/152
WEBS 2-6=-89/96, 3-5=-146/159

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 7, 54 lb uplift at joint 6 and 90 lb uplift at joint 5.

LOAD CASE(S) Standard



OCT 15 2008


Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V6 VALLEY

2 1 Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:59 2008 Page 1



Scale = 1/5/3

Plate Offsets (X,Y): [2:Edge,0-1-14]

2-0-0(0-1-8)

2-0-0(0-1-8)

LOADING (psf)
TCLL 16.0
TCDL 7.0
BCLL 10.0
BCDL 10.0

SPACING 2-0-0
Plates Increase 1.25
Lumber Increase 1.25
Rep Stress Incr YES
Code FBC2004/TPI2002

CSI
TC 0.01
BC 0.01
WB 0.00
(Matrix)

DEFL in (loc) l/dell L/d
Vert(LL) n/a - n/a 999
Vert(TL) n/a - n/a 999
Horz(TL) 0.00 n/a n/a

PLATES GRIP
MT20 244/190
Weight: 5 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, **except** end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=48/2-0-0, 3=48/2-0-0
Max Horz 1=19(LC 6)
Max Uplift 1=8(LC 6), 3=-16(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-15/8, 2-3=-26/29
BOT CHORD 1-3=0/0

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 8 lb uplift at joint 1 and 16 lb uplift at joint 3.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type
DAVENPORT V7 VALLEY

Qty Ply DAVENPORT_125_9TM04001

2 1

Job Reference (optional)

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:59 2008 Page 1

Maronda Homes Inc., Sanford, Florida


4-0-0

2x4

4-0-0

2

Scale = 1/8" = 1'-0"



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.10	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.09	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	0.00		n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 13 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=134/4-0-0, 3=134/4-0-0
Max Horz 1=54(LC 6)
Max Uplift 1=-22(LC 6), 3=-44(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-40/22, 2-3=-72/81
BOT CHORD 1-3=0/0

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 1 and 44 lb uplift at joint 3.

LOAD CASE(S) Standard



OCT 15 2008


Job Truss Truss Type
DAVENPORT V8 VALLEY

Maronda Homes Inc., Sanford, Florida

Qty Ply DAVENPORT_125_9TM04001

2 1 Job Reference (optional)

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:34:00 2008 Page 1



Scale = 1:13.9

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.06	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr	YES	WB 0.02	Horz(TL)	0.00		n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						Weight: 21 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-10-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size)

1=63/5-10-0, 4=94/5-10-0, 5=269/5-10-0
Max Horz 1=86(LC 6)
Max Uplift 4=31(LC 6), 5=88(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=-99/26, 2-3=-31/15, 3-4=-51/57
BOT CHORD 1-5=0/0, 4-5=0/0
WEBS 2-5=-144/161

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 4 and 88 lb uplift at joint 5.

LOAD CASE(S) Standard

OCT 15 2008



PRODUCT APPROVAL INFORMATION SHEET

Project Name: 14/1 Timberlands

Permit #

Project Address: 135 SW Black Maple CT Lake City FL 32024

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and product approval number(s) for the building components listed below as applicable to the building construction project for the permit number listed above. You should contact your product supplier if you do not know the product approval number for any of the applicable listed products. Information regarding statewide product approval may be obtained at: www.floridabuilding.org.

Category/Subcategory	Manufacturer	Product Description	Limitation of use	State #	Local #
A. EXTERIOR DOORS					
1. Swinging	Plastpro	Fiberglass Doors	Design Pressure: +50.0/-50.0 Other: See INST 6729.1 and EVAL 6729.1 for any additional use limitations and installation instructions.	6729.1	
2. Sliding	Simonton/Nora ndex	Sliding Glass Doors	Design Pressure: +50/-50 Other: 3-lite 108x96 3-lite 144x96 Missile Impact Rating: Large	5979.1	
3. Sectional					
4. Roll-Up	Wayne Dalton	Garage Doors	As indicated in evaluation report and installation drawings. Not to be used in HVHZ. Doors with glazing shall not be used in the wind-borne debris region unless protected or unless structure is designed as partially enclosed or door is a replacement door	5287.1- 5287.2 9174.4 9174.5	
B. WINDOWS					
1. Single Hung	H-R Windows	Single-Hung Windows	Not for use in HVHZ	5089.1- 5089.9,2 09262 09242	
2. Horizontal					

Slider					
9. Mullion	H-R Windows	Mullions	Not for use in HVHZ. See uploaded drawing for size limits, design pressure limits, and all other limits of use.	5782.1	
C. PANEL WALL					
1. Siding	Owens Corning	Siding	Refer to Evaluation Report for specific product profiles, attachment and design pressures.	4617.1-4617-2	
2. Soffits	Owens Corning	Soffit	Refer to Evaluation Report for wind load limitations specific to each profile and span.	6869.1-6869-5	
7. Glass Block					
D. ROOFING PRODUCTS					
1. Asphalt Shingles	Owens Corning		Products must be install in accordance with Florida Building Code Non High Velocity Hurricane Zone Area and per Manufacturers Installation Drawings. This Approval not for use in the HVHZ.	3663.1-3663.9	
2. Underlayments	Owens Corning	Waterproofing Underlayment	This Approval does not cover HVHZ. Products shall be installed in accordance with FBC Sections for Non-HVHZ and per manufacturers Installation Drawings	3349.1-3349.2	
3. Roofing Tiles					
E. SHUTTERS			N/A		
F. STRUCTURAL COMPONENTS					
1. Wood connector/anchor	Simpson Strong-Tie Co	Wood Connectors Anchors, Structural adhesive, Adjustable Post Base, Truss Bearing Enhancer, Stud-Plate Connector	Limitations per attached evaluation report. Acceptable for HVHZ.	474-R1 503-R1 538-R1 1423-R2 1463-R2 1725-R1 1901-R3 2304-R1 2355-R2 3751-R1	
2. Truss Plates	MITek Industries, Inc.	Truss Plates Metal Connector Plate	Products must be install in accordance with Florida Building Code per Manufacturers Installation Drawings	2197.R1 2197.R2 7987-R1	

	Alpine Engineered Products, Inc.	Truss Plates Alpine HS Metal Connector Plate	per TPI 1-1995	1999R-2	
3. Engineered lumber	Trus Joist, A Weyerhaeuser Business	Engineered Lumber-e-Rim Board, Microllam LVL, Parallam PSL, TimberStrand LSL, TJ-Strand Rim Board, TJI	Products must be install in accordance with Florida Building Code and per Manufacturers Installation Drawings	1630-R3 4478-R1 6527-R1	
	Boise Engineered Wood Products	Engineered Wood "T" Joist-BCI 400s- BCI 900s. Versa- Lam SP (laminated veneer lumber). AJS ALLJOIST	Products must be install in accordance with Florida Building Code and per Manufacturers Installation Drawings	1392-R1 1644-R1 1645-R1	
H. NEW EXTERIOR ENVELOPE PRODUCTS					
1.	James Hardie Bldg Products	fiber-cement cladding	Installed per Manufacturers Installation Drawings. Anchor Size, Type and Spacing are determined by the type of construction per Manufacturers Installation Drawings.	889.1- 889.10-	

In addition to completing the above list of manufacturers, product description and State approval number for the products used on this project, it is the Contractor's or Authorized Agent's responsibility to have a legible copy of each manufacturer's printed instructions, along with the list above, on the job site available to the inspector.

The products listed below did not demonstrate product approval at time of plan review. I understand that before these products can be inspected, they must be submitted for review for code compliance and approved by a Plans Examiner. This form will be revised to include each new product in the categories listed above and will be highlighted to indicate the new products and required information.

PRODUCT APPROVAL INFORMATION SHEET

Project Name: 14/1 Timberlands Permit # _____

Project Address: 135 SW Black Maple CT. Lake City FL 32024

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and product approval number(s) for the building components listed below as applicable to the building construction project for the permit number listed above. You should contact your product supplier if you do not know the product approval number for any of the applicable listed products. Information regarding statewide product approval may be obtained at: www.floridabuilding.org.

Category/Subcategory	Manufacturer	Product Description	Limitation of use	State #	Local #
A. EXTERIOR DOORS					
1. Swinging	Plastpro	Fiberglass Doors	Design Pressure: +50.0/-50.0 Other: See INST 6729.1 and EVAL 6729.1 for any additional use limitations and installation instructions.	6729.1	
2. Sliding	Simonton/Nora	Sliding Glass Doors	Design Pressure: +50/-50 Other: 3-lite 108x96 3-lite 144x96 Missile Impact Rating: Large	5979.1	
3. Sectional					
4. Roll-Up	Wayne Dalton	Garage Doors	As indicated in evaluation report and installation drawings. Not to be used in HVHZ. Doors with glazing shall not be used in the wind-borne debris region unless protected or unless structure is designed as partially enclosed or door is a replacement door	5287.1- 5287.2 9174.4 9174.5	
B. WINDOWS					
1. Single Hung	H-R Windows	Single-Hung Windows	Not for use in HVHZ	5089.1- 5089.9,2 09262 09242	
2. Horizontal					

Slider					
9. Mullion	H-R Windows	Mullions	Not for use in HVHZ. See uploaded drawing for size limits, design pressure limits, and all other limits of use.	5782.1	
C. PANEL WALL					
1. Siding	Owens Corning	Siding	Refer to Evaluation Report for specific product profiles, attachment and design pressures.	4617.1-4617-2	
2. Soffits	Owens Corning	Soffit	Refer to Evaluation Report for wind load limitations specific to each profile and span.	6869.1-6869-5	
7. Glass Block					
D. ROOFING PRODUCTS					
1. Asphalt Shingles	Owens Corning		Products must be install in accordance with Florida Building Code Non High Velocity Hurricane Zone Area and per Manufacturers Installation Drawings. This Approval not for use in the HVHZ.	3663.1-3663.9	
2. Underlayments	Owens Corning	Waterproofing Underlayment	This Approval does not cover HVHZ. Products shall be installed in accordance with FBC Sections for Non-HVHZ and per manufacturers Installation Drawings	3349.1-3349.2	
3. Roofing Tiles					
E. SHUTTERS			N/A		
F. STRUCTURAL COMPONENTS					
1. Wood connector/anchor	Simpson Strong-Tie Co	Wood Connectors Anchors, Structural adhesive, Adjustable Post Base, Truss Bearing Enhancer, Stud-Plate Connector	Limitations per attached evaluation report. Acceptable for HVHZ.	474-R1 503-R1 538-R1 1423-R2 1463-R2 1725-R1 1901-R3 2304-R1 2355-R2 3751-R1	
2. Truss Plates	MITek Industries, Inc.	Truss Plates Metal Connector Plate	Products must be install in accordance with Florida Building Code per Manufacturers Installation Drawings	2197.R1 2197.R2 7987-R1	

	Alpine Engineered Products, Inc.	Truss Plates Alpine HS Metal Connector Plate	per TPI 1-1995	1999R-2	
3. Engineered lumber	Trus Joist, A Weyerhaeuser Business	Engineered Lumber-e-Rim Board, Microllam LVL, Parallam PSL, TimberStrand LSL, TJ-Strand Rim Board, TJI	Products must be install in accordance with Florida Building Code and per Manufacturers Installation Drawings	1630-R3 4478-R1 6527-R1	
	Boise Engineered Wood Products	Engineered Wood "I" Joist-BCI 400s- BCI 900s, Versa- Lam SP (laminated veneer lumber). AJS ALLJOIST	Products must be install in accordance with Florida Building Code and per Manufacturers Installation Drawings	1392-R1 1644-R1 1645-R1	
H. NEW EXTERIOR ENVELOPE PRODUCTS					
1.	James Hardie Bldg Products	fiber-cement cladding	Installed per Manufacturers Installation Drawings. Anchor Size, Type and Spacing are determined by the type of construction per Manufacturers Installation Drawings.	889.1- 889.10-	

In addition to completing the above list of manufacturers, product description and State approval number for the products used on this project, it is the Contractor's or Authorized Agent's responsibility to have a legible copy of each manufacturer's printed instructions, along with the list above, on the job site available to the inspector.

The products listed below did not demonstrate product approval at time of plan review. I understand that before these products can be inspected, they must be submitted for review for code compliance and approved by a Plans Examiner. This form will be revised to include each new product in the categories listed above and will be highlighted to indicate the new products and required information.

**COLUMBIA COUNTY BUILDING DEPARTMENT
RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST
FOR THE FLORIDA RESIDENTIAL BUILDING CODE 2004 with 2005 & 2006
Supplements and One (1) and Two (2) Family Dwellings**

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

ALL BUILDING PLANS MUST INDICATE COMPLIANCE with the Current FLORIDA BUILDING CODES and the Current FLORIDA RESIDENTIAL CODE. ALL PLANS OR DRAWING SHALL PROVIDED CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE- AND-TWO FAMILY DWELLINGS.

FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER FIGURE R301.2(4) of the Residential Code (Florida Wind speed map) SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE -----110 MPH
3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

GENERAL REQUIREMENTS:

- Two (2) complete sets of plans containing the following:
- All drawings must be clear, concise and drawn to scale, details that are not used shall be marked void
- Condition space (Sq. Ft.) and total (Sq. Ft.) under roof shall be shown on the plans.
- Designers name and signature shall be on all documents and a licensed architect or engineer, signature and official embossed seal shall be affixed to the plans and documents per FBC 106.1.

Site Plan information including:

- Dimensions of lot or parcel of land
- Dimensions of all building set backs
- Location of all other structures (include square footage of structures) on parcel, existing or proposed well and septic tank and all utility easements.
- Provide a full legal description of property.

Wind-load Engineering Summary, calculations and any details required:

- Plans or specifications must meet state compliance with FRC Chapter 3
- The following information must be shown as per section FRC
- Basic wind speed (3-second gust), miles per hour
- Wind importance factor and nature of occupancy
- Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated
- The applicable internal pressure coefficient, Components and Cladding The design wind pressure in terms of psf (kN/m²), to be used for the design of exterior component and cladding materials not specifiably designed by the registered design professional.

Elevations Drawing including:

- All side views of the structure
- Roof pitch
- Overhang dimensions and detail with attic ventilation
- Location, size and height above roof of chimneys
- Location and size of skylights with Florida Product Approval
- Number of stories
- e) Building height from the established grade to the roofs highest peak

Floor Plan including:

- Dimensioned area plan showing rooms, attached garage, breeze ways, covered porches, deck, balconies and raised floor surfaces located more than 30 inches above the floor or grade
- All exterior and interior shear walls indicated
- Shear wall opening shown (Windows, Doors and Garage doors)
- Emergency escape and rescue opening in each bedroom (net clear opening shown)
- Safety glazing of glass where needed
- Fireplaces types (gas appliance) (vented or non-vented) or wood burning with Hearth (see chapter 10 of FRC)
- Stairs with dimensions (width, tread and riser and total run) details of guardrails, Handrails (see FRC 311)
- Plans must show and identify accessibility of bathroom (see FRC 322)

All materials placed within opening or onto/into exterior shear walls, soffits or roofs shall have Florida product approval number and mfg. installation information submitted with the plans (see Florida product approval form)

Foundation Plans Per FRC 403:

- a) Location of all load-bearing walls footings indicated as standard, monolithic, dimensions, size and type of reinforcing.
- b) All posts and/or column footing including size and reinforcing
- c) Any special support required by soil analysis such as piling.
- d) Assumed load-bearing value of soil _____ (psf)
- e) Location of horizontal and vertical steel, for foundation or walls (include # size and type)

CONCRETE SLAB ON GRADE Per FRC R506

- Show Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)
- Show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and Supports

PROTECTION AGAINST TERMITES Per FRC 320:

- Indicate on the foundation plan if soil treatment is used for subterranean termite prevention or submit other approved termite protection methods. Protection shall be provided by registered termiticides

Masonry Walls and Stem walls (load bearing & shear Walls) FRC Section R606

- Show all materials making up walls, wall height, and Block size, mortar type
- Show all Lintel sizes, type, spans and tie-beam sizes and spacing of reinforcement

Metal frame shear wall and roof systems shall be designed, signed and sealed by Florida Prof. Engineer or Architect

Floor Framing System: First and/or second story

- Floor truss package shall including layout and details, signed and sealed by Florida Registered Professional Engineer
- Show conventional floor joist type, size, span, spacing and attachment to load bearing walls, stem walls and/or piers
- Girder type, size and spacing to load bearing walls, stem wall and/or piers
- Attachment of joist to girder
- Wind load requirements where applicable
- Show required under-floor crawl space
- Show required amount of ventilation opening for under-floor spaces
- Show required covering of ventilation opening.
- Show the required access opening to access to under-floor spaces
- Show the sub-floor structural panel sheathing type, thickness and fastener schedule on the edges & intermediate of the areas structural panel sheathing
- Show Draft stopping, Fire caulking and Fire blocking
- Show fireproofing requirements for garages attached to living spaces, per FRC section R309
- Provide live and dead load rating of floor framing systems (psf).

WOOD WALL FRAMING CONSTRUCTION FRC CHAPTER 6

- Stud type, grade, size, wall height and oc spacing for all load bearing or shear walls.
- Fastener schedule for structural members per table R602.3 (1) are to be shown.
- Show wood structural panel's sheathing attachment to studs, joist, trusses, rafters and structural members, showing fastener schedule attachment on the edges & intermediate of the areas structural panel sheathing
- Show all required connectors with a max uplift rating and required number of connectors and oc spacing for continuous connection of structural walls to foundation and roof trusses or rafter systems.
- Show sizes, type, span lengths and required number of support jack studs, king studs for shear wall opening and girder or header per FRC Table R502.5 (1)
- Indicate where pressure treated wood will be placed.
- Show all wall structural panel sheathing, grade, thickness and show fastener schedule for structural panel sheathing edges & intermediate areas
- A detail showing gable truss bracing, wall balloon framing details or/ and wall hinge bracing detail

ROOF SYSTEMS:

- Truss design drawing shall meet section FRC R802.10 Wood trusses. Include a layout and truss details and be signed and sealed by Fl. Pro. Eng.
- Show types of connector's assemblies' and resistance uplift rating for all trusses and rafters
- Show gable ends with rake beams showing reinforcement or gable truss and wall bracing details
- Provide dead load rating of trusses

Conventional Roof Framing Layout Per FRC 802:

- Rafter and ridge beams sizes, span, species and spacing
- Connectors to wall assemblies' include assemblies' resistance to uplift rating.
- Valley framing and support details
- Provide dead load rating of rafter system.

ROOF SHEATHING FRC Table R602.3(2) FRC 803

- Include all materials which will make up the roof decking, identification of structural panel sheathing, grade, thickness and show fastener schedule for structural panel sheathing on the edges & intermediate areas

ROOF ASSEMBLIES FRC Chapter 9

- Include all materials which will make up the roof assemblies covering; with Florida Product Approval numbers for each component of the roof assemblies covering.

FCB Chapter 13 Florida Energy Efficiency Code for Building Construction

- Residential construction shall comply with this code by using the following compliance methods in the FBC Subchapter 13-6, Residential buildings compliance methods. Two of the required forms are to be submitted, showing dimensions condition area equal to the total condition living space area
- Show the insulation R value for the following areas of the structure: Attic space, Exterior wall cavity and Crawl space (if applicable)

HVAC information shown

- Manual J sizing equipment or equivalent computation
- Exhaust fans locations in bathrooms

Plumbing Fixture layout shown

- All fixtures waste water lines shall be shown on the foundation plan

Electrical layout shown including:

- Switches, outlets/receptacles, lighting and all required GFCI outlets identified
- Ceiling fans
- Smoke detectors
- Service panel, sub-panel, location(s) and total ampere ratings

- On the electrical plans identify the electrical service overcurrent protection device for the main electrical service. This device shall be installed on the exterior of structures to serve as a disconnecting means for the utility company electrical service. Conductors used from the exterior disconnecting means to a panel or sub panel shall have four-wire conductors, of which one conductor shall be used as an equipment ground. Indicate if the utility company service entrance cable will be of the overhead or underground type.
- Appliances and HVAC equipment and disconnects
- Arc Fault Circuits (AFCI) in bedrooms
- Notarized Disclosure Statement for Owner Builders
- Notice of Commencement Recorded (in the Columbia County Clerk Office) Notice Of Commencement is required to be filed with the building department Before Any Inspections Will Be Done.

Private Potable Water

- Size of pump motor
- Size of pressure tank
- Cycle stop valve if used

THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

- Building Permit Application: A current Building Permit Application form is to be completed and submitted for all residential projects.
- Parcel Number: The parcel number (Tax ID number) from the Property Appraiser (386) 758-1084 is required. A copy of property deed is also requested.
- Environmental Health Permit or Sewer Tap Approval: A copy of the Environmental Health permit, existing septic approval or sewer tap approval is required before a building permit can be issued. (386) 758-1058 (Toilet facilities shall be provided for construction workers)
- City Approval: If the project is to be located within the city limits of the Town of Fort White, prior approval is required. The Town of Fort White approval letter is required to be submitted by the owner or contractor to this office when applying for a Building Permit. (386) 497-2321
- Flood Information: All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.8 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.7 of the Columbia County Land Development Regulations. **CERTIFIED FINISHED FLOOR ELEVATIONS WILL BE REQUIRED ON ANY PROJECT WHERE THE BASE FLOOD ELEVATION (100 YEAR FLOOD) HAS BEEN ESTABLISHED.** A development permit will also be required. The permit cost is \$50.00.
- Driveway Connection: If the property does not have an existing access to a public road, then an application for a culvert permit (\$25.00) must be made. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (\$50.00). All culvert waivers are sent to the Columbia County Public Works Department for approval or denial.
- 911 Address: If the project is located in an area where the 911 address has been issued, then the proper Paper work from the 911 Addressing Departments must be submitted. (386) 758-1125

ALL REQUIRED INFORMATION IS TO BE SUBMITTED FOR REVIEW. NOTIFICATION WILL BE GIVEN WHEN THE APPLICATION AND PLANS ARE APPROVED AND READY TO PERMIT.

PRODUCT APPROVAL SPECIFICATION SHEET

Location: _____

Project Name: _____

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and the product approval number(s) on the building components listed below if they will be utilized on the construction project for which you are **applying for a building permit on or after April 1, 2004**. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. More information about statewide product approval can be obtained at www.floridabuilding.org

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
A. EXTERIOR DOORS			
1. Swinging			
2. Sliding			
3. Sectional			
4. Roll up			
5. Automatic			
6. Other			
B. WINDOWS			
1. Single hung			
2. Horizontal Slider			
3. Casement			
4. Double Hung			
5. Fixed			
6. Awning			
7. Pass-through			
8. Projected			
9. Mullion			
10. Wind Breaker			
11. Dual Action			
12. Other			
C. PANEL WALL			
1. Siding			
2. Soffits			
3. EIFS			
4. Storefronts			
5. Curtain walls			
6. Wall louver			
7. Glass block			
8. Membrane			
9. Greenhouse			
10. Other			
D. ROOFING PRODUCTS			
1. Asphalt Shingles			
2. Underlayments			
3. Roofing Fasteners			
4. Non-structural Metal Rf			
5. Built-Up Roofing			
6. Modified Bitumen			
7. Single Ply Roofing Sys			
8. Roofing Tiles			
9. Roofing Insulation			
10. Waterproofing			
11. Wood shingles /shakes			
12. Roofing Slate			

Category/Subcategory (cont.)	Manufacturer	Product Description	Approval Number(s)
13. Liquid Applied Roof Sys			
14. Cements-Adhesives – Coatings			
15. Roof Tile Adhesive			
16. Spray Applied Polyurethane Roof			
17. Other			
E. SHUTTERS			
1. Accordion			
2. Bahama			
3. Storm Panels			
4. Colonial			
5. Roll-up			
6. Equipment			
7. Others			
F. SKYLIGHTS			
1. Skylight			
2. Other			
G. STRUCTURAL COMPONENTS			
1. Wood connector/anchor			
2. Truss plates			
3. Engineered lumber			
4. Railing			
5. Coolers-freezers			
6. Concrete Admixtures			
7. Material			
8. Insulation Forms			
9. Plastics			
10. Deck-Roof			
11. Wall			
12. Sheds			
13. Other			
H. NEW EXTERIOR ENVELOPE PRODUCTS			
1.			
2.			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) the performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturers installation requirements.

I understand these products may have to be removed if approval cannot be demonstrated during inspection

Contractor or Contractor's Authorized Agent Signature

Print Name

Date

Location

Permit # (FOR STAFF USE ONLY)

02/02/04 – 2 of 2

Website: www.lcpermits.org

Effective April 1, 2004

Maronda Systems	4005 Maronda Way	Sanford FL 32771	(407) 321-0064	Fax (407) 321-3913
Engineer/Architect of Record:	Tomas Ponce, P.E.	367 Medallion PL.	Chuluota, FL 32766	FL PE # 50068,
Design Criteria: TPI	Design: Matrix Analysis	MiTek software		

PLAN JOB #	LOT	ADDRESS	DIV/SUB	MODEL	DAVENPORT A-M
9TM01401	14-1	135SW BLACK MAPLE CT	JAX-9TM	DVPM4 LEFT	

This structure was designed in accordance with, and meets the requirements of TPI standards and the FLORIDA 2004 BUILDING CODE for 125 M.P.H. Wind Zone. Truss loading is in accordance with ASCE 7-02. These trusses are designed for an enclosed building.

The Truss Engineering package for the above referenced site was generated by the Truss Designer/Architect/MiTek/Trenco.

I, Tomas Ponce, P.E. the Architect/Engineer of Record for the above referenced lot
Have reviewed the package and confirmed that it matches the physical and structural
Parameters found on the set of permit drawings.

[illegible]


HARDWARE LEGEND

- 1 HUS26
- 2 HUS28
- 3 JUS26
- 4 MP6F
- 5 MPA1 & MPA1F
- 6 SKH26 L/R
- 7 SKHH26 L/R
- 8 SUS26
- 9 SUS28
- 10 THD26
- 11 THD28
- 12 THD28-2
- 13 THDH28-3
- 14 THD48
- 15 THJ26**
- 16 LTW12

HARDWARE MANUFACTURED
BY USP

* HARDWARE MANUFACTURED
BY SIMPSON

** HARDWARE MANUFACTURED
BY CLEVELAND



DAVENPORT ELEVATION "A", "M"-FL

DESIGNER: WCA
CHECKER: MIKE

SCALE: 1/8" = 1'-0"
DATE: 10/18/2007

DESIGNER: K WARD

LOADING-FBC2004/TP12002


TC LIVE	15.00	SNOW LOAD	0.00
TC DEAD	7.00	LUMBER DOL	1.25
BC LIVE	10.00	PLATE DOL	1.25
BC DEAD	10.00	WIND	125
TOTAL	43.00	SPACING	2'-0"

GARAGE : LEFT

COPYRIGHT © 2007 MARONDA HOMES

Maronda Homes

14071 321-0064 4005 MARONDA WAY SANFORD, FLORIDA



1800 648 3387 • mttxsupport@mttx.com

OCT 29 2008

GENERAL NOTES

Trusses are not marked in any way to identify the frequency or location of temporary lateral restraint and diagonal bracing. Follow the recommendations for handling, installing and temporary restraining and bracing of trusses. Refer to BCSI Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for more detailed information.

Truss Design Drawings may specify locations of permanent lateral restraint or reinforcement for individual truss members. Refer to the BCSI-B3 Summary Sheet - Permanent Restraint/Bracing of Chords & Web Members for more information. All other permanent bracing design is the responsibility of the Building Designer.

Warning! The consequences of improper handling, erecting, installing, restraining and bracing can result in a collapse of the structure, or worse, serious personal injury or death.

El resultado de un manejo, levantamiento, instalación, restricción y arrioste incorrecto puede ser la caída de la estructura o aún peor, heridos o muertos.



Warning! Banding and truss plates have sharp edges. Wear gloves when handling and safety glasses when cutting banding.

Empaques y placas de metal tienen bordes afilados. Use guantes y lentes protectores cuando corte los empaques.

NOTAS GENERALES


Los trusses no están marcados de ningún modo que identifique la frecuencia o localización de restricción lateral y arrioste diagonal temporales. Use las recomendaciones de manejo, instalación, restricción y arrioste temporal de los trusses. Vea el folleto BCSI Guía de Buena Práctica para el Manejo, Instalación, Restricción y Arrioste de los Trusses de Madera Conectados con Placas de Metal para información más detallada.

Los dibujos de diseño de los trusses pueden especificar las localizaciones de restricción lateral permanente o refuerzo en los miembros individuales del truss. Vea la hoja resumen BCSI-B3 - Restricción/Arrioste Permanente de Cuerdas y Miembros Secundarios para más información. El resto de los diseños de arriostres permanentes son la responsabilidad del Diseñador del Edificio.




HANDLING — MANEJO

Warning! Avoid lateral bending. — Evite la flexión lateral.



Warning! Use special care in windy weather or near power lines and airports.

Utilice cuidado especial en días ventosos o cerca de cables eléctricos o de aeropuertos.




Warning! Use proper rigging and hoisting equipment.

Use equipo apropiado para levantar e improvisar.

Warning! The contractor is responsible for properly receiving, unloading and storing the trusses at the jobsite.

El contratista tiene la responsabilidad de recibir, descargar y almacenar adecuadamente los trusses en la obra.



Warning! If trusses are to be stored horizontally, place blocking of sufficient height beneath the stack of trusses at 8' to 10' on center.

For trusses stored for more than one week, cover bundles to prevent moisture gain but allow for ventilation.

Refer to BCSI Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for more detailed information pertaining to handling and jobsite storage of trusses.


Si los trusses estarán guardados horizontalmente, ponga bloqueando de altura suficiente detrás de la pila de los trusses.

Para trusses guardados por más de una semana, cubra los paquetes para prevenir aumento de humedad pero permita ventilación.

Vea el folleto BCSI Guía de Buena Práctica para el Manejo, Instalación, Restricción y Arrioste de los Trusses de Madera Conectados con Placas de Metal para información más detallada sobre el manejo y almacenamiento de los trusses en área de trabajo.

Warning! Do not store unbraced bundles upright.

No almacene verticalmente los trusses sueltos.



Warning! Do not store on uneven ground.

No almacene en tierra desigual.



HOISTING RECOMMENDATIONS FOR TRUSS BUNDLES RECOMENDACIONES PARA LEVANTAR PAQUETES DE TRUSSES.

Warning! Don't overload the crane.

¡Advertencia! No sobrecarga la grúa!

Warning! Never use banding alone to lift a bundle. Do not lift a group of individually banded bundles.


Nunca use sólo los empaques para levantar un paquete. No levante un grupo de empaques individuales.

Warning! A single lift point may be used for bundles with trusses up to 45'. Two lift points may be used for bundles with trusses up to 60'. Use at least 3 lift points for bundles with trusses greater than 60'.

Puede usar un solo lugar de levantar para paquetes de trusses hasta 45 pies.

Puede usar dos puntos de levantar para paquetes más de 60 pies.

Use por lo menos tres puntos de levantar para paquetes más de 60 pies.




Warning! Do not over load supporting structure with truss bundle. ¡Advertencia! No sobrecargue la estructura apoyada con el paquete de trusses.

Warning! Place truss bundles in stable position. Puse paquetes de trusses en una posición estable.

INSTALLATION OF SINGLE TRUSSES BY HAND INSTALACIÓN POR LA MANO DE TRUSSES INDIVIDUALES


Warning! Trusses 20' or less, support at peak.

Levante del pico los trusses de 20 pies o menos.



Warning! Trusses 30' or less, support at quarter points.

Levante de los cuartos de tramo los trusses de 30 pies o menos.



HOISTING OF SINGLE TRUSSES — LEVANTAMIENTO DE TRUSSES INDIVIDUALES

Warning! Hold each truss in position with the erection equipment until top chord temporary lateral restraint is installed and the truss is fastened to the bearing points.



Sostenga cada truss en posición con equipo de grúa hasta que la restricción lateral temporal de la cuerda superior esté instalada y el truss está asegurado en los soportes.

Warning! Using a single pick-point at the peak can damage the truss.

¡Advertencia! El uso de un solo lugar para levantar en el pico puede hacer daño al truss.



HOISTING RECOMMENDATIONS FOR SINGLE TRUSSES RECOMENDACIONES PARA LEVANTAR TRUSSES INDIVIDUALES




TEMPORARY RESTRAINT & BRACING RESTRICCIÓN Y ARRIOSTRE TEMPORAL

Warning! Refer to BCSI-B2 Summary Sheet - Truss Installation & Temporary Restraint/Bracing for more information.

Vea el resumen BCSI B2 - Restricción/Arrioste Temporal y Instalación de los Trusses para más información.


Warning! Locate ground braces for first truss directly in line with all rows of top chord temporary lateral restraint (see table in the next column).

Coloque los arriostres de tierra para el primer truss directamente en línea con cada una de las filas de restricción lateral temporal de la cuerda superior (vea la tabla en la próxima columna).



Warning! Do not walk on unbraced trusses.

No camine en trusses sueltos.



STEPS TO SETTING TRUSSES

AS MEDIDAS DE LA INSTALACIÓN DE LOS TRUSSES

- 1) Install ground bracing. 2) Set first truss and attach securely to ground bracing. 3) Set next 4 trusses with short member temporary lateral restraint (see below). 4) Install top chord diagonal bracing (see below). 5) Install web member plane diagonal bracing to stabilize the first five trusses (see below). 6) Install bottom chord temporary lateral restraint and diagonal bracing (see below). 7) Repeat process on groups of four trusses until all trusses are set.

- 1) Instale los arriostres de tierra. 2) Instale el primero truss y ate seguramente al arriostre de tierra. 3) Instale los próximos cuatro trusses con restricción lateral temporal de miembro corto (vea abajo). 4) Instale el arriostre diagonal de la cuerda superior (vea abajo). 5) Instale arriostre diagonal para los planos de los miembros secundarios para estable los primeros cinco trusses (vea abajo). 6) Instale la restricción lateral temporal y arriostre diagonal para la cuerda inferior (vea abajo). 7) Repita éste procedimiento en grupos de cuatro trusses hasta que todos los trusses estén instalados.

Refer to BCSI-B2 Summary Sheet - Truss Installation & Temporary Restraint/Bracing for more information.

Vea el resumen BCSI-B2 - Instalación de Trusses y Arriostre Temporal para mayor información.

RESTRAINT/BRACING FOR ALL PLANES OF TRUSSES

RESTRICCIÓN/ARRIOSTRE EN TODOS PLANOS DE TRUSSES.

This restraint & bracing method is for all trusses except 3x2 and 4x2 parallel chord trusses.

Este método de restricción y arriostre es para todo trusses excepto trusses de cuerdas paralelas 3x2 y 4x2.

TOP CHORD — CUERDA SUPERIOR

Truss Span Longitud de Tramo	Top Chord Temporary Lateral Restraint (TCLTR) Spacing Espaciamiento del Arriostre Temporal de la Cuerda Superior
Up to 30'	10' o.c. max.
Hasta 30 pies	10 pies máximo
30' to 45'	8' o.c. max.
30 a 45 pies	8 pies máximo
45' to 60'	6' o.c. max.
45 a 60 pies	6 pies máximo
60' to 80'+	4' o.c. max.
60 a 80 pies*	4 pies máximo


*Consult a Professional Engineer for trusses longer than 60'.

*Consulte a un Ingeniero para trusses de mas de 60 pies.

See BCSI-B2 for TCLTR options.
Vea el BCSI-B2 para las opciones de TCLTR.


Refer to BCSI-B3 Summary Sheet - Permanent Restraint/Bracing of Chords & Web Members for Gable End Frame restraint/bracing/reinforcement information.

Para información sobre restricción/arriostre/refuerzo para armazón de hastial vea el resumen BCSI-B3 - Restricción/Arriostre Permanente de Cuerdas y Miembros Secundarios.



WEB MEMBER PLANE — PLANO DE LOS MIEMBROS SECUNDARIOS

LATERAL RESTRAINT & DIAGONAL BRACING ARE VERY IMPORTANT LA RESTRICCIÓN LATERAL Y EL ARRIOSTRE DIAGONAL SON MUY IMPORTANTES!




10'-15' max. Same spacing as bottom chord Lateral Restraint

Some chord and web members not shown for clarity.

BOTTOM CHORD — CUERDA INFERIOR

Lateral Restraints - 2x4x12' or greater lapped over two trusses.




Some chord and web members not shown for clarity.

RESTRAINT & BRACING FOR 3x2 AND 4x2 PARALLEL CHORD TRUSSES

LA RESTRICCIÓN Y EL ARRIOSTRE PARA TRUSSES DE CUERDAS PARALELAS 3X2 Y 4X2

Refer to BCSI-B7 Summary Sheet - Temporary & Permanent Restraint/Bracing for Parallel Chord Trusses for more information.


Vea el resumen BCSI-B7 - Restricción y Arriostre Temporal y Permanente de Trusses de Cuerdas Paralelas para más información.



*Top chord Temporary Lateral Restraint spacing shall be 10' o.c. max. for 3x2 chords and 15' o.c. for 4x2 chords.


INSTALLING — INSTALACION

Tolerances for Out-of-Plane.
Tolerancias para Fuera-de-Plano.



Tolerances for Out-of-Plumb.
Tolerancias para Fuera-de-Plomada.

D/50 max.



D/50	D (ft.)
1/4"	1'
1/2"	2'
3/4"	3'
1"	4'
1-1/4"	5'
1-1/2"	6'
1-3/4"	7'
2"	≥8'

Max. Bow	Truss Length
3/4"	12.5'
7/8"	14.6'
1"	16.7'
1-1/8"	18.8'
1-1/4"	20.8'
1-3/8"	22.9'
1-1/2"	25.0'
1-3/4"	29.2'
2"	≥33.3'

CONSTRUCTION LOADING — CARGA DE CONSTRUCCION

Do not proceed with construction until all lateral restraint and bracing is securely and properly in place.

No proceda con la construcción hasta que todas las restricciones laterales y los arriostres estén colocados en forma apropiada y segura.

Do not exceed maximum stack heights. Refer to BCSI-B4 Summary Sheet - Construction Loading for more information.

No exceda las máximas alturas recomendadas. Vea el resumen BCSI-B4 Carga de Construcción para mayor información.

Material	Height
Gypsum Board	12"
Plywood or OSB	16"
Asphalt Shingles	2 bundles
Concrete Block	8"
Clay Tile	3-4 ties high



Do not overload small groups or single trusses. No sobrecargue pequeños grupos o trusses individuales.

Never stack materials near a peak. Nunca amontone material cerca del pico.

Place loads over as many trusses as possible. Coloque las cargas sobre tantos trusses como sea posible.

Position loads over load bearing walls. Coloque las cargas sobre las paredes soportantes.




ALTERATIONS — ALTERACIONES

Refer to BCSI-B5 Summary Sheet - Truss Damage, Jobsite Modifications & Installation Errors.

Vea el resumen BCSI-B5 Daños de trusses, Modificaciones en la Obra y Errores de Instalación.

Do not cut, alter, or drill any structural member of a truss unless specifically permitted by the Truss Design Drawing.

No corte, altere o perforo ningún miembro estructural de los trusses, a menos que esté específicamente permitido en el dibujo del diseño del truss.



Trusses that have been overloaded during construction or altered without the Truss Manufacturer's prior approval may render the Truss Manufacturer's limited warranty null and void.

Trusses que se han sobrecargado durante la construcción o han sido alterados sin una autorización previa del Fabricante de Trusses, pueden reducir o eliminar la garantía del Fabricante de Trusses.

NOTE: The Truss Manufacturer and Truss Designer rely on the presumption that the Contractor and crane operator (if applicable) are professionals with the capability to undertake the work they have agreed to do on any given project. If the Contractor believes it needs assistance in some aspect of the construction project, it should seek assistance from a competent party. The methods and procedures outlined in this document are intended to ensure that the overall construction techniques employed will put the trusses into place SAFELY. These recommendations for handling, installing, restraining and bracing trusses are based upon the collective experience of leading personnel involved with truss design, manufacture and installation, but must, due to the nature of responsibilities involved, be presented as only a GUIDE for use by a qualified Building Designer or Contractor. It is not intended that these recommendations be interpreted as superior to the Building Designer's design specification for handling, installing, restraining and bracing trusses and it does not preclude the use of other equivalent methods for restraining/bracing and providing stability for the walls, columns, floors, roofs and all the interrelated structural building components as determined by the Contractor. Thus, WITCA and TPI expressly disclaim any responsibility for damages arising from the use, application, or reliance on the recommendations and information contained herein.



6300 Enterprise Lane • Madison, WI 53719
608/274-4849 • www.stcindustry.com



TRUSS PLATE INSTITUTE
218 N. Lee St., Ste. 312 • Alexandria, VA 22314
703/683-1010 • www.tpins.com

B1WARN11x17 20061115

Maronda Systems

MARONDA SYSTEMS

4005 Maronda Way

Sanford, FL 32771

(407) 321-0064

Fax (407) 321-3913

Date: November 1, 2006

To: Building Department

From: Maronda Systems

Tomas Ponce

Professional Engineer


State of Florida #0050068

Subject: Valley Trusses

All valley trusses labeled V-1 through 100 are covered under the general valley sheet provided in the truss package signed and sealed by the engineer of record. The connections are noted on the structural info sheet of the plans. All criteria of the valley trusses are noted on the general sheet.

If you have any questions please feel free to call at 407-321-0064.

Sincerely,



Tomas Ponce, P.E.

Date: 11/1/06

STRONGBACKING PROVISIONS

Strongbacking is intended to enhance the performance of the truss by helping to limit differential deflection between adjacent trusses and to reduce vibration. Strongbacking is generally attached near the bottom of vertical webs or scabs at specified intervals and locations indicated on the Truss Design Drawing (TDD). ANSI/TPI 1 provides the following provisions for using strongbacking:

- ✓ The Building Designer specifies if strongbacking is required.
- ✓ Use a minimum 2x6 (nominal) lumber oriented with the depth vertical.
- ✓ Attach the strongbacking to each truss with a minimum of three (3) 16d common nails (0.162x3.5"). Shim the joint between the strongback and truss to ensure a solid connection.
- ✓ The strongbacking shall be as continuous as possible. When required to be cut, removed, or modified to allow for the installation of mechanical and/or plumbing lines, the continuity at the adjoining floor sections shall be maintained as specified by the Truss Designer.
- ✓ Spacing between strongbacking shall not exceed 10'.
- ✓ When specified to control vibration in floor assemblies, locate the strongbacking as stipulated on the Truss Design Drawing unless otherwise specified by the Building Designer.
- ✓ When specified to control deflection in floor assemblies, unless otherwise specified by the Truss Designer, install one strongback near the centerline of the truss clear span when the deflection due to live load exceeds 0.67" and install two strongbacks near the centerline of the clear span, or near the third points of the truss span, when the live load deflection exceeds 0.85".
- ✓ Floor trusses with ceilings attached that meet span/480 live load deflection criteria do not require strongbacking, unless required for a specific fire-rated assembly or specified in the Construction Documents.




FIGURE B7-12




FIGURE B7-14

- ✓ Attach the ends of each row of strongbacks to a wall or another secure end restraint.
- ✓ Many Truss Manufacturers will also include a supplemental tag, such as the one shown above, to further assist the erection/installation Contractor in correctly installing strongbacking.

LATERAL RESTRAINT & DIAGONAL BRACING ARE VERY IMPORTANT!



FIGURE B7-15

⊘ DO NOT WALK ON UNBRACED TRUSSES






FIGURE B7-13

NOV 02 2006






Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
DAVENPORT HS2 SPECIAL 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MITek Industries, Inc. Fri Oct 10 14:33:33 2008 Page 1

-1-0-0 6-8-6 12-10-3 19-0-0 27-0-0 33-2-13 39-5-11 46-0-0 47-0-0
1-0-0 6-8-6 6-1-13 6-1-13 8-0-0 6-2-13 6-2-13 6-6-5 1-0-0
Scale = 1:79.6



6-4-3 6-8-6 12-10-3 19-0-0 26-0-0 35-10-4 46-0-0
6-4-3 0-4-3 6-1-13 6-1-13 7-0-0 9-10-4 10-1-12

Plate Offsets (X,Y): [4:0-3-0,Edge], [6:0-5-4,0-2-4], [7:0-3-8,0-2-4], [9:0-3-0,Edge], [10:0-0-0,0-0-0], [11:0-3-4,0-2-0], [13:0-5-0,0-4-8], [15:0-5-0,0-4-8], [17:0-5-0,0-0-13]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.74	Vert(LL)	-0.36 13-14	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.94	Vert(TL)	-0.72 13-14	>652	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.90	Horz(TL)	-0.28 17	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						Weight: 265 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-8-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 4-9-11 oc bracing.

REACTIONS

(lb/size) 17=3204/0-8-6, 2=-741/0-8-0, 11=1563/0-8-6
Max Horz 11=137(LC 6)
Max Uplift 17=-566(LC 5), 2=-799(LC 11), 11=-368(LC 7)
Max Grav 17=3204(LC 1), 2=45(LC 7), 11=1563(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 7-8=-2819/907, 8-9=-4161/1218, 9-10=-4224/1208, 10-11=-4432/1437, 11-12=0/11, 6-7=-2705/902,
1-2=0/14, 2-3=-678/2453, 3-4=-846/279, 4-5=-785/297, 5-6=-1817/661
BOT CHORD 13-14=-911/3564, 11-13=-1217/4053, 16-17=-2355/768, 15-16=-43/758, 14-15=-261/1669,
2-17=-2169/701
WEBS 10-13=-135/314, 8-13=-7/660, 8-14=-977/423, 7-14=-48/744, 6-14=-293/1348, 6-15=-423/217,
5-15=-253/1105, 5-16=-1173/481, 3-16=-813/3094, 3-17=-2463/873


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearing at joint(s) 11 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 566 lb uplift at joint 17, 799 lb uplift at joint 2 and 368 lb uplift at joint 11.

LOAD CASE(S) Standard

[Signature]

OCT 15 2008




Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001
DAVENPORT HS3 SPECIAL 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:34 2008 Page 1

-1-0-0 6-8-6 12-10-3 19-0-0 25-1-8 33-2-13 39-5-11 46-0-0 47-0-0
1-0-0 6-8-6 6-1-13 6-1-13 6-1-8 8-1-5 6-2-13 6-6-5 1-0-0
Scale = 1/79.6



6-4-3 6-8-6 12-10-3 19-0-0 25-1-8 26-10-8 36-3-8 46-0-0
6-4-3 0-4-3 6-1-13 6-1-13 6-1-8 1-9-0 9-5-0 9-8-8

Plate Offsets (X,Y): [4:0-3-0,Edge], [6:0-5-12,0-2-8], [8:0-3-0,0-2-4], [10:0-3-0,Edge], [11:0-0-0,0-0-0], [12:0-3-4,0-2-0], [14:0-5-0,0-4-8], [15:0-5-4,0-3-12], [17:0-5-0,0-4-8], [19:0-5-0,0-0-13]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.76	Vert(LL)	-0.35 14-15	>999	240	MT20	244/190
TCCL 7.0	Lumber Increase	1.25	BC 0.94	Vert(TL)	-0.70 14-15	>669	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.67	Horz(TL)	-0.27 19	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 277 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-8-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 4-9-13 oc bracing.

REACTIONS (lb/size) 19=3199/0-8-6, 2=-736/0-8-0, 12=1564/0-8-6

Max Horz 12=137(LC 6)
Max Uplift 19=-566(LC 5), 2=-794(LC 11), 12=-368(LC 7)
Max Grav 19=3199(LC 1), 2=43(LC 7), 12=1564(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 8-9=-2923/925, 9-10=-4197/1239, 10-11=-4260/1228, 11-12=-4448/1424, 12-13=0/11, 6-7=-2553/893,
7-8=-2666/906, 1-2=0/14, 2-3=-677/2443, 3-4=-850/282, 4-5=-790/301, 5-6=-1819/656
BOT CHORD 14-15=-923/3558, 12-14=-1205/4064, 15-16=-479/2539, 18-19=-2345/768, 17-18=-47/763,
16-17=-252/1655, 2-19=-2160/701
WEBS 11-14=-110/286, 9-14=-19/668, 9-15=-901/435, 7-15=-129/388, 7-16=-525/187, 6-16=-311/1240,
6-17=-393/209, 5-17=-239/1091, 5-18=-1177/483, 3-18=-816/3092, 3-19=-2457/872, 8-15=-180/893


NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCCL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 566 lb uplift at joint 19, 794 lb uplift at joint 2 and 368 lb uplift at joint 12.


LOAD CASE(S) Standard

[Signature]

OCT 15 2008



Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001				
DAVENPORT	HS4	SPECIAL	1	1	Job Reference (optional)				
Maronda Homes Inc., Sanford, Florida					7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:34 2008 Page 1				
-1-0-0	6-8-6	11-10-3	17-0-0	23-1-8	29-0-0	34-6-13	40-1-11	46-0-0	47-0-0
1-0-0	6-8-6	5-1-13	5-1-13	6-1-8	5-10-8	5-6-13	5-6-13	5-10-5	1-0-0
Scale = 1:79.6									



6-4-3	6-8-6	11-10-3	17-0-0	23-1-8	28-10-8	37-3-8	46-0-0
6-4-3	0-4-3	5-1-13	5-1-13	6-1-8	5-9-0	8-5-0	8-8-8
Plate Offsets (X,Y): [4:0-3-0,Edge], [6:0-5-12,0-2-8], [8:0-3-0,0-2-4], [10:0-3-0,Edge], [11:0-0-0,0-0-0], [12:0-3-4,0-2-0], [14:0-5-0,0-4-8], [17:0-5-0,0-4-8]							

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.77	Vert(LL)	-0.34 14-15	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.95	Vert(TL)	-0.67 14-15	>693	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.54	Horz(TL)	-0.27 19	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
Weight: 271 lb									

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 2-9-7 oc purlins.
BOT CHORD 2 X 6 SYP No.2	BOT CHORD Rigid ceiling directly applied or 4-7-1 oc bracing.
WEBS 2 X 4 SYP No.2	

REACTIONS (lb/size) 19=3305/0-8-6, 2=-827/0-8-0, 12=1549/0-8-6
 Max Horz 12=124(LC 6)
 Max Uplift 19=628(LC 5), 2=-901(LC 11), 12=-355(LC 7)
 Max Grav 19=3305(LC 1), 2=38(LC 7), 12=1549(LC 1)


FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 8-9=-3175/1032, 9-10=-4217/1270, 10-11=-4265/1258, 11-12=-4383/1417, 12-13=0/11, 6-7=-2617/938,
 7-8=-2910/1002, 1-2=0/14, 2-3=-757/2667, 3-4=-442/154, 4-5=-388/169, 5-6=-1536/586
 BOT CHORD 14-15=-988/3655, 12-14=-1201/3993, 15-16=-578/2633, 18-19=-2557/845, 17-18=0/384,
 16-17=-217/1399, 2-19=-2365/775
 WEBS 11-14=-26/232, 9-14=-3/525, 9-15=-748/361, 7-15=-148/400, 6-16=-445/1571, 6-17=-619/282,
 5-17=-346/1325, 5-18=-1381/527, 3-18=-794/2940, 3-19=-2530/891, 8-15=-169/945, 7-16=-532/304

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 628 lb uplift at joint 19, 901 lb uplift at joint 2 and 355 lb uplift at joint 12.

LOAD CASE(S) Standard

[Handwritten signature]


OCT 15 2008



Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	HS5	SPECIAL	1	1	
			Job Reference (optional)		
Maronda Homes Inc., Sanford, Florida			7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:35 2008 Page 1		

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:35 2008 Page 1

Scale = 1.797



6-4-3	6-8-6	15-0-0	21-1-8	30-10-8	38-4-4	46-0-0
6-4-3	0-4-3	8-3-10	6-1-8	9-9-0	7-5-12	7-7-12

Plate Offsets (X,Y): [3:0-3-0,Edge], [6:0-5-12,0-2-8], [9:0-3-0,0-2-4], [11:0-3-0,Edge], [13:0-1-11,0-3-0], [13:0-0-0,0-0-0], [17:0-5-4,0-3-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.81	Vert(LL)	-0.35 16-17	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.76	Vert(TL)	-0.72 16-17	>654	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.65	Horz(TL)	-0.30 19	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)					Weight: 269 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2
SLIDER Right 2 X 4 SYP No.2 4-0-13

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 4-9-3 oc bracing.
WEBS	1 Row at midpt 5-19

REACTIONS

(lb/size) 13=1561/0-8-6, 19=3296/0-8-6, 2=-831/0-8-0
Max Horz 13=112(LC 6)
Max Uplift 13=-345(LC 7), 19=-666(LC 5), 2=-929(LC 11)
Max Grav 13=1561(LC 1), 19=3296(LC 1), 2=49(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 9-10=-3594/1160, 10-11=-4335/1394, 11-12=-4362/1386, 12-13=-4430/1377, 13-14=0/11,
6-7=-2803/1009, 7-8=-2802/1009, 8-9=-3309/1137, 1-2=0/14, 2-3=-784/2564, 3-4=-760/2617,
4-5=-636/2529, 5-6=-1283/508

BOT CHORD 15-16=-1167/4071, 13-15=-1164/4050, 16-17=-842/3157, 18-19=-201/111, 17-18=-178/1179,
2-19=-2325/800


WEBS 10-15=0/227, 8-16=-85/230, 8-17=-492/213, 6-17=-602/1970, 6-18=-844/365, 5-18=-348/1509, 5-19=-3371/1034, 4-19=-407/315, 7-17=-270/252, 9-16=-163/1024, 10-16=-722/349

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDF=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearing at joint(s) 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 345 lb uplift at joint 13, 666 lb uplift at joint 19 and 929 lb uplift at joint 2.

LOAD CASE(S) Standard

OCT 15 2008



Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT HS6S SPECIAL 1 1


Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:36 2008 Page 1

7-0-0 13-1-8 20-0-12 33-4-4 40-0-0 41-0-0
7-0-0 6-1-8 6-11-4 13-3-8 6-7-12 1-0-0

Scale = 1/68.4



7-0-0 20-0-12 26-10-8 33-4-4 40-0-0
7-0-0 13-0-12 6-9-12 6-5-12 6-7-12

Plate Offsets (X,Y): [2:0-5-12,0-2-8], [4:0-4-0,0-3-0], [5:0-3-0,0-2-4], [8:0-0-0,0-0-0], [8:0-0-11,0-4-4], [11:0-5-4,0-3-12], [13:0-5-4,0-3-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL in (loc)	L/dell	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.72	Vert(LL) -0.46 11-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.82	Vert(TL) -0.91 11-12	>522	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.68	Horz(TL) -0.42 15	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)					
							Weight: 262 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2 *Except*
T4 2 X 4 SYP No.1D
BOT CHORD 2 X 6 SYP No.2 *Except*
F1 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
SLIDER Right 2 X 4 SYP No.2 3-2-6

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, **except** end verticals.
BOT CHORD Rigid ceiling directly applied or 6-1-12 oc bracing.
JOINTS 1 Brace at Jt(s): 14

REACTIONS

(lb/size) 8=1764/0-8-6, 15=1698/0-3-8
Max Horz 8=-174(LC 7)
Max Uplift 8=-352(LC 5), 15=-328(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 5-6=-4644/1622, 6-7=-5044/1691, 7-8=-5096/1680, 8-9=0/11, 2-3=-4312/1587, 3-4=-4312/1587,
4-5=-4311/1567, 1-2=-2478/875, 1-15=-1576/614
BOT CHORD 10-11=-1609/4680, 8-10=-1600/4653, 12-13=-1652/4884, 11-12=-1652/4883, 14-15=-69/137,
13-14=-736/2255
WEBS 6-10=0/167, 6-11=-340/245, 4-11=-811/246, 4-12=0/278, 4-13=-677/223, 2-13=-838/2415,
2-14=-546/351, 1-14=-685/2174, 3-13=-304/268, 5-11=-332/1419


NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; **enclosed**; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearing at joint(s) 8, 15 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 352 lb uplift at joint 8 and 328 lb uplift at joint 15.

LOAD CASE(S) Standard

[Signature]

OCT 15 2008



Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT HS7S SPECIAL 1 1


Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:37 2008 Page 1

5-0-0 11-1-8 20-0-12 29-0-0 34-4-4 40-0-0 41-0-0
5-0-0 6-1-8 8-11-4 8-11-4 5-4-4 5-7-12 1-0-0

Scale = 1/68.4




Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT HS8S SPECIAL 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:38 2008 Page 1

3-0-0 9-1-8 16-5-0 23-8-8 31-0-0 35-4-4 40-0-0 41-0-0
3-0-0 6-1-8 7-3-8 7-3-8 7-3-8 4-4-4 4-7-12 1-0-0
Scale = 1:68 1



3-0-0 9-1-8 16-5-0 23-8-8 30-10-8 40-0-0
3-0-0 6-1-8 7-3-8 7-3-8 7-2-0 9-1-8

Plate Offsets (X,Y): [2:0-7-4,0-2-12], [9:0-0-0,0-0-0], [11:0-4-0,0-4-4], [13:0-5-0,0-5-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.38	Vert(LL)	-0.60 13-14	>790	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.80	Vert(TL)	-1.19 13-14	>398	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.84	Horz(TL)	-0.45 17	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 276 lb	

LUMBER

TOP CHORD 2 X 6 SYP No.2 *Except*
T2 2 X 6 SYP No.1D, T2 2 X 6 SYP No.1D
BOT CHORD 2 X 6 SYP No.1D *Except*
B1 2 X 4 SYP No.2, F1 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 5-6-1 oc bracing.
JOINTS 1 Brace at Jt(s): 15, 16

REACTIONS

(lb/size) 9=1745/0-8-6, 17=1699/Mechanical
Max Horz 9=-140(LC 7)
Max Uplift 9=-372(LC 5), 17=-378(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 8-9=-5394/1884, 9-10=0/8, 2-3=-4787/1754, 3-4=-6560/2397, 4-5=-6954/2537, 5-6=-6954/2537,
6-7=-6952/2535, 7-8=-6265/2286, 1-2=-1542/560, 1-17=-1672/609
BOT CHORD 9-11=-1775/4974, 14-15=-1726/4839, 13-14=-2340/6560, 12-13=-2229/6265, 11-12=-1751/4935,
16-17=-6/28, 15-16=-489/1408
WEBS 3-15=-972/509, 2-15=-1315/3682, 2-16=-1073/510, 1-16=-620/1759, 4-14=-433/312, 3-14=-667/1873,
6-13=-267/252, 4-13=-150/432, 7-12=-559/273, 7-13=-278/814, 8-11=-213/1139, 8-12=-530/1644


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 372 lb uplift at joint 9 and 378 lb uplift at joint 17.

LOAD CASE(S) Standard


[Signature]

OCT 15 2008



Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	HSGRD1S	SPECIAL	1	3	Job Reference (optional)
Maronda Homes Inc., Sanford, Florida			7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:39 2008 Page 1		

1-0-0 5-6-0 10-0-0 11-1-6 16-7-0 22-0-11 27-6-5 33-0-0 36-2-7 40-0-0 41-0-0
1-0-0 4-6-0 4-6-0 1-1-6 5-5-11 5-5-11 5-5-11 5-5-11 3-2-7 3-9-9 1-0-0
Scale = 1:68.4



5-6-0 10-0-0 11-1-6 16-7-0 22-0-11 27-6-5 32-7-8 36-2-7 40-0-0
5-6-0 4-6-0 1-1-6 5-5-11 5-5-11 5-5-11 5-1-3 3-6-15 3-9-9

Plate Offsets (X,Y): [2:0-5-12,0-2-8], [11:0-3-0,0-2-4], [13:0-0-0,0-0-0], [18:0-5-0,0-4-8], [21:0-6-0,0-3-8]

LOADING (psf)	SPACING	1-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.52	Vert(LL)	0.67 18-19	>711	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.89	Vert(TL)	-1.31 18-19	>361	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.50	Horz(TL)	-0.36 24	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 732 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-9-5 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 13=2856/0-8-6, 24=2901/Mechanical
Max Horz 13=-64(LC 6)
Max Uplift 13=-1416(LC 6), 24=-1181(LC 5)
Max Grav 13=2856(LC 1), 24=2923(LC 9)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 11-12=-9708/4864, 12-13=-8367/4164, 13-14=0/3, 2-25=-4439/1851, 25-26=-4439/1851, 3-26=-4439/1851, 3-4=-7307/3141, 4-27=-7307/3141, 5-27=-7307/3141, 5-28=-11743/5108, 6-28=-11743/5108, 6-29=-11743/5108, 29-30=-11743/5108, 7-30=-11743/5108, 7-31=-14903/6806, 8-31=-14903/6806, 8-32=-14903/6806, 9-32=-14903/6806, 9-33=-14903/6806, 33-34=-14903/6806, 34-35=-14903/6806, 10-35=-14903/6806, 10-36=-9587/4804, 36-37=-9587/4804, 11-37=-9587/4804, 1-2=-1102/453, 1-24=-2820/1153
BOT CHORD 16-38=-3872/7642, 15-38=-3791/7534, 13-15=-3776/7503, 20-39=-6576/14760, 39-40=-6576/14760, 19-40=-6576/14760, 19-41=-6576/14760, 41-42=-6576/14760, 42-43=-6576/14760, 18-43=-6576/14760, 18-44=-6277/13314, 44-45=-6277/13314, 45-46=-6277/13314, 17-46=-6277/13314, 17-47=-6277/13314, 47-48=-6277/13314, 16-48=-6277/13314, 21-49=-3678/8640, 20-49=-3674/8702, 23-24=-49/120, 23-50=-350/867, 50-51=-350/867, 22-51=-350/867, 22-52=-1846/4438, 52-53=-1847/4440, 21-53=-1848/4441
WEBS 12-15=-183/105, 12-16=-814/1621, 10-16=-4017/1598, 10-17=0/415, 10-18=-572/1715, 9-18=-386/364, 7-18=-239/152, 7-19=-57/590, 7-20=-3213/1568, 6-20=-247/302, 5-20=-3597/8135, 5-21=-6757/2891, 3-21=-1552/3450, 3-22=-2249/918, 2-23=-2116/806, 1-23=-973/2432, 2-22=-1813/4322, 11-16=-1599/3423

NOTES

- 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2 X 6 - 2 rows at 0-8-0 oc.
Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

OCT 15 2008



Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	HSGRD1S	SPECIAL	1	3	Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:40 2008 Page 2

NOTES

- 4) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) Refer to girder(s) for truss to truss connections.
- 8) Bearing at joint(s) 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1416 lb uplift at joint 13 and 1181 lb uplift at joint 24.
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 119 lb down and 114 lb up at 33-0-0, 108 lb down and 122 lb up at 30-11-4, 108 lb down and 122 lb up at 28-11-4, 108 lb down and 122 lb up at 26-11-4, 108 lb down and 122 lb up at 24-11-4, 108 lb down and 122 lb up at 22-11-4, 108 lb down and 122 lb up at 20-11-4, 108 lb down and 122 lb up at 18-11-4, 108 lb down and 122 lb up at 16-11-4, 108 lb down and 122 lb up at 14-11-4, 108 lb down and 122 lb up at 12-11-4, 108 lb down and 122 lb up at 10-11-4, 86 lb down and 1 lb up at 8-11-4, 86 lb down and 1 lb up at 6-11-4, 86 lb down and 1 lb up at 4-11-4, and 86 lb down and 1 lb up at 2-11-4, and 118 lb down and 1 lb up at 1-0-0 on top chord, and 690 lb down and 518 lb up at 33-0-0, 98 lb down at 30-11-4, 98 lb down at 28-11-4, 98 lb down at 26-11-4, 98 lb down at 24-11-4, 98 lb down at 22-11-4, 98 lb down at 20-11-4, 98 lb down at 18-11-4, 98 lb down at 16-11-4, 98 lb down at 14-11-4, 98 lb down at 12-11-4, 98 lb down at 10-11-4, 105 lb down and 84 lb up at 8-11-4, 105 lb down and 84 lb up at 6-11-4, 105 lb down and 84 lb up at 4-11-4, and 105 lb down and 84 lb up at 2-11-4, and 105 lb down and 84 lb up at 0-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard


- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 11-14=-23, 2-11=-23, 1-2=-23, 13-16=-20, 16-20=-20, 20-21=-20, 21-24=-20

Concentrated Loads (lb)

Vert: 11=-119(B) 8=-108(B) 2=-86(B) 16=-90(B) 4=-86(B) 23=-105(B) 25=-86(B) 26=-86(B) 27=-86(B) 28=-108(B) 29=-108(B) 30=-108(B) 31=-108(B) 32=-108(B) 33=-108(B) 34=-108(B) 35=-108(B) 36=-108(B) 37=-108(B) 38=-599(B) 39=-98(B) 40=-98(B) 41=-98(B) 42=-98(B) 43=-98(B) 44=-98(B) 45=-98(B) 46=-98(B) 47=-98(B) 48=-98(B) 49=-98(B) 50=-105(B) 51=-105(B) 52=-105(B) 53=-105(B)



[Handwritten Signature]

OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001


DAVENPORT H1S HIP

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:10 2008 Page 1

5-5-8 11-0-0 17-0-0 23-0-0 28-5-8 33-11-1 40-0-0
5-5-8 5-6-8 6-0-0 6-0-0 5-5-9 5-5-9 6-0-15

Scale = 1/67.3



5-5-8 11-0-0 17-0-0 23-0-0 31-2-4 40-0-0
5-5-8 5-6-8 6-0-0 6-0-0 8-2-4 8-9-12

Plate Offsets (X,Y): [3:0-3:0,0-2:4], [5:0-3:0,0-2:4], [9:0-0:1,0-1:11]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.59	Vert(LL)	-0.26 10-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.91	Vert(TL)	-0.54 10-12	>889	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.56	Horz(TL)	-0.15 17	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 236 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
WEDGE
Right: 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-8-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 5-9-8 oc bracing.
WEBS 1 Row at midpt 4-12, 4-15

REACTIONS (lb/size) 9=1711/Mechanical, 17=1711/Mechanical
Max Horz 9=-184(LC 7)
Max Uplift 9=-306(LC 7), 17=-281(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 5-6=-2548/946, 6-7=-3318/1112, 7-8=-3371/1095, 8-9=-3545/1185, 3-4=-1897/782, 4-5=-2323/922,
1-2=-1799/620, 2-3=-2091/796, 1-17=-1604/584
BOT CHORD 16-17=-28/71, 15-16=-515/1617, 14-15=-718/2305, 13-14=-718/2305, 12-13=-718/2305,
11-12=-934/2788, 10-11=-934/2788, 9-10=-1137/3198
WEBS 8-10=-191/234, 6-10=-67/578, 6-12=-646/304, 5-12=-125/690, 4-12=-129/87, 4-13=0/217, 4-15=-725/235,
3-15=-67/521, 2-15=-72/431, 2-16=-593/330, 1-16=-550/1744

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 306 lb uplift at joint 9 and 281 lb uplift at joint 17.

LOAD CASE(S) Standard



OCT 15 2008

4-7-12 9-0-0 17-0-0 25-0-0 32-4-11 40-0-0
 4-7-12 4-4-4 8-0-0 8-0-0 7-4-11 7-7-5

Scale = 1:67.3




Plate Offsets (X,Y): [3:0-5-12,0-2-8], [5:0-5-4,0-2-4], [6:0-3-0,0-3-0], [7:0-0-1,0-1-11], [9:0-3-0,0-3-4], [11:0-3-0,0-3-4]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	I/dell	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.69	Vert(LL)	-0.26	9-10	>999	240	MT20
TCDL 7.0	Lumber Increase	1.25	BC 0.93	Vert(TL)	-0.54	9-10	>880	180	
BCLL 10.0	Rep Stress Incr	YES	WB 0.56	Horz(TL)	-0.16	12	n/a	n/a	
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						Weight: 218 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2
 WEDGE
 Right: 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-7-4 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
 WEBS 1 Row at midpt 6-9, 2-12

REACTIONS (lb/size) 7=1711/Mechanical, 12=1711/Mechanical
 Max Horz 7=-171(LC 7)
 Max Uplift 7=-290(LC 7), 12=-306(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 5-6=-2797/1008, 6-7=-3576/1172, 3-4=-2636/1039, 4-5=-2636/1039, 1-2=-187/52, 2-3=-2079/777, 1-12=-177/100
 BOT CHORD 11-12=-496/1421, 10-11=-586/1892, 9-10=-819/2534, 8-9=-1112/3222, 7-8=-1112/3222
 WEBS 6-8=0/334, 6-9=-773/323, 5-9=-37/622, 5-10=-72/290, 4-10=-392/356, 3-10=-360/1012, 3-11=-160/201, 2-11=-134/717, 2-12=-1873/721

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 290 lb uplift at joint 7 and 306 lb uplift at joint 12.

LOAD CASE(S) Standard



OCT 15 2008

8-0-0 14-0-0 20-0-0 26-0-0 32-10-11 40-0-0
 8-0-0 6-0-0 6-0-0 6-0-0 6-10-11 7-1-5

Scale = 1/67.3




Plate Offsets (X,Y): [1:0-3-0,0-1-8], [2:0-5-0,0-2-4], [3:0-4-0,0-3-0], [5:0-5-12,0-2-8], [7:0-0-1,0-1-11]									
LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase 1.25	TC 0.58	Vert(LL) -0.24	8-9	>999	240		MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.89	Vert(TL) -0.50	8-9	>962	180			
BCLL 10.0	Rep Stress Incr YES	WB 0.64	Horz(TL) -0.16	15	n/a	n/a			
BCDL 10.0	Code FBC2004/TPI2002	(Matrix)							Weight: 224 lb


LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 2-9-9 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 5-8-13 oc bracing.
WEBS 2 X 4 SYP No.2	WEBS 1 Row at midpt 3-14
WEDGE	
Right: 2 X 4 SYP No.3	


REACTIONS (lb/size) 7=1711/Mechanical, 15=1711/Mechanical
 Max Horz 7=-165(LC 7)
 Max Uplift 7=-285(LC 4), 15=-319(LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 5-6=-2878/1039, 6-7=-3603/1188, 2-3=-1864/755, 3-4=-2849/1105, 4-5=-2849/1105, 1-2=-2079/747, 1-15=-1545/618
 BOT CHORD 14-15=-63/161, 13-14=-860/2586, 12-13=-860/2586, 11-12=-860/2586, 10-11=-861/2611, 9-10=-861/2611, 8-9=-1132/3246, 7-8=-1132/3246
 WEBS 6-8=0/318, 6-9=-714/298, 5-9=-44/548, 5-11=-128/467, 4-11=-288/255, 3-11=-129/401, 3-12=0/223, 3-14=-1102/372, 2-14=0/524, 1-14=-571/1791

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 285 lb uplift at joint 7 and 319 lb uplift at joint 15.


LOAD CASE(S) Standard


 OCT 15 2008



6-0-0 13-4-9 20-7-7 28-0-0 33-10-11 40-0-0
 6-0-0 7-4-9 7-2-13 7-4-9 5-10-11 6-1-5

Scale = 1/67.3



6-0-0 13-4-9 20-7-7 28-0-0 33-10-11 40-0-0
 6-0-0 7-4-9 7-2-13 7-4-9 5-10-11 6-1-5

Plate Offsets (X,Y): [2:0-4-0,0-1-13], [6:0-5-12,0-2-8], [8:0-0-1,0-1-11], [13:0-3-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.43	Vert(LL)	-0.30 10-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.82	Vert(TL)	-0.61 10-12	>786	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.50	Horz(TL)	-0.18 15	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 216 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2
 WEDGE
 Right: 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-11-12 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-8-12 oc bracing.
 WEBS 1 Row at midpt 3-14

REACTIONS (lb/size) 8=1711/Mechanical, 15=1711/Mechanical
 Max Horz 8=-152(LC 7)
 Max Uplift 8=-303(LC 4), 15=-344(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 6-7=-3074/1107, 7-8=-3625/1212, 2-3=-1729/692, 3-4=-3325/1265, 4-5=-3325/1265, 5-6=-3325/1265, 1-2=-1908/692, 1-15=-1599/615
 BOT CHORD 14-15=-28/72, 13-14=-1023/2963, 12-13=-1023/2963, 11-12=-958/2806, 10-11=-958/2806, 9-10=-1160/3263, 8-9=-1160/3263
 WEBS 7-9=0/255, 7-10=-519/223, 6-10=-12/485, 6-12=-235/748, 5-12=-346/317, 3-12=-157/467, 3-13=0/292, 3-14=-1559/549, 2-14=0/456, 1-14=-606/1813

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 303 lb uplift at joint 8 and 344 lb uplift at joint 15.

LOAD CASE(S) Standard



OCT 15 2008

5-0-0 11-0-14 17-0-0 22-11-2 29-0-0 34-4-11 40-0-0
 5-0-0 6-0-14 5-11-2 5-11-2 6-0-14 5-4-11 5-7-5

Scale = 1:67.3




Plate Offsets (X,Y): [2:0-3-0,0-2-4], [4:0-3-0,0-3-0], [6:0-3-0,0-2-4], [8:0-0-1,0-1-11], [10:0-2-12,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.36	Vert(LL)	-0.31 11-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.78	Vert(TL)	-0.62 11-12	>773	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.78	Horz(TL)	-0.19 16	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 222 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2
 WEDGE
 Right: 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-9 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-8-12 oc bracing.
 WEBS 1 Row at midpt 3-15

REACTIONS (lb/size) 8=1711/Mechanical, 16=1711/Mechanical
 Max Horz 8=-146(LC 7)
 Max Uplift 8=-312(LC 4), 16=-356(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 6-7=-3162/1137, 7-8=-3636/1224, 2-3=-1600/638, 3-4=-3504/1324, 4-5=-3504/1324, 5-6=-2876/1094, 1-2=-1759/642, 1-16=-1616/615
 BOT CHORD 15-16=-20/52, 14-15=-1003/2871, 13-14=-1003/2871, 12-13=-1003/2871, 11-12=-1232/3515, 10-11=-1232/3515, 9-10=-1176/3271, 8-9=-1176/3271
 WEBS 7-9=0/229, 7-10=-438/200, 6-10=-199/928, 5-10=-904/296, 5-11=0/241, 5-12=-29/59, 4-12=-269/251, 3-12=-290/827, 3-14=0/240, 3-15=-1662/592, 2-15=-10/451, 1-15=-597/1755

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 312 lb uplift at joint 8 and 356 lb uplift at joint 16.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT B1 SPECIAL 1 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:03 2008 Page 1

6-8-0 13-4-0 20-0-0 26-8-0 33-4-0 40-0-0
6-8-0 6-8-0 6-8-0 6-8-0 6-8-0 6-8-0

Scale = 1/67.5




Plate Offsets (X,Y): [3:0-4-0,0-3-0], [5:0-4-0,0-3-0], [10:0-3-0,0-3-0], [12:0-3-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.70	Vert(LL)	-0.40 11-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.83	Vert(TL)	-0.80 11-12	>597	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.86	Horz(TL)	0.18 8	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 223 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-9-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 5-4-0 oc bracing.
WEBS 1 Row at midpt 3-13, 5-9

REACTIONS (lb/size) 14=1707/Mechanical, 8=1707/Mechanical
Max Uplift 14=-418(LC 4), 8=-418(LC 4)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-14=-1577/646, 1-2=-2415/872, 2-3=-2415/872, 3-4=-4336/1565, 4-5=-4336/1565, 5-6=-2415/872, 6-7=-2415/872, 7-8=-1577/646
BOT CHORD 13-14=-25/68, 12-13=-1393/3856, 11-12=-1393/3856, 10-11=-1393/3856, 9-10=-1393/3856, 8-9=-25/68
WEBS 1-13=-992/2749, 2-13=-307/297, 3-13=-1677/606, 3-12=0/266, 3-11=-201/559, 4-11=-306/288, 5-11=-201/559, 5-10=0/266, 5-9=-1677/606, 6-9=-307/297, 7-9=-992/2749

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Provide adequate drainage to prevent water ponding.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 418 lb uplift at joint 14 and 418 lb uplift at joint 8.

LOAD CASE(S) Standard



[Signature]

OCT 15 2008

8-0-0 16-0-0 24-0-0 32-0-0 40-0-0
 8-0-0 8-0-0 8-0-0 8-0-0 8-0-0

Scale = 1/67.5

Mark Top




Plate Offsets (X,Y): [5:0-3-0,Edge], [11:0-3-0,0-3-0], [13:0-4-0,0-3-4], [14:0-3-8,0-3-4]

LOADING (psf)	SPACING	1-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.83	Vert(LL)	0.75 12-13	>635	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.82	Vert(TL)	-1.10 12-13	>432	180		
BCLL 10.0	Rep Stress Incr	NO	WB 0.87	Horz(TL)	0.18 10	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 410 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.1D
 WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-7-14 oc purlins, **except** end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-2-0 oc bracing.
 WEBS 1 Row at midpt 8-10


REACTIONS (lb/size) 15=3030/Mechanical, 10=2848/Mechanical
 Max Uplift 15=-1833(LC 9), 10=-1697(LC 9)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-15=-2676/1670, 1-16=-6079/3645, 16-17=-6079/3645, 17-18=-6079/3645, 2-18=-6079/3645, 2-3=-6079/3645, 3-19=-6079/3645, 19-20=-6079/3645, 4-20=-6079/3645, 4-21=-9072/5440, 5-21=-9072/5440, 5-22=-9072/5440, 6-22=-9072/5440, 6-23=-9072/5440, 23-24=-9072/5440, 7-24=-9072/5440, 7-8=-9072/5440, 8-25=-228/137, 25-26=-228/137, 26-27=-228/137, 9-27=-228/137, 9-10=-250/195
 BOT CHORD 15-28=-137/229, 28-29=-137/229, 29-30=-137/229, 14-30=-137/229, 14-31=-5446/9081, 31-32=-5446/9081, 32-33=-5446/9081, 13-33=-5446/9081, 13-34=-5446/9081, 34-35=-5446/9081, 35-36=-5446/9081, 12-36=-5446/9081, 12-37=-3644/6078, 37-38=-3644/6078, 38-39=-3644/6078, 11-39=-3644/6078, 11-40=-3644/6078, 40-41=-3644/6078, 41-42=-3644/6078, 10-42=-3644/6078
 WEBS 1-14=-3778/6301, 2-14=-569/466, 4-14=-3225/1934, 4-13=-243/603, 4-12=-9/6, 6-12=-574/463, 8-12=-1930/3216, 8-11=-235/595, 8-10=-6301/3777

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 Bottom chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1833 lb uplift at joint 15 and 1697 lb uplift at joint 10.



OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	BGRD1	SPECIAL	1	2	Job Reference (optional)
Maronda Homes Inc., Sanford, Florida			7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:05 2008 Page 2		

NOTES

8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 98 lb down and 83 lb up at 0-1-12, 98 lb down and 83 lb up at 2-2-4, 98 lb down and 83 lb up at 4-2-4, 98 lb down and 83 lb up at 6-2-4, 98 lb down and 83 lb up at 8-2-4, 98 lb down and 83 lb up at 10-2-4, 98 lb down and 83 lb up at 12-2-4, 98 lb down and 83 lb up at 14-2-4, 98 lb down and 83 lb up at 16-2-4, 98 lb down and 83 lb up at 18-2-4, 98 lb down and 83 lb up at 20-2-4, 98 lb down and 83 lb up at 22-2-4, 98 lb down and 83 lb up at 24-2-4, 98 lb down and 83 lb up at 26-2-4, 98 lb down and 83 lb up at 28-2-4, 98 lb down and 83 lb up at 30-2-4, 98 lb down and 83 lb up at 32-2-4, 98 lb down and 83 lb up at 34-2-4, and 98 lb down and 83 lb up at 36-2-4, and 98 lb down and 83 lb up at 38-2-4 on top chord, and 110 lb down and 72 lb up at 0-1-12, 110 lb down and 72 lb up at 2-2-4, 110 lb down and 72 lb up at 4-2-4, 110 lb down and 72 lb up at 6-2-4, 110 lb down and 72 lb up at 8-2-4, 110 lb down and 72 lb up at 10-2-4, 110 lb down and 72 lb up at 12-2-4, 110 lb down and 72 lb up at 14-2-4, 110 lb down and 72 lb up at 16-2-4, 110 lb down and 72 lb up at 18-2-4, 110 lb down and 72 lb up at 20-2-4, 110 lb down and 72 lb up at 22-2-4, 110 lb down and 72 lb up at 24-2-4, 110 lb down and 72 lb up at 26-2-4, 110 lb down and 72 lb up at 28-2-4, 110 lb down and 72 lb up at 30-2-4, 110 lb down and 72 lb up at 32-2-4, 110 lb down and 72 lb up at 34-2-4, and 110 lb down and 72 lb up at 36-2-4, and 110 lb down and 72 lb up at 38-2-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard


1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-9=-23, 10-15=-20

Concentrated Loads (lb)

Vert: 15=-110(F) 1=-98(F) 3=-98(F) 14=-110(F) 2=-98(F) 4=-98(F) 13=-110(F) 6=-98(F) 12=-110(F) 11=-110(F) 8=-98(F) 5=-98(F) 7=-98(F) 16=-98(F) 17=-98(F) 18=-98(F) 19=-98(F) 20=-98(F) 21=-98(F) 22=-98(F) 23=-98(F) 24=-98(F) 25=-98(F) 26=-98(F) 27=-98(F) 28=-110(F) 29=-110(F) 30=-110(F) 31=-110(F) 32=-110(F) 33=-110(F) 34=-110(F) 35=-110(F) 36=-110(F) 37=-110(F) 38=-110(F) 39=-110(F) 40=-110(F) 41=-110(F) 42=-110(F)



[Signature]

OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	GRD1	COMMON	2	3	

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:08 2008 Page 2

LOAD CASE(S) Standard


1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-23, 4-7=-23, 1-7=-20

Concentrated Loads (lb)

Vert: 10=-1826(F) 8=-1943(F) 11=-4002(F) 13=-1910(F) 14=-1932(F) 15=-1945(F) 16=-1976(F)



A handwritten signature in black ink, appearing to be "TP" or "T. Ponce", written over a horizontal line.

OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT T1 COMMON

6 1

Job Reference (optional)

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:53 2008 Page 1

Maronda Homes Inc., Sanford, Florida

-1-0-0 4-9-5 9-4-0 13-10-11 18-8-0 19-8-0
1-0-0 4-9-5 4-6-11 4-6-11 4-9-5 1-0-0
Scale = 1.332




Plate Offsets (X,Y): [2:0-0-1,0-0-15], [6:0-0-1,0-0-15], [8:0-4-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.27	Vert(LL)	-0.13	6-8	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.62	Vert(TL)	-0.30	6-8	>713	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.11	Horz(TL)	0.03	6	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 82 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-1-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 2=838/0-8-6, 6=838/0-8-6
Max Horz 2=73(LC 6)
Max Uplift 2=-230(LC 6), 6=-230(LC 7)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/10, 2-3=-1276/426, 3-4=-1056/313, 4-5=-1056/313, 5-6=-1276/426, 6-7=0/10
BOT CHORD 2-8=-293/1131, 6-8=-293/1131
WEBS 3-8=-246/193, 4-8=-37/573, 5-8=-246/193

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 230 lb uplift at joint 2 and 230 lb uplift at joint 6.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT G1 GABLE 1 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:06 2008 Page 1

-1-0-0 9-4-0 18-8-0
1-0-0 9-4-0 9-4-0

Scale: 3/8"=1'




Plate Offsets (X,Y): [14:0-3-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.10	Vert(LL)	0.00	1	n/r	120	MT20
TCDL 7.0	Lumber Increase	1.25	BC 0.09	Vert(TL)	0.01	1	n/r	120	244/190
BCLL 10.0	Rep Stress Incr	NO	WB 0.03	Horz(TL)	0.00	10	n/a	n/a	
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						Weight: 85 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 10=121/18-8-0, 2=179/18-8-0, 14=160/18-8-0, 15=183/18-8-0, 16=132/18-8-0, 17=277/18-8-0, 13=185/18-8-0, 12=125/18-8-0, 11=293/18-8-0
Max Horz 2=93(LC 6)
Max Uplift 10=32(LC 7), 2=115(LC 6), 15=102(LC 6), 16=82(LC 6), 17=151(LC 6), 13=104(LC 7), 12=71(LC 7), 11=176(LC 7)
Max Grav 10=121(LC 1), 2=179(LC 1), 14=160(LC 1), 15=187(LC 10), 16=132(LC 1), 17=277(LC 10), 13=188(LC 11), 12=125(LC 11), 11=293(LC 11)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/10, 2-3=-76/34, 3-4=-32/89, 4-5=-24/122, 5-6=-26/179, 6-7=-26/180, 7-8=-24/120, 8-9=-33/70, 9-10=-46/33
BOT CHORD 2-17=0/83, 16-17=0/83, 15-16=0/83, 14-15=0/83, 13-14=0/83, 12-13=0/83, 11-12=0/83, 10-11=0/83
WEBS 6-14=-83/0, 5-15=-101/137, 4-16=-72/119, 3-17=-145/197, 7-13=-101/139, 8-12=-69/112, 9-11=-153/213

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 32 lb uplift at joint 10, 115 lb uplift at joint 2, 102 lb uplift at joint 15, 82 lb uplift at joint 16, 151 lb uplift at joint 17, 104 lb uplift at joint 13, 71 lb uplift at joint 12 and 176 lb uplift at joint 11.

LOAD CASE(S) Standard



OCT 15 2008

-1-0-0 4-7-5 9-0-0 9-8-0 14-0-11 18-8-0 19-8-0
 1-0-0 4-7-5 4-4-11 0-8-0 4-4-11 4-7-5 1-0-0
 Scale = 1:33.7




Plate Offsets (X,Y): [2:0-0-1,0-0-15], [4:0-2-0,0-2-11], [6:0-2-0,0-2-11], [8:0-0-1,0-0-15], [10:0-4-0,0-3-0]										
LOADING (psf)		SPACING 2-0-0		CSI	DEFL in (loc)		l/defl	L/d	PLATES	GRIP
TCLL	16.0	Plates Increase	1.25	TC 0.27	Vert(LL)	-0.13 8-10	>999	240	MT20	24#/190
TCDL	7.0	Lumber Increase	1.25	BC 0.62	Vert(TL)	-0.30 8-10	>720	180		
BCLL	10.0	Rep Stress Incr	YES	WB 0.18	Horz(TL)	0.03 8	n/a	n/a		
BCDL	10.0	Code FBC2004/TPI2002		(Matrix)					Weight: 82 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 5-2-0 oc purlins.
BOT CHORD 2 X 4 SYP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2 X 4 SYP No.3	
REACTIONS (lb/size)	
2=838/0-8-6, 8=838/0-8-6	
Max Horz 2=71(LC 6)	
Max Uplift 2=-227(LC 6), 8=-227(LC 7)	
FORCES (lb) - Maximum Compression/Maximum Tension	
TOP CHORD 1-2=0/10, 2-3=-1278/432, 3-4=-1059/317, 4-5=-937/332, 5-6=-937/332, 6-7=-1059/317, 7-8=-1278/432, 8-9=0/10	
BOT CHORD 2-10=-299/1133, 8-10=-299/1133	
WEBS 3-10=-244/191, 7-10=-244/191, 5-10=-26/558	


NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Provide adequate drainage to prevent water ponding.
 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 227 lb uplift at joint 2 and 227 lb uplift at joint 8.

LOAD CASE(S) Standard



TOMAS PONCE
 LICENSE
 No. 50068
 STATE OF
 FLORIDA
 PROFESSIONAL ENGINEER


OCT 15 2008




REACTIONS (lb/size) 2=1807/0-8-6, 7=1807/0-8-6
Max Horz 2=61(LC 7)
Max Uplift2=-855(LC 7), 7=-855(LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/14, 2-3=-3481/1661, 3-4=-3522/1704, 4-12=-3288/1623, 12-13=-3288/1623, 5-13=-3288/1623,
5-6=-3519/1702, 6-7=-3480/1660, 7-8=0/14
BOT CHORD 2-11=-1478/3082, 10-11=-1541/3291, 10-14=-1541/3291, 14-15=-1541/3291, 9-15=-1541/3291,
7-9=-1417/3081
WEBS 3-11=-115/296, 4-11=-389/931, 4-9=-73/67, 5-9=-388/929, 6-9=-114/294

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 855 lb uplift at joint 2 and 855 lb uplift at joint 7.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 98 lb down and 83 lb up at 7-0-0, 98 lb down and 83 lb up at 9-0-12, and 98 lb down and 83 lb up at 9-7-4, and 98 lb down and 83 lb up at 11-8-0 on top chord, and 663 lb down and 404 lb up at 7-0-0, 110 lb down and 72 lb up at 9-0-12, and 110 lb down and 72 lb up at 9-7-4, and 663 lb down and 404 lb up at 11-7-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-46, 4-5=-46, 5-8=-46, 2-7=-40



OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT HGRD1 HIP


Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:28 2008 Page 2

LOAD CASE(S) Standard

Concentrated Loads (lb)

Vert: 4=-98(B) 5=-98(B) 11=-663(B) 9=-663(B) 12=-98(B) 13=-98(B) 14=-110(B) 15=-110(B)




A handwritten signature in black ink, appearing to be "T. Ponce", written over the seal.

OCT 15 2008

3-9-12 7-0-0 10-2-4 14-0-0
 3-9-12 3-2-4 3-2-4 3-9-12

Scale = 1:22.5



Job	Truss	Truss Type
DAVENPORT	GRD2	COMMON

Qty	Ply	DAVENPORT_125_9TM04001
1	2	

Job Reference (optional)

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:08 2008 Page 2

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-3=-46, 3-5=-46, 1-5=-40

Concentrated Loads (lb)

Vert: 7=-3714(F)



A handwritten signature in black ink, appearing to be "T. Ponce", written over a horizontal line.

OCT 15 2008

Job Truss Truss Type
DAVENPORT T2 COMMON

Qty Ply DAVENPORT_125_9TM04001

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:54 2008 Page 1

7-0-0 14-0-0 15-0-0
7-0-0 7-0-0 1-0-0
Scale: 1/2"=1'




Plate Offsets (X,Y): [1:0-0-1,0-1-3], [3:0-0-1,0-1-3]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.31	Vert(LL)	-0.08	1-5	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.53	Vert(TL)	-0.15	1-5	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.06	Horz(TL)	0.02	3	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 50 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 1=570/0-8-6, 3=641/0-8-6
Max Horz 1=-63(LC 7)
Max Uplift 1=-109(LC 6), 3=-193(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-862/266, 2-3=-877/269, 3-4=0/10
BOT CHORD 1-5=-137/746, 3-5=-137/746
WEBS 2-5=0/332

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 109 lb uplift at joint 1 and 193 lb uplift at joint 3.

LOAD CASE(S) Standard



[Signature]

OCT 15 2008

Job Truss Truss Type
DAVENPORT G2 GABLE

Qty Ply DAVENPORT_125_9TM04001

1 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:07 2008 Page 1

7-0-0

14-0-0


15-0-0

7-0-0

7-0-0

1-0-0

Scale 1/2"=1'



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.10	Vert(LL)	0.00	8	n/r	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.07	Vert(TL)	0.00	8	n/r		
BCLL 10.0	Rep Stress Incr	NO	WB 0.03	Horz(TL)	0.00	7	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						
									Weight: 59 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=109/14-0-0, 7=169/14-0-0, 11=180/14-0-0, 12=137/14-0-0, 13=266/14-0-0, 10=143/14-0-0, 9=249/14-0-0

Max Horz 1=-76(LC 7)

Max Uplift 1=-39(LC 7), 7=-138(LC 7), 12=-78(LC 6), 13=-161(LC 6), 10=-88(LC 7), 9=-131(LC 7)

Max Grav 1=109(LC 1), 7=169(LC 1), 11=180(LC 1), 12=141(LC 10), 13=266(LC 1), 10=147(LC 11), 9=249(LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-48/42, 2-3=-32/98, 3-4=-26/151, 4-5=-26/152, 5-6=-31/96, 6-7=-37/26, 7-8=0/10

BOT CHORD 1-13=0/75, 12-13=0/75, 11-12=0/75, 10-11=0/75, 9-10=0/75, 7-9=0/75

WEBS 4-11=-92/23, 3-12=-79/122, 2-13=-138/210, 5-10=-82/129, 6-9=-131/193

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 2-0-0 oc.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 39 lb uplift at joint 1, 138 lb uplift at joint 7, 78 lb uplift at joint 12, 161 lb uplift at joint 13, 88 lb uplift at joint 10 and 131 lb uplift at joint 9.


LOAD CASE(S) Standard



[Signature]

OCT 15 2008

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:44 2008 Page 1



Continued on page 2

Job	Truss	Truss Type
DAVENPORT	JGRD1	MONO TRUSS

Qty Ply DAVENPORT_125_9TM04001

2 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:44 2008 Page 2

LOAD CASE(S) Standard

Concentrated Loads (lb)

Vert: 9=6(F=3, B=3) 10=-101(F=-50, B=-50) 12=43(F=22, B=22) 13=-24(F=-12, B=-12) 14=-104(F=-52, B=-52)



A handwritten signature in black ink, appearing to be "T. Ponce", written over the seal area.

OCT 15 2008




Plate Offsets (X,Y): [2:0-2-0,0-7-6], [6:0-2-0,0-1-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.32	Vert(LL)	-0.04	6-7	>999	240	MT20
TCDL 7.0	Lumber Increase	1.25	BC 0.39	Vert(TL)	-0.08	6-7	>999	180	244/190
BCLL 10.0	Rep Stress Incr	NO	WB 0.24	Horz(TL)	0.02	8	n/a	n/a	
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)						Weight: 50 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2 *Except*
 W4 2 X 6 SYP No.2
 SLIDER Left 2 X 4 SYP No.2 2-7-11

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-6-7 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 7-5-5 oc bracing.

REACTIONS (lb/size) 2=550/0-11-14, 8=562/Mechanical
 Max Horz 2=133(LC 3)
 Max Uplift 2=273(LC 7), 8=334(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/6, 2-9=-1307/640, 3-9=-1272/657, 3-10=-1272/658, 4-10=-1241/632, 4-11=-348/215,
 5-11=-288/149, 5-6=-169/462
 BOT CHORD 2-12=-703/1201, 12-13=-697/1208, 7-13=-697/1222, 7-14=-706/1203, 6-14=-701/1227
 WEBS 4-7=0/254, 4-6=-913/501, 5-8=-596/368, 6-8=-172/203

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 273 lb uplift at joint 2 and 334 lb uplift at joint 8.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 11 lb down and 65 lb up at 4-4-12, 11 lb down and 65 lb up at 4-4-12, 61 lb down and 132 lb up at 7-2-11, 61 lb down and 132 lb up at 7-2-11, and 43 lb down at 1-6-13, and 43 lb down at 1-6-13 on top chord, and 21 lb up at 1-6-13, 21 lb up at 1-6-13, 18 lb down at 4-4-12, 18 lb down at 4-4-12, and 58 lb down at 7-2-11, and 58 lb down at 7-2-11 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard



OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	JSGRD1	SPECIAL	1	1	

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:48 2008 Page 2

LOAD CASE(S) Standard


1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-5=-46, 2-6=-40

Concentrated Loads (lb)

Vert: 10=-22(F=-11, B=-11) 11=-121(F=-61, B=-61) 12=41(F=21, B=21) 13=-36(F=-18, B=-18) 14=-116(F=-58, B=-58)



A handwritten signature in black ink, appearing to be "T. Ponce", written over a horizontal line.

OCT 15 2008

Job	Truss	Truss Type	Qty	Ply	DAVENPORT_125_9TM04001
DAVENPORT	J	MONO TRUSS	29	1	Job Reference (optional)
Maronda Homes Inc., Sanford, Florida			7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:40 2008 Page 1		




Plate Offsets (X,Y): [2:0-0-0,0-0-15], [2:0-0-14,0-6-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.39	Vert(LL)	-0.12	2-6	>639	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.44	Vert(TL)	-0.26	2-6	>309	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.02	Horz(TL)	0.01	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 28 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 WEBS 2 X 4 SYP No.2
 WEDGE
 Left: 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS (lb/size) 4=132/Mechanical, 2=355/0-8-6, 5=145/Mechanical
 Max Horz 2=143(LC 6)
 Max Uplift 4=19(LC 6), 2=127(LC 6), 5=72(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/10, 2-3=-106/26, 3-4=-17/48
 BOT CHORD 2-6=0/0, 5-6=0/0
 WEBS 3-6=-17/165

NOTES (5)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 4, 127 lb uplift at joint 2 and 72 lb uplift at joint 5.
- 5) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 4 and 5.

LOAD CASE(S) Standard



OCT 15 2008

-1-0-0 7-0-0
 1-0-0 7-0-0 Toe-Nail (See note below) 4
 Scale = 1:16.5




Plate Offsets (X,Y): [2-0-1-13,0-5-2]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.47	Vert(LL)	-0.12	2-5	>690	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.45	Vert(TL)	-0.30	2-5	>276	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.02	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 29 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2
 SLIDER Left 2 X 4 SYP No.2 3-9-9

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=154/Mechanical, 2=351/0-8-6, 5=138/Mechanical
 Max Horz 2=141(LC 6)
 Max Uplift 4=-140(LC 6), 2=-109(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/6, 2-3=-88/0, 3-4=-78/47
 BOT CHORD 2-5=-18/18

NOTES (6)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 4 and 109 lb uplift at joint 2.
- 6) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 4 and 5.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT JSA SPECIAL 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:48 2008 Page 1

-1-0-0

7-0-0

1-0-0

7-0-0

Scale = 1/18.0




Plate Offsets (X,Y): [2:0-2-1,0-5-2], [4:Edge,0-3-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.42	Vert(LL)	-0.10	2-5	>816	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.40	Vert(TL)	-0.24	2-5	>326	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.01	Horz(TL)	0.00	5	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 34 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
SLIDER Left 2 X 4 SYP No.2 3-5-13

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 2=335/0-8-6, 5=276/Mechanical
Max Horz 2=134(LC 6)
Max Uplift 2=107(LC 6), 5=93(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/6, 2-3=-85/0, 3-4=-74/44
BOT CHORD 2-5=-17/17
WEBS 4-5=-146/165

NOTES


- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 107 lb uplift at joint 2 and 93 lb uplift at joint 5.

LOAD CASE(S) Standard



[Signature]

OCT 15 2008



Job Truss Truss Type
DAVENPORT JS1 SPECIAL

Qty Ply DAVENPORT_125_9TM04001

2 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:46 2008 Page 1

-1-0-0

5-0-0

Toe-Nail (See note below)

1-0-0

5-0-0

Scale = 1:12.3




Plate Offsets (X,Y): [2:0-1-13,0-5-2]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.22	Vert(LL)	-0.03	2-5	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.23	Vert(TL)	-0.08	2-5	>772	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.01	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 21 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
SLIDER Left 2 X 4 SYP No.2 2-8-9

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=107/Mechanical, 2=267/0-8-6, 5=98/Mechanical

Max Horz 2=106(LC 6)
Max Uplift 4=-98(LC 6), 2=-98(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/6, 2-3=-64/0, 3-4=-55/32
BOT CHORD 2-5=-13/13

NOTES (6)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 98 lb uplift at joint 4 and 98 lb uplift at joint 2.
- 6) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 4 and 5.

LOAD CASE(S) Standard



OCT 15 2008

1-9-3

3-0-0

5.00

2

T1

HW1

15

14

612

B1

Toe-Nail (See note below)

3-0-0

3-0-0

0-8-6(0-1-8)

3x4


3x6

Scale = 1" = 9'-0"

LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc)	L/defl L/d	PLATES	GRIP
TCLL 16.0	Plates Increase 1.25	TC 0.14	Vert(LL) -0.00 2-4	>999 240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.06	Vert(TL) -0.01 2-4	>999 180		
BCLL 10.0	Rep Stress Incr YES	WB 0.00	Horz(TL) -0.00 3	n/a n/a		
BCDL 10.0	Code FBC2004/TPI2002	(Matrix)			Weight: 12 lb	

TOP CHORD	Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT JS2 SPECIAL 2 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:47 2008 Page 1

-1-0-0 3-0-0
1-0-0 Toe-Nail (See note below)

Scale = 1/8" = 1'-0"




Plate Offsets (X,Y): [2-0-1-13,0-5-2]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/dell	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.08	Vert(LL)	-0.00	2-5	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.08	Vert(TL)	-0.01	2-5	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 14 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
SLIDER Left 2 X 4 SYP No.2 1-7-9

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=57/Mechanical, 2=185/0-8-6, 5=58/Mechanical
Max Horz 2=72(LC 6)
Max Uplift 4=53(LC 6), 2=88(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/6, 2-3=-42/0, 3-4=-28/16
BOT CHORD 2-5=-8/8

NOTES (6)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 53 lb uplift at joint 4 and 88 lb uplift at joint 2.
- 6) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 4 and 5.

LOAD CASE(S) Standard



OCT 15 2008

OCT 15 2209

DAVENPORT JS3 SPECIAL


Maronda Homes Inc., Sanford, Florida

Qty	Ply	DAVENPORT_125_9TM04001
-----	-----	------------------------

2 1

Job Reference (optional)

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:47 2008 Page 1



LOADING (psf)		SPACING 2-0-0		CSI		0-8-6(0-1-8)						
TCLL	16.0	Plates Increase	1.25	TC	0.05	DEFL	in	(loc)	I/d _{eff}	L/d	PLATES	GRIP
TCDL	7.0	Lumber Increase	1.25	BC	0.01	Vert(LL)	-0.00	2	>999	240	MT20	244/190
BCLL	10.0	Rep Stress Incr	YES	WB	0.00	Vert(TL)	-0.00	2	>999	180		
BCDL	10.0	Code FBC2004/TPI2002		(Matrix)		Horz(TL)	-0.00	3	n/a	n/a		
											Weight: 7 lb	

LUMBER

TOP CHORD 2 X 6 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 4=19/Mechanical, 2=84/0-8-6, 3=11/Mechanical
Max Horz 2=29(LC 6)
Max Uplift 2=-54(LC 6), 3=-14(LC 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	$1-2=0/2$, $2-3=-18/4$
BOT CHORD	$2-4=-3/3$

NOTES (7)

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCFL=4.2psf; BCDL=6.0psf; Category II; Exp B; **enclosed**; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 2 and 14 lb uplift at joint 3.
- 6) SEE MiTek STANDARD PIGGYBACK TRUSS CONNECTION DETAIL FOR CONNECTION TO BASE TRUSS
- 7) Attach with (2) 16d Common Toe-Nails (0.162"x3.5") at joints 3 and 4.

LOAD CASE(S) Standard



OCT 15 2008

Enclosed;
Signed for C-C
ds.
at joint 3 and 11

OCT 15 2008


TOMAS PONCE
LICENSE
No. 50068
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V2S VALLEY 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:57 2008 Page 1



Scale = 1/8" = 1'-0"

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.13	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.12	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	0.00	2	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 14 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-5-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=152/4-5-0, 2=152/4-5-0
Max Horz 3=-61(LC 7)
Max Uplift 3=-50(LC 7), 2=-25(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-3=-81/92, 1-2=-46/25
BOT CHORD 2-3=-0/76

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 3 and 25 lb uplift at joint 2.

LOAD CASE(S) Standard

OCT 15 2008



Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001


DAVENPORT V3S GABLE 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:57 2008 Page 1

0-2-8 6-5-0
0-2-8 6-2-8

Scale = 1:15.4



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/dell	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.10	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.08	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr	YES	WB 0.03	Horz(TL)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 23 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 5=48/6-5-0, 3=118/6-5-0, 4=310/6-5-0
Max Horz 5=-96(LC 7)
Max Uplift 5=-16(LC 7), 4=-102(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-5=-26/29, 1-2=-28/6, 2-3=-99/36
BOT CHORD 4-5=-0/117, 3-4=-0/117
WEBS 2-4=-166/184


NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 16 lb uplift at joint 5 and 102 lb uplift at joint 4.

LOAD CASE(S) Standard

[Signature]

OCT 15 2008




Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V4S GABLE 1 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:58 2008 Page 1



LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/deff	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase	1.25	TC 0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.07	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr	YES	WB 0.02	Horz(TL)	0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 33 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6'-0'-0" oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10'-0'-0" oc bracing.

REACTIONS (lb/size) 7=80/8-2-8, 4=113/8-2-8, 6=166/8-2-8, 5=273/8-2-8
Max Horz 7=-127(LC 7)
Max Uplift 7=-26(LC 7), 6=-54(LC 7), 5=-90(LC 7)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-7=-43/46, 1-2=-25/13, 2-3=-68/12, 3-4=-139/33
BOT CHORD 6-7=-0/152, 5-6=-0/152, 4-5=-0/152
WEBS 2-6=-89/96, 3-5=-146/159

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 7, 54 lb uplift at joint 6 and 90 lb uplift at joint 5.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V6 VALLEY

2 1

Job Reference (optional)

Maronda Homes Inc., Sanford, Florida

7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:59 2008 Page 1




Plate Offsets (X,Y): [2:Edge,0-1-14]

2-0-0(0-1-8)

2-0-0(0-1-8)

LOADING (psf)
TCLL 16.0
TCDL 7.0
BCLL 10.0
BCDL 10.0

SPACING 2-0-0
Plates Increase 1.25
Lumber Increase 1.25
Rep Stress Incr YES
Code FBC2004/TPI2002

CSI
TC 0.01
BC 0.01
WB 0.00
(Matrix)

DEFL in (loc) l/defl L/d
Vert(LL) n/a - n/a 999
Vert(TL) n/a - n/a 999
Horz(TL) 0.00 n/a n/a

PLATES GRIP
MT20 244/190

Weight: 5 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 1=48/2-0-0, 3=48/2-0-0
Max Horz 1=19(LC 6)
Max Uplift 1=8(LC 6), 3=16(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-15/8, 2-3=-26/29
BOT CHORD 1-3=0/0

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 8 lb uplift at joint 1 and 16 lb uplift at joint 3.

LOAD CASE(S) Standard



OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V7 VALLEY 2 1

Maronda Homes Inc., Sanford, Florida

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:33:59 2008 Page 1


4-0-0

2x4

4-0-0

2

Scale = 1/8" = 1'-0"



LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase 1.25	TC 0.10	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.09	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr YES	WB 0.00	Horz(TL)	0.00		n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002	(Matrix)							
								Weight: 13 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=134/4-0-0, 3=134/4-0-0
Max Horz 1=54(LC 6)
Max Uplift 1=22(LC 6), 3=44(LC 6)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-40/22, 2-3=-72/81
BOT CHORD 1-3=0/0

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 1 and 44 lb uplift at joint 3.

LOAD CASE(S) Standard




OCT 15 2008

Job Truss Truss Type Qty Ply DAVENPORT_125_9TM04001

DAVENPORT V8 VALLEY 2 1

Job Reference (optional)
7.030 s Mar 11 2008 MiTek Industries, Inc. Fri Oct 10 14:34:00 2008 Page 1

Maronda Homes Inc., Sanford, Florida



LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	I/dell	L/d	PLATES	GRIP
TCLL 16.0	Plates Increase 1.25	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.06	Vert(TL)	n/a	-	n/a	999		
BCLL 10.0	Rep Stress Incr YES	WB 0.02	Horz(TL)	0.00		n/a	n/a		
BCDL 10.0	Code FBC2004/TPI2002	(Matrix)							
								Weight: 21 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.2
OTHERS 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-10-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=63/5-10-0, 4=94/5-10-0, 5=269/5-10-0
Max Horz 1=86(LC 6)
Max Uplift 4=-31(LC 6), 5=-88(LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=-99/26, 2-3=-31/15, 3-4=-51/57
BOT CHORD 1-5=0/0, 4-5=0/0
WEBS 2-5=-144/161

NOTES

- 1) Wind: ASCE 7-02; 125mph (3-second gust); h=25ft; TCDL=4.2psf; BCDL=6.0psf; Category II; Exp B; enclosed; MWFRS (low-rise) and C-C Interior(1) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Gable requires continuous bottom chord bearing.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 4 and 88 lb uplift at joint 5.

LOAD CASE(S) Standard

OCT 15 2008





14/1

11200 St. Johns Industrial Parkway North Suite 2, Jacksonville, Florida 32246

(904)646-1186 PHONE, (904)646-9553 FAX

Memorandum

Date: May 11, 2004

To:

From: Maronda Homes, Inc. of Florida
Permitting Department

Re: BORA-CARE

Effective with the permit packets from this point forward we will no longer be using pre-treated wood framing and trusses for our homes. We will be treating the wood once it is received on the job site with BORA-CARE Termiticide, Insecticide and Fungicide Concentrate. We ask that you please pass this information through the channels necessary to insure that everyone will know about this upcoming change including the inspectors. If you should have any questions at all in regards to this or if there is a different process to distribute this information, please feel free to contact me at any time.

Thank you,

Maronda Homes, Inc.
P: 904-646-1186
F: 904-646-4244

BORA-CARE®

Termiticide, Insecticide, and Fungicide Concentrate

A PRODUCT OF NISUS CORPORATION

For the Prevention and Control of:

TERMITES, CARPENTER ANTS, WOOD DESTROYING BEETLES, and DECAY FUNGI

FOR BOTH INTERIOR AND EXTERIOR USE

For use in and around Homes, Apartments, Garages, Museums, Public and Private Institutions, Schools, Hotels, Hospitals, Kennels, Stables, Farm Buildings, Trucks, Trailers, Warehouses, Supermarkets, Restaurants, and Food Processing Plants.

Authorized by the USDA for use on Non-Food Contact Surfaces in Edible Product Areas of Official Establishments Operating under the Meat, Poultry, Shell Egg Grading and Egg Products Inspection Programs.

ACTIVE INGREDIENT:

.Disodium Octaborate Tetrahydrate ($\text{Na}_2\text{B}_8\text{O}_{13} \cdot 4\text{H}_2\text{O}$):..... 40.0%

INERT INGREDIENTS:..... 60.0%

Density: 11.51 pounds per gallon

EPA Reg. No. 64405-1

EPA Est. 64405-TN-1

U.S. Patent Nos. 5,104,664 5,296,240 5,460,816 5,645,828

KEEP OUT OF REACH OF CHILDREN
CAUTION

PRECAUTIONARY STATEMENTS

Hazards To Humans & Domestic Animals

CAUTION: Harmful if absorbed through skin. Avoid contact with skin, eyes or clothing. Wash thoroughly with soap and water after handling.

Statement of Practical Treatment

If Inhaled: Remove victim to fresh air. Apply artificial respiration if indicated. Contact a physician if warranted. **If In Eyes:** Flush with plenty of water. Get medical attention if irritation persists.

If On Skin: Wash with plenty of soap and water. Get medical attention.

IN CASE OF A MEDICAL EMERGENCY involving this product call (800) 424-9300 or your local Poison Control Center.

Environmental Hazards

BORA-CARE® solutions carelessly spilled or applied to cropland or growing plants including trees and shrubs may kill or seriously retard plant growth. Cover plants and nearby soil with plastic to avoid contamination. Do not apply directly to water. Do not contaminate water when disposing of equipment washwaters.

DIRECTIONS FOR USE

It is a violation of Federal law to use this product in a manner inconsistent with its labeling.

NOTICE

Read and understand the entire label before using. Use only according to label directions.

Before buying or using this product, read "WARRANTY LIMITATIONS AND DISCLAIMER" statement found elsewhere on this label. If terms are unacceptable, return unopened package to seller for full refund of purchase price. Otherwise, use by the buyer or any other user constitutes acceptance of the terms under WARRANTY LIMITATIONS AND DISCLAIMER.

BORA-CARE® should be applied only to bare wood, plywood, particle board and other cellulosic materials where an intact water repellent barrier such as paint, stain, or a sealer is not present.

The use of this product in food processing establishments should be confined to time periods when the plant is not in operation. Foods should be removed or covered during treatment. All food processing surfaces should be covered during treatment or thoroughly cleaned before using. After treatment in food processing plants, thoroughly wash all equipment, benches, shelving, etc. where exposed food will be handled, with an effective cleaning compound and rinse with potable water.

When spraying overhead interior areas of homes, apartment buildings, etc. cover or protect all surfaces below the area being sprayed with plastic sheeting or other material which can be disposed of if contamination from dripping occurs. Do not apply in food serving areas while food is exposed.

BORA-CARE® is NOT a soil termiticide and should not be used directly to treat the soil.

STORAGE AND DISPOSAL

Do not contaminate water, food or feed by storage or disposal.

PESTICIDE STORAGE: Store in a dry place. Do not store where children or animals may gain access. Do not freeze.

PESTICIDE DISPOSAL: Do not contaminate water when disposing of equipment washwaters. Wastes resulting from the use of this product may be disposed of on site or at an approved waste disposal facility.

CONTAINER DISPOSAL: Triple rinse (or equivalent). Then offer for recycling or reconditioning, or puncture and dispose of in a sanitary landfill, or incineration, or if allowed by state and local authorities, by burning. If burned, stay out of smoke.

CLEANUP: Use soap and water to clean up tools.

SAFE HANDLING PROCEDURES

Applicators and other handlers must wear long-sleeved shirt and long pants, socks, shoes, chemical-resistant gloves, and protective eyewear. When applying BORA-CARE® in confined spaces, it is recommended that ventilation or an exhaust system be provided. If this is impractical, the use of a NIOSH approved respirator with an organic-vapor removing cartridge with a prefilter approved for pesticides (MSHA/NIOSH approval prefix TC-23C), or a canister approved for pesticides (MSHA/NIOSH approved prefix TC-14G), or a NIOSH approved respirator with an organic vapor (OV) cartridge or canister with any N, R, P or HE prefilter is recommended. Spills and over-spray may be cleaned with a damp cloth or absorbed with appropriate materials. (Refer to the BORA-CARE® Material Safety Data Sheet for additional health and safety information.)

I. MIXING INSTRUCTIONS

BORA-CARE® is a concentrate which **must** be diluted with clean water before use. The use of warm or hot water, if available, and an impeller type mixer which can be used with an electric drill aids the dilution process.

A. Hand Sprayers: Mix in a clean container and stir the solution until completely uniform. Always mix in a separate container then add the solution to a spray tank. Mixing BORA-CARE® directly in a spray tank can block hoses and nozzles.

B. High Volume Pumping Systems: Add all of the dilution water to tank, start recirculator, then slowly add BORA-CARE® concentrate. Allow to mix until uniform.

Use 1:1 and 2:1 BORA-CARE® solutions within 24 hours after mixing. 5:1-solutions will remain stable for up to 30 days. Do not leave unused solution under pressure or in tank overnight. Clean and/or flush equipment and lines with water after use.

BORA-CARE® may be tank-mixed with an approved non-residual pesticide for quicker knock-down of carpenter ants and other insects.

II. DILUTION RATIOS by volume.

TABLE A.

Target Pests	Dilution Ratios Water to BORA-CARE®	Application Notes
All Insects and Decay Fungi	1:1	Spray, Injection, Brush, Roller.
Subterranean and Formosan Termites	1:1 or 2:1	2:1 dilution ratio may be used for foaming
Drywood Termites	1:1 or 2:1	
Anobiid and Lyctid Powderpost Beetles	1:1 or 2:1	Use a 2:1 dilution ratio for treating hardwood floors. Logs require a 1:1 ratio.
All other beetle species	1:1	
Carpenter Ants	1:1 or 2:1	
Decay Fungi	1:1 or 2:1	Use a 1:1 dilution ratio on wood members 2" thick or greater.
Drywood Termites, Powderpost	5:1	Two (2) applications required for

Beetles and Decay Fungi

surface spray. For prevention only.

TABLE B.

Application	Dilution Ratios Water to BORA-CARE®	Application Notes
Logs, Large Beams and Dimensional Lumber	1:1	All Insects & Decay Fungi.
Preventative Treatment of Decking, Fences and Plywood	2:1	Use on wood members 2" in thickness or less.
Prevention of Powderpost Beetles and Drywood Termites	5:1	For prevention only.
Logs, Large Beams and Dimensional Lumber	5:1	Dip treatment only.

III. GENERAL INFORMATION

BORA-CARE® is an innovative termiticide, insecticide and fungicide that eliminates existing infestations and provides long term protection against:

Subterranean Termites: Reticulitermes, Heterotermes
Formosan Termites: Coptotermes
Dampwood Termites: Zootermopsis, Neotermes
Drywood Termites: Kaloterms, Incisitermes
Powderpost Beetles: Lyctidae, Bostrichidae
Anobiid Beetles: Anobiidae
Old House Borers, Longhorn Beetles: Cerambycidae, Hylotrupes
Ambrosia Beetles: Platypodidae, Scolytidae
Carpenter Ants: Camponotus
Brown Rot, White Rot, and Wood Decay Fungi

BORA-CARE® can be used on all cellulosic materials including wood, plywood, particle board, paper, oriented strand board (OSB), cardboard and wood composite structural components.

In areas where a soil treatment/barrier termiticide treatment is required by law, BORA-CARE® should be applied as a supplemental pretreatment to protect wood from subterranean termites that may penetrate chemical gaps occurring in termiticide-treated soil.

As a remedial treatment, BORA-CARE® will both eliminate and prevent infestations of Formosan, subterranean and drywood termites, wood boring beetles, carpenter ants and decay fungi. It may also be used as a supplement or alternative to fumigation in order to provide long term residual control.

Since BORA-CARE® is applied directly to the wood, it can be used in areas where environmental contamination is of concern (nearby wells, cisterns, etc.). The active ingredient in BORA-CARE® is an

inorganic salt and once in place, it will not decompose or volatilize out of the wood. Treatment is long lasting as long as the treated material is not exposed to rain, continuous water or ground contact.

Older wood boring beetle larvae (particularly Old House Borers) already present in the wood at the time of treatment may occasionally emerge sometime after treatment. This will not occur frequently enough to cause structural damage to any wooden member.

IV. REMEDIAL TREATMENT FOR THE CONTROL OF SUBTERRANEAN, FORMOSAN, DRYWOOD AND DAMPWOOD TERMITES; CARPENTER ANTS, OLD HOUSE BORERS, POWDERPOST AND OTHER WOOD BORING BEETLES AND WOOD DECAY FUNGI

A. Infested wood can be treated by spraying and/or injecting BORA-CARE® solution into beetle holes, termite and carpenter ant galleries and decay pockets. Apply one (1) coat of BORA-CARE® solution to the point of wetness to all infested and susceptible wood, paying particular attention to infested areas. Two (2) coats of BORA-CARE® solution need only be applied to those wood members with only one (1) or two (2) exposed sides. For quicker control, apply an additional coat onto heavily infested areas waiting at least 20 minutes between applications.

In cases where the infestation is not accessible from the surface, small holes may be drilled into the wood in order to gain access to the infested area. Inject enough diluted solution to completely flood galleries or voids. Adjacent intact wood may be treated by pressure injecting BORA-CARE® into holes drilled into the wood at eight (8) to ten (10) inch intervals. Inject at 40 psi for four (4) to six (6) seconds per hole.

For treating infested wall voids, refer to Sections IV. E. and F.

B. Basements and crawl spaces may be treated by applying one (1) coat of diluted BORA-CARE® solution to the point of wetness to all infested and susceptible wood surfaces including sill plates, piers, girders, subfloors, floor joists and any wood exposed to vertical access from the soil. On wood where access is limited to one (1) or two (2) sides of wood members, such as sills and plates on foundation walls, apply two (2) coats of BORA-CARE® solution. Wait at least 20 minutes between applications. Apply at a rate of approximately one (1) gallon of BORA-CARE® solution per 200 square feet of floor area (400 square feet of wood surface area).

C. Buildings on slabs may be treated by applying BORA-CARE® solution into wall voids by locating each stud and drilling a small hole through the wall covering to gain access to the infested area. Drill holes adjacent to the side of each stud every 18-24 inches along its length and inject at least 1/3 fluid ounce of BORA-CARE® solution per hole. Drill at least one hole per stud bay near the floor in order to treat the base plate in each void. Treat entire wall areas as opposed to single stud bays in order to include the infested area completely within the treatment zone.

D. Wood flooring can be treated by spray, brush or roller application. It will be necessary to remove any existing finish by complete coarse sanding or stripping prior to application. Apply a two (2) parts water to one (1) part BORA-CARE® (2:1) solution at a rate of approximately one (1) gallon of solution per 500 square feet of floor surface. For treating infestations of subterranean or Formosan termites, two (2) coats may be required, waiting at least one (1) hour between applications. Allow floor to completely dry (typically 48 to 72 hours). Moisture content must be 10% or less before applying final finish. BORA-CARE® applications may raise the grain of the wood and an additional light sanding may be necessary before applying a new finish. Although BORA-CARE® is compatible with most floor

coatings, always test a small section of treated floor with the new finish and check for appropriate adhesion prior to coating the entire floor.

NOTE: If surface is tacky or residue is evident after 72 hours of drying time, wash affected area with clean water and a mop, cloth or sponge, rinsing frequently. Allow surface to dry prior to final light sanding and application of finish coat.

E. For treating voids, wall studs and wood members not accessible by conventional application methods, spray or mist solution into voids and channels in damaged and suspected infested wood and/or through small holes drilled into walls and baseboard areas. Holes should be spaced no more than 24" apart along each member to be treated and at least one (1) hole must be drilled between each wall stud when treating base plates. Use sufficient amount of material to cover all areas to the point of wetness.

NOTE: Existing insulation may interfere with distribution of the BORA-CARE® solution. If necessary, remove or displace insulation prior to treatment.

F. Foam applications: BORA-CARE® can be applied to bare wood surfaces and void areas as a foam by mixing two (2) parts water with one (1) part BORA-CARE® (2:1) and adding 3 to 8 ounces of foaming agent per gallon of mixed solution. Apply foam being sure to completely fill the void. Foam will take approximately one (1) hour to return to liquid state and soak into bare wood.

Apply foamed BORA-CARE® to void spaces at a 1:20 to 1:30 foam ratio (one [1] gallon of mixed solution expanded with foaming agent to produce 20 to 30 gallons of foam). Apply enough foam to completely fill void and contact all wood surfaces in the void space.

G. Foam insulation may be treated by injecting a two (2) parts water to one (1) part BORA-CARE® (2:1) solution into the infested area and/or low pressure surface spraying at a rate of one (1) gallon per 300 to 400 square feet.

NOTE: Some types of foam insulation, such as polyisocyanurate and extruded polystyrene, have closed cell structures which do not allow significant penetration from surface application. These types of foam should be injected, as well as surface sprayed, to achieve proper control or prevention of infestations.

V. PREVENTATIVE AND/OR PRETREATMENT FOR WHOLE HOUSE PROTECTION FROM SUBTERRANEAN, FORMOSAN, DRYWOOD AND DAMPWOOD TERMITES, CARPENTER ANTS, OLD HOUSE BORERS, POWDERPOST AND OTHER WOOD BORING BEETLES AND WOOD DECAY FUNGI

NOTE: This treatment serves as a primary treatment for the control of Formosan and subterranean termites.

Pretreatment should be performed at a point during the construction process when the greatest access to all wood members is available. Normally this is at the "dried-in" stage of construction when all structural wood and sheathing is in place, yet prior to installation of insulation, mechanical systems, electrical wiring, etc.

Apply one (1) coat of a one (1) gallon water to one (1) gallon BORA-CARE® (1:1) solution to all wood surfaces to the point of wetness. Concentrate application in areas susceptible to attack, to include all sills, plates, floor joists, piers, girders and subfloors. Treat wood in all plumbing, electrical, and ductwork areas where they penetrate walls or floors. Treat all base plates and studs on interior and exterior walls, especially those surrounding any high moisture areas such as bathrooms, kitchens and laundry rooms. For buildings built on slabs, treat all wood in contact with the slab as well as all interior and exterior wall studs and wall sheathing material. In attics, treat all wood including ceiling joists, trusses, top plates, rafters and roof decking. Be sure that all sill plates and wood contacting garages and porches are treated.

In areas where access is limited to one (1) or two (2) sides of a wood member, apply two (2) coats of BORA-CARE® solution to the exposed surfaces. Wait at least 20 minutes between applications.

Treat all exterior wood including siding, fascias, soffits, eaves, roofing, porches, decks and railings (refer to Sections VIII and IX for complete exterior application information).

VI. PREVENTATIVE AND PRETREATMENTS FOR SUBTERRANEAN TERMITES (CRAWL SPACE, BASEMENT AND SLAB)

NOTE: This treatment serves as a primary treatment for the control of subterranean termites.

Use only a one (1) part water to one (1) part BORA-CARE® (1:1) solution when treating for subterranean termites.

Pretreatment may be performed at any point during the construction process, however it is best performed when greatest access to all wood members is available. Normally this is at the "dried-in" stage of construction when all structural wood and sheathing is in place, yet prior to installation of insulation, mechanical systems, electrical wiring, etc.

A. Buildings on Crawl Spaces and Basements: Apply one (1) coat of a one (1) gallon water to one (1) gallon BORA-CARE® (1:1) solution to point of wetness in a 24-inch wide uninterrupted band to all wood surfaces in crawl spaces and basements, to include all sills, plates, floor joists, piers, girders and subfloors as well as wood exposed to vertical access from the soil. Treat all wall base plates and the bottom two (2) feet of all interior and exterior wall studs. Treat any wood adjacent to plumbing, electrical conduit and ducts where they penetrate subfloors or plates, and all wood next to porches, garages, and fireplaces in order to provide a two (2) foot wide barrier of BORA-CARE® treatment against termite penetration.

On wood where access is limited to one (1) or two (2) sides of wood members such as sills and plates on foundation walls, apply two (2) coats of BORA-CARE® solution. Wait at least 20 minutes between applications. If accessible, treat the exterior of sill areas around the entire perimeter of the structure with a 24-inch wide band of BORA-CARE® solution beginning with the sill area and extending upwards onto the sheathing material.

On multiple story structures, treat only the first story above the masonry foundation level. Coated or painted wood may be treated by pressure injecting BORA-CARE® into holes drilled into the wood at eight (8) to ten (10) inch intervals. Inject at 40 psi for four (4) to six (6) seconds per hole.

B. Buildings on Slabs: Apply one (1) coat of a one (1) gallon water to one (1) gallon BORA-CARE® (1:1) solution to all base plates and the bottom 24 inches of all studs on all exterior and interior walls. In areas where access is limited to one (1) or two (2) sides of a wood member, apply two (2) coats of BORA-CARE® solution to the exposed surfaces. Wait at least 20 minutes between applications. Treat all wood in plumbing walls and apply to any wood in bath traps as well as wood adjacent to plumbing, electrical conduit and duct penetrations in order to provide a minimum 24 inch wide barrier of treatment between the soil and the balance of the structure.

VII. PREVENTATIVE TREATMENT FOR DRYWOOD TERMITES AND POWDERPOST BEETLES

Apply two (2) coats of a five (5) gallons water to one (1) gallon BORA-CARE® (5:1) solution to all wood surfaces to the point of wetness using a brush, spray or mist. Wait at least 20 minutes between applications.

VIII. TREATMENT OF EXTERIOR WOOD SURFACES LESS THAN TWO INCHES THICK SUCH AS DECKS, SHEDS, SIDING AND FENCES

Apply only to bare wood or to wood surfaces where an intact water repellent or finish is not present. If necessary, remove paint or finish prior to application. Apply one (1) coat of BORA-CARE® solution to the point of wetness to all wood surfaces. Apply two (2) coats of BORA-CARE® solution to heavily infested areas and to those surfaces where access is limited to one (1) or two (2) sides of wood members. Do not apply in rain or snow. Exterior wood surfaces must not be exposed to rain or snow for at least 48 hours after treatment. If inclement weather is expected, protect exterior treated surfaces with a plastic tarp.

For wood in contact with the ground or soil, see Section XI.

A. Finishing and Maintaining Treated Surfaces: For long term protection, exterior wood surfaces which have been treated with BORA-CARE® will require a topcoating with a water resistant finish such as paint or exterior stain. The finish or topcoat should be applied within six (6) weeks of treatment. It is important to allow BORA-CARE® treated wood to completely dry (at least 48 hours) before applying any protective topcoat. Coat a small section of treated wood with the finish to be used and check for compatibility prior to complete application.

IX. TREATMENT OF LOG STRUCTURES, TIMBERS, BEAMS, PILINGS, AND EXTERIOR WOOD MEMBERS TWO OR MORE INCHES THICK

Apply only to bare wood or to wood surfaces where an intact water repellent or other finish is not present. If necessary, remove paint or finish prior to application. Interior, unfinished surfaces which have accumulated dirt or cooking oils should be cleaned with a strong detergent prior to treatment. Apply a one (1) part water to one (1) part BORA-CARE® solution to the point of wetness to all interior and exterior wood surfaces. Refer to application chart for minimum amount of BORA-CARE® to treat various size logs or beams.

Typically, two (2) coats of solution will be required to treat round logs 10" or greater in diameter and rectangular logs larger than 6" x 12". Wait at least one (1) hour between applications. Two (2) coats of BORA-CARE® solution should also be applied to log ends, notches, corners and sill logs. Actual number of coats necessary to meet the minimum requirements will depend upon actual wood size, surface porosity and number of sides accessible for treatment. Do not apply in rain or snow. Exterior wood surfaces should not be exposed to rain or snow for at least 48 hours after treatment. If inclement weather is expected, protect exterior treated surfaces with a plastic tarp.

A. Finishing and Maintaining Treated Surfaces: For long term protection, exterior wood surfaces which have been treated with BORA-CARE® will require a topcoating with a water resistant finish paint or exterior stain. The finish or topcoat should be applied within six (6) weeks of treatment. It is important to allow BORA-CARE® treated wood to completely dry (at least 48 hours) before applying any protective topcoat. Coat a small section of treated wood with the finish to be used and check for compatibility prior to complete application.

X. DIP TREATING LOGS AND LUMBER

A dip treating solution may be prepared by mixing Five (5) part water to one (1) part BORA-CARE® (5:1). This will result in a stable solution containing 9% active ingredient. Bundled wood must be stickered in order to allow the solution to cover all wood surfaces. Logs and/or lumber should be submerged in the solution for at least one (1) minute or until all entrapped air has escaped. Protect treated wood from rain or snow for at least 24 hours after treatment.

XI. TREATMENT OF WOOD IN CONTACT WITH THE GROUND

A BORA-CARE® treatment to wood in contact with the ground or soil has a limited lifespan and will require periodic reapplication. Protection may be extended with the use of products such as JECTA® DIFFUSIBLE BORACIDE.

XII. APPLICATION RATES

TABLE A. Dimensional Lumber

Lumber Size (inches)	1 Gallon of Diluted BORA-CARE® Will Treat Up To:	Minimum Amount of Diluted BORA-CARE® To Treat 1000 Lineal Feet
1 x 4	1,200 Lineal Feet	0.8 Gallons
1 x 12	400	2.6
2 x 4	600	1.6
2 x 6	400	2.6
2 x 8	308	3.2
2 x 10	240	4.2
2 x 12	200	5.0
4 x 4	300	3.4
4 x 6	200	5.0
4 x 8	150	6.8
4 x 12	100	10.0
6 x 6	133	7.6
6 x 8	100	10.0
6 x 10	80	12.6
6 x 12	68	15.0

TABLE B. Panels, Siding and Plywood
(1:1 or 2:1 dilution ratio)

Thickness (inches)	1 Gallon of Diluted BORA-CARE® Will Treat Up To:	Minimum Amount of Diluted BORA-CARE® to Treat 1000 Square Feet
1/4	1,600 Square Feet	0.6 Gallons
3/8	1,067	1.0
1/2	800	1.2
3/4	533	1.8
1	400	2.6

TABLE C. Round logs
(1:1 dilution ratio only)

Diameter (inches)	1 Gallon of Diluted BORA-CARE® Will Treat Up To:	Minimum Amount of Diluted BORA-CARE® to Treat 1000 Lineal Feet
6	167 Lineal Feet	6.0 Gallons
8	96	10.4
10	61	16.4
12	43	23.4

NOTE: The numbers listed above are based on an application rate of one (1) gallon of BORA-CARE® solution to 400 board feet of wood.

XIII. WARRANTY LIMITATIONS AND DISCLAIMER

Because of varying conditions affecting use and application, manufacturer warns buyer that these may impair or vary the results or effects of the use of this product. In any event, complete prevention of decay or insect infestation is not guaranteed. Neither the manufacturer nor seller shall be liable in respect to any injury or damage suffered by reason of the use of this product for a purpose not indicated by the label or when used contrary to the directions or instructions hereon nor with respect to breach of any warranty not expressly specified herein. Buyer accepts this material subject to these terms and assumes all risk of usage and handling except when used or handled in accordance with this label.

It is not intended that this product be used to practice any applicable patent, whether mentioned or not, without procurement of a license, if necessary, from the owner, following investigation by the user.



100 Nisus Drive
Rockford, TN 37853
800-264-0870
www.nisuscorp.com

BORA-CARE® and JECTA®
are Registered Trademarks of NISUS Corporation.

MADE IN THE U.S.A.

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

14/1

Project Name: DAVENPORT NORTH Address: City, State: , Owner: ELECTRIC Climate Zone: North	Builder: MARONDA HOMES Permitting Office: Permit Number: Jurisdiction Number:
--	--

1. New construction or existing New ☐ 2. Single family or multi-family Single family ☐ 3. Number of units, if multi-family 1 ☐ 4. Number of Bedrooms 4 ☐ 5. Is this a worst case? Yes ☐ 6. Conditioned floor area (ft²) 2527 ft² ☐ 7. Glass type¹ and area: (Label reqd. by 13-104.4.5 if not default) <table style="width: 100%;"> <tr> <td style="width: 30%;">a. U-factor:</td> <td style="width: 30%;">Description</td> <td style="width: 40%;">Area</td> </tr> <tr> <td>(or Single or Double DEFAULT)</td> <td>7a. (Dble Default)</td> <td>237.0 ft²</td> </tr> <tr> <td>b. SHGC:</td> <td></td> <td></td> </tr> <tr> <td>(or Clear or Tint DEFAULT)</td> <td>7b. (Clear)</td> <td>237.0 ft²</td> </tr> </table> 8. Floor types <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Slab-On-Grade Edge Insulation</td> <td style="width: 30%;">R=0.0, 211.0(p) ft</td> <td style="width: 40%;">☐</td> </tr> <tr> <td>b. N/A</td> <td></td> <td>☐</td> </tr> <tr> <td>c. N/A</td> <td></td> <td>☐</td> </tr> </table> 9. Wall types <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Concrete, Int Insul, Exterior</td> <td style="width: 30%;">R=4.1, 1173.0 ft²</td> <td style="width: 40%;">☐</td> </tr> <tr> <td>b. Frame, Wood, Adjacent</td> <td>R=13.0, 326.0 ft²</td> <td>☐</td> </tr> <tr> <td>c. N/A</td> <td></td> <td>☐</td> </tr> <tr> <td>d. N/A</td> <td></td> <td>☐</td> </tr> <tr> <td>e. N/A</td> <td></td> <td>☐</td> </tr> </table> 10. Ceiling types <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Under Attic</td> <td style="width: 30%;">R=30.0, 2650.0 ft²</td> <td style="width: 40%;">☐</td> </tr> <tr> <td>b. N/A</td> <td></td> <td>☐</td> </tr> <tr> <td>c. N/A</td> <td></td> <td>☐</td> </tr> </table> 11. Ducts <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Sup: Unc. Ret: Con. AH(Sealed):Interior</td> <td style="width: 30%;">Sup. R=6.0, 250.0 ft</td> <td style="width: 40%;">☐</td> </tr> <tr> <td>b. N/A</td> <td></td> <td>☐</td> </tr> </table>	a. U-factor:	Description	Area	(or Single or Double DEFAULT)	7a. (Dble Default)	237.0 ft ²	b. SHGC:			(or Clear or Tint DEFAULT)	7b. (Clear)	237.0 ft ²	a. Slab-On-Grade Edge Insulation	R=0.0, 211.0(p) ft	☐	b. N/A		☐	c. N/A		☐	a. Concrete, Int Insul, Exterior	R=4.1, 1173.0 ft ²	☐	b. Frame, Wood, Adjacent	R=13.0, 326.0 ft ²	☐	c. N/A		☐	d. N/A		☐	e. N/A		☐	a. Under Attic	R=30.0, 2650.0 ft ²	☐	b. N/A		☐	c. N/A		☐	a. Sup: Unc. Ret: Con. AH(Sealed):Interior	Sup. R=6.0, 250.0 ft	☐	b. N/A		☐	12. Cooling systems <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Central Unit</td> <td style="width: 30%;">Cap: 47.5 kBtu/hr</td> <td style="width: 40%;">☐</td> </tr> <tr> <td></td> <td>SEER: 13.00</td> <td>☐</td> </tr> <tr> <td>b. N/A</td> <td></td> <td>☐</td> </tr> <tr> <td>c. N/A</td> <td></td> <td>☐</td> </tr> </table> 13. Heating systems <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Electric Heat Pump</td> <td style="width: 30%;">Cap: 47.5 kBtu/hr</td> <td style="width: 40%;">☐</td> </tr> <tr> <td></td> <td>HSPF: 8.00</td> <td>☐</td> </tr> <tr> <td>b. N/A</td> <td></td> <td>☐</td> </tr> <tr> <td>c. N/A</td> <td></td> <td>☐</td> </tr> </table> 14. Hot water systems <table style="width: 100%;"> <tr> <td style="width: 30%;">a. Electric Resistance</td> <td style="width: 30%;">Cap: 50.0 gallons</td> <td style="width: 40%;">☐</td> </tr> <tr> <td></td> <td>EF: 0.90</td> <td>☐</td> </tr> <tr> <td>b. N/A</td> <td></td> <td>☐</td> </tr> <tr> <td>c. Conservation credits</td> <td></td> <td>☐</td> </tr> <tr> <td colspan="3">(HR-Heat recovery, Solar</td> </tr> <tr> <td colspan="3">DHP-Dedicated heat pump)</td> </tr> </table> 15. HVAC credits PT, ☐ <table style="width: 100%;"> <tr> <td colspan="3">(CF-Ceiling fan, CV-Cross ventilation,</td> </tr> <tr> <td colspan="3">HF-Whole house fan,</td> </tr> <tr> <td colspan="3">PT-Programmable Thermostat,</td> </tr> <tr> <td colspan="3">MZ-C-Multizone cooling,</td> </tr> <tr> <td colspan="3">MZ-H-Multizone heating)</td> </tr> </table>	a. Central Unit	Cap: 47.5 kBtu/hr	☐		SEER: 13.00	☐	b. N/A		☐	c. N/A		☐	a. Electric Heat Pump	Cap: 47.5 kBtu/hr	☐		HSPF: 8.00	☐	b. N/A		☐	c. N/A		☐	a. Electric Resistance	Cap: 50.0 gallons	☐		EF: 0.90	☐	b. N/A		☐	c. Conservation credits		☐	(HR-Heat recovery, Solar			DHP-Dedicated heat pump)			(CF-Ceiling fan, CV-Cross ventilation,			HF-Whole house fan,			PT-Programmable Thermostat,			MZ-C-Multizone cooling,			MZ-H-Multizone heating)		
a. U-factor:	Description	Area																																																																																																											
(or Single or Double DEFAULT)	7a. (Dble Default)	237.0 ft ²																																																																																																											
b. SHGC:																																																																																																													
(or Clear or Tint DEFAULT)	7b. (Clear)	237.0 ft ²																																																																																																											
a. Slab-On-Grade Edge Insulation	R=0.0, 211.0(p) ft	☐																																																																																																											
b. N/A		☐																																																																																																											
c. N/A		☐																																																																																																											
a. Concrete, Int Insul, Exterior	R=4.1, 1173.0 ft ²	☐																																																																																																											
b. Frame, Wood, Adjacent	R=13.0, 326.0 ft ²	☐																																																																																																											
c. N/A		☐																																																																																																											
d. N/A		☐																																																																																																											
e. N/A		☐																																																																																																											
a. Under Attic	R=30.0, 2650.0 ft ²	☐																																																																																																											
b. N/A		☐																																																																																																											
c. N/A		☐																																																																																																											
a. Sup: Unc. Ret: Con. AH(Sealed):Interior	Sup. R=6.0, 250.0 ft	☐																																																																																																											
b. N/A		☐																																																																																																											
a. Central Unit	Cap: 47.5 kBtu/hr	☐																																																																																																											
	SEER: 13.00	☐																																																																																																											
b. N/A		☐																																																																																																											
c. N/A		☐																																																																																																											
a. Electric Heat Pump	Cap: 47.5 kBtu/hr	☐																																																																																																											
	HSPF: 8.00	☐																																																																																																											
b. N/A		☐																																																																																																											
c. N/A		☐																																																																																																											
a. Electric Resistance	Cap: 50.0 gallons	☐																																																																																																											
	EF: 0.90	☐																																																																																																											
b. N/A		☐																																																																																																											
c. Conservation credits		☐																																																																																																											
(HR-Heat recovery, Solar																																																																																																													
DHP-Dedicated heat pump)																																																																																																													
(CF-Ceiling fan, CV-Cross ventilation,																																																																																																													
HF-Whole house fan,																																																																																																													
PT-Programmable Thermostat,																																																																																																													
MZ-C-Multizone cooling,																																																																																																													
MZ-H-Multizone heating)																																																																																																													

Glass/Floor Area: 0.09

Total as-built points: 28994

Total base points: 32964

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: Wayne CampbellDATE: Wayne Campbell

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: Melma McKeaneDATE: Melma McKeane

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.



BUILDING OFFICIAL: _____

DATE: _____

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BSPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X SPM X SOF = Points				
.18	2527.0	18.59	8456.0	1.Double, Clear	W	1.0	6.0	71.0	38.52	0.97	2654.0
				2.Double, Clear	S	1.0	6.0	16.0	35.87	0.94	539.0
				3.Double, Clear	E	1.0	6.0	78.0	42.06	0.97	3176.0
				4.Double, Clear	W	1.0	8.0	40.0	38.52	0.99	1524.0
				5.Double, Clear	N	1.0	6.0	32.0	19.20	0.97	598.0
				As-Built Total:				237.0	8491.0		
WALL TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Adjacent	326.0	0.70	228.2	1. Concrete, Int Insul, Exterior	4.1		1173.0	1.13		1331.4	
Exterior	1173.0	1.70	1994.1	2. Frame, Wood, Adjacent	13.0		326.0	0.60		195.6	
Base Total: 1499.0 2222.3				As-Built Total:		1499.0		1527.0			
DOOR TYPES Area X BSPM = Points				Type	Area X SPM = Points						
Adjacent	18.0	2.40	43.2	1.Exterior Wood			20.0	6.10		122.0	
Exterior	38.0	6.10	231.8	2.Adjacent Wood			18.0	2.40		43.2	
				3.Exterior Wood			18.0	6.10		109.8	
Base Total: 56.0 275.0				As-Built Total:		56.0		275.0			
CEILING TYPES Area X BSPM = Points				Type	R-Value		Area X SPM X SCM = Points				
Under Attic	2527.0	1.73	4371.7	1. Under Attic	30.0		2650.0	1.73 X 1.00		4584.5	
Base Total: 2527.0 4371.7				As-Built Total:		2650.0		4584.5			
FLOOR TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Slab	211.0(p)	-37.0	-7807.0	1. Slab-On-Grade Edge Insulation	0.0		211.0(p)	-41.20		-8693.2	
Raised	0.0	0.00	0.0								
Base Total: -7807.0				As-Built Total:		211.0		-8693.2			
INFILTRATION Area X BSPM = Points				Area X SPM = Points							
2527.0 10.21 25800.7				2527.0 10.21 25800.7							

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT						
Summer Base Points: 33318.7				Summer As-Built Points: 31984.9						
Total Summer Points	X System Multiplier	=	Cooling Points	Total Component (System - Points)	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	=	Cooling Points
33318.7	0.3250		10828.6	(sys 1: Central Unit 47500btuh ,SEER/EFF(13.0) Ducts:Unc(S),Con(R),Int(AH),R6.0(INS) 31985 1.00 (1.08 x 1.147 x 0.86) 0.260 0.950 8468.3 31984.9 1.00 1.072 0.260 0.950 8468.3						

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X WPM X WOF = Points				
.18	2527.0	20.17	9175.0	1.Double, Clear	W	1.0	6.0	71.0	20.73	1.01	1483.0
				2.Double, Clear	S	1.0	6.0	16.0	13.30	1.03	218.0
				3.Double, Clear	E	1.0	6.0	78.0	18.79	1.02	1489.0
				4.Double, Clear	W	1.0	8.0	40.0	20.73	1.00	831.0
				5.Double, Clear	N	1.0	6.0	32.0	24.58	1.00	786.0
				As-Built Total:				237.0		4807.0	
WALL TYPES Area X BWPM = Points				Type	R-Value		Area X WPM		= Points		
Adjacent	326.0	3.60	1173.6	1. Concrete, Int Insul, Exterior	4.1		1173.0	6.42		7530.7	
Exterior	1173.0	3.70	4340.1	2. Frame, Wood, Adjacent	13.0		326.0	3.30		1075.8	
Base Total: 1499.0 5513.7				As-Built Total:		1499.0				8606.5	
DOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM		= Points		
Adjacent	18.0	11.50	207.0	1.Exterior Wood			20.0	12.30		246.0	
Exterior	38.0	12.30	467.4	2.Adjacent Wood			18.0	11.50		207.0	
				3.Exterior Wood			18.0	12.30		221.4	
Base Total: 56.0 674.4				As-Built Total:		56.0				674.4	
CEILING TYPES Area X BWPM = Points				Type	R-Value		Area X WPM X WCM		= Points		
Under Attic	2527.0	2.05	5180.4	1. Under Attic	30.0		2650.0	2.05 X 1.00		5432.5	
Base Total: 2527.0 5180.4				As-Built Total:		2650.0				5432.5	
FLOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM		= Points		
Slab	211.0(p)	8.9	1877.9	1. Slab-On-Grade Edge Insulation	0.0		211.0(p)	18.80		3966.8	
Raised	0.0	0.00	0.0								
Base Total: 1877.9				As-Built Total:		211.0				3966.8	
INFILTRATION Area X BWPM = Points						Area X WPM		= Points			
2527.0 -0.59 -1490.9						2527.0 -0.59		-1490.9			

WINTER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: , , ,

PERMIT #:

BASE			AS-BUILT						
Winter Base Points: 20930.4			Winter As-Built Points: 21996.2						
Total Winter Points	X System Multiplier	= Heating Points	Total Component (System - Points)	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Heating Points	
20930.4	0.5540	11595.5	(sys 1: Electric Heat Pump 47500 btuh ,EFF(8.0) Ducts:Unc(S),Con(R),Int(AH),R6.0 21996.2 1.000 (1.060 x 1.169 x 0.88) 0.426 0.950 9751.3 21996.2 1.00 1.095 0.426 0.950 9751.3						

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT						
WATER HEATING										
Number of Bedrooms	X	Multiplier	= Total	Tank Volume	EF	Number of Bedrooms	X	Tank X Ratio	Multiplier X Credit	= Total Multiplier
4		2635.00	10540.0	50.0	0.90	4		1.00	2693.56	1.00 10774.2
				As-Built Total:						10774.2

CODE COMPLIANCE STATUS							
BASE				AS-BUILT			
Cooling Points	+	Heating Points	+ Hot Water Points	= Total Points	Cooling Points	+	Heating Points + Hot Water Points = Total Points
10829		11595	10540	32964	8468		9751 10774 28994

PASS



Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	✓
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	✓
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	✓
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	✓
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	✓
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	✓
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	✓

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	✓
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	✓
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	✓
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	✓
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	✓
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	✓

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 86.9

The higher the score, the more efficient the home.

ELECTRIC, . . .

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 47.5 kBtu/hr
3. Number of units, if multi-family	1		SEER: 13.00
4. Number of Bedrooms	4	b. N/A	
5. Is this a worst case?	Yes	c. N/A	
6. Conditioned floor area (ft ²)	2527 ft ²		
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		13. Heating systems	
a. U-factor:	Description Area	a. Electric Heat Pump	Cap: 47.5 kBtu/hr
(or Single or Double DEFAULT)	7a. (Dble Default) 237.0 ft ²		HSPF: 8.00
b. SHGC:		b. N/A	
(or Clear or Tint DEFAULT)	7b. (Clear) 237.0 ft ²	c. N/A	
8. Floor types		14. Hot water systems	
a. Slab-On-Grade Edge Insulation	R=0.0, 211.0(p) ft	a. Electric Resistance	Cap: 50.0 gallons
b. N/A			EF: 0.90
c. N/A		b. N/A	
9. Wall types		c. Conservation credits	
a. Concrete, Int Insul, Exterior	R=4.1, 1173.0 ft ²	(HR-Heat recovery, Solar	
b. Frame, Wood, Adjacent	R=13.0, 326.0 ft ²	DHP-Dedicated heat pump)	
c. N/A		15. HVAC credits	PT,
d. N/A		(CF-Ceiling fan, CV-Cross ventilation,	
e. N/A		HF-Whole house fan,	
10. Ceiling types		PT-Programmable Thermostat,	
a. Under Attic	R=30.0, 2650.0 ft ²	MZ-C-Multizone cooling,	
b. N/A		MZ-H-Multizone heating)	
c. N/A			
11. Ducts			
a. Sup: Unc. Ret: Con. AH(Sealed):Interior	Sup. R=6.0, 250.0 ft		
b. N/A			

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: [Signature]
Address of New Home: 135 SW BLACK MAPLE CT

Date: 11/25/08

City/FL Zip: LAKE CITY FL 32024



*NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStarTM designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.
EnergyGauge® (Version: FLRCSB v4.5)



Project Summary
Entire House
Maronda Homes

Job:
Date:
By: G. Carmack

4005 Maronda Way, Sanford, FL 32771 Phone: 407-321-3913 Fax: 407-321-0064

Project Information

For: DAVENPORT

Notes:

Design Information

Weather: Jacksonville, Int'l AP, FL, US

Winter Design Conditions

Outside db	32 °F
Inside db	70 °F
Design TD	38 °F

Summer Design Conditions

Outside db	93 °F
Inside db	75 °F
Design TD	18 °F
Daily range	M
Relative humidity	50 %
Moisture difference	51 gr/lb

Heating Summary

Structure	35160 Btuh
Ducts	5770 Btuh
Central vent (100 cfm)	4175 Btuh
Humidification	0 Btuh
Piping	0 Btuh
Equipment load	45105 Btuh

Sensible Cooling Equipment Load Sizing

Structure	20194 Btuh
Ducts	12342 Btuh
Central vent (100 cfm)	1934 Btuh
Blower	0 Btuh

Infiltration

Method	Simplified
Construction quality	Average
Fireplaces	0

	Heating	Cooling
Area (ft ²)	2527	2527
Volume (ft ³)	20216	20216
Air changes/hour	0.32	0.16
Equiv. AVF (cfm)	108	54

Use manufacturer's data	n
Rate/swing multiplier	0.98
Equipment sensible load	33642 Btuh

Latent Cooling Equipment Load Sizing

Structure	1879 Btuh
Ducts	2839 Btuh
Central vent (100 cfm)	3485 Btuh
Equipment latent load	8204 Btuh

Equipment total load	41846 Btuh
Req. total capacity at 0.76 SHR	3.7 ton

Heating Equipment Summary

Make TEMPSTAR
Trade HEAT PUMP
Model N4H348AKB

Efficiency	8 HSPF
Heating input	
Heating output	0 Btuh @ 47°F
Temperature rise	0 °F
Actual air flow	0 cfm
Air flow factor	0.000 cfm/Btuh
Static pressure	0.60 in H2O
Space thermostat	

Cooling Equipment Summary

Make	TEMPSTAR
Trade	HEAT PUMP
Cond	N4H348AKB
Coil	FSU4X4800A
Efficiency	13 SEER
Sensible cooling	36100 Btuh
Latent cooling	11400 Btuh
Total cooling	47500 Btuh
Actual air flow	1460 cfm
Air flow factor	0.045 cfm/Btuh
Static pressure	0.60 in H2O
Load sensible heat ratio	0.81

Bold/italic values have been manually overridden

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.



wrightsoft

Right-Suite Residential 6.0.90 RSR21115

C:\Documents and Settings\gcarmack\My Documents\Man J Calcs 2007\JACKSONVILLE\DAVENPORT 13.rpt Ca

2008-Sep-22 13:45:49

Page 1

Duct System Summary

Entire House

Maronda Homes

Job: DAVENPORT
Date:
By: G. Carmack

4005 Maronda Way, Sanford, FL 32771 Phone: 407-321-3913 Fax: 407-321-0064

Project Information

For: DAVENPORT

	Heating	Cooling
External static pressure	0.60 in H2O	0.60 in H2O
Pressure losses	0.00 in H2O	0.00 in H2O
Available static pressure	0.60 in H2O	0.60 in H2O
Supply / return available pressure	0.46 / 0.14 in H2O	0.46 / 0.14 in H2O
Lowest friction rate	0.100 in/100ft	0.100 in/100ft
Actual air flow	1460 cfm	1460 cfm
Total effective length (TEL)	26 ft	

Supply Branch Detail Table

Name	Design (Btuh)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	Rect Size (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
MASTER BDR	h 626 5	240	240	0.100	8	x0	VIFx	5.0	0.0	st1
MASTER BATH	h 294 7	75	75	0.100	6	x0	VIFx	10.0	0.0	st1
MASTER TOILET	h 111 6	25	25	0.100	4	x0	VIFx	20.0	0.0	st1
LIVING ROOM	h 310 7	155	155	0.100	7	x0	VIFx	5.0	0.0	st1
FAMILY ROOM	c 413 9	165	165	0.100	7	x0	VIFx	5.0	0.0	st1
DINING ROOM	h 434 1	125	125	0.100	6	x0	VIFx	5.0	0.0	st1
NOOK	h 265 3	125	125	0.100	6	x0	VIFx	20.0	0.0	st1
KITCHEN	c 262 7	100	100	0.100	6	x0	VIFx	10.0	0.0	st1
BDR #4	h 325 2	130	130	0.100	6	x0	VIFx	10.0	0.0	ST2
bDR #3	h 198 4	90	90	0.100	6	x0	VIFx	5.0	0.0	ST2
BATH	h 867	20	20	0.100	4	x0	VIFx	15.0	0.0	ST2
BDR #2	c 410 9	160	160	0.100	7	x0	VIFx	15.0	0.0	ST2
UTILITY	h 907	50	50	0.100	4	x0	VIFx	10.0	0.0	ST3

Supply Trunk Detail Table

Name	Trunk Type	Htg (cfm)	Clg (cfm)	Design FR	Veloc (fpm)	Diam (in)	Rect Duct Size (in)	Duct Material	Trunk
st1	Peak AVF	1010	1010	0.100	590	16	0 x 0	VinIFlx	
ST2	Peak AVF	400	400	0.100	517	10	0 x 0	VinIFlx	
ST3	Peak AVF	50	50	0.100	284	4	0 x 0	VinIFlx	

Bold/italic values have been manually overridden

Return Branch Detail Table

Name	Grill Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	RectSize (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb1	0x0	1460	1460	6.0	2.308	669	18	x0 0		VIFx	

27543

FIELD DENSITY WORKSHEET

CLIENT Maronda Homes DATE 1-5-09
 PROJECT NAME Timberlands Lot 14 PROJECT NO. _____
 EARTH CONTRACTOR _____ PERMIT NO. _____
 COMPACTION REQUIREMENT (%) 95 ☐ Standard Proctor TESTED BY S.L.
☒ Modified Proctor FIELD CONTACT _____
 TOTAL ON-SITE TIME _____ MILES FROM OFFICE _____
☐ Limerock ☐ Subgrade ☐ Pipe Backfill ☒ Building Pad ☐ Building Footing ☐ Other _____

TEST LOCATION	LAB PROCTOR		TEST DEPTH	PROBE DEPTH	% MOIST.	WET DENSITY (PCF)	DRY DENSITY (PCF)	% COMP.
	DENS.	OMC						
	105.8	10.7	F/G	12"				
6 NE of SW corner of Pad					5.9	109.6	103.5	97.8
Center of Pad					6.2	110.7	104.2	98.5
6 SW of NE corner of Pad					6.0	110.2	104.0	98.3

REMARKS _____

- * Density failed to meet minimum project requirement
- ** Retest indicates minimum density requirement was obtained.
- () Client is aware of unsatisfactory test results.

COLUMBIA COUNTY OFFICE OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 10-4S-16-02856-114

Building permit No. 000027543

Use Classification SFD, UTILITY

Fire: 44.94

Permit Holder TED BROCK

Waste: 117.25

Owner of Building MARONDA HOMES

Total: 162.19

Location: 135 SW BLACK MAPLE CT., LAKE CITY, FL

Date: 03/23/2009

Wayne A. Durr


Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)



LOT FOURTEEN (14) OF "MARICANDS" AS PER PLAT THEREOF, AS RECORDED IN PLAT BOOK '9, PAGE 27 OF THE PUBLIC RECORDS OF COLUMBIA COUNTY, FLORIDA.

16 EAST, COLUMBIA COUNTY, FLORIDA



3) MARONDA HOMES

BUILDING SETBACK INFORMATION FOR
"TIMBERLANDS" IS AS FOLLOWS: FRONT

25', HEAR 15', SIDE 10'

ELEVATIONS SHOWN HEREON ARE BASED UPON A BENCHMARK SET IN A 8" PILE AT THE FRONT OF LOT 2, WITH AN ELEVATION OF 98.76'. THIS INFORMATION WAS PROVIDED TO THIS SURVEYOR BY BIRDT SURVEYING (PLATTING SUPERVISOR) DATA UNKNOWN.

- 1) TO THE BEST OF MY KNOWLEDGE, THERE ARE NO ENCROACHMENTS, BOUNDARY LINE DISPUTES, EASEMENTS, OR CLAIMS OF EASEMENTS, OTHER THAN ARE DEPICTED ON THIS DRAWING.
- 2) ALL UTILITIES AND OR IMPROVEMENTS, IF ANY, MAY NOT BE SHOWN ON THIS DRAWING.

- 3) IN THE OPINION OF THIS SURVEYOR THE BOUNDARY SHOWN HEREIN BEST REPRESENTS THE LOCATION OF THE SUBJECT PROPERTY IN RELATION TO THE ADJACENT PROPERTY. THE SURVEYOR HAS BEEN FOUND TO BE RESPONSIBLE TO THIS SURVEYOR.
- 4) BLINDING STRUCK LINES REFLECT HEREON ARE SHOWN AS PER THE RECORD PLAT, BUT ARE SUBJECT TO CHANGE PRIOR TO ANY NEW CONSTRUCTION. THE SURVEYOR HAS BEEN FOUND TO BE RESPONSIBLE TO THIS SURVEYOR FOR THE CURRENT SURVEY REQUIREMENTS.
- 5) THIS USE OF SURVEY HEREON CONTAINING LOCATED AS THE POINT OF FIELD WORK COMPLETION (SEE THE BLOCK).
- 6) ASKS OF ENVIRONMENTAL CONCERN HAVE NOT BEEN LOCATED BY THIS SURVEYOR, UNLESS OTHERWISE NOTED HEREON.

CURVE	RADIUS	TANGENT	LENGTH	DELTA	CHORD	CHORD BEARING
C9	60.00'	51.87'	85.54'	81°41'05"	76.40'	N 77°05'15" W

IN THE OPEN OF THIS STATE, ACCORDING TO THE NATIONAL FLOOD INSURANCE PROGRAM, FLOOD INSURANCE RATE MAP COMMUNITY PANEL NO. 120070-0175-B, DATED 01-6-88, THIS PROPERTY IS IN FLOOD ZONE "X" WHICH IS AN AREA DETERMINED TO BE OUTSIDE 500-YEAR FLOOD PLAIN, AS SCALED FLOOD MAP INFORMATION FROM THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAPS, SHOWN ON THIS MAP, WAS CURRENT AS OF THE REFERENCED DATE. MAP REVISIONS AND AMENDMENTS ARE PERIODICALLY MADE BY LETTER AND MAY NOT BE REFLECTED ON THE MOST CURRENT MAP.

THIS SURETY IS SUBJECT TO ANY FACTS THAT MAY BE DISCLOSED BY A FULL AND ACCURATE TITLE SEARCH. THIS SURETOR HAS NOT PERFORMED A SEARCH OF THE PUBLIC RECORDS ON THIS PARCEL FOR ANY CLAIMS OF TITLE, EASEMENTS, OR RESTRICTIONS THAT MAY AFFECT THIS PARCEL. THE PRESENCE OR ABSENCE OF ANY SUCH CLAIMS ARE NOT CERTIFIED HEREON.

A/C	AIR CONDITIONER
ASPH	ASPHALT
C	CABLE TIED FROM MEASURED
C/S	CABLE STRAP
C/B	CONCRETE BLOCK
CLF	CHAIN LINK FENCE
CM	CONCRETE MOUNTMENT
CONC	CONCRETE
ELEV	ELEVATION
FNC	FENCE
LJ	USED SURVEYOR BUSINESS
MH	MANHOLE
O/L	OVERHEAD UTILITIES
PB	PUBLIC WORKS DEPARTMENT
R/W	RIGHT-OF-WAY
T/C	TRUCK CHASSIS
WM	WATER METER
WV	WATER VALVE

NOT VALID WITHOUT THE SIGNATURE AND THE ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER. ADDITIONS OR DELETIONS TO THIS MAP BY ANYONE OTHER THAN THIS SURVEYOR IS PROHIBITED.

I HEREBY CERTIFY THAT THE SURVEY DATA SHOWN HEREON, IS A TRUE AND CORRECT REPRESENTATION OF A SURVEY PERFORMED UNDER MY SUPERVISION OF THE HEREON DESCRIBED PROPERTY, AND IT MEETS THE MINIMUM TECHNICAL STANDARDS AS SET FORTH BY THE FLORIDA BOARD OF LAND SURVEYORS, PURSUANT TO SECTION 472.007, FLORIDA STATUTES, AND CHAPTER 61A02-2.00, FLORIDA ADMINISTRATIVE CODE.

BY: ~~_____~~
JAMES E. BRINKMAN, PSM - FLA CERT# 5582
DATE: 11/24/08

BRINKMAN SURVEYING & MAPPING INC.

4607 NW 6th STREET SUITE C, GAINESVILLE, FL 32609
PHONE: (352) 374-7707 FAX: (352) 374-6757

THE BENCHMARK IN QUALITY SERVICE™ DRAWN BY: ZL CHECKED BY: J.B.	E 1" = 30' 11/5/2008
--	------------------------------------

PREPARED FOR: WARONDA

166-
DINAM

Architectural floor plan of a rectangular room with a sloped partition. The plan shows a room with a total width of 9'-11" and a total length of 29'-10". A sloped partition divides the room into two sections. The left section has a width of 5'-0" and a length of 29'-10". The right section has a width of 4'-7 1/2" and a length of 29'-10". The partition is labeled with dimensions 5'-1 5/8" and 5'-1 5/8".

3/4" DEEP POURED CONC. SLAB
W/ 6X6 10/10 MESH OR FIBER
MESH/FIBER MIX ADDED TO THE
CONCRETE ON CLEAN COMPACT FILL

10' X 30' PORCH SLAB

HOUSE SLAB

8" X 8" POURED
CONC. MOND FOOTING
W/ 1 #5 BAR

10³-Q³

FOUNDATION PLAN

SCALE: $1/4" = 1' - 0"$

DESIGNED BY

GOVERNMENT, INC.

1980 DOLGNER PLACE SUITE 1058 SANFORD, FL 32771 .407-322-8122

© COPYRIGHT 2007 ALL RIGHTS RESERVED

NO REPRODUCTION MAY BE MADE WITHOUT THE EXPRESSED WRITTEN CONSENT OF COVERALL ALUMINUM, INC.

GENERAL NOTES:

1. MAX HEIGHT FROM TOP 1x2 TO BOTTOM OF 2x4 IS 7'-2"
2. MAX DISTANCE BETWEEN 2x4 POSTS IS 5'-7"
3. BUILDING STYLES MAY VARY BUT ALUMINUM SCREEN ENCLOSURES WILL BE TYP FOR ALL APPLICATIONS.

THIS PLAN HAS BEEN DESIGNED IN ACCORDANCE WITH THE ALUMINUM STRUCTURES DESIGN MANUAL BY LAWRENCE & BENNETT AND ARE IN COMPLIANCE WITH THE 2004 BUILDING CODE EDITION WITH 2006 SUPPLEMENTS, CHAPTER 20, ASME 30 AND THE 2005 ALUMINUM DESIGN MANUAL PART 1-A & 11-A EXPOSURE B.

DANIEL L. SMITH
DRAFTING SERVICE

407-709-2981 811 BILL BECK BLVD.
KISSIMMEE, FLORIDA 34744


2 SIDED 10x30 ALUMINUM
SCREENED ENCLOSURE
PLAN VIEWS

ഭിന്നി, പാ


Date: 04-06-07

02

RIGHT ELEVATION



REAR ELEVATION



SCALE: 1/4" = 1'-0"

DESIGNED BY:
COVERALL ALUMINUM, INC.

1980 DOLNER PLACE SUITE 1068 SANFORD, FL 32771 407-322-8122
COPYRIGHT 2007 ALL RIGHTS RESERVED
NO REPRODUCTION MAY BE MADE WITHOUT THE EXPRESSED WRITTEN CONSENT OF COVERALL ALUMINUM, INC.

2 SIDED 10x30 ALUMINUM SCREENED ENCLOSURE ELEVATIONS

Cont'n. No.
Date: 04-06-07

01


THIS PLAN HAS BEEN DESIGNED IN ACCORDANCE WITH THE ALUMINUM STRUCTURES DESIGN MANUAL BY LAWRENCE & BENNETT, AND ARE IN COMPLIANCE WITH THE 2004 BUILDING CODE EDITION WITH 2006 SUPPLEMENTS, CHAPTER 20, ASME 35 AND THE 2005 ALUMINUM DESIGN MANUAL PART 1-A & 11-A EXPOSURE B.



407-700-2081 811 BILL BECK BLVD.
KISSIMMEE, FLORIDA 34744

LEGAL DESCRIPTION:
LOT FOURTEEN (14) OF "TIMBERLANDS" AS PER PLAT THEREOF, AS RECORDED IN PLAT BOOK '9', PAGE 27 OF THE PUBLIC RECORDS OF COLUMBIA COUNTY, FLORIDA.

PROPOSED BUILDING LAYOUT
IN SECTION 10, TOWNSHIP 4 SOUTH, RANGE 16 EAST, COLUMBIA COUNTY, FLORIDA



CERTIFIED TO:

1) MARONDA HOMES

BUILDING SETBACK NOTE:


BUILDING SETBACK INFORMATION FOR "TIMBERLANDS" IS AS FOLLOWS: FRONT 25', REAR 15', SIDE 10'

BENCHMARK NOTE:

ELEVATIONS SHOWN HEREON ARE BASED UPON A BENCHMARK SET IN A 8" PINE AT THE FRONT OF LOT 2, WITH AN ELEVATION OF 98.76'. THIS INFORMATION WAS PROVIDED TO THIS SURVEYOR BY BRIT SURVEYING (PLATTING SURVEYOR) DATUM UNKNOWN.

SURVEYOR NOTES:

- 1) TO THE BEST OF MY KNOWLEDGE, THERE ARE NO ENCROACHMENTS, BOUNDARY LINE DISPUTES, EASEMENTS, OR CLAIMS OF EASEMENTS, OTHER THAN ARE DEPICTED ON THIS DRAWING.
- 2) ALL UTILITIES AND OR IMPROVEMENTS, IF ANY, MAY NOT BE SHOWN ON THIS DRAWING.
- 3) IN THE OPINION OF THIS SURVEYOR THE BOUNDARY SHOWN HEREON BEST REPRESENTS THE LOCATION OF THE SUBJECT PROPERTY IN RELATION TO THE DESCRIPTION AND THOSE PROPERTY CORNERS FOUND TO BE ACCEPTABLE TO THIS SURVEYOR.
- 4) BUILDING SETBACK LINES DEPICTED HEREON ARE SHOWN AS PER THE RECORD PLAT, BUT ARE SUBJECT TO CHANGE. PRIOR TO ANY NEW CONSTRUCTION, THE APPROPRIATE GOVERNING AUTHORITY SHOULD BE CONTACTED FOR THE CURRENT SETBACK REQUIREMENTS.
- 5) THIS MAP OF SURVEY REFLECTS CONDITIONS LOCATED AS OF THE DATE OF FIELD WORK COMPLETION (SEE TITLE BLOCK).
- 6) AREAS OF ENVIRONMENTAL CONCERN HAVE NOT BEEN LOCATED BY THIS SURVEYOR, UNLESS OTHERWISE DEPICTED HEREON.



CURVE TABLE:

CURVE	RADIUS	TANGENT	LENGTH	DELTA	CHORD	CHORD BEARING
C9	60.00'	51.87'	85.54'	81°41'05"	78.48'	N 77°05'13" W

FLOOD NOTE:

IN THE OPINION OF THIS SURVEYOR, ACCORDING TO THE NATIONAL FLOOD INSURANCE PROGRAM, FLOOD INSURANCE RATE MAP COMMUNITY PANEL NO. 120070-0175-B, DATED 1-6-88, THIS PROPERTY IS IN FLOOD ZONE "X" WHICH IS AN AREA DETERMINED TO BE OUTSIDE 500-YEAR FLOOD PLAIN, AS SCALED FROM SAID MAP. INFORMATION FROM THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAPS, SHOWN ON THIS MAP, WAS CURRENT AS OF THE REFERENCED DATE. MAP REVISIONS AND AMENDMENTS ARE PERIODICALLY MADE BY LETTER AND MAY NOT BE REFLECTED ON THE MOST CURRENT MAP.

TITLE NOTE:

THIS SURVEY IS SUBJECT TO ANY FACTS THAT MAY BE DISCLOSED BY A FULL AND ACCURATE TITLE SEARCH. THIS SURVEYOR HAS NOT PERFORMED A SEARCH OF THE PUBLIC RECORDS ON THIS PARCEL FOR ANY CLAIMS OF TITLE, EASEMENTS, OR RESTRICTIONS THAT MAY EFFECT THIS PARCEL. THE PRESENCE OR ABSENCE OF ANY SUCH CLAIMS ARE NOT CERTIFIED HEREON.

ABBREVIATIONS:
A/C = AIR CONDITIONER
ASPH = ASPHALT
C = CALCULATED FROM MEASURED
CATV = CABLE TELEVISION
C/B = CONCRETE BLOCK
CLF = CHAIN LINK FENCE
CM = CONCRETE MONUMENT
CONC = CONCRETE
ELEC = ELECTRIC
ELEV = ELEVATION
FND = FOUND
FNC = FENCE
LB = LICENSED SURVEYOR BUSINESS
(M) = FIELD MEASURED
MH = MANHOLE
O.U. = OVERHEAD UTILITIES
P = PLAT
PB = PLAT BOOK
P.U.E. = PUBLIC UTILITIES EASEMENT
TRANS = TRANSFORMER
TYP = TYPICAL
WM = WATER METER
WV = WATER VALVE

THIS IS NOT A BOUNDARY SURVEY
CERTIFICATE OF SURVEYOR:

NOT VALID WITHOUT THE SIGNATURE AND THE ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER. ADDITIONS OR DELETIONS TO THIS MAP BY ANYONE OTHER THAN THIS SURVEYOR IS PROHIBITED.

I HEREBY CERTIFY THAT THE SURVEY DATA SHOWN HEREON, IS A TRUE AND CORRECT REPRESENTATION OF A SURVEY PERFORMED UNDER MY SUPERVISION OF THE HERON DESCRIBED PROPERTY, AND IT MEETS THE MINIMUM TECHNICAL STANDARDS AS SET FORTH BY THE FLORIDA BOARD OF LAND SURVEYORS, PURSUANT TO SECTION 472.027, FLORIDA STATUTES, AND CHAPTER 61G12-6, FLORIDA ADMINISTRATIVE CODE.

BY:  JAMES E. BRINKMAN, PSM - F.L.A. CERT# 5582
DATE: 11/24/08

BRINKMAN SURVEYING & MAPPING INC.



4607 NW 8th STREET SUITE C, GAINESVILLE, FL 32609
PHONE: (352) 374-7707 FAX: (352) 374-8757

SCALE: 1" = 30'

"THE BENCHMARK IN QUALITY SERVICE"

DATE: 11/5/2008

DRAWN BY: ZL

CHECKED BY: J.B.


FIELD WORK COMPLETED ON **** FIELDBOOK **, PAGE **

PREPARED FOR: MARONDA

DRAWING NUMBER
166-08

LEGAL DESCRIPTION:
LOT FOURTEEN (14) OF "TIMBERLANDS" AS
PER PLAT THEREOF, AS RECORDED IN PLAT
BOOK '9', PAGE 27 OF THE PUBLIC
RECORDS OF COLUMBIA COUNTY, FLORIDA.

BOUNDARY SURVEY
IN SECTION 10, TOWNSHIP 4 SOUTH, RANGE
16 EAST, COLUMBIA COUNTY, FLORIDA



CERTIFIED TO:

1) MARONDA HOMES

BUILDING SETBACK NOTE:

BUILDING SETBACK INFORMATION FOR
"TIMBERLANDS" IS AS FOLLOWS: FRONT
25', REAR 15', SIDE 10'

BENCHMARK NOTE:

ELEVATIONS SHOWN HEREON ARE BASED UPON A
BENCHMARK SET IN A 8" PINE AT THE FRONT OF LOT
2, WITH AN ELEVATION OF 98.76'. THIS INFORMATION
WAS PROVIDED TO THIS SURVEYOR BY BRITT
SURVEYING (PLATTING SURVEYOR) DATUM UNKNOWN.

SURVEYOR NOTES:

- 1) TO THE BEST OF MY KNOWLEDGE, THERE ARE NO
ENCROACHMENTS, BOUNDARY LINE DISPUTES,
EASEMENTS, OR CLAIMS OF EASEMENTS, OTHER THAN
ARE DEPICTED ON THIS DRAWING.
- 2) ALL UTILITIES AND OR IMPROVEMENTS, IF ANY, MAY NOT
BE SHOWN ON THIS DRAWING.
- 3) IN THE OPINION OF THIS SURVEYOR THE BOUNDARY
SHOWN HEREON BEST REPRESENTS THE LOCATION OF
THE SUBJECT PROPERTY IN RELATION TO THE
DESCRIPTION AND THOSE PROPERTY CORNERS FOUND
TO BE ACCEPTABLE TO THIS SURVEYOR.
- 4) BUILDING SETBACK LINES DEPICTED HEREON ARE
SHOWN AS PER THE RECORD PLAT, BUT ARE SUBJECT
TO CHANGE. PRIOR TO ANY NEW CONSTRUCTION, THE
APPROPRIATE GOVERNING AUTHORITY SHOULD BE
CONTACTED FOR THE CURRENT SETBACK REQUIREMENTS.
- 5) THIS MAP OF SURVEY REFLECTS CONDITIONS LOCATED
AS OF THE DATE OF FIELD WORK COMPLETION (SEE
TITLE BLOCK).
- 6) AREAS OF ENVIRONMENTAL CONCERN HAVE NOT BEEN
LOCATED BY THIS SURVEYOR, UNLESS OTHERWISE
DEPICTED HEREON.

S.W. BLACK
MAPLE COURT
60' RIGHT-OF-WAY

CURVE TABLE:

CURVE	RADIUS	TANGENT	LENGTH	DELTA	CHORD	CHORD BEARING
C9(P)	60.00'	51.87'	85.54'	81°41'05"	78.48'	N 77°05'13" W
C9(M)	60.00'	51.81'	85.47'	81°37'13"	78.43'	N 77°07'03" W

FLOOD NOTE:

IN THE OPINION OF THIS SURVEYOR, ACCORDING TO THE NATIONAL
FLOOD INSURANCE PROGRAM, FLOOD INSURANCE RATE MAP
COMMUNITY PANEL NO. 120070-0175-B, DATED 1-6-88, THIS
PROPERTY IS IN FLOOD ZONE "X" WHICH IS AN AREA DETERMINED
TO BE OUTSIDE 500-YEAR FLOOD PLAIN, AS SCALED FROM SAID
MAP. INFORMATION FROM THE FEDERAL EMERGENCY MANAGEMENT
AGENCY (FEMA) FLOOD INSURANCE RATE MAPS, SHOWN ON THIS
MAP, WAS CURRENT AS OF THE REFERENCED DATE. MAP REVISIONS
AND AMENDMENTS ARE PERIODICALLY MADE BY LETTER AND MAY
NOT BE REFLECTED ON THE MOST CURRENT MAP.

TITLE NOTE:

THIS SURVEY IS SUBJECT TO ANY FACTS THAT MAY BE
DISCLOSED BY A FULL AND ACCURATE TITLE SEARCH. THIS
SURVEYOR HAS NOT PERFORMED A SEARCH OF THE
PUBLIC RECORDS ON THIS PARCEL FOR ANY CLAIMS OF
TITLE, EASEMENTS, OR RESTRICTIONS THAT MAY AFFECT
THIS PARCEL. THE PRESENCE OR ABSENCE OF ANY SUCH
CLAIMS ARE NOT CERTIFIED HEREON.

S 89°15'24"E 334.45' (P)
S 89°15'24"E 334.45' (M)

LOT 14
40.56 ACRES
M.F.F. = 106.50'

BUILDING SETBACK
LINES (TYPICAL)

BEARING BASIS
S 89°15'24"E 534.72' (P)
S 89°15'24"E 534.65' (M)

LEGEND:

- = FOUND 1/2" REBAR & CAP
L.B. 7593
- = SET 1/2" REBAR & CAP
L.B. 6894
- ⊞ = CAVY RISER
- ⊞ = TELEPHONE HANDHOLE

ABBREVIATIONS:

A/C = AIR CONDITIONER
ASPH = ASPHALT
C = CALCULATED FROM MEASURED
CATV = CABLE TELEVISION
C/B = CONCRETE BLOCK
CLF = CHAIN LINK FENCE
CM = CONCRETE MONUMENT
CONC = CONCRETE
ELEC = ELECTRIC
ELEV = ELEVATION
FND = FOUND
FNC = FENCE
LB = LICENSED SURVEYOR BUSINESS
(M) = FIELD MEASURED
MH = MANHOLE
O.U. = OVERHEAD UTILITIES
P = PLAT
PB = PLAT BOOK
P.U.E. = PUBLIC UTILITIES EASEMENT
TRANS = TRANSFORMER
TYP = TYPICAL
WM = WATER METER
WV = WATER VALVE

CERTIFICATE OF SURVEYOR :

NOT VALID WITHOUT THE SIGNATURE AND THE ORIGINAL RAISED SEAL OF
A FLORIDA LICENSED SURVEYOR AND MAPPER. ADDITIONS OR DELETIONS
TO THIS MAP BY ANYONE OTHER THAN THIS SURVEYOR IS PROHIBITED.

I HEREBY CERTIFY THAT THE SURVEY DATA SHOWN HEREON, IS A
TRUE AND CORRECT REPRESENTATION OF A SURVEY PERFORMED UNDER
MY SUPERVISION OF THE HERON DESCRIBED PROPERTY, AND IT MEETS
THE MINIMUM TECHNICAL STANDARDS AS SET FORTH BY THE FLORIDA
BOARD OF LAND SURVEYORS, PURSUANT TO SECTION 472.227, FLORIDA
STATUTES, AND CHAPTER 61617-6, FLORIDA ADMINISTRATIVE CODE.

BY:
JAMES E. BRINKMAN, PLS - FLA. CERT# 5382
DATE: 1/12/09

BRINKMAN SURVEYING & MAPPING INC.

4807 NW 8th STREET SUITE C, GAINESVILLE, FL 32609
PHONE: (352) 374-7707 FAX: (352) 374-8757

SCALE: 1" = 30'
DATE: 11/5/2008
FIELD WORK COMPLETED ON 1/8/2009
FIELD BOOK 99, PAGE 39

PREPARED FOR: MARONDA	DRAWN BY: ZL	CHECKED BY: J.B.	DRAWING NUMBER 166-08
-----------------------	--------------	------------------	--------------------------



HOMETEAM
PEST DEFENSE®

TREATMENT WORKORDER

☐ Termite Baiting System w/Tubes-under-the slab

☐ Treat Only ☒ Tubes-under-the slab and Treat ☐ Bora-Care

DATE CALLED IN:	1-9	DATE OF SCHEDULE:	1-12
TIME CALLED IN:		TIME SCHEDULE:	8:30

JOB NAME:	SUBDIVISION:		
JOB ADDRESS:	135 SW Black Maple Ct		
BILLING NAME:	BELLING PHONE:		
BILLING ADDRESS:			
CALLED IN BY:	PHONE:	PERMIT NUMBER:	

LOT & MODEL NUMBER: Lot 141

DATE & TIME COMPLETED: 1/12/09

SQUARE FOOT: 3496 LINEAR FOOT:

SLAB TYPE: mono

BLOCKVOIDS:

TYPE OF FILL: sand/dirt

APPROX. DEPTH OF FOOTING: Outside:

Inside:

☐ Addition ☐ Spot Treat ☐ Pool Addition ☐ Driveway

☐ Final/Completion ☐ Other

PESTICIDE USED: Imax Pro

TOTAL APPLIED: 175 gal

PERCENT (%) USED: 1%

STICKER POSTED: yps

PRICE PER SQ. FT. =

TOTAL FOR P.T. =

ADDITIONAL

TAX:

TOTAL AMOUNT \$

X

X TECHNICIAN:

I hereby acknowledge the satisfactory completion of the above described work.
GT 23 / TCI