



Lumber design values are in accordance with ANSI/TPI 1 section 6.3
These truss designs rely on lumber values established by others.

RE: 2435655 - LIPSCOMB EAGLE - LOT 11 FV

MiTek USA, Inc.

6904 Parke East Blvd.
Tampa, FL 33610-4115

Site Information:

Customer Info: Lipscomb Eagle Project Name: Spec Hse Model: Custom
Lot/Block: 11 Subdivision: Fairway View III
Address: N/A, N/A
City: Columbia Cty State: FL

Name Address and License # of Structural Engineer of Record, If there is one, for the building.

Name: License #:
Address:
City: State:


General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2017/TPI2014 Design Program: MiTek 20/20 8.2
Wind Code: ASCE 7-10 Wind Speed: 130 mph
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 30 individual, Truss Design Drawings and 0 Additional Drawings.

With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

| No. | Seal# | Truss Name | Date | No. | Seal# | Truss Name | Date |
|-----|-----------|------------|---------|-----|-----------|------------|---------|
| 1 | T20989237 | CJ01 | 8/11/20 | 23 | T20989259 | T09T | 8/11/20 |
| 2 | T20989238 | CJ03 | 8/11/20 | 24 | T20989260 | T10 | 8/11/20 |
| 3 | T20989239 | CJ05 | 8/11/20 | 25 | T20989261 | T11 | 8/11/20 |
| 4 | T20989240 | EJ01 | 8/11/20 | 26 | T20989262 | T12 | 8/11/20 |
| 5 | T20989241 | EJ02 | 8/11/20 | 27 | T20989263 | T12G | 8/11/20 |
| 6 | T20989242 | EJ03 | 8/11/20 | 28 | T20989264 | T13 | 8/11/20 |
| 7 | T20989243 | HJ05 | 8/11/20 | 29 | T20989265 | T14 | 8/11/20 |
| 8 | T20989244 | HJ10 | 8/11/20 | 30 | T20989266 | T15 | 8/11/20 |
| 9 | T20989245 | PB01 | 8/11/20 | | | | |
| 10 | T20989246 | PB02 | 8/11/20 | | | | |
| 11 | T20989247 | T01 | 8/11/20 | | | | |
| 12 | T20989248 | T01G | 8/11/20 | | | | |
| 13 | T20989249 | T02 | 8/11/20 | | | | |
| 14 | T20989250 | T03 | 8/11/20 | | | | |
| 15 | T20989251 | T04 | 8/11/20 | | | | |
| 16 | T20989252 | T05 | 8/11/20 | | | | |
| 17 | T20989253 | T06 | 8/11/20 | | | | |
| 18 | T20989254 | T07 | 8/11/20 | | | | |
| 19 | T20989255 | T07T | 8/11/20 | | | | |
| 20 | T20989256 | T08 | 8/11/20 | | | | |
| 21 | T20989257 | T08T | 8/11/20 | | | | |
| 22 | T20989258 | T09 | 8/11/20 | | | | |



The truss drawing(s) referenced above have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource-Jacksonville.

Truss Design Engineer's Name: Velez, Joaquin

My license renewal date for the state of Florida is February 28, 2021.

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11, 2020

Velez, Joaquin


1 of 1

| | | | | | |
|----------------|---------------|-------------------------|----------|----------|---|
| Job 2435655 | Truss CJ01 | Truss Type Jack-Open | Qty 8 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV T20989237 |
|----------------|---------------|-------------------------|----------|----------|---|

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:56:58 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-1QTaWeDnmBFR4HovPKxsxsJqgGbz33UC1DuS6yowoZ



Scale = 1:9.4

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|----------|--------|------|--------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.17 | Vert(LL) | -0.00 | 7 | >999 | 240 | MT20 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.04 | Vert(CT) | 0.00 | 7 | >999 | 180 | 244/190 |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.00 | Horz(CT) | 0.00 | 2 | n/a | n/a | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MP | | | | | | |
| | | | | | | | | Weight: 6 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=64(LC 12)
Max Uplift 3=-6(LC 1), 2=-108(LC 12), 4=-25(LC 19)
Max Grav 3=10(LC 16), 2=179(LC 1), 4=28(LC 16)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=108.



Joaquín Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | |
|---------|-------|------------|-----|-----|----------------------------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV |
| 2435655 | CJ03 | Jack-Open | 4 | 1 | T20989238 |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:56:59 2020 Page 1
ID:1bYwwjYqtpHfMFFctmROVywFXb-Vc1zk_EPXVNIiRN5z2F5U3r?Qfw?KWJdRhyR_YyowoY



Scale = 1:15.3

| LOADING (psf) | SPACING- | CSI. | DEFL. | PLATES | GRIP |
|---------------|----------------------|-----------|-----------------------------|---------------|----------|
| TCLL 20.0 | 2-0-0 | TC 0.17 | in (loc) l/defl L/d | MT20 | 244/190 |
| TCDL 7.0 | Plate Grip DOL 1.25 | BC 0.11 | Vert(LL) 0.01 4-7 >999 240 | | |
| BCLL 0.0 * | Lumber DOL 1.25 | WB 0.00 | Vert(CT) -0.01 4-7 >999 180 | | |
| BCDL 10.0 | Rep Stress Incr YES | Matrix-MP | Horz(CT) 0.00 3 n/a n/a | | |
| | Code FBC2017/TPI2014 | | | Weight: 12 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=120(LC 12)
Max Uplift 3=60(LC 12), 2=91(LC 12), 4=26(LC 9)
Max Grav 3=65(LC 19), 2=210(LC 1), 4=50(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2, 4.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|----------------|---------------|-------------------------|----------|----------|--|-----------|
| Job 2435655 | Truss CJ05 | Truss Type Jack-Open | Qty 4 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV Job Reference (optional) | T20989239 |
|----------------|---------------|-------------------------|----------|----------|--|-----------|

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:56:59 2020 Page 1

ID:1bYwwjYqtpHfiMFFctmROVywFXb-Vc1zk_EPXVNiIRN5z2F5U3ryofsLKWJdRhyR_YyowoY



Scale = 1:21.0

Plate Offsets (X,Y)-- [2:0-1-12,0-1-8]

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|----------|--------|------|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.34 | Vert(LL) | 0.08 | 4-7 | >721 | 240 | MT20 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.35 | Vert(CT) | 0.07 | 4-7 | >834 | 180 | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.00 | Horz(CT) | -0.00 | 3 | n/a | n/a | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MP | | | | | | |
| | | | | | | | | Weight: 19 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=177(LC 12)
Max Uplift 3=111(LC 12), 2=102(LC 12), 4=46(LC 9)
Max Grav 3=123(LC 19), 2=276(LC 1), 4=89(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 3=111, 2=102.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|--------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989240 |
| 2435655 | EJ01 | Jack-Partial | 16 | 1 | Job Reference (optional) | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:05 2020 Page 1
ID:1bYwwjYqtpHfIMFFctmROVywFXb-JmOE_2JA7L7SQMrFJIMVjK5sM4pbkEoWpcPmCCyowoS



Scale = 1:27.3

Plate Offsets (X,Y)-- [2:0-1-8,0-1-8]

| LOADING (psf) | SPACING- | | CSI. | DEFL. | in | (loc) | I/defl | L/d | PLATES | GRIP |
|---------------|----------------------|------|-----------|----------|-------|-------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.78 | Vert(LL) | 0.33 | 4-7 | >253 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.74 | Vert(CT) | 0.28 | 4-7 | >295 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.00 | Horz(CT) | -0.01 | 3 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | Weight: 25 lb | FT = 20% |

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-10-4 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=225(LC 12)
Max Uplift 3=144(LC 12), 2=120(LC 12), 4=66(LC 9)
Max Grav 3=178(LC 19), 2=346(LC 1), 4=126(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 3=144, 2=120.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|------------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989241 |
| 2435655 | EJ02 | Jack-Open Girder | 1 | 1 | Job Reference (optional) | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:06 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-oyycCNJoteFJ2WQRi0tkGYeA7U81TZZf2G9JkeyowR



Scale = 1:26.0

| Plate Offsets (X,Y)-- | | [6-0-2-0-0-2-12] | | | | | | | | | |
|-----------------------|-------|----------------------|------|-----------|------|----------|-------|----------|--------|---------------|----------|
| LOADING (psf) | | SPACING- | | CSI. | | DEFL. | | in (loc) | I/defl | L/d | |
| TCLL | 20.0 | Plate Grip DOL | 1.25 | TC | 0.20 | Vert(LL) | -0.02 | 6-7 | >999 | 240 | |
| TCDL | 7.0 | Lumber DOL | 1.25 | BC | 0.79 | Vert(CT) | -0.04 | 6-7 | >999 | 180 | |
| BCLL | 0.0 * | Rep Stress Incr | NO | WB | 0.54 | Horz(CT) | 0.01 | 6 | n/a | n/a | |
| BCDL | 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | | |
| | | | | | | | | | | Weight: 42 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-9-11 oc bracing.

REACTIONS.

(size) 1=0-3-8, 6=Mechanical
Max Horz 1=189(LC 8)
Max Uplift 1=447(LC 8), 6=609(LC 8)
Max Grav 1=1041(LC 1), 6=1362(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1570/581
BOT CHORD 1-7=-637/1341, 6-7=-637/1341
WEBS 2-7=-561/1428, 2-6=-1587/754

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=447, 6=609.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 339 lb down and 248 lb up at 1-4-12, and 779 lb down and 313 lb up at 3-4-12, and 779 lb down and 313 lb up at 5-4-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)
Vert: 1-3=-54, 3-4=-14, 1-5=-20
- Concentrated Loads (lb)
Vert: 7=-779(B) 11=-339(B) 12=-779(B)



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | |
|---------|-------|------------|-----|-----|----------------------------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV |
| 2435655 | EJ03 | Jack-Open | 2 | 1 | T20989242 |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:10 2020 Page 1
ID:1bYwwjYqtpHfiMFFctmROVywFXb-gkB71IMJtlkW7jD6rygQOote5gaPU1Fyu7XIPyowoN



Scale = 1:15.3

| LOADING (psf) | SPACING- | | CSI. | DEFL. | in | (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|------|-----------|----------|-------|-------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.17 | Vert(LL) | 0.01 | 4-7 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.11 | Vert(CT) | -0.01 | 4-7 | >999 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.00 | Horz(CT) | 0.00 | 3 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MP | | | | | | Weight: 12 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=120(LC 12)
Max Uplift 3=60(LC 12), 2=91(LC 12), 4=26(LC 9)
Max Grav 3=65(LC 19), 2=210(LC 1), 4=50(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2, 4.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|----------------|---------------|-----------------------------------|----------|----------|----------------------------|-----------|
| Job 2435655 | Truss HJ05 | Truss Type DIAGONAL HIP GIRDER | Qty 2 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV | T20989243 |
|----------------|---------------|-----------------------------------|----------|----------|----------------------------|-----------|

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:11 2020 Page 1
ID:1bYwwjYqtpHfIMFFctmROVywFXb-8wIVF5NxiBtb8HIPgZTvzbL0KV_68xHOBYS4QryowoM



| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | I/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|-----------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.30 | Vert(LL) | -0.03 4-7 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.22 | Vert(CT) | -0.04 4-7 | >999 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | NO | WB 0.00 | Horz(CT) | 0.00 2 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MP | | | | | Weight: 17 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-2-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=119(LC 8)
Max Uplift 3=-83(LC 8), 2=-227(LC 4), 4=-43(LC 5)
Max Grav 3=84(LC 1), 2=296(LC 1), 4=71(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=227.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 83 lb down and 76 lb up at 1-6-1, and 83 lb down and 76 lb up at 1-6-1 on top chord, and 60 lb down and 52 lb up at 1-6-1, and 60 lb down and 52 lb up at 1-6-1 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 4-5=-20



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11, 2020



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|---------------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989244 |
| 2435655 | HJ10 | Diagonal Hip Girder | 2 | 1 | Job Reference (optional) | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:12 2020 Page 1
ID:1bYwwjYqtpHfMFFctmROVwFXb-c6JtISROZTU?SmRtbDG_8Vpu6kvEWIKXQCdyowL



Scale = 1:26.8

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in | (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|-------|-------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.58 | Vert(LL) | 0.11 | 6-7 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.60 | Vert(CT) | -0.11 | 6-7 | >999 | 180 | | |
| BCLL 0.0 | Rep Stress Incr | NO | WB 0.40 | Horz(CT) | -0.01 | 5 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | Weight: 44 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 7-0-1 oc bracing.

REACTIONS.

(size) 4=Mechanical, 2=0-4-9, 5=Mechanical
Max Horz 2=225(LC 26)
Max Uplift 4=131(LC 8), 2=404(LC 4), 5=274(LC 5)
Max Grav 4=149(LC 1), 2=527(LC 1), 5=299(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-740/536
BOT CHORD 2-7=-607/629, 6-7=-607/629
WEBS 3-7=-144/283, 3-6=-674/650

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 4=131, 2=404, 5=274.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 83 lb down and 76 lb up at 1-6-1, 83 lb down and 76 lb up at 1-6-1, 102 lb down and 59 lb up at 4-4-0, 102 lb down and 59 lb up at 4-4-0, and 133 lb down and 119 lb up at 7-1-15, and 133 lb down and 119 lb up at 7-1-15 on top chord, and 60 lb down and 52 lb up at 1-6-1, 60 lb down and 52 lb up at 1-6-1, 20 lb down and 34 lb up at 4-4-0, 20 lb down and 34 lb up at 4-4-0, and 42 lb down and 61 lb up at 7-1-15, and 42 lb down and 61 lb up at 7-1-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 5-8=-20
Concentrated Loads (lb)
Vert: 7=-5(F=-3, B=-3) 12=-73(F=-36, B=-36) 15=-59(F=-29, B=-29)



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|----------------|---------------|-------------------------|----------|----------|--|-----------|
| Job 2435655 | Truss PB01 | Truss Type Piggyback | Qty 2 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV Job Reference (optional) | T20989245 |
|----------------|---------------|-------------------------|----------|----------|--|-----------|

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:13 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-4JtFgnPBEo8JNbSnn_VN20QO8JfncmhfsLBUkyowoK



Scale = 1:14.4




Plate Offsets (X,Y)-- [3:0-3-0,0-1-12], [4:0-3-0,0-1-12]

| LOADING (psf) | SPACING- | | CSI. | DEFL. | in | (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|----------|----------|------|-------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 2-0-0 | TC 0.15 | Vert(LL) | 0.00 | 5 | n/r | 120 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.27 | Vert(CT) | 0.00 | 6 | n/r | 120 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.00 | Horz(CT) | 0.00 | 5 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-R | | | | | | Weight: 20 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=5-7-11, 5=5-7-11
Max Horz 2=31(LC 11)
Max Uplift 2=-99(LC 12), 5=-99(LC 13)
Max Grav 2=238(LC 1), 5=238(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-294/266, 3-4=-251/244, 4-5=-294/267
BOT CHORD 2-5=-192/251

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCp=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 5.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610


| | | | | | | |
|----------------|---------------|-------------------------|----------|----------|--|-----------|
| Job 2435655 | Truss PB02 | Truss Type Piggyback | Qty 4 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV Job Reference (optional) | T20989246 |
|----------------|---------------|-------------------------|----------|----------|--|-----------|

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:13 2020 Page 1
ID:1bYwwjYqIpHfMFFctmROVywFXb-4JlFgnPBEo8JNbSnn_VN20QPZJipcrPhfsLBUkyowok



Scale = 1:15.1



| LOADING (psf) | SPACING- | | CSI. | DEFL. | in | (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|------|----------|----------|------|-------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.13 | Vert(LL) | 0.00 | 5 | n/r | 120 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.08 | Vert(CT) | 0.00 | 5 | n/r | 120 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.02 | Horz(CT) | 0.00 | 4 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-P | | | | | | Weight: 23 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 2=5-7-11, 4=5-7-11, 6=5-7-11
Max Horz 2=-61(LC 10)
Max Uplift 2=-75(LC 12), 4=-83(LC 13), 6=-40(LC 12)
Max Grav 2=140(LC 1), 4=140(LC 20), 6=196(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4, 6.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | |
|---|--------------|----------------------|-----------|----------|---|
| Job 2435655 | Truss T01 | Truss Type Common | Qty 10 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV T20989247 |
| Builders FirstSource, Jacksonville, FL - 32244, | | | | | Job Reference (optional) |

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:14 2020 Page 1
ID:1bYwwjYqtpHfIMFFctmROVywFXb-ZVRet7Qq?6GA?11_Lh0cbEzVGisoLEHqtW5k0AyowoJ



| Plate Offsets (X,Y)→ [6:0-2-8,Edge], [9:0-4-0,0-3-0] | | | | | | | | | | | | | | | | | |
|--|--|----------------------|--|-----------|--|----------------|--|----------|--|--------|--|-----|--|--------|--|---------|--|
| LOADING (psf) | | SPACING- 2-0-0 | | CSI. | | DEFL. | | in (loc) | | l/defl | | L/d | | PLATES | | GRIP | |
| TCLL 20.0 | | Plate Grip DOL 1.25 | | TC 0.39 | | Vert(LL) 0.16 | | 8-9 | | >999 | | 240 | | MT20 | | 244/190 | |
| TCDL 7.0 | | Lumber DOL 1.25 | | BC 0.86 | | Vert(CT) -0.27 | | 8-9 | | >967 | | 180 | | | | | |
| BCLL 0.0 * | | Rep Stress Incr NO | | WB 0.30 | | Horz(CT) 0.04 | | 6 | | n/a | | n/a | | | | | |
| BCDL 10.0 | | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | | | | | | | | |
| Weight: 107 lb FT = 20% | | | | | | | | | | | | | | | | | |

| | |
|-----------------------|---|
| LUMBER- | BRACING- |
| TOP CHORD 2x4 SP No.2 | TOP CHORD Structural wood sheathing directly applied or 4-5-0 oc purlins. |
| BOT CHORD 2x4 SP No.2 | BOT CHORD Rigid ceiling directly applied or 7-7-14 oc bracing. |
| WEBS 2x4 SP No.3 | |

REACTIONS. (size) 2=0-3-8, 6=0-3-8
Max Horz 2=-224(LC 10)
Max Uplift 2=-433(LC 12), 6=-433(LC 13)
Max Grav 2=1072(LC 1), 6=1071(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1640/716, 3-4=-1507/703, 4-5=-1503/700, 5-6=-1638/716
BOT CHORD 2-9=-580/1498, 8-9=-267/988, 6-8=-504/1365
WEBS 4-8=-309/713, 5-8=-339/282, 4-9=-311/715, 3-9=-338/281

- NOTES-
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=433, 6=433.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 4-7=-54, 9-10=-20, 8-9=-80(F=60), 8-13=-20



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|----------------|---------------|--------------------------------------|----------|----------|--|-----------|
| Job 2435655 | Truss T01G | Truss Type Common Supported Gable | Qty 1 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV Job Reference (optional) | T20989248 |
|----------------|---------------|--------------------------------------|----------|----------|--|-----------|

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:16 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-VtZOloR4XjWuE2AMS624gf2uXWjcpBJ7Lqar53yowoH



Scale = 1:45.4




Plate Offsets (X,Y)-- [2:0-3-8,Edge], [9:0-3-0,Edge], [16:0-3-8,Edge]

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|----------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.14 | Vert(LL) | -0.01 | 17 | n/r | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.14 | Vert(CT) | -0.01 | 17 | n/r | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.08 | Horz(CT) | 0.01 | 16 | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-S | | | | | Weight: 118 lb | FT = 20% |

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 21-8-0.
(lb) - Max Horz 2=214(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 2, 16, 22, 26, 21, 18 except 24=111(LC 12), 25=102(LC 12), 20=117(LC 13), 19=101(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 2, 16, 24, 25, 26, 20, 19, 18 except 22=317(LC 19), 21=285(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 16, 22, 26, 21, 18 except (jt=lb) 24=111, 25=102, 20=117, 19=101.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|--------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989249 |
| 2435655 | T02 | Roof Special | 1 | 1 | Job Reference (optional) | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:17 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-z46mV8Si1elsCIZ0paJCSbx0wv2YZNHZUJ0dVyowoG



4x6 ||

Scale = 1:41.6




Plate Offsets (X,Y)- [2:0-6-0,0-0-3], [8:0-8-0,0-0-4]

| LOADING (psf) | SPACING- | | CSI. | DEFL. | in (loc) | I/defl | L/d | PLATES | GRIP |
|---------------|----------------------|--|-----------|----------|----------|--------|------|----------------|----------|
| TCLL 20.0 | Plate Grip DOL 1.25 | | TC 0.67 | Vert(LL) | -0.24 | 9-15 | >485 | 240 | MT20 |
| TCDL 7.0 | Lumber DOL 1.25 | | BC 0.77 | Vert(CT) | -0.50 | 9-15 | >235 | 180 | 244/190 |
| BCLL 0.0 * | Rep Stress Incr YES | | WB 0.41 | Horz(CT) | 0.01 | 9 | n/a | n/a | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | |
| | | | | | | | | Weight: 117 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
4-12,6-9: 2x4 SP No.3
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-11-6 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 9-10.

REACTIONS.

(size) 8=Mechanical, 2=0-3-8, 9=0-3-8
Max Horz 2=215(LC 9)
Max Uplift 8=228(LC 13), 2=238(LC 12), 9=239(LC 12)
Max Grav 8=389(LC 20), 2=512(LC 23), 9=829(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-644/352, 3-4=-1123/561, 4-5=-1274/689, 5-6=-233/302, 7-8=-411/338
BOT CHORD 2-12=-292/529, 11-12=-191/421, 9-10=-595/195, 8-9=-211/316
WEBS 3-12=-609/346, 3-11=-448/915, 5-11=-656/1207, 7-9=-383/278, 5-10=-490/190

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCPi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=228, 2=238, 9=239.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | |
|----------------|--------------|----------------------|----------|----------|---|
| Job 2435655 | Truss T03 | Truss Type Common | Qty 2 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV T20989250 |
|----------------|--------------|----------------------|----------|----------|---|

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:18 2020 Page 1

ID:1bYwwjYqtPffMFFctmROVywFXb-RGg8jUTK3KmcUMKlaX5YI48B?KI4H3gQo83y9xyowof



Scale = 1:41.9




Plate Offsets (X,Y) - [2:0-6-0,0-0-3], [6:0-6-0,0-0-4]

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in | (loc) | I/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|-------|-------|--------|-----|----------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.34 | Vert(LL) | -0.08 | 7-12 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.52 | Vert(CT) | -0.17 | 7-12 | >999 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.21 | Horz(CT) | 0.03 | 6 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | | |
| | | | | | | | | | Weight: 104 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-9-12 oc bracing.

REACTIONS.

(size) 6=Mechanical, 2=0-3-8
Max Horz 2=215(LC 11)
Max Uplift 6=293(LC 13), 2=347(LC 12)
Max Grav 6=799(LC 1), 2=885(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1239/557, 3-4=-1125/541, 4-5=-1120/547, 5-6=-1249/564
BOT CHORD 2-9=-446/1139, 7-9=-173/721, 6-7=-413/1050
WEBS 4-7=-220/500, 5-7=-352/297, 4-9=-208/485, 3-9=-356/290

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (it=lb) 6=293, 2=347.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

| | | | | | |
|----------------|--------------|--------------------------|----------|----------|---|
| Job 2435655 | Truss T04 | Truss Type Hip Girder | Qty 1 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV T20989251 |
|----------------|--------------|--------------------------|----------|----------|---|

Builders FirstSource, Jacksonville, FL - 32244,


8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:20 2020 Page 1

ID:1bYwvYqtpHfMFFctmROVYwFXb-Nfov8AUaay0KjgU8hy70qVDN87?ql06jGSY2Eqyow0D

Job Reference (optional)

| | | | | | | | | | | | |
|-------|--------|--------|--------|---------|--------|--------|--------|--------|---------|--------|---------|
| 1-6-0 | 3-10-4 | 7-0-0 | 12-0-0 | 17-1-12 | 20-8-0 | 24-2-4 | 29-4-0 | 34-4-0 | 37-5-12 | 41-4-0 | 42-10-0 |
| 1-6-0 | 3-10-4 | 3-1-12 | 5-0-0 | 5-1-12 | 3-6-4 | 3-6-4 | 5-1-12 | 5-0-0 | 3-1-12 | 3-10-4 | 1-6-0 |

Scale = 1:72.2



| | |
|----------------------|--|
| Plate Offsets (X,Y)- | [4:0-3-0,0-1-12], [5:0-3-8,0-1-8], [10:0-3-8,0-1-8], [11:0-3-0,0-1-12], [19:0-5-0,0-4-12], [21:0-5-0,0-4-12] |
|----------------------|--|

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | I/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|-------------|--------|-----|----------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 1.00 | Vert(LL) | 0.15 23-24 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.50 | Vert(CT) | -0.16 23-24 | >999 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | NO | WB 0.92 | Horz(CT) | 0.05 13 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | |
| | | | | | | | | Weight: 264 lb | FT = 20% |

| | |
|-----------------------|---|
| LUMBER- | BRACING- |
| TOP CHORD 2x4 SP No.2 | TOP CHORD Structural wood sheathing directly applied or 3-5-2 oc purlins. |
| BOT CHORD 2x6 SP No.2 | BOT CHORD Rigid ceiling directly applied or 5-10-11 oc bracing. |
| WEBS 2x4 SP No.3 | WEBS 1 Row at midpt 7-19, 10-19 |

REACTIONS. (size) 2=0-3-8, 19=(0-3-8 + bearing block) (req. 0-4-14), 13=0-3-8
Max Horz 2=155(LC 25)
Max Uplift 2=1027(LC 8), 19=3207(LC 5), 13=549(LC 9)
Max Grav 2=1459(LC 19), 19=4142(LC 1), 13=797(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=2439/1819, 3-4=2289/1765, 4-5=2087/1674, 5-6=1191/968, 6-7=1191/968,
7-9=1319/1758, 9-10=1319/1758, 11-12=980/860, 12-13=1125/882
BOT CHORD 2-24=1567/2071, 23-24=1439/1918, 21-23=1587/2087, 19-21=144/256,
15-16=617/788, 13-15=705/948
WEBS 4-24=465/688, 4-23=282/278, 5-23=52/320, 5-21=1154/901, 6-21=483/411,
7-21=1528/2007, 7-19=2477/1919, 9-19=504/427, 10-19=2265/1822, 10-16=629/835,
11-16=972/734, 11-15=508/695

- NOTES-**
- 2x6 SP No.2 bearing block 12" long at jt. 19 attached to front face with 3 rows of 10d (0.131"x3") nails spaced 3" o.c. 12 Total fasteners. Bearing is assumed to be SP No.2.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCp=0.18; MWFRS (envelope) gable end zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=1027, 19=3207, 13=549.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 149 lb down and 148 lb up at 7-0-0, 149 lb down and 145 lb up at 9-0-12, 149 lb down and 145 lb up at 11-0-12, 149 lb down and 145 lb up at 13-0-12, 149 lb down and 145 lb up at 15-0-12, 149 lb down and 145 lb up at 17-0-12, 149 lb down and 145 lb up at 19-0-12, 149 lb down and 134 lb up at 20-8-0, 149 lb down and 145 lb up at 22-3-4, 149 lb down and 145 lb up at 24-3-4, 149 lb down and 145 lb up at 26-3-4, 149 lb down and 145 lb up at 28-3-4, 149 lb down and 145 lb up at 30-3-4, and 149 lb down and 145 lb up at 32-3-4, and 229 lb down and 287 lb up at 34-4-0 on top chord, and 336 lb down and 391 lb up at 7-0-0, 86 lb down and 86 lb up at 9-0-12, 86 lb down and 86 lb up at 11-0-12, 86 lb down and 86 lb up at 13-0-12, 86 lb down and 86 lb up at 15-0-12, 86 lb down and 86 lb up at 17-0-12, 86 lb down and 86 lb up at 19-0-12, 86 lb down and 86 lb up at 20-8-0, 86 lb down and 86 lb up at 22-3-4, 86 lb down and 86 lb up at 26-3-4, 86 lb down and 86 lb up at 28-3-4, 86 lb down and 86 lb up at 30-3-4, and 86 lb down and 86 lb up at 32-3-4, and 336 lb down and 391 lb up at 34-3-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of Contractor on page 2



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | |
|--------------------------|-------|------------|-----|-----|----------------------------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV |
| 2435655 | T04 | Hip Girder | 1 | 1 | T20989251 |
| Job Reference (optional) | | | | | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:20 2020 Page 2
ID:1bYwwjYqlpHfiMFFctmROVywFXb-Nfov8AUaay0KjgU8hy70qVDN87?ql06jGSY2EqyowoD

NOTES-

9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 4-11=-54, 11-14=-54, 2-13=-20

Concentrated Loads (lb)

Vert: 24=-336(B) 4=-109(B) 21=-64(B) 6=-109(B) 7=-109(B) 9=-109(B) 11=-182(B) 15=-336(B) 29=-109(B) 30=-109(B) 31=-109(B) 32=-109(B) 33=-109(B) 34=-109(B) 35=-109(B) 36=-109(B) 37=-109(B) 38=-109(B) 39=-64(B) 40=-64(B) 41=-64(B) 42=-64(B) 43=-64(B) 44=-64(B) 45=-64(B) 46=-64(B) 47=-64(B) 48=-64(B) 49=-64(B)



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

| | | | | | | |
|----------------|--------------|-------------------|----------|----------|--|-----------|
| Job 2435655 | Truss T05 | Truss Type Hip | Qty 2 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV Job Reference (optional) | T20989252 |
|----------------|--------------|-------------------|----------|----------|--|-----------|


Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:22 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-K1wfYsWr6ZG1yzeWpN9UvwshxZ8DrJ0jm19ljyowoB

| | | | | | | | | | |
|-------|--------|--------|--------|--------|---------|--------|---------|--------|---------|
| 1-6-0 | 4-11-4 | 9-0-0 | 14-6-2 | 20-8-0 | 26-9-15 | 32-4-0 | 36-4-12 | 41-4-0 | 42-10-0 |
| 1-6-0 | 4-11-4 | 4-0-12 | 5-6-1 | 6-1-14 | 6-1-14 | 5-6-1 | 4-0-12 | 4-11-4 | 1-6-0 |

Scale = 1:72.2



| | | | |
|----------------------|-----------------|---|-----------|
| Plate Offsets (X,Y)~ | | [2:0-1-8,0-1-8], [4:0-3-0,0-1-12], [9:0-3-0,0-1-12], [11:0-1-8,0-1-8] | |
| LOADING (psf) | SPACING- | 2-0-0 | CSI. |
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.42 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.96 |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.36 |
| BCDL 10.0 | Code | FBC2017/TPI2014 | Matrix-MS |
| DEFL. | in (loc) | l/defl | L/d |
| Vert(LL) | -0.28 13-15 | >999 | 240 |
| Vert(CT) | -0.54 13-15 | >921 | 180 |
| Horz(CT) | 0.16 11 | n/a | n/a |
| PLATES | GRIP | | |
| MT20 | 244/190 | | |
| Weight: 219 lb | | FT = 20% | |

| | |
|-----------------------|---|
| LUMBER- | BRACING- |
| TOP CHORD 2x4 SP No.2 | TOP CHORD Structural wood sheathing directly applied or 3-2-2 oc purlins. |
| BOT CHORD 2x4 SP No.2 | BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing. |
| WEBS 2x4 SP No.3 | WEBS 1 Row at midpt 5-18, 8-13 |

| | |
|------------|--|
| REACTIONS. | (size) 2=0-3-8, 11=0-3-8 |
| | Max Horz 2=191(LC 11) |
| | Max Uplift 2=643(LC 12), 11=643(LC 13) |
| | Max Grav 2=1610(LC 1), 11=1610(LC 1) |

| | |
|-----------|---|
| FORCES. | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |
| TOP CHORD | 2-3=-2645/1239, 3-4=-2419/1159, 4-5=-2060/1057, 5-6=-2877/1447, 6-8=-2877/1447, 8-9=-2060/1057, 9-10=-2419/1159, 10-11=-2645/1239 |
| BOT CHORD | 2-18=-942/2236, 16-18=-1119/2701, 15-16=-1244/2973, 13-15=-1121/2701, 11-13=-955/2236 |
| WEBS | 3-18=-334/244, 4-18=-407/956, 5-18=-964/535, 5-16=-161/397, 8-15=-161/397, 8-13=-964/535, 9-13=-407/956, 10-13=-333/244 |

- NOTES-
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCp=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=643, 11=643.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

MiTek
6904 Parke East Blvd.
Tampa, FL 33610


| | | | | | | |
|---|--------------|-------------------|----------|----------|----------------------------|-----------|
| Job 2435655 | Truss T06 | Truss Type Hip | Qty 2 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV | T20989253 |
| Builders FirstSource, Jacksonville, FL - 32244, | | | | | | |

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:23 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-oEU1mBXTtOua7DiN4hjS7r?vLwEyla9yQmjr9yowoA

1-6-0 5-11-7 11-0-0 17-6-13 23-9-3 30-4-0 35-4-9 41-4-0 42-10-0
1-6-0 5-11-7 5-0-9 6-6-13 6-2-6 6-6-13 5-0-9 5-11-7 1-6-0

Scale = 1:72.2



| | |
|-----------------------|---|
| Plate Offsets (X,Y) - | [2:0-6-0,0-0-3], [4:0-4-0,0-2-4], [8:0-4-0,0-2-4], [10:0-6-0,0-0-3] |
|-----------------------|---|

| | | | | | | | | | |
|---------------|----------------------|-------|-----------|----------|-------------|--------|-----|----------------|----------|
| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.52 | Vert(LL) | -0.27 15-17 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.84 | Vert(CT) | -0.53 15-17 | >942 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.36 | Horz(CT) | 0.14 10 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | Weight: 227 lb | FT = 20% |

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
14-16: 2x4 SP M 31
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-3-11 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-1-5 oc bracing.
WEBS 1 Row at midpt 5-17, 7-13

REACTIONS. (size) 2=0-3-8, 10=0-3-8
Max Horz 2=-228(LC 10)
Max Uplift 2=639(LC 12), 10=639(LC 13)
Max Grav 2=1610(LC 1), 10=1610(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2645/1198, 3-4=-2289/1116, 4-5=-1929/1023, 5-7=-2435/1248, 7-8=-1929/1023,
8-9=-2289/1116, 9-10=-2645/1198
BOT CHORD 2-18=-895/2221, 17-18=-895/2221, 15-17=-933/2386, 13-15=-934/2386, 12-13=-908/2221,
10-12=-908/2221
WEBS 3-17=-491/295, 4-17=-350/850, 5-17=-736/427, 5-15=-91/296, 7-15=-91/296,
7-13=-736/427, 8-13=-350/850, 9-13=-490/296

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=639, 10=639.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989254 |
| 2435655 | T07 | Hip | 1 | 1 | Job Reference (optional) | |


Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:24 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-GQ1PzXX5eAWCHovwoCy?LO7FkjhfhJA4WGNbyowo9



Scale = 1:73.4



| | |
|-----------------------|---|
| Plate Offsets (X,Y)-- | [2:0-6-0,0-0-3], [5:0-6-0,0-2-4], [7:0-6-0,0-2-4], [10:0-6-0,0-0-3] |
|-----------------------|---|

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | I/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|-------------|--------|-----|----------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.74 | Vert(LL) | -0.20 13-15 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.70 | Vert(CT) | -0.38 13-15 | >999 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.76 | Horz(CT) | 0.13 10 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | Weight: 231 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-2-4 oc bracing.

REACTIONS.

(size) 2=0-3-8, 10=0-3-8
Max Horz 2=264(LC 10)
Max Uplift 2=635(LC 12), 10=635(LC 13)
Max Grav 2=1610(LC 1), 10=1610(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2645/1181, 3-5=-2168/1059, 5-6=-2105/1138, 6-7=-2105/1138, 7-9=-2168/1059,
9-10=-2645/1181
BOT CHORD 2-18=-890/2220, 17-18=-890/2220, 15-17=-600/1796, 13-15=-602/1796, 12-13=-890/2220,
10-12=-890/2220
WEBS 3-18=0/258, 3-17=-622/365, 5-17=-139/516, 5-15=-346/560, 6-15=-475/362,
7-15=-346/560, 7-13=-139/516, 9-13=-622/365, 9-12=0/258

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are 3x6 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=635, 10=635.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | |
|--------------------------|---------------|-------------------|----------|----------|---|
| Job 2435655 | Truss T07T | Truss Type Hip | Qty 1 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV T20989255 |
| Job Reference (optional) | | | | | |


Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:25 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-kcboBtYjPUecqRM5UVjBXyWl8fZQ3ESPkFp1yowo8



Scale = 1:75.8



| | |
|-----------------------|--|
| Plate Offsets (X,Y)-- | [2:0-6-0,0-0-4], [3:0-3-0,0-3-0], [4:0-6-0,0-2-4], [7:0-3-0,0-1-12], [8:0-3-0,0-3-0], [10:0-1-8,0-1-8], [11:0-6-0,0-0-3], [14:0-5-4,0-0-0], [16:0-2-8,0-3-0] |
|-----------------------|--|


| | | | | | | | | | |
|---------------|-----------------|-----------------|-----------|----------|-------------|--------|-----|----------------|----------|
| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.76 | Vert(LL) | -0.26 15-16 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.66 | Vert(CT) | -0.51 15-16 | >969 | 180 | MT20HS | 187/143 |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.93 | Horz(CT) | 0.25 11 | n/a | n/a | | |
| BCDL 10.0 | Code | FBC2017/TPI2014 | Matrix-MS | | | | | Weight: 261 lb | FT = 20% |

| | |
|--|---|
| LUMBER- | BRACING- |
| TOP CHORD 2x4 SP No.2 | TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins. |
| BOT CHORD 2x4 SP No.2 *Except* | BOT CHORD Rigid ceiling directly applied or 5-8-2 oc bracing. |
| 6-17: 2x4 SP No.3, 14-16,9-13: 2x4 SP M 31 | WEBS 1 Row at midpt 5-16 |
| WEBS 2x4 SP No.3 *Except* | |
| 10-14: 2x4 SP No.2 | |

REACTIONS. (size) 2=0-3-8, 11=0-3-8
Max Horz 2=264(LC 10)
Max Uplift 2=635(LC 12), 11=635(LC 13)
Max Grav 2=1610(LC 1), 11=1610(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2618/1169, 3-4=-2157/1066, 4-5=-2093/1130, 5-6=-2138/1120, 6-7=-2143/1119,
7-8=-3362/1639, 8-9=-3302/1470, 9-10=-4799/2078, 10-11=-2640/1174
BOT CHORD 2-21=-866/2189, 20-21=-867/2188, 18-20=-598/1790, 6-16=-293/256, 15-16=-692/2038,
14-15=-1888/4581, 13-14=-520/1292, 9-14=-413/1066, 11-13=-908/2184
WEBS 3-21=0/266, 3-20=-611/357, 4-20=-160/527, 4-18=-336/562, 5-18=-518/348,
16-18=-725/2012, 7-16=-420/754, 7-15=-613/1226, 8-15=-393/331, 9-15=-1783/797,
10-14=-1472/3580, 10-13=-2048/857

- NOTES-
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=635, 11=635.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



| | | | | | | |
|---------|-------|------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989256 |
| 2435655 | T08 | Hip | 1 | 1 | Job Reference (optional) | |


Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:27 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-g?YcZax5uK3IWUcwlfcz0ebyKju3Glt1kw_wyowo6



Scale = 1:73.4



| | | | | | | |
|-----------------------|-------|--------|--------|--------|---------|--------|
| Plate Offsets (X,Y) - | 7-9-1 | 15-0-0 | 20-8-0 | 26-4-0 | 33-6-15 | 41-4-0 |
| | 7-9-1 | 7-2-15 | 5-8-0 | 5-8-0 | 7-2-15 | 7-9-1 |

| | | | | | | | | | |
|---------------|----------------------|-------|-----------|----------|-------------|--------|-----|----------------|----------|
| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | I/defl | L/d | PLATES | GRIP |
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.73 | Vert(LL) | -0.15 15-16 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.74 | Vert(CT) | -0.29 12-14 | >999 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.57 | Horz(CT) | 0.13 10 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | Weight: 241 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-1-2 oc bracing.
WEBS 1 Row at midpt 3-16, 6-15, 9-14

REACTIONS.

(size) 2=0-3-8, 10=0-3-8
Max Horz 2=300(LC 10)
Max Uplift 2=630(LC 12), 10=630(LC 13)
Max Grav 2=1610(LC 1), 10=1610(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=2601/1147, 3-5=2035/1008, 5-6=1802/1013, 6-7=1802/1013, 7-9=2035/1008, 9-10=2601/1147
BOT CHORD 2-18=868/2170, 16-18=868/2170, 15-16=507/1666, 14-15=508/1666, 12-14=842/2170, 10-12=842/2170
WEBS 3-18=0/320, 3-16=728/430, 5-16=182/548, 5-15=279/392, 6-15=339/266, 7-15=279/392, 7-14=182/548, 9-14=728/431, 9-12=0/320

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCp=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are 3x6 MT20 unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=630, 10=630.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610


| | | | | | | |
|---------|-------|------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989257 |
| 2435655 | T08T | Hip | 1 | 1 | Job Reference (optional) | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:28 2020 Page 1
ID:1bYwwjYqtpHfMFFctmROVywFXb-8BHwpvacIP0Bhu5g9dGu9BYobMfWdShu5hUTVMYowos5



Scale = 1:81.5



| | |
|----------------------|---|
| Plate Offsets (X,Y)- | [2:0-6-0,0-0-3], [3:0-4-0,0-3-0], [4:0-6-0,0-2-4], [6:0-3-0,0-1-12], [7:0-2-12,0-3-4], [9:0-1-4,0-1-8], [10:0-6-0,0-0-3], [13:0-5-4,0-0-0], [15:0-2-8,0-2-12] |
|----------------------|---|

| | | | | | | | | | |
|---------------|----------------------|-------|-----------|----------|-------------|--------|-----|----------------|----------|
| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.78 | Vert(LL) | -0.24 16 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.77 | Vert(CT) | -0.47 14-15 | >999 | 180 | MT20HS | 187/143 |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.82 | Horz(CT) | 0.26 10 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | Weight: 262 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
6-17: 2x4 SP No.3, 13-15,8-12: 2x4 SP M 31
WEBS 2x4 SP No.3 *Except*
9-13: 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 5-8-7 oc bracing. Except:
10-0-0 oc bracing: 15-17
WEBS 1 Row at midpt 3-19, 5-18, 5-15, 7-15, 8-14

REACTIONS.

(size) 2=0-3-8, 10=0-3-8
Max Horz 2=301(LC 10)
Max Uplift 2=560(LC 12), 10=558(LC 13)
Max Grav 2=1618(LC 1), 10=1625(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2599/1133, 3-4=-2044/1009, 4-5=-1820/1006, 5-6=-1899/1001, 6-7=-2294/1075,
7-8=-3157/1369, 8-9=-4859/2039, 9-10=-2666/1150
BOT CHORD 2-21=-813/2162, 19-21=-814/2156, 18-19=-501/1677, 6-15=-307/795, 14-15=-1009/2716,
13-14=-1874/4667, 12-13=-503/1305, 8-13=-394/1096, 10-12=-887/2204
WEBS 3-21=0/324, 3-19=-716/431, 4-19=-200/565, 4-18=-272/405, 5-18=-508/293,
15-18=-538/1749, 7-15=-999/508, 7-14=-129/571, 8-14=-1993/882, 9-13=-1442/3631,
9-12=-2069/829

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl.,
GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions
shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide
will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb)
2=560, 10=558.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989258 |
| 2435655 | T09 | Hip | 1 | 1 | Job Reference (optional) | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:29 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVYwFXb-cOr1FbETj92l2gsjLn7iO5ydyQMz22KLD12pyow4

| | | | | | | | | |
|-------|-------|--------|--------|--------|--------|---------|--------|---------|
| 1-6-0 | 5-7-5 | 11-1-0 | 17-0-0 | 24-4-0 | 30-3-0 | 35-8-11 | 41-4-0 | 42-10-0 |
| 1-6-0 | 5-7-5 | 5-5-11 | 5-11-0 | 7-4-0 | 5-11-0 | 5-5-11 | 5-7-5 | 1-6-0 |

Scale = 1:73.4




Plate Offsets (X,Y)-- [2:0-6-0,0-0-3], [6:0-4-0,0-2-4], [7:0-6-0,0-2-4], [11:0-6-0,0-0-3]

| LOADING (psf) | SPACING- | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-----------|----------|-------------|--------|-----|----------------|----------|
| TCLL 20.0 | Plate Grip DOL 1.25 | TC 0.89 | Vert(LL) | -0.29 16-18 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL 1.25 | BC 0.92 | Vert(CT) | -0.53 13-15 | >938 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr YES | WB 0.49 | Horz(CT) | 0.13 11 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | Matrix-MS | | | | | Weight: 241 lb | FT = 20% |

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 1 Row at midpt 5-16, 7-16, 8-15

REACTIONS. (size) 2=0-3-8, 11=0-3-8
Max Horz 2=337(LC 10)
Max Uplift 2=625(LC 12), 11=625(LC 13)
Max Grav 2=1610(LC 1), 11=1610(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2647/1163, 3-5=-2483/1155, 5-6=-1885/972, 6-7=-1577/906, 7-8=-1903/972,
8-10=-2499/1155, 10-11=-2647/1163
BOT CHORD 2-18=-942/2419, 16-18=-710/2030, 15-16=-416/1593, 13-15=-670/1923, 11-13=-883/2229
WEBS 3-18=-318/261, 5-18=-172/522, 5-16=-654/412, 6-16=-229/672, 7-15=-254/775,
8-15=-653/412, 8-13=-172/520, 10-13=-318/262

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCPi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=625, 11=625.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

MiTek
6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989259 |
| 2435655 | T09T | Hip | 1 | 1 | Job Reference (optional) | |


Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:30 2020 Page 1

ID:1bYwwjYqtpHfMFFctmROVywFXb-5aPhEbcE0HvwCF3H2JMEce7Z9Is5INBZ?zabFyowo3

| | | | | | | | | | | |
|-------|-------|--------|--------|--------|--------|---------|--------|---------|--------|---------|
| 1-6-0 | 5-7-5 | 11-1-0 | 17-0-0 | 24-4-0 | 27-4-0 | 32-10-0 | 38-0-8 | 39-5-12 | 41-4-0 | 42-10-0 |
| 1-6-0 | 5-7-5 | 5-5-11 | 5-11-0 | 7-4-0 | 3-0-0 | 5-6-0 | 5-2-8 | 1-5-4 | 1-10-4 | 1-6-0 |

Scale = 1:76.8



| | | | | | | | | | |
|---------------|----------------------|-------|-----------|----------|-------------|--------|-----|----------------|----------|
| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.88 | Vert(LL) | -0.31 20-22 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.91 | Vert(CT) | -0.57 20-22 | >866 | 180 | MT20HS | 187/143 |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 1.00 | Horz(CT) | 0.26 12 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | |
| | | | | | | | | Weight: 271 lb | FT = 20% |

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
 8-18: 2x4 SP No.3, 15-17, 10-14: 2x4 SP M 31
WEBS 2x4 SP No.3 *Except*
 11-15: 2x4 SP No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied or 5-7-15 oc bracing.
WEBS 1 Row at midpt 5-20, 7-20, 7-19, 10-16

REACTIONS. (size) 2=0-3-8, 12=0-3-8
 Max Horz 2=337(LC 10)
 Max Uplift 2=625(LC 12), 12=625(LC 13)
 Max Grav 2=1610(LC 1), 12=1610(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=2646/1163, 3-5=2475/1155, 5-6=1870/971, 6-7=1558/906, 7-8=2268/1218,
 8-9=2337/1108, 9-10=3069/1338, 10-11=4817/2033, 11-12=2636/1141
BOT CHORD 2-22=942/2368, 20-22=709/1979, 19-20=417/1542, 8-17=272/234, 16-17=968/2626,
 15-16=1901/4663, 14-15=492/1287, 10-15=381/1089, 12-14=878/2178
WEBS 3-22=318/261, 5-22=173/519, 5-20=652/413, 6-20=226/638, 7-19=384/155,
 17-19=389/1547, 7-17=589/1269, 9-17=885/442, 9-16=139/536, 10-16=2075/949,
 11-15=1436/3602, 11-14=2040/809

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCp=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=625, 12=625.



Joaquin Velez PE No.68182
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
 Tampa, FL 33610

| | | | | | | |
|---------|-------|----------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989260 |
| 2435655 | T10 | Piggyback Base | 6 | 1 | Job Reference (optional) | |


Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:32 2020 Page 1

ID:1bYwwYqtpHfMFFcmROVywFXb-1yWRfGe6meXd9WPROTLqJ1jXjz_JZFmU0JShf7yowo1

1-6-0 5-7-5 11-1-0 17-0-0 24-4-0 27-4-0 32-10-0 38-0-8 39-5-12 41-4-0 42-10-0
1-6-0 5-7-5 5-5-11 5-11-0 7-4-0 3-0-0 5-6-0 5-2-8 1-5-4 1-10-4 1-6-0

Scale = 1:76.8



| LOADING (psf) | | SPACING- | | CSI. | | DEFL. | | PLATES | | GRIP | |
|---------------|-------|----------------------|------|-----------|------|----------|----------------------|--------|--|----------------|----------|
| TCLL | 20.0 | Plate Grip DOL | 1.25 | TC | 0.51 | Vert(LL) | -0.31 20-22 >999 240 | MT20 | | 244/190 | |
| TCDL | 7.0 | Lumber DOL | 1.25 | BC | 0.91 | Vert(CT) | -0.57 20-22 >872 180 | MT20HS | | 187/143 | |
| BCLL | 0.0 * | Rep Stress Incr | YES | WB | 0.81 | Horz(CT) | 0.26 12 n/a n/a | | | | |
| BCDL | 10.0 | Code FBC2017/TP12014 | | Matrix-MS | | | | | | Weight: 271 lb | FT = 20% |

| LUMBER- | | BRACING- | |
|-----------|---|-----------|--|
| TOP CHORD | 2x4 SP No.2 *Except* 6-7: 2x4 SP M 31 | TOP CHORD | Structural wood sheathing directly applied or 2-2-15 oc purlins, except |
| BOT CHORD | 2x4 SP No.2 *Except* 8-18: 2x4 SP No.3, 15-17,10-14: 2x4 SP M 31 | BOT CHORD | 2-0-0 oc purlins (5-7-13 max.): 6-7. |
| WEBS | 2x4 SP No.3 *Except* 11-15: 2x4 SP No.2 | WEBS | Rigid ceiling directly applied or 5-7-15 oc bracing. 1 Row at midpt 5-20, 7-20, 7-19, 7-17, 10-16 |

| REACTIONS. | |
|------------|-----------------------------|
| (size) | 2=0-3-8, 12=0-3-8 |
| Max Horz | 2=337(LC 10) |
| Max Uplift | 2=625(LC 12), 12=625(LC 13) |
| Max Grav | 2=1610(LC 1), 12=1610(LC 1) |

| FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. | |
|--|--|
| TOP CHORD | 2-3=-2646/1163, 3-5=-2475/1155, 5-6=-1870/971, 6-7=-1558/906, 7-8=-2270/1219, 8-9=-2338/1108, 9-10=-3069/1338, 10-11=-4817/2033, 11-12=-2636/1141 |
| BOT CHORD | 2-22=-942/2368, 20-22=-709/1979, 19-20=-416/1542, 8-17=-274/236, 16-17=-968/2626, 15-16=-1902/4663, 14-15=-492/1287, 10-15=-381/1089, 12-14=-878/2178 |
| WEBS | 3-22=-319/261, 5-22=-173/519, 5-20=-651/413, 6-20=-226/637, 7-19=-384/155, 17-19=-389/1546, 7-17=-592/1272, 9-17=-885/442, 9-16=-139/536, 10-16=-2075/949, 11-15=-1436/3602, 11-14=-2040/809 |

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCp=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=625, 12=625.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




| | | | | | | |
|---------|-------|---------------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989261 |
| 2435655 | T11 | Roof Special Girder | 1 | 1 | Job Reference (optional) | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:33 2020 Page 1

ID:1bYwwjYqtpHfIMFFctmROVywFXb-V94pscekXxTng_dyBs3sEFhnNQullRdFzCEBayowo0



| LOADING (psf) | | SPACING- | | CSI. | | DEFL. | | PLATES | | GRIP | |
|---------------|-------|----------------------|------|-----------|------|----------|----------------------|--------|--|----------------|----------|
| TCLL | 20.0 | Plate Grip DOL | 1.25 | TC | 0.62 | Vert(LL) | 0.09 10-12 >999 240 | MT20 | | 244/190 | |
| TCDL | 7.0 | Lumber DOL | 1.25 | BC | 0.57 | Vert(CT) | -0.15 10-12 >999 180 | | | | |
| BCLL | 0.0 * | Rep Stress Incr | NO | WB | 0.59 | Horz(CT) | 0.03 8 n/a n/a | | | | |
| BCDL | 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | | |
| | | | | | | | | | | Weight: 163 lb | FT = 20% |


| LUMBER- | | BRACING- | |
|-----------|----------------------|-----------|---|
| TOP CHORD | 2x4 SP No.2 | TOP CHORD | Structural wood sheathing directly applied or 4-0-7 oc purlins, except end verticals. |
| BOT CHORD | 2x6 SP No.2 *Except* | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing, Except: |
| | 8-11: 2x6 SP M 26 | | 8-9-15 oc bracing: 2-12. |
| WEBS | 2x4 SP No.3 *Except* | WEBS | 1 Row at midpt 6-8 |
| | 8-13: 2x6 SP No.2 | | |

| REACTIONS. | |
|------------|----------------------------|
| (size) | 2=0-3-8, 8=0-3-8 |
| Max Horz | 2=283(LC 8) |
| Max Uplift | 2=423(LC 8), 8=1087(LC 9) |
| Max Grav | 2=1100(LC 1), 8=2270(LC 1) |

| FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. | |
|--|--|
| TOP CHORD | 2-3=-1705/616, 3-4=-1538/592, 4-5=-2016/851, 5-6=-1665/658 |
| BOT CHORD | 2-12=-697/1443, 10-12=-415/1049, 9-10=-686/1577, 8-9=-686/1577 |
| WEBS | 3-12=-318/290, 4-12=-219/547, 4-10=-575/1233, 5-10=-1179/575, 6-10=-433/653, 6-9=-350/894, 6-8=-1921/822 |

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=423, 8=1087.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 153 lb down and 144 lb up at 23-2-12 on top chord, and 1342 lb down and 629 lb up at 21-8-12, and 89 lb down and 86 lb up at 23-2-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

| LOAD CASE(S) Standard | |
|---|--|
| 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25 | |
| Uniform Loads (plf) | |
| Vert: 1-4=-54, 4-5=-54, 5-7=-54, 2-8=-20 | |
| Concentrated Loads (lb) | |
| Vert: 16=-123(F) 19=-1342(F) 20=-64(F) | |




Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

| | | | | | | |
|----------------|--------------|----------------------|----------|----------|----------------------------|-----------|
| Job 2435655 | Truss T12 | Truss Type Common | Qty 4 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV | T20989262 |
|----------------|--------------|----------------------|----------|----------|----------------------------|-----------|

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:33 2020 Page 1
ID:1bYwwjYqtpHfMFFctmROVywFXb-V94pscekXxfTng_dyBs3sEFIRNU4IIKdFzCEBayowo0



Scale = 1:23.2

Plate Offsets (X,Y) - [4:0-2-8, Edge]

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in | (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|-------|-------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.32 | Vert(LL) | 0.05 | 5-8 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.30 | Vert(CT) | -0.05 | 5-8 | >999 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.09 | Horz(CT) | 0.00 | 4 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | | |
| | | | | | | | | | Weight: 40 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-4-8 oc bracing.

REACTIONS.

(size) 4=0-3-8, 2=0-3-8
Max Horz 2=112(LC 9)
Max Uplift 4=138(LC 13), 2=195(LC 12)
Max Grav 4=376(LC 1), 2=469(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=483/605, 3-4=480/602
BOT CHORD 2-5=440/362, 4-5=440/362
WEBS 3-5=377/235

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCCL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 4=138, 2=195.



Joaquín Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|------------------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989263 |
| 2435655 | T12G | Common Supported Gable | 1 | 1 | Job Reference (optional) | |

Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:34 2020 Page 1
ID:1bYwwjYqtpHfMFctmROVywFXb-zLeB4yfMHFnKPPzqWuNIPSozsmzt1LinUdxok0yowo?



Scale = 1:23.1




Plate Offsets (X,Y)-- [2:0-3-8,Edge], [8:0-3-8,Edge]

| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in | (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|----------|----------|-------|-------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.15 | Vert(LL) | -0.00 | 9 | n/r | 120 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.06 | Vert(CT) | -0.01 | 9 | n/r | 120 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.04 | Horz(CT) | 0.00 | 8 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-S | | | | | | Weight: 51 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.


- All bearings 10-4-0.
(b) - Max Horz 2--111(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2 except 8--108(LC 13), 12--123(LC 12), 10--126(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 2, 8, 11, 12, 10

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 8=108, 12=123, 10=126.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---|--------------|------------------------|----------|----------|----------------------------|--------------------------|
| Job 2435655 | Truss T13 | Truss Type Half Hip | Qty 1 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV | T20989264 |
| Builders FirstSource, Jacksonville, FL - 32244, | | | | | | Job Reference (optional) |

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:35 2020 Page 1
ID:1bYwwjYqtpHfMFFctmROVywFXb-RXCaHlg72ZvB0z704buXxfl2oA7smlpwihhLGSyowo_



Scale = 1:28.1

| Plate Offsets (X,Y)-- [3:0-5-8,0-2-0], [5:0-1-12,0-1-8] | | | | | | | | | |
|---|--|----------------------|--|-----------|--|------------------------------|--|---------------|----------|
| LOADING (psf) | | SPACING- 2-0-0 | | CSI. | | DEFL. in (loc) l/defl L/d | | PLATES GRIP | |
| TCLL 20.0 | | Plate Grip DOL 1.25 | | TC 0.52 | | Vert(LL) 0.10 6-10 >999 240 | | MT20 | 244/190 |
| TCDL 7.0 | | Lumber DOL 1.25 | | BC 0.47 | | Vert(CT) -0.16 6-10 >768 180 | | | |
| BCLL 0.0 * | | Rep Stress Incr YES | | WB 0.22 | | Horz(CT) 0.01 2 n/a n/a | | | |
| BCDL 10.0 | | Code FBC2017/TPI2014 | | Matrix-MS | | | | Weight: 58 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except*
5-7: 2x6 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 5=0-3-8
Max Horz 2=236(LC 12)
Max Uplift 2=180(LC 12), 5=173(LC 12)
Max Grav 2=455(LC 1), 5=350(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-359/90
BOT CHORD 2-6=-158/264, 5-6=-159/272
WEBS 3-6=-19/279, 3-5=-487/276

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Provide adequate drainage to prevent water ponding.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=180, 5=173.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCS Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---------|-------|------------|-----|-----|----------------------------|-----------|
| Job | Truss | Truss Type | Qty | Ply | LIPSCOMB EAGLE - LOT 11 FV | T20989265 |
| 2435655 | T14 | Hip Girder | 1 | 1 | Job Reference (optional) | |


Builders FirstSource, Jacksonville, FL - 32244,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:36 2020 Page 1

ID: 1bYwwjYqtpHfMFFctmROVywFXb-vkmyVehdps12e7iCdJPmUltJQaYdVF4xxQvnyowzn



Scale = 1:19.4



| Plate Offsets (X,Y)=- | | [2:0-1-8,0-1-0], [3:0-5-8,0-2-0], [5:0-1-8,0-1-0] | | | | | | | | | |
|-----------------------|--|---|-------|-----------|--|----------|------------|--------|-----|---------------|----------|
| LOADING (psf) | | SPACING- | 2-0-0 | CSI. | | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
| TCLL 20.0 | | Plate Grip DOL | 1.25 | TC 0.15 | | Vert(LL) | 0.01 8 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | | Lumber DOL | 1.25 | BC 0.12 | | Vert(CT) | -0.01 8-11 | >999 | 180 | | |
| BCLL 0.0 * | | Rep Stress Incr | NO | WB 0.04 | | Horz(CT) | -0.00 5 | n/a | n/a | | |
| BCDL 10.0 | | Code FBC2017/TPI2014 | | Matrix-MS | | | | | | Weight: 36 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 5=0-3-8
Max Horz 2=82(LC 25)
Max Uplift 2=278(LC 8), 5=278(LC 9)
Max Grav 2=379(LC 19), 5=380(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-363/325, 3-4=-285/312, 4-5=-365/340
BOT CHORD 2-8=-256/335, 7-8=-261/340, 5-7=-248/329

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=278, 5=278.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 81 lb down and 59 lb up at 3-0-0, and 120 lb down and 137 lb up at 4-3-8 on top chord, and 112 lb down and 80 lb up at 3-0-0, and 112 lb down and 80 lb up at 4-2-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-4=-54, 4-6=-54, 9-12=-20
Concentrated Loads (lb)
Vert: 3=-6(B) 4=-14(B) 8=-19(B) 7=-19(B)



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11,2020



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

| | | | | | | |
|---|--------------|----------------------|----------|----------|----------------------------|---|
| Job 2435655 | Truss T15 | Truss Type Common | Qty 3 | Ply 1 | LIPSCOMB EAGLE - LOT 11 FV | T20989266 |
| Builders FirstSource, Jacksonville, FL - 32244, | | | | | | 8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:36 2020 Page 1 |
| Job Reference (optional) | | | | | | ID:1bYwwjYqtpHfMFFctmROVywFXb-vkmyVehdps12e7iCdJPmUttJAaXxVFY4xxQvnyownz |

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Aug 11 11:57:36 2020 Page 1
ID:1bYwwjYqtpHfMFFctmROVywFXb-vkmyVehdps12e7iCdJPmUttJAaXxVFY4xxQvnyownz



| LOADING (psf) | SPACING- | 2-0-0 | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|----------------------|-------|-----------|----------|-----------|--------|-----|---------------|----------|
| TCLL 20.0 | Plate Grip DOL | 1.25 | TC 0.16 | Vert(LL) | 0.01 6-12 | >999 | 240 | MT20 | 244/190 |
| TCDL 7.0 | Lumber DOL | 1.25 | BC 0.16 | Vert(CT) | -0.01 6-9 | >999 | 180 | | |
| BCLL 0.0 * | Rep Stress Incr | YES | WB 0.06 | Horz(CT) | 0.00 4 | n/a | n/a | | |
| BCDL 10.0 | Code FBC2017/TPI2014 | | Matrix-MS | | | | | Weight: 32 lb | FT = 20% |

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 4=0-3-8
Max Horz 2=-93(LC 10)
Max Uplift 2=-153(LC 12), 4=-153(LC 13)
Max Grav 2=351(LC 1), 4=351(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-302/394, 3-4=-302/394

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCp=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=153, 4=153.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

August 11, 2020



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.




Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Symbols

PLATE LOCATION AND ORIENTATION



* Plate location details available in MITek 20120 software or upon request.

PLATE SIZE


4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



BEARING



Industry Standards:

ANSI/TP1: National Design Specification for Metal

Plate Connected Wood Truss Construction.

DSB-89: Design Standard for Bracing.


Building Component Safety Information,

Guide to Good Practice for Handling,

Installing & Bracing of Metal Plate

Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved



MITek Engineering Reference Sheet: MIL-7473 rev. 5/19/2020

General Safety Notes


Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g., diagonal or X-bracing, is always required. See BCSL.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

AUGUST 1, 2016

T-BRACE / I-BRACE DETAIL WITH 2X BRACE ONLY

MII-T-BRACE 2



MiTek USA, Inc.

ENGINEERED BY
TRENCO
A MiTek Affiliate

MiTek USA, Inc. Page 1 of 1

Note: T-Bracing / I-Bracing to be used when continuous lateral bracing is impractical. T-Brace / I-Brace must cover 90% of web length.

Note: This detail NOT to be used to convert T-Brace / I-Brace webs to continuous lateral braced webs.

Nailing Pattern

| T-Brace size | Nail Size | Nail Spacing |
|--|-------------------|--------------|
| 2x4 or 2x6 or 2x8 | 10d (0.131" X 3") | 6" o.c. |
| Note: Nail along entire length of T-Brace / I-Brace (On Two-Ply's Nail to Both Plies) | | |

Brace Size for One-Ply Truss

Specified Continuous Rows of Lateral Bracing




| Web Size | 1 | 2 |
|------------|-------------|-------------|
| 2x3 or 2x4 | 2x4 T-Brace | 2x4 I-Brace |
| 2x6 | 2x6 T-Brace | 2x6 I-Brace |
| 2x8 | 2x8 T-Brace | 2x8 I-Brace |

Brace Size for Two-Ply Truss

Specified Continuous Rows of Lateral Bracing

| Web Size | 1 | 2 |
|------------|-------------|-------------|
| 2x3 or 2x4 | 2x4 T-Brace | 2x4 I-Brace |
| 2x6 | 2x6 T-Brace | 2x6 I-Brace |
| 2x8 | 2x8 T-Brace | 2x8 I-Brace |

T-Brace / I-Brace must be same species and grade (or better) as web member.



Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 12, 2018


AUGUST 1, 2016

SCAB-BRACE DETAIL

MII-SCAB-BRACE

MiTek USA, Inc.


Page 1 of 1




Note: Scab-Bracing to be used when continuous lateral bracing at midpoint (or T-Brace) is impractical.
Scab must cover full length of web +/- 6".

*** THIS DETAIL IS NOT APPLICABLE WHEN BRACING IS REQUIRED AT 1/3 POINTS OR I-BRACE IS SPECIFIED.

APPLY 2x SCAB TO ONE FACE OF WEB WITH
2 ROWS OF 10d (0.131" X 3") NAILS SPACED 6" O.C.
SCAB MUST BE THE SAME GRADE, SIZE AND
SPECIES (OR BETTER) AS THE WEB.



Scab-Brace must be same species grade (or better) as web member.



Thomas A. Albani PE No. 39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 12, 2018

AUGUST 1, 2016


STANDARD REPAIR TO REMOVE END
VERTICAL (RIBBON NOTCH VERTICAL)

MII-REP05


MiTek USA, Inc. Page 1 of 1




1. THIS IS A SPECIFIC REPAIR DETAIL TO BE USED ONLY FOR ITS ORIGINAL INTENTION. THIS REPAIR DOES NOT IMPLY THAT THE REMAINING PORTION OF THE TRUSS IS UNDAMAGED. THE ENTIRE TRUSS SHALL BE INSPECTED TO VERIFY THAT NO FURTHER REPAIRS ARE REQUIRED. WHEN THE REQUIRED REPAIRS ARE PROPERLY APPLIED, THE TRUSS WILL BE CAPABLE OF SUPPORTING THE LOADS INDICATED.
2. ALL MEMBERS MUST BE RETURNED TO THEIR ORIGINAL POSITIONS BEFORE APPLYING REPAIR AND HELD IN PLACE DURING APPLICATION OF REPAIR.
3. THE END DISTANCE, EDGE DISTANCE, AND SPACING OF NAILS SHALL BE SUCH AS TO AVOID SPLITTING OF THE WOOD.
4. LUMBER MUST BE CUT CLEANLY AND ACCURATELY AND THE REMAINING WOOD MUST BE UNDAMAGED.
5. THIS REPAIR IS TO BE USED FOR SINGLE PLY TRUSSES IN THE 4X ORIENTATION ONLY.
6. CONNECTOR PLATES MUST BE FULLY IMBEDDED AND UNDISTURBED.




REFER TO INDIVIDUAL
TRUSS DESIGN FOR
PLATE SIZES AND
LUMBER GRADES



TRUSSES BUILT
WITH 4x2 MEMBERS



REFER TO INDIVIDUAL
TRUSS DESIGN FOR
PLATE SIZES AND
LUMBER GRADES



TRUSSES BUILT
WITH 4x2 MEMBERS

ATTACH 2x4 SQUASH BLOCK (CUT TO FIT TIGHTLY)
TO BOTH SIDES OF THE TRUSS AS SHOWN WITH
10d (0.131" X 3") NAILS SPACED 3" O.C.



Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:





February 12, 2018

AUGUST 1, 2016

Standard Gable End Detail

MII-GE130-D-SP

MiTek USA, Inc. Page 1 of 2




NOTE:

1. MINIMUM GRADE OF #2 MATERIAL IN THE TOP AND BOTTOM CHORDS.
2. CONNECTION BETWEEN BOTTOM CHORD OF GABLE END TRUSS AND WALL TO BE PROVIDED BY PROJECT ENGINEER OR ARCHITECT.
3. BRACING SHOWN IS FOR INDIVIDUAL TRUSS ONLY. CONSULT BLDG. ARCHITECT OR ENGINEER FOR TEMPORARY AND PERMANENT BRACING OF ROOF SYSTEM.
4. "L" BRACES SPECIFIED ARE TO BE FULL LENGTH. GRADES: 1x4 SRB OR 2x4 STUD OR BETTER WITH ONE ROW OF 10d NAILS SPACED 6" O.C.
5. DIAGONAL BRACE TO BE APPROXIMATELY 45 DEGREES TO ROOF DIAPHRAM AT 4'-0" O.C.
6. CONSTRUCT HORIZONTAL BRACE CONNECTING A 2x6 STUD AND A 2x4 STUD AS SHOWN WITH 16d NAILS SPACED 6" O.C. HORIZONTAL BRACE TO BE LOCATED AT THE MIDSPAN OF THE LONGEST STUD. ATTACH TO VERTICAL STUDS WITH (4) 10d NAILS THROUGH 2x4. (REFER TO SECTION A-A)
7. GABLE STUD DEFLECTION MEETS OR EXCEEDS L/240.
8. THIS DETAIL DOES NOT APPLY TO STRUCTURAL GABLES.
9. DO NOT USE FLAT BOTTOM CHORD GABLES NEXT TO SCISSOR TYPE TRUSSES.
10. SOUTHERN PINE LUMBER DESIGN VALUES ARE THOSE EFFECTIVE 06-01-13 BY SPIB/ALSC.
11. NAILS DESIGNATED 10d ARE (0.131" X 3") AND NAILS DESIGNATED 16d ARE (0.131" X 3.5")

PROVIDE 2x4 BLOCKING BETWEEN THE FIRST TWO TRUSSES AS NOTED. TOENAIL BLOCKING TO TRUSSES WITH (2) - 10d NAILS AT EACH END. ATTACH DIAGONAL BRACE TO BLOCKING WITH (5) - 10d NAILS.

(4) - 8d (0.131" X 2.5") NAILS MINIMUM, PLYWOOD SHEATHING TO 2x4 STD SPF BLOCK




| Minimum Stud Size Species and Grade | Stud Spacing | Without Brace | 1x4 L-Brace | 2x4 L-Brace | DIAGONAL BRACE | 2 DIAGONAL BRACES AT 1/3 POINTS |
|-------------------------------------|--------------|---------------------|-------------|-------------|----------------|---------------------------------|
| | | Maximum Stud Length | | | | |
| 2x4 SP No. 3 / Stud | 12" O.C. | 3-9-13 | 4-1-1 | 5-9-6 | 7-1-3 | 11-5-7 |
| 2x4 SP No. 3 / Stud | 16" O.C. | 3-5-4 | 3-6-8 | 5-0-2 | 6-10-8 | 10-3-13 |
| 2x4 SP No. 3 / Stud | 24" O.C. | 2-9-11 | 2-10-11 | 4-1-1 | 5-7-6 | 8-5-1 |

- * Diagonal braces over 6'-3" require a 2x4 T-Brace attached to one edge. Diagonal braces over 12'-6" require 2x4 I-braces attached to both edges. Fasten T and I braces to narrow edge of diagonal brace with 10d nails 8" o.c., with 3" minimum end distance. Brace must cover 90% of diagonal length.





MAX MEAN ROOF HEIGHT = 30 FEET
CATEGORY II BUILDING
EXPOSURE D
ASCE 7-98, ASCE 7-02, ASCE 7-05 130 MPH
ASCE 7-10 160 MPH
DURATION OF LOAD INCREASE : 1.60

STUD DESIGN IS BASED ON COMPONENTS AND CLADDING.
CONNECTION OF BRACING IS BASED ON MWFRS.




Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 12, 2018



PROVIDE 2x4 BLOCKING BETWEEN THE FIRST TWO TRUSSES AS NOTED. TOENAIL BLOCKING TO TRUSSES WITH (2) - 10d NAILS AT EACH END. ATTACH DIAGONAL BRACE TO BLOCKING WITH (5) - 10d NAILS.

(4) - 8d (0.131" X 2.5") NAILS MINIMUM, PLYWOOD SHEATHING TO 2x4 STD SPF BLOCK



NOTE:


1. MINIMUM GRADE OF #2 MATERIAL IN THE TOP AND BOTTOM CHORDS.
2. CONNECTION BETWEEN BOTTOM CHORD OF GABLE END TRUSS AND WALL TO BE PROVIDED BY PROJECT ENGINEER OR ARCHITECT.
3. BRACING SHOWN IS FOR INDIVIDUAL TRUSS ONLY. CONSULT BLDG. ARCHITECT OR ENGINEER FOR TEMPORARY AND PERMANENT BRACING OF ROOF SYSTEM.
4. "L" BRACES SPECIFIED ARE TO BE FULL LENGTH. GRADES: 1x4 SRB OR 2x4 STUD OR BETTER WITH ONE ROW OF 10d NAILS SPACED 6" O.C.
5. DIAGONAL BRACE TO BE APPROXIMATELY 45 DEGREES TO ROOF DIAPHRAM AT 4'-0" O.C.
6. CONSTRUCT HORIZONTAL BRACE CONNECTING A 2x6 STUD AND A 2x4 STUD AS SHOWN WITH 16d NAILS SPACED 6" O.C. HORIZONTAL BRACE TO BE LOCATED AT THE MIDSPAN OF THE LONGEST STUD. ATTACH TO VERTICAL STUDS WITH (4) 10d NAILS THROUGH 2x4. (REFER TO SECTION A-A)
7. GABLE STUD DEFLECTION MEETS OR EXCEEDS L/240.
8. THIS DETAIL DOES NOT APPLY TO STRUCTURAL GABLES.
9. DO NOT USE FLAT BOTTOM CHORD GABLES NEXT TO SCISSOR TYPE TRUSSES.
10. SOUTHERN PINE LUMBER DESIGN VALUES ARE THOSE EFFECTIVE 06-01-13 BY SPIB/ALSC.
11. NAILS DESIGNATED 10d ARE (0.131" X 3") AND NAILS DESIGNATED 16d ARE (0.131" X 3.5")

| Minimum Stud Size Species and Grade | Stud Spacing | Without Brace | 1x4 L-Brace | 2x4 L-Brace | DIAGONAL BRACE | 2 DIAGONAL BRACES AT 1/3 POINTS |
|-------------------------------------|--------------|---------------|-------------|-------------|----------------|---------------------------------|
| | | | | | | |
| 2x4 SP No. 3 / Stud | 12" O.C. | 4-0-7 | 4-5-6 | 6-3-8 | 8-0-15 | 12-1-6 |
| 2x4 SP No. 3 / Stud | 16" O.C. | 3-8-0 | 3-10-4 | 5-5-6 | 7-4-1 | 11-0-1 |
| 2x4 SP No. 3 / Stud | 24" O.C. | 3-0-10 | 3-1-12 | 4-5-6 | 6-1-5 | 9-1-15 |

- * Diagonal braces over 6'-3" require a 2x4 T-Brace attached to one edge. Diagonal braces over 12'-6" require 2x4 I-braces attached to both edges. Fasten T and I braces to narrow edge of diagonal brace with 10d nails 8" o.c., with 3" minimum end distance. Brace must cover 90% of diagonal length.

MAX MEAN ROOF HEIGHT = 30 FEET
CATEGORY II BUILDING
EXPOSURE B or C
ASCE 7-98, ASCE 7-02, ASCE 7-05 130 MPH
ASCE 7-10 160 MPH
DURATION OF LOAD INCREASE : 1.60

STUD DESIGN IS BASED ON COMPONENTS AND CLADDING.
CONNECTION OF BRACING IS BASED ON MWFRS.




Thomas A. Albani PE No. 39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 12, 2018




JANUARY 6, 2017

Standard Gable End Detail

MII-GE140-001



MiTek USA, Inc. Page 1 of 2




TRUSS GEOMETRY AND CONDITIONS SHOWN ARE FOR ILLUSTRATION ONLY.

SEE INDIVIDUAL MITEK ENGINEERING DRAWINGS FOR DESIGN CRITERIA

PROVIDE 2x4 BLOCKING BETWEEN THE FIRST TWO TRUSSES AS NOTED. TOENAIL BLOCKING TO TRUSSES WITH (2) - 10d NAILS AT EACH END. ATTACH DIAGONAL BRACE TO BLOCKING WITH (5) - 10d NAILS.

(4) - 8d (0.131" X 2.5") NAILS MINIMUM, PLYWOOD SHEATHING TO 2x4 STD DF/SPF BLOCK



NOTE:

1. MINIMUM GRADE OF #2 MATERIAL IN THE TOP AND BOTTOM CHORDS.
2. CONNECTION BETWEEN BOTTOM CHORD OF GABLE END TRUSS AND WALL TO BE PROVIDED BY PROJECT ENGINEER OR ARCHITECT.
3. BRACING SHOWN IS FOR INDIVIDUAL TRUSS ONLY. CONSULT BLDG. ARCHITECT OR ENGINEER FOR TEMPORARY AND PERMANENT BRACING OF ROOF SYSTEM.
4. "L" BRACES SPECIFIED ARE TO BE FULL LENGTH. GRADES: 1x4 SRB OR 2x4 STUD OR BETTER WITH ONE ROW OF 10d NAILS SPACED 6" O.C.
5. DIAGONAL BRACE TO BE APPROXIMATELY 45 DEGREES TO ROOF DIAPHRAM AT 4'-0" O.C.
6. CONSTRUCT HORIZONTAL BRACE CONNECTING A 2x6 STUD AND A 2x4 STUD AS SHOWN WITH 16d NAILS SPACED 6" O.C. HORIZONTAL BRACE TO BE LOCATED AT THE MIDSPAN OF THE LONGEST STUD. ATTACH TO VERTICAL STUDS WITH (4) 10d NAILS THROUGH 2x4. (REFER TO SECTION A-A)
7. GABLE STUD DEFLECTION MEETS OR EXCEEDS L/240.
8. THIS DETAIL DOES NOT APPLY TO STRUCTURAL GABLES.
9. DO NOT USE FLAT BOTTOM CHORD GABLES NEXT TO SCISSOR TYPE TRUSSES.
10. NAILS DESIGNATED 10d ARE (0.131" X 3") AND NAILS DESIGNATED 16d ARE (0.131" X 3.5")

| Minimum Stud Size Species and Grade | Stud Spacing | Without Brace | 1x4 L-Brace | 2x4 L-Brace | DIAGONAL BRACE | 2 DIAGONAL BRACES AT 1/3 POINTS |
|-------------------------------------|--------------|---------------|-------------|-------------|----------------|---------------------------------|
| | | | | | | |
| 2x4 DF/SPF Std/Stud | 12" O.C. | 3-10-1 | 3-11-7 | 5-7-2 | 7-8-2 | 11-6-4 |
| 2x4 DF/SPF Std/Stud | 16" O.C. | 3-3-14 | 3-5-1 | 4-10-2 | 6-7-13 | 9-11-11 |
| 2x4 DF/SPF Std/Stud | 24" O.C. | 2-8-9 | 2-9-8 | 3-11-7 | 5-5-2 | 8-1-12 |

- * Diagonal braces over 6'-3" require a 2x4 T-Brace attached to one edge. Diagonal braces over 12'-6" require 2x4 I-braces attached to both edges. Fasten T and I braces to narrow edge of web with 10d nails 8" o.c., with 3" minimum end distance. Brace must cover 90% of diagonal length.


MAXIMUM WIND SPEED = 140 MPH
MAX MEAN ROOF HEIGHT = 30 FEET
CATEGORY II BUILDING
EXPOSURE B or C
ASCE 7-98, ASCE 7-02, ASCE 7-05
DURATION OF LOAD INCREASE : 1.60

STUD DESIGN IS BASED ON COMPONENTS AND CLADDING.
CONNECTION OF BRACING IS BASED ON MWFRS.





Thomas A. Albani PE No. 39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


January 19, 2018



MiTek USA, Inc.

ENGINEERED BY
TRENCO
A MiTek AffiliateTRUSS GEOMETRY AND CONDITIONS
SHOWN ARE FOR ILLUSTRATION ONLY.12
Varies to Common TrussSEE INDIVIDUAL MITEK ENGINEERING
DRAWINGS FOR DESIGN CRITERIAPROVIDE 2x4 BLOCKING BETWEEN THE FIRST
TWO TRUSSES AS NOTED. TOENAIL BLOCKING
TO TRUSSES WITH (2) - 10d NAILS AT EACH END.
ATTACH DIAGONAL BRACE TO BLOCKING WITH
(5) - 10d NAILS.(4) - 8d (0.131" X 2.5") NAILS MINIMUM, PLYWOOD
SHEATHING TO 2x4 STD SPF BLOCK

Roof Sheathing

Diag. Brace
at 1/3 points
if neededHORIZONTAL BRACE
(SEE SECTION A-A)* - Diagonal Bracing
Refer to Section A-A** - L-Bracing Refer
to Section B-B

NOTE:

1. MINIMUM GRADE OF #2 MATERIAL IN THE TOP AND BOTTOM CHORDS.
2. CONNECTION BETWEEN BOTTOM CHORD OF GABLE END TRUSS AND WALL TO BE PROVIDED BY PROJECT ENGINEER OR ARCHITECT.
3. BRACING SHOWN IS FOR INDIVIDUAL TRUSS ONLY. CONSULT BLDG. ARCHITECT OR ENGINEER FOR TEMPORARY AND PERMANENT BRACING OF ROOF SYSTEM.
4. "L" BRACES SPECIFIED ARE TO BE FULL LENGTH, SPF or SP No.3 OR BETTER WITH ONE ROW OF 10d NAILS SPACED 6" O.C.
5. DIAGONAL BRACE TO BE APPROXIMATELY 45 DEGREES TO ROOF DIAPHRAM AT 4'-0" O.C.
6. CONSTRUCT HORIZONTAL BRACE CONNECTING A 2x6 AND A 2x4 AS SHOWN WITH 16d NAILS SPACED 6" O.C. HORIZONTAL BRACE TO BE LOCATED AT THE MIDSPAN OF THE LONGEST GABLE STUD. ATTACH TO VERTICAL GABLE STUDS WITH (4) 10d NAILS THROUGH 2x4. (REFER TO SECTION A-A)
7. GABLE STUD DEFLECTION MEETS OR EXCEEDS L/240.
8. THIS DETAIL DOES NOT APPLY TO STRUCTURAL GABLES.
9. DO NOT USE FLAT BOTTOM CHORD GABLES NEXT TO SCISSOR TYPE TRUSSES.
10. SOUTHERN PINE LUMBER DESIGN VALUES ARE THOSE EFFECTIVE 06-01-13 BY SPIB/ALSC.
11. NAILS DESIGNATED 10d ARE (0.131" X 3") AND NAILS DESIGNATED 16d ARE (0.131" X 3.5")

| Minimum Stud Size Species and Grade | Stud Spacing | Without Brace | 2x4 L-Brace | DIAGONAL BRACE | 2 DIAGONAL BRACES AT 1/3 POINTS |
|-------------------------------------|--------------|---------------------|-------------|----------------|---------------------------------|
| | | Maximum Stud Length | | | |
| 2x4 SP No. 3 / Stud | 12" O.C. | 3-9-7 | 5-8-8 | 6-11-1 | 11-4-4 |
| 2x4 SP No. 3 / Stud | 16" O.C. | 3-4-12 | 4-11-15 | 6-9-8 | 10-2-3 |
| 2x4 SP No. 3 / Stud | 24" O.C. | 2-9-4 | 4-0-7 | 5-6-8 | 8-3-13 |
| 2x4 SP No. 2 | 12" O.C. | 3-11-13 | 5-8-8 | 6-11-1 | 11-11-7 |
| 2x4 SP No. 2 | 16" O.C. | 3-7-7 | 4-11-5 | 6-11-1 | 10-10-5 |
| 2x4 SP No. 2 | 24" O.C. | 3-1-15 | 4-0-7 | 6-3-14 | 9-5-14 |

- * Diagonal braces over 6'-3" require a 2x4 T-Brace attached to one edge. Diagonal braces over 12'-6" require 2x4 I-braces attached to both edges. Fasten T and I braces to narrow edge of diagonal brace with 10d nails 6" o.c., with 3" minimum end distance. Brace must cover 90% of diagonal length. T or I braces must be 2x4 SPF No. 2 or SP No. 2.

MAX MEAN ROOF HEIGHT = 30 FEET
EXPOSURE D
ASCE 7-10 170 MPH
DURATION OF LOAD INCREASE : 1.60

STUD DESIGN IS BASED ON COMPONENTS AND CLADDING.
CONNECTION OF BRACING IS BASED ON MWFRS.



Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


February 12, 2018

AUGUST 1, 2016

Standard Gable End Detail

MII-GE180-D-SP

MiTek USA, Inc. Page 1 of 2



MiTek USA, Inc.

ENGINEERED BY
TRENCO

A MiTek Affiliate

DIAGONAL BRACE
4'-0" O.C. MAXTypical 2x4 L-Brace Nailed To
2x4 Verticals W/10d Nails spaced 6" o.c.

Vertical Stud

SECTION B-B

TRUSS GEOMETRY AND CONDITIONS
SHOWN ARE FOR ILLUSTRATION ONLY.12
Varies to Common TrussSEE INDIVIDUAL MITEK ENGINEERING
DRAWINGS FOR DESIGN CRITERIA* - Diagonal Bracing
Refer to Section A-A** - L-Bracing Refer
to Section B-B

NOTE:


1. MINIMUM GRADE OF #2 MATERIAL IN THE TOP AND BOTTOM CHORDS.
2. CONNECTION BETWEEN BOTTOM CHORD OF GABLE END TRUSS AND WALL TO BE PROVIDED BY PROJECT ENGINEER OR ARCHITECT.
3. BRACING SHOWN IS FOR INDIVIDUAL TRUSS ONLY. CONSULT BLDG. ARCHITECT OR ENGINEER FOR TEMPORARY AND PERMANENT BRACING OF ROOF SYSTEM.
4. "L" BRACES SPECIFIED ARE TO BE FULL LENGTH, SPF or SP No.3 OR BETTER WITH ONE ROW OF 10d NAILS SPACED 6" O.C.
5. DIAGONAL BRACE TO BE APPROXIMATELY 45 DEGREES TO ROOF DIAPHRAM AT 4'-0" O.C.
6. CONSTRUCT HORIZONTAL BRACE CONNECTING A 2x6 AND A 2x4 AS SHOWN WITH 16d NAILS SPACED 6" O.C. HORIZONTAL BRACE TO BE LOCATED AT THE MIDSPAN OF THE LONGEST GABLE STUD. ATTACH TO VERTICAL GABLE STUDS WITH (4) 10d NAILS THROUGH 2x4. (REFER TO SECTION A-A)
7. GABLE STUD DEFLECTION MEETS OR EXCEEDS $L/240$.
8. THIS DETAIL DOES NOT APPLY TO STRUCTURAL GABLES.
9. DO NOT USE FLAT BOTTOM CHORD GABLES NEXT TO SCISSOR TYPE TRUSSES.
10. SOUTHERN PINE LUMBER DESIGN VALUES ARE THOSE EFFECTIVE 06-01-13 BY SPIB/ALSC.
11. NAILS DESIGNATED 10d ARE (0.131" X 3") AND NAILS DESIGNATED 16d ARE (0.131" X 3.5")

| Minimum Stud Size Species and Grade | Stud Spacing | Without Brace | 2x4 L-Brace | DIAGONAL BRACE | 2 DIAGONAL BRACES AT 1/3 POINTS |
|-------------------------------------|--------------|---------------|-------------|----------------|---------------------------------|
| | | | | | |
| 2x4 SP No. 3 / Stud | 12" O.C. | 3-7-12 | 5-4-11 | 6-2-1 | 10-11-3 |
| 2x4 SP No. 3 / Stud | 16" O.C. | 3-2-8 | 4-8-1 | 6-2-1 | 9-7-7 |
| 2x4 SP No. 3 / Stud | 24" O.C. | 2-7-7 | 3-9-12 | 5-2-13 | 7-10-4 |
| 2x4 SP No. 2 | 12" O.C. | 3-10-0 | 5-4-11 | 6-2-1 | 11-6-1 |
| 2x4 SP No. 2 | 16" O.C. | 3-5-13 | 4-8-1 | 6-2-1 | 10-5-7 |
| 2x4 SP No. 2 | 24" O.C. | 3-0-8 | 3-9-12 | 6-1-1 | 9-1-9 |

- * Diagonal braces over 6'-3" require a 2x4 T-Brace attached to one edge. Diagonal braces over 12'-6" require 2x4 I-braces attached to both edges. Fasten T and I braces to narrow edge of diagonal brace with 10d nails 6in o.c., with 3in minimum end distance. Brace must cover 90% of diagonal length. T or I braces must be 2x4 SPF No. 2 or SP No. 2.

MAX MEAN ROOF HEIGHT = 30 FEET
EXPOSURE D
ASCE 7-10 180 MPH
DURATION OF LOAD INCREASE : 1.60


STUD DESIGN IS BASED ON COMPONENTS AND CLADDING.
CONNECTION OF BRACING IS BASED ON MWFRS.




PROVIDE 2x4 BLOCKING BETWEEN THE FIRST TWO TRUSSES AS NOTED. TOENAIL BLOCKING TO TRUSSES WITH (2) - 10d NAILS AT EACH END. ATTACH DIAGONAL BRACE TO BLOCKING WITH (5) - 10d NAILS.

(4) - 8d (0.131" X 2.5") NAILS MINIMUM, PLYWOOD SHEATHING TO 2x4 STD SPF BLOCK

Roof Sheathing




Diag. Brace at 1/3 points if needed



Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 12, 2018



MiTek USA, Inc.


ENGINEERED BY
TRENCO
 A MiTek Affiliate

MiTek USA, Inc. Page 1 of 1

MAXIMUM WIND SPEED = REFER TO NOTES D AND OR E
 MAX MEAN ROOF HEIGHT = 30 FEET
 MAX TRUSS SPACING = 24" O.C.
 CATEGORY II BUILDING
 EXPOSURE B or C
 ASCE 7-10
 DURATION OF LOAD INCREASE : 1.60

DETAIL IS NOT APPLICABLE FOR TRUSSES
 TRANSFERRING DRAG LOADS (SHEAR TRUSSES).
 ADDITIONAL CONSIDERATIONS BY BUILDING
 ENGINEER/DESIGNER ARE REQUIRED.


- A - PIGGYBACK TRUSS, REFER TO MITEK TRUSS DESIGN DRAWING. SHALL BE CONNECTED TO EACH PURLIN WITH (2) (0.131" X 3.5") TOE-NAILED.
- B - BASE TRUSS, REFER TO MITEK TRUSS DESIGN DRAWING.
- C - PURLINS AT EACH BASE TRUSS JOINT AND A MAXIMUM 24" O.C. UNLESS SPECIFIED CLOSER ON MITEK TRUSS DESIGN DRAWING. CONNECT TO BASE TRUSS WITH (2) (0.131" X 3.5") NAILS EACH.
- D - 2 X X 4'-0" SCAB, SIZE TO MATCH TOP CHORD OF PIGGYBACK TRUSS, MIN GRADE #2, ATTACHED TO ONE FACE, CENTERED ON INTERSECTION, WITH (2) ROWS OF (0.131" X 3") NAILS @ 4" O.C. SCAB MAY BE OMITTED PROVIDED THE TOP CHORD SHEATHING IS CONTINUOUS OVER INTERSECTION AT LEAST 1 FT. IN BOTH DIRECTIONS AND:
1. WIND SPEED OF 115 MPH OR LESS FOR ANY PIGGYBACK SPAN, OR
 2. WIND SPEED OF 116 MPH TO 160 MPH WITH A MAXIMUM PIGGYBACK SPAN OF 12 ft.
- E - FOR WIND SPEEDS BETWEEN 126 AND 160 MPH, ATTACH MITEK 3X8 20 GA Nail-On PLATES TO EACH FACE OF TRUSSES AT 72" O.C. W/ (4) (0.131" X 1.5") NAILS PER MEMBER. STAGGER NAILS FROM OPPOSING FACES. ENSURE 0.5" EDGE DISTANCE. (MIN. 2 PAIRS OF PLATES REQ. REGARDLESS OF SPAN)




WHEN NO GAP BETWEEN PIGGYBACK AND BASE TRUSS EXISTS:

REPLACE TOE NAILING OF PIGGYBACK TRUSS TO PURLINS WITH Nail-On PLATES AS SHOWN, AND INSTALL PURLINS TO BOTTOM EDGE OF BASE TRUSS TOP CHORD AT SPECIFIED SPACING SHOWN ON BASE TRUSS MITEK DESIGN DRAWING.

SCAB CONNECTION PER
NOTE D ABOVE




FOR ALL WIND SPEEDS, ATTACH MITEK 3X8 20 GA Nail-On PLATES TO EACH FACE OF TRUSSES AT 48" O.C. W/ (4) (0.131" X 1.5") PER MEMBER. STAGGER NAILS FROM OPPOSING FACES ENSURE 0.5" EDGE DISTANCE.



This sheet is provided as a Piggyback connection detail only. Building Designer is responsible for all permanent bracing per standard engineering practices or refer to BCSI for general guidance on lateral restraint and diagonal bracing requirements.

VERTICAL WEB TO
EXTEND THROUGH
BOTTOM CHORD
OF PIGGYBACK



FOR LARGE CONCENTRATED LOADS APPLIED TO CAP TRUSS REQUIRING A VERTICAL WEB:

- 1) VERTICAL WEBS OF PIGGYBACK AND BASE TRUSS MUST MATCH IN SIZE, GRADE, AND MUST LINE UP AS SHOWN IN DETAIL.
- 2) ATTACH 2 x x 4'-0" SCAB TO EACH FACE OF TRUSS ASSEMBLY WITH 2 ROWS OF 10d (0.131" X 3") NAILS SPACED 4" O.C. FROM EACH FACE. (SIZE AND GRADE TO MATCH VERTICAL WEBS OF PIGGYBACK AND BASE TRUSS.) (MINIMUM 2X4)
- 3) THIS CONNECTION IS ONLY VALID FOR A MAXIMUM CONCENTRATED LOAD OF 4000 LBS (@1.15). REVIEW BY A QUALIFIED ENGINEER IS REQUIRED FOR LOADS GREATER THAN 4000 LBS.
- 4) FOR PIGGYBACK TRUSSES CARRYING GIRDER LOADS, NUMBER OF PLYS OF PIGGYBACK TRUSS TO MATCH BASE TRUSS.
- 5) CONCENTRATED LOAD MUST BE APPLIED TO BOTH THE PIGGYBACK AND THE BASE TRUSS DESIGN.




Thomas A. Albani PE No.39380
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

February 12, 2018

AUGUST 1, 2016

STANDARD PIGGYBACK TRUSS CONNECTION DETAIL

MII-PIGGY-ALT
7-10




MiTek USA, Inc. Page 1 of 1

MAXIMUM WIND SPEED = REFER TO NOTES D AND OR E
MAX MEAN ROOF HEIGHT = 30 FEET
MAX TRUSS SPACING = 24" O.C.
CATEGORY II BUILDING
EXPOSURE B or C
ASCE 7-10
DURATION OF LOAD INCREASE : 1.60

DETAIL IS NOT APPLICABLE FOR TRUSSES
TRANSFERING DRAG LOADS (SHEAR TRUSSES).
ADDITIONAL CONSIDERATIONS BY BUILDING
ENGINEER/DESIGNER ARE REQUIRED.


- A - PIGGYBACK TRUSS, REFER TO MITEK TRUSS DESIGN DRAWING.
SHALL BE CONNECTED TO EACH PURLIN
WITH (2) 0(0.131" X 3.5") TOE-NAILED.
- B - BASE TRUSS, REFER TO MITEK TRUSS DESIGN DRAWING.
- C - PURLINS AT EACH BASE TRUSS JOINT AND A MAXIMUM 24" O.C.
UNLESS SPECIFIED CLOSER ON MITEK TRUSS DESIGN DRAWING.
CONNECT TO BASE TRUSS WITH (2) (0.131" X 3.5") NAILS EACH.
- D - 2 X $\frac{1}{2}$ " X 4'-0" SCAB, SIZE TO MATCH TOP CHORD OF
PIGGYBACK TRUSS, MIN GRADE #2, ATTACHED TO ONE FACE, CENTERED ON
INTERSECTION, WITH (2) ROWS OF (0.131" X 3") NAILS @ 4" O.C.
SCAB MAY BE OMITTED PROVIDED THE TOP CHORD SHEATHING
IS CONTINUOUS OVER INTERSECTION AT LEAST 1 FT. IN BOTH
DIRECTIONS AND:
1. WIND SPEED OF 115 MPH OR LESS FOR ANY PIGGYBACK SPAN, OR
 2. WIND SPEED OF 116 MPH TO 160 MPH WITH A MAXIMUM
PIGGYBACK SPAN OF 12 ft.
- E - FOR WIND SPEED IN THE RANGE 126 MPH - 160 MPH
ADD 9" x 9" x 1/2" PLYWOOD (or 7/16" OSB) GUSSET
EACH SIDE AT 48" O.C. OR LESS. ATTACH WITH
3 - 6d (0.113" X 2") NAILS INTO EACH CHORD FROM
EACH SIDE (TOTAL - 12 NAILS)




WHEN NO GAP BETWEEN PIGGYBACK AND BASE TRUSS EXISTS:

REPLACE TOE NAILING OF PIGGYBACK TRUSS TO PURLINS WITH PLYWOOD
GUSSETS AS SHOWN, AND INSTALL PURLINS TO BOTTOM EDGE OF BASE
TRUSS TOP CHORD AT SPECIFIED SPACING SHOWN ON BASE
TRUSS MITEK DESIGN DRAWING.

SCAB CONNECTION PER
NOTE D ABOVE




7" x 7" x 1/2" PLYWOOD (or 7/16" OSB) GUSSET EACH SIDE AT 24" O.C.
ATTACH WITH 3 - 6d (0.113" X 2") NAILS INTO EACH CHORD
FROM EACH SIDE (TOTAL - 12 NAILS)




This sheet is provided as a Piggyback connection
detail only. Building Designer is responsible for all
permanent bracing per standard engineering practices or
refer to BCSI for general guidance on lateral restraint
and diagonal bracing requirements.

VERTICAL WEB TO
EXTEND THROUGH
BOTTOM CHORD
OF PIGGYBACK



FOR LARGE CONCENTRATED LOADS APPLIED
TO CAP TRUSS REQUIRING A VERTICAL WEB:

- 1) VERTICAL WEBS OF PIGGYBACK AND BASE TRUSS
MUST MATCH IN SIZE, GRADE, AND MUST LINE UP
AS SHOWN IN DETAIL.
- 2) ATTACH 2 x $\frac{1}{2}$ " X 4'-0" SCAB TO EACH FACE OF
TRUSS ASSEMBLY WITH 2 ROWS OF 10d (0.131" X 3") NAILS
SPACED 4" O.C. FROM EACH FACE. (SIZE AND GRADE TO MATCH
VERTICAL WEBS OF PIGGYBACK AND BASE TRUSS.)
(MINIMUM 2X4)
- 3) THIS CONNECTION IS ONLY VALID FOR A MAXIMUM
CONCENTRATED LOAD OF 4000 LBS (@1.15). REVIEW
BY A QUALIFIED ENGINEER IS REQUIRED FOR LOADS
GREATER THAN 4000 LBS.
- 4) FOR PIGGYBACK TRUSSES CARRYING GIRDER LOADS,
NUMBER OF PLYS OF PIGGYBACK TRUSS TO MATCH BASE TRUSS.
- 5) CONCENTRATED LOAD MUST BE APPLIED TO BOTH
THE PIGGYBACK AND THE BASE TRUSS DESIGN.



Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd, Tampa FL 33610
Date:


January 19, 2018

AUGUST 1, 2016

STANDARD REPAIR DETAIL FOR BROKEN CHORDS, WEBS
AND DAMAGED OR MISSING CHORD SPLICE PLATES

MII-REP01A1

MiTek USA, Inc. Page 1 of 1




| TOTAL NUMBER OF NAILS EACH SIDE OF BREAK * | | X INCHES | MAXIMUM FORCE (lbs) 15% LOAD DURATION | | | | | | | |
|--|----|----------|---------------------------------------|------|------|------|------|------|------|------|
| | | | SP | | DF | | SPF | | HF | |
| | | | 2x4 | 2x6 | 2x4 | 2x6 | 2x4 | 2x6 | 2x4 | 2x6 |
| 20 | 30 | 24" | 1706 | 2559 | 1561 | 2342 | 1320 | 1980 | 1352 | 2028 |
| 26 | 39 | 30" | 2194 | 3291 | 2007 | 3011 | 1697 | 2546 | 1738 | 2608 |
| 32 | 48 | 36" | 2681 | 4022 | 2454 | 3681 | 2074 | 3111 | 2125 | 3187 |
| 38 | 57 | 42" | 3169 | 4754 | 2900 | 4350 | 2451 | 3677 | 2511 | 3767 |
| 44 | 66 | 48" | 3657 | 5485 | 3346 | 5019 | 2829 | 4243 | 2898 | 4347 |

* DIVIDE EQUALLY FRONT AND BACK

ATTACH 2x SCAB OF THE SAME SIZE AND GRADE AS THE BROKEN MEMBER TO EACH FACE OF THE TRUSS (CENTER ON BREAK OR SPLICE) WITH 10d (0.131" X 3") NAILS (TWO ROWS FOR 2x4, THREE ROWS FOR 2x6) SPACED 4" O.C. AS SHOWN. STAGGER NAIL SPACING FROM FRONT FACE AND BACK FACE FOR A NET 0-2-0 O.C. SPACING IN THE MAIN MEMBER. USE A MIN. 0-3-0 MEMBER END DISTANCE.

THE LENGTH OF THE BREAK (C) SHALL NOT EXCEED 12". (C=PLATE LENGTH FOR SPLICE REPAIRS)
THE MINIMUM OVERALL SCAB LENGTH REQUIRED (L) IS CALCULATED AS FOLLOWS:
 $L = (2) X + C$



THE LOCATION OF THE BREAK MUST BE GREATER THAN OR EQUAL TO THE REQUIRED X DIMENSION FROM ANY PERIMETER BREAK OR HEEL JOINT AND A MINIMUM OF 6" FROM ANY INTERIOR JOINT (SEE SKETCH ABOVE)

DO NOT USE REPAIR FOR JOINT SPLICES

NOTES:

1. THIS REPAIR DETAIL IS TO BE USED ONLY FOR THE APPLICATION SHOWN. THIS REPAIR DOES NOT IMPLY THAT THE REMAINING PORTION OF THE TRUSS IS UNDAMAGED. THE ENTIRE TRUSS SHALL BE INSPECTED TO VERIFY THAT NO FURTHER REPAIRS ARE REQUIRED. WHEN THE REQUIRED REPAIRS ARE PROPERLY APPLIED, THE TRUSS WILL BE CAPABLE OF SUPPORTING THE LOADS INDICATED.
2. ALL MEMBERS MUST BE RETURNED TO THEIR ORIGINAL POSITIONS BEFORE APPLYING REPAIR AND HELD IN PLACE DURING APPLICATION OF REPAIR.
3. THE END DISTANCE, EDGE DISTANCE AND SPACING OF NAILS SHALL BE SUCH AS TO AVOID UNUSUAL SPLITTING OF THE WOOD.
4. WHEN NAILING THE SCABS, THE USE OF A BACKUP WEIGHT IS RECOMMENDED TO AVOID LOOSENING OF THE CONNECTOR PLATES AT THE JOINTS OR SPLICES.
5. THIS REPAIR IS TO BE USED FOR SINGLE PLY TRUSSES IN THE 2x ORIENTATION ONLY.
6. THIS REPAIR IS LIMITED TO TRUSSES WITH NO MORE THAN THREE BROKEN MEMBERS.



Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 19, 2018


AUGUST 1, 2016

LATERAL TOE-NAIL DETAIL

MII-TOENAIL_SP

MiTek USA, Inc.

Page 1 of 1



MiTek USA, Inc.

 ENGINEERED BY
TRENCO
 A MiTek Affiliate


NOTES:

1. TOE-NAILS SHALL BE DRIVEN AT AN ANGLE OF 45 DEGREES WITH THE MEMBER AND MUST HAVE FULL WOOD SUPPORT. (NAIL MUST BE DRIVEN THROUGH AND EXIT AT THE BACK CORNER OF THE MEMBER END AS SHOWN.)
2. THE END DISTANCE, EDGE DISTANCE, AND SPACING OF NAILS SHALL BE SUCH AS TO AVOID UNUSUAL SPLITTING OF THE WOOD.
3. ALLOWABLE VALUE SHALL BE THE LESSER VALUE OF THE TWO SPECIES FOR MEMBERS OF DIFFERENT SPECIES.

 THIS DETAIL APPLICABLE TO THE
 THREE END DETAILS SHOWN BELOW

 VIEWS SHOWN ARE FOR
 ILLUSTRATION PURPOSES ONLY

| TOE-NAIL SINGLE SHEAR VALUES PER NDS 2001 (lb/nail) | | | | | | |
|---|-------|-------|------|------|------|-------|
| | DIAM. | SP | DF | HF | SPF | SPF-S |
| 3.5" LONG | .131 | 88.0 | 80.6 | 69.9 | 68.4 | 59.7 |
| | .135 | 93.5 | 85.6 | 74.2 | 72.6 | 63.4 |
| | .162 | 108.8 | 99.6 | 86.4 | 84.5 | 73.8 |
| 3.25" LONG | .128 | 74.2 | 67.9 | 58.9 | 57.6 | 50.3 |
| | .131 | 75.9 | 69.5 | 60.3 | 59.0 | 51.1 |
| | .148 | 81.4 | 74.5 | 64.6 | 63.2 | 52.5 |




 SIDE VIEW
 (2x3)
 2 NAILS

 VALUES SHOWN ARE CAPACITY PER TOE-NAIL.
 APPLICABLE DURATION OF LOAD INCREASES MAY BE APPLIED.

EXAMPLE:




(3) - 16d (0.162" X 3.5") NAILS WITH SPF SPECIES BOTTOM CHORD

For load duration increase of 1.15:

3 (nails) X 84.5 (lb/nail) X 1.15 (DOL) = 291.5 lb Maximum Capacity

 SIDE VIEW
 (2x4)
 3 NAILS

 SIDE VIEW
 (2x6)
 4 NAILS

 Thomas A. Albani PE No.39380
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:


January 19, 2018





GENERAL SPECIFICATIONS

1. NAIL SIZE 10d (0.131" X 3")
2. WOOD SCREW = 3" WS3 USP OR EQUIVALENT
DO NOT USE DRYWALL OR DECKING TYPE SCREW
3. INSTALL VALLEY TRUSSES (24" O.C. MAXIMUM) AND SECURE PER DETAIL A
4. BRACE VALLEY WEBS IN ACCORDANCE WITH THE INDIVIDUAL DESIGN DRAWINGS.
5. BASE TRUSS SHALL BE DESIGNED WITH A PURLIN SPACING EQUIVANT TO THE RAKE DIMENSION OF THE VALLEY TRUSS SPACING.
6. NAILING DONE PER NDS - 01
7. VALLEY STUD SPACING NOT TO EXCEED 48" O.C.



SECURE VALLEY TRUSS
W/ ONE ROW OF 10d
NAILS 6" O.C.

ATTACH 2x4 CONTINUOUS NO.2 SP
TO THE ROOF W/ TWO USP WS3 (1/4" X 3")
WOOD SCREWS INTO EACH BASE TRUSS.

DETAIL A
(NO SHEATHING)
N.T.S.

WIND DESIGN PER ASCE 7-98, ASCE 7-02, ASCE 7-05 146 MPH
WIND DESIGN PER ASCE 7-10 160 MPH
MAX MEAN ROOF HEIGHT = 30 FEET
ROOF PITCH = MINIMUM 3/12 MAXIMUM 6/12
CATEGORY II BUILDING
EXPOSURE C
WIND DURATION OF LOAD INCREASE : 1.60
MAX TOP CHORD TOTAL LOAD = 50 PSF
MAX SPACING = 24" O.C. (BASE AND VALLEY)
MINIMUM REDUCED DEAD LOAD OF 6 PSF
ON THE TRUSSES



Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd, Tampa FL 33610
Date:

January 19, 2018


AUGUST 1, 2016

TRUSSED VALLEY SET DETAIL

MII-VALLEY HIGH WIND2



MiTek USA, Inc.

Page 1 of 1




GENERAL SPECIFICATIONS


1. NAIL SIZE 10d (0.131" X 3")
2. WOOD SCREW = 4.5" WS45 USP OR EQUIVANT
3. INSTALL SHEATHING TO TOP CHORD OF BASE TRUSSES.
4. INSTALL VALLEY TRUSSES (24" O.C. MAXIMUM) AND SECURE TO BASE TRUSSES AS PER DETAIL A
5. BRACE VALLEY WEBS IN ACCORDANCE WITH THE INDIVIDUAL DESIGN DRAWINGS.
6. NAILING DONE PER NDS-01
7. VALLEY STUD SPACING NOT TO EXCEED 48" O.C.



SECURE VALLEY TRUSS
W/ ONE ROW OF 10d
NAILS 6" O.C.




WIND DESIGN PER ASCE 7-98, ASCE 7-02, ASCE 7-05 146 MPH
WIND DESIGN PER ASCE 7-10 160 MPH
MAX MEAN ROOF HEIGHT = 30 FEET
ROOF PITCH = MINIMUM 3/12 MAXIMUM 6/12
CATEGORY II BUILDING
EXPOSURE C
WIND DURATION OF LOAD INCREASE : 1.60
MAX TOP CHORD TOTAL LOAD = 50 PSF
MAX SPACING = 24" O.C. (BASE AND VALLEY)
MINIMUM REDUCED DEAD LOAD OF 6 PSF
ON THE TRUSSES



Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 12, 2018




MiTek USA, Inc.


ENGINEERED BY
TRENCO
A MiTek Affiliate

GENERAL SPECIFICATIONS

1. NAIL SIZE 16d (0.131" X 3.5")
2. INSTALL VALLEY TRUSSES (24" O.C. MAXIMUM) AND SECURE PER DETAIL A
3. BRACE VALLEY WEBS IN ACCORDANCE WITH THE INDIVIDUAL DESIGN DRAWINGS.
4. BASE TRUSS SHALL BE DESIGNED WITH A PURLIN SPACING EQUIVALENT TO THE RAKE DIMENSION OF THE VALLEY TRUSS SPACING.
5. NAILING DONE PER NDS - 01
6. VALLEY STUD SPACING NOT TO EXCEED 48" O.C.
7. ALL LUMBER SPECIES TO BE SP.



SECURE VALLEY TRUSS
W/ ONE ROW OF 16d
NAILS 6" O.C.



DETAIL A
(MAXIMUM 1" SHEATHING)
N.T.S.

WIND DESIGN PER ASCE 7-98, ASCE 7-02, ASCE 7-05 120 MPH
WIND DESIGN PER ASCE 7-10 150 MPH
MAX MEAN ROOF HEIGHT = 30 FEET
ROOF PITCH = MINIMUM 3/12 MAXIMUM 10/12
CATEGORY II BUILDING
EXPOSURE C OR B
WIND DURATION OF LOAD INCREASE : 1.60
MAX TOP CHORD TOTAL LOAD = 60 PSF
MAX SPACING = 24" O.C. (BASE AND VALLEY)
MINIMUM REDUCED DEAD LOAD OF 4.2 PSF
ON THE TRUSSES



Thomas A. Albani PE No. 39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


February 12, 2018

AUGUST 1, 2016

TRUSSED VALLEY SET DETAIL
(HIGH WIND VELOCITY)

MII-VALLEY


MiTek USA, Inc. Page 1 of 1



MiTek USA, Inc.

ENGINEERED BY
TRENCO
A MiTek Affiliate

NOTE: VALLEY STUD SPACING NOT
TO EXCEED 48" O.C. SPACING




ATTACH VALLEY TRUSSES TO
LOWER TRUSSES WITH
USP RT7 OR EQUIVALENT

WIND DESIGN PER ASCE 7-98, ASCE 7-02, ASCE 7-05 146 MPH
WIND DESIGN PER ASCE 7-10 160 MPH
MAX MEAN ROOF HEIGHT = 30 FEET
CATEGORY II BUILDING
EXPOSURE B or C
WIND DURATION OF LOAD INCREASE : 1.6
MAX TOP CHORD TOTAL LOAD = 50 PSF
MAX SPACING = 24" O.C. (BASE AND VALLEY)


SUPPORTING TRUSSES DIRECTLY UNDER
VALLEY TRUSSES MUST BE DESIGNED
WITH A MAXIMUM UNBRACED LENGTH OF
2'-10" ON AFFECTED TOP CHORDS.

NOTES:

- SHEATHING APPLIED AFTER
INSTALLATION OF VALLEY TRUSSES
- THIS DETAIL IS NOT APPLICABLE FOR
SPF-S SPECIES LUMBER.




FOR BEVELED BOTTOM
CHORD, CLIP MAY BE
APPLIED TO EITHER FACE




CLIP MAY BE APPLIED
TO THIS FACE UP TO
A MAXIMUM 6/12 PITCH

NON-BEVELED
BOTTOM CHORD






NON-BEVELED
BOTTOM CHORD

CLIP MUST BE APPLIED
TO THIS FACE WHEN
PITCH EXCEEDS 6/12.
(MAXIMUM 12/12 PITCH)




Thomas A. Albani PE No. 39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 19, 2018



- NOTE:
1. MINIMUM GRADE OF #2 MATERIAL IN THE TOP AND BOTTOM CHORDS.
 2. CONNECTION BETWEEN BOTTOM CHORD OF GABLE END TRUSS AND WALL TO BE PROVIDED BY PROJECT ENGINEER OR ARCHITECT.
 3. BRACING SHOWN IS FOR INDIVIDUAL TRUSS ONLY. CONSULT BLDG. ARCHITECT OR ENGINEER FOR TEMPORARY AND PERMANENT BRACING OF ROOF SYSTEM.
 4. "L" BRACES SPECIFIED ARE TO BE FULL LENGTH. GRADES: 2x4 No 3/STUD SP OR BETTER WITH ONE ROW OF 10d NAILS SPACED 6" O.C.
 5. DIAGONAL BRACE TO BE APPROXIMATELY 45 DEGREES TO ROOF DIAPHRAM AT 4'-0" O.C.
 6. CONSTRUCT HORIZONTAL BRACE CONNECTING A 2x6 STUD AND A 2x4 STUD AS SHOWN WITH 16d NAILS SPACED 6" O.C. HORIZONTAL BRACE TO BE LOCATED AT THE MIDSPAN OF THE LONGEST STUD. ATTACH TO VERTICAL STUDS WITH (4) 10d NAILS THROUGH 2x4. (REFER TO SECTION A-A)
 7. GABLE STUD DEFLECTION MEETS OR EXCEEDS L/240.
 8. THIS DETAIL DOES NOT APPLY TO STRUCTURAL GABLES.
 9. DO NOT USE FLAT BOTTOM CHORD GABLES NEXT TO SCISSOR TYPE TRUSSES.
 10. NAILS DESIGNATED 10d ARE (0.131" X 3") AND NAILS DESIGNATED 16d ARE (0.131" X 3.5")



| Minimum Stud Size Species and Grade | Stud Spacing | Without Brace | 2x4 L-Brace | DIAGONAL BRACE | 2 DIAGONAL BRACES AT 1/3 POINTS |
|-------------------------------------|--------------|---------------------|-------------|----------------|---------------------------------|
| | | Maximum Stud Length | | | |
| 2x4 SP No 3/Stud | 12" O.C. | 3-11-3 | 6-8-0 | 7-2-14 | 11-9-10 |
| 2x4 SP No 3/Stud | 16" O.C. | 3-6-14 | 5-9-5 | 7-1-13 | 10-8-11 |
| 2x4 SP No 3/Stud | 24" O.C. | 3-1-8 | 4-8-9 | 6-2-15 | 9-4-7 |

- * Diagonal braces over 6'-3" require a 2x4 T-Brace attached to one edge. Diagonal braces over 12'-6" require 2x4 I-braces attached to both edges. Fasten T and I braces to narrow edge of web with 10d nails 8" o.c., with 3" minimum end distance. Brace must cover 90% of diagonal length.


MAXIMUM WIND SPEED = 146 MPH
 MAX MEAN ROOF HEIGHT = 30 FEET
 CATEGORY II BUILDING
 EXPOSURE B or C
 ASCE 7-98, ASCE 7-02, ASCE 7-05
 DURATION OF LOAD INCREASE : 1.60

STUD DESIGN IS BASED ON COMPONENTS AND CLADDING.
 CONNECTION OF BRACING IS BASED ON MWFRS.



Thomas A. Albani PE No.39380
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd, Tampa FL 33610
 Date:

January 19, 2018



MiTek USA, Inc.

 ENGINEERED BY
TRENCO
 A MiTek Affiliate

MiTek USA, Inc.

Page 1 of 1

TRUSS CRITERIA:

LOADING: 40-10-0-10

DURATION FACTOR: 1.15

SPACING: 24" O.C.

TOP CHORD: 2x4 OR 2x6


PITCH: 4/12 - 12/12

HEEL HEIGHT: STANDARD HEEL UP TO 12" ENERGY HEEL

END BEARING CONDITION

NOTES:

1. ATTACH 2x_ SCAB (MINIMUM NO.2 GRADE SPF, HF, SP, DF) TO ONE FACE OF TRUSS WITH TWO ROWS OF 10d (0.131" X 3") SPACED 6" O.C.
2. THE END DISTANCE, EDGE DISTANCE, AND SPACING OF NAILS SHALL BE SUCH AS TO AVOID UNUSUAL SPLITTING OF THE WOOD.
3. WHEN NAILING THE SCABS, THE USE OF A BACKUP WEIGHT IS RECOMMENDED TO AVOID LOOSENING OF THE CONNECTOR PLATES AT THE JOINTS OR SPLICES.




IMPORTANT

This detail to be used only with trusses (spans less than 40') spaced 24" o.c. maximum and having pitches between 4/12 and 12/12 and total top chord loads not exceeding 50 psf.


Trusses not fitting these criteria should be examined individually.

REFER TO INDIVIDUAL TRUSS DESIGN
FOR PLATE SIZES AND LUMBER GRADES



Thomas A. Albani PE No.39380
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:



February 12, 2018



TO MINIMIZE VIBRATION COMMON TO ALL SHALLOW FRAMING SYSTEMS, 2x6 "STRONGBACK" IS RECOMMENDED, LOCATED EVERY 8 TO 10 FEET ALONG A FLOOR TRUSS.

NOTE 1: 2X6 STRONGBACK ORIENTED VERTICALLY MAY BE POSITIONED DIRECTLY UNDER THE TOP CHORD OR DIRECTLY ABOVE THE BOTTOM CHORD. SECURELY FASTENED TO THE TRUSS USING ANY OF THE METHODS ILLUSTRATED BELOW.

NOTE 2: STRONGBACK BRACING ALSO SATISFIES THE LATERAL BRACING REQUIREMENTS FOR THE BOTTOM CHORD OF THE TRUSS WHEN IT IS PLACED ON TOP OF THE BOTTOM CHORD, IS CONTINUOUS FROM END TO END, CONNECTED WITH A METHOD OTHER THAN METAL FRAMING ANCHOR, AND PROPERLY CONNECTED, BY OTHERS, AT THE ENDS.



ALTERNATE METHOD OF SPLICING:
OVERLAP STRONGBACK MEMBERS A MINIMUM OF 4'-0" AND FASTEN WITH (12) - 10d (0.131" X 3") NAILS STAGGERED AND EQUALLY SPACED.
(TO BE USED ONLY WHEN STRONGBACK IS NOT ALIGNED WITH A VERTICAL)




Thomas A. Albani PE No.39380
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 12, 2018

$$9' 1-1/8''$$

- 1) REFER TO HIB 01 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED).
- 2) ALL TUBES/SEES (INCLUDING TUBES/SEES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL VOPS FOR ALTERNATE BRACING REQUIREMENTS.

- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FURRED BY BUILDER.
- 4) ALL TRUSSEES ARE DESIGNED FOR 2" o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
- 6) 5/8"X2 TRUSSEES MUST BE INSTALLED WITH THE TOP BEAMS UP.
- 7) BECAUSE AERIAL LIFT (LIFT) TO BE FURNISHED BY BUILDER.



| | | | | | |
|------------|---------|--------------|-----|-----------------------|---------|
| DATE: | 8-11-20 | PLAN BY: | KLH | Original Reference #: | 2435644 |
| Issued by: | | Modified by: | | Cost Amt: | 2435644 |

