



ROOF VENTILATION:
R806.2 Minimum vent area.
The minimum net free ventilating area shall be 1/150 of the area of the vented space.
Exception: The minimum net free ventilation area shall be 1/300 of the vented space provided one or more of the following conditions are met:
1. In Climate Zones 6, 7 and 8, a Class I or II vapor retarder is installed on the warm-in-winter side of the ceiling.
2. At least 40 percent and not more than 50 percent of the required ventilating area is provided by ventilators located in the upper portion of the attic or rafter space. Upper ventilators shall be located no more than 3 feet below the ridge or highest point of the space, measured vertically, with the balance of the required ventilation provided by eave or cornice vents. Where the location of wall or roof framing members conflicts with the installation of upper ventilators, installation more than 3 feet below the ridge or highest point of the space shall be permitted.


FRONT ELEVATION
SCALE: 1/4" = 1'-0"



RIGHT ELEVATION
SCALE: 1/4" = 1'-0"



LEFT ELEVATION
SCALE: 1/4" = 1'-0"



REAR ELEVATION
SCALE: 1/4" = 1'-0"



Review for Code Compliance
Universal Engineering Science

Lawrence Perrell
Examiner-License No.

PX2707

10/22/2023

Live-Well Homes

Marvin & Page Anderson Res.

PROJECT ADDRESS:
434 SW Don Cook Way, Fort White, FL

FL PE 53915
This item has been digitally signed and sealed by Mark Disosway P.E. on digital signature date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

C=US, O=Florida, dnQualifier=A014 10C0000017E97 DE07CA000746F0, CN=Mark d Disosway
2023-09-15 13:33:07

DIMENSIONS:
Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Disosway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 7th Edition Florida Building Code Residential (2020) to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.


Mark Disosway P.E.
163 SW Midtown Place
Suite 103
Lake City, Florida 32025
386.754.5419
disoswaydesign@gmail.com

JOB NUMBER:
231080

1
OF 6 SHEETS

ELECTRICAL PLAN NOTES:	
E - 1	WIRE ALL APPLIANCES, HVAC UNITS AND OTHER EQUIPMENT PER MANUF. SPECIFICATIONS.
E - 2	CONSULT THE OWNER FOR THE NUMBER OF SEPERATE TELEPHONE LINES TO BE INSTALLED.
E - 3	ALL INSTALLATIONS SHALL BE PER NAT'L. ELECTRIC CODE
E - 4	ALL SMOKE DETECTORS SHALL BE 120V W/ BATTERY BACKUP OF THE PHOTOELECTRIC TYPE, AND SHALL BE INTERLOCKED TOGETHER. INSTALL INSIDE AND NEAR ALL BEDROOMS.
E - 5	TELEPHONE, TELEVISION AND OTHER LOW VOLTAGE DEVICES OR OUTLETS SHALL BE AS PER THE OWNER'S DIRECTIONS, & IN ACCORDANCE W/ APPLICABLE SECTIONS OF NEC-LATEST EDITION.
E - 6	ELECTRICAL CONTR SHALL BE RESPONSIBLE FOR THE DESIGN & SIZING OF ELECTRICAL SERVICE AND CIRCUITS.
E - 7	ENTRY OF SERVICE (UNDERGROUND OR OVERHEAD) TO BE DETERMINED BY POWER COMPANY.
E - 8	ALL 120-VOLT, SINGLE-PHASE, 15- AND 20-AMPERE BRANCH CIRCUITS SUPPLYING OUTLETS INSTALLED IN DWELLING UNIT FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, DENS, BEDROOMS, SUN ROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS, OR SIMILAR ROOMS OR AREAS SHALL BE PROTECTED BY A LISTED ARC-FAULT CIRCUIT INTERRUPTER, COMBINATION-TYPE INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUIT.
E - 9	ALL OUTLETS TO BE LOCATED ABOVE BASE FLOOD ELEVATION.
E - 10	A SERVICE DISCONNECT WITH OVER CURRENT PROTECTION SHALL BE INSTALLED OUTSIDE OF THE BUILDING, ON THE LOAD SIDE OF THE METER, AT THE PLACE ELECTRIC CONDUCTORS ENTER THE BUILDING.
E - 11	SERVICE ENTRANCE CONDUCTORS MAY NOT BE LOCATED INSIDE OF THE OF THE BUILDING WITHOUT SPECIAL APPROVAL OF THE BUILDING OFFICIAL.
E - 12	CARBON MONOXIDE ALARMS SHALL BE REQUIRED WITHIN 10' OF ALL ROOMS FOR SLEEPING PURPOSES IN BUILDINGS HAVING A FOSSIL-FUEL-BURNING HEATER OR APPLIANCE, A FIREPLACE, OR ATTACHED GARAGE.
E - 13	ALL OUTLETS LOCATED IN RESIDENTIAL TO BE TAMPER-RESISTANT PER NEC.
E - 14	A MINIMUM OF 75% OF PERMANENTLY INSTALLED LAMPS OR LIGHTING FIXTURES SHALL BE HIGH EFFICACY FBC EC SEC. R404.1

ELECTRICAL LEGEND	
	CEILING FAN (PRE-WIRE FOR LIGHT KIT)
	DOUBLE SECURITY LIGHT
	2x4 FLUORESCENT LIGHT FIXTURE
	RECESSED CAN LIGHT
	BATH EXHAUST FAN WITH LIGHT
	BATH EXHAUST FAN
	LIGHT FIXTURE
	DUPLEX OUTLET
	220v OUTLET
	GFI DUPLEX OUTLET
	SMOKE DETECTOR
	WALL SWITCH
	3 WAY WALL SWITCH
	4 WAY WALL SWITCH
	WATER PROOF GFI OUTLET
	PHONE JACK
	TELEVISION JACK
	GARAGE DOOR OPENER
	CARBON MONOXIDE ALARM



Review for Code Compliance
Universal Engineering Science

Lawrence Pennell
Examiner-License No.

PX2707

10/22/2023


Live-Well Homes

Marvin & Page Anderson Res.

PROJECT ADDRESS:
434 SW Don Cook Way, Fort White, FL

FL PE 53915

This item has been digitally signed and sealed by Mark Disoway P.E. on digital signature date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.



C=US, O=Florida,
dnQualifier=A014
10C0000017E97
DE07CA000746F
0, CN=Mark d
Disoway
2023-09-15 13:
35:43

DIMENSIONS:
Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disoway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Disoway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.


CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 7th Edition Florida Building Code Residential (2020) to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.


Mark Disoway P.E.
163 SW Midtown Place
Suite 103
Lake City, Florida 32025
386.754.5419
disowaydesign@gmail.com

JOB NUMBER:
231080


3
OF 6 SHEETS



ONE STORY WALL SECTION
SCALE: 3/4" = 1'-0"



ONE STORY WALL SECTION




ONE STORY WALL SECTION

(TYP.) CORNER FRAMING
WOOD FRAME


Wind Speed	Sheathing Thickness Plywood Or OSB	Required Nail	Nail spacing along panel edges	Nail spacing along intermediate supports in the panel field
120 mph Exp. B	7/16"	ASTM F1667 RSR5-01 (2 3/8" x 0.131")	6" oc	12" oc
120 mph Exp. C	7/16"	ASTM F1667 RSR5-01 (2 3/8" x 0.131")	6" oc	12" oc
130 mph Exp. B	15/32"	ASTM F1667 RSR5-03 (2 1/2" x 0.131") or ASTM F1667 RSR5-04 (3" x 0.120")	6" oc	6" oc
130 mph Exp. C	15/32"	ASTM F1667 RSR5-01 (2 3/8" x 0.131")	6" oc	6" oc
130 mph Exp. D	15/32"	ASTM F1667 RSR5-03 (2 1/2" x 0.131") or ASTM F1667 RSR5-04 (3" x 0.120")	6" oc	6" oc
140 mph Exp. B	7/16"	ASTM F1667 RSR5-01 (2 3/8" x 0.131")	6" oc	6" oc
140 mph Exp. C	15/32"	ASTM F1667 RSR5-03 (2 1/2" x 0.131") or ASTM F1667 RSR5-04 (3" x 0.120")	6" oc	6" oc
140 mph Exp. D	15/32"	ASTM F1667 RSR5-03 (2 1/2" x 0.131") or ASTM F1667 RSR5-04 (3" x 0.120")	6" oc	6" oc
150 mph Exp. C	15/32"	ASTM F1667 RSR5-03 (2 1/2" x 0.131") or ASTM F1667 RSR5-04 (3" x 0.120")	6" oc	6" oc
150 mph Exp. D	15/32"	ASTM F1667 RSR5-03 (2 1/2" x 0.131") or ASTM F1667 RSR5-04 (3" x 0.120")	4" oc	4" oc

Note: For sheathing located a minimum of 4 feet from the perimeter edge of the roof, including 4 feet on each side of ridges and hips, nail spacing is permitted to be 8 inches on center along panel edges and 6 inches on center along intermediate supports in the panel field. Note: This table specifies the code minimum thickness of roof sheathing. The thickness of the sheathing may need to be increased based in the type of roofing material being used. See manufacturer Florida product approval.




(TYP.) GABLE BRACING DETAIL
WOOD FRAME

(TYP.) GABLE WALL w/ VAULTED CEILING
WOOD FRAME




TYPICAL HEADER STRAPING DETAIL

ONE STORY WOOD FRAME w/ STRAPS & ANCHORS




(TYP.) WALL CONNECTIONS

ONE STORY WOOD FRAME




SHEATHING FOR UPLIFT ATTACHMENT DETAILS



(TYP.) GABLE WALL w/ VAULTED CEILING


WOOD FRAME



PORCH POST CONNECTIONS


(TYP.) PORCH POST

ONE STORY WOOD




(TYP.) BEAM TO WALL

WOOD FRAME w/ STRAPS & ANCHORS




INTERIOR BEARING WALL UPLIFT STRAP TABLE



PORCH POST CONNECTIONS


(TYP.) PORCH POST

ONE STORY WOOD




(TYP.) BEAM TO WALL

WOOD FRAME w/ STRAPS & ANCHORS



(TYP.) WALL CONNECTIONS

ONE STORY WOOD FRAME



(TYP.) GIRDER TRUSS HOLD DOWN DETAIL


WOOD FRAME w/ STRAPS & ANCHORS



PORCH POST CONNECTIONS


(TYP.) PORCH POST

ONE STORY WOOD



(TYP.) BEAM TO WALL

WOOD FRAME w/ STRAPS & ANCHORS



(TYP.) WALL CONNECTIONS

ONE STORY WOOD FRAME

Uplift SP	Uplift SPF	Truss Connector	To Plate	To Truss/Rafter
615	485	SDWC15600	-	-
415	290	H3	4-8d x 1 1/2"	4-8d x 1 1/2"
575	495	H2.5A	5-8d x 1 1/2"	5-8d x 1 1/2"
1340	1015	H10A	9-10d 1 1/2"	9-10d 1 1/2"
720	620	LTS12-20	6-10d 1 1/2"	6-10d 1 1/2"
1000	860	MTS12-30	7-10d 1 1/2"	7-10d 1 1/2"
1450	1245	HTS20-30	12-10d 1 1/2"	12-10d 1 1/2"
Uplift SP	Uplift SPF	Truss Ties	To One Member	To Other Member
1235	1235	LSTA21	8-10d	8-10d
1640	1455	MSTA24	9-10d	9-10d
1030	1030	CS20	7-10d	7-10d
Uplift SP	Uplift SPF	Stud Plate Ties	To Stud	To Plate
585	535	SP1	6-10d	4-10d
1065	605	SP2	6-10d	6-10d
771	771	LSTA24	10-10d	wrap under or over plate
1235	1235	LSTA24	14-10d	wrap under or over plate
Uplift SP	Uplift SPF	Holdowns @ Stewall	To Stud / Post	Anchor
1825	1800	DTT22	8-SDS 1/4"x1 1/2"	1/2"x12" Titen HD
4235	3640	HTT4	18-16d x 12"	1/2"x12" Titen HD
Uplift SP	Uplift SPF	Holdowns @ Mono	To Stud / Post	Anchor
1925	1800	DTT22	8-SDS 1/4"x1 1/2"	1/2"x12" Titen HD
4235	3640	HTT4	18-16d x 12"	1/2"x12" Titen HD
Uplift SP	Uplift SPF	Post Bases @ Stewall	To Post	Anchor
2475	1900	ABU4Z	12-16d	5/8"x12" Drill & Epoxy
2475	1900	ABU6Z	12-16d	5/8"x12" Drill & Epoxy
Uplift SP	Uplift SPF	Post Bases @ Mono	To Post	Anchor
2475	1900	ABU4Z	12-16d	5/8"x12" Drill & Epoxy
2475	1900	ABU6Z	12-16d	5/8"x12" Drill & Epoxy

CONNECTOR TABLE

EXTERIOR WALL STUD TABLE FOR SPF #2 STUDS:

THIS STUD HEIGHT TABLE IS PER 2012 WFCM, TABLE 3.20B5, EXTERIOR LOAD BEARING & NON LOAD BEARING STUD LENGTHS FOR WALLS WITH OSB EXTERIOR AND 1/2" GYP INTERIOR RESISTING INTERIOR ZONE WINDLOADS, 130 MPH, EXPOSURE C, STUD DEFLECTION LIMIT H/240 (NOT OK FOR BRITTLE FINISH). STUD SPACINGS SHALL BE MULTIPLIED BY 0.8 FOR FRAMING LOCATED WITHIN 4 FEET OF CORNERS FOR END ZONE LOADING. (END ZONE EXAMPLE 16" O.C. x 0.8 = 12.8" O.C.)

(1) 2x4 @ 16" OC	TO 10'-1" STUD HEIGHT
(1) 2x4 @ 12" OC	TO 11'-2" STUD HEIGHT
(1) 2x6 @ 16" OC	TO 15'-7" STUD HEIGHT
(1) 2x6 @ 12" OC	TO 17'-3" STUD HEIGHT

EXTERIOR WALL STUD TABLE FOR SPF #2 STUDS:

GRADE & SPECIES TABLE

		Fb	E
2x8	SP #2	925	1.4
2x10	SP #2	800	1.4
2x12	SP #2	750	1.4
GLB	24F-V3 SP	2600	1.9
LSL	TIMBERSTRAND	1700	1.7
LVL	MICROLAM	2950	2.0
PSL	PARALAM	2900	2.0

GRADE & SPECIES TABLE

BEARING SYSTEM DESIGN:

THE SEAL ON THESE PLANS FOR COMPLIANCE WITH FBCL, IS BASED ON REACTIONS, UPLIFTS, AND BEARING LOCATIONS IN TRUSS ENGINEERING SUBMITTED TO THE WIND LOAD ENGINEER. IT IS THE RESPONSIBILITY OF THE BUILDER TO CHECK ALL DETAILS OF THE COMPLETE ROOF SYSTEM DESIGN SUBMITTED BY THE TRUSS MANUFACTURER AND HAVE IT SIGNED, AND SEALED BY A DESIGN PROFESSIONAL FOR CORRECT APPLICATION OF FBCL REQUIRED LOADS AND ANY SPECIAL LOADS. THE BUILDER IS RESPONSIBLE TO REVIEW EACH INDIVIDUAL TRUSS MEMBER AND THE TRUSS ROOF SYSTEM AS A WHOLE AND TO PROVIDE RESTRAINT FOR ANY LATERAL BRACING. THE BUILDER SHOULD USE CARE CHECKING THE ROOF DESIGN BECAUSE THE WIND LOAD ENGINEER IS SPECIFICALLY NOT RESPONSIBLE FOR THE TRUSS LAYOUT WHICH WAS CREATED BY THE TRUSS MANUFACTURER AND THE TRUSS DESIGNER ALSO DENIES RESPONSIBILITY FOR THE LAYOUT PER NOTES ON THEIR SEALED TRUSS SHEETS.

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

BEARING SYSTEM DESIGN:

GENERAL NOTES:

TRUSSES: TRUSSES SHALL BE DESIGNED BY A FLORIDA LICENSED ENGINEER IN ACCORDANCE WITH THE FBCL. TRUSS ENGINEERING SHALL INCLUDE TRUSS DESIGN, PLACEMENT PLANS, TEMPORARY AND PERMANENT BRACING DETAILS, TRUSS-TO-TRUSS CONNECTIONS, AND UPLIFT AND REACTION LOADS FOR ALL BEARING LOCATIONS. TRUSS ENGINEERING IS THE RESPONSIBILITY OF THE TRUSS MANUFACTURER AND SHALL BE SIGNED & SEALED BY THE MANUFACTURER'S DESIGN ENGINEER. IT IS THE BUILDER'S RESPONSIBILITY TO VERIFY THE TRUSS DESIGNER HAS SATISFIED ALL THE ABOVE REQUIREMENTS AND TO SELECT UPLIFT CONNECTIONS BASED ON TRUSS ENGINEERING UPLIFT AND PROVIDE FOOTINGS FOR INTERIOR BEARING WALLS. BUILDER IS TO FURNISH TRUSS ENGINEERING TO WIND LOAD ENGINEER FOR REVIEW OF TRUSS REACTIONS ON THE BUILDING STRUCTURE. STRAP 2X6 RAFTERS WITH MIN. UPLIFT CONNECTION 415LB EACH END, 2X6 RAFTERS 700 LB EACH END.

SITE PREPARATION: SITE ANALYSIS AND PREPARATION IS NOT PART OF THIS PLAN. FOUNDATION: CONFIRM THAT THE FOUNDATION DESIGN & SITE CONDITIONS MEET GRAVITY LOAD REQUIREMENTS (ASSUME 1500 PSF BEARING CAPACITY UNLESS VISUAL OBSERVATION OR SOILS TEST PROVES OTHERWISE).

CONCRETE: MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS, F_c = 2500 PSI. WELDED WIRE REINFORCED SLAB: 6" x 6" W1.4 x W1.4, F_y = 80ksi, WELDED WIRE REINFORCEMENT FABRIC (W.W.F.) CONFORMING TO ASTM A185, LOCATED IN MIDDLE OF THE SLAB, SUPPORTED WITH APPROVED MATERIALS OR SUPPORTS AT SPACINGS NOT TO EXCEED 3'.

FIBER CONCRETE SLAB: CONCRETE SLABS ON GROUND CONTAINING SYNTHETIC FIBER REINFORCEMENT. FIBER LENGTH 12 INCH TO 2 INCHES. DOSAGE AMOUNTS FROM 0.75 TO 1.5 POUNDS PER CUBIC YARD PER THE MANUFACTURER'S RECOMMENDATIONS. FIBERS TO COMPLY WITH ASTM C 1118. SUPPLIER TO PROVIDE ASTM C 1118 CERTIFICATION OF COMPLIANCE WHEN REQUESTED BY BUILDING OFFICIAL.

CONTROL JOINTS: WHERE SPECIFIED, SAWN CONTROL JOINTS IN SLAB-ON-GRADE SHALL BE CUT IN ACCORDANCE WITH ACI 302. JOINTS SHALL BE CUT WITHIN 12 HOURS OF SLAB PLACEMENT. THE LENGTH / WIDTH RATIOS OF SLAB AREAS SHALL NOT EXCEED 1:5 AND TYPICAL SPACING OF CUTS TO BE LEFT. DO NOT CUT W/WW OR REINFORCING STEEL (RECOMMENDED LOCATION OF CONTROL JOINTS IS SUBJECT TO OWNER AND CONTRACTOR'S APPROVAL. THE CONTROL JOINTS ARE NOT INTENDED TO PREVENT CRACKS BUT RATHER TO ENCOURAGE THE SLAB TO CRACK ON A GIVEN LINE.)

REBAR: ASTM A615, GRADE 40, DEFORMED BARS, F_y = 40 KSI. ALL LAP SPLICES 40" DB (25" FOR #5 BARS). UNO. ALL REINFORCEMENT SHALL BE DETAILLED AND PLACED IN ACCORDANCE WITH 318-88, I.B.C.

ROOF SHEATHING: ALL ROOFS ARE HORIZONTAL. DIAPHRAGMS, SHEATHING, UNBLOCKED, APPLIED PERPENDICULAR TO FRAMING, OVER A MINIMUM OF 3 FRAMING MEMBERS, WITH PANEL EDGES STAGGERED.

STRUCTURAL CONNECTORS: MANUFACTURERS AND PRODUCT NUMBER FOR CONNECTORS, ANCHORS, AND REINFORCEMENT ARE LISTED FOR EXAMPLE NOT ENDORSEMENT. AN EQUIVALENT DEVICE OF THE SAME OR OTHER MANUFACTURER CAN BE SUBSTITUTED FOR ANY DEVICES LISTED IN THE EXAMPLE TABLES AS LONG AS IT MEETS THE REQUIRED LOAD CAPACITIES. MANUFACTURER'S INSTALLATION INSTRUCTIONS MUST BE FOLLOWED TO ACHIEVE RATED LOADS.

ANCHOR BOLTS: A-307 ANCHOR BOLTS WITH MINIMUM EMBEDMENT AS SPECIFIED IN DRAWINGS BUT NO LESS THAN 7" IN CONCRETE OR REINFORCED BOND BEAM OR 10" IN GROUTED CMU.

BUILDER'S RESPONSIBILITY:

THE BUILDER AND OWNER ARE RESPONSIBLE FOR THE FOLLOWING, WHICH ARE SPECIFICALLY NOT PART OF THE WIND LOAD ENGINEER'S SCOPE OF WORK.

CONFIRM SITE CONDITIONS, FOUNDATION BEARING CAPACITY, GRADE AND BACKFILL HEIGHT, WIND SPEED AND DEBRIS ZONE, AND FLOOD ZONE.

PROVIDE MATERIALS AND CONSTRUCTION TECHNIQUES, WHICH COMPLY WITH FBCL REQUIREMENTS FOR THE STATED WIND VELOCITY AND DESIGN PRESSURES.

PROVIDE A CONTINUOUS LOAD PATH FROM TRUSSES TO FOUNDATION. IF YOU BELIEVE THE PLAN OBTAIN A CONTINUOUS LOAD PATH CONNECTION, CALL THE WIND LOAD ENGINEER IMMEDIATELY.

VERIFY THE TRUSS MANUFACTURER'S SEALED ENGINEERING INCLUDES TRUSS DESIGN, PLACEMENT PLANS, TEMPORARY AND PERMANENT BRACING DETAILS, TRUSS-TO-TRUSS CONNECTIONS, AND UPLIFT AND REACTION LOADS FOR ALL BEARING LOCATIONS.

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

GENERAL NOTES:

Live-Well Homes

Marvin & Page Anderson Res.

PROJECT ADDRESS: 434 SW Don Cook Way, Fort White, FL

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes

Live-Well Homes


Live-Well Homes



STEM WALL HEIGHT (FEET)	UNBALANCED BACKFILL HEIGHT	VERTICAL REINFORCEMENT FOR 8" CMU STEM WALL (INCHES O.C.)			VERTICAL REINFORCEMENT FOR 12" CMU STEM WALL (INCHES O.C.)		
		#5	#7	#8	#5	#7	#8
3.3	3.0	96	96	96	96	96	96
4.0	3.7	96	96	96	96	96	96
4.7	4.3	88	96	96	96	96	96
5.3	5.0	56	96	96	96	96	96
6.0	5.7	40	80	96	80	96	96
6.7	6.3	32	56	80	56	96	96
7.3	7.0	24	40	56	40	80	96
8.0	7.7	16	32	48	32	64	80
8.7	8.3	8	24	32	24	48	64
9.3	9.0	8	16	24	16	40	48

<p>MASONRY NOTE:</p> <p>MASONRY CONSTRUCTION AND MATERIALS FOR THIS PROJECT SHALL CONFORM TO ALL REQUIREMENTS OF "SPECIFICATION FOR MASONRY STRUCTURES" (ACI 318-11) AND ACI 308-11. THE CONTRACTOR AND MASON MUST IMMEDIATELY BEFORE PROCEEDING, NOTIFY THE ENGINEER OF ANY CONFLICTS BETWEEN ACI 308-11, 302 AND THESE DESIGN DRAWINGS. ANY EXCEPTION TO ACI 308-11, 302 MUST BE APPROVED BY THE ENGINEER IN WRITING.</p>	
<p>ACI308.1-102 Section</p>	<p>Specific Requirements</p>
<p>1.A Concrete strength</p>	<p>8" block bearing walls $F_m = 1500$ psi</p>
<p>1.B Mortar</p>	<p>ASTM C270, Type S</p>
<p>2.G Grout</p>	<p>ASTM C476, admixtures require approval</p>
<p>3.C CMU standard</p>	<p>ASTM C90, standard, Hollow, medium surface finish, 8"x8"x16" running bond and 12"x12"x16" 16" H+16" column block</p>
<p>3.B Gray brick standard</p>	<p>ASTM C216, Grade 3, Grade SW, Type FBS, S 2x4 7x7 11-12</p>
<p>2.A Reinforcing bars, #3-#11</p>	<p>ASTM A615, Grade 60, $F_y \geq 40$ ksi, Lap splice ≥ 40 bars dia.</p>
<p>2.AF Coating for corrosion protection</p>	<p>Envirotech, steel metal ties completely embedded in mortar or grout, ASTM A225, Class G60, 0.60 mil min. 304SS</p>
<p>2.AF Coating for corrosion protection</p>	<p>Joint reinforcement in walls exposed to moisture or wet areas, steel mesh that is not completely embedded in mortar or grout, ASTM A193, Class B2, 1/50 oz/ft² or 304SS</p>
<p>3.3.E.2 Pipes, conduits, and accessories</p>	<p>Any not shown on the project drawings require engineering approval.</p>
<p>3.3.E.7 Movement joints</p>	<p>Contractor assumes responsibility for type and location of movement joints if not installed on project drawings.</p>

BOTTOM OF EXTERIOR FOOTINGS SHALL BE A MINIMUM OF 12" BELOW UNDISTURBED SOIL OR ENGINEERED FILL




FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

FOUNDATION NOTES	
FN - 1	DIMENSIONS ON FOUNDATION & STRUCTURAL SHEETS ARE NOT EXACT; REFER TO ARCHITECTURAL PLANS FOR ACTUAL DIMENSIONS, RECESSES IN SLAB STEP DOWNS, ETC. DISOWAY DESIGN GROUP OR MARK DISOWAY, INC. IS NOT RESPONSIBLE FOR DIMENSION ERRORS ON THIS PLAN.
FN - 2	CONTRACTOR SHALL VERIFY NEED FOR INTERIOR BEARING IN ALL AREAS BY REVIEWING THE ROOF TRUSS PLAN (BY THE SUPPLIER) BEFORE FINALIZING FOUNDATION PLAN.
FN - 3	THE SLAB SHALL BE: 4" CONCRETE SLAB REINFORCED W/ 4 #4 WELDED BARS @ 18" ON CENTER, 6 MIL. @ 11 1/2" DEPTH OR FIBER MESH CONCRETE, 6-MIL. POLY VAPOR BARRIER W/ 8" LAPS SEALED W/ POLY TAPE OVER TERMITATE-TREATED & COMPACTED FILL (ALSO, ANY OTHER CODE REQUIRED TERMITATE-TREATMENT METHOD CAN BE USED INSTEAD).

FOUNDATION DESIGN: Size footings per truss reactions and other loads. Locate footings per truss bearings. Interior shear walls require a thickened slab footing. For point loads > 5000 lb or repetitive loads > 3000 lb per truss provide pad footing 1' x 1' sqft. #5, 8"oc each way per 1500 lb of load.



10/22/2023

Live-Well Homes

PROJECT ADDRESS:
434 SW Don Cook Way, Fort White, FL

FL PE 53915

This item has been digitally signed and sealed
Mark Disosway PE on digital signature date.
Printed copies of this document are not consid-
signed and sealed and the signature must be
verified on any electronic copies.

C=US, O=Florida
dnQualifier=A0
10C0000017E97
E07CA000746F
CN=Mark d
Disosway
2023-09-15 13:3
20

DIMENSIONS:
Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disoway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Disosway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering, comply with the 7th Edition Florida Building Code Residential (2020) to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.


Mark Disosway P.E.
163 SW Midtown Place
Suite 103
Lake City, Florida 32025
386.754.5419
disoswaydesign@gmail.com

JOB NUMBER:
231080

S-2
OF 6 SHEETS

LUMBER SIZE & GRADE MINIMUM REQUIREMENTS

RIDGE BOARD	2X6 SYP #2
RAFTER SPANS 20'-0" OR LESS	2X4 SYP #2
PURLINS / LATERAL BRACING	2X4 SPF #2
SLEEPERS	2X (WIDTH OF RAFTER SEAT CUT) SPF #3 OR 2 PARALLEL 2X4 SPF #3
CRIPPLES & BLOCKING	2X4 SPF #2 OR BETTER
TRUSS BELOW	SEE TRUSS DESIGN - SOUTHERN PINE MATERIAL



SECTION CUT PARALLEL TO VALLEY RAFTER

ROOF OVER FRAMING & BRACING DETAIL
SCALE: N.T.S.

VALLEY ROOF PLAN MEMBER LEGEND

== TRUSS
== TRUSS UNDER VALLEY FRAMING
--- VALLEY RAFTER OR RIDGE
--- CRIPPLE

CRIPPLES 4'-0" O.C. FOR 20 psf (TL) AND 10 psf (TD) (TYP. SHINGLE ROOF) MAX

CONNECTION REQUIREMENT NOTES


1	2X4 RAFTERS TO RIDGE	3-16d OR 6-131 x 3" TOE NAILS
2	CRIPPLE TO RIDGE	3-16d OR 6-131 x 3" FACE NAILS
3	CRIPPLE TO RAFTERS	3-16d OR 6-131 x 3" FACE NAILS
4	RAFTER TO SLEEPER OR BLOCKING	6-16d OR 12-131 x 3" TOE NAILS
5	SLEEPER TO TRUSS	4-16d OR 8-131 x 3" FACE NAILS EACH TRUSS
6	RIDGE BOARD TO ROOF BLOCK	3-16d OR 6-131 x 3" TOE NAILS
7	RIDGE BOARD TO TRUSS	3-16d OR 6-131 x 3" TOE NAILS
8	PURLIN TO TRUSS (TYP.)	3-16d OR 6-131 x 3" NAILS
9	PURLIN TO TRUSS (IF CRIPPLE IS ATTACHED TO PURLIN)	4-16d OR 6-131 x 3" NAILS
10	TRUSS TO BLOCKING	3-16d OR 6-131 x 3" END NAILS
11	CRIPPLE TO TRUSS	3-16d OR 6-131 x 3" FACE NAILS
12	CRIPPLE TO PURLIN	3-16d OR 6-131 x 3" FACE NAILS

GENERAL NOTES

MAXIMUM RAFTER SPANS:
6'-0" FOR 2X4, 8'-0" FOR 2X6 SPF #2 OR SYP #2.
MAXIMUM ROOF AREA PER SUPPORT:
1602 IN ZONES 2 & 3, 2402 IN ZONE 1, (EXAMPLE: 4'-0" O.C. X 4'-0" SPAN = 1602 OR 2'-0" X 8'-0" SPAN = 1602)
PURLINS REQUIRED 2'-0" O.C. IF EXISTING SHEATHING IS REMOVED.
PURLINS SHOULD OVERLAP SHEATHING ONE TRUSS SPACING MINIMUM.
IN CASES THAT THIS IS IMPRACTICAL, OVERLAP SHEATHING A MINIMUM OF 6" AND NAIL UPWARDS THROUGH SHEATHING INTO PURLIN WITH A MINIMUM OF 8-8d COMMON WIRE NAILS.
THIS DRAWING APPLIES TO VALLEYS WITH THE FOLLOWING CONDITIONS:
- SPANS (DISTANCES BETWEEN HEELS) 40'-0" OR LESS
- MAXIMUM VALLEY HEIGHT: 14'-0" OR LESS
- MAXIMUM WIND SPEED: 130 MPH
- MAXIMUM MEAN ROOF HEIGHT: 30 FEET
- MAXIMUM TOTAL LOADING: 40 psf
- MEETS FBC / ASCE 7-16 WIND REQUIREMENTS
- EXPOSURE CATEGORY "C", I = 1.0, Kd = 1.0
- ENCLOSED BUILDING

CRIPPLE, BRACING, & BLOCKING NOTES

2X4 CONTINUOUS LATERAL BRACE (CLB) MIN. IS REQUIRED FOR CRIPPLES 5'-0" TO 10'-0" LONG NAILS W/ 2-10d NAILS OR 2X4 "I" OR SCAB BRACE NAIL TO FLAT EDGE OF CRIPPLE WITH 8d NAILS @ 8" O.C. "I" OR SCAB MUST BE 90% OF CRIPPLE LENGTH. CRIPPLES OVER 10'-0" LONG REQUIRE TWO CLBS OR BOTH FACES W/ "I" OR SCAB. USE STRESS GRADED LUMBER & BOX OR COMMON NAILS.
- NARROW EDGE OF CRIPPLE CAN FACE RIDGE OR RAFTER, AS LONG AS THE PROPER NUMBER OF NAILS ARE INSTALLED INTO RIDGE BOARD.
- INSTALL BLOCKING UNDER RAFTER IF SLEEPERS ARE NOT USED.
- INSTALL BLOCKING UNDER CRIPPLES IF CRIPPLES FALL BETWEEN LOWER TRUSS TOP CHORDS AND LATERAL BRACING IS NOT USED.
- APPLY ALL NAILING IN ACCORDANCE TO NDS-1997 SECTION 12. NAILS ARE COMMON WIRE NAILS UNLESS NOTED OTHERWISE.




STRUCTURAL PLAN

SCALE: 1/4" = 1'-0"

STRUCTURAL PLAN NOTES

- SN-1 DIMENSIONS ON STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL FLOOR PLAN FOR ACTUAL DIMENSIONS
- PERMANENT TRUSS BRACING IS TO BE INSTALLED AT LOCATIONS AS SHOWN ON THE SEALED TRUSS DRAWINGS. LATERAL BRACING IS TO BE RESTRAINED PER BCS11-03, BCS1-B1, BCS1-B2, & BCS1-B3. BCS1-B1, BCS1-B2, & BCS1-B3 ARE FURNISHED BY THE TRUSS SUPPLIER, WITH THE SEALED TRUSS PACKAGE

HEADER LEGEND



UNLESS NOTED OTHERWISE (MINIMUM REQUIREMENTS) ***SEE STRUCTURAL PLAN FOR ANY SPECIFIC CALL OUTS***	
BEAM / HEADERS (SIZE)	ALL LOAD BEARING FRAME WALL & PORCH HEADERS SHALL BE A MINIMUM OF (2) 2X6 SP #2 (UNO)
HEADERS (JACK & KING STUDS)	ALL LOAD BEARING FRAME WALL HEADERS SHALL HAVE (1) JACK STUD & (1) KING STUD EACH SIDE (UNO)
HEADERS (STRAPPING)	ALL HEADERS w/ UPLIFT TO BE STRAPPED DOWN @ EACH SIDE WITH (1) LSTA24, 14-10d @ TOP & BOTTOM OF WALL WRAP UNDER BOTTOM PLATE & OVER TOP PLATE 1/2" X 10" ANCHOR BOLT w/ 3" X 3" X 1/4" WASHER MUST BE LOCATED WITHIN 6" OF KING STUD @ ALL DOOR LOCATIONS (UNO)
JACK STUDS UNDER GIRDER TRUSS	USE ONE JACK STUD GIRDER SUPPORT PER 2000 LB LOAD

ACTUAL vs REQUIRED SHEARWALL

	TRANSVERSE	LONGITUDINAL
ACTUAL	17436 LBF	11196 LBF
REQUIRED	10730 LBF	9054 LBF



Review for Code Compliance
Universal Engineering Science

Lawrence Pennell
Examiner-License No.

PX2707

10/22/2023

Live-Well Homes

Marvin & Page Anderson Res.

PROJECT ADDRESS:
434 SW Den Cook Way, Fort White, FL

FL PE 53915

This item has been digitally signed and sealed by Mark Disoway P.E. on digital signature date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

C=US, O=Florida, dnQualifier=A01410C0000017E97DE07CA000746F0, CN=Mark d Disoway
2023-09-15 13:34:38

DIMENSIONS:
Stated dimensions supersede scaled dimensions. Refer all questions to Mark Disoway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:
Mark Disoway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 7th Edition Florida Building Code Residential (2020) to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.

Mark Disoway P.E.
163 SW Midtown Place
Suite 103
Lake City, Florida 32025
386.754.5419
disowaydesign@gmail.com

JOB NUMBER:

231080

S-3

OF 6 SHEETS