The Mobile of the second of th

APPROVAL

T-MOBILE

NETWORK

BACKHAUL

OPERATIONS

PROPERTY OWNER OR REP.

CONSTRUCTION MANAGER

LAND USE PLANNER

T-MOBILE SITE NUMBER: 9JK0345B

T-MOBILE SITE NAME:

MICROWAVE T-MOBILE PROJECT:

BUSINESS UNIT #:

612 SOUTHWEST HILLIARD LANE **SITE ADDRESS:**

FORT WHITE, FL 32038

DATE

COUNTY: COLUMBIA GUYED TOWER

APPROVALS

SIGNATURE

SITE TYPE: 300'-0" **TOWER HEIGHT:**

T-MOBILE SITE NUMBER:


9JK0345B

BU #: **846216 FORT WHITE**

612 SOUTHWEST HILLIARD LANE FORT WHITE, FL 32038

EXISTING 300'-0" GUYED TOWER

ISSUED FOR:						
EV	DATE	DRWN	DESCRIPTION	DES./QA		
0	9/11/24	NQM	CONSTRUCTION	MD		



CROWN CASTLE USA INC. ROFESSIONAL ENGINEER LICENSE: #5789 COA #28970

IT IS A VIOLATION OF LAW FOR ANY PERSON, OF A LICENSED PROFESSIONAL ENGINEER,

SHEET NUMBER

REVISION

SITE INFORMATION

FORT WHITE

CROWN CASTLE USA INC.

BU NUMBER:

TOWER OWNER: CROWN CASTLE

2000 CORPORATE DRIVE CANONSBURG, PA 15317

29° 54' 31.23" / 29.90879

CARRIER/APPLICANT:

T-MOBILE 7025 AC SKINNER PKWY

JACKSONVILLE, FL 32256 SITE ADDRESS: 612 SOUTHWEST HILLIARD LANE

FORT WHITE, FL 32038

COUNTY:

LATITUDE: LONGITUDE:

-82° 40' 19.58" / -82.6721° LAT/LONG TYPE NAD83

GROUND ELEVATION:

AREA OF CONSTRUCTION: CURRENT ZONING:

MAP/PARCEL#:

OCCUPANCY CLASSIFICATION: U

TYPE OF CONSTRUCTION:

A.D.A. COMPLIANCE:

FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION

EXISTING

01-7S-16-04104-001

PROPERTY OWNER:

GLOBAL SIGNAL ACQUISITION ATLANTA, GA 30384-7455

COLUMBIA COUNTY 135 NE HERNANDO AVE. SUITE-21 JURISDICTION:

LAKE CITY FL 32055

ELECTRIC PROVIDER:

CLAY ELECTRIC CO-OP

PROJECT TEAM

A&E FIRM

2000 CORPORATE DRIVE CANONSBURG, PA 15317

CROWN CASTLE USA INC. CONTACTS:

2000 CORPORATE DRIVE CANONSBURG, PA 15317

KEVIN DEPATIE - PROJECT MANAGER KEVIN.DEPATIE@CROWNCASTLE.COM

NITSA CRENSHAW - AES

NITSA.CRENSHAW@CROWNNCASTLE.COM

PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE CROWN NOC AT (800) 788-7011 & CROWN CONSTRUCTION MANAGER

C-2 TOWER ELEVATIONS C-3 ANTENNA PLANS MICROWAVE MOUNTING DETAILS AND SPECIFICATIONS C-4

DRAWING INDEX

SHEET DESCRIPTION

SHEET #

T-1

T-2

TITLE SHEET

SITE PLAN

GENERAL NOTES

THE PARTIES ABOVE HEREBY APPROVE AND ACCEPT THESE DOCUMENT AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL CONSTRUCTION DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND ANY CHANGES AND MODIFICATIONS THEY MAY IMPOSE

PROJECT DESCRIPTION

CONNECTIVITY AND CAPACITY TO THE EXISTING ELIGIBLE

• INSTALL (2) CERAGON - FIBEAIR IP-20A RFU-D-HP ODUS

• INSTALL (2) COMMSCOPE - LDF4-50A CABLES (1/2")



REFERENCE DOCUMENTS: STRUCTURAL ANALYSIS: MORRISON HERSHFIELD DATED: 7/25/24

SITE DESIGN CRITERIA:

EXPOSURE CATEGORY: RISK CATEGORY: TOPOGRAPHIC CATEGORY:

CREST HEIGHT:

SEISMIC RESPONSE: NA

MECHANICAL

ELECTRICAL.

MOUNT ANALYSIS: TRYLON DATED: 7/17/24

ORDER ID: 672918

LOCATION MAP

NO SCALE

APPLICABLE CODES &

REFERENCE DOCUMENTS

2023 FLORIDA BUILDING CODE 8TH

2023 FLORIDA BUILDING CODE 8TH

2023 FLORIDA BUILDING CODE 8TH

WIND SPEED: V = 121 MPH (ULTIMATE 3 SECOND GUST)

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN

ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK

EDITION/2021 IBC

EDITION/2021 IMC

EDITION/2020 NEC

APPLICABLE CODES: TIA-222-H / ASCE 7-16

MICROWAVE PATH: DATED: 4/5/24

NOT CONFORMING TO THESE CODES:


THE PURPOSE OF THIS PROJECT IS TO ENHANCE BROADBAND WIRELESS FACILITY.

- INSTALL (1) ANDREW-COMMSCOPE VHLP4-11W/A MICROWAVE DISH

- INSTALL (2) ERICSSON NTM 201 3929/2 56.9MM (2-1/8")

CROWN CASTLE USA, INC.

ALL DRAWINGS CONTAINED HEREIN ARE FORMATTED FOR 11X17. CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.



CROWN CASTLE USA INC. SITE ACTIVITY REQUIREMENTS:

- NOTICE TO PROCEED- NO WORK SHALL COMMENCE PRIOR TO CROWN CASTLE USA INC. WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE CROWN CASTLE USA INC. NOC AT 800-788-7011 & THE CROWN CASTLE USA INC. CONSTRUCTION MANAGER.
- "LOOK UP" CROWN CASTLE USA INC. SAFETY CLIMB REQUIREMENT: "LOOK UP" — CROWN CASTLE USA INC. SAFETY CLIMB REQUIREMENT:
 THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE
 CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT
 REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR
 FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE
 STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF
 THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH
 MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS
 INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT
 AND REPORTED TO YOUR CROWN CASTLE USA INC. POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB
 MAINTENANCE AND CONTRACTOR NOTICE TICKET.
- PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISD REQUIREMENTS.

 ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING
- PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANS/ASSE A10.48 (LATEST EDITION): FEDERAL STATE, AND LOCAL REQULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND CROWN CASTLE USA INC. STANDARD CED-STD-10253 INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
- ALL SITE WORK TO COMPLY WITH QAS-STD-10068 "INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON CROWN CASTLE USA INC. TOWER SITE," CED-STD-10294 "STANDARD FOR INSTALLATION OF MOUNTS AND APPURTENANCES," AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS. THE CONTRACTOR
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY CROWN CASTLE USA INC. PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.

 ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REQULATIONS AND ORDINANCES. ROUTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.

 THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES PRIOR TO THE START OF CONSTRUCTION.
- ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR EXTERME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW, THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
- ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND PROJECT SPECIFICATIONS LATEST APPROVED REVISION
- SPECIFICATIONS, CATEST APPROVED REVISION.

 CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK, IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
- ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL
- OF CONTRACTOR, TOWER OWNER, CROWN CASTLE USA INC., AND/OR LOCAL UTILITIES.

 THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS,
- THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT
- 16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED
- THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL
- MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION
- OF OWNER.
- CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION, TRASH AND DEBRIS SHOULD BE REMOVED
- 22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW

GENERAL NOTES:

FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY: CONTRACTOR: GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION CARRIER: T-MOBILE

TOWER OWNER: CROWN CASTLE USA INC. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY

WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.

THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDIRES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINETHED STRUCTURE ONLY. NOTES AND DETAILS AND SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE PROJECT, SIMILAR WORK ON THE PROJECT,

DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT,
AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS,
GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER
CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO
ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY
OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE
CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS.
IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE
ENGINEER OF RECORD IS TO BE NOTHIFIED AS SOON AS POSSIBLE.
PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE
EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION
DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CROWN CASTLE.
ALL MATERIALS FURNISHED AND INSTALLED SHALL BESING STRICT ACCORDANCE WITH ALL APPLICABLE CODES,
REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS,
ORDINANCES, RULES, REQULATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REQULATIONS,
UNLESS NOTED OTHERWISE. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND

UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.

THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND CROWN CASTLE PRIOR TO PROCEEDING

WITH ANY SUCH CHANGE OF INSTALLATION.

CONTRACTOR IS TO PERFORM A SITE INVESTIGATION AND IS TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN

JRAWINGS. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEM<mark>ENTS, PAVEMENTS, CURBS, LAND</mark>SCAPING AND STRUCTURES. ANY

DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF CROWN CASTLE USA INC. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY, ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.

CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

- ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST—IN—PLACE CONCRETE.
 UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
- ALL CONCEPTE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90'F AT TIME OF PLACEMENT
- CONCRETE EXPOSED TO FREEZE—THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER—TO—CEMENT RATIO (W/C) OF 0.45.
- ALL STELL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE #4 BARS AND SMALLER.....

ON DRAWINGS CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH...
CONCRETE EXPOSED TO EARTH OR WEATHER:

#6 BARS AND LARGER...... #5 BARS AND SMALLER.... CONCRETE NOT EXPOSED TO EARTH OR WEATHER:

SLAB AND WALLS... BEAMS AND COLUMNS.

A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

GREENFIELD GROUNDING NOTES:

OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

- ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN
- THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.

 THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE
- METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT
- COMMINS.

 METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED
- WITH THE POWER CIRCUITS TO BTS FOUIPMENT. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
- ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
 ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
 USE OF 90' BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45' BENDS CAN BE ADEQUATELY SUPPORTED.
 EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
 ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
 COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
 ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.

- APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.

 ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.

 MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
- MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND KING, IN ACCORDANCE WITH THE NEC.

 BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTORS.

 GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDUITORS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONNETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.

 ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION.
- POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).

 BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY)

ELECTRICAL INSTALLATION NOTES:

- ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE

- ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.

 CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.

 WIRNING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.

 ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.

 1. ALL GOUIPMENT SHALL BEAR THE UNDERWRITERS LABBRATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.

 2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERYIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.

 EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH CUTY.
- LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND
- PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
 ALL TIE WRAPS SHALL BE CUT FLUSH WITH APPROVED CUTTING TOOL TO REMOVE SHARP EDGES.
- ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS
- OTHERWISE SPECIFIED.

 POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH
 TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.

 ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND
 BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75 C (90° C IF AVAILABLE).

 RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE
- AND NEC.
- ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR
- ELECTRICAL METALLIC TUBING (EMT) OR METAL—CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.

 UNDERGROUND CONDUIT SHALL BE SCHEDULE 40 PVC ON STRAIGHTS AND SCHEDULE 80 PVC UNDER ALL TRAFFIC EASEMENTS AND ALL ELBOWS/90S. ABOVE GRADE CONDUIT TO BE SCH 80 PVC OR IMC/RMC CONDUIT. EMT IS ALLOWED AT STUB UF LOCATIONS AND INDOORS ONLY.
- LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
- OCCURS OF FLEXIBILITY IS NEEDED.
 CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION—TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE
- CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND
- MIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS
- WIREMAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMAYL).

 SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).

 CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER—ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERFENDICULAR TO STRUCTURE WALL AND CELING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON DUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON DUSHINGT, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY—COATED SHEET STEFT SHALL METER OR EXCEPT LIST ON AND NEMA 3.6 (OR
- STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3R (OR BETTER) FOR EXTERIOR LOCATIONS.

 METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY—COATED OR NON—CORRODING; SHALL MEET OR
- EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED
- NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.

 THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR CROWN CASTLE USA INC.
 BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
- BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.

 THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY. 28.

APWA UNIFORM COLOR CODE:

TEMPORARY SURVEY MARKINGS LECTRIC POWER LINES, CABLES,

CONDUIT. AND LIGHTING CABLES

GAS. OIL, STEAM, PETROLEUM, OR

RECLAIMED WATER, IRRIGATION, AND SLURRY LINES

SEWERS AND DRAIN LINES

COMMUNICATION, ALARM OR SIGNAL LINES. CARLES OR CONDUIT AND TRAFFIC LOOPS

WHITE PROPOSED EXCAVATION

YELLOW GAS, OIL, STEAM, CASEOUS MATERIALS

POTABLE WATER

INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "T-MOBILE".

ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.

SYSIEM	CONDUCTOR	COLOR	
	A PHASE	BLACK	
120/240V, 1Ø	B PHASE	RED	
120/2400, 12	NEUTRAL	WHITE	
	GROUND	GREEN	
	A PHASE	BLACK	
	B PHASE	RED	
120/208V, 3Ø	C PHASE	BLUE	
	NEUTRAL	WHITE	
	GROUND	GREEN	
	A PHASE	BROWN	
	B PHASE	ORANGE OR PURPLE	
277/480V, 3Ø	C PHASE	YELLOW	
	NEUTRAL	GREY	
	GROUND	GREEN	
DC VOLTAGE	POS (+)	RED**	
DC VOLIAGE	NEG (-)	BLACK**	

RFDS RRH RRU SIAD TMA TYP UMTS W.P.

ABBRE'	<u>VIATIONS:</u>
(E) FIF	ANTENNA EXISTING FACILITY INTERFACE FRAME GENERATOR
GPS	GLOBAL POSITIONING SYSTEM
GSM LTE	GLOBAL SYSTEM FOR MOBILE LONG TERM EVOLUTION
MGB MW	MASTER GROUND BAR MICROWAVE
(N)	NEW
NEC	NATIONAL ELECTRIC CODE
(P) PP	PROPOSED POWER PLANT
QTY	QUANTITY
RECT RBS	RECTIFIER RADIO BASE STATION
RET	REMOTE ELECTRIC TILT
RFDS	RADIO FREQUENCY DATA SHEET

REMOTE RADIO HEAD

REMOTE RADIO UNIT SMART INTEGRATED DEVICE TOWER MOUNTED AMPLIFIER UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM WORK POINT




T-MOBILE SITE NUMBER: 91K0345B

> BU #: **846216 FORT WHITE**

612 SOUTHWEST HILLIARD LANE FORT WHITE, FL 32038

EXISTING 300'-0" GUYED TOWER

 _				
		ISSU	ED FOR:	•
REV	DATE	DRWN	DESCRIPTION	DES./QA
0	9/11/24	NQM	CONSTRUCTION	MD




PROFESSIONAL ENGINEER LICENSE: #57890 COA #28970

IT IS A VIOLATION OF LAW FOR ANY PERSON UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER,

SHEET NUMBER:

REVISION








T-MOBILE SITE NUMBER: 9JK0345B

> BU #: **846216** FORT WHITE

612 SOUTHWEST HILLIARD LANE FORT WHITE, FL 32038

EXISTING 300'-0" GUYED TOWER

	ISSUED FOR:				
REV	DATE	DRWN	DESCRIPTION	DES./QA	
0	9/11/24	NQM	CONSTRUCTION	MD	



CROWN CASTLE USA INC. PROFESSIONAL ENGINEER LICENSE: #57890

COA #28970


IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

SHEET NUMBER:

REVISION:

SITE PLAN 1) SCALE: 4' 3' 2' 1' 0 1/4"=1'-0" (FULL SIZE) 4' 1/8"=1'-0" (11x17)





T Mobile




T-MOBILE SITE NUMBER: 9JK0345B

> BU #: **846216 FORT WHITE**

612 SOUTHWEST HILLIARD LANE FORT WHITE, FL 32038

EXISTING 300'-0" GUYED TOWER

Г	ISSUED FOR:				
REV	DATE	DRWN	DESCRIPTION	DES./QA	
0	9/11/24	NQM	CONSTRUCTION	MD	




CROWN CASTLE USA INC. PROFESSIONAL ENGINEER LICENSE: #57890 COA #28970


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

REVISION:







INSTALLER NOTE:

TWIST AND SWAY LIMITATIONS OF TIA 222 G ANNEX D FOR THIS DISH MEET BOTH THE ALLOWABLE 3 DB DEGRADATION AND THE 10 DB DEGRADATION LIMIT.





T Mobile




T-MOBILE SITE NUMBER: 9JK0345B

> BU #: **846216** FORT WHITE

612 SOUTHWEST HILLIARD LANE FORT WHITE, FL 32038

EXISTING 300'-0" GUYED TOWER

	ISSUED FOR:				
REV	DATE	DRWN	DESCRIPTION	DES./QA	
0	9/11/24	NQM	CONSTRUCTION	MD	




CROWN CASTLE USA INC. PROFESSIONAL ENGINEER LICENSE: #57890 COA #28970


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SHEET NUMBER:

REVISION:




MICROWAVE & ODU MOUNTING DETAIL SCALE: NOT TO SCALE






MICROWAVE SPECS			
MANUFACTURER	COMMSCOPE		
MODEL #	VHLP4-11W/A		
ØxD	50.8"ø x 30.2"		
WEIGHT	71.0 LBS		

COMMSCOPE - VHLP4-11W/A 2 SCALE: NOT TO SCALE





ODU SPECS		
MANUFACTURER	CERAGON	
MODEL #	FIBEAIR IP-20A RFU-D-HP	
HxWxD	12.6" x 11.3" x 4.2"	
WEIGHT	26.5 LBS	

CERAGON - FIBEAIR IP-20A RFU-D-HP SCALE: NOT TO SCALE

NOT USED

SCALE: NOT TO SCALE

T Mobile




T-MOBILE SITE NUMBER: 9JK0345B

> BU #: **846216** FORT WHITE

612 SOUTHWEST HILLIARD LANE FORT WHITE, FL 32038

EXISTING 300'-0" GUYED TOWER

\bigcap	ISSUED FOR:				
REV	DATE	DRWN	DESCRIPTION	DES./QA	
0	9/11/24	NQM	CONSTRUCTION	MD	



CROWN CASTLE USA INC.

PROFESSIONAL ENGINEER LICENSE: #57890
COA #28970

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

SHEET NUMBER:

REVISION:

NOT USED SCALE: NOT TO SCALE

NOT USED (4) SCALE: NOT TO SCALE


iQ.link — Link Budget Report

Date Printed: 05-APR-2024 Create Date: 05-APR-2024 Link ID: 3011892

Link Name: 9JK0174A_9JK0345B

Region: South

Created By: CVance5



Path length (6.76 mi)

9JK0174A			
Latitude:	29-57- 5.4 N		
Longitude:	82-34-14.6 W		
Azimuth:	244.15 Deg		
Elevation:	150.92 ft		

Frequency (GHz) = 11.00 GHz								
K1:	1.33							
%F1:	0.60							
K2:	0.67							
%F2:	0.30							

9JK0345B								
Latitude:	29-54-31.2 N							
Longitude:	82-40-19.6 W							
Azimuth:	64.10 Deg							
Elevation:	75.46 ft							

Antenna CL: 194.00 ft AGL	K3: 1.33	Antenna CL: 250.00 ft AGL	
	%F3: 1.00		

	Transmission details	
SITE ID:	9JK0174A	9JK0345B
[CLUSTER_ID_LABEL]:	[CLUSTER_ID_A]	[CLUSTER_ID_B]
[CALL_SIGN_LABEL]:	[CALL_SIGN_A]	[CALL_SIGN_B]
ASR #:		
AAV_CONTRACT_ID:	ATT224	WST185-
AAV_CONTRACT_STATUS:	Selected	Selected
Ethernet Installed:	Ethernet	Ethernet
Latitude:	29-57- 5.4 N	29-54-31.2 N
Longitude:	82-34-14.6 W	82-40-19.6 W
Azimuth (deg):	244.15 Deg	64.10 Deg
Vertical angle (deg):	0.07 Down	0.01 Down
Elevation:	150.92 ft	75.46 ft
Antenna model:	VHLP4-11WA	VHLP4-11WA
Antenna manufacturer:	ANDREW CORPORATION	ANDREW CORPORATION
Antenna ld:	228	228
Antenna gain (dBi):	40.70 dBi	40.70 dBi
Antenna diameter:	3.94 ft	3.94 ft
Antenna CL:	194.00 ft AGL	250.00 ft AGL
Diversity Antenna model:		
Diversity Antenna manufacturer:		
Diversity Antenna Id:		
Diversity Antenna gain (dBi):		
Diversity Antenna diameter:		
Diversity Antenna CL:		
Branch Loss Tx/Rx (dB):	4.60/4.60	4.60/4.60
Attenuator Common/Tx/Rx (dB):		
Waveguide #1 Model, Len, Loss(dB):		
Waveguide #2 Model, Len, Loss(dB):		
Waveguide #3 Model, Len, Loss(dB):		

Total Waveguide Loss (dB):							
Other Losses (dB):	0.00	0.00					
Frequency (GHz):	11.00 GHz						
Path length:	6.76 mi						
Free space loss (dB):	134.0)1 dB					
Atmospheric absorption loss (dB):	0.16	6 dB					
Obstruction Loss (dB):	0.00 dB	(oLOS)					
Field margin (dB):	1.00) dB					
Net path loss (dB):	58.37 dB	58.37 dB					
Configuration:	4+0/DP/DM	4+0/DP/DM					
Radio model:	IP20D-HP11-80X-A_4501	IP20D-HP11-80X-A_4501					
Radio manufacturer:	Ceragon Networks	Ceragon Networks					
Radio Id:	754	754					
Frequency Plan: Frequency (MHz):	High: N/A	Low: N/A					
Polarization:	N/A	N/A					
Emission designator:	80M0D7W	80M0D7W					
Climatic factor:	1.00						
Terrain roughness factor:	2.:	26					
Average annual temperature:	68.26	degF					
Design Path Polarity:	Veri	tical					
Rain region:	Jacksonvi	lle, Florida					
0.01% Rain Rate:	72.9 mm/hr						
	Passive Repeaters						
Antenna model:							
Antenna manufacturer:							
Antenna height:							

Modulation / Throughput	, ,		EIRP A/B (dBm)		Receive Signal A/B (dBm)		Composite Fade Margin A/B (dB)		Radio Threshold/ ACM Drop Level A/B (dBm)	
BPSK 67.00 Mbps	36.00	36.00	72.10	72.10	-25.97	-25.97	59.33	59.33	-86.30	-86.30

4QAM 136.00 Mbps	36.00	36.00	72.10	72.10	-25.97	-25.97	53.53	53.53	-80.50	-80.50
8QAM 195.00 Mbps	36.00	36.00	72.10	72.10	-25.97	-25.97	49.83	49.83	-76.80	-76.80
16QAM 279.00 Mbps	35.00	35.00	71.10	71.10	-26.97	-26.97	45.83	45.83	-73.80	-73.80
32QAM 368.00 Mbps	35.00	35.00	71.10	71.10	-26.97	-26.97	42.43	42.43	-70.40	-70.40
64QAM 451.00 Mbps	34.00	34.00	70.10	70.10	-27.97	-27.97	38.53	38.53	-67.50	-67.50
128QAM 533.00 Mbps	33.00	33.00	69.10	69.10	-28.97	-28.97	34.53	34.53	-64.50	-64.50
256QAM 614.00 Mbps	32.00	32.00	68.10	68.10	-29.97	-29.97	30.83	30.83	-61.80	-61.80
512QAM 675.00 Mbps	32.00	32.00	68.10	68.10	-29.97	-29.97	28.13	28.13	-59.10	-59.10
1KLQAM 735.00 Mbps	31.00	31.00	67.10	67.10	-30.97	-30.97	23.93	23.93	-55.90	-55.90
1KHQAM 780.00 Mbps	31.00	31.00	67.10	67.10	-30.97	-30.97	23.53	23.53	-55.50	-55.50
2KQAM 826.00 Mbps	31.00	31.00	67.10	67.10	-30.97	-30.97	20.63	20.63	-52.60	-52.60

Modulation/Throughput	Worst Mont	h Multipath	Worst Month Rain		Annual Multipath		Annual Rain		Total Annual		Total Active in Mode	
	(100-%)	(s)	(100-%)	(s)	(100-%)	(s)	(100-%)	(s)	(100-%)	(s)	(100-%)	(s)
BPSK 67.00 Mbps	99.999996	0.12	99.998255	45.85	99.999998	0.48	99.999798	63.66	99.999797	64.14	0.000122	38.34
4QAM 136.00 Mbps	99.999983	0.45	99.997402	68.28	99.999994	1.83	99.999681	100.65	99.999675	102.48	0.000125	39.33
8QAM 195.00 Mbps	99.999960	1.05	99.996592	89.57	99.999986	4.30	99.999564	137.51	99.999550	141.81	0.000205	64.75
16QAM 279.00 Mbps	99.999900	2.63	99.995366	121.77	99.999966	10.79	99.999379	195.77	99.999345	206.56	0.000268	84.58
32QAM 368.00 Mbps	99.999781	5.76	99.993921	159.77	99.999925	23.60	99.999152	267.53	99.999077	291.13	0.000493	155.53
64QAM 451.00 Mbps	99.999462	14.15	99.991587	221.10	99.999816	57.94	99.998767	388.72	99.998584	446.66	0.000879	277.11
128QAM 533.00 Mbps	99.998648	35.53	99.988117	312.29	99.999539	145.54	99.998166	578.23	99.997705	723.77	0.001467	462.67
256QAM 614.00 Mbps	99.996830	83.30	99.983468	434.45	99.998918	341.17	99.997320	845.27	99.996238	1186.44	0.001838	579.50
512QAM 675.00 Mbps	99.994098	155.11	99.978710	559.50	99.997986	635.29	99.996415	1130.65	99.994400	1765.94	0.005415	1707.80
1KLQAM 735.00 Mbps	99.984475	407.99	99.968058	839.43	99.994701	1670.97	99.994283	1802.76	99.988985	3473.74	0.000783	246.90
1KHQAM 780.00 Mbps	99.982977	447.36	99.966742	874.02	99.994190	1832.19	99.994012	1888.45	99.988202	3720.64	0.007983	2517.36
2KQAM 826.00 Mbps	99.966808	872.27	99.955121	1179.43	99.988672	3572.48	99.991548	2665.52	99.980219	6238.01	99.980219	31529761.99

Multipath fading method - VIGANTS Rain fading method - Crane City/Jacksonville, Florida