

BEARING HEIGHT SCHEDULE

8'-0"

OVERHANG

1'-0"

ROOF PITCH(S)

7/12

NOTES :

- 1) REFER TO HDG 94 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACKS) REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACKS REQUIRED
- 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V05 FOR ALTERNATE BRACING REQUIREMENTS
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER
- 4) ALL TRUSSES ARE DESIGNED FOR 2' o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED
- 6) SY#2 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP
- 7) ALL ROOF TRUSS HANGERS TO BE SIMPSON HES36 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSS HANGERS TO BE SIMPSON THA422 UNLESS OTHERWISE NOTED
- 8) BEAM/ACER/LINTEL (HBR) TO BE FURNISHED BY BUILDER

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND V05S. ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

Equipped Delivery Date: _____

Approved By: _____ Date: _____



PHONE: 904-437-3546 FAX: 904-437-3494

Jacksonville

PHONE: 904-772-6100 FAX: 904-772-1973

Lake City

PHONE: 386-755-6894 FAX: 386-755-7973

Sanford

PHONE: 407-322-0099 FAX: 407-322-5593

BUILDER: **KOUNS BUTLER BUILDERS**

LEGAL ADDRESS: **COLUMBIA, FL**

MODEL: **CUSTOM**

DATE: **09/07/07** DRAWN BY: **A** SCALE: **NTS**

MONDRA GONZALEZ