20178
For Office Use Only Application # 1909-63 Date Received 91 19 By M6 Permit # 38678
Zoning Official /// / Date 9-19-19 Flood Zone X Land Use 49 Zoning 41-5
FEMA Map # N/A Elevation N/A MFE Above River N/A Plans Examiner 1.C. Date 9-23-19
Comments Floor 1' Above Rd. , NON Habi Fable Stoucture
NOC Deed of PA Dev Permit # In Floodway Letter of Auth. from Contractor
□ F W Comp. letter □ Owner Builder Disclosure Statement □ Land Owner Affidavit □ Ellisville Water ♣App Fee Paid
Site Plan (Denv. Health Approval 19 0720 to Sub VF Form 9.27.19 Fox 386-755-1220
Applies of (Who will sign/pickup the permit) Mike Todd Phone 386-755-4387
Applicati (Allo Alli sign/bickob ine benim)
Address 129 NE Colbain AVC LANCE CITY TE 200
Owners Name Robert + Andrea Smith Phone 386-303-2667
911 Address 2872 NW Brown Rd. LAKE City FL 32055
Contractors Name Mike Todd Construction Inc. Phone 386-755-4387
Address 129 NE Colburn que LAKE City FL 3205T
Contractor Email Mike & mike todd construction, com ***Include to get updates on this job.
Fee Simple Owner Name & Address
Bonding Co. Name & Address
Architect/Engineer Name & Address Marty J. Humphries 7932 240th st O'Brien FL 32071
Mortagae Lenders Name & Address
Circle the correct power company FL Power & Light Clay Elec. Suwannee Valley Elec. Duke Energy Cal
Property ID Number 20-35-16-02203-002 Estimated Construction Cost 52,000
Subdivision NameN/aLotBlockUnitPhase
Driving Directions from a Major Road 90 to to Brown Rd, 90 right about 3 miles,
Address is on the Left
Construction ofCANDONT DetacludCommercial ORResidential
Construction of CAMPON Sequence: Exxon) CAMPONT
Type of Subclore (module, module from the module)
Use/Occupancy of the building now N/A Is this changing
If Yes, Explain, Proposed Use/Occupancy
Is the building Fire Sprinkled? NO If Yes, blueprints included Or Explain NA ACNEASE
Entrance Changes (Ingress/Egress) NO If Yes, Explain
Zoning Applications applied for (Site & Development Plan, Special Exception, etc.)
Revised 7-1-15

Columbia County Building Permit Application

CODE: Florida Building Code 2017 6th Edition and the 2014 National Electrical Code.

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

TIME LIMITATIONS OF APPLICATION: An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless pursued in good faith or a permit has been issued.

TIME LIMITATIONS OF PERMITS: Every permit issued shall become invalid unless the work authorized by such permit is commenced within **180** days after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of 180 days after the time work is commenced. A valid permit receives an approved inspection every 180 days. Work shall be considered not suspended, abandoned or invalid when the permit has received an approved inspection within 180 days of the previous approved inspection.

FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment: According to Florida Law, those who work on your property or provide materials, and are not paid-in-full, have a right to enforce their claim for payment against your property. This claim is known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look to your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

NOTICE OF RESPONSIBILITY TO CONTRACTOR AND AGENT: YOU ARE HEREBY NOTIFIED as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that result in ponding of water, or other damage to roadway and other public infrastructure facilities caused by you or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

OWNERS CERTIFICATION: I CERTIFY THAT ALL THE FOREGOING INFORMATION IS ACCURATE AND THAT ALL WORK WILL BE DONE IN COMPLIANCE WITH ALL APPLICABLE LAWS REGULATING CONSTRUCTION AND ZONING.

NOTICE TO OWNER: There are some properties that may have deed restrictions recorded upon them. These restrictions may limit or prohibit the work applied for in your building permit. You must verify if your property is encumbered by any restrictions or face possible litigation and or fines.

rint Owners Name Owners Signatu

**Property owners <u>must sign</u> here <u>before</u> any permit will be issued.

**If this is an Owner Builder Permit Application then, ONLY the owner can sign the building permit when it is issued.

CONTRACTORS AFFIDAVIT: By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit including all application and permit time limitations.

Contractor's License Number CGC 209

Contractor's Signature

Columbia County
Competency Card Number 539

Affirmed under penalty of perjury to by the Contractor and subscribed before me this 8 day of 20 10

Personally known or Produced Identification

State of Florida Notary Signature (For the Contractor)

GRACE MARIE THOMAS

Notary Public - State of Florida

Commission # GG 346366

My Comm. Expires Jun 18. 2023

NOTICE OF COMMENCEMENT

Tax Parcel Identification Number:

20-35-16-02203-002

Clerk's Office Stamp

My Comm. Expires Jun 18, 2023

Inst: 201912022013 Date: 09/19/2019 Time: 1:50PM Page 1 of 1 B: 1394 P: 2606, P.DeWitt Cason, Clerk of Court

Columbia, County, By: BD

Deputy Clerk

M. C. No. 912.12
THE UNDERSIGNED hereby gives notice that improvements will be made to certain real property, and in accordance with Section 713.13 of the Florida Statutes, the following information is provided in this NOTICE OF COMMENCEMENT .
1. Description of property (legal description): a) Street (job) Address: 2872 Nw Brown Rd Lake City FL. 3205-5
2. General description of improvements: CAPPORT
3. Owner Information or Lessee information if the Lessee contracted for the improvements: a) Name and address: Robert Andrea Swith 2872 NW Brown Rd Lake City FL 3 2055 b) Name and address of fee simple titleholder (if other than owner) c) Interest in property DWH CAS
4. Contractor Information a) Name and address: Mike Toda Construction 129 NE Colburn Ave Lake G& Ft. 32.057
5. Surety Information (if applicable, a copy of the payment bond is attached):
P) VANORING OF ROUGH
c) Telephone No.:
6. Lender a) Name and address: N/A
b) Phone No
713.13(1)(a)7., Florida Statutes: - (1) Construction 129 NE Colburn Ave Lake C. & FL 32055
7. Person within the State of Florida designated by Owner apon which is a 129 NE Colburn Ave Lake C. & FL. 32055 a) Name and address: Mike Todd Construction 129 NE Colburn Ave Lake C. & FL. 32055 b) Telephone No.: 386-755-4387
8. In addition to himself or herself, Owner designates the following person to receive a copy of the Lienor's Notice as provided in
Section 713.13(I)(b), Florida Statutes:
8. In addition to himself or herself, Owner designates the following person to receive a copy of the deficiency of the d
b) Telephone No.:
 Expiration date of Notice of Commencement (the expiration date will be 1 year from the date of recording unless a different date is specified):
WARNING TO OWNER: ANY PAYMENTS MADE BY THE OWNER AFTER THE EXPIRATION OF THE NOTICE OF COMMENCEMENT ARE CONSIDERED IMPROPER PAYMENTS UNDER CHAPTER 713, PART I, SECTION 713.13, FLORIDA STATUTES, AND CAN RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY; A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT YOUR LENDER OR AN ATTORNEY BEFORE COMMENCING WORK OR RECORDING YOUR NOTICE OF COMMENCEMENT.
STATE OF FLORIDA COUNTY OF COLUMBIA 10. Signature of Owner or Lessee, or Owner's or Lessee's Authorized Office/Director/Partner/Manager
Mike Fill - Contactor Printed Name and Signatory's Title/Office
The foregoing instrument was acknowledged before me, a Florida Notary, this 8 day of Sept. 20 9 by: Stace Notary for 1 to Toda (Name of Person) (Type of Authority) (name of party on behalf of whom instrument was executed)
Personally Known Or Produced Identification Type
Notary Signature State of Fioric Commission # GG 346366

SUBCONTRACTOR VERIFICATION

APPLICATION/PERMIT #

THIS FORM MUST BE SUBMITTED BEFORE A PERMIT WILL BE ISSUED

Columbia County issues combination permits. One permit will cover all trades doing work at the permitted site. It is REQUIRED that we have records of the subcontractors who actually did the trade specific work under the general contractors permit.

NOTE: It shall be the responsibility of the general contractor to make sure that all of the subcontractors are licensed with the Columbia County Building Department.

Use website to confirm licenses: http://www.columbiacountyfla.com/PermitSearch/ContractorSearch.aspx

NOTE: If this should change prior to completion of the project, it is your responsibility to have a corrected form submitted to our office, before that work has begun.

Violations will result in stop work orders and/or fines.

Violations will r	esult in stop work orders and/or fines.	
		Need
ELECTRICAL	Print Name MAH Burns Electric Signature	□ Lic □ Liab
	Company Name: MAH Burns Electric	□ W/C
	Company Name: 77/77/ Ditty 2	□ EX
CC#	License #: EC 1300 6731 Phone #: 366 - 8948	E DE
	Print Name Signature	Need Lic
MECHANICAL/	Print Name 3.g.matevo	🗆 Liab
A/C	Company Name:	□ W/C
CC#	License #:Phone #:	□ DE
	Print Name Don Bitts Signature Don Britis	Need ☐ Lic
PLUMBING/		□ Uab
GAS	Company Name: Honchus Dlumbing	□ w/c
	License #:	☐ EX ☐ DE
CC#	License #: CFUPA 0 4/0	Need
ROOFING	Print Name Mike Todd Const. Signature Signature	□ Uc □ Liab
	Company Name: Mike Todd Construction	□ Liab
-2Q	Change # 26/ - 755-4387	□ EX
cc# <u>539</u>	License #: <u>C&C 006 209</u> Phone #: <u>386 - 755 - 4387</u>	□ DE Need
SHEET METAL	Print NameSignature	☐ Lic
		□ Liab □ W/C
	Company Name:	□ EX
CC#	License #:Phone #:	□ DE
SIDE CYCTERA!	Print NameSignature	Need Lic
FIRE SYSTEM/	Print Name	□ Liab
SPRINKLER	Company Name:	□ W/C
CC#	License#: Phone #:	□ DE
	1	Need
SOLAR	Print Name Signature	☐ Liab
1 1	Company Name:	. □ W/C
CC#	License #: Phone #:	D DE
- CC#		Need
STATE	Print NameSignature	□ Lic □ Liab
-		□ W/C
SPECIALTY	Company Name:	D EX
CC#	License #: Phone #:	DE DE

Legend

Parceis

2018Aerials

Roads

Roads

others

Dirt 💮

Interstate

Main

Other

Paved

Private

SectionTownshipAndRange

SRWMD Wetlands

2018 Flood Zones

0.2 PCT ANNUAL CHANCE

O A


AE

AH

LidarElevations

Columbia County, FLA - Building & Zoning Property Map

Printed: Thu Sep 19 2019 16:14:45 GMT-0400 (Eastern Daylight Time)



Parcel Information

Parcel No: 20-3S-16-02203-002

Owner: SMITH ROBERT D & ANDREA G

Subdivision:

Lot:

Acres: 33.4630928 Deed Acres: 33.72 Ac

District: District 3 Bucky Nash Future Land Uses: Agriculture - 3

Flood Zones:

Official Zoning Atlas: A-3, PRD

All data, information, and maps are provided"as is" without warranty or any representation of accuracy, timeliness of completeness. Columbia County, FL makes no warranties, express or implied, as to the use of the information obtained here. There are no implies warranties of merchantability or fitness for a particular purpose. The requester acknowledges and accepts all limitations, including the fact that the data, information, and maps are dynamic and in a constant state of maintenance, and update.

Aerial Viewer

Pictometery

Columbia County Property Appraiser Jeff Hampton

2019 Preliminary Certified Values

Parcel: << 20-3S-16-02203-002

_	
יס	100
_	11

Owner & Property Info		Result: 209 o	f 299	
Owner SMITH ROBERT D & ANDREA G 2872 NW BROWN RD LAKE CITY, FL 32055				
Site	2872 BROWN RD, LAKE	2872 BROWN RD, LAKE CITY		
Description*	COMM NW COR, RUN S 855.43 FT, SE 60 DEG 677.73 FT FOR POB, CONT SE 60 DEG 1270.11 FT, SW 13 DEG 1109.31 FT, NW 77 DEG 1154.78 FT, N 481.05 FT, E 238.42 FT, N 975.44 FT TO POB. ORB 893-1637,			
Area	33.72 AC	S/T/R	20-3S-16	
Use Code**	IMPROVED A (005000)	Tax District	3	

^{*}The Description above is not to be used as the Legal Description for this parcel

updated: 8/14/2019

Google Maps

2019	O 2016 O 2013	○ 2010 ○	2007 0 20	05 ✔ Sales
+	ERALL .			THE STATE OF THE S
	7.4		AN SUNSET MILE	Provide C
		1		
				RAY MILTON

Property & Assessment Values 2018 Certified Values 2019 Preliminary Certified \$6,742 \$6,742 Mkt Land (1) Mkt Land (1) \$7,852 Ag Land (1) \$7,852 Ag Land (1) \$242,436 \$224,469 Building (1) Building (1) \$47,076 \$47,855 XFOB (6) XFOB (6) \$541,369 \$524,181 Just Just \$304,106 \$286,918 Class Class \$304,106 **Appraised** \$286,918 Appraised \$15,310 SOH Cap [?] \$5,829 SOH Cap [?] \$288,796 \$283,558 Assessed Assessed нх нз \$50,000 нх нз \$50,000 Exempt Exempt county:\$238,796 county:\$233,558 city:\$238,796 city:\$233,558 Total Total other:\$238,796 other:\$233,558 Taxable Taxable school:\$263,796 school:\$258,558

▼ Sales History						
Sale Date	Sale Price	Book/Page	Deed	V/I	Quality (Codes)	RCode
12/15/1999	\$188,900	893/1637	WD	V	Q	

▼ Building Characteristics						
Bldg Sketch	Bldg Item	Bldg Desc*	Year Blt	Base SF	Actual SF	Bldg Value
Sketch	1	SINGLE FAM (000100)	2004	2861	4331	\$242,436

*Bldg Desc determinations are used by the Property Appraisers office solely for the purpose of determining a property's Just Value for ad valorem tax purposes and should not be used for any other purpose.

▼ Extra Features & Out Buildings (Codes)							
Code	Desc	Year Blt	Value	Units	Dims	Condition (% Good)	
0190	FPLC PF	2004	\$2,400.00	2.000	0 x 0 x 0	(000.00)	
0280	POOL R/CON	2004	\$10,895.00	512.000	16 x 32 x 0	(000.00)	
0282	POOL ENCL	2004	\$7,403.00	1645.000	35 x 47 x 0	(000.00)	
0166	CONC.PAVMT	2004	\$19,128.00	9564.000	0 x 0 x 0	(000.00)	
0040	BARN,POLE	2005	\$4,000.00	1.000	0 x 0 x 0	(000.00)	

in any legal transaction.
**The <u>Use Code</u> is a FL Dept. of Revenue (DOR) code and is not maintained by the Property Appraiser's office. Please contact your city or county Planning & Zoning office for specific zoning information.

Calumbia Caunts Branasts American

STATE OF FLORIDA DEPARTMENT OF HEALTH APPLICATION FOR CONSTRUCTION PERMIT

Permit Application Number 19-0720 PART II - SITEPLAN -----Scale: Each block represents 10 feet and 1 inch = 40 feet. ndl cive Notes: Site Plan submitted by:_ Plan Approved Not Approved_ County Health Department CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DETERMENT DH 4015, 08/09 (Obsoletes previous editions which may not be used) Incorporated: 64E-6.001, FAC (Slock Number: 5744-002-4015-6)



STATE OF FLORIDA DEPARTMENT OF HEALTH ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM APPLICATION FOR CONSTRU

PERMIT NO_	19-0720	د
DATE PAID:	9/251	4
FEE PAID:	LODIZ	
RECEIPT #:	14352	1

APPLICATION	FOR CONSTRUCTION PERMIT	RECEIPT #: 14353
APPLICATION FOR: [] New System [] [] Repair []	Existing System [] Holding Abandonment [] Tempora	Tank [] Innovative
APPLICANT: Sob + (Alimo some	
AGENT: WRITED)		
MATLING ADDRESS: 2872		TELEPHONE: 386-755-438
Lake (, d	2 + L 3225	
BY A PERSON LICENSED PURSUAN APPLICANT'S RESPONSIBILITY OF PLATTED (MM/DD/YY) IF REQUES	F OR APPLICANT'S AUTHORIZED AGENT. NT TO 489.105(3)(m) OR 489.552, FLO FO PROVIDE DOCUMENTATION OF THE DAT STING CONSIDERATION OF STATUTORY GR	ALDA STATITURE THE TA THE
PROPERTY INFORMATION		
LOT: BLOCK:	SUBDIVISION:	PLATTED:
PROPERTY ID #: 20-35-16	-02203-202 ZONING: US	M OR EQUIVALENT: (4)
PROPERTY SIZE: 3 ACRES	WATER SUPPLY: [] PRIVATE PUBLIC	C []<=2000GPD (1\2000GPD
25 SEWER AVAILABLE AS PER 38	1.0065, FS? [Y (N)	ISPANCE DO CERTO
PROPERTY ADDRESS: 3572	UN Boom P) Lake City	C) 3 SEMER; FT
DIRECTIONS TO PROPERTY:	un 90 West to Bc	70/
Crown Come 1	45 m in 5.	awn Ka
Heart Land Ran	el sign on Left	
BUILDING INFORMATION	[CARESIDENTIAL [] COMM	ERCIAL
Unit Type of No Establishment	No. of Building Commercial/I Bedrooms Area Sqft Table 1, Cha	nstitutional System Design
2 Carport	0 1440	
3		
4		
[] Floor/Equipment Drains	[] Other (Specify)	
SIGNATURE: DE LOS		DATE: 925/19

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and approval numbers on the building components listed below if they will be utilized on the construction project for which you are applying for a building permit. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. Statewide approved

products are listed online @ www.floridabuilding.org

oroducts are listed online @ www Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
. EXTERIOR DOORS			
. SWINGING	Pirstpro	Fibers 1450 6 panel	FL 17347,9
. SLIDING	P113 1 P10		
: SECTIONAL/ROLL UP			
O. OTHER			
. WINDOWS			FZ 239
A. SINGLE/DOUBLE HUNG	PET 5-400 Scrius	Vingl LOW E	1220
B. HORIZONTAL SLIDER			
. CASEMENT			
D. FIXED			
E. MULLION			
F. SKYLIGHTS			
G. OTHER			
3. PANEL WALL			
A. SIDING		i ccci	FL 16503
B. SOFFITS	Kaycan	Aluminum Soffit	PC 10303
C. STOREFRONTS			
D. GLASS BLOCK			
E. OTHER			
4. ROOFING PRODUCTS			FL10124-R11
A. ASPHALT SHINGLES	GAF	Asphalt Shinges	T-LIVIZT-KI
B. NON-STRUCTURAL METAL			
C. ROOFING TILES			
D. SINGLE PLY ROOF			
E. OTHER			
5. STRUCTURAL COMPONENTS			FL-13872-R
A. WOOD CONNECTORS	Simpson	LSTA-MSTA-STAPPINS	12 100.21
B. WOOD ANCHORS		CO TORRESTOR	
C. TRUSS PLATES		Tiecei, Co	
D. INSULATION FORMS		SEL TOP ITE	
E. LINTELS		101 CC (1)	
F. OTHERS		Compute 15	
		O Compliance	
6. NEW EXTERIOR		No The Y	_
		an review. I understand that at the time of inspection of the	

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturers installation requirements.

Further, I understand these products may have to be removed if approval cannot be demonstrated during inspection.

(03)	9/17/19	
Contractor OR Agent Signature	Date	NOTES:
Contractor of the general and		





BC CALC® Member Report

PASSED

August 30, 2019 15:22:24

Build 7192

Job name: Address:

2067658 Smith

File name: Specifier:

City, State, Zip: Builder: Code reports:

Lake City, FL

Mike Todd Construction

Designer: Company:

Brian Cannady

ESR-1040

Builders FirstSource

Design	Description	Results	Product	Plies	Control
Design				1 1103	Control
RB01 RB02 RB03		Passed	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	3	Pos. Moment 99.9% Pos. Moment 78.6% Pos. Moment 94.1%

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER® , AJS™, ALLJOIST® , BC RIM BOARD™, BCI® , BOISE GLULAM™, BC FloorValue® , VERSA-LAM®, VERSA-RIM PLUS® , VERSA-RIM®, VERSA-STRAND®, VERSA-STUD® are trademarks of Boise Cascade Wood Products L.L.C.







Triple 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP RB01 (RoofHeader)




BC CALC® Member Report

Description:

August 30, 2019 15:22:24

This report has a cover page. See the cover page(s) for project data and important information regarding this analysis and product installation.



Total Horizontal Product Length = 13-08-00

Reaction Summary (Down / Uplift) (lbs)

. todolloll odil	milary (Domin,	opinity (186)				
Bearing	Live	Dead	Snow	Wind	Roof Live	
B1, 5-1/2"		2427 / 0		1872 / 0	2708 / 0	
B2, 2-1/2"		2340 / 0		1805 / 0	2611 / 0	

Load Summary					Live	Dead	Snow	Wind	Roof Live	Tributary		
Tag	Description	Load Type	Ref.	Start	End	Loc.	100%	90%	115%	160%	125%	
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	13-08-00	Top		18				00-00-00
1	36' span roof load	Unf. Area (lb/ft²)	L	00-00-00	13-08-00	Top		331		269	389	01-00-00

Controls Summary	Value	% Allowable	Duration	Case	Location
Pos. Moment	15893 ft-lbs	99.9%	125%	4	06-11-08
End Shear	4067 lbs	27.5%	125%	4	01-05-06
Total Load Deflection	L/442 (0.356")	40.7%	n\a	7	06-11-08
Live Load Deflection	L/798 (0.197")	30.1%	n\a	16	06-11-08
Max Defl.	0.356"	35.6%	n\a	7	06-11-08
Span / Depth	13.3				

Bearing	g Supports	_Dim. (LxW)	Value	% Allow Support	% Allow Member	Material	
B1	Wall/Plate	5-1/2" x 5-1/4"	5862 lbs	n\a	27.1%	Unspecified	
B2	Column	2-1/2" x 5-1/4"	5652 lbs	n\a	57.4%	Unspecified	

Cautions

For roof members with slope (1/4)/12 or less final design must ensure that ponding instability will not occur.

For roof members with slope (1/2)/12 or less final design must account for Rain-on-Snow surcharge load.

Notes

Design meets Code minimum (L/180) Total load deflection criteria.

Design meets Code minimum (L/240) Live load deflection criteria.

Design meets arbitrary (1") Maximum Total load deflection criteria.

Calculations assume member is braced at all supports. See engineering report for the unbraced length.

BC CALC® analysis is based on IBC 2009.

Design based on Dry Service Condition.

Install screws from both sides, staggering screws by half of the spacing to avoid splitting.

Member has no side loads.



Triple 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP RB01 (RoofHeader)




BC CALC® Member Report

Description:

August 30, 2019 15:22:24

This report has a cover page. See the cover page(s) for project data and important information regarding this analysis and product installation.

Connection Diagram: Full Length of Member



a minimum = 1-1/2"

c = 8-7/8"

b minimum = 4"


d = 24"

e minimum = 1"

Install screws from both sides, staggering screws by half of the spacing to avoid splitting.

Member has no side loads.

Connectors are: SDS 1/4 x 3-1/2





Triple 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP RB02 (RoofHeader)




BC CALC® Member Report

August 30, 2019 15:22:24

Description:

This report has a cover page. See the cover page(s) for project data and important information regarding this analysis and product installation.



Total Horizontal Product Length = 13-00-00

Reaction Summary (Down / Uplift) (lbs)

iteaction our	illiary (Down /)	opinii) (ibə)				
Bearing	Live	Dead	Snow	Wind	Roof Live	
B1, 2-1/2"		2201 / 0		2050 / 0	2453 / 0	
B2. 5-1/4"		1288 / 0		1338 / 0	1375 / 0	

Lo	Load Summary					Live	ve Dead	Snow	Wind	Roof Live	Tributary	
Tag	Description	Load Type	Ref.	Start	End	Loc.	100%	90%	115%	160%	125%	
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	13-00-00	Top		18				00-00-00
1	36' span roof load	Unf. Area (lb/ft²)	L	00-00-00	04-11-04	Top		331		269	389	01-00-00
2	7' Setback GT	Conc. Pt. (lbs)	L	05-10-08	05-10-08	Top		1231		1613	1449	n∖a
3	Corner set	Trapezoidal (lb/ft)	L	06-10-00		Тор		72		68	84	n\a
					12-10-00	·		58		81	84	

Controls Summary	Value	% Allowable	Duration	Case	Location
Pos. Moment	14251 ft-lbs	78.6%	125%	4	05-10-08
End Shear	3770 lbs	25.5%	125%	4	01-02-06
Total Load Deflection	L/545 (0.275")	33.0%	n\a	7	06-01-06
Live Load Deflection	L/941 (0.159")	25.5%	n\a	16	06-01-06
Max Defl.	0.275"	27.5%	n\a	7	06-01-06
Span / Depth	12.6				

Bearin	g Supports	Dim. (LxW)	Value	% Allow Support	% Allow Member	Material
B1	Column	2-1/2" x 5-1/4"	5578 lbs	n\a	56.7%	Unspecified
B2	Column	5-1/4" x 5-1/4"	3323 lbs	n\a	16.1%	Unspecified

Cautions

For roof members with slope (1/4)/12 or less final design must ensure that ponding instability will not occur.

For roof members with slope (1/2)/12 or less final design must account for Rain-on-Snow surcharge load.

Notes

Design meets Code minimum (L/180) Total load deflection criteria.

Design meets Code minimum (L/240) Live load deflection criteria.

Design meets arbitrary (1") Maximum Total load deflection criteria.

Calculations assume member is braced at all supports. See engineering report for the unbraced length.

BC CALC® analysis is based on IBC 2009.

Design based on Dry Service Condition.

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Install screws from both sides, staggering screws by half of the spacing to avoid splitting.

Member has no side loads.





Triple 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP RB02 (RoofHeader)

This report has a cover page. See the cover page(s) for project data and important information regarding this analysis and product installation.




BC CALC® Member Report

Description:

August 30, 2019 15:22:24

Connection Diagram: Full Length of Member



a minimum = 1-1/2"

c = 8-7/8"

b minimum = 4"

d = 24"

e minimum = 1"

Connection design assumes point load is top-loaded. For connection design of side-loaded point loads, please consult a technical representative or professional of Record.

Install screws from both sides, staggering screws by half of the spacing to avoid splitting.

Member has no side loads.

Connectors are: SDS 1/4 x 3-1/2





Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP RB03 (RoofHeader)




August 30, 2019 15:22:24

BC CALC® Member Report

Description:

This report has a cover page. See the cover page(s) for project data and important information regarding this analysis and product installation.



Total Horizontal Product Length = 18-00-00

Reaction Summary (Down / Uplift) (lbs)

Troublion Guin	mary (Domir c	pint, (186)				
Bearing	Live	Dead	Snow	Wind	Roof Live	
B1, 2-1/2"		873 / 0		529 / 0	900 / 0	
B2, 2-1/2"		766 / 0		593 / 0	774 / 0	

Lo	ad Summary						Live	Dead	Snow	Wind	Roof Live	Tributary
Tag	Description	Load Type	Ref.	Start	End	Loc.	100%	90%	115%	160%	125%	
0	Self-Weight	Unf. Lin. (lb/ft)	L	00-00-00	18-00-00	Top		12				00-00-00
1	7' End Jack	Unf. Area (lb/ft²)	L	00-00-00	11-10-00	Top		87		57	103	01-00-00
3	Corner set	Trapezoidal (lb/ft)	L	11-10-00		Top		72		68	84	n\a
					17-10-00	·		58		81	84	

Controls Summary	Value	% Allowable	Duration	Case	Location
Pos. Moment	7527 ft-lbs	94.1%	125%	4	08-08-05
End Shear	1532 lbs	15.5%	125%	4	01-02-06
Total Load Deflection	L/472 (0.45")	38.1%	n\a	7	09-00-00
Live Load Deflection	L/898 (0.237")	26.7%	n\a	16	09-00-00
Max Defl.	0.45"	45.0%	n\a	7	09-00-00
Span / Depth	17.9				

Bearing	Supports	Dim. (LxW)	Value	% Allow Support	% Allow Member	Material
B1	Column	2-1/2" x 3-1/2"	1945 lbs	n\a	29.6%	Unspecified
B2	Column	2-1/2" x 3-1/2"	1791 lbs	n\a	27.3%	Unspecified

Cautions

For roof members with slope (1/4)/12 or less final design must ensure that ponding instability will not occur.

For roof members with slope (1/2)/12 or less final design must account for Rain-on-Snow surcharge load.

Notes

Design meets Code minimum (L/180) Total load deflection criteria.

Design meets Code minimum (L/240) Live load deflection criteria.

Design meets arbitrary (1") Maximum Total load deflection criteria.

Calculations assume member is braced at all supports. See engineering report for the unbraced length.

BC CALC® analysis is based on IBC 2009.

Design based on Dry Service Condition.

Install Screws with screw heads in the loaded ply.

Member has no side loads.



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP RB03 (RoofHeader)

PASSED


BC CALC® Member Report

Description:

August 30, 2019 15:22:24

This report has a cover page. See the cover page(s) for project data and important information regarding this analysis and product installation.

Connection Diagram: Full Length of Member




a minimum = 1-1/2" b minimum = 4" c = 8-7/8"

d = 24"

e minimum = 1"

Install Screws with screw heads in the loaded ply. Member has no side loads.

Connectors are: SDS 1/4 x 3-1/2



Smith Carport Columbia County, Florida Wind Load Analysis Requirements

(In Compliance with the 2017 Florida Building Code)

Prepared By: Marty J. Humphries, P.E. # 51976 7932 240th St., O'Brien, FL 32071 (386)935-2406

Description of New Carport:

Footprint: 40' deep x 36' wide overall dimensions with 36' wide x 14' deep enclosed work/storage areas and 36' wide x 26' deep carport area (See plans by Mike Todd)

Walls: 8" masonry block wall with stucco exterior and furring strips, rigid insulation and blueboard hard-coat interior.

Roof Structure: Pre-engineered roof trusses at 2' on center and 15/32" OSB sheathing with Synthetic roof underlayment and architectural shingles

Roof Type: Hip roof (analyzed for 2' eave overhangs and carport) Foundation: monolithic slab (see attached foundation details)

Windload Data and Exposure:

Basic Wind Speed = 120 mph(Vult)

Importance Factor = 1.0

Exposure category = B

Height and Exposure Adjustment Coefficient = 1.0

Residential Occupancy = Group R3

Mean roof height = 16'

Roof Cross Slope = 6:12

Eave Overhang= (Analyzed for 2"eave overhangs)

Wall Height = 10'

Shear Wall locations = exterior walls only

Component and Cladding Pressures = Roof(Zone 1=10.0,-14.0, Zone 2=10.0,-24.0, Zone 3=10.0,--36.0), Wall(Zone 4=15.5,-16.0, Zone 5=15.5,-20.0)(units are psf)

The following requirements supercede the plan requirements by "Mike Todd" where applicable.

Nailing Pattern Requirements:

Roof sheathing:

Shall be 15/32" OSB min. nailed with 8d ring-shank nails 6" on center including overhang areas

Strapping and Anchor Requirements:

truss to exterior wall plate, porch header locations:

Install one Simpson model H10A hurricane anchor each location for common/tier trusses and one Simpson model H2.5A hurricane clip at jack trusses. Install Simpson model H10A-2 anchor for double trusses with 1-H2.5A clip in addition. At 8" masonry walls

mits 5 SL-8-26-19

1 of 4

install Simpson Hetal12 embedded anchors at each truss location.

Carport columns: Install Simpson HD5B hold down anchor connected to top of masonry column with 1 – 5/8"x12" anchor bolt or 1 – 5/8" steel all-thread embedded 12" into top of masonry column and epoxied with Simpson SET-XP epoxy. Connect HD5B to LVL header with 2-3/4" bolts. At block wall cast a block-out 5"

deep into masonry block wall and install 1 - 5/8" steel all-threads embedded 12" into masonry wall and install nut, lock washer, and 2"x 2" plate washer at

all-thread.

Footer Requirements:

Exterior wall Monolithic footer: 18" min. x 16" wide with 3-#5 rebar continuous (See attached Detail)

Carport Monolithic footer: 18" deep x 16" wide with 3-#5 rebar continuous (See attached Detail)

Header Requirements:

Carport: Header shall be 3 – 1.75"x14" LVL's(Fb=2250 min., 1.5E min.) nailed together with 4-12d nails 10" on center


Porch/Carport Ceilings:

Install 1x4 SPF lathes 16" on center connected to trusses with 2-8d nails each location and covered with solid aluminum soffit material, vinyl soffit material or hardi-panel.

Note: Masonry column height shall be constructed such that finished top plate of masonry wall matches finished top height of LVL carport header.

Note: Equivalent capacity anchors may be substituted, installed in accordance with the manufacturers requirements.

Muty 571 8-26-19 2 of



 $^{15}\!\!/_{32}$ " OSB sheathing with metal clips between trusses (neil with 8d ring-shank neils 6° 0.C.) pre-engineered trusses at 2' on enter architectural shingles w 'Tiger Paw' synthetic underlayment Install Simpson hurricane clip 5.25*x14* LVL beam (Fb=2250 E=1.5 min.) see sheets 1 and 2 for requirements aluminum eave drip(cont.) solid aluminum or vinyl soffit over 1x4 lathes at 16° on center nailed w 2-8d nails at 2x6 SPF sub-facia each truss connection. aluminum wrap around 2′ top of columns vented aluminum or vinyl soffit 2-3/4" galvanized carriage bolts Install Simpson HD5B holdown anchor %"× 12" anchor bolt PT sole plate 16'x16' masonry block column w 4-*5 rebar vertical (one each corner) poured solid w 3000 psi conc. w stucco finish 25″ min. lap 4" concrete slab welded wire mesh(6x6-10gage) (chairs 3' 0.C. each way) or fibercrete 6 mil visqueen lapped 6 <u>6</u>" and sealed 18" min compacted fill (chemically treated for termites) cont. 16' wide x 18' deep(min.) monolithic footer (3000 psi concrete) 16" (3) cont. # 5 rebar CARPORT COLUMN/FOUNDATION DETAIL (N.T.S.) Sheet DETAIL PREPARED BY: Smith Corport 4 MARTY J. HUMPHRIES P.E. # 51976

Columbia County, FL

0f

4

7932 240TH ST.. O'BRIEN. FL 32071

4.7



Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

RE: 2067658 - MIKE TODD CONST - SMITH CARPORT

MiTek USA, Inc.

6904 Parke East Blvd. Tampa, FL 33610-4115

Site Information:

Customer Info: Mike Todd Const Project Name: Smith Carport Model: Custom

Lot/Block: N/A Address: 2872 NW Brown Road, N/A

Subdivision: N/A

City: Columbia Cty

State: FL

Name Address and License # of Structural Engineer of Record, If there is one, for the building.

Name:

License #:

Address:

City:

State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2017/TPI2014

Design Program: MiTek 20/20 8.2

Wind Code: ASCE 7-10

Wind Speed: 130 mph

Roof Load: 37.0 psf

Floor Load: N/A psf

This package includes 21 individual, Truss Design Drawings and 0 Additional Drawings. With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No. 12345678910	Seal# T18132971 T18132972 T18132974 T18132975 T18132977 T18132978 T18132978 T18132980 T18132980	Truss Name CJ01 CJ01A CJ03 CJ03A CJ05 CJ05A EJ01 EJ01A HJ10 HJ10A T01	Date 9/17/19 9/17/19 9/17/19 9/17/19 9/17/19 9/17/19 9/17/19 9/17/19
13 14 15 16 17 18 19 20 21	T18132983 T18132984 T18132985 T18132986 T18132987 T18132987 T18132989 T18132990 T18132991	T02 T02A T03 T03A T04 T04A T05 T06 T07	9/17/19 9/17/19 9/17/19 9/17/19 9/17/19 9/17/19 9/17/19 9/17/19



The truss drawing(s) referenced above have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource-Jacksonville.

Truss Design Engineer's Name: Albani, Thomas

My license renewal date for the state of Florida is February 28, 2021.

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.




Thomas A. Albani PE No.39380 MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610

September 17,2019

MIKE TODD CONST - SMITH CARPORT Truss Type Qty Plv Job Truss T18132971 CJ01 Jack-Open 2067658 Job Reference (optional) 8.240 s Jul 14 2019 MiTek Industries, Inc. Tue Sep 17 12:50:42 2019 Page 1 Jacksonville, FL - 32244, Builders FirstSource, ID:BdOFrdQ122jR1Mb5pLe1CxzwohK-RUOgPuxVcgYJ9OcwiYHLoEc78NBwclG0bePj4sycjYB

-2-0-0 2-0-0

Scale = 1:9.5



Structural wood sheathing directly applied or 1-0-0 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

Plate Offsets (X,Y)-	[2:0-1-4,0-1-9]								-	
LOADING (psf) TCLL 20.0 TCDL 7.0 BCLL 0.0 BCDL 10.0	SPACING- Plate Grip DOL Lumber DOL Rep Stress Incr Code FBC2017/T/	2-0-0 1.25 1.25 YES PI2014	CSI. TC 0.32 BC 0.07 WB 0.00 Matrix-MP	DEFL. Vert(LL) Vert(CT) Horz(CT)	in 0.00 0.00 0.00	(loc) 7 7 2	l/defl >999 >999 n/a	L/d 240 180 n/a	PLATES MT20 Weight: 7 lb	GRIP 244/190 FT = 20%

BRACING-

TOP CHORD

BOT CHORD

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2

> 3=-27/Mechanical, 2=254/0-8-0, 4=-46/Mechanical (lb/size)

Max Horz 2=66(LC 12)

Max Uplift 3=-27(LC 1), 2=-162(LC 12), 4=-46(LC 1)

Max Grav 3=25(LC 16), 2=254(LC 1), 4=44(LC 16)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=162.



MITek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610 Date:


September 17,2019

MARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.





1-0-0 1-0-0

Structural wood sheathing directly applied or 1-0-0 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

LOADING (psf)	SPACING-	2-0-0	CSI.		DEFL.	1	(1)	l/defl	1.14	DIATES	CDID
			COI.			HI	(loc)	Masil	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip Do	OL 1.25	TC	0.32	Vert(LL)	0.00	7	>999	240	MT20	244/190
CDL 7.0	Lumber DOL	. 1.25	BC	0.07	Vert(CT)	0.00	7	>999	180		
CLL 0.0	* Rep Stress I	ncr YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
3CDL 10.0	Code FBC20	017/TPI2014	Matri	x-MP	1		_			Weight: 7 lb	FT = 20%

BRACING-

TOP CHORD

BOT CHORD

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

(lb/size) 3=-27/Mechanical, 2=254/0-3-8, 4=-46/Mechanical

Max Horz 2=66(LC 12)

Max Uplift 3=-27(LC 1), 2=-162(LC 12), 4=-46(LC 1)

Max Grav 3=25(LC 16), 2=254(LC 1), 4=44(LC 16)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=162.



MiTek USA, Inc. FL Cert 6634 6904 Parke East Bivd. Tampa FL 33610 Date:

September 17,2019



MIKE TODD CONST - SMITH CARPORT Qty ٥lv Truss Type Truss T18132973 Job Jack-Open CJ03 2067658 Job Reference (optional)

8.240 s Jul 14 2019 MiTek Industries, Inc. Tue Sep 17 12:50:43 2019 Page 1 Jacksonville, FL - 32244, Builders FirstSource, ID:BdOFrdQ122jR1Mb5pLe1CxzwohK-vgy3cDy7N_gAnXB6FFoaKR9ltnX9LCW9pl8HclycjYA -2-0-0 2-0-0 Scale = 1:14.6 6.00 12 0-4-B ۸ Δ° Ų, 3x4

Plate Offsets (X,Y)	[2:0-0-3,0-0-5]			
LOADING (psf) TCLL 20.0 TCDL 7.0	SPACING- 2-0-0 Plate Grip DOL 1.25 Lumber DOL 1.25	CSI. TC 0.32 BC 0.07	DEFL. in (loc) I/defl L/d PLATES GRIP Vert(LL) -0.00 4-7 >999 240 MT20 244/190 Vert(CT) -0.01 4-7 >999 180	
BCLL 0.0 * BCDL 10.0	Rep Stress Incr YES Code FBC2017/TPi2014	WB 0.00 Matrix-MP	Horz(CT) 0.00 3 n/a n/a Weight: 13 lb FT = 20%	

BRACING-

TOP CHORD

BOT CHORD

3-0-0

Structural wood sheathing directly applied or 3-0-0 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

LUMBER-

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

(lb/size) 3=52/Mechanical, 2=253/0-8-0, 4=20/Mechanical REACTIONS.


Max Horz 2=113(LC 12)

Max Uplift 3=-48(LC 12), 2=-126(LC 12) Max Grav 3=52(LC 1), 2=253(LC 1), 4=48(LC 3)

FORCES. (ib) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3 except (jt=lb) 2=126.



September 17,20



WARNING - verify design parameters and READ NOTES ON THIS AND INCLUDED MITER REPERENCE PAGE MIT-1/15 Rev. 1900/32015 BEFORE USE.

Design valid for use only with MITER® connectors. This design is based only upon parameters and properly incorporate this design into the overall a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, detivery, erection and bracing of trusses and truss systems, see

ANSI/TP11 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.






Plate Offsets (X,Y)- [2:0-1-4,0-1-9] LOADING (psf) SPACING-2-0-0 CSI. DEFL in (loc) I/defl 1 /d **PLATES** GRIP **TCLL** 20.0 Plate Grip DOL 1.25 TC 0.32 Vert(LL) 0.01 4-7 >999 240 MT20 244/190 TCDI. 7.0 Lumber DOL 1.25 BC 0.07 Vert(CT) -0.01 >999 180 **BCLL** 0.0 Rep Stress Incr YES WB 0.00 Horz(CT) -0.00 n/a BCDL Code FBC2017/TPI2014 10.0 Matrix-MP Weight: 13 lb FT = 20%

BRACING-

TOP CHORD

BOT CHORD

LUMBER-

TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No 2

REACTIONS. (lb/size) 3=52/Mechanical, 2=253/0-3-8, 4=20/Mechanical

Max Horz 2=113(LC 12)

Max Uplift 3=-48(LC 12), 2=-126(LC 12), 4=-22(LC 9) Max Grav 3=52(LC 1), 2=253(LC 1), 4=48(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (|t=|b|) 2=126.




Structural wood sheathing directly applied or 3-0-0 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

6904 Parke East Blvd. Tampa FL 33610

September 17,2019





TOP CHORD

BOT CHORD

LUMBER-

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

3=108/Mechanical, 2=313/0-8-0, 4=53/Mechanical REACTIONS. (lb/size)


Max Horz 2=162(LC 12)

Max Uplift 3=-98(LC 12), 2=-137(LC 12), 4=-1(LC 12) Max Grav 3=108(LC 1), 2=313(LC 1), 4=87(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

 3) *This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide
- will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (it=lb) 2=137.



Structural wood sheathing directly applied or 5-0-0 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

6904 Parke East Blvd. Tampa FL 33610 Date:

September 17,201



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chard members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

**AMSIVTP1 Quality Criteria, DSB-89 and BCSI Building Composition available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



Job Truss Type Truss Qty MIKE TODD CONST - SMITH CARPORT T18132976 2067658 CJ05A Jack-Open Job Reference (optional) Builders FirstSource, Jacksonville, FL - 32244, 8.240 s Jul 14 2019 MiTek industries, Inc. Tue Sep 17 12:50:45 2019 Page 1 $ID: BdOFrdQ122jR1Mb5pLe1CxzwohK-r34p1v_Ovbwu0rKVNgr2QsEeUa8Up60SHcdOhBycjY8$ -2-0-0 2-0-0 Scale = 1:19.5 6.00 12 0-4-B Plate Offsets (X,Y)-[2:0-1-4,0-1-9] LOADING (psf) SPACING-CSI. DEFL. (loc) **V**def L/d **PLATES** GRIP Plate Grip DOL TCLL. 20.0 1.25 TC 0.38 Vert(LL) 0.08 >750 4-7 240 MT20 244/190 TCDL 7.0 Lumber DOL 1.25 ВС 0.34 Vert(CT) 0.07 >856 180 **BCLL** 0.0 Rep Stress Incr YES WB 0.00 Horz(CT) -0.00 n/a n/a BCDI. 10.0 Code FBC2017/TPI2014 Matrix-MP Weight: 19 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 BRACING-

TOP CHORD **BOT CHORD** Structural wood sheathing directly applied or 5-0-0 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. 3=108/Mechanical, 2=313/0-3-8, 4=53/Mechanical

Max Horz 2=162(LC 12)

Max Uplift 3=-98(LC 12), 2=-137(LC 12), 4=-44(LC 9) Max Grav 3=108(LC 1), 2=313(LC 1), 4=87(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4,2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members
- 4) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=137.




MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610

September 17,201!

🛕 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE





BRACING-

TOP CHORD

BOT CHORD

LUMBER-

TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2

REACTIONS.

3=160/Mechanical, 2=380/0-8-0, 4=81/Mechanical (lb/size)

Max Horz 2=144(LC 12)


Max Uplift 3=-94(LC 12), 2=-81(LC 12)

Max Grav 3=160(LC 1), 2=380(LC 1), 4=125(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members. 4) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.



Structural wood sheathing directly applied or 6-0-0 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

September 17,201

👠 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent bracit is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, eraction and bracing of trusses and truss systems, see

ANS/TPM Quality Criteria, DSB-89 and BCSI Building Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



Job Truss Truss Type MIKE TODD CONST - SMITH CARPORT Qty Ply T18132978 2067658 12 EJ01A Jack-Partial Job Reference (optional) Builders FirstSource. Jacksonville, FL - 32244. 8.240 s Jul 14 2019 MiTek Industries, Inc. Tue Sep 17 12:50:47 2019 Page 1 ID:BdOFrdQ122jR1Mb5pLe1CxzwohK-nSBZSb?eRCAcG9UtU5tWVHKrzOkRH0Wlkw6Ul3ycjY6 -2-0-0 7-0-0 2-0-0 Scale: 1/2"=1" 6.00 12 0-4-B 3x4 / Plate Offsets (X,Y)- [2:0-1-13,0-1-8] LOADING (psf) SPACING-2-0-0 CSI. DEFL. (loc) I/defl Ľď **PLATES** GRIP TCLL 20.0 Plate Grip DOL 1.25 TC 0.89 Vert(LL) >250 0.33 4-7 240 MT20 244/190 TCDL 7.0 Lumber DOL 1.25 вс 0.76 Vert(CT) 0.29 >287 180 4-7 BCLL 0.0 Rep Stress Incr YES WB 0.00 Horz(CT) -0.01 n/a n/a BCDL. Code FBC2017/TPI2014 10.0 Matrix-MS Weight: 26 lb FT = 20%

BRACING-

TOP CHORD

BOT CHORD

REACTIONS.

TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2

(lb/size) 3=160/Mechanical, 2=380/0-3-8, 4=81/Mechanical

Max Horz 2=144(LC 12)

Max Uplift 3=-94(LC 12), 2=-115(LC 9), 4=-62(LC 9) Max Grav 3=160(LC 1), 2=380(LC 1), 4=125(LC 3)

FORCES. (ib) - Max. Comp./Max. Ten. - All forces 250 (ib) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 4) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=115.



Structural wood sheathing directly applied or 2-2-0 oc purlins.

Rigid ceiling directly applied or 9-10-2 oc bracing.


MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610 Date:

September 17,201

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MIN-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses snat furuse systems, see ANSITPH Quality Criteria, DSB-89 and BCSI Building Com Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.





BOT CHORD

Rigid ceiling directly applied or 9-9-0 oc bracing.

TOP CHORD

2x4 SP No.2 **BOT CHORD** 2x4 SP No.2

2x4 SP No.3 WERS

REACTIONS.

4=150/Mechanical, 2=463/0-10-15, 5=251/Mechanical (lb/size)

Max Horz 2=233(LC 22)

Max Uplift 4=-141(LC 4), 2=-264(LC 4), 5=-103(LC 8) Max Grav 4=150(LC 1), 2=463(LC 1), 5=266(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-638/221

BOT CHORD 2-7=-327/573, 6-7=-327/573

WEBS 3-6=-603/345

NOTES-

- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except ((t=lb) 4=141, 2=264, 5=103.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 86 lb down and 103 lb up at 1-6-1, 86 lb down and 103 lb up at 1-6-1, 89 lb down and 21 lb up at 4-4-0, 89 lb down and 21 lb up at 4-4-0, and 50 lb down and 97 lb up at 7-1-15, and 50 lb down and 97 lb up at 7-1-15 on top chord, and 36 lb down and 74 lb up at 1-6-1, 36 lb down and 74 lb up at 1-6-1, 28 lb down and 2 lb up at 4-4-0, 28 lb down and 2 lb up at 4-4-0, and 44 lb down and 15 lb up at 7-1-15, and 44 lb down and 15 lb up at 7-1-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 5-8=-20

Concentrated Loads (lb)


Vert: 7=5(F=2, B=2) 11=50(F=25, B=25) 12=-64(F=-32, B=-32) 13=70(F=35, B=35) 14=-49(F=-24, B=-24)



MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610 Date:

September 17,201





BOT CHORD

Rigid ceiling directly applied or 7-7-1 oc bracing.

BOT CHORD 2x4 SP No.2

WEBS

2x4 SP No.3

(lb/size) 4=150/Mechanical, 2=463/0-4-9, 5=251/Mechanical

Max Horz 2=233(LC 4)

Max Uplift 4=-143(LC 4), 2=-345(LC 4), 5=-216(LC 5) Max Grav 4=150(LC 1), 2=463(LC 1), 5=266(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD

REACTIONS.

2-3=-628/448

BOT CHORD 2-7=-510/573, 6-7=-510/573

WEBS

3-6=-603/537

NOTES-

1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60

2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.

5) Refer to girder(s) for truss to truss connections.

- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 4=143, 2=345, 5=216,
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 83 lb down and 103 lb up at 1-6-1, 83 lb down and 103 lb up at 1-6-1, 26 lb down and 38 lb up at 4-4-0, 26 lb down and 38 lb up at 4-4-0, and 50 lb down and 97 lb up at 7-1-15, and 50 lb down and 97 lb up at 7-1-15 on top chord, and 69 lb down and 74 lb up at 1-6-1, 69 lb down and 74 lb up at 1-6-1, 53 lb down and 30 lb up at 4-4-0, 53 lb down and 30 lb up at 4-4-0, and 40 lb down and 59 lb up at 7-1-15, and 40 lb down and 59 lb up at 7-1-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 5-8=-20

Concentrated Loads (lb)

Vert: 7=5(F=2, B=2) 11=50(F=25, B=25) 12=-64(F=-32, B=-32) 13=70(F=35, B=35) 14=-49(F=-24, B=-24)



Thomas A. Albani PE No.39380 MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610


September 17,2019

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal rijury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



Job	Truss	Truss Type		Qty	Ply	MIKE TODD CONST -	SMITH CARPORT	
								T18132981
2067658	T01	HIP GIRDER		1	2	1		
						Job Reference (options		
Builders FirstSource.	Jacksonville, FL - 3	2244.		100000000000000000000000000000000000000	3.240 s Jul	14 2019 MiTek Industrie	es, Inc. Tue Sep 17 12:50	52 2019 Page 1
2				ID:BdOFrdQ122jR1I	Mb5pLe1C	xzwohK-8P7SVI3nGlpvl	MwNrHeThCL1nmPR9yBl	(UuCqFQHycjY1
-2-0-0	7-0-0	12-2-10	18-0-0	23-9-6		29-0-0	36-0-0	38-0-0
2-0-0	7-0-0	5-2-10	5-9-6	5-9-6		5-2-10	7-0-0	2-0-0



	-	7-0-0 7-0-0	14-5-5 7-5-5			21-6-11 7-1-6	-	29-0-0 7-5-5		36-0-0 7-0-0	
Plate Offse	ets (X,Y)-	[3:0-3-0,0-2-0], [8:0-3-0,0						, , , ,			
OADING	(psf)	SPACING-	2-0-0	CSI.		DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
CLL	20,0	Plate Grip DOL	1.25	TC	0.57	Vert(LL)	-0.26 13-14	>999	240	MT20	244/190
CDL	7.0	Lumber DOL	1.25	BC	0.72	Vert(CT)	-0.50 13-14	>873	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.41	Horz(CT)	0.12 9	n/a	n/a		
BCDL	10.0	Code FBC2017/T	PI2014	Matrix	c-MS					Weight: 399 lb	FT = 20%

BRACING-

TOP CHORD

BOT CHORD

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.2 **BOT CHORD** 2x6 SP No.2 **WEBS**

2x4 SP No.3

(lb/size) 2=2680/0-8-0, 9=2725/0-8-0

Max Horz 2=-61(LC 6)

Max Uplift 2=-763(LC 8), 9=-831(LC 9)

FORCES. (ib) - Max. Comp./Max. Ten. - All forces 250 (ib) or less except when shown

TOP CHORD 2-3=-5287/1565, 3-4=-4734/1446, 4-5=-7070/2118, 5-7=-7100/2155, 7-8=-4822/1575, 8-9=-5387/1712

BOT CHORD 2-16=-1360/4656, 14-16=-2000/6629, 13-14=-2243/7405, 11-13=-2043/6678,

9-11=-1453/4746 WEBS

3-16=-480/1877, 4-16=-2370/806, 4-14=-126/851, 5-14=-494/291, 5-13=-444/226,

7-13=-73/834, 7-11=-2313/729, 8-11=-435/1847

NOTES-

- 1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 - Top chords connected as follows: 2x4 1 row at 0-9-0 oc.

Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.

Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.

2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

Unbalanced roof live loads have been considered for this design.

4) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60

- 5) Provide adequate drainage to prevent water ponding.
 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=763, 9=831.
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 125 lb down and 100 lb up at 7-0-0, 106 lb down and 100 lb up at 9-0-12, 106 lb down and 100 lb up at 11-0-12, 106 lb down and 100 lb up at 15-0-12, 106 lb down and 100 lb up 100 lb up at 20-11-4, 106 lb down and 100 lb up at 22-11-4, 106 lb down and 100 lb up at 24-11-4, and 106 lb down and 100 lb up at 26-11-4, and 227 lb down and 250 lb up at 29-0-0 on top chord, and 294 lb down and 131 lb up at 7-0-0, 85 lb down at 9-0-12, 85 lb down at 11-0-12, 85 lb down at 13-0-12, 85 lb down at 15-0-12, 85 lb down at 17-0-12, 85 lb down at 18-11-4, 85 lb down at 20-11-4, 85 ib down at 22-11-4, 85 ib down at 24-11-4, and 85 ib down at 26-11-4, and 294 ib down and 131 ib up at 28-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.



Structural wood sheathing directly applied or 4-2-15 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

Thomas A. Albani PE No.39380 MITek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610 Date:

September 17,201

🛦 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 13/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see MSITPH1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suita 312, Alexandria, VA 22314.

Job	Truss	Truss Type	Qty	Ply	MIKE TODD CONST - SMITH CARPORT T18132981
2067658	T01	HIP GIRDER	1	2	Job Reference (optional)

Builders FirstSource,

Jacksonville, FL - 32244,

8.240 s Jul 14 2019 MiTek Industries, Inc. Tue Sep 17 12:50:52 2019 Page 2 ID:BdOFrdQ122jR1Mb5pLe1CxzwohK-8P?SVI3nGlpvMwNrHeThCL1nmPR9yBKUuCqFQHycjY1

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25


Uniform Loads (plf) Vert: 1-3=-54, 3-8=-54, 8-10=-54, 2-9=-20

Concentrated Loads (lb)

Vert: 3=-106(B) 6=-106(B) 8=-180(B) 16=-284(B) 11=-284(B) 21=-106(B) 22=-106(B) 23=-106(B) 24=-106(B) 25=-106(B) 26=-106(B) 27=-106(B) 28=-106(B) 29=-106(B) 30=-61(B) 31=-61(B) 32=-61(B) 33=-61(B) 34=-61(B) 35=-61(B) 35=-61(B) 37=-61(B) 38=-61(B) 39=-61(B)



Job	Truss		Truss Ty	/ре		Qty	Ply	MIKE TODD CONST -	- SMITH CARPORT	T18132982
2067658	T01A		HIP GIR	DER		1	2	Job Reference (option	ai)	
Builders FirstSource,	Jacksonville,	FL - 32244,				ID:BdOFrdQ12	8.240 s Ju 2iR1Mb5pLe	I 14 2019 MiTek Industri 1CxzwohK-0AEzLg6HJ	ies, Inc. Tue Sep 17 12:50 zJKrXgcWUXdMBCTI0o5i):56 2019 Page 1 J4pqoTZ2ycjXz
-2-0-0	7-0-0	7	12-2-10	- 1	18-0-0	23-9-6	i	29-0-0	36-0-0	38-0-0
2-0-0	7-0-0		5-2-10		5-9-6	5-9-6	10	5-2-10	7-0-0	2-0-0



	-	7-0-0 7-0-0	14-5-5 7-5-5	t	21-6-11 7-1-6	1	29-0-0 7-5-5		36-0-0 7-0-0	——
Plate Offsets	(X,Y)-	[3:0-3-0,0-2-0], [8:0-3-0,0			200					
	psf) 20.0 7.0	SPACING- Plate Grip DOL Lumber DOL	2-0-0 1.25 1.25	CSI. TC 0.57 BC 0.72	DEFL. Vert(LL) Vert(CT)	in (loc) 0.42 13-14 -0.50 13-14	l/defl >999 >873	L/d 240 180	PLATES MT20	GRIP 244/190
BCLL	0.0 * 0.0	Rep Stress Incr Code FBC2017/T	NO Pl2014	WB 0.41 Matrix-MS	Horz(CT)	0.12 9	n/a	n/a	Weight; 399 lb	FT = 20%

BRACING-

TOP CHORD

BOT CHORD

LUMBER-

TOP CHORD 2x4 SP No.2 **BOT CHORD** 2x6 SP No.2

WEBS 2x4 SP No.3

REACTIONS. (lb/size) 2=2680/0-3-8, 9=2725/0-3-8

Max Horz 2=-61(LC 25)

Max Uplift 2=-1613(LC 5), 9=-1680(LC 4)

FORCES. (ib) - Max. Comp./Max. Ten. - All forces 250 (ib) or less except when shown. TOP CHORD 2-3=-5287/3361, 3-4=-4734/3085, 4-5=-7070/4570, 5-7=-7100/4608, 7-8=-4822/3217,

8-9=-5387/3511

BOT CHORD 2-16=-2966/4656, 14-16=-4203/6629, 13-14=-4696/7405, 11-13=-4247/6678,

9-11=-3061/4746 WEBS

3-16=-1282/1877, 4-16=-2371/1491, 4-14=-590/851, 5-14=-494/293, 5-13=-444/226,

7-13=-536/834, 7-11=-2313/1413, 8-11=-1237/1847

NOTES-

- 1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 - Top chords connected as follows: 2x4 1 row at 0-9-0 oc.
 - Bottom chords connected as follows: 2x6 2 rows staggered at 0-9-0 oc.
 - Webs connected as follows: 2x4 1 row at 0-9-0 oc.
- 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 3) Unbalanced roof live loads have been considered for this design.
 4) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl. GCpi=0.18; MWFRS (envelope); porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.

 This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (it=lb) 2=1613, 9=1680.



Structural wood sheathing directly applied or 4-2-15 oc purlins.

Rigid ceiling directly applied or 7-4-5 oc bracing.

Thomas A. Albani PE No.39380 MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610

September 17,201

Continued on page 2

🛕 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system, Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design, Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **

ANSTPH Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



					T		
Job		Truss	Truss Type	Qty	Ply	MIKE TODD CONST - SMITH CARPORT	T18132982
2067658		T01A	HIP GIRDER	1	2		
					-	Job Reference (optional)	
7.71	F: .10	t		- 1	R 240 e Jul	14 2019 MiTek Industries, Inc., Tue Sep 17 12:50:56 2019	J Page 2

Builders FirstSource, Jacksonville, FL - 32244, ID:BdOFrdQ122jR1Mb5pLe1CxzwahK-0AEzLg6HJzJKrXgcWUXdMBCTl0o5u_J4pqoTZ2ycjXz

NOTES-

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 125 lb down and 100 lb up at 7-0-0, 106 lb down and 100 lb up at 9-0-12, 106 lb down and 100 lb up at 11-0-12, 106 lb down and 100 lb up at 13-0-12, 106 lb down and 100 lb up at 15-0-12, 106 lb down and 100 lb up at 17-0-12, 106 lb down and 100 lb up at 17-0-12, 106 lb down and 100 lb up at 17-0-12, 106 lb down and 100 lb up at 18-0-12, 106 lb down and 100 lb u lb down and 100 lb up at 18-11-4, 106 lb down and 100 lb up at 20-11-4, 106 lb down and 100 lb up at 22-11-4, 106 lb down and 100 lb up at 24-11-4, and 106 lb down and 100 lb up at 26-11-4, and 227 lb down and 252 lb up at 29-0-0 on top chord, and 294 lb down and 335 lb up at 7-0-0, 85 lb down and 82 lb up at 9-0-12, 85 lb down and 82 lb up at 11-0-12, 85 lb down and 82 lb up at 11-0-12, 85 lb down and 82 lb up at 13-0-12, 85 lb down and 82 l 18-11-4, 85 lb down and 82 lb up at 20-11-4, 85 lb down and 82 lb up at 22-11-4, 85 lb down and 82 lb up at 24-11-4, and 85 lb down and 82 lb up at 26-11-4, and 294 ib down and 335 lb up at 28-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-3=-54, 3-8=-54, 8-10=-54, 2-9=-20


Concentrated Loads (lb)

Vert: 3=-106(F) 6=-106(F) 8=-180(F) 16=-284(F) 11=-284(F) 21=-106(F) 22=-106(F) 23=-106(F) 24=-106(F) 25=-106(F) 26=-106(F) 27=-106(F) 28=-106(F) 29=-106(F) 30=-61(F) 31=-61(F) 32=-61(F) 31=-61(F) 31=-61(F)

http://ap2.columbia.floridapa.com: 88/gismapserver?LAYERS = allroadtext & MAP = %2Fww... 9/17/2019 =

dot	Truss		Truss Type	 Qty	Ply	MIKE TODD CONST - S	MITH CARPORT	T18132983
2067658	T02		Hip	1	1	Job Reference (optional)		
Builders FirstSource,	Jacksonville,	FL - 32244,		 ID:BdOFrdQ12	8.240 s Ju 2iR1Mb5pLe1	14 2019 MiTek Industries CxzwohK-UNoLY07v4HRI	, Inc. Tue Sep 17 12	2:50:57 2019 Page 1 7dLxD1UX05UycjXy
-2-0-0	4-9-8	9-0-0	14-8-10	21-3-6	27-0			
2-0-0	4-9-8	4-2-8	5-8-10	6-6-12	5-8-	10 4-2-8	4-9-8	2-0-0

Scale = 1:65.2



—	9-0-0	+	18-0-0 9-0-0		27-0-0 9-0-0		+	36-0-0 9-0-0	
Plate Offsets (X,Y)-	9-0-0 [2:0-1-15,0-1-8], [4:0-3-0,	,0-2-0], [8:0-3-0			8+0+0			8-0-0	
OADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	V/defl	L/d	PLATES	GRIP
CLL 20.0	Plate Grip DOL	1.25	TC 0.46	Vert(LL)	-0.20 14	>999	240	MT20	244/190
CDL 7.0	Lumber DOL	1,25	BC 0.93	Vert(CT)	-0.43 14-16	>999	180		
CLL 0.0 *	Rep Stress Incr	YES	WB 0.77	Horz(CT)	0.13 10	n/a	n/a		
3CDL 10.0	Code FBC2017/Ti	PI2014	Matrix-MS	1 '				Weight: 181 lb	FT = 20%

TOP CHORD

BOT CHORD

REACTIONS.

TOP CHORD 2x4 SP No.2 **BOT CHORD** 2x4 SP No.2 **WEBS**

2x4 SP No.3

2=1440/0-8-0, 10=1440/0-8-0 (lb/size)

Max Horz 2=-75(LC 10)

Max Uplift 2=-264(LC 9), 10=-264(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2515/1280, 3-4=-2263/1140, 4-5=-1997/1079, 5-7=-2595/1352, 7-8=-1997/1079, 8-9=-2263/1140, 9-10=-2515/1280


BOT CHORD 2-16=-985/2206, 14-16=-1078/2532, 12-14=-1083/2532, 10-12=-1017/2206

3-16=-265/269, 4-16=-309/742, 5-16=-765/388, 7-12=-765/388, 8-12=-309/742, **WEBS**

9-12=-265/268

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide
- will fit between the bottom chord and any other members.
 6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=264, 10=264.



Structural wood sheathing directly applied or 3-3-7 oc purlins.

Rigid ceiling directly applied or 2-2-0 oc bracing.

Date:


September 17,201

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE. Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSUTP!1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



Job	Truss	201100	Truss Type	Qty	Ply	MIKE TO	DD CONST - SMITH C	ARPORT	
						. }			T18132984
2067658	T02A		Hip	[1		1			
							rence (optional)		
Builders FirstSource.	Jacksonvi	lle. FL - 32244.			8.240 s	ul 14 2019 M	MiTek Industries, Inc. T	ue Sep 17 12:50:5	8 2019 Page 1
				ID:BdOFrdQ122	R1Mb5pLe1	CxzwohK-zZl	MkmM8YrbZ24rq?evZ6	5RcHnUqRMMoBM	IG8HadwycjXx
-2-0-0	4-9-8	9-0-0	14-8-10	21-3-6	27	-0-0	31-2-8	36-0-0	38-0-0
	4-9-8	4-2-8	5-8-10	6-6-12	5-	8-10	4-2-8	4-9-8	2-0-0



	i	9-0-0		18-0-0		27-0-0		7	36-0-0		
	9-0-0			9-0-0		9-0-0			9-0-0		
Plate Offse	ts (X,Y)-	[2:0-8-0,0-0-3], [4:0-3-0,0	0-8-0,0-0-3]								
LOADING	(psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC 0.68	Vert(LL)	0.43 14-16	>999	240	MT20	244/190	
TCDL	7.0	Lumber DOL	1.25	BC 0.93	Vert(CT)	-0.43 14-16	>999	180			
BCLL	0.0 *	Rep Stress Incr	YES	WB 0.77	Horz(CT)	0.13 10	n/a	n/a			
BCDL	10.0	Code FBC2017/TI	PI2014	Matrix-MS					Weight; 181 lb	FT = 20%	

BRACING-TOP CHORD

BOT CHORD

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.2 2x4 SP No.2 BOT CHORD 2x4 SP No.3 **WEBS**

(lb/size) 2=1440/0-3-8, 10=1440/0-3-8

Max Horz 2=-75(LC 10)

Max Uplift 2=-680(LC 9), 10=-680(LC 8)

FORCES. (ib) - Max. Comp./Max. Ten. - All forces 250 (ib) or less except when shown.

TOP CHORD 2-3=-2515/2713, 3-4=-2263/2535, 4-5=-1997/2342, 5-7=-2595/2989, 7-8=-1997/2342,

8-9=-2263/2535, 9-10=-2515/2713

BOT CHORD 2-16=-2286/2206, 14-16=-2576/2532, 12-14=-2581/2532, 10-12=-2317/2206 WEBS

3-16=-265/334, 4-16=-943/742, 5-16=-765/693, 7-12=-765/693, 8-12=-942/742,

9-12=-265/334

NOTES-

1) Unbalanced roof live loads have been considered for this design.


2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Extenor(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

3) Provide adequate drainage to prevent water ponding.

- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.

6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.

7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=680, 10=680.



Structural wood sheathing directly applied or 3-3-7 oc purlins.

Rigid ceiling directly applied or 2-2-0 oc bracing.

MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610 Date:

September 17,201

🗥 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev., 10/03/2015 BEFORE USE. Design valid for use only with MITe® connectors. This design is based only upon parameters shown, and is for an Individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, crection and bracing of trusses and truss systems, see

ANSITE! Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



Job	Truss		Truss Type	Qty	Ply	MIKE TODD CONST - SMI	TH CARPORT	
2007650	Too		l Co-					T18132985
2067658	T03		Hip	1	1			
						Job Reference (optional)		
Builders FirstSource,	Jacksonville,	FL - 32244,			8.240 s Jul	14 2019 MiTek Industries, Ir	nc. Tue Sep 17 12:51:0	00 2019 Page 1
						CxzwohK-vyUUA29oNCpmJ	J9_NIKcZX1M8OdCvqp	YfkSmgipycjXv
-2-0-0	5-7-15	11-0-0	18-0-0	25-0-0		30-4-1	36-0-0	38-0-0
2-0-0	5-7-15	5-4-1	7-0-0	7-0-0		5-4-1	5-7-15	2-0-0




Plate Offsets (X,Y)	5-7-15 5-4-1 [4:0-6-0,0-2-8], [6:0-6-0,0-2-8], [8:0-2-1	7-0-0 5,Edge]	7-0-0 5	-4-1 ' 5-7-15 '
LOADING (psf) TCLL 20.0 TCDL 7.0 BCLL 0.0 * BCDL 10.0	SPACING- 2-0-0 Plate Grip DOL 1.25 Lumber DOL 1.25 Rep Stress Incr YES Code FBC2017/TPI2014	CSI. TC 0.59 BC 0.60 WB 0.33 Matrix-MS	DEFL. in (loc) I/defl L/ Vert(LL) -0.16 13 >999 24 Vert(CT) -0.32 11-13 >999 18 Horz(CT) 0.12 8 n/a n/	0 MT20 244/190

BOT CHORD

REACTIONS.

TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS

2x4 SP No.3

(lb/size) 2=1440/0-8-0, 8=1440/0-8-0

Max Horz 2=-88(LC 10)

Max Uplift 2=-275(LC 12), 8=-275(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2523/1262, 3-4=-2111/1110, 4-5=-2190/1225, 5-6=-2190/1225, 6-7=-2111/1110,

7-8=-2523/1262

BOT CHORD 2-16=-963/2201, 15-16=-963/2201, 13-15=-705/1835, 11-13=-711/1835, 10-11=-993/2201,

8-10=-993/2201

WEBS

3-15=-428/324, 4-15=-118/400, 4-13=-227/566, 5-13=-434/325, 6-13=-227/566,

6-11=-118/400, 7-11=-428/323

NOTES-

1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

3) Provide adequate drainage to prevent water ponding.

- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads,
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.

6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.

7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=275, 8=275.



Structural wood sheathing directly applied or 3-1-14 oc purlins.

Rigid ceiling directly applied or 5-11-6 oc bracing.

MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd, Tampa FL 33610 Date:


September 17,2019

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEX REFERENCE PAGE MII-7473 rev 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property demange. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANS/VTP11 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



Job	Truss	Tru	iss Type	Qty	Ply	MIKE TODD CONST - SMITH	CARPORT	
400	111000			1 '	'	}		T18132986
2067658	TO3A	Hip		1	1			
200.000		1.			1	Job Reference (optional)		
Builders FirstSource.	Jacksonville, F	1 - 32244			8.240 s Ju	I 14 2019 MiTek Industries, Inc.	Tue Sep 17 12:51:1	01 2019 Page 1
Danasia i natobaros;	oud.toomvine; v			ID:BdOFrdQ122jF	1Mb5pLe1	CxzwohK-N81sONAQ8WxdxlZa	J17o3EvIO1Y8ZB7	py6VEEFycjXu
-2-0-0	5-7-15	11-0-0	18-0-0	25-0-0		30-4-1	36-0-0	38-0-0
2-0-0	5-7-15	5-4-1	7-0-0	7-0-0		5-4-1	5-7-15	2-0-0



	ł	5-7-15	11-0-0	18-0-0	25-	0-0		30-4-1	36-0-0	
		5-7-15	5-4-1	7-0-0	7-	D- O	1	5-4-1	5-7-15	
Plate Offse	ts (X,Y)	[4:0-6-0,0-2-8], [6:0-6-0,0	0-2-8], [8:0-2-1	5,Edge]						
LOADING	(psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC 0.70	Vert(LL)	0.31 11-13	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC 0.60	Vert(CT) -	0.32 13-15	>999	180		
BCLL	0.0 *	Rep Stress Incr	YES	WB 0.70	Horz(CT)	0.12 8	n/a	n/a		
BCDL	10.0	Code FBC2017/T	PI2014	Matrix-MS					Weight: 192 lb	FT = 20%

BRACING-

TOP CHORD

BOT CHORD

LUMBER-

TOP CHORD 2x4 SP No.2 2x4 SP No.2 2x4 SP No.3 **BOT CHORD**

WEBS

(lb/size) 2=1440/0-3-8, 8=1440/0-3-8 Max Horz 2=-88(LC 10) REACTIONS.

Max Uplift 2=-652(LC 9), 8=-652(LC 8)

FORCES. ((b) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 2-3=-2523/2772, 3-4=-2111/2363, 4-5=-2190/2552, 5-6=-2190/2552, 6-7=-2111/2363, TOP CHORD

7-8=-2523/2772

BOT CHORD 2-16=-2315/2201, 15-16=-2315/2201, 13-15=-1834/1835, 11-13=-1840/1835,

10-11=-2346/2201, 8-10=-2346/2201

WEBS 3-15=-428/588, 4-15=-521/400, 4-13=-479/566, 5-13=-434/322, 6-13=-479/566,

6-11=-521/400, 7-11=-428/587

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Extenor(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- 3) Provide adequate drainage to prevent water ponding.
 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=652, 8=652.



Structural wood sheathing directly applied or 3-1-14 oc purlins.

Rigid ceiling directly applied or 3-8-7 oc bracing.


MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610


September 17,201

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MIN-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss well and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSITPHI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N, Lee Street, Suite 312, Alexandria, VA 22314,







1	6-8-9 6-8-9	13-0-0 6-3-7		23-0-0		29-3 6-3-		36-0-0 6-8-9	
Plate Offsets (X,Y)-			2-0], [7:0-3-0,0-3-0], [8						
LOADING (psf) TCLL 20.0 TCDL 7.0 BCLL 0.0 * BCDL 10.0	SPACING- Plate Grip DOL Lumber DOL Rep Stress Incr Code FBC2017/	2-0-0 1,25 1,25 YES TPI2014	CSI. TC 0.53 BC 1.00 WB 0.54 Matrix-MS	DEFL. Vert(LL) Vert(CT) Horz(CT)	in (loc) -0.33 12-13 -0.63 12-13 0.11 8	l/defl >999 >689 n/a	L/d 240 180 n/a	PLATES MT20 Weight: 191 lb	GRIP 244/190 FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2 **BOT CHORD** 2x4 SP No.2 2x4 SP No.3 **WEBS**

BRACING-

TOP CHORD **BOT CHORD WEBS**

Structural wood sheathing directly applied or 3-4-2 oc purlins.

Rigid ceiling directly applied or 2-2-0 oc bracing. 1 Row at midpt 5-13, 5-12

REACTIONS. (lb/size) 2=1440/0-8-0, 8=1440/0-8-0

Max Horz 2=102(LC 11) Max Uplift 2=-289(LC 12), 8=-289(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2484/1262, 3-4=-1974/1062, 4-5=-1702/1018, 5-6=-1702/1018, 6-7=-1974/1062,

7-8=-2484/1262

2-15=-954/2159, 13-15=-955/2156, 12-13=-697/1807, 10-12=-979/2156, 8-10=-978/2159

3-13=-536/414, 4-13=-248/575, 5-13=-303/141, 5-12=-303/141, 6-12=-248/575,

7-12=-536/414

NOTES-

BOT CHORD WEBS

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 3) Provide adequate drainage to prevent water ponding.

4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (it=lb) 2=289, 8=289.



Thomas A. Albani PE No.39380 MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610


September 17,201!

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a bruss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of Individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see MSVIPPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



Job	Truss	Truss Type			Qty	Ply	MIKE TODD CONST	- SMITH CARPORT	
		la constitución de la constituci							T1813298
2067658	T04A	Hip			1	1			
						1	Job Reference (option	nal)	
Builders FirstSource,	Jacksonville, FL - 32244,					8.240 s Jul	I 14 2019 MiTek Industr	ries, Inc. Tue Sep 17 12:51	:04 2019 Page 1
					ID:BdOFrdQ12	2jR1Mb5pLe	e1CxzwohK-njj?0PCIRF	RJComH8_AgVhtXmNFTgm	YeFe3kuraycjXr
-2-0-0	6-8-9	13-0-0	1	18-0-0	23-0-0	- 7	29-3-7	36-0-0	38-0-0
2-0-0	6-8-9	6-3-7	1	5-0-0	5-0-0		6-3-7	6-8-9	2-0-0



	-	6-8-9	13-0-0		23-0-0	-		-3-7	36-0-0	
Plata Offi	sets (X,Y)-	[3:0-3-0,0-3-4], [4:0-3-0,0	6-3-7	201 17:0 2 0 0 2 41 1	10-0-0 9-0-2-15 Edge		6-	3-7	' 6-8-9	· · · · · · · · · · · · · · · · · · ·
riate Oils	3613 (A, I)	[3.0-3-0,0-3-4], [4.0-3-0,0	0-2-0], [0.0-3-0,t	-2-0], [7.0-3-0,0-3-4], [6.0-2-13,Eugej					
LOADING	G (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	Vdefl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC 0.78	Vert(LL)	0.51 12-13	>843	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC 1.00	Vert(CT)	-0.63 12-13	>689	180		
BCLL	0.0	Rep Stress Incr	YES	WB 0.65	Horz(CT)	0.11 8	n/a	n/a		
BCDL	10.0	Code FBC2017/T	Pl2014	Matrix-MS					Weight: 191 lb	FT = 20%

BRACING-

WEBS

TOP CHORD

BOT CHORD

1 Row at midpt

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.2 **BOT CHORD** 2x4 SP No.2 **WEBS**

2x4 SP No.3

(lb/size) 2=1440/0-3-8, 8=1440/0-3-8

Max Horz 2=-102(LC 10)

Max Uplift 2=-622(LC 9), 8=-622(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2484/2730, 3-4=-1974/2240, 4-5=-1702/2082, 5-6=-1702/2082, 6-7=-1974/2240,

7-8=-2484/2730

BOT CHORD 2-15=-2272/2159, 13-15=-2266/2156, 12-13=-1760/1807, 10-12=-2290/2156,

8-10=-2296/2159

WEBS 3-13=-536/709, 4-13=-777/575, 5-13=-303/140, 5-12=-303/140, 6-12=-777/575,

7-12=-536/709

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb)



Structural wood sheathing directly applied or 3-4-2 oc purlins. Rigid celling directly applied or 2-2-0 oc bracing.

5-13, 5-12


MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd, Tampa FL 33610

September 17,201

🗥 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters whom, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web endfor chord members only. Additional temporary and permanent bracing is always required for stability and to prevent bucking of individual truss web endfor chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSUTP!1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



Job	Truss	Truss Type		Qty	Ply	MIKE TODD COM	NST - SMITH CARPORT	
								T18132989
2067658	T05	Hip		2	1			
		-				Job Reference (o		
Builders FirstSource.	Jacksonville, FL - 32244,			8	3.240 s Jul	14 2019 MiTek Inc	dustries, Inc. Tue Sep 17 12:51:0	05 2019 Page 1
			ID:Bd	OFrdQ122	jR1Mb5pL	e1CxzwohK-FvHN	IEIDxCkR2QwsLYtBkE43vletpV_	TOtjTRN0ycjXq
-2-0-0	7-10-12	15-0-0	21-0-0		21	B-1-4	36-0-0	38-0-0
2-0-0	7-10-12	7-1-4	6-0-0		7	7-1-4	7-10-12	2-0-0



	ř	7-10-12	T	15-0-0	21-0-0	28-1-4	1	36-0-0	
		7-10-12		7-1-4	6-0-0	7-1-4		7-10-12	1
Plate Offse	ets (X,Y)-	[3:0-4-0,0-3-0], [4:0-6-0,0	-2-8], [5:0-3-0,0	-2-0], [6:0-4-0,0-3-0	0], [7:0-2-15,Edge]				
LOADING	(psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc) I/defl	L∕d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC 0.94	Vert(LL)	0.28 12-14 >999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC 0.75	Vert(CT)	-0.28 12-14 >999	180		
BCLL	0.0 *	Rep Stress incr	YES	WB 0.74	Horz(CT)	0.11 7 n/a	n/a		
BCDL	10.0	Code FBC2017/T	PI2014	Matrix-MS				Weight: 189 lb	FT = 20%

BRACING-

WEBS

TOP CHORD

BOT CHORD

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3

(lb/size) 2=1440/0-3-8, 7=1440/0-3-8

Max Horz 2=-115(LC 10)

Max Uplift 2=-590(LC 9), 7=-590(LC 8)

FORCES. (ib) - Max. Comp./Max. Ten. - All forces 250 (ib) or less except when shown.

2-3=-2445/2695, 3-4=-1818/2074, 4-5=-1547/1938, 5-6=-1819/2075, 6-7=-2445/2695 BOT CHORD

2-14=-2231/2115, 12-14=-2230/2114, 11-12=-1486/1547, 9-11=-2250/2114, 7-9=-2251/2114

WEBS 3-14=-326/322, 3-12=-662/888, 4-12=-667/484, 5-11=-666/485, 6-11=-661/886,

6-9=-325/321

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=590, 7=590.



Structural wood sheathing directly applied or 2-2-0 oc purlins.

3-12, 4-11, 6-11

Rigid ceiling directly applied or 3-4-12 oc bracing.


1 Row at midpt


MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610

September 17,201

🛕 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MIL-7473 rov. 10/03/2015 BEFORE USE.







- 1	8-6-14		17-0-0	, 19-0-0	27-5-2		36-0-0	
_	8-6-14		8-5-2	2-0-0	8-5-2	1	8-6-14	
Plate Offsets (X,Y)-	[4:0-3-0,Edge], [6:0-3-0,0	-2-0], [7:0-6-0,0	-2-8], [9:0-3-0,Edge	, [11:0-2-15,Edge]				
LOADING (psf) TCLL 20.0 TCDL 7.0 BCLL 0.0 * BCDL 10.0	SPACING- Plate Grip DOL Lumber DOL Rep Stress Incr Code FBC2017/T	2-0-0 1.25 1.25 YES PI2014	CSI. TC 0.70 BC 0.85 WB 1.00 Matrix-MS	DEFL. Vert(LL) Vert(CT) Horz(CT)	0.38 13-15	V/defl L/d >999 240 >999 180 n/a n/a	PLATES MT20 Weight: 210 lb	GRIP 244/190 FT = 20%

BRACING-TOP CHORD

BOT CHORD

WEBS

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.2 2x4 SP No.2 **BOT CHORD** WEBS

2x4 SP No.3

(lb/size) 2=1440/0-3-8, 11=1440/0-3-8

Max Horz 2=-129(LC 10)

Max Uplift 2=-556(LC 9), 11=-556(LC 8)

(ib) - Max. Comp./Max. Ten. - All forces 250 (ib) or less except when shown.

TOP CHORD 2-3=-2495/2758, 3-5=-2283/2676, 5-6=-1636/1951, 6-7=-1400/1817, 7-8=-1634/1948,

8-10=-2283/2677, 10-11=-2495/2759

2-18=-2314/2178, 16-18=-1850/1821, 15-16=-1309/1398, 13-15=-1857/1821, BOT CHORD

11-13=-2340/2179

WEBS 3-18=-273/315, 5-18=-623/467, 5-16=-591/762, 6-16=-707/501, 7-15=-701/497,

8-15=-594/767, 8-13=-626/469, 10-13=-272/313

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=556, 11=556.



Structural wood sheathing directly applied or 3-5-11 oc purlins.

5-16, 7-16, 8-15

Rigid ceiling directly applied or 3-5-5 oc bracing.

1 Row at midpt

Thomas A. Albani PE No.39380 MiTek USA, Inc. FL Gert 6634 6904 Parke East Blvd. Tampa FL 33610


September 17,201

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rov. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent bucking of individual truss web and/or chord members only. Additional temporary and permanent tracing is shways required for stability and to prevent collapse with possible personal injury and property damage. For general guidence regarding the fabrication, storage, delivery, eraction and bracing of trusses and truss systems, see

ANSI/TP11 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.





LUMBER-

TOP CHORD 2x4 SP No.2 2x4 SP No.2 **BOT CHORD**

2x4 SP No.3 WEBS

BRACING-

TOP CHORD BOT CHORD WEBS

Structural wood sheathing directly applied or 3-4-11 oc purlins.

Rigid ceiling directly applied or 3-4-0 oc bracing. 6-14, 7-14, 5-14 1 Row at midpt

REACTIONS. (lb/size) 2=1440/0-3-8, 10=1440/0-3-8

Max Horz 2=-135(LC 10)

Max Uplift 2=-538(LC 9), 10=-538(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown 2-3=-2476/2741, 3-5=-2268/2682, 5-6=-1570/1906, 6-7=-1570/1906, 7-9=-2268/2682,

9-10=-2476/2741

2-16=-2295/2157, 14-16=-1760/1748, 12-14=-1766/1748, 10-12=-2318/2157 BOT CHORD WEBS

6-14=-1449/1067, 7-14=-605/762, 7-12=-703/505, 9-12=-299/344, 5-14=-605/762,

5-16=-703/505, 3-16=-299/344

NOTES-

TOP CHORD

1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp C; Encl. GCpi=0.18; MWFRS (envelope) and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.

5) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.

6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=538, 10=538.



MiTek USA, Inc. FL Cert 6634 6904 Parke East Blvd. Tampa FL 33610

September 17,201

🛕 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

**ASITPH Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




Symbols

PLATE LOCATION AND ORIENTATION



Apply plates to both sides of truss and fully embed teeth. offsets are indicated Center plate on joint unless x, y Dimensions are in ft-in-sixteenths.



plates 0- ५,६" from outside edge of truss. For 4 x 2 orientation, locate

connector plates. required direction of slots in This symbol indicates the

*Plate location details available in MiTek 20/20 software or upon request.

PLATE SIZE

4 × 4


the length parallel to slots. to slots. Second dimension is width measured perpendicular The first dimension is the plate

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



number where bearings occur. Min size shown is for crushing only reaction section indicates joint (supports) occur. Icons vary but Indicates location where bearings

Industry Standards


ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.

DSB-89

Guide to Good Practice for Handling, Building Component Safety Information Connected Wood Trusses Installing & Bracing of Metal Plate Design Standard for Bracing.

Numbering System

6-4-8



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988 ER-3907, ESR-2362, ESR-1397, ESR-3282

truss unless otherwise shown. Trusses are designed for wind loads in the plane of the

established by others. section 6.3 These truss designs rely on lumber values Lumber design values are in accordance with ANSI/TPI 1

© 2012 MiTek® All Rights Reserved



MiTek Engineering Reference Sheet: MII-7473 rev. 10/03/2015

General Safety Notes

Damage or Personal Injury Failure to Follow Could Cause Property

- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
- Truss bracing must be designed by an engineer. For bracing should be considered. may require bracing, or alternative Tor I wide truss spacing, individual lateral braces themselves

Ņ

Never exceed the design loading shown and never stack materials on inadequately braced trusses.

ω

Provide copies of this truss design to the building designer, eraction supervisor, property owner and all other interested parties.

4.

Cut members to bear tightly against each other

Ċ

- Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
- Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
- Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
- Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
- Plate type, size, orientation and location dimensions ndicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that
- Top chords must be sheathed or purlins provided at spacing indicated on design
- 14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
- Connections not shown are the responsibility of others
- Do not cut or alter truss member or plate without prior approval of an engineer
- 17. Instail and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable project engineer before use. environmental, health or performance risks. Consult with
- Review all portions of this design (front, back, words is not sufficient. and pictures) before use. Reviewing pictures alone
- Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.