

PROJECT DESCRIPTION:

30x355 LG NEON2: LG355N1C-N5 (355W) MODULES
ROOF MOUNTED SOLAR PHOTOVOLTAIC MODULES
SYSTEM SIZE: 10.650 kW DC STC
ARRAY AREA #1: 557.75 SQ FT.



EQUIPMENT SUMMARY

30 LG NEON2: LG355N1C-N5 (355W) MODULES
30 ENPHASE: IQ7PLUS-72-2-US MICROINVERTERS


GOVERNING CODES:
FLORIDA RESIDENTIAL CODE, 7th EDITION 2020 (FRC)
FLORIDA PLUMBING CODE, 7th EDITION 2020 (FPC)
FLORIDA BUILDING CODE, 7th EDITION 2020 (FBC)
FLORIDA MECHANICAL CODE, 7th EDITION 2020 (FMC)
NEC 2017 CODE BOOK
ASCE 7-16

| SHEET INDEX | |
|-------------|---------------------------------------|
| A-00 | PLOT PLAN & VICINITY MAP |
| A-01 | SYMBOLS & SYSTEM DESCRIPTION |
| S-01 | ROOF PLAN & MODULES |
| S-01.1 | PARTIAL PRESSURE AND MODULES EXPOSURE |
| S-02 | STRUCTURAL ATTACHMENT DETAILS |
| S-02.1 | STRUCTURAL CALCULATIONS |
| E-01 | ELECTRICAL LINE DIAGRAM |
| E-02 | WIRING CALCULATIONS |
| E-03 | SYSTEM LABELING |

DS-01-06 DATA SHEETS



2 HOUSE PHOTO
A-00 SCALE: NTS



3 VICINITY MAP
A-00 SCALE: NTS



DESIGNED TO PERMIT


CASTILLO ENGINEERING SERVICES, LLC

COA #28345
620 N. WYMORE ROAD,
SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING
SERVICES, LLC

| REVISIONS | | |
|-------------|------|-----|
| DESCRIPTION | DATE | REV |
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER



Digitally signed by:
Ermocrates E Castillo
Date: 2021.03.29 17:23:04

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

PLOT PLAN & VICINITY MAP

SHEET SIZE


**ANSI B
11" X 17"**

SHEET NUMBER

A-00


Symbols:

Section.....




Sheet where section is located

Elevation




Detail ID Letter
Sheet where section is located

Detail



Detail ID Letter
Sheet where section is located

Detail




Detail ID Letter
Area to be enlarged
Sheet where section is located

Keyed Notes


1

Keyed note designation on applicable sheet


Ground Terminal



Grounding Point/rod....



Solar Panel



or 00

Module with Source Circuit number

Combiner Box

CB


DC Disconnect

DCD


Main Distribution Panel

MDP


Fuse




Overcurrent Breaker ..



Inverter



Transformer



Automatic

ATS


Transfer Switch

Abbreviations:

| | |
|--------|-------------------------------|
| AC | Alternating Current |
| APPROX | Approximate |
| AWG | American Wire Gauge |
| CB | Combiner Box |
| DC | Direct Current |
| DCD | Direct Current Disconnect |
| DISC | Disconnect |
| (E) | Existing |
| EL | Elevation |
| EQ | Equal |
| JB | Junction Box |
| MCB | Main Combiner Box |
| MFR | Manufacturer |
| MIN | Minimum |
| MISC | Miscellaneous |
| (N) | New |
| OCPD | OverCurrent Protection Device |
| POCC | Point Of Common Coupling |
| PV | Photovoltaic |
| SF | Squarefoot/feet |
| STC | Standard Test Conditions |
| TBD | To Be Determined |
| TYP | Typical |
| VIF | Verify In Field |
| WP | Weather Proof |

System Description

This system is a grid-tied, PV system, with PV generation consisting of 30 LG NEON2 LG355N1C-N5 (355W) MODULES with a combined STC rated dc output power of 10650W. The modules are connected into 30 ENPHASE IQ7PLUS-72-2-US MICROINVERTERS. The inverter has electronic maximum power point tracking to maximize energy captured by the PV modules. The inverter also has an internal ground fault detection and interruption device that is set to disconnect the array in the event that a ground fault that exceeds one ampere should occur. The inverter has DC and AC disconnect integrated system and labels are provided as required by the *National Electric Code*



When the sun is shining, power from the PV array is fed into the inverter, where it is converted from DC to AC. The inverter output is then used to contribute to the power requirements of the occupancy. If PV power meets the requirements of the loads of the occupancy, any remaining PV power is sold back to the utility. When utility power is available, but PV power is not available, building loads are supplied by the utility.

The inverter meets the requirements of IEEE 1547 and UL 1741. This means that if it detects a loss of utility power, it will automatically disconnect from the utility. When utility voltage is restored, the inverter automatically reconnects to the utility grid after verifying utility voltage and frequency stability.

On a day with average Florida sunshine, this system outputs 41.93 kWh per day on site.

REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO

Digitally
Signed by:
Ermocrates E Castillo
Date:
2021.03.29
17:23:04

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

SYMBOLS &
SYSTEM

DESCRIPTION


ANSI B
11" X 17"

SHEET NUMBER

A-01

MODULE TYPE, DIMENSIONS & WEIGHT

NUMBER OF MODULES = 30 MODULES
MODULE TYPE = LG NEON2: LG355N1C-N5 (355W) MODULES
MODULE WEIGHT = 39.68 LBS / 18 KG.
MODULE DIMENSIONS = 66.93"x 40.0" = 18.59 SF
UNIT WEIGHT OF ARRAY = 2.13 PSF



| ARRAY AREA & ROOF AREA CALC'S | | | | | | | | |
|-------------------------------|------------|---------------------|---------------------|--------------------------------|-------|---------|------------|---------------|
| ROOF | ROOF TYPE | ARRAY AREA (sq.Ft.) | ROOF AREA (Sq. Ft.) | ROOF AREA COVERED BY ARRAY (%) | TILT | AZIMUTH | TRUSS SIZE | TRUSS SPACING |
| #1 | METAL ROOF | 557.75 | 1002.91 | 55.61 | 22.6° | 180° | 2"x6" | 24" o.c. |

GENERAL INSTALLATION PLAN NOTES:

1) ROOF ATTACHMENTS TO TRUSSES SHALL BE INSTALLED AS SHOWN IN SHEET S-02 AND AS FOLLOWS FOR EACH WIND ZONE:

| WIND ZONES | NON - EXPOSED MODULES | | EDGE / EXPOSED MODULES | |
|------------|-----------------------|------------|------------------------|------------|
| | SPAN | CANTILEVER | SPAN | CANTILEVER |
| ZONE 1 | 3' - 0" | 1' - 0" | 3' - 0" | 1' - 0" |
| ZONE 1' | X | X | X | X |
| ZONE 2e | 3' - 0" | 1' - 0" | 3' - 0" | 1' - 0" |
| ZONE 2n | 3' - 0" | 1' - 0" | 3' - 0" | 1' - 0" |
| ZONE 2r | 3' - 0" | 1' - 0" | 3' - 0" | 1' - 0" |
| ZONE 3e | 3' - 0" | 1' - 0" | 3' - 0" | 1' - 0" |
| ZONE 3r | 3' - 0" | 1' - 0" | 3' - 0" | 1' - 0" |

SEE SHEET S-02.1 FOR SUPPORTING CALCULATIONS

2) EXISTING RESIDENTIAL BUILDING HAVE 2X6 SYP TRUSSES SPACED @ 24" O.C. AND METAL ROOF DECKS WITH MEAN ROOF HEIGHTS OF 15 FT WITH SEAMS SPACED 12" O.C. EXISTING ROOF SLOPE FOR THE SOLAR RETROFIT IS 22.6 DEGREES. CONTRACTOR TO FIELD VERIFY AND SHALL REPORT TO THE ENGINEER IF ANY DISCREPANCIES EXIST BETWEEN PLANS AND IN FIELD CONDITIONS.

* I CERTIFY THAT THE INSTALLATION OF THE MODULES IS IN COMPLIANCE WITH FBC: RESIDENTIAL CHAPTER 3. BUILDING STRUCTURE WILL SAFELY ACCOMMODATE LATERAL AND UPLIFT WIND LOADS AND EQUIPMENT DEAD LOADS. *



CASTILLO ENGINEERING SERVICES, LLC
COA # 28345
620 N. WYMORE ROAD, SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY CASTILLO ENGINEERING SERVICES, LLC

REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER



Digitally signed by:
Ermocrates E Castillo
Date: 2021.03.29 17:23:05

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME


ROOF PLAN & MODULES

SHEET SIZE

ANSI B
11" X 17"


SHEET NUMBER


S-01




LEGEND

- PVM - PRODUCTION METER (IF REQUIRED)
- UM - UTILITY METER
- SD - SOLADECK
- ACD - AC DISCONNECT
- MDP - MAIN DISTRIBUTION PANEL
- □ - VENT, ATTIC FAN (ROOF OBSTRUCTION)
- - PV ROOF ATTACHMENT
- - SEAM
- - CONDUIT
- CB - COMBINER BOX





(E) BACK YARD



(E) FRONT YARD

| FOR EXPOSED MODULES | | | | | | | |
|---------------------|----|------|------|------|------|------|--|
| 1 | 1' | 2e | 2n | 2r | 3e | 3r | |
| 27.4 | 0 | 27.4 | 38.4 | 38.4 | 38.4 | 43.2 | |

Module Size 18.59 Sq. ft.

| Exposed modules | | | | | | | | Partial Pressure |
|-----------------|-------|----|----|------|------|----|------|------------------|
| | 1 | 1' | 2e | 2n | 2r | 3e | 3r | |
| P1 | 10.62 | 0 | 0 | 7.97 | 0 | 0 | 0 | 32.11 |
| P2 | 8.36 | 0 | 0 | 4.25 | 5.97 | 0 | 0 | 33.43 |
| P3 | 6.10 | 0 | 0 | 6.51 | 5.97 | 0 | 0 | 34.79 |
| P4 | 11.45 | 0 | 0 | 1.17 | 5.43 | 0 | 0.54 | 31.77 |
| P5 | 12.62 | 0 | 0 | 0 | 5.97 | 0 | 0 | 30.93 |
| P6 | 17.03 | 0 | 0 | 1.56 | 0 | 0 | 0 | 28.32 |
| P7 | 9.11 | 0 | 0 | 3.51 | 4.30 | 0 | 1.66 | 33.43 |

| FOR NON-EXPOSED MODULES | | | | | | | |
|-------------------------|----|------|------|------|------|------|--|
| 1 | 1' | 2e | 2n | 2r | 3e | 3r | |
| 18.2 | 0 | 18.2 | 25.6 | 25.6 | 25.6 | 28.8 | |

Module Size 18.59 Sq. ft.





| Non-Exposed modules | | | | | | | | Partial Pressure |
|---------------------|-------|----|------|------|------|----|----|------------------|
| | 1 | 1' | 2e | 2n | 2r | 3e | 3r | |
| P8 | 12.62 | 0 | 0 | 0 | 5.97 | 0 | 0 | 20.58 |
| P9 | 11.31 | 0 | 0 | 1.30 | 5.97 | 0 | 0 | 21.08 |
| P10 | 18.51 | 0 | 0 | 0.08 | 0 | 0 | 0 | 18.23 |
| P11 | 8.44 | 0 | 9.47 | 0.66 | 0 | 0 | 0 | 18.45 |
| P12 | 9.12 | 0 | 9.47 | 0 | 0 | 0 | 0 | 18.20 |

ALLOWABLE MODULE UPLIFT PRESSURE 2 RAILS: 88 PSF

NOTE : PARTIAL PRESSURES OF THE WIND ZONES ON ALL MODULES HAVE BEEN VERIFIED AND ARE WITHIN THE ALLOWABLE PER THE MANUFACTURER SPECIFICATION, INSTALLER SHOULD FOLLOW THE LAYOUT TO AVOID HIGHER ZONAL PARTIAL PRESSURES. ANY CHANGES IN LAYOUT SHOULD BE REPORTED BACK TO THE ENGINEER OF RECORD.

2h₂ DISTANCE : 0' - 10"
0.5h DISTANCE : 7' - 6"

LEGEND

-  - EXPOSED MODULE
-  - NON- EXPOSED MODULE
-  - MIN. MODULE EDGE DISTANCE LINE
-  - MODULE EXPOSURE LINE

Castillo Engineering

DESIGNED TO PERMIT

CASTILLO ENGINEERING SERVICES, LLC
COA # 28345
620 N. WYMORE ROAD, SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING SERVICES, LLC

REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO

Digitally signed by:
Ermocrates E Castillo
Date: 2021.03.29 17:23:05

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST.,
LAKE CITY, FL 32025

SHEET NAME

PARTIAL PRESSURE AND
MODULES EXPOSURE

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER


S-01.1

| REVISIONS | | |
|-------------|------|-----|
| DESCRIPTION | DATE | REV |
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO 

Digitally
Signed by:
Ermocrates
E Castillo
Date:
2021.03.29
17:23:06



PROJECT NAME



ALERTAS RESIDENCE

487 SE DEER ST.,
LAKE CITY, FL 32025



SHEET NAME
STRUCTURAL
ATTACHMENT
DETAILS

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
S-02



ProteaBracket




FOR STANDING SEAM SPECIFIC MECHANICAL LOAD TEST
INFORMATION AND CLAMP INSTALLATION INFORMATION
PLEASE VISIT: WWW.S-5.COM

1 ATTACHMENT DETAIL (FRONT VIEW)

S-02

SCALE - 3" = 1'-0"




2 ATTACHMENT DETAIL

S-02

SCALE: 1" = 1'-0"

(N) PROTEA BRACKET



3 ATTACHMENT DETAIL (ENLARGED VIEW)

S-02

SCALE: 6" = 1'-0"

REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO

Digitally
Signed by:
Ermocrates
E Castillo
Date:
2021.03.29
17:23:06

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME


STRUCTURAL
CALCULATIONS

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

S-02.1



WIND LOAD CALCULATIONS FOR MODULES INSTALLED ON ROOFS WITH A HEIGHT LESS THAN 60'

| SITE INFORMATION | | | |
|--|----------|------------------------------|---------|
| FBC VERSION | 2020 | RISK CATEGORY | II |
| MEAN ROOF HEIGHT (ft) | 15.0 | EXPOSURE CATEGORY | B |
| ROOF LENGTH (ft) | 62.0 | ROOF SLOPE | 5 /12 |
| ROOF WIDTH (ft) | 48.0 | ROOF SLOPE (°) | 22.6 |
| PARAPET HEIGHT (ft) | 0.0 | ROOF TYPE | GABLE |
| MODULE LENGTH (in) | 66.9 | ULTIMATE WIND SPEED | 120 mph |
| MODULE WIDTH (in) | 40.0 | NOMINAL WIND SPEED | 93 mph |
| MODULE ORIENTATION | PORTRAIT | EXPOSURE FACTOR (C_e) | 1.000 |
| MODULE AREA (sq. ft) | 18.59 | TEMPERATURE FACTOR (C_t) | 1.000 |
| GROUND SNOW LOAD (psf) | 0.0 | IMPORTANCE FACTOR (I_s) | 1.000 |
| DEAD LOAD (psf) | 3.0 | SLOPE FACTOR (C_s) | 0.910 |
| SLOPED ROOF SNOW LOAD (psf) | 0.0 | K_D | 0.850 |
| EFFECTIVE WIND AREA (ft ²) | 18.6 | K_{ZT} | 1.000 |
| GROUND ELEVATION (ft) | 172.0 | K_E | 0.994 |
| HVHZ | NO | K_Z | 0.575 |

| DESIGN CALCULATIONS | | | | | | | |
|--|-----------|-------|--------|--------------|------|----------------|--|
| VELOCITY PRESSURE (q) = .00256*K _E K _Z K _{zT} K _D V ² | | | | | | | |
| VELOCITY PRESSURE(ASD) 10.7 psf | | | | | | | |
| WIDTH OF PRESSURE COEFFICIENT | 48' * 10% | = | 4.8' | ZONE WIDTH A | 4 FT | | |
| | 15' * 40% | = | 6' | ZONE 2 WIDTH | N/A | (FOR (°) < 7°) | |
| | | | | ZONE 3 WIDTH | N/A | (FOR (°) < 7°) | |
| EXTERNAL PRESSURE COEFFICIENT | ZONE 1 | 0.472 | -1.519 | | | | |
| | ZONE 1' | 0.472 | X | | | | |
| | ZONE 2e | 0.472 | -1.519 | | | | |
| | ZONE 2n | 0.472 | -2.202 | | | | |
| | ZONE 2r | 0.472 | -2.202 | | | | |
| | ZONE 3e | 0.472 | -2.202 | | | | |
| | ZONE 3r | 0.472 | -2.505 | | | | |
| INTERNAL PRESSURE COEFFICIENT (+/-) | | 0.18 | | | | | |


| DESIGN PRESSURES | | | | | |
|------------------|------|-------|-----|--------------------------------------|---------|
| ROOF ZONE | DOWN | UP | | | |
| 1 | 16.0 | -18.2 | psf | | |
| 1' | 16.0 | X | psf | Module allowable uplift pressure 2 n | 88 psf |
| 2e | 16.0 | -18.2 | psf | Module allowable uplift pressure 3 r | 125 psf |
| 2n | 16.0 | -25.6 | psf | Module allowable down pressure | 125 psf |
| 2r | 16.0 | -25.6 | psf | | |
| 3e | 16.0 | -25.6 | psf | | |
| 3r | 16.0 | -28.8 | psf | | |

| ARRAY FACTORS | | | |
|----------------------------------|-----|----------------------|--------|
| ARRAY EDGE FACT OR (EXPOSED) | 1.5 | SOLAR PANEL PRESSURE | |
| ARRAY EDGE FACT OR (NON-EXPOSED) | 1 | EQUALIZATION FACT OR | 0.6923 |

| ADJUSTED DESIGN PRESSURES | | | | |
|---------------------------|------|--------------|-----------------|-----|
| ROOF ZONE | DOWN | UP (Exposed) | UP (N. Exposed) | |
| 1 | 16.0 | -27.4 | -18.2 | psf |
| 1' | 16.0 | X | X | psf |
| 2e | 16.0 | -27.4 | -18.2 | psf |
| 2n | 16.0 | -38.4 | -25.6 | psf |
| 2r | 16.0 | -38.4 | -25.6 | psf |
| 3e | 16.0 | -38.4 | -25.6 | psf |
| 3r | 16.0 | -43.2 | -28.8 | psf |

| ATTACHMENTS USED | | |
|---------------------|------------|-----|
| ATTACHMENT MODEL | S-5 protea | |
| ATTACHMENT STRENGTH | 422 | lbs |

| MAX DESIGN LOADS ALLOWABLE | | | | | | |
|----------------------------|-------|--------------|-----------------|--------------|------------|-------------|
| LIMIT MAX SPAN TO | | N/A | in | | | |
| RAFTER/SEAM SPACING | | 12 | in | NO. OF RAILS | Exposed: 2 | Non. Exp: 2 |
| ROOF ZONE | DOWN | UP (Exposed) | UP (N. Exposed) | | SPANS (E) | SPANS (N.E) |
| 1 | 133.9 | 228.9 | 152.6 | lbs | 36 in | 36 in |
| 1' | 0.0 | X | X | lbs | X in | X in |
| 2e | 133.9 | 228.9 | 152.6 | lbs | 36 in | 36 in |
| 2n | 133.9 | 321.0 | 214.0 | lbs | 36 in | 36 in |
| 2r | 133.9 | 321.0 | 214.0 | lbs | 36 in | 36 in |
| 3e | 133.9 | 321.0 | 214.0 | lbs | 36 in | 36 in |
| 3r | 133.9 | 361.8 | 241.2 | lbs | 36 in | 36 in |



SOLAR ARRAY (10.650 kW-DC STC)
(30) LG NEON2: LG355N1C-N5 (355W) MODULES
(03) BRANCH OF 10 MODULES

NOTE:
1. SUBJECT PV SYSTEMS HAS BEEN DESIGNED TO MEET THE REQUIREMENTS OF THE NEC 2017, AND THOSE SET FORTH BY THE FLORIDA SOLAR ENERGY CENTER CERTIFICATION, INCLUDING MAXIMUM NUMBER OF MODULE STRINGS, MAXIMUM NUMBER OF MODULES PER STRING, MAXIMUM OUTPUT, MODULE MANUFACTURER AND MODEL NUMBER, INVERTER MANUFACTURER AND MODEL NUMBER, AS APPLICABLE.
2. LOAD CALCULATIONS PRIOR TO MAIN BREAKER DE-RATE TO BE PROVIDED BY INSTALLER OR ELECTRICAL CONTRACTOR.

INTERCONNECTION
120% RULE - NEC 705.12(B)(2)(3)(b)
UTILITY FEED + SOLAR BACKFEED
175A + 50A = 225A
BUSS RATING x 120%
200A x 120% = 240A

DESIGNED TO PERMIT

CASTILLO ENGINEERING SERVICES, LLC
COA # 28345
620 N. WYMORE ROAD,
SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING SERVICES, LLC

| REVISIONS | | |
|-------------|------|-----|
| DESCRIPTION | DATE | REV |
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

Digitally signed by:
Ermocrates E Castillo
Date: 2021.03.29 17:23:07

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

ELECTRICAL LINE DIAGRAM

SHEET SIZE

**ANSI B
11" X 17"**

SHEET NUMBER

E-01

AC CONDUCTOR AMPACITY CALCULATIONS:
FROM ROOF TOP SOLADECK TO LOAD CENTER

AC CONDUCTOR AMPACITY CALCULATIONS:
FROM AC COMBINER BOX TO MSP

ELECTRICAL NOTES

| | |
|--------------------------|-------------------|
| Module Manufacturer | LG |
| Module Model | LG355N1G-N5 |
| Inverter Manufacturer | ENPHASE |
| Inverter Model | ENPHASE IQ 7 PLUS |
| Modules/Branch Circuit 1 | 10 |
| Modules/Branch Circuit 2 | 10 |
| Modules/Branch Circuit 3 | 10 |
| TOTAL ARRAY POWER (kW) | 10.65 |
| SYSTEM AC VOLTAGE | 240V 1-PHASE |

| DESIGN TEMPERATURE | |
|-----------------------|-----|
| MIN. AMBIENT TEMP. °F | 32 |
| MAX. AMBIENT TEMP. °F | 117 |
| CALCULATED MAX. VOC | 45 |
| CALCULATED MIN VMP | 27 |
| CONDUIT FILL | |
| NUMBER OF CONDUITS | 1 |

| AMPACITY CALCULATIONS | | | | | | | | | | |
|-----------------------------|----------|--------------------|-----|-------------------|--------------------|----------------|-----------------|----------------|---------------------|----------------------------|
| CIRCUIT | MAX AMPS | 1.25 X MAX AMPS | AWG | 90 °C AMPACITY | AMBIENT TEMP °F | TEMP DERATE | CONDUIT FILL | FILL DERATE | DERATED AMPACITY | MAXIMUM CIRCUIT BREAKER |
| CIRCUIT 1 | 12.1 | 15.1 | #12 | 30 | 95 | 0.96 | 6 | 0.8 | 23.04 | 20 A |
| CIRCUIT 2 | 12.1 | 15.1 | #12 | 30 | 95 | 0.96 | 6 | 0.8 | 23.04 | 20 A |
| CIRCUIT 3 | 12.1 | 15.1 | #12 | 30 | 95 | 0.96 | 6 | 0.8 | 23.04 | 20 A |
| AC COMBINER PANEL OUTPUT | 36.3 | 45.3 | #6 | 75 | 95 | 0.96 | 3 | 1 | 72 | 50 A |

| | |
|------------------------------|----|
| MAXIMUM CIRCUIT VOLTAGE DROP | 2% |
|------------------------------|----|

| VOLTAGE DROP CALCULATIONS | | | | | |
|---------------------------|-----|-------------------|------|-----|---------------|
| CIRCUIT | AWG | CIRCULAR MILLS | I | V | MAX LENGTH |
| CIRCUIT 1 | #12 | 6530 | 12.1 | 240 | 101 FEET |
| CIRCUIT 2 | #12 | 6530 | 12.1 | 240 | 101 FEET |
| CIRCUIT 3 | #12 | 6530 | 12.1 | 240 | 101 FEET |
| COMBINER PANEL OUTPUT | #6 | 26240 | 36.3 | 240 | 135 FEET |

| NOTES | |
|---|--|
| TEMP DERATE BASED ON NEC TABLE 310.15(B)(2)(A) | |
| CONDUIT FILL DERATE BASED ON NEC TABLE 310.15(B)(3)(A) | |
| MAXIMUM VOC CALCULATED USING MODULE MANUFACTURE TEMPERATURE COEFFICIENTS PER NEC 690.7(A) | |
| UNLESS OTHERWISE SPECIFIED, ALL WIRING MUST BE THHN OR THWN-2 COPPER | |
| ALL WIRE SIZES LISTED ARE THE MINIMUM ALLOWABLE | |
| | IN ANY CELL INDICATES THAT THE SYSTEM IS SAFE AND COMPLIES WITH NEC REQUIREMENTS |
| | IN ANY CELL INDICATES A POTENTIALLY UNSAFE CONDITION |
| INFORMATION INPUT BY SYSTEM DESIGNER | |
| INFORMATION OBTAINED FROM MANUFACTURER DATASHEETS | |

I ERMOCRATES CASTILLO PE# 52590 AN ENGINEER LICENSED PURSUANT TO CHAPTER 471, CERTIFY THAT THE PV ELECTRICAL SYSTEM AND ELECTRICAL COMPONENTS ARE DESIGNED AND APPROVED USING THE STANDARDS CONTAINED IN THE MOST RECENT VERSION OF THE FLORIDA BUILDING CODE. FBC 107.

| MODULE PROPERTIES | | | |
|-------------------|----------|--------|----------|
| VOC | 41.5 | ISG | 10.8 |
| VMPP | 34.7 | IMP | 10.25 |
| TC VOC | 0.26%/°C | TC VMP | 0.34%/°C |
| PMP | 355.0 | NOCT | 45 °C |

| INVERTER PROPERTIES | |
|----------------------|--------------|
| OUTPUT VOLTAGE | 240 L-L 1-PH |
| MAX INPUT DC VOLTAGE | 60 VOC |
| OPERATING RANGE | 16 - 60 VOC |
| MPPT VOLTAGE RANGE | 27 - 45 VOC |
| START VOLTAGE | 22 VOC |
| MAX INPUT POWER | 440 WDC |
| CONTINUOUS AC POWER | 290 VA |

1. ALL EQUIPMENT TO BE LISTED BY UL OR OTHER NRTL, AND LABELED FOR ITS APPLICATION.
2. ALL CONDUCTORS SHALL BE COPPER, RATED FOR 600 V AND 90 DEGREE C WET ENVIRONMENT. THE TERMINALS ARE RATED FOR 75 DEGREE C.
3. THE WIRES ARE SIZED ACCORDING TO NEC 110.14.
4. WIRING, CONDUIT, AND RACEWAYS MOUNTED ON ROOFTOPS SHALL BE ROUTED DIRECTLY TO, AND LOCATED AS CLOSE AS POSSIBLE TO THE NEAREST RIDGE, HIP, OR VALLEY.
5. WORKING CLEARANCES AROUND ALL NEW AND EXISTING ELECTRICAL EQUIPMENT SHALL COMPLY WITH NEC 110.26.
6. DRAWINGS INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS. CONTRACTOR SHALL FURNISH ALL NECESSARY OUTLETS, SUPPORTS, FITTINGS AND ACCESSORIES TO FULFILL APPLICABLE CODES AND STANDARDS.
7. WHERE SIZES OF JUNCTION BOXES, RACEWAYS, AND CONDUITS ARE NOT SPECIFIED, THE CONTRACTOR SHALL SIZE THEM ACCORDINGLY.
8. ALL WIRE TERMINATIONS SHALL BE APPROPRIATELY LABELED AND READILY VISIBLE.
9. MODULE GROUNDING CLIPS TO BE INSTALLED BETWEEN MODULE FRAME AND MODULE SUPPORT RAIL, PER THE GROUNDING CLIP MANUFACTURER'S INSTRUCTION.
10. MODULE SUPPORT RAIL TO BE BONDED TO CONTINUOUS COPPER G.E.C. VIA WEEB LUG OR ILSGO GBL-4DBT LAY-IN LUG.
11. THE POLARITY OF THE GROUNDED CONDUCTORS IS NEGATIVE .
12. UTILITY HAS 24-HR UNRESTRICTED ACCESS TO ALL PHOTOVOLTAIC SYSTEM COMPONENTS LOCATED AT THE SERVICE ENTRANCE.
13. MODULES CONFORM TO AND ARE LISTED UNDER UL 1703.
14. RACKING CONFORMS TO AND IS LISTED UNDER UL 2703.
15. CONDUCTORS EXPOSED TO SUNLIGHT SHALL BE LISTED AS SUNLIGHT RESISTANT PER NEC ARTICLE 300.6 (C) (1) AND ARTICLE 310.10 (D).
16. CONDUCTORS EXPOSED TO WET LOCATIONS SHALL BE SUITABLE FOR USE IN WET LOCATIONS PER NEC ARTICLE 310.10 (C).

| ENPHASE IQ7PLUS-72-2-US MICROINVERTER | | |
|---------------------------------------|-------------------------------------|---------------|
| Input Data (DC) | | |
| | Recommended Input Power (STC) | 235-440W + |
| | Maximum Input DC Voltage | 60V |
| | Peak Power Tracking Voltage | 27V-45V |
| | Operating Range | 16V-60V |
| | Min. / Max. Start Voltage | 22V / 60V |
| | Max DC Short Circuit Current | 15A |
| Output Data (AC) | | |
| | Maximum Output Power | 290W |
| | Nominal Output Current | 1.21A |
| | Nominal Voltage / Range | 240V/211-264V |
| | Nominal Frequency / Range | 60 Hz |
| | Extended Frequency / Range | 47-68 Hz |
| | Power Factor at rated power | 1.0 |
| | Maximum unit per 20A Branch Circuit | 13 (240 VAC) |

Castillo

Engineering

DESIGNED TO PERMIT

CASTILLO ENGINEERING SERVICES, LLC

COA # 28345

620 N. WYMORE ROAD, SUITE 250, MAITLAND, FL 32751

TEL: (407) 289-2575

ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING
SERVICES, LLC

| REVISIONS | | |
|-------------|------|-----|
| DESCRIPTION | DATE | REV |
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO

Digitally
Signed by:
Ermocrates
E Castillo
Date:
2021.03.29
17:23:07

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME
WIRING
CALCULATIONS

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
E-02

⚠

WARNING

ELECTRIC SHOCK HAZARD

TERMINALS ON BOTH LINE AND
LOAD SIDES MAY BE ENERGIZED
IN THE OPEN POSITION

LABEL LOCATION:
AC DISCONNECT, POINT OF INTERCONNECTION
(PER CODE: NEC 690.13(B))

⚠

WARNING

DUAL POWER SOURCE
SECOND SOURCE IS PHOTOVOLTAIC SYSTEM

LABEL LOCATION:
POINT OF INTERCONNECTION
(PER CODE: NEC 705.12(B)(2)(3)(b))

⚡

RAPID SHUTDOWN
SWITCH FOR
SOLAR PV SYSTEM

LABEL LOCATION:
AC DISCONNECT
(PER CODE: NEC690.56(C)(3))

ADHESIVE FASTENED SIGNS:

- THE LABEL SHALL BE SUITABLE FOR THE ENVIRONMENT WHERE IT IS INSTALLED.
- WHERE REQUIRED ELSEWHERE IN THIS CODE, ALL FIELD APPLIED LABELS, WARNINGS, AND MARKINGS SHOULD COMPLY WITH ANSI Z535.4 [NEC 110.21(B) FIELD MARKING].
- ADHESIVE FASTENED SIGNS MAY BE ACCEPTABLE IF PROPERLY ADHERED. VINYL SIGNS SHALL BE WEATHER RESISTANT [IFC 605.11.1.3]

⚡

10.65 KW SOLAR
DISCONNECT LOCATED

LABEL LOCATION:
AC DISCONNECT, POINT OF INTERCONNECTION
(PER CODE: NEC690.54)

⚡

AC COMBINER BOX

LABEL LOCATION:
COMBINER BOX
(PER CODE: NEC690.52)

⚡

AC DISCONNECT

LABEL LOCATION:
AC DISCONNECT, POINT OF INTERCONNECTION
(PER CODE: NEC690.54)

⚡

PHOTOVOLTAIC SYSTEM AC DISCONNECT

RATED AC OPERATING CURRENT 36.3 AMPS
AC NOMINAL OPERATING VOLTAGE 240 VOLTS

LABEL LOCATION:
AC DISCONNECT, POINT OF INTERCONNECTION
(PER CODE: NEC690.54)

⚠

WARNING

INVERTER OUTPUT CONNECTION DO NOT
RELOCATE THIS OVERCURRENT DEVICE

LABEL LOCATION:
POINT OF INTERCONNECTION
(PER CODE: NEC 705.12(B)(2)(3)(b))

| | | | |
|--|------|----|--|
| DATA PER PANEL | | | |
| NOMINAL OPERATING AC VOLTAGE - | 240 | V | |
| NOMINAL OPERATING AC FREQUENCY- | 60 | Hz | |
| MAXIMUM AC POWER- | 290 | VA | |
| MAXIMUM AC CURRENT- | 1.21 | A | |
| MAXIMUM OVERCURRENT DEVICE RATING FOR AC MODULE PROTECTION PER CIRCUIT- | 20 | A | |

LABEL LOCATION:
COMBINER BOX
(PER CODE: NEC690.52)

⚡

SOLAR
BREAKER

LABEL LOCATION:
POINT OF INTERCONNECTION
(PER CODE: NEC 705.12(B)(2)(3)(b))

⚡

SOLAR CONNECTION
LINE SIDE TAP

LABEL LOCATION:
POINT OF INTERCONNECTION
(PER CODE: NEC 705.12(A))

⚡

PHOTOVOLTAIC
SYSTEM
MICROINVERTERS
LOCATED UNDER EACH
PV MODULE IN
ROOF TOP ARRAY

LABEL LOCATION:
INVERTER
(PER CODE: NEC690.52)

⚡

SOLAR PV SYSTEM EQUIPPED
WITH RAPID SHUTDOWN

TURN RAPID SHUTDOWN
SWITCH TO THE
"OFF" POSITION TO
SHUT DOWN PV SYSTEM
AND REDUCE
SHOCK HAZARD
IN THE ARRAY

SOLAR ELECTRIC
PV PANELS

LABEL LOCATION:
AC DISCONNECT, POINT OF INTERCONNECTION
(PER CODE: NEC 690.56(C)(1)(a), IFC 605.11.3.1(1))

⚡

IMPORTANT

Castillo
Engineering

DESIGNED TO PERMIT:

C

CASTILLO ENGINEERING
SERVICES, LLC
COA # 28345
620 N. WYMORE ROAD,
SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING
SERVICES, LLC

| REVISIONS | | |
|-------------|------|-----|
| DESCRIPTION | DATE | REV |
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO

Digitally
Signed by:
Ermocrates
E Castillo
Date:
2021.03.29
17:23:08

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

SYSTEM
LABELING

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

E-03

LG NeON[®]2

360W 355W 350W

The LG NeON[®] 2 is one of the most powerful and versatile modules on the market today. Featuring LG's Cello Technology in monocrystalline n-type solar cells, the LG NeON[®] 2 increases power output. Now includes a 25 years product and 90.1% performance warranty for higher performance and reliability. The new LG NeON[®] 2 has been designed with aesthetics in mind using new cell design.



Feature



Enhanced Performance Warranty

LG NeON[®] 2 has an enhanced performance warranty. After 25 years, LG NeON[®] 2 is guaranteed to perform at minimum 90.1% of initial performance.



Enhanced Product warranty

LG has extended the warranty of the NeON[®] 2 to 25 years, which is among the top of industry standards.

About LG Electronics

LG Electronics is a global big player, committed to expanding its operations with the solar market. The company first embarked on a solar energy source research program in 1985, supported by LG Group's vast experience in the semi-conductor, LCD, chemistry and materials industries. In 2010, LG Solar successfully released its first Mono[®] series to the market, which is now available in 32 countries. The NeON[®] (previous Mono[®] NeON), NeON[®]2, NeON[®]2 BiFacial won the "Intersolar AWARD" in 2013, 2015 and 2016, which demonstrates LG Solar's lead, innovation and commitment to the industry.



LG NeON[®]2

LG360N1C-N5 LG355N1C-N5 LG350N1C-N5

General Data

| Cell Properties(Material / Type) | Monocrystalline / N-type |
|----------------------------------|--------------------------------|
| Cell Maker | LG |
| Cell Configuration | 60 Cells (6 x 10) |
| Number of Busbars | 12EA |
| Module Dimensions (L x W x H) | 1,700mm x 1,016mm x 40 mm |
| Weight | 18.0 kg |
| Glass(Material) | Tempered Glass with AR Coating |
| Backsheet(Color) | White |
| Frame(Material) | Anodized Aluminium |
| Junction Box(Protection Degree) | IP 68 with 3 Bypass Diodes |
| Cables(Length) | 1,000 mm x 2EA |
| Connector(Type / Maker) | MC 4 / MC |

Certifications and Warranty

| Certifications | IEC 61215-1/-1-1-2:2016, IEC 61730-1/2:2016 ISO 9001, ISO 14001, ISO 50001 OHSAS 18001 |
|-------------------------------|--|
| Salt Mist Corrosion Test | IEC 61701:2012 Severity 6 |
| Ammonia Corrosion Test | IEC 62716 : 2013 |
| Hail Test | 25mm (1") diameter at 23 m/s (52 mph) |
| Fire Rating | Class C (UL 790) |
| Solar Module Product Warranty | 25 Years |
| Solar Module Output Warranty | Linear Warranty* |

* 1) First year : 98% 2) After 1st year : 0.33% annual degradation, 3) 90.1% for 25 years

Temperature Characteristics


| NMOT* | [°C] | 42 ± 3 |
|-------|--------|--------|
| Pmax | [%/°C] | -0.34 |
| Voc | [%/°C] | -0.26 |
| Isc | [%/°C] | 0.03 |

* NMOT (Nominal Module Operating Temperature) Irradiance 800 W/m², Ambient temperature 20 °C, Wind speed 1 m/s, Spectrum AM 1.5

Electrical Properties (NMOT)

| Model | | LG360N1C-N5 | LG355N1C-N5 | LG350N1C-N5 |
|-----------------------------|-----|-------------|-------------|-------------|
| Maximum Power (Pmax) | [W] | 270 | 266 | 263 |
| MPP Voltage (Vmpp) | [V] | 33.0 | 32.6 | 32.2 |
| MPP Current (Impp) | [A] | 8.20 | 8.17 | 8.15 |
| Open Circuit Voltage (Voc) | [V] | 39.2 | 39.1 | 39.0 |
| Short Circuit Current (Isc) | [A] | 8.71 | 8.68 | 8.64 |

I-V Curves



Electrical Properties (STC*)

| Model | | LG360N1C-N5 | LG355N1C-N5 | LG350N1C-N5 |
|---------------------------------|-----|-------------|-------------|-------------|
| Maximum Power (Pmax) | [W] | 360 | 355 | 350 |
| MPP Voltage (Vmpp) | [V] | 35.1 | 34.7 | 34.3 |
| MPP Current (Impp) | [A] | 10.28 | 10.25 | 10.22 |
| Open Circuit Voltage(Voc, ±5%) | [V] | 41.6 | 41.5 | 41.4 |
| Short Circuit Current(Isc, ±5%) | [A] | 10.84 | 10.80 | 10.76 |
| Module Efficiency | [%] | 20.8 | 20.6 | 20.3 |
| Power Tolerance | [%] | 0 ~ +3 | | |

* STC (Standard Test Condition): Irradiance 1000 W/m², Cell temperature 25 °C, AM 1.5,

Measurement Tolerance of Pmax : ± 3%

Operating Conditions

| Operating Temperature | [°C] | -40 ~ +90 |
|-------------------------------|------------|-------------|
| Maximum System Voltage | [V] | 1000(IEC) |
| Maximum Series Fuse Rating | [A] | 20 |
| Mechanical Test Load* (Front) | [Pa / psf] | 5,400 / 113 |
| Mechanical Test Load* (Rear) | [Pa / psf] | 4,000 / 84 |


* Based on IEC 61215-2: 2016 (Test Load = Design Load x Safety Factor(1.5))

※ Mechanical Test Loads 6,000Pa / 5,400Pa based on IEC 61215:2005

Packaging Configuration

| Number of Modules per Pallet | [EA] | 25 |
|---|------|-----------------------|
| Number of Modules per 40ft HQ Container | [EA] | 650 |
| Packaging Box Dimensions (L x W x H) | [mm] | 1,750 x 1,120 x 1,221 |
| Packaging Box Gross Weight | [kg] | 464 |

Dimensions (mm / inch)



Castillo Engineering

DESIGNED TO PERMIT*

CASTILLO ENGINEERING SERVICES, LLC

COA # 28345
620 N. WYMORE ROAD,
SUITE 250,
MAITLAND, FL 32751

TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING
SERVICES, LLC

REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO

Digitally signed by:
Ermocrates E Castillo
Date: 2021.03.29 17:23:08

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

DATA SHEET

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

DS-01



LG Electronics Inc.
Energy Business Division
LG Twin Towers, 128 Yeoul-daero, Yeongdeungpo-gu, Seoul
07336, Korea
www.lg-solar.com

Product specifications are subject to change without notice.
DS-N5-60-C-G-F-EN-200507

© 2020 LG Electronics. All rights reserved.





LG Electronics U.S.A., Inc.
111 Sylvan Avenue
Englewood Cliffs, NJ 07632
201.816.2000

Friday, February 5, 2021

RE: Mechanical Load Testing to Determine Structural Performance under Uniform Static Pressure

To: Castillo Engineering,


Upon your request we have conducted in house tests to determine the structural performance of the LG Module frames listed below. Our test results meet the requirements you presented in our conference call on January 29th. We will present the test criteria, results, and product limitations that may result from these test conditions in this letter.

The specifications and conditions presented in this letter apply retroactively to the following LG module(s);

| | 2 Rails | 3 Rails |
|-------|--|---------|
| Front | 9,000Pa | 9,000Pa |
| Rear | 6,350Pa | 9,000Pa |
| Model | LGxxxN1C(K)-N5(L5), LGxxxN1C(K)-A6(B6) LGxxxQ1C(K)-V5, LGxxxQ1C(K)-A6 | |

*The result is based on test load.

Our R&D department has tested these modules to determine the structural performance of under uniform static loading to represent the effects of a wind load on the module. This test was designed only to determine structural performance; the revised specifications apply only to the mechanical performance of the module. A safety factor of 1.5 should be applied to these test loads for obtaining design loads. It is not recommend designing any system to the full test load.



The scope of this test does not include electrical functionality or performance testing. Subjecting the module to these pressures may result in power degradation or total power loss. The electrical function and power generation warranties and specifications of these products are not altered by this document.

If you have any additional questions or concerns about this letter or the test protocol, contact your LG Solar Sales Representative.

Castillo Engineering
DESIGNED TO PERMIT
CASTILLO ENGINEERING SERVICES, LLC
COA # 28345
620 N. WYMORE ROAD,
SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING SERVICES, LLC

| REVISIONS | | |
|-------------|------|-----|
| DESCRIPTION | DATE | REV |
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO

Digitally signed by:
Ermocrates E Castillo
Date: 2021.03.29 17:23:09

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

DATA SHEET

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

DS-02

Enphase IQ 7 and IQ 7+ Microinverters

The high-powered smart grid-ready **Enphase IQ 7 Micro™** and **Enphase IQ 7+ Micro™** dramatically simplify the installation process while achieving the highest system efficiency.

Part of the Enphase IQ System, the IQ 7 and IQ 7+ Microinverters integrate seamlessly with the Enphase IQ Envoy™, Enphase Q Aggregator™, Enphase IQ Battery™, and the Enphase Enlighten™ monitoring and analysis software.

IQ Series Microinverters extend the reliability standards set forth by previous generations and undergo over a million hours of power-on testing, enabling Enphase to provide an industry-leading warranty of up to 25 years.

Easy to Install

- Lightweight and simple
- Faster installation with improved, lighter two-wire cabling
- Built-in rapid shutdown compliant (NEC 2014 & 2017)

Productive and Reliable

- Optimized for high powered 60-cell and 72-cell* modules
- More than a million hours of testing
- Class II double-insulated enclosure
- UL listed

Smart Grid Ready

- Complies with advanced grid support, voltage and frequency ride-through requirements
- Remotely updates to respond to changing grid requirements
- Configurable for varying grid profiles
- Meets CA Rule 21 (UL 1741-SA)

* The IQ 7+ Micro is required to support 72-cell modules.



To learn more about Enphase offerings, visit enphase.com



Enphase IQ 7 and IQ 7+ Microinverters

| INPUT DATA (DC) | IQ7-60-2-US | | IQ7PLUS-72-2-US | |
|--|---|----------------------|--------------------------------|----------------------|
| Commonly used module pairings ¹ | 235 W - 350 W + | | 235 W - 440 W + | |
| Module compatibility | 60-cell PV modules only | | 60-cell and 72-cell PV modules | |
| Maximum input DC voltage | 48 V | | 60 V | |
| Peak power tracking voltage | 27 V - 37 V | | 27 V - 45 V | |
| Operating range | 16 V - 48 V | | 16 V - 60 V | |
| Min/Max start voltage | 22 V / 48 V | | 22 V / 60 V | |
| Max DC short circuit current (module Isc) | 15 A | | 15 A | |
| Overvoltage class DC port | II | | II | |
| DC port backfeed current | 0 A | | 0 A | |
| PV array configuration | 1 x 1 ungrounded array; No additional DC side protection required; AC side protection requires max 20A per branch circuit | | | |
| OUTPUT DATA (AC) | IQ 7 Microinverter | | IQ 7+ Microinverter | |
| Peak output power | 250 VA | | 295 VA | |
| Maximum continuous output power | 240 VA | | 290 VA | |
| Nominal (L-L) voltage/range ² | 240 V / 211-264 V | 208 V / 183-229 V | 240 V / 211-264 V | 208 V / 183-229 V |
| Maximum continuous output current | 1.0 A | 1.15 A | 1.21 A | 1.39 A |
| Nominal frequency | 60 Hz | | 60 Hz | |
| Extended frequency range | 47 - 68 Hz | | 47 - 68 Hz | |
| AC short circuit fault current over 3 cycles | 5.8 Arms | | 5.8 Arms | |
| Maximum units per 20 A (L-L) branch circuit ³ | 16 (240 VAC) 13 (208 VAC) | | 13 (240 VAC) 11 (208 VAC) | |
| Overvoltage class AC port | III | | III | |
| AC port backfeed current | 0 A | | 0 A | |
| Power factor setting | 1.0 | | 1.0 | |
| Power factor (adjustable) | 0.7 leading ... 0.7 lagging | | 0.7 leading ... 0.7 lagging | |
| EFFICIENCY | @240 V | @208 V | @240 V | @208 V |
| Peak CEC efficiency | 97.6 % | 97.6 % | 97.5 % | 97.3 % |
| CEC weighted efficiency | 97.0 % | 97.0 % | 97.0 % | 97.0 % |
| MECHANICAL DATA | IQ 7 Microinverter | | | |
| Ambient temperature range | -40°C to +65°C | | | |
| Relative humidity range | 4% to 100% (condensing) | | | |
| Connector type | MC4 (or Amphenol F-4 UTX with additional Q-DCC-5 adapter) | | | |
| Dimensions (WxHxD) | 212 mm x 175 mm x 30.2 mm (without bracket) | | | |
| Weight | 1.08 kg (2.38 lbs) | | | |
| Cooling | Natural convection - No fans | | | |
| Approved for wet locations | Yes | | | |
| Pollution degree | PD3 | | | |
| Enclosure | Class II double-insulated, corrosion resistant polymeric enclosure | | | |
| Environmental category / UV exposure rating | NEMA Type 6 / outdoor | | | |
| FEATURES | | | | |
| Communication | Power Line Communication (PLC) | | | |
| Monitoring | Enlighten Manager and MyEnlighten monitoring options. Both options require installation of an Enphase IQ Envoy. | | | |
| Disconnecting means | The AC and DC connectors have been evaluated and approved by UL for use as the load-break disconnect required by NEC 690. | | | |
| Compliance | CA Rule 21 (UL 1741-SA) UL 62109-1, UL1741/IEEE1547, FCC Part 15 Class B, ICES-0003 Class B, CAN/CSA-C22.2 NO. 107.1-01 This product is UL Listed as PV Rapid Shut Down Equipment and conforms with NEC-2014 and NEC-2017 section 690.12 and C22.1-2015 Rule 64-218 Rapid Shutdown of PV Systems, for AC and DC conductors, when installed according manufacturer's instructions. | | | |

1. No enforced DC/AC ratio. See the compatibility calculator at <https://enphase.com/en-us/support/module-compatibility>.
2. Nominal voltage range can be extended beyond nominal if required by the utility.
3. Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area.

To learn more about Enphase offerings, visit enphase.com

© 2018 Enphase Energy. All rights reserved. All trademarks or brands used are the property of Enphase Energy, Inc.
2018-02-08



REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER



Digitally
Signed by:
Ermocrates
E Castillo
Date:
2021.03.29
17:23:09

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

DATA SHEET

SHEET SIZE


ANSI B
11" X 17"

SHEET NUMBER

DS-03

Enphase IQ Combiner 3 (X-IQ-AM1-240-3)

The **Enphase IQ Combiner 3™** with Enphase IQ Envoy™ consolidates interconnection equipment into a single enclosure and streamlines PV and storage installations by providing a consistent, pre-wired solution for residential applications. It offers up to four 2-pole input circuits and Eaton BR series busbar assembly.



Smart

- Includes IQ Envoy for communication and control
- Flexible networking supports Wi-Fi, Ethernet, or cellular
- Optional AC receptacle available for PLC bridge
- Provides production metering and optional consumption monitoring

Simple

- Reduced size from previous combiner
- Centered mounting brackets support single stud mounting
- Supports back and side conduit entry
- Up to four 2-pole branch circuits for 240 VAC plug-in breakers (not included)
- 80 A total PV or storage branch circuits

Reliable

- Durable NRTL-certified NEMA type 3R enclosure
- Five-year warranty
- UL listed



To learn more about Enphase offerings, visit enphase.com



Enphase IQ Combiner 3

| MODEL NUMBER | |
|--|--|
| IQ Combiner 3 X-IQ-AM1-240-3 | IQ Combiner 3 with Enphase IQ Envoy™ printed circuit board for integrated revenue grade PV production metering (ANSI C12.20 +/- 0.5%) and optional* consumption monitoring (+/- 2.5%). |
| ACCESSORIES and REPLACEMENT PARTS (not included, order separately) | |
| Enphase Mobile Connect™ CELLMODEM-03 (4G / 12-year data plan) CELLMODEM-01 (3G / 5-year data plan) CELLMODEM-M1 (4G based LTE-M / 5-year data plan) | Plug and play industrial grade cellular modem with data plan for systems up to 60 microinverters. (Available in the US, Canada, Mexico, Puerto Rico, and the US Virgin Islands, where there is adequate cellular service in the installation area.) |
| Consumption Monitoring* CT CT-200-SPLIT | Split core current transformers enable whole home consumption metering (+/- 2.5%). |
| Circuit Breakers BRK-10A-2-240 BRK-15A-2-240 BRK-20A-2P-240 | Supports Eaton BR210, BR215, BR220, BR230, BR240, BR250, and BR260 circuit breakers. Circuit breaker, 2 pole, 10A, Eaton BR210 Circuit breaker, 2 pole, 15A, Eaton BR215 Circuit breaker, 2 pole, 20A, Eaton BR220 |
| EPLC-01 | Power line carrier (communication bridge pair), quantity 2 |
| XA-PLUG-120-3 | Accessory receptacle for Power Line Carrier in IQ Combiner 3 (required for EPLC-01) |
| XA-ENV-PCBA-3 | Replacement IQ Envoy printed circuit board (PCB) for Combiner 3 |
| ELECTRICAL SPECIFICATIONS | |
| Rating | Continuous duty |
| System voltage | 120/240 VAC, 60 Hz |
| Eaton BR series busbar rating | 125 A |
| Max. continuous current rating (output to grid) | 65 A |
| Max. fuse/circuit rating (output) | 90 A |
| Branch circuits (solar and/or storage) | Up to four 2-pole Eaton BR series Distributed Generation (DG) breakers only (not included) |
| Max. continuous current rating (input from PV) | 64 A |
| Max. total branch circuit breaker rating (input) | 80A of distributed generation / 90A with IQ Envoy breaker included |
| Production Metering CT | 200 A solid core pre-installed and wired to IQ Envoy |
| MECHANICAL DATA | |
| Dimensions (WxHxD) | 49.5 x 37.5 x 16.8 cm (19.5" x 14.75" x 6.63"). Height is 21.06" (53.5 cm with mounting brackets). |
| Weight | 7.5 kg (16.5 lbs) |
| Ambient temperature range | -40° C to +46° C (-40° to 115° F) |
| Cooling | Natural convection, plus heat shield |
| Enclosure environmental rating | Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction |
| Wire sizes | • 20 A to 50 A breaker inputs: 14 to 4 AWG copper conductors • 60 A breaker branch input: 4 to 1/0 AWG copper conductors • Main lug combined output: 10 to 2/0 AWG copper conductors • Neutral and ground: 14 to 1/0 copper conductors Always follow local code requirements for conductor sizing. |
| Altitude | To 2000 meters (6,560 feet) |
| INTERNET CONNECTION OPTIONS | |
| Integrated Wi-Fi | 802.11b/g/n |
| Ethernet | Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included) |
| Cellular | Optional, CELLMODEM-01 (3G) or CELLMODEM-03 (4G) or CELLMODEM-M1 (4G based LTE-M) (not included) |
| COMPLIANCE | |
| Compliance, Combiner | UL 1741 CAN/CSA C22.2 No. 107.1 47 CFR, Part 15, Class B, ICES 003 Production metering: ANSI C12.20 accuracy class 0.5 (PV production) |
| Compliance, IQ Envoy | UL 60601-1/CANCSA 22.2 No. 61010-1 |
| * Consumption monitoring is required for Enphase Storage Systems. | |

To learn more about Enphase offerings, visit enphase.com

© 2018 Enphase Energy. All rights reserved. All trademarks or brands in this document are registered by their respective owner.
2018-09-13



**CASTILLO ENGINEERING
SERVICES, LLC**
COA # 28345
620 N. WYMORE ROAD,
SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590


**COPYRIGHTED BY
CASTILLO ENGINEERING
SERVICES, LLC**

REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO



Digitally
Signed by:
Ermocrates
E Castillo
Date:
2021.03.29
17:23:10

PROJECT NAME

ALERTAS RESIDENCE

**487 SE DEER ST,
LAKE CITY, FL 32025**

SHEET NAME

DATA SHEET

SHEET SIZE

**ANSI B
11" X 17"**

SHEET NUMBER

DS-04


SOLARMOUNT



SOLARMOUNT defined the standard in solar racking. Features are designed to get installers off the roof faster. Our grounding & bonding process eliminates copper wire and grounding straps to reduce costs. Systems can be configured with standard or light rail to meet your design requirements at the lowest cost possible. The superior aesthetics package provides a streamlined clean edge for enhanced curb appeal, with no special brackets required for installation.



LOSE ALL OF THE COPPER & LUGS
System grounding through Enphase microinverters and trunk cables



SMALL IS THE NEXT NEW BIG THING
Light Rail is Fully Compatible with all SM Components



ENHANCED DESIGN & LAYOUT TOOLS
Featuring Google Map Capabilities within U-Builder

FAST INSTALLATION. SUPERIOR AESTHETICS

OPTIMIZED COMPONENTS • VERSATILITY • DESIGN TOOLS • QUALITY PROVIDER

SOLARMOUNT



OPTIMIZED COMPONENTS

INTEGRATED BONDING & PRE-ASSEMBLED PARTS

Components are pre-assembled and optimized to reduce installation steps and save labor time. Our new grounding & bonding process eliminates copper wire and grounding straps or bonding jumpers to reduce costs. Utilize the microinverter mount with a wire management clip for an easier installation.

VERSATILITY

ONE PRODUCT - MANY APPLICATIONS

Quickly set modules flush to the roof or at a desired tilt angle. Change module orientation to portrait or landscape while securing a large variety of framed modules on flat, low slope or steep pitched roofs. Available in mill, clear and dark anodized finishes to outperform your projects financial and aesthetic aspirations.

AUTOMATED DESIGN TOOL

DESIGN PLATFORM AT YOUR SERVICE

Creating a bill of materials is just a few clicks away with U-Builder, a powerful online tool that streamlines the process of designing a code compliant solar mounting system. Save time by creating a user profile, and recall preferences and projects automatically when you log in. You will enjoy the ability to share projects with customers; there's no need to print results and send to a distributor, just click and share.



LISTED UL2703

BONDING & GROUNDING
MECHANICAL LOADING
SYSTEM FIRE CLASSIFICATION

UNIRAC CUSTOMER SERVICE MEANS THE HIGHEST LEVEL OF PRODUCT SUPPORT



TECHNICAL SUPPORT

Unirac's technical support team is dedicated to answering questions & addressing issues in real time. An online library of documents including engineering reports, stamped letters and technical data sheets greatly simplifies your permitting and project planning process.



CERTIFIED QUALITY PROVIDER

Unirac is the only PV mounting vendor with ISO certifications for 9001:2015, 14001:2015 and OHSAS 18001:2007, which means we deliver the highest standards for fit, form, and function. These certifications demonstrate our excellence and commitment to first class business practices.




BANKABLE WARRANTY

Don't leave your project to chance. Unirac has the financial strength to back our products and reduce your risk. Have peace of mind knowing you are receiving products of exceptional quality. SOLARMOUNT is covered by a twenty five (25) year limited product warranty and a five (5) year limited finish warranty.




PROTECT YOUR REPUTATION WITH QUALITY RACKING SOLUTIONS BACKED BY ENGINEERING EXCELLENCE AND A SUPERIOR SUPPLY CHAIN


PUB2017/1828 - PRINTED




INTEGRATED BONDING
MIDCLAMP



INTEGRATED BONDING
SPLICE BAR



INTEGRATED BONDING
L-FOOT w/ T-BOLT



INTEGRATED BONDING
MICROINVERTER MOUNT w/
WIRE MANAGEMENT



DESIGNED TO PERMIT

**CASTILLO ENGINEERING
SERVICES, LLC**
COA # 28345
620 N. WYMORE ROAD,
SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING
SERVICES, LLC

REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER



Digitally
Signed by:
Ermocrates
E Castillo
Date:
2021.03.29
17:23:10

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

DATA SHEET

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

DS-05

CASTILLO ENGINEERING
SERVICES, LLC
COA # 28345
620 N. WYMORE ROAD,
SUITE 250,
MAITLAND, FL 32751
TEL: (407) 289-2575
ERMOCRATES E. CASTILLO - FL PE 52590

COPYRIGHTED BY
CASTILLO ENGINEERING
SERVICES, LLC

REVISIONS

| DESCRIPTION | DATE | REV |
|-------------|------|-----|
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT INSTALLER

SUNPRO

Digitally
Signed by:
Ermocrates
E Castillo
Date:
2021.03.29
17:23:11

PROJECT NAME

ALERTAS RESIDENCE

487 SE DEER ST,
LAKE CITY, FL 32025

SHEET NAME

DATA SHEET

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

DS-06

