



STATE OF FLORIDA
DEPARTMENT OF HEALTH
ONSITE SEWAGE TREATMENT AND DISPOSAL
SYSTEM

PERMIT #: **12-SC-2109612**
APPLICATION #: **AP1525846**
DATE PAID: **7-15-20**
FEE PAID: **310.00**
RECEIPT #: **1525846**
DOCUMENT #: **PR1378513**

CONSTRUCTION PERMIT FOR: OSTDS New
APPLICANT: NEW GENERATION**20-0553 CHRISTIAN MINISTRY INC
PROPERTY ADDRESS: 608 MARVIN BURNETT Lake City, FL 32055
LOT: _____ BLOCK: _____ SUBDIVISION: _____
PROPERTY ID #: 08110-000 [SECTION, TOWNSHIP, RANGE, PARCEL NUMBER]
[OR TAX ID NUMBER]

SYSTEM MUST BE CONSTRUCTED IN ACCORDANCE WITH SPECIFICATIONS AND STANDARDS OF SECTION 381.0065, F.S., AND CHAPTER 64E-6, F.A.C. DEPARTMENT APPROVAL OF SYSTEM DOES NOT GUARANTEE SATISFACTORY PERFORMANCE FOR ANY SPECIFIC PERIOD OF TIME. ANY CHANGE IN MATERIAL FACTS, WHICH SERVED AS A BASIS FOR ISSUANCE OF THIS PERMIT, REQUIRE THE APPLICANT TO MODIFY THE PERMIT APPLICATION. SUCH MODIFICATIONS MAY RESULT IN THIS PERMIT BEING MADE NULL AND VOID. ISSUANCE OF THIS PERMIT DOES NOT EXEMPT THE APPLICANT FROM COMPLIANCE WITH OTHER FEDERAL, STATE, OR LOCAL PERMITTING REQUIRED FOR DEVELOPMENT OF THIS PROPERTY.

SYSTEM DESIGN AND SPECIFICATIONS

T [3,200] GALLONS / GPD New Septic CAPACITY
A [] GALLONS / GPD _____ CAPACITY
N [] GALLONS GREASE INTERCEPTOR CAPACITY [MAXIMUM CAPACITY SINGLE TANK:1250 GALLONS]
K [2,700] GALLONS DOSING TANK CAPACITY [300.00] GALLONS @ [6] DOSES PER 24 HRS #Pumps [2]

D [2,250] SQUARE FEET Drainfield 750 x 3 SYSTEM
R [] SQUARE FEET _____ SYSTEM
A TYPE SYSTEM: [] STANDARD [] FILLED [X] MOUND [] _____
I CONFIGURATION: [X] TRENCH [] BED [] _____
N

F LOCATION OF BENCHMARK: Nail in 10" pine tree south of system site

I ELEVATION OF PROPOSED SYSTEM SITE [24.00] [INCHES] FT [] ABOVE [X] BELOW BENCHMARK/REFERENCE POINT
E BOTTOM OF DRAINFIELD TO BE [24.00] [INCHES] FT [] ABOVE [X] BELOW BENCHMARK/REFERENCE POINT
L

D FILL REQUIRED: [18.00] INCHES EXCAVATION REQUIRED: [] INCHES

O PE designed system is to be served with 2 pumps using an indexing valve system serving three 750 SQFT drain fields.
T 3200 gallon septic tank can be substituted for a 2200 gal septic and a 1050 gall on septic tank in series.
H
E
R

SPECIFICATIONS BY: Paul Lloyd TITLE: P Soil Eval.

APPROVED BY: Sallie A Ford TITLE: Environmental Health Director Columbia CHD

DATE ISSUED: 07/29/2020 EXPIRATION DATE: 01/17/2022

DH 4016, 08/09 (Obsoletes all previous editions which may not be used)
Incorporated: 64E-6.003, FAC



STATE OF FLORIDA
DEPARTMENT OF HEALTH
ONSITE SEWAGE TREATMENT AND DISPOSAL
SYSTEM

APPLICATION FOR CONSTRUCTION PERMIT

CR # 10-7650

PERMIT NO. 20-0559
DATE PAID: 7/15/20
FEE PAID: 310.88
RECEIPT #: 1525846

APPLICATION FOR:

☒ New System ☐ Existing System ☐ Holding Tank ☐ Innovative
☐ Repair ☐ Abandonment ☐ Temporary ☐

APPLICANT: NEW GENERATION CHRISTIAN MINISTRY INC

AGENT: DCM CONSTRYCTION INC.

TELEPHONE: (386) 867-5055

MAILING ADDRESS: 184 N. MARION AVE.

LAKE CITY

FL 32055

TO BE COMPLETED BY APPLICANT OR APPLICANT'S AUTHORIZED AGENT. SYSTEMS MUST BE CONSTRUCTED BY A PERSON LICENSED PURSUANT TO 489.105(3) (m) OR 489.552, FLORIDA STATUTES. IT IS THE APPLICANT'S RESPONSIBILITY TO PROVIDE DOCUMENTATION OF THE DATE THE LOT WAS CREATED OR PLATTED (MM/DD/YY) IF REQUESTING CONSIDERATION OF STATUTORY GRANDFATHER PROVISIONS.

PROPERTY INFORMATION

LOT: N/A BLOCK: N/A SUBDIVISION: METES AND BOUNDS PLATTED: _____

PROPERTY ID #: 07-4S-17-08110-000 ZONING: COM I/M OR EQUIVALENT: ☐ NO ☐

PROPERTY SIZE: 25.150 ACRES WATER SUPPLY: ☐ PRIVATE PUBLIC ☐ ≤ 2000 GPD ☒ > 2000 GPD

IS SEWER AVAILABLE AS PER 381.0065, FS? ☐ NO ☐

DISTANCE TO SEWER: N/A FT

PROPERTY ADDRESS: 608 MARVIN BURNETT RD. LAKE CITY

DIRECTIONS TO PROPERTY:

90 WEST, TURN LEFT ON SISTERS WELCOM BLVD. TURN LEFT ON BASCOM NORRIS DR. TURN RIGHT ON MARVIN BURNETT RD. TURN RIGHT ON SW HIDEAWAY DR. SITE ON RIGHT.

BUILDING INFORMATION ☐ RESIDENTIAL ☒ COMMERCIAL

Unit No.	Type of Establishment	No. of Bedrooms	Building Area Sqft	Commercial/Institutional System Design Table 1, Chapter 64E-6, FAC
1	SCHOOL BUILDING	0	11,152	12 CLASS ROOMS X 15 STUDENTS = 180 STUDENTS
2				180 STUDENTS X 10 GPD = 1800 TOTAL GPD
3				
4				

☐ Floor/Equipment Drains ☐ Other (Specify) _____

SIGNATURE: [Signature]

DATE: 7/15/2020