



Lumber design values are in accordance with ANSI/TPI 1 section 6.3  
These truss designs rely on lumber values established by others.

RE: 4294972 - LAKIESHA DIXON

**MiTek, Inc.**

16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200

**Site Information:**

Customer Info: LAKIESHA DIXON Project Name: Dixon Res. Model: Custom  
Lot/Block: N/A Subdivision: N/A  
Address: TBD, TBD  
City: Columbia Cty State: FL

**Name Address and License # of Structural Engineer of Record, If there is one, for the building.**

Name: License #:  
Address:  
City: State:

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: FBC2023/TPI2014 Design Program: MiTek 20/20 8.7  
Wind Code: ASCE 7-22 Wind Speed: 130 mph  
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 4 individual, Truss Design Drawings and 0 Additional Drawings.  
With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No.	Seal#	Truss Name	Date
1	T35369557	T01	10/25/24
2	T35369558	T01G	10/25/24
3	T35369559	T02	10/25/24
4	T35369560	T02G	10/25/24




This item has been digitally signed and sealed by ORegan, Philip, PE on the date adjacent to the seal.  
Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies

The truss drawing(s) referenced above have been prepared by  
MiTek USA, Inc. under my direct supervision based on the parameters  
provided by Builders FirstSource-Lake City, FL.

Truss Design Engineer's Name: ORegan, Philip  
My license renewal date for the state of Florida is February 28, 2025.

**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Philip J. O'Regan PE No.58126  
MiTek Inc. DBA MiTek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

October 25,2024

Job 4294972	Truss T01	Truss Type COMMON	Qty 25	Ply 1	LAKIESHA DIXON	T35369557
----------------	--------------	----------------------	-----------	----------	----------------	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Sep 25 2024 MiTek Industries, Inc. Thu Oct 24 16:17:26 2024 Page 1  
 ID:6lvXpaCz4GibwP7IbzYF17yQdK9-bpJxMhM4Gg6aKZ7FJj0y3UZLQNuTBB64ZRPnteyQ8yN  
 -1-6-0 6-9-11 13-4-6 20-0-0 26-7-10 33-2-5 40-0-0 41-6-0  
 1-6-0 6-9-11 6-6-11 6-7-10 6-7-10 6-6-11 6-9-11 1-6-0

Scale = 1:68.9




Plate Offsets (X,Y)-	[2:0-0-0,0-1-4], [3:0-3-0,0-3-4], [7:0-3-0,0-3-4], [8:0-0-0,0-1-4]
----------------------	--

<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 20.0	Plate Grip DOL	1.25	TC 0.62	Vert(LL)	-0.18 11-13	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.92	Vert(CT)	-0.40 11-13	>884	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.40	Horz(CT)	0.05 8	n/a	n/a		
BCDL 10.0	Code	FBC2023/TPI2014	Matrix-MS						
								Weight: 197 lb	FT = 20%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-5-5 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 6-13, 4-15

**REACTIONS.** (size) 2=0-3-8, 15=0-8-0, 8=0-8-0  
 Max Horz 2=-154(LC 17)  
 Max Uplift 2=-261(LC 8), 15=-890(LC 8), 8=-535(LC 9)  
 Max Grav 2=268(LC 25), 15=1898(LC 1), 8=1071(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-133/479, 3-4=-355/980, 4-5=-859/437, 5-6=-860/437, 6-7=-1843/836, 7-8=-2215/969  
 BOT CHORD 2-16=-436/313, 15-16=-522/310, 11-13=-511/1437, 10-11=-858/2027, 8-10=-830/2043  
 WEBS 5-13=-80/292, 6-13=-844/524, 6-11=-162/523, 7-11=-406/316, 4-13=-300/874, 4-15=-1691/763, 3-15=-573/501, 3-16=-261/247

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 2-6-0, Zone1 2-6-0 to 20-0-0, Zone2 20-0-0 to 25-7-14, Zone1 25-7-14 to 41-6-0 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 261 lb uplift at joint 2, 890 lb uplift at joint 15 and 535 lb uplift at joint 8.

This item has been digitally signed and sealed by O'Regan, Philip, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
 MiTek Inc. DBA MiTek USA FL Cert 6634  
 16023 Swingley Ridge Rd. Chesterfield, MO 63017  
 Date:

October 25,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)



Job 4294972	Truss T01G	Truss Type COMMON SUPPORTED GAB	Qty 2	Ply 1	LAKIESHA DIXON	T35369558
----------------	---------------	------------------------------------	----------	----------	----------------	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.730 s Sep 25 2024 MITek Industries, Inc. Thu Oct 24 16:17:27 2024 Page 1

ID:6lvXpaCz4GibwP7ibzYFI7yQdK9-4?lJZ1Ni1\_ERyjI5sRXBci6d9mRXwj5Eo59KQ5yQ8yM 40-0-0 41-6-0 1-6-0 20-0-0 20-0-0 1-6-0

Scale = 1:72.4




Plate Offsets (X,Y)-- [2:0-2-4,0-2-1], [24:0-2-4,0-2-1], [32:0-3-0,0-3-0], [36:0-3-0,0-3-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.17	Vert(LL) -0.00	25	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.10	Vert(CT) -0.00	25	n/r	120		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.09	Horz(CT) 0.01	24	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-S					Weight: 225 lb	FT = 20%

**LUMBER-**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.3

**BRACING-**  
TOP CHORD 2-0-0 oc purlins (6-0-0 max.).  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** All bearings 40-0-0.  
(lb) - Max Horz 2=148(LC 16)  
Max Uplift All uplift 100 lb or less at joint(s) 35, 36, 37, 38, 39, 40, 41, 33, 32, 31, 30, 29, 28, 27 except 2=-132(LC 8), 42=-121(LC 12), 26=-123(LC 13), 24=-149(LC 9)  
Max Grav All reactions 250 lb or less at joint(s) 2, 34, 35, 36, 37, 38, 39, 40, 41, 42, 33, 32, 31, 30, 29, 28, 27, 26, 24

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 10-11=-68/267, 11-12=-82/323, 12-13=-95/378, 13-14=-95/378, 14-15=-82/323, 15-16=-68/267

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 35, 36, 37, 38, 39, 40, 41, 33, 32, 31, 30, 29, 28, 27 except (jt=lb) 2=132, 42=121, 26=123, 24=149.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, P on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
MITek Inc. DBA MITek USA FL Cert 6634  
16023 Swingley Ridge Rd. Chesterfield, MO 63017  
Date:

October 25,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
16023 Swingley Ridge Rd.  
Chesterfield, MO 63017  
314.434.1200 / MITek-US.com

Job 4294972	Truss T02	Truss Type Monopitch	Qty 25	Ply 1	LAKIESHA DIXON	T35369559
----------------	--------------	-------------------------	-----------	----------	----------------	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Sep 25 2024 MiTek Industries, Inc. Thu Oct 24 16:17:27 2024 Page 1  
ID:6lvXpaCz4GibwP7IbzYF17yQdK9-4?IJZ1N11\_ERYjiSsRXBci6aHmPHwg2Eo59KQ5yQ8yM



Scale = 1:14.5




Plate Offsets (X,Y)--	[2:0-3-5,Edge], [5:0-3-0,0-1-0]							
<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 20.0	Plate Grip DOL 1.25	TC 0.36	Vert(LL) 0.05	4-8	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.25	Vert(CT) -0.04	4-8	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.29	Horz(CT) -0.00	9	n/a	n/a		
BCDL 10.0	Code FBC2023/TPI2014	Matrix-MR					Weight: 22 lb	FT = 20%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 8-6-4 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

**REACTIONS.** (size) 2=0-3-8, 9=0-2-0  
 Max Horz 2=63(LC 8)  
 Max Uplift 2=-268(LC 8), 9=-147(LC 8)  
 Max Grav 2=309(LC 1), 9=183(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-299/393  
 BOT CHORD 2-4=-423/287

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -1-6-0 to 1-5-10, Zone1 1-5-10 to 5-6-12 zone; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 6) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 9.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=268, 9=147.

This item has been digitally signed and sealed by O'Regan, Philip, P on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
 MiTek Inc. DBA MiTek USA FL Cert 6634  
 16023 Swingley Ridge Rd. Chesterfield, MO 63017  
 Date:

October 25,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

**MiTek®**  
 16023 Swingley Ridge Rd.  
 Chesterfield, MO 63017  
 314.434.1200 / MiTek-US.com

Job 4294972	Truss T02G	Truss Type MONO TRUSS	Qty 2	Ply 1	LAKIESHA DIXON	T35369560
----------------	---------------	--------------------------	----------	----------	----------------	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.730 s Sep 25 2024 MiTek Industries, Inc. Thu Oct 24 16:17:28 2024 Page 1  
ID:6lvXpaCz4GibwP7IbzYF17yQdK9-YBRhmNNKoIMlatHeQ82Q9vedZAftfBoN1lutyXyQ8yL



Scale = 1:14.1




Plate Offsets (X,Y)-	[2:0-2-12,0-2-10], [2:0-9-14,0-3-7]
----------------------	-------------------------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.83	Vert(LL)	-0.01	1	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.63	Vert(CT)	0.02	1	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	2	n/a	n/a		
BCDL 10.0	Code	FBC2023/TPI2014	Matrix-MP						Weight: 22 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD 2-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

**REACTIONS.** (size) 2=5-8-8, 4=5-8-8, 2=5-8-8  
 Max Horz 2=69(LC 8)  
 Max Uplift 2=-289(LC 8), 4=-140(LC 12)  
 Max Grav 2=422(LC 1), 4=254(LC 1), 2=422(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 3-4=-140/348

- NOTES-**
- 1) Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 zone; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
  - 3) Gable requires continuous bottom chord bearing.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=289, 4=140, 2=289.
  - 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been digitally signed and sealed by O'Regan, Philip, P on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Philip J. O'Regan PE No.58126  
 MiTek Inc. DBA MiTek USA FL Cert 6634  
 16023 Swingley Ridge Rd. Chesterfield, MO 63017  
 Date:


October 25,2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MI-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)




# Symbols

## PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{1}{16}$ \"/>

— This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in MITtek software or upon request.

## PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I for bracing if indicated.

## BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

## Industry Standards:

- ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
- DSB-22: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.
- BCSI:

# Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

## Product Code Approvals

ICC-ES Reports:  
ESR-1988, ESR-2362, ESR-2685, ESR-3282  
ESR-4722, ESL-1388

## Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITtek® All Rights Reserved

# General Safety Notes




## Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

# MITek®

MITtek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023

# 4/12 PITCH - 18" OH



**Several Notes:**  
 1. The ASHTRU 1-2002 call "Truss to Wall" connections are the responsibility of the Building Designer, not the Truss Manufacturer.  
 2. The Manufacturer's specifications for all hanger connections are to be 24" x 6" x 1/2" U.S.C.  
 3. All hangers are to be Simpson or equivalent U.S.C.O.  
 4. All hanger connections to be made in accordance with the applicable code.  
 5. Trusses are not designed to support back U.S.C.O.  
 6. Dimensions are Per Truss, Shown.

**Notes:**  
 No back charges will be accepted by Builders FirstSource unless approved in writing first.  
 BCI (888) 644-4444

ACSI lumber is certified to truss plans. Any ACSI lumber that comes in contact with truss plans is to be marked on both ends with an approved laser applied stamp.  
 Refer to BCSI-01 Summary Sheet-Order for hanger information and to the ACSI website for more information on ACSI Wood. These prior to and during truss installation.

It is the responsibility of the Contractor to ensure of the proper installation of the truss placement along with the manufacturer's documents and field conditions of the structure connections. If a warranty or dispute is involved, Builders FirstSource will be required to provide the truss placement documents.

It is the responsibility of the Contractor to make sure the placement of trusses are adjusted for plumbing drops, cut lights, etc., so the trusses do not interfere with these type of items.

All trusses are designed for their systems to be designed as to NOT impose any loads on the trusses beyond their design capacity. Trusses are designed to carry any additional loads from above.

This truss placement plan was not created by an engineer, but rather by the Builders FirstSource staff and is solely to be used as an installation guide and does not require a seal. Complete responsibility for the design and construction of the truss system shall remain with the contractor which may be modified by the truss design engineer.

Table and trusses require continuous bottom chord bearing. Refer to local codes for wall framing requirements.

Although all attempts have been made to do an accurate design, Builders FirstSource does not assume any liability for individual truss drawings and truss placement plans for proper installation and placement.



Lake City  
 PHONE: 386-755-6894  
 FAX: 386-755-7873

Jacksonville  
 PHONE: 904-772-6100  
 FAX: 904-772-1973

Tallahassee  
 PHONE: 850-576-5177

Builder: LAKIESHA DIXON  
 Project Address: Columbia City

Model:	Custom
Date:	10-23-24
Drawn By:	KLH
Checked By:	KLH
Issue 1 Date:	N/A
Issue 2 Date:	N/A
Project No.:	4294972
Issue 1 No.:	4294972

MITEK PLATE APPROVAL #'S 2197.2-2197.4, BOISE EWP PRODUCT #'S LVL FL1644-R2, BCI JOISTS FL1392-R2