



Lumber design values are in accordance with ANSI/TPI 1 section 6.3
These truss designs rely on lumber values established by others.

RE: 3000644 - IC CONST. - DALTON RES.

MiTek USA, Inc.
6904 Parke East Blvd.
Tampa, FL 33610-4115

Site Information:

Customer Info: IC CONSTRUCTION Project Name: Dalton Res. Model: Custom
Lot/Block: N/A Subdivision: N/A
Address: 512 SW Upstage Glen, N/A
City: Columbia Cty State: FL

Name Address and License # of Structural Engineer of Record, If there is one, for the building.

Name: License #:
Address:
City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2020/TPI2014 Design Program: MiTek 20/20 8.4
Wind Code: ASCE 7-16 Wind Speed: 130 mph
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 92 individual, Truss Design Drawings and 0 Additional Drawings.

With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	T26659339	CJ01	1/27/22	23	T26659361	HJ05	1/27/22
2	T26659340	CJ01A	1/27/22	24	T26659362	HJ06	1/27/22
3	T26659341	CJ02	1/27/22	25	T26659363	HJ09	1/27/22
4	T26659342	CJ02A	1/27/22	26	T26659364	HJ10	1/27/22
5	T26659343	CJ03	1/27/22	27	T26659365	PB01	1/27/22
6	T26659344	CJ03A	1/27/22	28	T26659366	PB02	1/27/22
7	T26659345	CJ03B	1/27/22	29	T26659367	PB03	1/27/22
8	T26659346	CJ04	1/27/22	30	T26659368	PB04	1/27/22
9	T26659347	CJ04B	1/27/22	31	T26659369	PB05	1/27/22
10	T26659348	CJ05	1/27/22	32	T26659370	PB06	1/27/22
11	T26659349	EJ01	1/27/22	33	T26659371	T01G	1/27/22
12	T26659350	EJ02	1/27/22	34	T26659372	T02	1/27/22
13	T26659351	EJ03	1/27/22	35	T26659373	T02G	1/27/22
14	T26659352	EJ04	1/27/22	36	T26659374	T03	1/27/22
15	T26659353	EJ05	1/27/22	37	T26659375	T04	1/27/22
16	T26659354	EJ06	1/27/22	38	T26659376	T05	1/27/22
17	T26659355	EJ07	1/27/22	39	T26659377	T06	1/27/22
18	T26659356	EJ08	1/27/22	40	T26659378	T07	1/27/22
19	T26659357	EJ09	1/27/22	41	T26659379	T08	1/27/22
20	T26659358	EJ10	1/27/22	42	T26659380	T09	1/27/22
21	T26659359	EJ11	1/27/22	43	T26659381	T10	1/27/22
22	T26659360	HJ01	1/27/22	44	T26659382	T11	1/27/22




The truss drawing(s) referenced above have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource-Lake City, FL.

Truss Design Engineer's Name: O'Regan, Philip

My license renewal date for the state of Florida is February 28, 2023.

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022



RE: 3000644 - IC CONST. - DALTON RES.

MiTek USA, Inc.
6904 Parke East Blvd.
Tampa, FL 33610-4115

Site Information:

Customer Info: IC CONSTRUCTION Project Name: Dalton Res. Model: Custom
Lot/Block: N/A Subdivision: N/A
Address: 512 SW Upstage Glen, N/A
City: Columbia Cty State: FL

No.	Seal#	Truss Name	Date
45	T26659383	T12	1/27/22
46	T26659384	T13	1/27/22
47	T26659385	T14	1/27/22
48	T26659386	T15	1/27/22
49	T26659387	T16	1/27/22
50	T26659388	T17	1/27/22
51	T26659389	T18	1/27/22
52	T26659390	T19	1/27/22
53	T26659391	T20	1/27/22
54	T26659392	T21	1/27/22
55	T26659393	T22	1/27/22
56	T26659394	T23	1/27/22
57	T26659395	T24	1/27/22
58	T26659396	T25	1/27/22
59	T26659397	T26	1/27/22
60	T26659398	T27	1/27/22
61	T26659399	T28	1/27/22
62	T26659400	T29	1/27/22
63	T26659401	T30	1/27/22
64	T26659402	T31	1/27/22
65	T26659403	T32	1/27/22
66	T26659404	T33	1/27/22
67	T26659405	T33D	1/27/22
68	T26659406	T34	1/27/22
69	T26659407	T34D	1/27/22
70	T26659408	T35	1/27/22
71	T26659409	T35D	1/27/22
72	T26659410	T36	1/27/22
73	T26659411	T37	1/27/22
74	T26659412	T38	1/27/22
75	T26659413	T39	1/27/22
76	T26659414	T40	1/27/22
77	T26659415	T41	1/27/22
78	T26659416	T42	1/27/22
79	T26659417	T43	1/27/22
80	T26659418	T44	1/27/22
81	T26659419	T45	1/27/22
82	T26659420	T46	1/27/22
83	T26659421	T47	1/27/22
84	T26659422	T48	1/27/22
85	T26659423	T49	1/27/22
86	T26659424	T50	1/27/22
87	T26659425	T51	1/27/22
88	T26659426	T52	1/27/22
89	T26659427	T53	1/27/22
90	T26659428	T54	1/27/22
91	T26659429	T55	1/27/22
92	T26659430	T55G	1/27/22

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659339
3000644	CJ01	Jack-Open	7	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:52 2022 Page 1
ID:fGlai9?qNSljAv9NJPFv3izruuC-H71oQQVrex8uSdJUNqDIYoVahofq5WtkrJ32kYzrTtb




Plate Offsets (X,Y)-- [2:Edge,0-1-8]											
LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC	0.24	Vert(LL)	-0.00	7	>999	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.06	Vert(CT)	0.00	7	>999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a		
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MP						Weight: 6 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2


REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=67(LC 12)
Max Uplift 3=-6(LC 1), 2=-114(LC 12), 4=-19(LC 1)
Max Grav 3=10(LC 16), 2=179(LC 1), 4=29(LC 16)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=114.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659340
3000644	CJ01A	Jack-Open	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:53 2022 Page 1
ID:fGlaI9?qNSIjAv9NJPFv3izruuC-IKbAemWTPFGI3nuhxXkX4?2i4C_Cqz7u4zocG?zrTta



Scale = 1:12.9





Plate Offsets (X,Y)-- [2:0-2-0,0-1-12]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.39	Vert(LL)	-0.00	7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.11	Vert(CT)	0.00	7	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 7 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=96(LC 12)
Max Uplift 3=-4(LC 1), 2=-123(LC 12), 4=-21(LC 19)
Max Grav 3=12(LC 8), 2=179(LC 1), 4=39(LC 16)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=123.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:
January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659341
3000644	CJ02	Jack-Open	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:53 2022 Page 1
ID:fGlaI9?qNSIjAv9NJPFv3izruuC-1KbAemWTPFGI3nuhXkX4?2IUC?3qz7u4zocG?zrTta



Scale = 1:9.8

Plate Offsets (X,Y)--		[2:Edge,0-1-8]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL	1.25	TC 0.23		Vert(LL)	-0.00 7	>999	240	MT20	244/190
TCDL 7.0		Lumber DOL	1.25	BC 0.06		Vert(CT)	0.00 7	>999	180		
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.00		Horz(CT)	0.00 2	n/a	n/a		
BCDL 10.0		Code	FBC2020/TPI2014	Matrix-MP						Weight: 6 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=71(LC 12)
Max Uplift 3=-4(LC 12), 2=-109(LC 12), 4=-13(LC 1)
Max Grav 3=10(LC 8), 2=177(LC 1), 4=26(LC 16)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=109.

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-1-11 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659342
3000644	CJ02A	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:54 2022 Page 1
ID:fGlai9?qNSljAv9NJPFv3izruuC-EW9Zr6W59YOchxTtUEGmdDawGcKGZQF1lcY9oRzrTtZ



Scale = 1:9.9

Plate Offsets (X,Y)-- [2:Edge,0-1-8], [6:0-0-7,0-8-1]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.23	Vert(LL)	0.00	9	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.06	Vert(CT)	0.00	9	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.01	Horz(CT)	0.00	2	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MP						Weight: 7 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-2-5 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 2=0-3-8, 5=Mechanical, 5=Mechanical
Max Horz 2=72(LC 12)
Max Uplift 2=-107(LC 12), 5=-17(LC 1), 5=-17(LC 1)
Max Grav 2=175(LC 1), 5=27(LC 16)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5 except (jt=lb) 2=107.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659343
3000644	CJ03	Jack-Open	6	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:55 2022 Page 1
ID:fGlai9?qNSijAv9NJPFv3izruuC-ijix3SXjwsWTJ5232yn?AQ75L?fvItDlBXGHIKtZrTtY



Scale = 1:15.3

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.21	Vert(LL)	-0.01	4-7	>999	MT20	244/190
TCDL 7.0	1.25	BC 0.10	Vert(CT)	-0.01	4-7	>999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MP					Weight: 12 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=125(LC 12)
Max Uplift 3=63(LC 12), 2=97(LC 12)
Max Grav 3=70(LC 19), 2=210(LC 1), 4=50(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 2-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659344
3000644	CJ03A	Jack-Open	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:55 2022 Page 1
ID:fGlai9?qNSljAv9NJPFv3izruuC-ijx3SXjwsWTJ5232yn?AQ73X?eSItDlBXGHIKtztY



Scale = 1:21.3

Plate Offsets (X,Y)--		[2:0-4-0,0-0-8]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.33
TCDL 7.0	Lumber DOL	1.25	BC 0.13
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MP
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.01 4-7 >999 240
			Vert(CT) -0.01 4-7 >999 180
			Horz(CT) -0.00 3 n/a n/a
			PLATES
			MT20
			GRIP
			244/190
			Weight: 14 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2


REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=179(LC 12)
Max Uplift 3=-82(LC 12), 2=-76(LC 12), 4=-1(LC 12)
Max Grav 3=75(LC 19), 2=210(LC 1), 4=51(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 2-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2, 4.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659345
3000644	CJ03B	Jack-Open	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:56 2022 Page 1
ID:fGlai9?oNSIjAv9NJPFv3izruuC-AvHJGoYMhAeKwFcGcfEidGyP0v1KlKmw1GtJzrTtX



Scale = 1:15.0

Plate Offsets (X,Y)-- [3:0-5-13,0-0-6]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	I/defl	L/d
TCLL	20.0	Plate Grip DOL	1.25	TC	0.22	Vert(LL)	-0.00	9	>999
TCDL	7.0	Lumber DOL	1.25	BC	0.05	Vert(CT)	-0.00	9	>999
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	2	n/a
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MP					
								PLATES	GRIP
								MT20	244/190
								Weight: 14 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-0-5 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 2=0-3-8, 6=Mechanical, 4=Mechanical
Max Horz 2=89(LC 12)
Max Uplift 2=-98(LC 12), 6=-16(LC 12)
Max Grav 2=180(LC 1), 6=50(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 6.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:
January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659346
3000644	CJ04	Jack-Open	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:57 2022 Page 1
ID:fGlaig9?qNSljAv9NJPFv3izruuC-e5qhU7Z_STmBYOBSANpTFRcRxpKUmn7T_ampPmzrTtW



Scale = 1:18.2

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.20	Vert(LL)	-0.01	4-7	>999	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.16	Vert(CT)	-0.02	4-7	>999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MP					Weight: 16 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=155(LC 12)
Max Uplift 3=-90(LC 12), 2=-102(LC 12), 4=-4(LC 12)
Max Grav 3=101(LC 19), 2=242(LC 1), 4=70(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 3-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=102.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659347
3000644	CJ04B	Jack-Open	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:58 2022 Page 1

ID:fGlai9?qNSIjAv9NJPfV3izruuC-6HO3hTZcDnu2AYmej4Kin2lbeDhHVDxdDEWMxCzrTtV

-1-6-0
1-6-0
3-0-0
3-0-0
3-5-2
0-5-2

Scale = 1:20.9




Plate Offsets (X,Y)-- [2:Edge,0-1-8]											
LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC	0.21	Vert(LL)	-0.01	8-11	>999	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.12	Vert(CT)	-0.01	8-11	>999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.00	2	n/a		
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MP						Weight: 22 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-5-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 6=Mechanical, 2=0-3-8, 7=Mechanical
Max Horz 2=179(LC 12)
Max Uplift 2=-68(LC 12), 7=-143(LC 12)
Max Grav 6=50(LC 16), 2=224(LC 1), 7=129(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 0-5-0, Interior(1) 0-5-0 to 3-4-6 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 7=143.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	CJ05	Jack-Open	6	1	T26659348

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:58 2022 Page 1
ID:fGlai9?QNSljAv9NJPfV3izruuC-6HO3hTZcDnu2AYmej4Kin2laLDfPVEMdDEWMxCzrTtV



Scale = 1:21.0

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.29	Vert(LL)	0.04	4-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.24	Vert(CT)	-0.06	4-7	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 19 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=184(LC 12)
Max Uplift 3=117(LC 12), 2=108(LC 12), 4=7(LC 12)
Max Grav 3=130(LC 19), 2=276(LC 1), 4=89(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 4-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 3=117, 2=108.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659349
3000644	EJ01	Jack-Partial	9	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:03:59 2022 Page 1
ID:fGlai9?qNSijAv9NJPfV3izruuC-aUySupaE_50vniLrHorxKGIk4dyaEgHmSuFwTezrTtU



Scale = 1:26.6




Plate Offsets (X,Y)-- [2:0-1-12,Edge]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.36	Vert(LL)	-0.08	6-9	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.44	Vert(CT)	-0.15	6-9	>544	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.09	Horz(CT)	0.00	2	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 31 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=235(LC 12)
Max Uplift 4=69(LC 12), 2=128(LC 12), 5=93(LC 12)
Max Grav 4=83(LC 19), 2=346(LC 1), 5=194(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-6=273/255

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 6-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 5 except (jt=lb) 2=128.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659350
3000644	EJ02	Jack-Partial	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:00 2022 Page 1
ID:fGlai9?qNSlJAv9NJPFv3izruuC-2gWq69bslO8mPsw1rVMAfTqxu0Llz5qwhY?T05zrTtT



Scale = 1:35.8

Plate Offsets (X,Y)-- [2:0-4-4,0-0-12]													
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.22	Vert(LL)	-0.01	8-9	>999	240	MT20	244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.15	Vert(CT)	-0.02	8-9	>999	180			
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.13	Horz(CT)	-0.00	8	n/a	n/a			
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 41 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 6=Mechanical, 2=0-3-8, 8=Mechanical
Max Horz 2=318(LC 12)
Max Uplift 6=103(LC 12), 2=-69(LC 12), 8=-117(LC 12)
Max Grav 6=108(LC 19), 2=345(LC 1), 8=189(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=-272/0, 2-3=0/278
BOT CHORD 2-9=-223/257, 8-9=-227/253
WEBS 4-8=-303/271

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 0-5-0, Interior(1) 0-5-0 to 6-11-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 6=103, 8=117.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610


6904 Parke East Blvd
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659353
3000644	EJ05	Jack-Open	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:02 2022 Page 1

ID:fGlai9?qNSIjAv9NJPfV3izruuC-?3eaXrd6H0PteA4PywPeyuvAoqxzR1MD8sUa4zzrTtR



Scale = 1:26.6

Plate Offsets (X,Y)--		[2:0-1-8,0-1-8]	
LOADING (psf)		SPACING-	2-0-0
TCLL 20.0		Plate Grip DOL	1.25
TCDL 7.0		Lumber DOL	1.25
BCLL 0.0 *		Rep Stress Incr	YES
BCDL 10.0		Code	FBC2020/TPI2014
		CSI.	
		TC 0.65	
		BC 0.52	
		WB 0.00	
		Matrix-MS	
		DEFL.	
		in (loc)	L/defl
		Vert(LL) 0.16	4-7 >526
		Vert(CT) -0.22	4-7 >379
		Horz(CT) -0.01	3 n/a
			L/d
			240
			180
			n/a
		PLATES	GRIP
		MT20	244/190
		Weight: 25 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2


REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=235(LC 12)
Max Uplift 3=152(LC 12), 2=128(LC 12), 4=11(LC 12)
Max Grav 3=188(LC 19), 2=346(LC 1), 4=126(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 6-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 3=152, 2=128.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659354
3000644	EJ06	Jack-Open	7	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:03 2022 Page 1

ID:fGlaI9?QNSIjAv9NJPfV3izruuC-TFCykBdl2JXKGJfcWdwtU6SPPEGAATPMNWD7cQzrTtQ




Plate Offsets (X,Y)-- [2:0-1-8,0-1-8]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.40	Vert(LL)	0.24	7-8	>325	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.59	Vert(CT)	-0.22	7-8	>359	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.08	Horz(CT)	-0.01	2	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MP						Weight: 34 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 6=Mechanical, 2=0-3-8, 7=Mechanical
Max Horz 2=309(LC 12)
Max Uplift 6=148(LC 12), 2=-68(LC 12), 7=-67(LC 12)
Max Grav 6=160(LC 19), 2=335(LC 1), 7=119(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=-298/164, 2-3=-152/330

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 0-5-0, Interior(1) 0-5-0 to 6-7-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 7 except (jt=lb) 6=148.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610


Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	EJ07	Half Hip	1	1	T26659355

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:04 2022 Page 1
ID:fGIai9?qNSIjAv9NJPFv3izruuC-xRmLyXeNpdfBuTEo4LR61J?ePekevWfVbAzh9sZrTtP



Scale = 1:35.5



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.19	Vert(LL)	-0.01	7-8	>999	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.12	Vert(CT)	-0.01	7-8	>999		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.10	Horz(CT)	-0.00	7	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP					Weight: 47 lb	FT = 20%
	Code FBC2020/TPI2014							

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 2=0-3-8, 7=Mechanical
Max Horz 2=313(LC 12)
Max Uplift 2=-62(LC 12), 7=-227(LC 12)
Max Grav 2=332(LC 1), 7=276(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=0/251
WEBS 4-7=-283/244

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 0-5-0, Interior(1) 0-5-0 to 6-6-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 7=227.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659356
3000644	EJ08	Jack-Open Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:05 2022 Page 1
ID:fGlai9?qNSIJAv9NJPFv3izruuC-PeJ9tf?axn2Vdp_e2yLaXXpo1yNeMXfqqiEhlzrTtO



Scale = 1:28.6




Plate Offsets (X,Y)-- [3:0-4-0,0-2-6], [6:0-4-4,0-2-0]

LOADING (psf)	SPACING-		CSL.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.15	Vert(LL)	0.05	8-9	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.60	Vert(CT)	-0.05	8-9	>999	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.16	Horz(CT)	-0.00	8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 51 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 8=Mechanical
Max Horz 2=246(LC 27)
Max Uplift 2=-215(LC 8), 8=-470(LC 8)
Max Grav 2=433(LC 1), 8=537(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 3-4=-431/212, 4-6=-475/354, 2-3=-447/190
BOT CHORD 2-9=-297/348
WEBS 6-8=-389/377, 6-9=-389/492

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=215, 8=470.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 192 lb down and 223 lb up at 4-10-13 on top chord, and 298 lb down and 271 lb up at 4-10-13 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 3-6=-54, 6-7=-54, 8-10=-20, 1-3=-54
Concentrated Loads (lb)
Vert: 6=-132(F) 14=-274(F)



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	EJ09	Jack-Open	1	1	T26659357

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:05 2022 Page 1
ID:fGlai9?qNSijAv9NJPFv3izruuC-PeJ9tf?axn2Vdp_e2yLaXXIN10peO5fqqiEhlzrTtO



Scale = 1:22.5

Plate Offsets (X,Y)--		[1:0-1-9,0-1-8]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.43
TCDL 7.0	Lumber DOL	1.25	BC 0.38
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MP
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) 0.04 3-6 >999 240
			Vert(CT) -0.03 3-6 >999 180
			Horz(CT) -0.00 2 n/a n/a
			PLATES
			MT20
			GRIP
			244/190
			Weight: 15 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-2-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 1=0-3-8, 2=Mechanical, 3=Mechanical
Max Horz 1=175(LC 12)
Max Uplift 2=132(LC 12), 3=18(LC 12)
Max Grav 1=153(LC 1), 2=121(LC 19), 3=77(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 4-1-12 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3 except (jt=lb) 2=132.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	EJ10	Jack-Open Girder	1	1	T26659358

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:06 2022 Page 1

ID:fGlai9?qNSljAv9NJPfV3izruuC-tqt5MCgdLEvv7nNBBmTa6k4_RROENqfo3USoDkzrTtN



Scale = 1:22.5

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.16	Vert(LL)	-0.01	5-7	>999	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.24	Vert(CT)	-0.02	5-7	>999		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.11	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Rep Stress Incr NO	Matrix-MP					Weight: 23 lb	FT = 20%
	Code FBC2020/TPI2014							

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-2-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=0-3-8, 3=Mechanical, 5=Mechanical
Max Horz 1=175(LC 23)
Max Uplift 3=-253(LC 29), 5=-338(LC 8)
Max Grav 1=219(LC 1), 3=217(LC 8), 5=662(LC 29)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-395/364

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 3=253, 5=338.
- 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 170 lb down at 1-10-12, and 177 lb down at 3-10-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 1-4=-20
Concentrated Loads (lb)
Vert: 5=-177(F) 8=-170(F)



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659359
3000644	EJ11	Jack-Open	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:07 2022 Page 1
ID:fGlai9?qNSljAv9NJPFv3izruuC-L0RTaYgF6Y1mlyNIT?pfyd8HrlW6IHyl8BLmBzrTtM

-1-6-0
1-6-0
2-8-0
2-8-0

Scale = 1:17.7




Plate Offsets (X,Y)--		[2:Edge,0-1-8]	
LOADING (psf)		SPACING-	2-0-0
TCLL 20.0		Plate Grip DOL	1.25
TCDL 7.0		Lumber DOL	1.25
BCLL 0.0 *		Rep Stress Incr	YES
BCDL 10.0		Code	FBC2020/TPI2014
		CSI.	
		TC 0.21	
		BC 0.11	
		WB 0.02	
		Matrix-MP	
		DEFL.	
		in (loc)	I/defl
		Vert(LL) -0.01 7-10	>999
		Vert(CT) -0.01 7-10	>999
		Horz(CT) 0.00 2	n/a
		L/d	
		240	
		180	
		n/a	
		PLATES	GRIP
		MT20	244/190
		Weight: 17 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-8-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
JOINTS 1 Brace at Jt(s): 4


REACTIONS.

(size) 5=Mechanical, 2=0-3-8, 6=Mechanical
Max Horz 2=220(LC 12)
Max Uplift 5=-98(LC 12), 2=-98(LC 12), 6=-54(LC 12)
Max Grav 5=104(LC 19), 2=321(LC 1), 6=115(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 2-7-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 2, 6.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:
January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659360
3000644	HJ01	Jack-Open	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:07 2022 Page 1
ID:fGlai9?qNSljAv9NJPFv3izruuCLoRTaYgF6Y1mxyNIT?pfyd66rls6lbyl8BLmBzrTtM



Scale = 1:13.2

Plate Offsets (X,Y)-- [2:Edge,0-2-0]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.35	Vert(LL)	0.00	7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.09	Vert(CT)	0.00	7	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MP						Weight: 15 lb	FT = 20%

LUMBER-

TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2
WEDGE
Left: 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-7-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 3=Mechanical, 2=0-5-1, 4=Mechanical
Max Horz 2=93(LC 12)
Max Uplift 3=38(LC 1), 2=186(LC 12), 4=17(LC 1)
Max Grav 3=37(LC 8), 2=315(LC 1), 4=25(LC 16)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=186.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659361
3000644	HJ05	Diagonal Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:08 2022 Page 1
ID:fGlaI9?qNSIjAv9NJPfV3izruuC-pC?rnuhtsr9dM5XZJBW2B99JWF3Crlr5WoxuldrTtL



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.25	Vert(LL)	-0.02	4-7	>999	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.21	Vert(CT)	-0.04	4-7	>999		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.00	Horz(CT)	0.00	2	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MP					Weight: 18 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-5 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-5-8, 4=Mechanical
Max Horz 2=148(LC 26)
Max Uplift 3=-98(LC 8), 2=-157(LC 8), 4=-7(LC 8)
Max Grav 3=100(LC 1), 2=287(LC 1), 4=80(LC 3)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 2=157.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 104 lb down and 92 lb up at 1-3-15 on top chord, and 28 lb down and 48 lb up at 1-3-15, and 29 lb down and 24 lb up at 2-2-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 4-5=-20



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659362
3000644	HJ06	Jack-Open Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:09 2022 Page 1
ID:fGlai9?qNSIjAv9NJPFv3izruuC-HPZE?EiVd9HU_E6mtu1HkNiStfNkaB1EiSgSq3zrTtK




Plate Offsets (X,Y)-- [2:0-1-9,0-1-8]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.34	Vert(LL)	-0.05	6-9	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.32	Vert(CT)	-0.09	6-9	>811	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.07	Horz(CT)	0.00	2	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 28 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-10-11 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 4=Mechanical, 2=0-4-9, 5=Mechanical
Max Horz 2=229(LC 26)
Max Uplift 4=-97(LC 8), 2=-206(LC 8), 5=-103(LC 8)
Max Grav 4=95(LC 32), 2=352(LC 1), 5=176(LC 30)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-326/176

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 2=206, 5=103.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 93 lb down and 89 lb up at 1-6-1, 93 lb down and 89 lb up at 1-6-1, and 119 lb down and 118 lb up at 4-4-0, and 119 lb down and 118 lb up at 4-4-0 on top chord, and 39 lb down and 48 lb up at 1-6-1, 39 lb down and 48 lb up at 1-6-1, and 31 lb down and 9 lb up at 4-4-0, and 31 lb down and 9 lb up at 4-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 5-7=-20
Concentrated Loads (lb)
Vert: 13=-4(F=-2, B=-2)



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659363
3000644	HJ09	Diagonal Hip Girder	3	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:10 2022 Page 1
ID:fGlaI9?qNSIjAv9NJPFv3izruuC-mb7cCaj8OTPLcOhyQcYWHaFeo2iJJC?O_6Q?MWzrTtJ



LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.26	Vert(LL) 0.07	6-7	>999	240		MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.43	Vert(CT) -0.06	6-7	>999	180			
BCLL 0.0 *	Rep Stress Incr NO	WB 0.21	Horz(CT) -0.01	5	n/a	n/a			
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS						Weight: 39 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-3-4 oc bracing.

REACTIONS.

(size) 4=Mechanical, 2=0-5-8, 5=Mechanical
Max Horz 2=243(LC 8)
Max Uplift 4=-217(LC 8), 2=-256(LC 8), 5=-247(LC 8)
Max Grav 4=210(LC 32), 2=416(LC 19), 5=336(LC 32)

FORCES.


(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-557/302
BOT CHORD 2-7=-421/450, 6-7=-421/450
WEBS 3-6=-497/465

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 4=217, 2=256, 5=247.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 106 lb down and 71 lb up at 1-6-0, 143 lb down and 94 lb up at 4-11-14, and 105 lb down and 59 lb up at 6-1-3, and 160 lb down and 159 lb up at 8-5-4 on top chord, and 23 lb down and 45 lb up at 1-6-0, 52 lb down and 25 lb up at 3-7-14, 37 lb down and 16 lb up at 4-11-14, and 91 lb down and 160 lb up at 6-1-3, and 91 lb down and 28 lb up at 8-5-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 5-8=-20
Concentrated Loads (lb)
Vert: 4=-116(F) 6=-67(F) 11=71(F) 12=-2(F) 13=59(B) 15=-11(B) 16=-9(F) 17=-80(B)



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see


ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:11 2022 Page 1
ID:fGlai9?qNSIjAv9NJPFv3izruuC-Enh_Qwkm9mXCDYg8_J3lponkMS_j2iIXDm9VvyzrTtl




6904 Parke East Blvd
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659365
3000644	PB01	GABLE	2	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:12 2022 Page 1
ID:fGlai9?qNSlJAv9NJPfV3izruuC-i_EMdGkOw4f3rirKY0a_M?K0GsTVnZ2hRQv6ROzrTtH



Scale = 1:20.7




Plate Offsets (X,Y)-- [2:0-3-3,0-1-8], [4:0-3-0,0-1-12], [6:0-3-0,0-1-12], [8:0-3-3,0-1-8]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.13	Vert(LL)	0.00	8	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.12	Vert(CT)	0.00	8	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 38 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.


REACTIONS.

- All bearings 10-5-6.
(lb) - Max Horz 2=49(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 2, 8, 12, 10 except 11=141(LC 9)
Max Grav All reactions 250 lb or less at joint(s) 2, 8, 12, 10 except 11=299(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-11 to 2-10-5, Exterior(2R) 2-10-5 to 7-1-3, Interior(1) 7-1-3 to 9-3-7, Exterior(2E) 9-3-7 to 11-10-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4'-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6-0 tall by 2'-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8, 12, 10 except (jt=lb) 11=141.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659366
3000644	PB02	Piggyback	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:13 2022 Page 1
ID:fGlai9?qNSijAv9NJPfV3izruuC-AAokrcI0hOnwTsQX6k5DuDt6BGj8W0Kqg4efzqrTtG



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.51	Vert(LL)	0.01 8 n/r 120	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.42	Vert(CT)	0.02 8 n/r 120				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.05	Horz(CT)	-0.00 7 n/a n/a				
BCDL	10.0	Code FBC2020/TPI2014		Matrix-S							
								Weight: 66 lb FT = 20%			

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


- All bearings 17-3-11.
(lb) - Max Horz 2=103(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2 except 9=233(LC 13), 11=189(LC 12), 10=164(LC 8), 7=136(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 2 except 9=442(LC 1), 11=339(LC 23), 10=309(LC 24), 7=273(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 5-6=-340/273, 6-7=-390/304
BOT CHORD 7-9=-271/340

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-11 to 3-3-11, Interior(1) 3-3-11 to 5-8-9, Exterior(2E) 5-8-9 to 6-5-2, Exterior(2R) 6-5-2 to 9-5-2, Interior(1) 9-5-2 to 17-7-7, Exterior(2E) 17-7-7 to 18-8-5 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 9, 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 9=233, 11=189, 10=164, 7=136.
- N/A
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659367
3000644	PB03	GABLE	2	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:14 2022 Page 1
ID:fGlai9?qNSijAv9NJPfV3izruuC-eMM72xmeShvm50?jRdSRQPJ?f6VFTY_vkODVHrTtF
14-9-2 19-0-0 4-2-14

Scale = 1:33.0




Plate Offsets (X,Y)-- [2:0-3-3,0-1-8], [7:0-3-0,0-1-12], [8:0-3-3,0-1-8]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.31	Vert(LL)	0.00	9	n/r	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.22	Vert(CT)	0.01	9	n/r		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.05	Horz(CT)	0.00	8	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-S					Weight: 69 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS.

All bearings 17-3-11.
(lb) - Max Horz 2=110(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 8 except 2=108(LC 12), 14=119(LC 12), 12=151(LC 9),
10=155(LC 13), 13=104(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 2, 8, 13 except 14=357(LC 19), 12=257(LC 1), 10=321(LC 24)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-11 to 3-3-11, Interior(1) 3-3-11 to 6-0-14, Exterior(2E) 6-0-14 to 7-10-13, Interior(1) 7-10-13 to 14-9-2, Exterior(2R) 14-9-2 to 17-9-2, Interior(1) 17-9-2 to 18-8-5 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4'-0" oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8 except (jt=lb) 2=108, 14=119, 12=151, 10=155, 13=104.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659368
3000644	PB04	GABLE	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:15 2022 Page 1
ID:fGlai9?qNSljAv9NJPFv3izruuC-6ZwVFHnGD?1di9ZvD98h_eyVO3Ta_vL77O7m2jzrTtE




Plate Offsets (X,Y)--		[2:0-3-3,0-1-8], [4:0-3-0,0-1-12], [6:0-3-0,0-1-12], [8:0-3-3,0-1-8]									
LOADING (psf)		SPACING-		CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC	0.21	Vert(LL)	0.01	9	n/r	120	MT20
TCDL	7.0	Lumber DOL	1.25	BC	0.16	Vert(CT)	0.01	9	n/r	120	244/190
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.08	Horz(CT)	0.00	8	n/a	n/a	
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-S							
										Weight: 70 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS.


All bearings 17-3-11.
(lb) - Max Horz 2=-129(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2, 8 except 11=-110(LC 9), 13=-254(LC 12), 10=-250(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 2, 11, 8 except 13=396(LC 19), 10=392(LC 20)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-13=-282/266, 7-10=-277/262

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-11 to 3-3-11, Interior(1) 3-3-11 to 7-1-2, Exterior(2R) 7-1-2 to 11-4-1, Interior(1) 11-4-1 to 11-10-14, Exterior(2R) 11-10-14 to 16-1-12, Interior(1) 16-1-12 to 18-8-5 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4'-0" oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8 except (jt=lb) 11=110, 13=254, 10=250.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Builders FirstSource (Lake City, FL) Lake City, FL - 32055, 8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:16 2022 Page 1
ID:fGlai9?qNSlJAv9NJPfV3izruuC-alUtTdn_uJ9UKJ86nsfwWrVgjTphjMSGM2tJa9zrTtD
9-6-0 19-0-0
9-6-0 9-6-0



LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS	2x4 SP No.3		

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Vase: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-11 to 3-3-11, Interior(1) 3-3-11 to 9-6-0, Exterior(2R) 9-6-0 to 12-6-0, Interior(1) 12-6-0 to 18-8-5 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 4-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 6 except (jt=lb) 11=285, 8=284.
- 10) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.




January 27, 2022

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659370
3000644	PB06	Piggyback	14	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:17 2022 Page 1
ID:fGlaI9?qNSIjAv9NJPFv3izruuC-2x2FgoXlclLyTjJLaA9331ubtBBSq3Qbhct6czTtC



LOADING (psf)	SPACING-	CSL.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.03	Vert(LL)	-0.00	4	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.03	Vert(CT)	-0.00	4	n/r	120		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-P						Weight: 8 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-3-11 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 2=1-7-6, 4=1-7-6
Max Horz 2=26(LC 11)
Max Uplift 2=-45(LC 12), 4=-45(LC 13)
Max Grav 2=89(LC 1), 4=89(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659371
3000644	T01G	Roof Special Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:17 2022 Page 1
ID:fGlai9?qNSljAv9NJPfV3izruuC-2x2FgzoXlclLyTjLLaA9331m7i8USpeQbht6czTtC



4x6 =

Scale = 1:33.3




Plate Offsets (X,Y)-- [2:0-2-10,Edge], [5:0-0-1,0-0-0], [7:0-2-15,Edge]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.57		Vert(LL)	-0.04	9	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.20		Vert(CT)	-0.06	9	n/r	120	MT20HS	187/143
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.09		Horz(CT)	0.00	7	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-S								
										Weight: 73 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


- All bearings 11-6-0.
(lb) - Max Horz 2=-183(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2 except 7=-106(LC 13), 12=-179(LC 12), 10=-192(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 11, 12, 10 except 7=282(LC 1), 2=281(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 4-12=-232/271, 3-4=-217/290, 8-10=-233/272, 6-8=-217/291

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3E) -1-6-0 to 0-9-0, Exterior(2N) 0-9-0 to 5-9-0, Corner(3R) 5-9-0 to 8-9-0, Exterior(2N) 8-9-0 to 13-0-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are MT20 plates unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 7=106, 12=179, 10=192.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659372
3000644	T02	Roof Special	11	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:18 2022 Page 1
ID:fGlai9?qNSijAv9NJPFv3izruuC-X8cduJp9WwQCZdIUuHhObGaxwHrFb9JzqLMQe2zrTtB



4x6 ||

Scale = 1:58.9




Plate Offsets (X,Y)-- [2:0-0-4,Edge], [7:0-0-0,Edge], [10:0-3-8,0-3-0], [12:0-3-8,0-3-0]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.57	Vert(LL)	-0.23 10-12	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.40	Vert(CT)	-0.42 10-12	>648	180	MT20HS	187/143
BCLL 0.0 *	Rep Stress Incr NO	WB 0.45	Horz(CT)	0.02 7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 169 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP M 26
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-8-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 5-12, 5-10

REACTIONS.

(size) 7=0-3-8, 2=0-3-8
Max Horz 2=339(LC 11)
Max Uplift 7=528(LC 13), 2=528(LC 12)
Max Grav 7=1419(LC 20), 2=1420(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-1966/675, 3-5=-2071/1002, 5-6=-2073/1003, 6-7=-1965/675
BOT CHORD 2-12=-571/1682, 10-12=-201/953, 7-10=-428/1524
WEBS 4-12=-396/474, 3-4=-422/480, 5-12=-733/1436, 5-10=-734/1437, 8-10=-396/474, 6-8=-423/481

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 0-0-11, Interior(1) 0-0-11 to 11-6-0, Exterior(2R) 11-6-0 to 14-6-0, Interior(1) 14-6-0 to 24-6-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=528, 2=528.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 2-5=-54, 5-7=-54, 2-12=-20, 10-12=-80(F=-60), 7-10=-20, 1-2=-54, 7-9=-54



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659373
3000644	T02G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:20 2022 Page 1
ID:fGlai9?qNSljAv9NJPFv3izruuC-TWjOJ?qP2XgwpXSt0ijshhJP495f6xSHfrXjwzrTt9



Scale = 1:63.2




Plate Offsets (X,Y)-- [2:0-0-4,Edge], [7:0-0-0,Edge]

LOADING (psf)	SPACING-	CSL.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.44	Vert(LL) 0.04	2-17	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.21	Vert(CT) -0.04	2-17	>999	180	MT20HS	187/143
BCLL 0.0 *	Rep Stress Incr YES	WB 0.31	Horz(CT) 0.01	7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS						
							Weight: 223 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 5-17, 5-12

REACTIONS.


All bearings 11-9-8 except (jt=length) 2=0-3-8, 16=0-3-8.
(lb) - Max Horz 2=339(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 7, 15, 11, 10, 16 except 2=275(LC 12), 12=519(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 15, 13, 11, 10 except 7=252(LC 1), 2=723(LC 19), 12=701(LC 20), 16=287(LC 18)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=693/226, 3-5=806/561
BOT CHORD 2-17=228/697, 16-17=118/347, 15-16=118/347, 13-15=118/347, 12-13=118/347,
11-12=142/287, 10-11=142/287, 7-10=143/288
WEBS 4-17=428/484, 3-4=428/482, 5-17=521/739, 5-12=469/193, 8-12=422/482,
6-8=418/477

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 0-0-10, Interior(1) 0-0-10 to 11-6-0, Exterior(2R) 11-6-0 to 14-6-0, Interior(1) 14-6-0 to 24-6-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are MT20 plates unless otherwise indicated.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 15, 11, 10, 16 except (jt=lb) 2=275, 12=519.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659375
3000644	T04	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:22 2022 Page 1

ID:fGlaig9?qNSIjAv9NJPfV3izruuC-Pvr8jhsfZ9we2EcF77mKm6kcLund7w79kzKenpzrTt7



Scale = 1:53.4

Plate Offsets (X,Y)-- [2:0-0-1,Edge], [2:0-2-10,Edge], [5:0-2-0,0-1-13], [6:0-6-4,0-2-0]

LOADING (psf)	SPACING-		CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.61	Vert(LL)	-0.08 9-10	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.46	Vert(CT)	-0.14 9-10	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.65	Horz(CT)	0.02 9	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS					Weight: 178 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x4 SP No.3 *Except*
 8-9: 2x6 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-10 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 8-4-5 oc bracing.
 WEBS 1 Row at midpt 6-11

REACTIONS.


(size) 9=0-3-0, 2=0-3-8
 Max Horz 2=400(LC 12)
 Max Uplift 9=340(LC 13), 2=334(LC 12)
 Max Grav 9=957(LC 2), 2=1019(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1159/349, 3-5=-878/383, 5-6=-620/355, 6-7=-1073/475, 7-8=-762/291,
 8-9=-815/363
 BOT CHORD 2-13=-471/949, 11-13=-470/942, 10-11=-243/604
 WEBS 3-11=-467/335, 5-11=-144/389, 6-10=-261/533, 7-10=-885/497, 8-10=-375/980

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to -0-0-3, Interior(1) -0-0-3 to 10-2-8, Exterior(2E) 10-2-8 to 15-8-13, Interior(1) 15-8-13 to 22-8-12 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=340, 2=334.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
 Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659376
3000644	T05	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:23 2022 Page 1
ID:fGla19?gNSljAv9NJPfV3izruuC-t5PWx0tHKS2VgOBShqHZIKHrk11sQdlzd3BKFzrTt6



Scale = 1:49.5




Plate Offsets (X,Y)-- [2:0-0-1,Edge], [2:0-2-10,Edge], [5:0-2-4,0-2-0], [7:0-2-4,0-2-0]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.37	Vert(LL)	-0.27 10-11	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.85	Vert(CT)	-0.43 10-11	>630	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.51	Horz(CT)	0.02 10	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 184 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except*
9-10: 2x6 SP No.2


REACTIONS. (size) 10=0-3-0, 2=0-3-8
Max Horz 2=398(LC 12)
Max Uplift 10=-395(LC 9), 2=-310(LC 12)
Max Grav 10=963(LC 2), 2=994(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1171/321, 3-5=-982/403, 5-6=-720/324, 6-7=-905/356, 7-8=-753/292
BOT CHORD 2-14=-448/861, 13-14=-446/854, 11-13=-318/791, 10-11=-208/456
WEBS 3-13=-459/321, 5-13=-185/485, 8-10=-825/395, 7-11=-133/404, 8-11=-183/578,
6-11=-540/330

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to -0-0-3, Interior(1) -0-0-3 to 8-2-8, Exterior(2R) 8-2-8 to 11-2-8, Interior(1) 11-2-8 to 13-8-10, Exterior(2R) 13-8-10 to 16-8-10, Interior(1) 16-8-10 to 22-8-12 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=395, 2=310.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659377
3000644	T06	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:24 2022 Page 1

ID:fGlai9?QNSljAv9NJPfV3izruuC-LHzu8Muw5mAMHYleFYoorXqw8hSUBm2SCHpksizrTt5




Plate Offsets (X,Y)-- [2:0-0-1,Edge], [2:0-2-10,Edge], [3:0-6-4,0-2-0], [6:0-4-4,0-2-0]

LOADING (psf)	SPACING-	CSL	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.72	Vert(LL)	-0.14	8-9	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.56	Vert(CT)	-0.23	8-9	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.94	Horz(CT)	0.02	8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS						Weight: 168 lb	FT = 20%

LUMBER-


TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except*
7-8: 2x6 SP No.2

REACTIONS. (size) 8=0-3-0, 2=0-3-8
Max Horz 2=465(LC 12)
Max Uplift 8=351(LC 12), 2=361(LC 12)
Max Grav 8=952(LC 2), 2=971(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=1107/341, 3-5=981/348, 5-6=779/247, 6-7=570/265, 7-8=786/398
BOT CHORD 2-12=537/821, 11-12=536/815, 9-11=511/983
WEBS 4-12=0/255, 5-9=689/406, 7-9=394/820

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to -0-0-3, Interior(1) -0-0-3 to 6-2-8, Exterior(2R) 6-2-8 to 9-2-8, Interior(1) 9-2-8 to 15-1-7, Exterior(2R) 15-1-7 to 18-1-7, Interior(1) 18-1-7 to 22-8-12 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=351, 2=361.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659378
3000644	T07	Roof Special Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:25 2022 Page 1

ID:fGlai9?qNSlJAv9NJPfV3izruuC-pUXHMiuYs4IDvIKpFJ1NIM945mvKD7bRxYIO8zrTt4



Scale = 1:57.0

Plate Offsets (X,Y)-- [2:0-2-10,Edge], [3:0-6-4,0-2-0], [7:0-6-4,0-2-0], [9:0-4-0,0-4-0], [11:0-4-0,0-4-8]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.51	Vert(LL)	0.11 12-13	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.68	Vert(CT)	-0.14 12-13	>999	180	MT20HS	187/143
BCLL 0.0 *	Rep Stress Incr NO	WB 0.96	Horz(CT)	0.03 9	n/a	n/a		
BCDL 10.0	Code FBC2020/TP12014	Matrix-MS					Weight: 197 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3 *Except*
8-9: 2x6 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-5-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-5 oc bracing.
WEBS 1 Row at midpt 8-9, 6-10, 7-9

REACTIONS.

(size) 9=0-3-0, 2=0-3-8
Max Horz 2=524(LC 26)
Max Uplift 9=555(LC 8), 2=921(LC 8)
Max Grav 9=1073(LC 2), 2=1727(LC 32)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=2214/1188, 3-5=2185/1046, 5-6=1651/702, 6-7=797/320
BOT CHORD 2-13=1386/1943, 12-13=1374/1920, 11-12=1349/2266, 10-11=800/1331, 9-10=335/599
WEBS 4-13=407/846, 3-4=361/752, 3-12=238/670, 5-12=346/305, 5-11=1522/893, 6-11=650/1240, 6-10=1191/753, 7-10=550/1202, 7-9=1085/607

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=555, 2=921.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 248 lb down and 236 lb up at 4-4-4, and 259 lb down and 279 lb up at 5-5-4 on top chord, and 221 lb down and 149 lb up at 4-2-8, and 642 lb down and 358 lb up at 5-5-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 2-3=-54, 3-5=-54, 5-7=-54, 7-8=-54, 2-9=-20, 1-2=-54



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659378
3000644	T07	Roof Special Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,


8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:25 2022 Page 2
ID:fGlai9?qNSIjAv9NJPfV3izruuC-pUXHMiuYs4IDviKqFJ1NIM945mvKD7bRxYIO8zrTt4

LOAD CASE(S) Standard
Concentrated Loads (lb)
Vert: 3=-47(F) 13=-133(F) 14=90(F) 15=-642(F)

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659379
3000644	T08	Half Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:26 2022 Page 1
ID:fGlai9?QNSijAv9NJPFv3izruuC-Ig5fZ2vAdNQ3Xsv1MzqGwyvPVVDV3rYlfbIrxazrTt3



Scale = 1:29.0

Plate Offsets (X,Y)-- [4:0-5-8,0-2-0], [7:0-3-8,0-4-0]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.15	Vert(LL)	0.01	7-8	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.14	Vert(CT)	-0.02	7-8	>999	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.24	Horz(CT)	0.00	6	n/a	n/a		
BCDL 10.0	Code FBC2020/TP12014		Matrix-MS						Weight: 64 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 6=Mechanical
Max Horz 2=246(LC 8)
Max Uplift 2=231(LC 8), 6=436(LC 8)
Max Grav 2=501(LC 1), 6=678(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-596/231, 3-4=-335/155
BOT CHORD 2-8=-338/518, 7-8=-338/518, 6-7=-181/277
WEBS 3-7=-318/204, 4-7=-342/608, 4-6=-659/432

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=231, 6=436.
- 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 90 lb down and 69 lb up at 7-0-0 on top chord, and 439 lb down and 319 lb up at 7-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 4-5=-54, 2-6=-20
Concentrated Loads (lb)
Vert: 7=-426(B) 4=-18(B)



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TP11 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659380
3000644	T09	HIP GIRDER	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,


8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:27 2022 Page 1

ID:fGlai9?qNSijAv9NJPfV3izruuC-mse1nOwoOhYw80UDwgLVTASW2vStoEbuuF1PT0zrTt2

-1-6-0	3-10-4	7-0-0	11-4-0	15-8-0	20-0-0	23-1-12	27-0-0	28-6-0	1-6-0
1-6-0	3-10-4	3-1-12	4-4-0	4-4-0	4-4-0	3-1-12	3-10-4	1-6-0	

Scale = 1:48.9

Bracing



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.42	Vert(LL)	0.10 12-13 >999	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.58	Vert(CT)	-0.13 12-13 >999				
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.51	Horz(CT)	0.02 9 n/a				
BCDL	10.0	Code FBC2020/TP12014		Matrix-MS							
										Weight: 169 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-11-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 5-14

REACTIONS.


(size) 2=0-3-8, 14=0-3-8, 9=0-3-8
Max Horz 2=162(LC 7)
Max Uplift 2=430(LC 27), 14=1718(LC 5), 9=791(LC 9)
Max Grav 2=319(LC 6), 14=2870(LC 1), 9=1307(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=493/873, 3-4=536/973, 4-5=444/827, 5-6=1335/906, 6-7=1712/1171,
7-8=2000/1297, 8-9=2136/1307
BOT CHORD 2-15=771/583, 14-15=771/583, 13-14=480/755, 12-13=947/1564, 11-12=1020/1810,
9-11=1020/1810
WEBS 3-14=244/258, 4-14=683/435, 5-14=2111/1322, 5-13=780/1337, 6-13=501/391,
7-12=395/721, 8-12=319/272

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=430, 14=1718, 9=791.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 91 lb down and 69 lb up at 7-0-0, 91 lb down and 66 lb up at 9-0-12, 91 lb down and 66 lb up at 11-0-12, 91 lb down and 59 lb up at 13-0-12, 91 lb down and 59 lb up at 13-11-4, 91 lb down and 66 lb up at 15-11-4, and 91 lb down and 66 lb up at 17-11-4, and 225 lb down and 213 lb up at 20-0-0 on top chord, and 292 lb down and 206 lb up at 7-0-0, 165 lb down and 113 lb up at 9-0-12, 165 lb down and 113 lb up at 11-0-12, 165 lb down and 113 lb up at 13-0-12, 165 lb down and 113 lb up at 13-11-4, 165 lb down and 113 lb up at 15-11-4, and 165 lb down and 113 lb up at 17-11-4, and 439 lb down and 319 lb up at 19-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659380
3000644	T09	HIP GIRDER	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:27 2022 Page 2
ID:fGlai9?qNSIjAv9NJPfV3izruuC-mse1nOwoOhYw80UDwgLVTASW2vStoEbuuF1PT0zrTt2

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)
Vert: 1-4=-54, 4-7=-54, 7-10=-54, 2-9=-20
- Concentrated Loads (lb)
Vert: 4=-18(B) 7=-92(B) 14=-269(B) 5=-18(B) 6=-18(B) 12=-426(B) 20=-18(B) 21=-18(B) 23=-18(B) 24=-18(B) 25=-156(B) 26=-156(B) 27=-156(B) 28=-156(B) 29=-156(B) 30=-156(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659381
3000644	T10	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:28 2022 Page 1
ID:fGla9?qNSijAv9NJPfV3izruuC-E3CP_kxQ9?gnm93PUNtk?N_iSJlqXfA17vny?TzrTt1



Scale = 1:47.1




Plate Offsets (X,Y)-- [2:0-6-0,0-0-4], [4:0-3-0,0-1-12], [8:0-6-0,0-0-3]

LOADING (psf)	SPACING-	CSL.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.38	Vert(LL) 0.11	12-18	>803	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.79	Vert(CT) -0.26	9-11	>921	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.62	Horz(CT) 0.02	8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 143 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.


(size) 8=0-3-8, 2=0-3-8, 12=0-3-8
Max Horz 2=190(LC 9)
Max Uplift 8=311(LC 13), 2=107(LC 12), 12=478(LC 12)
Max Grav 8=770(LC 20), 2=263(LC 23), 12=1243(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=65/277, 5-6=734/383, 6-7=901/388, 7-8=1101/493
BOT CHORD 9-11=183/550, 8-9=347/940
WEBS 3-12=291/252, 4-12=991/312, 4-11=189/671, 5-11=586/303, 5-9=103/371,
6-9=38/275, 7-9=354/279

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 9-0-0, Exterior(2R) 9-0-0 to 13-6-0, Interior(1) 13-6-0 to 18-0-0, Exterior(2R) 18-0-0 to 22-2-6, Interior(1) 22-2-6 to 27-0-0 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=311, 2=107, 12=478.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659382
3000644	T11	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:29 2022 Page 1

ID:fGlai9?qNSijAv9NJPfv3izruuC-iFmnB4x2wloeOJec25OzYbXtkiBJG8qBLZWVXvzrTt0




LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.34	Vert(LL)	0.13 12-18 >651 240	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.39	Vert(CT)	-0.13 12-18 >684 180				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.46	Horz(CT)	0.02 7 n/a n/a				
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS							
								Weight: 146 lb FT = 20%			

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-2-6 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS. (size) 7=0-3-8, 2=0-3-8, 12=0-3-8
Max Horz 2=228(LC 9)
Max Uplift 7=321(LC 13), 2=152(LC 12), 12=412(LC 12)
Max Grav 7=721(LC 1), 2=351(LC 23), 12=1034(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=472/263, 4-5=336/256, 5-6=705/366, 6-7=1113/485
BOT CHORD 11-12=303/235, 9-11=87/548, 8-9=323/906, 7-8=323/906
WEBS 3-12=938/452, 3-11=198/700, 5-11=381/197, 5-9=153/382, 6-9=508/337

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 11-0-0, Exterior(2R) 11-0-0 to 15-2-15, Interior(1) 15-2-15 to 16-0-0, Exterior(2R) 16-0-0 to 20-2-15, Interior(1) 20-2-15 to 27-0-0 zone; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=321, 2=152, 12=412.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659383
3000644	T12	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:30 2022 Page 1

ID:fGlai9?qNSljAv9NJPFv3izruuC-ARKAPQyghcwV?TDobovC4o4?76Ve?YGKaDG34LzrTt?




Plate Offsets (X,Y)-- [3:0-4-0,0-3-0], [4:0-3-0,0-1-12], [5:0-3-0,0-1-12], [7:0-2-8,Edge]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.49	Vert(LL)	0.16 12-18	>539	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.51	Vert(CT)	0.13 12-18	>648	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.64	Horz(CT)	0.02 7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 144 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-11-5 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-10-6 oc bracing.

REACTIONS.


(size) 7=0-3-8, 2=0-3-8, 12=0-3-8
Max Horz 2=266(LC 9)
Max Uplift 7=328(LC 13), 2=142(LC 12), 12=415(LC 12)
Max Grav 7=735(LC 1), 2=354(LC 1), 12=990(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=-585/354, 4-5=-423/342, 5-6=-586/325, 6-7=-1099/476
BOT CHORD 10-11=-41/423, 8-10=-297/882, 7-8=-297/882
WEBS 3-12=-835/424, 3-11=-71/437, 6-10=-633/419, 6-8=-7/306

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 13-0-0, Exterior(2E) 13-0-0 to 14-0-0, Exterior(2R) 14-0-0 to 18-2-15, Interior(1) 18-2-15 to 27-0-0 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=328, 2=142, 12=415.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 33610

Job 3000644	Truss T13	Truss Type Common	Qty 1	Ply 1	IC CONST. - DALTON RES. Job Reference (optional)	T26659384
----------------	--------------	----------------------	----------	----------	---	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:31 2022 Page 1
ID:fGlai9?qNSIjAv9NJPFv3izruuC-eeuYcmzJSw2Mddo_9WQRd0c91Wrfk?nUpt?ccozrTt_



Scale = 1:52.3




Plate Offsets (X,Y)-- [5:0-2-8,Edge]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.55	Vert(LL)	0.22	9-12	>395	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.53	Vert(CT)	0.19	9-12	>455	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.69	Horz(CT)	0.01	5	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 132 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-7 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.


(size) 1=0-3-8, 5=0-3-8, 9=0-3-8
Max Horz 1=256(LC 9)
Max Uplift 1=-99(LC 9), 5=-312(LC 13), 9=-421(LC 12)
Max Grav 1=245(LC 23), 5=715(LC 1), 9=1075(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-541/327, 3-4=-540/306, 4-5=-1056/446
BOT CHORD 6-8=-272/845, 5-6=-272/845
WEBS 3-8=-129/252, 4-8=-627/422, 4-6=0/294, 2-8=-97/500, 2-9=-890/424

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 13-6-0, Exterior(2R) 13-6-0 to 16-6-0, Interior(1) 16-6-0 to 27-0-0 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 5=312, 9=421.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659385
3000644	T14	Roof Special Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:33 2022 Page 1
ID:fGlai9?gNSljAv9NJPfV3izruuC-a001R?Z_XJ4sxyNHxSviriUuKXACzJnGBUjfgzTsy




Plate Offsets (X,Y)--		[2:0-5-8,Edge], [3:0-2-0,0-1-13], [7:0-6-0,0-2-4], [16:0-2-12,0-2-12]					
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc) l/defl L/d
TCLL	20.0	Plate Grip DOL	1.25	TC	0.59	Vert(LL)	-0.04 11-12 >999 240
TCDL	7.0	Lumber DOL	1.25	BC	0.46	Vert(CT)	-0.09 11-12 >999 180
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.43	Horz(CT)	-0.01 11 n/a n/a
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS			
						PLATES	GRIP
						MT20	244/190
						Weight: 192 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
2-17: 2x6 SP No.2, 6-17: 2x4 SP No.3
WEBS 2x4 SP No.3
WEDGE
Left: 2x4 SP No.3

REACTIONS.

(size) 2=0-3-8, 16=0-3-8, 11=0-3-8
Max Horz 2=380(LC 34)
Max Uplift 2=47(LC 4), 16=1046(LC 8), 11=252(LC 34)
Max Grav 2=264(LC 19), 16=1821(LC 1), 11=692(LC 23)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 4-5=-281/188, 5-6=-254/383, 6-7=-202/380, 7-8=-683/276, 8-9=-535/239,
9-10=-535/243, 10-11=-636/267
BOT CHORD 16-17=-344/542, 12-14=-359/695
WEBS 5-18=-102/294, 5-16=-411/247, 7-16=-1016/448, 7-14=-322/807, 8-14=-353/226,
8-12=-389/255, 10-12=-170/439

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 16=1046, 11=252.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 102 lb down and 104 lb up at 0-11-13 on top chord, and 24 lb down and 30 lb up at 0-11-13, and 658 lb down and 456 lb up at 7-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659385
3000644	T14	Roof Special Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:33 2022 Page 2
ID:fGlai9?qNSljAv9NJPfv3izruuC-a0011R?Z_XJ4sxyNHxSviRiUuKXACzJnGBUjfgzrTsy


LOAD CASE(S) Standard
Uniform Loads (plf)
Vert: 1-3=-54, 3-4=-54, 4-7=-54, 7-8=-54, 8-9=-54, 9-10=-54, 17-20=-20, 11-16=-20
Concentrated Loads (lb)
Vert: 3=22(F) 24=-658(F)

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659386
3000644	T15	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:34 2022 Page 1

ID:fGlaI9?QNSIJAv9NJPFv3izruuC-3DagFn?BlrRxU4WZqe_8FeEdJqSxI5wvREGC7zrTsx



4x6 =

Scale = 1:68.7





Plate Offsets (X,Y)-- [2:0-1-11,0-1-3], [3:0-6-4,0-2-0], [5:0-3-8,0-2-0], [12:0-5-12,0-2-8]

LOADING (psf)	SPACING-		CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.74	Vert(LL)	-0.10 16-18	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.65	Vert(CT)	-0.20 16-18	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.91	Horz(CT)	0.04 10	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS					Weight: 212 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2 *Except*
 7-14: 2x4 SP No.3
 WEBS 2x4 SP No.3
 SLIDER Left 2x6 SP No.2 1-11-8

REACTIONS.


(size) 2=0-3-8, 10=0-3-8
 Max Horz 2=380(LC 12)
 Max Uplift 2=493(LC 12), 10=416(LC 12)
 Max Grav 2=1195(LC 2), 10=1159(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1318/519, 3-4=-1604/660, 4-5=-1465/565, 5-6=-1209/578, 6-7=-1280/541,
 7-8=-873/396, 8-9=-942/394, 9-10=-1061/433
 BOT CHORD 2-19=-646/1053, 18-19=-644/1041, 16-18=-908/1721, 15-16=-519/1198, 7-12=-487/1065,
 11-12=-445/1076
 WEBS 3-18=-453/1234, 4-18=-787/433, 4-16=-549/331, 5-16=-20/420, 6-15=-475/287,
 12-15=-549/1310, 6-12=-414/251, 7-11=-966/496, 8-11=-252/688, 9-11=-321/873

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 2-4-10, Exterior(2E) 2-4-10 to 4-0-9, Interior(1) 4-0-9 to 11-0-0, Exterior(2R) 11-0-0 to 14-0-0, Interior(1) 14-0-0 to 21-4-0, Exterior(2R) 21-4-0 to 24-4-0, Interior(1) 24-4-0 to 27-8-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=493, 10=416.



Philip J. O'Regan PE No.58126
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
 Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659387
3000644	T16	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:36 2022 Page 1

ID:fGlai9?qNSIjAv9NJPFv3izruuC-?bhRfT1RGShfjOgyy30cK3Kz9XYhPEODy9jNG?zrTsv



Scale = 1:68.7




Plate Offsets (X,Y)-- [2:0-1-11,0-1-3], [3:0-6-4,0-2-0], [5:0-5-8,0-2-0], [11:0-6-0,0-2-0]

LOADING (psf)	SPACING-		CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.71	Vert(LL)	-0.07 14-15	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.54	Vert(CT)	-0.16 14-15	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.79	Horz(CT)	0.03 9	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS					Weight: 208 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
6-13: 2x4 SP No.3
WEBS 2x4 SP No.3
SLIDER Left 2x6 SP No.2 1-11-8

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-2-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-6-10 oc bracing. Except:
10-0-0 oc bracing: 11-13
WEBS 1 Row at midpt 5-11

REACTIONS.


(size) 2=0-3-8, 9=0-3-8
Max Horz 2=380(LC 12)
Max Uplift 2=493(LC 12), 9=416(LC 12)
Max Grav 2=1118(LC 1), 9=1049(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1267/542, 3-4=-1360/643, 4-5=-1207/529, 5-6=-953/484, 6-7=-781/398,
7-8=-864/394, 8-9=-991/432
BOT CHORD 2-17=-632/908, 15-17=-631/904, 14-15=-820/1386, 6-11=-122/262, 10-11=-439/948
WEBS 3-15=-347/903, 4-15=-631/337, 4-14=-479/355, 5-14=-40/327, 11-14=-486/892,
6-10=-843/490, 7-10=-252/554, 8-10=-320/776

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 3-9-6, Exterior(2E) 3-9-6 to 6-0-9, Interior(1) 6-0-9 to 13-0-0, Exterior(2R) 13-0-0 to 16-0-0, Interior(1) 16-0-0 to 21-4-0, Exterior(2R) 21-4-0 to 24-4-0, Interior(1) 24-4-0 to 27-8-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=493, 9=416.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659388
3000644	T17	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:37 2022 Page 1

ID:fGlai9?gNSljAv9NJPFv3izruuC-ToFtp231mpWLYF8WmXstHs9AxvM8niMBpSxoRzrTsu




Plate Offsets (X,Y)-- [2:0-1-11,0-1-3], [3:0-6-4,0-2-0], [5:0-5-8,0-2-0], [7:0-5-8,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.70	Vert(LL)	-0.08 14-16	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.51	Vert(CT)	-0.17 14-16	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.34	Horz(CT)	0.03 9	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 216 lb	FT = 20%


LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
6-13: 2x4 SP No.3
WEBS 2x4 SP No.3
SLIDER Left 2x6 SP No.2 1-11-8

REACTIONS. (size) 2=0-3-8, 9=0-3-8
Max Horz 2=378(LC 12)
Max Uplift 2=447(LC 12), 9=326(LC 12)
Max Grav 2=1115(LC 1), 9=1043(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1276/481, 3-4=-1245/541, 4-5=-1052/443, 5-6=-777/422, 6-7=-776/422,
7-8=-856/364, 8-9=-986/418
BOT CHORD 2-17=-682/900, 16-17=-552/900, 14-16=-649/1260, 10-11=-229/662
WEBS 3-16=-221/699, 4-16=-477/231, 4-14=-526/386, 5-14=-109/339, 11-14=-319/792,
7-11=-269/498, 7-10=-285/180, 8-10=-263/773

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 5-2-3, Exterior(2E) 5-2-3 to 8-0-9, Interior(1) 8-0-9 to 15-0-0, Exterior(2R) 15-0-0 to 18-0-0, Interior(1) 18-0-0 to 21-6-9, Exterior(2R) 21-6-9 to 24-6-9, Interior(1) 24-6-9 to 27-8-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=447, 9=326.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659389
3000644	T18	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:38 2022 Page 1

ID:fGlai9?qNSlJAv9NJPfV3izruuC-x_pB492io3xMziqK3U25PUPKOLCKtDqWQTCULuzrTst




Plate Offsets (X,Y)-- [2:0-1-11,0-0-15], [3:0-6-4,0-2-0], [5:0-5-8,0-2-0], [11:0-2-12,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.67	Vert(LL)	-0.11 14-15	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.59	Vert(CT)	-0.20 14-15	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.41	Horz(CT)	0.03 9	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 219 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2 *Except*
 6-13: 2x4 SP No.3
 WEBS 2x4 SP No.3
 SLIDER Left 2x6 SP No.2 1-11-8

REACTIONS.


(size) 2=0-3-8, 9=0-3-8
 Max Horz 2=403(LC 12)
 Max Uplift 2=456(LC 12), 9=360(LC 12)
 Max Grav 2=1230(LC 19), 9=1151(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1404/487, 3-4=-1280/526, 4-5=-978/413, 5-6=-765/415, 6-7=-942/430,
 7-8=-673/257, 8-9=-1114/408
 BOT CHORD 2-17=-958/1093, 15-17=-551/1098, 14-15=-598/1340, 6-11=-173/378, 10-11=-191/561
 WEBS 3-15=-142/565, 4-15=-329/171, 4-14=-698/416, 5-14=-114/315, 11-14=-281/956,
 7-11=-132/350, 7-10=-573/283, 8-10=-315/926

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 6-7-0, Exterior(2R) 6-7-0 to 9-7-0, Interior(1) 9-7-0 to 17-0-0, Exterior(2E) 17-0-0 to 19-6-9, Exterior(2R) 19-6-9 to 22-6-9, Interior(1) 22-6-9 to 27-8-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=456, 9=360.



Philip J. O'Regan PE No.58126
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component


Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
 Tampa, FL 36610

 **WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


 6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659391
3000644	T20	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,


8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:41 2022 Page 1

ID:fGlai9?gNSljAv9NJPFv3izruuC-MZVKJA5a5_Jxq9Zvlcco171xOYCv3ZRY6QQ8xDzrTsq



7.00 12 4x8 = 4x4 =

Scale = 1:70.7




Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659392
3000644	T21	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:42 2022 Page 1

ID:fGlai9?qNSIjAv9NJPfV3izruuC-ql3iwW6CsRoRJ85IK71aKa4nyb7o1s5L4AhUfzrTsp



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.38	Vert(LL)	-0.08 16-18 >999 240	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.53	Vert(CT)	-0.13 16-18 >999 180				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.41	Horz(CT)	0.03 11 n/a n/a				
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS							
								Weight: 238 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2 *Except*
 8-15: 2x4 SP No.3
 WEBS 2x4 SP No.3
 SLIDER Left 2x4 SP No.3 1-11-8

REACTIONS.


(size) 2=0-3-8, 11=0-3-8
 Max Horz 2=391(LC 12)
 Max Uplift 2=393(LC 12), 11=328(LC 13)
 Max Grav 2=1193(LC 2), 11=1143(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-4=1380/466, 4-5=1133/487, 5-6=817/447, 6-7=881/481, 7-8=754/419,
 8-9=924/426, 9-10=667/258, 10-11=1103/409
 BOT CHORD 2-19=527/1100, 18-19=527/1101, 16-18=270/828, 8-13=85/303, 12-13=191/553
 WEBS 4-18=400/336, 5-18=120/438, 6-16=491/307, 7-16=198/426, 13-16=246/865,
 9-13=166/346, 9-12=569/282, 10-12=315/912

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 10-9-6, Exterior(2R) 10-9-6 to 13-9-6, Interior(1) 13-9-6 to 16-7-7, Exterior(2R) 16-7-7 to 19-7-7, Interior(1) 19-7-7 to 19-11-2, Exterior(2R) 19-11-2 to 22-11-2, Interior(1) 22-11-2 to 27-8-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=393, 11=328.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date: January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
 Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659393
3000644	T22	Monopitch Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:43 2022 Page 1
ID:fGlai9?gNSljAv9NJPFv3izruuC-lxc47s6qdcZf3Tils1eG6Y6JaMzMXW1FZkvF05zrTso



Scale = 1:28.3

Plate Offsets (X,Y)-- [1:0-3-4,0-1-8]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.19	Vert(LL)	-0.02	5-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.41	Vert(CT)	-0.03	5-7	>999	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.29	Horz(CT)	0.01	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						Weight: 44 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.

(size) 1=0-3-8, 4=0-3-8
Max Horz 1=212(LC 8)
Max Uplift 1=344(LC 8), 4=673(LC 8)
Max Grav 1=905(LC 1), 4=626(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 1-2=-874/368
BOT CHORD 1-5=-460/743, 4-5=-460/743
WEBS 2-5=-377/698, 2-4=-892/546

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=344, 4=673.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 372 lb down and 134 lb up at 0-7-4, 318 lb down and 153 lb up at 2-7-4, and 286 lb down and 209 lb up at 4-7-4, and 286 lb down and 560 lb up at 6-7-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 1-4=-20
Concentrated Loads (lb)
Vert: 7=-372(F) 8=-318(F) 9=-286(F) 10=-27(F)



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659394
3000644	T23	Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:44 2022 Page 1

ID:fGlai9?QNSljAv9NJPfV3izruuC-m8ASLC7SOvhWdhUQI9VfifMAIK4GwqOoOfOYXzrTsn



Scale = 1:44.5




Plate Offsets (X,Y)-- [4:0-5-8,0-2-0], [5:0-3-8,0-2-0]

LOADING (psf)	SPACING-		CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.65	Vert(LL)	0.19 12-13	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.37	Vert(CT)	-0.21 12-13	>999	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.51	Horz(CT)	0.05 7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS					Weight: 154 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP M 26
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-11-1 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-7-1 oc bracing.

REACTIONS.

(size) 2=0-3-8, 7=0-3-8
Max Horz 2=-219(LC 25)
Max Uplift 2=-1332(LC 8), 7=-1334(LC 9)
Max Grav 2=1988(LC 1), 7=1990(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-3529/2425, 3-4=-2798/2026, 4-5=-2393/1832, 5-6=-2811/2035, 6-7=-3529/2425
BOT CHORD 2-13=-2107/3027, 12-13=-2107/3027, 10-12=-1637/2399, 9-10=-1960/2994,
7-9=-1960/2994
WEBS 3-13=-311/522, 3-12=-781/583, 4-12=-796/1098, 5-10=-796/1094, 6-10=-768/575,
6-9=-303/509

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=1332, 7=1334.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 31 lb down and 39 lb up at 9-0-12, 114 lb down and 103 lb up at 11-0-12, 114 lb down and 92 lb up at 12-2-0, and 114 lb down and 103 lb up at 13-3-4, and 31 lb down and 39 lb up at 15-3-4 on top chord, and 545 lb down and 440 lb up at 7-0-12, 196 lb down and 216 lb up at 9-0-12, 161 lb down and 137 lb up at 11-0-12, 161 lb down and 137 lb up at 12-2-0, 161 lb down and 137 lb up at 13-3-4, and 196 lb down and 216 lb up at 15-3-4, and 545 lb down and 440 lb up at 17-3-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659394
3000644	T23	Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,


8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:44 2022 Page 2
ID:fGlai9?qNSIjAv9NJPfV3izruuC-m8ASLC7SOvhWhdHUQI9VfifMAIK4GwqOoOfoYXzrTsn

LOAD CASE(S) Standard
Uniform Loads (plf)
Vert: 1-4=-54, 4-5=-54, 5-8=-54, 2-7=-20
Concentrated Loads (lb)
Vert: 11=-144(F) 18=-12(F) 19=-33(F) 20=-33(F) 21=-33(F) 22=-12(F) 23=-545(F) 24=-185(F) 25=-144(F) 26=-144(F) 27=-185(F) 28=-545(F)

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659395
3000644	T24	Common	2	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:45 2022 Page 1
ID:fGlai9?qNSijAv9NJPFv3izruuC-EKkrYY859DpNJnsg_SgkBzBbj9Zq?OzY12OM4_zrTsm



Scale = 1:48.9




Plate Offsets (X,Y)-- [6:0-2-8,Edge]

LOADING (psf)	SPACING-	CSL.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.40	Vert(LL)	-0.15	8-10	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.73	Vert(CT)	-0.22	8-10	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.39	Horz(CT)	0.04	6	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS						Weight: 119 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.


(size) 2=0-3-8, 6=0-3-8
Max Horz 2=259(LC 11)
Max Uplift 2=406(LC 12), 6=406(LC 13)
Max Grav 2=1135(LC 19), 6=1135(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1580/529, 3-4=-1478/567, 4-5=-1478/567, 5-6=-1579/529
BOT CHORD 2-10=-494/1498, 8-10=-189/954, 6-8=-335/1303
WEBS 4-8=-298/755, 5-8=-376/341, 4-10=-298/756, 3-10=-376/341

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 12-2-0, Exterior(2R) 12-2-0 to 15-2-0, Interior(1) 15-2-0 to 25-10-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=406, 6=406.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659396
3000644	T25	Common	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:46 2022 Page 1
ID:fGlai9?qNSijAv9NJPfV3izruuC-iWIDmu9jwXxEwwRtIX9BzkAkIDZvnkrzhGi8vdQzrTsl




Plate Offsets (X,Y)-- [6:0-2-8,Edge]		8-2-6		16-1-10		24-4-0	
		8-2-6		7-11-4		8-2-6	
LOADING (psf)	SPACING-	2-0-0		CSI.	DEFL.	in (loc) l/defl L/d	
TCLL 20.0	Plate Grip DOL	1.25		TC 0.42	Vert(LL)	-0.15 7-9 >999	240
TCDL 7.0	Lumber DOL	1.25		BC 0.74	Vert(CT)	-0.22 7-12 >999	180
BCLL 0.0 *	Rep Stress Incr	YES		WB 0.40	Horz(CT)	0.04 6 n/a	n/a
BCDL 10.0	Code	FBC2020/TPI2014		Matrix-MS			
						PLATES	GRIP
						MT20	244/190
						Weight: 116 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.


(size) 6=0-3-8, 2=0-3-8
Max Horz 2=249(LC 11)
Max Uplift 6=-352(LC 13), 2=-407(LC 12)
Max Grav 6=1054(LC 20), 2=1136(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1582/531, 3-4=-1480/569, 4-5=-1491/579, 5-6=-1593/541
BOT CHORD 2-9=-514/1485, 7-9=-209/942, 6-7=-379/1325
WEBS 4-7=-310/769, 5-7=-383/347, 4-9=-298/755, 3-9=-376/341

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 12-2-0, Exterior(2R) 12-2-0 to 15-2-0, Interior(1) 15-2-0 to 24-4-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=352, 2=407.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659398
3000644	T27	Roof Special Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:49 2022 Page 1

ID:fGlaI9?QNSIjAv9NJPFv3izruuC-75_LOvBbDSKpnOASDIlgMpm8hmuAx4G7ygMZEIzrTsi

1-6-0 2-3-8 7-1-0 12-2-0 14-9-11 19-6-0 24-2-4 29-1-5 33-10-10 38-9-11 43-2-10 48-4-0 49-10-0
1-6-0 2-3-8 4-9-8 5-1-0 2-7-11 4-8-4 4-8-4 4-11-1 4-9-5 4-11-1 4-4-15 5-1-6 1-6-0

Scale = 1:89.3




Plate Offsets (X,Y)-- [3:0-0-1,0-2-0], [6:0-4-12,Edge], [9:0-3-0,Edge], [12:0-6-0,0-2-4], [22:0-3-8,0-4-8]

LOADING (psf)	SPACING-		CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.92	Vert(LL)	0.33	3-30	>878	240	MT20
TCDL 7.0	Lumber DOL	1.25	BC 0.96	Vert(CT)	-0.43	3-30	>670	180	
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.94	Horz(CT)	0.23	22	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						
								Weight: 338 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2 *Except*
1-5: 2x4 SP M 31
BOT CHORD 2x6 SP No.2 *Except*
2-31,3-28,6-26: 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-7-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 4-7-1 oc bracing. Except:
10-0-0 oc bracing: 26-28
WEBS 1 Row at midpt 10-22, 10-19, 6-25

REACTIONS.


(size) 2=0-3-8, 22=(0-3-8 + bearing block) (req. 0-4-11), 14=0-3-8
Max Horz 2=260(LC 26)
Max Uplift 2=267(LC 27), 22=2219(LC 9), 14=1178(LC 9)
Max Grav 2=486(LC 15), 22=3954(LC 1), 14=1405(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-34=-411/317, 3-4=-601/430, 4-5=-281/402, 5-6=-231/388, 6-7=-686/1497,
7-8=-686/1496, 8-10=-1058/2457, 10-11=-1492/1943, 11-12=-1492/1943,
12-13=-1735/1968, 13-14=-2393/2182
BOT CHORD 3-30=-306/615, 29-30=-307/616, 28-29=-728/598, 22-25=-2383/1238, 20-22=-1792/1420,
19-20=-1792/1420, 17-19=-1627/1534, 16-17=-1806/2015, 14-16=-1806/2015
WEBS 4-30=-34/276, 4-29=-706/440, 5-29=-507/301, 6-29=-522/1029, 25-28=-682/541,
8-25=-576/1606, 8-22=-1593/728, 10-22=-2775/1877, 10-20=-160/350, 10-19=-1087/1787,
11-19=-474/496, 12-19=-831/398, 12-17=-819/1039, 13-17=-712/557, 13-16=-305/465,
6-25=-1087/426

NOTES-

- 1) 2x6 SP No.2 bearing block 12" long at jt. 22 attached to front face with 3 rows of 10d (0.131"x3") nails spaced 3" o.c. 12 Total fasteners. Bearing is assumed to be SP No.2.
- 2) Unbalanced roof live loads have been considered for this design.
- 3) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 4) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=267, 22=2219, 14=1178.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659398
3000644	T27	Roof Special Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),
Lake City, FL - 32055,
8.430 s Aug 16 2021 MiTek Industries, Inc.
Wed Jan 26 13:04:50 2022
Page 2
ID:fGlai9?qNSIjAv9NJPFv3izruuC-blXkbFCDzISgPYIem?Gvu0vJQAEPgXWHAK67mBzrTsh

- NOTES-**
- 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 159 lb down and 148 lb up at 25-3-4, 159 lb down and 148 lb up at 27-3-4, 159 lb down and 148 lb up at 29-3-4, 159 lb down and 148 lb up at 31-3-4, 159 lb down and 148 lb up at 33-3-4, and 159 lb down and 148 lb up at 35-3-4, and 159 lb down and 148 lb up at 37-3-4 on top chord, and 94 lb down and 87 lb up at 25-3-4, 94 lb down and 87 lb up at 27-3-4, 94 lb down and 87 lb up at 29-3-4, 94 lb down and 87 lb up at 31-3-4, 94 lb down and 87 lb up at 33-3-4, 94 lb down and 87 lb up at 35-3-4, 94 lb down and 87 lb up at 37-3-4, and 236 lb down and 247 lb up at 39-3-4, and 517 lb down and 490 lb up at 41-3-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25


Uniform Loads (plf)

Vert: 1-3=-54, 3-5=-54, 5-6=-54, 6-12=-54, 12-15=-54, 31-33=-20, 3-28=-20, 26-27=-20, 14-26=-20

Concentrated Loads (lb)

Vert: 20=-84(F) 10=-77(F) 18=-84(F) 38=-77(F) 39=-77(F) 40=-77(F) 41=-77(F) 42=-77(F) 43=-77(F) 44=-84(F) 45=-84(F) 46=-84(F) 47=-84(F) 48=-84(F) 49=-212(F) 50=-517(F)

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:51 2022 Page 1
ID:fGlai9?nSljAv9NJPFv3izruuC-3U56pbDsk3aW1kQKjn8RERTJacgPOZQP_rglzdTsg
49-10-0
1-6-0 2-3-8 7-1-0 12-4-9 13-0-0 18-7-2 24-2-4 30-0-14 35-11-7 40-3-7 47-1-11 48-3-8
1-6-0 2-3-8 4-9-8 5-3-9 0-7-7 5-7-2 5-7-2 5-10-9 5-10-9 4-4-0 6-10-5 1-1-13
1-6-8
Scale = 1:88.4



REACTIONS. (size) 2=0-3-8, 23=(0-3-8 + bearing block) (req. 0-3-14), 16=0-3-0
 Max Horz 2=339(LC 11)
 Max Uplift 2=-149(LC 12), 23=-1224(LC 9), 16=-341(LC 8)
 Max Grav 2=430(LC 20), 23=3283(LC 2), 16=606(LC 24)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 3-31=-426/215, 3-4=-392/203, 4-5=-401/324, 5-6=-139/548, 6-7=-136/549,
7-9=-800/2303, 9-10=-800/2303, 10-11=-237/592, 11-12=-267/702, 12-13=-380/498,
14-16=-258/155

BOT CHORD 3-28=-139/296, 27-28=-389/284, 6-27=-276/203, 23-25=-1177/586, 20-23=-1198/638,
19-20=-1198/638, 17-19=-355/382

WEBS 4-28=-459/382, 5-28=-507/1026, 5-27=-783/391, 25-27=-1153/582, 7-27=-418/1096,
7-25=-70/444, 7-23=-1759/684, 9-23=-310/238, 10-23=-1803/682, 10-20=-0/332,
10-19=-448/1125, 11-19=-438/249, 12-19=-464/248, 12-17=-115/424, 13-17=-429/345,
13-16=-484/288

NOTES-

- 1) 2x4 SP No.2 bearing block 12" long at jt. 23 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SP No.2.
- 2) Unbalanced roof live loads have been considered for this design.
- 3) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCFL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 12-4-9, Exterior(2R) 12-4-9 to 17-2-8, Interior(1) 17-2-8 to 35-11-7, Exterior(2E) 35-11-7 to 40-3-7, Interior(1) 40-3-7 to 47-1-11, Exterior(2E) 47-1-11 to 49-10-0 zone; end vertical right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 4) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=149, 23=1224, 16=341.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022



WARNING – Verify design parameters and READ NOTES ON THIS AND INCLUDED W/ITER KEY INFORMATION FOR IM-17473 REV. 3/15/2020 BEFORE USE.
Design valid for use only with MiteK® connectors. This design is based only upon parameters shown, and is for individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1-1 Quality Criteria, DSB-89 and BCS Building Component Safety Information** available from Truss Plate Institute, 26750 Grain Highway, Suite 203 Waldorf, MD 20681



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659400
3000644	T29	Roof Special	1	1	Job Reference (optional)	


Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:53 2022 Page 1

ID:fGlai9?QNSijAv9NJPFv3izruuC-?tDsEHE6GgqEG?TDS7pcWfXrxOGXtTjtKKnNWzrTse

1-6-0	2-3-8	7-1-0	13-0-0	15-2-14	21-2-5	27-1-11	33-1-2	37-5-2	44-3-7	48-3-8	49-10-0
1-6-0	2-3-8	4-9-8	5-11-0	2-2-14	5-11-7	5-11-7	5-11-7	4-4-0	6-10-5	4-0-1	1-6-8

Scale = 1:88.4



Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659401
3000644	T30	Roof Special	1	1	Job Reference (optional)	


Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:55 2022 Page 1

ID:fGlai9?qNSijAv9NJPFv3izruuC-xFLdfzGMol4yVJdbZYs4b4cEPB2ZLnZ0KcptRPzrTsc

1-6-0 2-3-8 7-1-0 13-0-0 18-1-2 24-2-4 30-2-14 34-6-13 41-5-2 48-3-8 49-10-0
1-6-0 2-3-8 4-9-8 5-11-0 5-1-2 6-1-2 6-0-10 4-4-0 6-10-5 6-10-6 1-6-8

Scale = 1:89.2



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.65	Vert(LL)	0.22 3-25 >999 240	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.51	Vert(CT)	-0.30 3-25 >964 180				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.96	Horz(CT)	0.14 20 n/a n/a				
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS							
								Weight: 371 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2 *Except*
6-8: 2x6 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
3-26: 2x6 SP No.2, 5-23: 2x4 SP No.3
WEBS 2x4 SP No.3 *Except*
6-20,8-20: 2x4 SP No.2, 11-13: 2x6 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 5-6-9 oc bracing.
WEBS 1 Row at midpt 7-20, 9-17, 10-14
2 Rows at 1/3 pts 6-20, 8-20

REACTIONS.


(size) 2=0-3-8, 20=(0-3-8 + bearing block) (req. 0-4-4), 13=0-3-0
Max Horz 2=446(LC 11)
Max Uplift 2=129(LC 8), 20=1247(LC 12), 13=437(LC 8)
Max Grav 2=411(LC 20), 20=3593(LC 19), 13=633(LC 24)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-28=-474/337, 3-4=-368/331, 4-5=-415/961, 5-6=-305/898, 6-7=-637/2040,
7-8=-637/2039, 8-9=-472/1391, 9-10=-252/430, 10-11=-393/450, 11-13=-572/455
BOT CHORD 5-24=-353/344, 20-22=-937/561, 17-20=-1048/676, 16-17=-767/578, 14-16=-762/579
WEBS 4-25=-3/301, 4-24=-753/388, 22-24=-927/569, 6-24=-425/763, 6-22=-73/416,
6-20=-1967/777, 7-20=-384/317, 8-20=-1753/640, 8-17=-315/827, 9-17=-707/398,
9-16=0/312, 9-14=-423/962, 10-14=-358/232, 11-14=-326/320

NOTES-

- 1) 2x4 SP No.2 bearing block 12" long at jt. 20 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SP No.2.
- 2) Unbalanced roof live loads have been considered for this design.
- 3) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 22-11-2, Interior(1) 22-11-2 to 30-2-14, Exterior(2E) 30-2-14 to 34-6-13, Interior(1) 34-6-13 to 41-5-2, Exterior(2R) 41-5-2 to 46-3-1, Interior(1) 46-3-1 to 49-10-0 zone; end vertical right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 4) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb)
2=129, 20=1247, 13=437.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659402
3000644	T31	Piggyback Base	1	1	Job Reference (optional)	


Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:57 2022 Page 1

ID:fGlai9?qNSiJAv9NJPFv3izruuC-ueTN4eHcKvKgldn_hzuYhVhXg?i_ph7Jnwl_WHzrTsa

1-6-0	2-3-8	7-1-0	12-6-0	18-1-2	19-3-8	22-5-12	30-2-14	31-8-9	38-6-14	42-6-0	48-3-8	49-10-0
1-6-0	2-3-8	4-9-8	5-5-0	5-7-2	1-2-6	3-2-4	7-9-1	1-5-11	6-10-5	3-11-2	5-9-8	1-6-8

Scale = 1:99.0



2-3-8	7-1-0	12-6-0	13-0-0	16-0-0	19-3-8	22-5-12	30-2-14	31-8-9	38-6-14	42-6-0	48-3-8
2-3-8	4-9-8	5-5-0	0-6-0	3-0-0	3-3-8	3-2-4	7-9-1	1-5-11	6-10-5	3-11-2	5-9-8

Plate Offsets (X,Y)-- [3:0-0-5,0-2-0], [4:0-3-0,0-3-0], [6:0-3-0,0-1-12], [9:0-4-8,0-2-0], [11:0-6-0,0-2-4]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.85	Vert(LL) 0.21	3-27	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.64	Vert(CT) -0.30	3-27	>898	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.95	Horz(CT) 0.14	22	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 405 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2 *Except*
 3-28: 2x6 SP No.2, 7-23,29-30: 2x4 SP No.3
 WEBS 2x4 SP No.3 *Except*
 9-22: 2x4 SP No.2, 13-15: 2x6 SP No.2

REACTIONS. (size) 2=0-3-8, 22=(0-3-8 + bearing block) (req. 0-4-0), 15=0-3-0
 Max Horz 2=447(LC 11)
 Max Uplift 2=-132(LC 8), 22=-1180(LC 12), 15=-428(LC 8)
 Max Grav 2=400(LC 20), 22=3395(LC 19), 15=773(LC 24)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-34=-473/340, 3-4=-355/354, 4-5=-421/918, 5-6=-310/865, 6-7=-416/1426,
 7-8=-417/1430, 8-9=-534/1784, 9-10=-292/933, 10-11=-225/699, 11-12=-427/523,
 12-13=-494/413, 13-15=-718/444
 BOT CHORD 24-25=-1091/629, 20-22=-678/547, 19-20=-597/516, 17-19=-210/325, 16-17=-162/358
 WEBS 4-27=-16/258, 4-25=-660/359, 5-25=-352/347, 6-25=-549/1071, 6-24=-1533/720,
 22-24=-1594/888, 8-24=-389/1176, 8-22=-1246/623, 9-22=-1667/624, 9-20=-411/897,
 10-20=-633/443, 11-19=-912/356, 11-17=-154/480, 12-17=-263/211, 13-16=-262/421,
 10-19=-270/853

NOTES-


- 2x4 SP No.2 bearing block 12" long at jt. 22 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SP No.2.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 22-11-2, Interior(1) 22-11-2 to 30-2-14, Exterior(2E) 30-2-14 to 31-8-9, Interior(1) 31-8-9 to 38-6-14, Exterior(2R) 38-6-14 to 43-4-13, Interior(1) 43-4-13 to 49-10-0 zone; end vertical right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- All plates are 3x6 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb)

2=132, 22=1180, 15=428.

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



Philip J. O'Regan PE No.58126
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

January 27,2022



6904 Parke East Blvd.
 Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659402
3000644	T31	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,


8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:04:57 2022 Page 2
ID:fGlai9?qNSIjAv9NJPfV3izruuC-ueTN4eHcKvKgldn_hzuYhVhXg?i_ph7Jnwl_WHzrTsa

NOTES-
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


Job 3000644	Truss T32	Truss Type PIGGYBACK BASE	Qty 1	Ply 1	IC CONST. - DALTON RES.	T26659403
----------------	--------------	------------------------------	----------	----------	-------------------------	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jan 27 14:13:34 2022 Page 1
ID:fGlaI9?qNSIjAv9NJPfV3izruuC-GCRQz6wDsd4Yz8XLr2radXpV3aEmHX13VwjoPtzrJBV



Scale = 1:93.9



	8-1-0	16-0-0	19-3-8	22-5-12	29-10-5	37-1-2	42-6-0	48-3-8
	8-1-0	7-11-0	3-3-8	3-2-4	7-4-9	7-2-13	5-4-14	5-9-8

Plate Offsets (X,Y)-- [7:0-3-0,0-1-12], [12:0-4-0,0-2-4], [21:0-3-8,0-3-0]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.66	Vert(LL)	-0.16	25-26	>999	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.70	Vert(CT)	-0.26	25-26	>999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.93	Horz(CT)	-0.04	16	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS						
							Weight: 383 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
6-25,8-22: 2x4 SP No.3
WEBS 2x4 SP No.3 *Except*
11-21,12-20: 2x4 SP No.2, 14-16: 2x6 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-3-3 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 7-12.
BOT CHORD Rigid ceiling directly applied or 5-3-12 oc bracing. Except:
1 Row at midpt 6-24, 8-23
WEBS 1 Row at midpt 7-23, 9-21, 11-21, 12-20, 13-18

REACTIONS.


(lb/size) 2=738/0-3-8, 21=2106/0-3-8, 16=890/0-3-0
Max Horz 2=447(LC 11)
Max Uplift 2=370(LC 12), 21=-846(LC 9), 16=-498(LC 13)
Max Grav 2=823(LC 19), 21=2375(LC 2), 16=1107(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-30=-1132/435, 3-30=-1080/448, 3-4=-1023/458, 4-5=-925/476, 5-6=-432/393, 6-7=-401/455, 7-8=-217/350, 8-9=-219/353, 9-31=-220/546, 10-31=-220/546, 10-32=-220/546, 11-32=-220/546, 11-33=-425/517, 12-33=-425/517, 12-13=-752/485, 13-34=-685/376, 34-35=-728/366, 14-35=-796/364, 14-16=-1017/511
BOT CHORD 2-26=-510/1055, 26-36=-275/614, 36-37=-275/614, 25-37=-275/614, 24-25=-288/667, 22-23=-1051/402, 21-22=-422/226, 21-38=-196/404, 20-38=-196/404, 19-20=-178/559, 18-19=-178/559, 18-39=-256/582, 17-39=-256/582
WEBS 3-26=-326/289, 5-26=-232/693, 5-25=-662/386, 7-24=-498/966, 7-23=-933/362, 9-22=-391/1067, 9-21=-1132/643, 11-21=-1194/408, 11-20=-33/679, 12-20=-403/100, 12-18=-75/416, 13-17=-263/194, 14-17=-261/704

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 24-11-2, Interior(1) 24-11-2 to 37-1-2, Exterior(2R) 37-1-2 to 43-11-2, Interior(1) 43-11-2 to 49-10-0 zone; end vertical right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- All plates are 3x6 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 370 lb uplift at joint 2, 846 lb uplift at joint 21 and 498 lb uplift at joint 16.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659405
3000644	T33D	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:01 2022 Page 1

ID:fGlaI9?qNSijAv9NJPFv3izruuC-mPiuv0K7O8q6DE5lwpzUrLsKHc1vIVsuiYGCf2zrTsW

1-6-0	6-2-0	11-0-0	16-3-8	18-1-2	24-6-0	30-9-2	37-1-2	42-6-0	48-3-8	49-10-0
1-6-0	6-2-0	4-10-0	5-3-8	1-9-10	6-4-14	6-3-2	6-4-0	5-4-14	5-9-8	1-6-8

Scale = 1:86.3




Plate Offsets (X,Y)-- [3:0-3-0,0-3-0], [6:0-6-0,0-2-4], [10:0-3-0,0-1-12]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.43	Vert(LL) 0.22	23-25	>872	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.70	Vert(CT) -0.24	23-25	>795	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.90	Horz(CT) 0.04	13	n/a	n/a		
BCDL 10.0	Code FBC2020/TP12014	Matrix-MS					Weight: 372 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2 *Except*
 WEBS 2x4 SP No.3 *Except*
 OTHERS 2x6 SP No.2

REACTIONS.


(size) 2=0-3-8, 13=0-3-0, 23=0-3-8
 Max Horz 2=440(LC 11)
 Max Uplift 2=-297(LC 12), 13=-498(LC 13), 23=-930(LC 9)
 Max Grav 2=696(LC 25), 13=1329(LC 26), 23=2066(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-829/923, 3-4=-717/948, 4-5=-324/373, 5-6=-457/425, 6-7=-999/572, 7-9=-999/572, 9-10=-1288/637, 10-11=-1408/625, 11-12=-1015/390, 12-13=-1248/515
 BOT CHORD 2-25=-723/697, 23-25=-369/332, 22-23=-1506/612, 5-22=-1489/602, 19-21=-128/301, 18-19=-426/1288, 17-18=-369/1160, 10-17=-67/365
 WEBS 3-25=-315/289, 4-25=-668/613, 4-23=-562/562, 5-21=-444/1171, 6-21=-924/467, 6-19=-418/1181, 7-19=-365/284, 9-19=-498/259, 10-18=-202/284, 14-17=-357/895, 11-17=-230/476, 11-14=-781/400, 12-14=-351/998

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 24-11-2, Interior(1) 24-11-2 to 37-1-2, Exterior(2R) 37-1-2 to 43-11-2, Interior(1) 43-11-2 to 47-7-4 zone; end vertical right exposed; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- All plates are 3x6 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=297, 13=498, 23=930.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
 Tampa, FL 36610

Builders FirstSource (Lake City, FL) Lake City, FL - 32055, 8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:03 2022 Page 1
ID: fGlaI9? qNSjAV9NJPFv3izruuC-ioeqeKiMNw44pTYE81E? ywmxfmKQODR7BAsIjxzTsU
1-6-0 6-2-0 11-0-0 16-3-8 18-1-2 24-6-0 30-9-2 37-1-2 42-6-0 48-3-8 49-10-0
1-6-0 6-2-0 4-10-0 5-3-8 1-9-10 6-4-14 6-3-2 6-4-0 5-4-14 5-9-8 1-6-8



LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-4-13 oc purlins, except end verticals, and 2-0-0 oc purlins (4-5-9 max.): 6-10.
BOT CHORD	2x4 SP No.2 *Except*		
	5-24: 2x6 SP No.2, 10-16,27-28,30-31: 2x4 SP No.3	BOT CHORD	Rigid ceiling directly applied or 5-10-4 oc bracing. Except: 10-0-0 oc bracing: 16-18
WEBS	2x4 SP No.3 *Except*		
	12-14: 2x6 SP No.2	WEBS	1 Row at midpt 4-24, 6-22, 9-21, 11-15

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD
2-3=858/979, 3-4=735/1004, 4-5=354/430, 5-6=513/478, 6-7=1134/639,
7-8=1134/639, 9-10=1470/709, 10-11=1621/722, 11-12=1061/450, 12-14=1343/607



BOT CHORD
2-26=724/701, 24-26=371/336, 23-24=1502/604, 5-23=1490/595, 21-22=133/341,
19-21=467/1469, 18-19=388/1343, 10-18=101/465

WEBS
3-26=315/289, 4-26=667/612, 4-24=561/561, 5-22=436/1165, 6-22=899/454,
6-21=428/1239, 7-21=364/284, 9-21=532/253, 10-19=211/274, 15-18=373/1001,
11-18=252/626, 11-15=936/441, 12-15=350/1056

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCPI=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 24-11-2, Interior(1) 24-11-2 to 37-1-2, Exterior(2R) 37-1-2 to 43-11-2, Interior(1) 43-11-2 to 49-10-0 zone; end vertical right exposed; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 4) Provide adequate drainage to prevent water ponding.
- 5) All plates are 2x4 MT20 unless otherwise indicated.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=325, 14=595, 24=922.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 27, 2022



Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659407
3000644	T34D	PIGGYBACK BASE	3	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:05 2022 Page 1

ID:fGlai9?nSijAv9NJPFv3izruuC-fAxOIONeRMLXirOW9f1Q?B0?GDPPhLZUd9EPqqrTsS

1-6-0	6-2-0	11-0-0	16-3-8	18-1-2	24-6-0	30-9-2	37-1-2	42-6-0	48-3-8
1-6-0	6-2-0	4-10-0	5-3-8	1-9-10	6-4-14	6-3-2	6-4-0	5-4-14	5-9-8

Scale = 1:86.3




Plate Offsets (X,Y)-- [3:0-3-0,0-3-0], [6:0-6-0,0-2-4], [10:0-3-0,0-2-5], [21:0-1-8,0-1-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.43	Vert(LL) 0.22	23-25	>868	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.70	Vert(CT) -0.24	23-25	>794	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.79	Horz(CT) 0.05	13	n/a	n/a		
BCDL 10.0	Code FBC2020/TP12014	Matrix-MS					Weight: 372 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2 *Except*
 5-23: 2x6 SP No.2, 10-15,26-27,29-30: 2x4 SP No.3
 WEBS 2x4 SP No.3 *Except*
 12-13: 2x6 SP No.2
 OTHERS 2x6 SP No.2

REACTIONS.


(size) 2=0-3-8, 13=0-3-0, 23=0-3-8
 Max Horz 2=440(LC 11)
 Max Uplift 2=-313(LC 12), 13=-504(LC 13), 23=-935(LC 9)
 Max Grav 2=701(LC 25), 13=1324(LC 26), 23=2046(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-854/960, 3-4=-732/985, 4-5=-348/411, 5-6=-507/463, 6-7=-1122/624,
 7-9=-1122/624, 9-10=-1446/693, 10-11=-1579/693, 11-12=-1011/395, 12-13=-1243/521
 BOT CHORD 2-25=-729/701, 23-25=-375/336, 22-23=-1488/617, 5-22=-1476/608, 20-21=-138/340,
 18-20=-477/1446, 17-18=-427/1308, 10-17=-97/433
 WEBS 3-25=-315/289, 4-25=-668/612, 4-23=-561/562, 5-21=-447/1153, 6-21=-887/464,
 6-20=-431/1221, 7-20=-364/284, 9-20=-515/263, 10-18=-207/291, 14-17=-393/959,
 11-17=-261/622, 11-14=-934/472, 12-14=-356/993

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 24-11-2, Interior(1) 24-11-2 to 37-1-2, Exterior(2R) 37-1-2 to 43-11-2, Interior(1) 43-11-2 to 47-7-4 zone; end vertical right exposed; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=313, 13=504, 23=935.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
 Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659408
3000644	T35	Piggyback Base	2	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:07 2022 Page 1

ID:fGlai9?gNSljAv9NJPFv3izruuC-bZ39A3Puz_bFx9YvG43u4c6Lm15K9Fon5TjWsizTsQ

1-6-0	6-2-0	11-0-0	16-3-8	18-1-2	24-6-0	30-9-2	37-1-2	42-6-0	48-3-8	49-10-0
1-6-0	6-2-0	4-10-0	5-3-8	1-9-10	6-4-14	6-3-2	6-4-0	5-4-14	5-9-8	1-6-8




Plate Offsets (X,Y)-- [3:0-3-0,0-3-0], [6:0-6-0,0-2-4], [10:0-3-0,0-2-5], [18:0-6-4,0-3-4], [22:0-1-8,0-1-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.43	Vert(LL) 0.22	24-26	>859	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.70	Vert(CT) 0.20	24-26	>976	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.81	Horz(CT) 0.03	14	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 351 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2 *Except*
 5-24: 2x6 SP No.2, 10-16,28-29: 2x4 SP No.3
 WEBS 2x4 SP No.3 *Except*
 12-14: 2x6 SP No.2

REACTIONS.


(size) 2=0-3-8, 14=0-3-0, 24=0-3-8
 Max Horz 2=379(LC 9)
 Max Uplift 2=-298(LC 12), 14=-597(LC 13), 24=-884(LC 9)
 Max Grav 2=700(LC 25), 14=1480(LC 26), 24=2093(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-833/894, 3-4=-725/919, 4-5=-277/344, 5-6=-481/413, 6-7=-1171/608,
 7-9=-1171/608, 9-10=-1532/712, 10-11=-1740/713, 11-12=-1461/578, 12-14=-1388/609
 BOT CHORD 2-26=-721/699, 24-26=-369/334, 23-24=-1535/567, 5-23=-1523/557, 21-22=-121/350,
 19-21=-430/1532, 18-19=-347/1445, 16-18=0/301, 10-18=-86/580
 WEBS 3-26=-315/289, 4-26=-666/612, 4-24=-560/561, 5-22=-404/1193, 6-22=-926/423,
 6-21=-440/1282, 7-21=-364/284, 9-21=-574/236, 9-19=-68/280, 11-15=-571/263,
 12-15=-385/1255, 15-18=-383/1340, 11-18=-181/340

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 24-11-2, Interior(1) 24-11-2 to 37-1-2, Exterior(2R) 37-1-2 to 43-11-2, Interior(1) 43-11-2 to 49-10-0 zone; end vertical right exposed; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- All plates are 3x6 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=298, 14=597, 24=884.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
 MiTek USA, Inc. FL Cert 6634
 6904 Parke East Blvd. Tampa FL 33610
 Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
 Tampa, FL 36610

Builders FirstSource (Lake City, FL) Lake City, FL - 32055, 8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:09 2022 Page 1
ID:fGlaI9?qNSIjAv9NJPFv3izruuC-XyBvbIQ8VbrzBTiLOV6MA1BhGqnod9E4YnCdxbzrTsO
1-6-0 6-2-0 11-0-0 16-3-8 18-1-2 24-6-0 30-9-2 37-1-2 42-6-0 48-3-8 49-9-8
1-6-0 6-2-0 4-10-0 5-3-8 1-9-10 6-4-14 6-3-2 6-4-0 5-4-14 5-9-8 1-6-0



LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-3-9 oc purlins, except end verticals, and 2-0-0 oc purlins (4-4-9 max.): 6-10.
BOT CHORD	2x4 SP No.2 *Except*	BOT CHORD	
	5-23: 2x6 SP No.2, 10-15,28-29: 2x4 SP No.3		Rigid ceiling directly applied or 5-9-13 oc bracing. Except:
WEBS	2x4 SP No.3 *Except*		10-0-0 oc bracing: 15-17
	12-13: 2x6 SP No.2	WEBS	1 Row at midpt 4-23, 6-21, 9-20
OTHERS	2x6 SP No.2		

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-835/875, 3-4=-727/900, 4-5=-270/325, 5-6=-478/399, 6-7=-1164/593,
7-9=-1164/593, 9-10=-1519/679, 10-11=-1696/677, 11-12=-1407/529, 12-13=-1301/526

BOT CHORD 2-25=-727/700, 23-25=-373/335, 22-23=-1525/579, 5-22=-1514/570, 20-21=-126/350,
18-20=-440/1518, 17-18=-379/1406, 15-17=0/301, 10-17=-71/538

WEBS 3-25=-315/290, 4-25=-667/612, 4-23=-560/561, 5-21=-414/1185, 6-21=-918/433,
6-20=-442/1271, 7-20=-364/284, 9-20=-563/246, 9-18=-74/273, 10-18=-230/271,
14-17=-399/1303, 11-17=-183/345, 11-14=-578/280, 12-14=-373/1132

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 24-11-2, Interior(1) 24-11-2 to 37-1-2, Exterior(2R) 37-1-2 to 43-11-2, Interior(1) 43-11-2 to 47-7-4 zone; end vertical right exposed; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 4) Provide adequate drainage to prevent water ponding.
- 5) All plates are 3x6 MT20 unless otherwise indicated.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=285, 23=897, 13=506.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 27, 2022

Job 3000644	Truss T37	Truss Type ROOF SPECIAL	Qty 1	Ply 1	IC CONST. - DALTON RES. T26659411
----------------	--------------	----------------------------	----------	----------	--------------------------------------


Builders FirstSource, Lake City, FL 32055

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jan 27 14:18:01 2022 Page 1

ID:fGlai9?qNSlJAv9NJPFv3izruuC-ya3M?P9i_gjgVASf_d7ByqN6hDNFLKYMuyuQHvzrJ7K

1-6-0 6-2-0 11-0-0 16-1-12 18-1-2 24-2-0 30-2-14 34-6-13 41-5-2 48-3-8 49-10-0
1-6-0 6-2-0 4-10-0 5-1-12 1-11-6 6-0-14 6-0-14 4-4-0 6-10-5 6-10-6 1-6-8

Scale = 1:86.4




LOADING (psf)	SPACING-	2-0-0	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.73	Vert(LL)	-0.12 21-23	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.64	Vert(CT)	-0.18 21-23	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.71	Horz(CT)	0.04 14	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS					Weight: 366 lb	FT = 20%

LUMBER-	BRACING-	
TOP CHORD 2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-3-2 oc purlins, except end verticals, and 2-0-0 oc purlins (3-11-2 max.): 7-9, 10-11.
BOT CHORD 2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2x4 SP No.3 *Except* 12-14: 2x6 SP No.2	WEBS	6-0-0 oc bracing: 20-21 9-7-3 oc bracing: 17-18. 1 Row at midpt 5-21, 6-21, 7-20, 7-19, 8-19, 9-19, 10-18, 10-17, 11-15

REACTIONS. (lb/size) 2=606/0-3-8, 21=1887/0-3-8, 14=1241/0-3-0	
Max Horz 2=447(LC 11)	
Max Uplift 2=231(LC 12), 21=702(LC 12), 14=533(LC 13)	
Max Grav 2=657(LC 19), 21=2176(LC 2), 14=1398(LC 26)	

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD 2-3=-730/224, 3-4=-621/232, 4-5=-523/250, 5-27=-102/271, 6-27=-90/336, 6-7=-275/279, 7-28=-751/442, 8-28=-751/442, 8-29=-747/439, 9-29=-747/439, 9-10=-1176/544, 10-30=-1283/565, 11-30=-1283/565, 11-31=-1040/457, 12-31=-1119/431, 12-14=-1295/549	
BOT CHORD 2-23=-317/776, 23-32=-210/334, 22-32=-210/334, 22-33=-210/334, 21-33=-210/334, 20-21=-270/288, 19-35=-306/982, 18-35=-306/982, 18-36=-380/1287, 17-36=-380/1287, 16-17=-273/893, 16-37=-273/893, 15-37=-273/893	
WEBS 3-23=-329/289, 5-23=-236/691, 5-21=-664/398, 6-21=-1496/596, 6-20=-327/1174, 7-20=-1060/346, 7-19=-418/1183, 8-19=-384/306, 9-19=-510/247, 9-18=-314/784, 10-18=-654/392, 10-17=-304/185, 11-17=-197/613, 11-15=-313/177, 12-15=-250/1010	

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-3-15, Interior(1) 3-3-15 to 18-1-2, Exterior(2R) 18-1-2 to 22-11-2, Interior(1) 22-11-2 to 30-2-14, Exterior(2E) 30-2-14 to 34-6-13, Interior(1) 34-6-13 to 41-5-2, Exterior(2R) 41-5-2 to 46-3-1, Interior(1) 46-3-1 to 49-10-0 zone; end vertical right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 3x6 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 231 lb uplift at joint 2, 702 lb uplift at joint 21 and 533 lb uplift at joint 14.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601





6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659413
3000644	T39	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:15 2022 Page 1
ID:fGlai9?qNSljAv9NJPfV3izruuC-M5YAroVv5Rb6vO9RklDmPIRe7FoX1pxywjfx8EzrTsl



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.73	Vert(LL)	0.22 24-27 >879 240	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.81	Vert(CT)	-0.40 17-19 >956 180				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.99	Horz(CT)	0.03 15 n/a n/a				
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS							
								Weight: 345 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except*
13-15: 2x6 SP No.2

REACTIONS.


(size) 1=Mechanical, 22=0-3-8, 15=0-3-0
Max Horz 1=428(LC 11)
Max Uplift 1=118(LC 12), 22=824(LC 13), 15=539(LC 13)
Max Grav 1=388(LC 23), 22=2597(LC 2), 15=1214(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=410/519, 2-4=279/547, 4-5=368/785, 5-6=219/698, 8-9=893/404,
9-10=1113/545, 10-11=1330/568, 11-12=1352/565, 13-15=267/120
BOT CHORD 1-24=492/315, 22-24=423/269, 21-22=394/478, 19-21=273/880, 17-19=401/1062,
16-17=576/1371
WEBS 2-24=331/298, 4-24=855/620, 4-22=563/684, 5-22=301/266, 6-22=1692/585,
6-21=562/1326, 8-21=1206/583, 8-19=182/666, 9-19=378/251, 10-17=108/468,
11-17=392/236, 11-16=611/352, 12-16=538/1394, 12-15=995/539

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 4-9-15, Interior(1) 4-9-15 to 18-1-2, Exterior(2E) 18-1-2 to 21-4-14, Exterior(2R) 21-4-14 to 26-2-13, Interior(1) 26-2-13 to 35-11-7, Exterior(2E) 35-11-7 to 40-3-7, Interior(1) 40-3-7 to 47-1-11, Exterior(2E) 47-1-11 to 49-10-0 zone; end vertical right exposed; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- All plates are 3x6 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=118, 22=824, 15=539.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659414
3000644	T40	Piggyback Base	1	1	Job Reference (optional)	


Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:16 2022 Page 1

ID:fGlai9?QNSijAv9NJPfV3izruuC-ql6Z38WxsIjzXXkeITk?yV_uHf7?mI469NPVhhrTsH

6-2-0	11-0-0	16-1-12	18-1-2	21-4-14	25-8-5	29-11-12	34-4-11	38-9-11	43-4-5	48-4-0	49-10-0
6-2-0	4-10-0	5-1-12	1-11-6	3-3-11	4-3-7	4-3-7	4-5-0	4-5-0	4-6-10	4-11-11	1-6-0

Scale = 1:85.3



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.44	Vert(LL)	0.22 22-25 >881 240	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.86	Vert(CT)	-0.44 17-19 >879 180				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.03 13 n/a n/a				
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS							
								Weight: 315 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-9 oc purlins, except 2-0-0 oc purlins (5-2-6 max.): 6-7, 9-11.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 4-20, 5-20, 6-19, 7-19, 8-19, 8-17
2 Rows at 1/3 pts 6-20

REACTIONS.


(size) 1=Mechanical, 20=0-3-8, 13=0-3-8
Max Horz 1=362(LC 8)
Max Uplift 1=133(LC 9), 20=853(LC 13), 13=518(LC 13)
Max Grav 1=338(LC 23), 20=2804(LC 2), 13=1163(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-315/451, 2-4=-183/483, 4-5=-350/1025, 5-6=-201/957, 8-9=-1427/736,
9-10=-1181/562, 10-11=-1238/629, 11-12=-1481/660, 12-13=-1699/779
BOT CHORD 1-22=-423/421, 20-22=-632/534, 19-20=-519/553, 17-19=0/456, 15-17=-352/1293,
13-15=-551/1455
WEBS 2-22=-333/298, 4-22=-854/631, 4-20=-568/684, 5-20=-301/264, 6-20=-1942/614,
6-19=-562/1432, 8-19=-1012/623, 8-17=-698/1559, 9-17=-852/521, 10-17=-255/198,
11-15=-153/549, 12-15=-370/288

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 4-10-0, Interior(1) 4-10-0 to 18-1-2, Exterior(2E) 18-1-2 to 21-4-14, Exterior(2R) 21-4-14 to 26-2-14, Interior(1) 26-2-14 to 38-9-11, Exterior(2R) 38-9-11 to 43-6-1, Interior(1) 43-6-1 to 49-10-0 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=133, 20=853, 13=518.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:
January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659415
3000644	T41	Piggyback Base	1	1	Job Reference (optional)	


Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:18 2022 Page 1

ID:fGlai9?qNSijAv9NJPFv3izruuC-mgEJUqXnNMzhmru0PumT1w3ByTpmECPOdhublZzrTsF



Scale = 1:85.3



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659416
3000644	T42	Piggyback Base Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:20 2022 Page 2
ID:fGlaI9?qNSljAv9NJPfV3izruuC-i3L3uWZ2vzDP?91PXIoX6L8TfGTRi45h4?NiqSzsTsD

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)
- Vert: 1-6=-54, 6-7=-54, 7-9=-54, 9-11=-54, 11-13=-54, 12-26=-20
- Concentrated Loads (lb)
- Vert: 11=-42(B) 14=-101(B) 31=-35(B) 32=-35(B) 38=-87(B) 39=-87(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659417
3000644	T43	Piggyback Base	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:20 2022 Page 1
ID:fGlai9?qNSlJAv9NJPfV3izruuC-i3L3uWZ2vzDP?91PXl0x6L8Z9GTGi4bh4?NiqSsrTsD



Scale = 1:62.3

Plate Offsets (X,Y)-- [2:0-3-0,0-1-12], [3:0-3-0,0-1-12], [7:0-6-0,0-0-3]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.39	Vert(LL)	-0.23 8-10	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.90	Vert(CT)	-0.36 8-10	>805	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.97	Horz(CT)	0.03 7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 169 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.


(size) 11=Mechanical, 7=0-3-8
Max Horz 11=-494(LC 13)
Max Uplift 11=-454(LC 13), 7=-324(LC 13)
Max Grav 11=1053(LC 20), 7=1075(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-465/258, 3-4=-589/221, 4-6=-1441/454, 6-7=-1619/486
BOT CHORD 10-11=-117/409, 8-10=-32/850, 7-8=-323/1350
WEBS 2-10=-406/917, 4-10=-792/473, 4-8=-215/718, 6-8=-361/320, 2-11=-949/437

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 5-11-6, Exterior(2R) 5-11-6 to 10-2-4, Interior(1) 10-2-4 to 24-0-8 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 11=454, 7=324.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Builders FirstSource (Lake City, FL), Lake City, FL - 32055, 8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:21 2022 Page 1
ID: fGlaI9?7NSljAv9NJPFv3izruuC-BFvS6saggHMGdJcb50JAfZhygpXRXvrJf6GMuzrTsC
2-7-10 5-11-6 11-11-10 17-10-15 24-0-8 25-6-8
2-7-10 3-3-11 6-0-4 5-11-5 6-1-9 1-6-0



LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-3-4 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 2-3.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midbt 3-11, 4-11, 1-12, 2-12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-464/257, 3-4=-588/220, 4-6=-1432/444, 6-7=-1608/475
BOT CHORD 11-12=-127/438, 9-11=0/848, 7-9=-2473/1330
WEBS 2-11=-403/915, 4-11=-789/468, 4-9=-205/709, 6-9=-353/312, 2-12=-947/435

Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


January 27, 2022

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659419
3000644	T45	Piggyback Base	2	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL),

Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:22 2022 Page 1
ID:fGlai9?gNSIjAv9NJPFv3izruuC-fSTqJCbIRbU7FSBnejrPBmEvg4AqA?S_XJspuKzrTsB



Scale = 1:65.0

Plate Offsets (X,Y)-- [2:0-3-0,0-1-12], [3:0-3-0,0-1-12], [7:0-6-0,0-0-3]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.39	Vert(LL)	-0.22	9-11	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.90	Vert(CT)	-0.35	9-11	>820	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.94	Horz(CT)	0.03	7	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 172 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.


(size) 12=0-3-8, 7=0-3-8
Max Horz 12=-528(LC 13)
Max Uplift 12=-449(LC 13), 7=-385(LC 13)
Max Grav 12=1059(LC 20), 7=1166(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-482/268, 3-4=-609/233, 4-6=-1450/456, 6-7=-1626/487
BOT CHORD 11-12=-120/451, 9-11=-8/865, 7-9=-283/1346
WEBS 2-11=-396/908, 4-11=-787/468, 4-9=-205/705, 6-9=-353/312, 2-12=-951/433

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 6-2-6, Exterior(2R) 6-2-6 to 10-5-4, Interior(1) 10-5-4 to 25-9-8 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 12=449, 7=385.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	T46	Flat Girder	1	1	T26659420

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:23 2022 Page 1

ID:fGlai9?QNSIjAv9NJPfV3izruuC-7e1CXXbwCuc_scm_CRMek_m1NUXavZz8mzbMQnzrTsA



Scale = 1:56.6

Plate Offsets (X,Y)-- [5:0-4-0,0-4-12]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.58	Vert(LL)	-0.03	4-5	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.73	Vert(CT)	-0.06	4-5	>999	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.48	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						Weight: 94 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

REACTIONS.

(size) 6=0-3-8, 4=0-4-0
Max Uplift 6=-825(LC 4), 4=-807(LC 4)
Max Grav 6=1741(LC 2), 4=1705(LC 2)

FORCES.


(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-6=-1238/612, 1-2=-464/218, 2-3=-464/218, 3-4=-1238/612
WEBS 1-5=-587/1251, 3-5=-587/1251

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=825, 4=807.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 999 lb down and 474 lb up at 1-7-4, and 998 lb down and 472 lb up at 3-7-4, and 998 lb down and 472 lb up at 5-7-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 4-6=-20
Concentrated Loads (lb)
Vert: 5=-862(F) 9=-864(F) 10=-862(F)



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659421
3000644	T47	Flat	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:24 2022 Page 1
ID:fGlai9?qNSlJAv9NJPFv3izruuC-bqbaktcYzCkrUmLam8ttHBJCdtssse56H?dLwzDzrTs9



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.61	Vert(LL)	-0.26	4-5	>425	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.80	Vert(CT)	-0.51	4-5	>213		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.16	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS					Weight: 59 lb	FT = 20%
	Code FBC2020/TPI2014							

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 5=0-3-8, 4=0-3-8
Max Uplift 5=-166(LC 8), 4=-166(LC 8)
Max Grav 5=338(LC 1), 4=338(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

BOT CHORD 4-5=-298/163
WEBS 2-5=-201/416, 2-4=-201/416

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=166, 4=166.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	T48	Flat	1	1	T26659422

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:25 2022 Page 1
ID:fGlai9?qNSlJAv9NJPfV3izruuC-319yyDdAkWsi6wwMKsO6pPrQUHMcNV_QEH4TVfzrTs8



Scale = 1:40.4

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.41	Vert(LL)	-0.01	5-6	>999	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.19	Vert(CT)	-0.02	5-6	>999		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.38	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS					Weight: 77 lb	FT = 20%
	Code FBC2020/TPI2014							

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 6=0-3-8, 4=0-3-8
Max Uplift 6=-166(LC 8), 4=-166(LC 8)
Max Grav 6=338(LC 1), 4=338(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-6=-298/474, 3-4=-298/474
WEBS 1-5=-339/245, 2-5=-292/590, 3-5=-339/245

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=166, 4=166.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	T49	Flat	1	1	T26659423

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:26 2022 Page 1
ID:fGlai9?qNSIjAv9NJPFv3izruuC-XDjL9ZepVp_Zj4VZtZvLMcObJhhB6wKaSxq016zrTs7



Bracing

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.41	Vert(LL) -0.02	5-6	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.23	Vert(CT) -0.03	5-6	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.50	Horz(CT) 0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 88 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.


(size) 6=0-3-8, 4=0-3-8
Max Uplift 6=-166(LC 8), 4=-166(LC 8)
Max Grav 6=395(LC 2), 4=395(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-6=-306/474, 3-4=-306/474
WEBS 1-5=-317/258, 2-5=-293/593, 3-5=-317/258

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=166, 4=166.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659424
3000644	T50	Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:26 2022 Page 1
ID:fGlai9?oNSljAv9NJPfV3izruuC-XDjL9ZepVp_Zj4VZtZvLMcOajhgj6?CaSxq016zrTs7



Bracing

Scale = 1:62.9

Plate Offsets (X,Y)-- [2:0-4-0,0-2-4], [3:0-4-0,0-2-4]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.51	Vert(LL)	-0.02	5-6	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.26	Vert(CT)	-0.03	5-6	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.19	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 112 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3


REACTIONS.

(size) 7=0-3-8, 5=0-3-8
Max Horz 7=-24(LC 8)
Max Uplift 7=-139(LC 8), 5=-120(LC 13)
Max Grav 7=398(LC 2), 5=397(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-7=-396/275, 3-5=-360/220

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 1-1-3, Exterior(2R) 1-1-3 to 5-4-2, Interior(1) 5-4-2 to 7-11-13, Exterior(2E) 7-11-13 to 9-3-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=139, 5=120.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	T51	Hip	1	1	T26659425

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:27 2022 Page 1

ID:fGlai9?qNSijAv9NJPFv3izruuC-?PHjMveRG76QLE4IRGQauqxpB51_rRDjhaZaZYzrTs6



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.21	Vert(LL)	-0.02	5-6	>999	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.19	Vert(CT)	-0.03	5-6	>999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.20	Horz(CT)	0.00	5	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 117 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.


(size) 8=0-3-8, 5=0-3-8
Max Horz 8=-79(LC 8)
Max Uplift 8=-157(LC 13), 5=-138(LC 12)
Max Grav 8=422(LC 20), 5=420(LC 19)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-8=-352/205, 4-5=-337/187
WEBS 1-7=-110/262

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 3-1-18, Exterior(2E) 3-1-18 to 9-3-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=157, 5=138.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.
3000644	T52	Common	1	1	T26659426

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:28 2022 Page 1
ID:fGlai9?qNSljAv9NJPFv3izruuC-Tbq5aF31REGzNfx?_ypR1TzIVNUauWtwEJ76_zrTs5



Scale = 1:74.1

Bracing

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.28	Vert(LL)	-0.02	4-5	>999	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.24	Vert(CT)	-0.04	4-5	>999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.20	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 102 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.

(size) 6=0-3-8, 4=0-3-8
Max Horz 6=-89(LC 8)
Max Uplift 6=-166(LC 13), 4=-147(LC 12)
Max Grav 6=452(LC 20), 4=449(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 1-6=-368/233, 3-4=-355/211
WEBS 1-5=-104/271, 3-5=-82/252

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 4-6-8, Exterior(2R) 4-6-8 to 7-6-8, Interior(1) 7-6-8 to 9-3-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=166, 4=147.

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 2-5, 1-6, 3-4



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659427
3000644	T53	Monopitch	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:29 2022 Page 1

ID:fGlai9?qNSljAv9NJPFv3izruuC-yoOTnbghokM7aXE8ZhT2_F016uafJOu08u2heQzrTs4

-1-6-0
1-6-0
5-3-8
5-3-8

Scale = 1:31.7




Plate Offsets (X,Y)-- [2:0-4-1,0-0-2]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.76	Vert(LL)	0.19	5-8	>330	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.76	Vert(CT)	0.17	5-8	>356	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.05	2	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 31 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
SLIDER Left 2x4 SP No.3 1-11-8

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-3-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 9-10-2 oc bracing.

REACTIONS.


(size) 5=0-3-8, 2=0-3-8
Max Horz 2=272(LC 12)
Max Uplift 5=192(LC 12), 2=-61(LC 9)
Max Grav 5=179(LC 1), 2=283(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-4=-276/346, 4-5=-192/311

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 5-1-12 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 5=192.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659428
3000644	T54	Monopitch	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:30 2022 Page 1
ID:fGlaI9?qNSIjAv9NJPFv3izruuC-Q_yr?xhJZ2U_ChoK6P_HWSZE0lxZ2r89NYoEAtzrTs3



Scale = 1:31.1

Plate Offsets (X,Y)-- [1:0-3-8,Edge]

LOADING (psf)	SPACING-	CSL.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.62	Vert(LL)	0.10	4-7	>612	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.65	Vert(CT)	-0.09	4-7	>655		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.00	Horz(CT)	-0.04	1	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP						
	Code FBC2020/TPI2014						Weight: 28 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
SLIDER Left 2x4 SP No.3 1-11-8

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-3-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 1=Mechanical, 4=0-3-8
Max Horz 1=218(LC 12)
Max Uplift 4=202(LC 12)
Max Grav 1=190(LC 1), 4=229(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-3=-275/125, 3-4=-202/282

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 5-1-12 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 4=202.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659429
3000644	T55	MONO TRUSS	16	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:30 2022 Page 1
ID:fGlai9?qNSljAv9NJPfV3izruuC-Q_yr?xhJZ2U_ChoK6P_HWSZATlwE2nm9NYoEAtzrTs3



Scale = 1:18.1




Plate Offsets (X,Y)-- [2:0-0-6,0-0-5]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.84	Vert(LL)	0.25	5-9	>387	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.73	Vert(CT)	0.22	5-9	>425	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.28	Horz(CT)	-0.00	10	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 36 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 3-7-4 oc bracing.

REACTIONS.


(size) 2=0-3-8, 10=0-2-0
Max Horz 2=121(LC 8)
Max Uplift 2=325(LC 8), 10=222(LC 8)
Max Grav 2=381(LC 1), 10=260(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-524/1010, 5-6=-607/210, 4-6=-607/210
BOT CHORD 2-5=-1128/503
WEBS 3-5=-442/942, 4-10=-268/647

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=22ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 7-6-12 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 10.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=325, 10=222.



Philip J. O'Regan PE No.58126
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

January 27, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	IC CONST. - DALTON RES.	T26659430
3000644	T55G	GABLE	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.430 s Aug 16 2021 MiTek Industries, Inc. Wed Jan 26 13:05:31 2022 Page 1
ID:fGlai9?QNSljAv9NJPfV3izruuC-uAWECHxKMcqrNWg6VW3g5VfiQJnGwJcCXnjJzrTs2
8-0-0
8-0-0

Scale = 1:17.6





Plate Offsets (X,Y)--		[2:0-3-8,Edge], [2:0-7-12,Edge]																	
LOADING (psf)		SPACING-		2-0-0		CSI.		DEFL.		in (loc)		I/defl		L/d		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL		1.25		TC	0.24	Vert(LL)	0.00	1		n/r		120		MT20	244/190		
TCDL	7.0	Lumber DOL		1.25		BC	0.10	Vert(CT)	0.00	1		n/r		120					
BCLL	0.0 *	Rep Stress Incr		YES		WB	0.09	Horz(CT)	0.00	7		n/a		n/a					
BCDL	10.0	Code FBC2020/TPI2014				Matrix-S										Weight: 36 lb		FT = 20%	

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.


For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

PLATE SIZE


4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION




BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:
ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:
ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved



Mittek Engineering Reference Sheet: MII-7473 rev. 5/19/2020

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.