


**ROOF VENTILATION:**  
R906.2 Minimum vent area.  
The minimum net free ventilating area shall be 1/150 of the area of the vented space.  
Exception: The minimum net free ventilation area shall be 1/300 of the vented space provided one or more of the following conditions are met:  
1. In Climate Zones 5, 7 and 8, a Class I or II vapor retarder is installed on the warm-in-winter side of the ceiling.  
2. At least 40 percent and not more than 50 percent of the required ventilating area is provided by ventilators located in the upper portion of the attic or rafter space. Upper ventilators shall be located no more than 3 feet below the ridge or highest point of the space, measured vertically, with the balance of the required ventilation provided by eave or cornice vents. Where the location of wall or roof framing members conflicts with the installation of upper ventilators, installation more than 3 feet below the ridge or highest point of the space shall be permitted.

**FRONT ELEVATION**  
SCALE: 1/4" = 1'-0"

**LEFT ELEVATION**  
SCALE: 1/4" = 1'-0"

**RIGHT ELEVATION**  
SCALE: 1/4" = 1'-0"

**REAR ELEVATION**  
SCALE: 1/4" = 1'-0"



**FLOOR PLAN**

SCALE: 1/4" = 1'-0"  
NOTE: ALL CEILING HEIGHTS TO BE 8'-0" UNLESS OTHERWISE NOTED

**R302.5.1 Opening protection:**  
Openings from a private garage directly into a room used for sleeping purposes shall not be permitted. Other openings between the garage and residence shall be equipped with solid wood doors not less than 1 3/8 inches in thickness, solid or honeycomb-core steel doors not less than 1 3/8 inches thick, or 20-minute fire-rated doors, equipped with a self-closing device.

TABLE R302.6 DWELLING/GARAGE SEPARATION:	
SEPARATION	MATERIAL
From the residence and attic	Not less than 1/2-inch gypsum board or equivalent applied to the garage side
From all habitable rooms above the garage	Not less than 5/8-inch Type X gypsum board or equivalent
Structure(s) supporting floor/ceiling assemblies used for separation required by this section	Not less than 1/2-inch gypsum board or equivalent
Garages located less than 3 feet from a dwelling unit on the same lot applied to the interior side of exterior walls that are within this area	Not less than 1/2-inch gypsum board or equivalent

**AREA SUMMARY**

LIVING AREA	1227	S. F.
GARAGE AREA	328	S. F.
PORCH AREA	157	S. F.
TOTAL AREA	1712	S. F.

Hometown Homes  
Spec House - 204 NW Sparr Lane

PROJECT ADDRESS:  
204 NW Sparr Lane  
Lake City, FL 32055


**DIMENSIONS:**  
Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

**COPYRIGHTS AND PROPERTY RIGHTS:**  
Mark Disosway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first its express written permission and consent of Mark Disosway.

**CERTIFICATION:** I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to civil engineering comply with the 6th Edition Florida Building Code Residential (2017) to the best of my knowledge.

**LIMITATION:** This design is valid for one building, at specified location.

MARK DISOSWAY PE, 53915



Monday, May 6, 2019


Mark Disosway P.E.  
163 SW Midtown Place  
Suite 108  
Lake City, Florida 32025  
386.754.5419  
disoswaydesign@gmail.com

JOB NUMBER:  
190403

1  
OF 5 SHEETS

39846






**TYPICAL DESIGN WALL SECTION**  
**NON - STRUCTURAL DATA**

SCALE: 1" = 1'-0"

**ELECTRICAL PLAN NOTES**

- E -1 WIRE ALL APPLIANCES, HVAC UNITS AND OTHER EQUIPMENT PER MANUF. SPECIFICATIONS.
- E -2 CONSULT THE OWNER FOR THE NUMBER OF SEPARATE TELEPHONE LINES TO BE INSTALLED.
- E -3 ALL INSTALLATIONS SHALL BE PER NATL. ELECTRIC CODE.
- E -4 ALL SMOKE DETECTORS SHALL BE 120V W/ BATTERY BACKUP OF THE PHOTOELECTRIC TYPE, AND SHALL BE INTERLOCKED TOGETHER. INSTALL INSIDE AND NEAR ALL BEDROOMS.
- E -5 TELEPHONE, TELEVISION AND OTHER LOW VOLTAGE DEVICES OR OUTLETS SHALL BE AS PER THE OWNER'S DIRECTIONS, & IN ACCORDANCE W/ APPLICABLE SECTIONS OF NEC-LATEST EDITION.
- E -6 ELECTRICAL CONTR SHALL BE RESPONSIBLE FOR THE DESIGN & SIZING OF ELECTRICAL SERVICE AND CIRCUITS.
- E -7 ENTRY OF SERVICE (UNDERGROUND OR OVERHEAD) TO BE DETERMINED BY POWER COMPANY.
- E -8 ALL 120-VOLT, SINGLE-PHASE, 15- AND 20-AMPERE BRANCH CIRCUITS SUPPLYING OUTLETS INSTALLED IN DWELLING UNIT FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, DENS, BEDROOMS, SUN ROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS, OR SIMILAR ROOMS OR AREAS SHALL BE PROTECTED BY A LISTED ARC-FAULT CIRCUIT INTERRUPTER, COMBINATION-TYPE INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUIT.
- E -9 ALL OUTLETS TO BE LOCATED ABOVE BASE FLOOD ELEVATION
- E -10 A SERVICE DISCONNECT WITH OVER CURRENT PROTECTION SHALL BE INSTALLED OUTSIDE OF THE BUILDING, ON THE LOAD SIDE OF THE METER, AT THE PLACE ELECTRIC CONDUCTORS ENTER THE BUILDING. SERVICE ENTRANCE CONDUCTORS MAY NOT BE LOCATED INSIDE OF THE OF THE BUILDING WITHOUT SPECIAL APPROVAL OF THE BUILDING OFFICIAL.
- E -11 CARBON MONOXIDE ALARMS SHALL BE REQUIRED WITHIN 10' OF ALL ROOMS FOR SLEEPING PURPOSES IN BUILDINGS HAVING A FOSSIL-FUEL-BURNING HEATER OR APPLIANCE, A FIREPLACE, OR ATTACHED GARAGE.
- E -12 ALL OUTLETS LOCATED IN RESIDENTIAL TO BE TAMPER-RESISTANT PER NEC.

ELECTRICAL LEGEND	
	CEILING FAN (PRE-WIRE FOR LIGHT KIT)
	DOUBLE SECURITY LIGHT
	FLUORESCENT LIGHT FIXTURE
	RECESSED CAN LIGHT
	BATH EXHAUST FAN WITH LIGHT
	BATH EXHAUST FAN
	LIGHT FIXTURE
	DUPLEX OUTLET
	220v OUTLET
	GFI DUPLEX OUTLET
	SMOKE DETECTOR
	WALL SWITCH 1
	3 WAY WALL SWITCH
	4 WAY WALL SWITCH
	WATER PROOF GFI OUTLET
	PHONE JACK
	TELEVISION JACK
	GARAGE DOOR OPENER
	CARBON MONOXIDE ALARM



Hometown Homes

Spec House - 204 NW Sparr Lane


PROJECT ADDRESS:  
204 NW Sparr Lane  
Lake City, FL 32055

**DIMENSIONS:**  
Stated dimensions supersede scaled dimensions. Refer all questions to Mark Discosway, P.E. for resolution. Do not proceed without clarification.

**COPYRIGHTS AND PROPERTY RIGHTS:**  
Mark Discosway, P.E. hereby expressly reserves its common law copyright and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without the express written permission and consent of Mark Discosway.

**CERTIFICATION:** I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to electrical engineering, comply with the 6th Edition Florida Building Code Residential (2017) to the best of my knowledge.

**LIMITATION:** This design is valid for one building, at specified location.




Mark Discosway P.E.  
163 SW Midtown Place  
Suite 103  
Lake City, Florida 32025  
386.7545419  
discoswaydesign@gmail.com

JOB NUMBER:  
190403

**2**  
OF 5 SHEETS






**ONE STORY WALL SECTION**  
SCALE: 3/4" = 1'-0"


- RING-SHANK NAILS SHALL HAVE THE FOLLOWING MINIMUM DIMENSIONS:
- 0.113 INCH NOMINAL ROOT SHANK DIAMETER
  - RING DIAMETER OF 0.010 OVER SHANK DIAMETER
  - 16 TO 20 RINGS PER INCH
  - 0.280 INCH FULL ROUND HEAD DIAMETER
  - 2-3/8 INCH NAIL LENGTH

- NAILING PATTERN SHALL BE:
- 4" OC GABLE END (SEE GABLE BRACING DETAIL)
  - 6" OC @ EDGES ALL ZONES
  - 6" OC @ INTERMEDIATE FRAMING IN ZONE 3
  - 12" OC @ INTERMEDIATE FRAMING IN ZONE 1 & 2




**ROOF SHEATHING FASTENING**

- FOR OVERHANGES 12"-24" USE A DROPPED GABLE TRUSS WH 2X4 OUTLOOKER @ 24" O.C. w/ H2.5a TO GABLE TRUSS AND (4) 131"x3.25" NAILS TO 2nd TRUSS (BLOCK BETWEEN OUTLOOKER)




**SPACE RAT RUN & DIAGONAL BRACE 6'-0" O.C. FOR GABLE HEIGHT UP TO 25'-0" 130 MPH, EXP. C, ENCLCD**


**(TYP.) GABLE BRACING DETAIL**  
WOOD FRAME




**SHEATHING FOR UPLIFT ATTACHMENT DETAILS**  
ONE STORY WOOD FRAME



**(TYP.) INTERIOR BEARING WALL**  
ONE STORY WOOD FRAME w/ STRAPS & ANCHORS



**(TYP.) PORCH POST**  
ONE STORY WOOD



**(TYP.) BEAM TO WALL**  
WOOD FRAME w/ STRAPS & ANCHORS

CONNECTOR TABLE					
Uplift SP	Uplift SPF	Truss Connector	To Plate	To Truss/Rafter	
615	485	SDWC15600	-	-	
415	290	H3	4-8dX1 1/2"	4-8dX1 1/2"	
575	495	H2.5A	5-8dX1 1/2"	5-8dX1 1/2"	
1340	1015	H10A	9-10d1 1/2"	9-10d1 1/2"	
720	820	LTS12-20	6-10d1 1/2"	6-10d1 1/2"	
1000	860	MTS12-30	7-10d1 1/2"	7-10d1 1/2"	
1450	1245	HTS25-30	12-10d1 1/2"	12-10d1 1/2"	
Uplift SP	Uplift SPF	Strap Ties	To One Member	To Other Member	
1235	1235	LSTA21	8-10d	8-10d	
1640	1455	MSTA24	9-10d	9-10d	
1030	1030	CS20	7-10d	7-10d	
Uplift SP	Uplift SPF	Stud Plate Ties	To Stud	To Plate	
685	635	SP1	6-10d	4-10d	
1065	605	SP2	7-10d	6-10d	
771	771	LSTA24	10-10d	wrap under or over plate	
1235	1235	LSTA24	14-10d	wrap under or over plate	
Uplift SP	Uplift SPF	Holdowns @ Stewall	To Stud / Post	Anchor	
1825	1830	DTT22	8-SDS 1/4"x1 1/2"	12"x12" Titen HD	
4235	3640	HTT4	18-16dX2 1/2"	12"x12" Titen HD	
Uplift SP	Uplift SPF	Holdowns @ Mono	To Stud / Post	Anchor	
1825	1800	DTT22	8-SDS 1/4"x1 1/2"	12"x6" Titen HD	
4235	3640	HTT4	18-16dX2 1/2"	12"x12" Titen HD	
Uplift SP	Uplift SPF	Post Bases @ Stewall	To Post	Anchor	
2200	2000	ABU44	12-16d	5/8"x12" Drill & Epoxy	
2300	2000	ABU66	12-16d	5/8"x7" Drill & Epoxy	
Uplift SP	Uplift SPF	Post Bases @ Mono	To Post	Anchor	
2200	2000	ABU44	12-16d	5/8"x7" Drill & Epoxy	
2300	2000	ABU66	12-16d	5/8"x7" Drill & Epoxy	

**EXTERIOR WALL STUD TABLE FOR SPF #2 STUDS:**

THIS STUD HEIGHT TABLE IS PER 2012 WFCM, TABLE 3.20B5, EXTERIOR LOAD BEARING & NON LOAD BEARING STUD LENGTHS FOR WALLS WITH OSB EXTERIOR AND 1/2" GYP INTERIOR RESISTING INTERIOR ZONE WINDLOADS, 130 MPH, EXPOSURE C, STUD DEFLECTION LIMIT H/240 (NOT OK FOR BRITTLE FINISH). STUD SPACINGS SHALL BE MULTIPLIED BY 0.8 FOR FRAMING LOCATED WITHIN 4 FEET OF CORNERS FOR END ZONE LOADING. (END ZONE EXAMPLE 16" O.C. x 0.8 = 12.8" O.C.)

(1) 2x4 @ 16" OC	TO 10'-1" STUD HEIGHT
(1) 2x4 @ 12" OC	TO 11'-2" STUD HEIGHT
(1) 2x6 @ 16" OC	TO 15'-7" STUD HEIGHT
(1) 2x6 @ 12" OC	TO 17'-3" STUD HEIGHT

GRADE & SPECIES TABLE			
2x8	SP #2	925	1.4
2x10	SP #2	800	1.4
2x12	SP #2	750	1.4
GLB	24F-V3 SP	2600	1.9
LSL	TIMBERSTRAND	1700	1.7
LVL	MICROLAM	2950	2.0
PSL	PAROLAM	2900	2.0

## GENERAL NOTES:

TRUSSES: TRUSSES SHALL BE DESIGNED BY A FLORIDA LICENSED ENGINEER IN ACCORDANCE WITH THE FBOR. TRUSS ENGINEERING SHALL INCLUDE TRUSS DESIGN, PLACEMENT PLANS, TEMPORARY AND PERMANENT BRACING DETAILS, TRUSS-TO-TRUSS CONNECTIONS, AND UPLIFT AND REACTION LOADS FOR ALL BEARING LOCATIONS. TRUSS ENGINEERING IS THE RESPONSIBILITY OF THE TRUSS MANUFACTURER AND SHALL BE SIGNED & SEALED BY THE MANUFACTURER'S DESIGN ENGINEER. IT IS THE BUILDER'S RESPONSIBILITY TO VERIFY THE TRUSS DESIGNER FULLY SATISFIED ALL THE ABOVE REQUIREMENTS AND TO SELECT UPLIFT CONNECTIONS BASED ON TRUSS ENGINEERING UPLIFT AND PROVIDE FOOTINGS FOR INTERIOR BEARING WALLS. BUILDER IS TO FURNISH TRUSS ENGINEERING TO WIND LOAD ENGINEER FOR REVIEW OF TRUSS REACTIONS ON THE BUILDING STRUCTURE. STRAP 2X6 RAFTERS WITH MIN. UPLIFT CONNECTION 415LB EACH END, 2X8 RAFTERS 700 LB EACH END.

SITE PREPARATION: SITE ANALYSIS AND PREPARATION IS NOT PART OF THIS PLAN FOUNDATION: CONFIRM THAT THE FOUNDATION DESIGN & SITE CONDITIONS MEET GRADUITY LOAD REQUIREMENTS (ASSUME 1500 PSF BEARING CAPACITY UNLESS VISUAL OBSERVATION OR SOILS TEST PROVES OTHERWISE) CONCRETE: MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS,  $P_c = 2500$  PSI.

WELDED WIRE REINFORCED SLAB: 8" x 8" W14 x W14, FB = 85KSI, WELDED WIRE REINFORCEMENT FABRIC (W.W.M.) CONFORMING TO ASTM A185, LOCATED IN MIDDLE OF THE SLAB, SUPPORTED WITH APPROVED MATERIALS OR SUPPORTS AT SPACINGS NOT TO EXCEED 7'.

FIBER CONCRETE SLAB: CONCRETE SLABS ON GROUND CONTAINING SYNTHETIC FIBER REINFORCEMENT, FIBER LENGTH 1/2 INCH TO 2 INCHES. DOSAGE AMOUNTS FROM 0.75 TO 1.5 POUNDS PER CUBIC YARD PER THE MANUFACTURER'S RECOMMENDATIONS. FIBERS TO COMPLY WITH ASTM C-1116. SUPPLIER TO PROVIDE ASTM C-1116 CERTIFICATION OF COMPLIANCE WHEN REQUESTED BY BUILDING OFFICIAL.

CONTROL JOINTS: WHERE SPECIFIED, SAWN CONTROL JOINTS IN SLAB-ON-GRADE SHALL BE CUT HORIZONTAL PERPENDICULAR TO FRAMING, OVER A MINIMUM OF 3 FRAMING MEMBERS, WITH PANEL EDGES STAGGERED. THE LENGTH / WIDTH RATIOS OF SLAB AREAS SHALL NOT EXCEED 1.5 AND TYPICAL SPACING OF CUTS TO BE 12FT. DO NOT CUT W/M OR REINFORCING STEEL. (RECOMMENDED LOCATION OF CONTROL JOINTS IS SUBJECT TO OWNER AND CONTRACTOR'S APPROVAL. THE CONTROL JOINTS ARE NOT INTENDED TO PREVENT CRACKS BUT RATHER TO ENCOURAGE THE CRACK ON A GIVEN LINE.)

REBAR: ASTM A615, GRADE 40, DEFORMED BARS, FY = 60 KSI, ALL LAP SPLICES 40" DB (25" FOR #5 BARS), UNO. ALL REINFORCEMENT SHALL BE DETAILED AND PLACED IN ACCORDANCE WITH ACI 315-96, U.N.O.


ROOF SHEATHING: ALL ROOFS ARE HORIZONTAL DIAPHRAGMS. 7/16" OSB SHEATHING, UNBLOCKED, APPLIED PERPENDICULAR TO FRAMING, OVER A MINIMUM OF 3 FRAMING MEMBERS, WITH PANEL EDGES STAGGERED.

STRUCTURAL CONNECTORS: MANUFACTURERS AND PRODUCT NUMBER FOR CONNECTORS, ANCHORS, AND REINFORCEMENT ARE LISTED FOR EXAMPLE, NOT ENDORSEMENT. AN EQUIVALENT DEVICE OF THE SAME OR OTHER MANUFACTURER CAN BE SUBSTITUTED FOR ANY DEVICES LISTED IN THE EXAMPLE TABLES AS LONG AS IT MEETS THE REQUIRED LOAD CAPACITIES. MANUFACTURER'S INSTALLATION INSTRUCTIONS MUST BE FOLLOWED TO ACHIEVE RATED LOADS.


ANCHOR BOLTS: 307 ANCHOR BOLTS WITH MINIMUM EMBEDMENT AS SPECIFIED IN DRAWINGS BUT NO LESS THAN 7" IN CONCRETE OR REINFORCED BOND BEAM OR 19" IN GROUTED CMU.

**BUILDER'S RESPONSIBILITY:**  
THE BUILDER AND OWNER ARE RESPONSIBLE FOR THE FOLLOWING, WHICH ARE SPECIFICALLY NOT PART OF THE WIND LOAD ENGINEER'S SCOPE OF WORK.  
CONFIRM SITE CONDITIONS: FOUNDATION BEARING CAPACITY, GRADE AND BACKFILL HEIGHT, WIND SPEED AND DEBRIS ZONE, AND FLOOD ZONE.  
PROVIDE MATERIALS AND CONSTRUCTION TECHNIQUES, WHICH COMPLY WITH FBOR REQUIREMENTS FOR THE STATED WIND VELOCITY AND DESIGN PRESSURES.  
PROVIDE A CONTINUOUS LOAD PATH FROM TRUSSES TO FOUNDATION. IF YOU BELIEVE THE PLAN OMTS A CONTINUOUS LOAD PATH CONNECTION, CALL THE WIND LOAD ENGINEER IMMEDIATELY.  
VERIFY THE TRUSS MANUFACTURER'S SEALED ENGINEERING INCLUDES TRUSS DESIGN, PLACEMENT PLANS, TEMPORARY AND PERMANENT BRACING DETAILS, TRUSS-TO-TRUSS CONNECTIONS, AND UPLIFT AND REACTION LOADS FOR ALL BEARING LOCATIONS.

**ROOF SYSTEM DESIGN:**  
THE SEAL ON THESE PLANS FOR COMPLIANCE WITH FBOR IS BASED ON REACTIONS, UPLIFTS, AND BEARING LOCATIONS IN TRUSS ENGINEERING SUBMITTED TO THE WIND LOAD ENGINEER. IT IS THE RESPONSIBILITY OF THE BUILDER TO CHECK ALL DETAILS OF THE COMPLETE ROOF SYSTEM DESIGN SUBMITTED BY THE TRUSS MANUFACTURER AND HAVE IT SIGNED, AND SEALED BY A DESIGN PROFESSIONAL FOR CORRECT APPLICATION OF FBOR REQUIRED LOADS AND ANY SPECIAL LOADS. THE BUILDER IS RESPONSIBLE TO REVIEW EACH INDIVIDUAL TRUSS MEMBER AND THE TRUSS ROOF SYSTEM AS A WHOLE AND TO PROVIDE RESTRAINT FOR ANY LATERAL BRACING. THE BUILDER SHOULD USE CARE CHECKING THE ROOF DESIGN BECAUSE THE WIND LOAD ENGINEER IS SPECIFICALLY NOT RESPONSIBLE FOR THE TRUSS LAYOUT WHICH WAS CREATED BY THE TRUSS MANUFACTURER AND THE TRUSS DESIGNER ALSO DENIES RESPONSIBILITY FOR THE LAYOUT PER NOTES ON THEIR SEALED TRUSS SHEETS.



**(TYP.) INTERSECTING WALL FRAMING**  
WOOD FRAME




**TYPICAL HEADER STRAPING DETAIL**  
ONE STORY WOOD FRAME w/ STRAPS & ANCHORS


HEADER STRAP TABLE			
Uplift	Top Connection	Bottom Connection	
< 1235	LSTA24, 14-10d wrap over plate	1/2" x 10" Anchor bolt w/ 3" x 3" x 1/4" washer must be located within 6" of king stud @ all door locations	
< 1455	MSTA24, 18-10d header to jacks	DTT22	
< 1800	(2) MSTA24, 18-10d header to jacks	DTT22	
< 2910	(2) MSTA24, 18-10d header to jacks	HTT4	

SILL PLATE SPANS FOR 10'-0" WALL HEIGHT				
DESIGN WIND SPEED	MAX. SPANS FOR SPF #2	BASED ON WFCM TABLE A-3.28B		
	(1) 2x4	(2) 2x4	(1) 2x6	(2) 2x6
130 MPH EXP. C	5'-2"	7'-9"	7'-3"	11'-3"


FOR OTHER WALL HEIGHTS (H) SILL SPAN SHALL BE DIVIDED BY (H/10)




**(TYP.) BEAM TO WALL**  
WOOD FRAME w/ STRAPS & ANCHORS




**INTERIOR SHEAR WALL**  
ONE STORY WOOD FRAME w/ STRAPS & AB



**(TYP.) CORNER FRAMING**  
WOOD FRAME



**(TYP.) WALL CONNECTIONS**  
ONE STORY WOOD FRAME



**OPENING FORCE TRANSFER**  
WOOD FRAME

**(TYP.) GARAGE DOOR BUCK INSTALLATION**  
WOOD FRAME

DESIGN CRITERIA & LOADS:			
BUILDING CODE	6TH EDITION FLORIDA BUILDING CODE RESIDENTIAL (2017)		
CODE FOR DESIGN LOADS	ASCE 7-10		
<b>WINDLOADS</b>			
BASIC WIND SPEED (ASCE 7-10, 3S GUST)	130 MPH		
WIND EXPOSURE (BUILDER MUST FIELD VERIFY)	C		
TOPOGRAPHIC FACTOR (BUILDER MUST FIELD VERIFY)	1		
RISK CATEGORY	II		
ENCLOSURE CLASSIFICATION	ENCLOSED		
INTERNAL PRESSURE COEFFICIENT	0.18		
ROOF ANGLE	7.45 DEGREES		
MEAN ROOF HEIGHT	30 FT		
<b>C&amp;C DESIGN PRESSURES</b>			
FLOOR LOADING	40 PSF LIVE LOAD		
ROOMS OTHER THAN SLEEPING ROOM	30 PSF LIVE LOAD		
ROOF LOADING	20 PSF LIVE LOAD		
FLAT OR < 4:12	16 PSF LIVE LOAD		
4:12 TO < 12:12	12 PSF LIVE LOAD		
12:12 & GREATER	12 PSF LIVE LOAD		
SOIL BEARING CAPACITY	1500 PSF		
FLOOD ZONE	THIS BUILDING IS NOT IN THE FLOOD ZONE		

COMPONENT & CLADDING DESIGN PRESSURES 130 MPH (EXP. C)			
EFFECTIVE WIND AREA (FT <sup>2</sup> )	ZONE 4 INTERIOR	ZONE 5 END 4' FROM ALL OUTSIDE CORNER	
0-20	+25.6(Vasd)	-27.8(Vasd)	+25.6(Vasd)
0-20	+42.6(Vult)	-46.2(Vult)	+42.6(Vult)
<b>GARAGE DOOR DESIGN PRESSURES 130 MPH (EXP. C)</b>			
8x7 GARAGE DOOR	+22.8(Vasd)	-25.5(Vasd)	
16x7 GARAGE DOOR	+21.7(Vasd)	-24.1(Vasd)	

Homelown Homes  
Spec House - 204 NW Sparr Lane

PROJECT ADDRESS:  
204 NW Sparr Lane  
Lake City, FL 32055

DIMENSIONS: Stated dimensions supersede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.  
COPYRIGHTS AND PRIORITY RIGHTS: Mark Disosway, P.E. hereby expressly reserves its common law copyright/related property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without the express written permission and consent of Mark Disosway.  
CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 6th Edition Florida Building Code Residential (2017), to the best of my knowledge.  
LIMITATION: This design is valid for one building, at specified location.

MARK DISOSWAY P.E. 53915



Mark Disosway P.E.  
163 SW Midtown Place  
Suite 103  
Lake City, Florida 32025  
386.7545419  
disoswaydesign@gmail.com


JOB NUMBER:  
190403  
S-I  
OF 5 SHEETS




TALL STEM WALL TABLE:						
The table assumes 60 ksi reinforcing bars with 6" hook in the footing and bent 24" into the reinforced slab at the top. The vertical steel is to be placed toward the tension side of the CMU wall (away from the soil pressure, within 2" of exterior side of the wall). If the wall is over 8' high, add Duowall ladder reinforcement at 6" OC vertically or a horizontal bond beam with 1#5 continuous at mid height. For higher irts of the wall 12" CMU may be used with reinforcement as shown in the table below.						
STEM WALL HEIGHT (FEET)	UNBALANCED BACKFILL HEIGHT	VERTICAL REINFORCEMENT FOR 8" CMU STEM WALL (INCHES O.C.)			VERTICAL REINFORCEMENT FOR 12" CMU STEM WALL (INCHES O.C.)	
		#5	#7	#8	#5	#7
3.3	3.0	96	96	6	96	96
4.0	3.7	96	96	16	96	96
4.7	4.3	88	96	16	96	96
5.3	5.0	56	96	16	96	96
6.0	5.7	40	80	16	80	96
6.7	6.3	32	56	10	56	96
7.3	7.0	24	40	16	40	80
8.0	7.7	16	32	18	32	64
8.7	8.3	8	24	12	24	48
9.3	9.0	8	16	14	16	40

MASONRY NOTE:	
MASONRY CONSTRUCTION AND MATERIALS FOR THIS PROJECT SHALL CONFORM TO ALL REQUIREMENTS OF "SPECIFICATION FOR MASONRY STRUCTURES" (ACI 530.1/ASCE 6/TMS 602). THE CONTRACTOR AND MASON MUST IMMEDIATELY, BEFORE PROCEEDING, NOTIFY THE ENGINEER OF ANY CONFLICTS BETWEEN ACI 530.1-02 AND THESE DESIGN DRAWINGS. ANY EXCEPTIONS TO ACI 530.1-02 MUST BE APPROVED BY THE ENGINEER IN WRITING.	
ACI 530.1-02 Section	Specific Requirements
1.4A Compressive strength	8" block bearing walls: $f_m = 1500$ psi
2.1 Mortar	ASTM C 270, Type N, UNO
2.2 Grout	ASTM C 476, admixtures require approval
2.3 CMU standard	ASTM C 90-02, Normal weight, Hollow, medium surface finish, 8"x8"x16" running bond and 12"x12" or 16"x16" column block
2.3 Clay brick standard	ASTM C 216-02, Grade SW, Type FBS, 8"x2 1/4"x11 1/8"
2.4 Reinforcing bars, #3 - #11	ASTM 615, Grade 40, $F_y = 40$ ksi, Lap splices min 40 bar dia. (25" for #5)
2.4F Coating for corrosion protection	Anchors, sheet metal ties completely embedded in mortar or grout, ASTM A525, Class GB5, 0.50 oz/lb or 304SS
2.4F Coating for corrosion protection	Joint reinforcement in walls exposed to moisture or wire ties, anchors, sheet metal ties not completely embedded in mortar or grout, ASTM A165, Class B2, 1.50 oz/lb or 304SS
3.3.E.2 Pipes, conduits, and accessories	Any not shown on the project drawings require engineering approval.
3.3.E.7 Movement joints	Contractor assumes responsibility for type and location of movement joints if not detailed on project drawings.


BOTTOM OF EXTERIOR FOOTINGS SHALL BE A MINIMUM OF 12" BELOW UNDISTURBED SOIL OR ENGINEERED FILL PER FBC 2017-RES. SECTION R403.1.4




F2 S-2 INTERIOR BEARING FOOTING  
SCALE: 1/2" = 1'-0"




F3 S-2 INTERIOR BEARING STEP FOOTING  
SCALE: 1/2" = 1'-0"




F5 S-2 GARAGE DOOR POCKET FOOTING  
SCALE: 1/2" = 1'-0"



F1 S-2 STEM WALL FOOTING  
SCALE: 1/2" = 1'-0"



F4 S-2 STEM WALL CURB FOOTING  
SCALE: 1/2" = 1'-0"



FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

FOUNDATION NOTES	
FN-1	DIMENSIONS ON FOUNDATION & STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL PLANS FOR ACTUAL DIMENSIONS, RECESSES IN SLAB, STEP DOWNS, ETC. DISOSWAY DESIGN GROUP OR MARK DISOSWAY, P.E. IS NOT RESPONSIBLE FOR DIMENSION ERRORS ON THIS PLAN.
FN-2	CONTRACTOR SHALL VERIFY NEED FOR INTERIOR BEARING IN ALL AREAS BY REVIEWING THE ROOF TRUSS PLAN (BY THE SUPPLIER) BEFORE FINALIZING FOUNDATION PLAN
FN-3	THE SLAB SHALL BE 4" CONCRETE SLAB REINFORCED w/ (06x14) #4 WELDED WIRE MESH PLACED ON CHAIRS @ 1 1/2" DEPTH OR FIBER MESH CONCRETE, 6-MIL POLY VAPOR BARRIER w/ 6" LAPS SEALED w/ POLY TAPE OVER TERMITES-TREATED & COMPACTED FILL (ALSO, ANY OTHER CODE-APPROVED TERMITES-TREATMENT METHOD CAN BE USED INSTEAD)

Hometown Homes

Spec House - 204 NW Sparr Lane

PROJECT ADDRESS:  
204 NW Sparr Lane  
Lake City, FL 32055

DIMENSIONS:  
Stated dimensions supersede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:  
Mark Disosway, P.E. hereby expressly reserves its common law copyright and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without the express written permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 6th Edition Florida Building Code Residential (2017) to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.

MARK DISOSWAY P.E. 53915



Monday, Mar 6, 2019


Mark Disosway P.E.  
163 SW Midtown Place  
Suite 103  
Lake City, Florida 32025  
386.75x.5419  
disoswaydesign@gmail.com

JOB NUMBER:  
190403

S-2  
OF 5 SHEETS




NOTE:  
THIS RYTAL FRAME IS DESIGNED FOR NARROW WALL SEGMENTS w/ 6:1 ASPECT  
RATIOX SUCH AS BESIDE FRONT LOAD GARAGE DOORS




SECTION DETAIL

(TYP) PORTAL FRAME SHEARWALL  
ONE SYPY WOOD FRAME


NOTE: DO NOT  
SPLIT WOOD




OUTSIDE ELEVATION



INSIDE ELEVATION



CORNER FRAMING DETAIL




STRUCTURAL PLAN

SCALE: 1/4" = 1'-0"

STRUCTURAL PLAN NOTES

- SN-1 ALL LOAD BEARING FRAME WALL & PORCH HEADERS SHALL BE A MINIMUM OF (2) 2X10 SP #2 (U.N.O.)
- SN-2 ALL LOAD BEARING FRAME WALL HEADERS SHALL HAVE: (1) JACK STUD & (1) KING STUD EACH SIDE (U.N.O.)
- SN-3 ALL HEADERS w/ UPLIFT TO BE STRAPPED DOWN @ EACH SIDE WITH (1) LSTA24, 14-10d @ TOP & BOTTOM OF WALL WRAP UNDER BOTTOM PLATE & OVER TOP PLATE 1/2" X 10" ANCHOR BOLT w/ 3" X 3" X 1/4" WASHER MUST BE LOCATED WITHIN 6" OF KING STUD @ ALL DOOR LOCATIONS (U.N.O.)
- SN-4 USE ONE JACK STUD GIRDER SUPPORT PER 2500 LB LOAD
- SN-5 DIMENSIONS ON STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL FLOOR PLAN FOR ACTUAL DIMENSIONS
- SN-6 PERMANENT TRUSS BRACING IS TO BE INSTALLED AT LOCATIONS AS SHOWN ON THE SEALED TRUSS DRAWINGS. LATERAL BRACING IS TO BE RESTRAINED PER BCSI1-03, BCSI-B1, BCSI-B2, & BCSI-B3. BCSI-B1, BCSI-B2, & BCSI-B3 ARE FURNISHED BY THE TRUSS SUPPLIER, WITH THE SEALED TRUSS PACKAGE

HEADER LEGEND



ACTUAL vs REQUIRED SHEARWALL		
	TRANSVERSE	LONGITUDINAL
ACTUAL	11196 LBF	21050 LBF
REQUIRED	10789 LBF	5020 LBF

CONNECTIONS, WALL, & HEADER DESIGN IS BASED  
ON REACTIONS & UPLIFTS FROM TRUSS ENGINEERING  
FURNISHED BY BUILDER. BUILDERS FIRST SOURCE  
JOB #1761094

Hometown Homes

Epoco Houco 204 NW Eparr Lane

PROJECT ADDRESS:  
204 NW Eparr Lane  
Lake City, FL 32025

DIMENSIONS:  
Stated dimensions approximate scaled  
dimensions. Refer all questions to  
Mark Disosway, P.E. for resolution.  
Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:  
Mark Disosway, P.E. hereby expressly reserves  
its common law copyright and property right in  
these instruments of service. This document is  
not to be reproduced, altered or copied in any  
form or manner without the express written  
permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have  
examined this plan, and that the applicable  
portions of the plan, relating to wind engineering  
comply with the 8th Edition Florida  
Building Code Residential (2017)  
to the best of my knowledge.

LIMITATION: This design is valid for one  
building, at specified location.

MARK DISOSWAY P.E. 53915

Mark Disosway P.E.  
163 SW Miltown Place  
Suite 103  
Lake City, Florida 32025  
386.734.5419  
disoswaydesign@gmail.com

JOB NUMBER:  
190403

S-3  
OF 5 SHEETS