## GENERAL NOTES SECTIONS

7.

A. CONCRETE & FOUNDATION DESIGN:

1. ALL CONCRETE AND FOUNDATIONS ATTACHED TO
THE HOST STRUCTURE SHALL HAVE A PRE

BE 3000 PSI MINIMUM. ALL CONCRETE GRADE BEAMS AND FOOTINGS SHALL

FIBERMESH (3/4" PER CUBIC YARD MIN.) MEETING APPROPRIATE ACI AND ASTM REQUIREMENTS MAY BE ALL SLABS ON GRADE SHALL BE A MINIMUM OF 4" USED IN LIEU OF WELDED WIRE MESH ALL CONCRETE FILLED SUPPORTED SLABS SHALL BE 2500 PSI MINIMUM, 3 1/2" NOMINAL THICKNESS.

ALL REINFORCING SHALL CONFORM TO ASTM A615, BE GRADE 60 (60 KSI MIN.) DEFORMED BARS, #3 BARS ALL OVER POUR CONCRETE FILLED SUPPORTED SLABS SHALL BE 3000 PSI MIN., 2" MINIMUM. THICKNESS. MAY BE GRADE 40

THICK WITH FIBERMESH.

THE CONCRETE SHALL CONFORM TO ASTM C94 FOR THE FOLLOWING: OPC (PORTLAND CEMENT TYPE 1,- ASTM C 150). AGGREGATES - #6 STONE, ASTM C 33 SIZE NO. 67

SOIL BEARING PRESSURE SHALL BE A MINIMUM OF

AIR ENTRAINING +/- 1% - ASTM C 260. WATER REDUCING AGENT - ASTM C 494. LESS THAN 3/4".

10. METAL WELDED WIRE SHALL CONFORM TO ASTM OTHER ADMIXTURES SHALL NOT BE PERMITTED. CLEAN POTABLE WATER.

AMERICAN CONCRETE INSTITUTE MANUAL STANDARD PRACTICE, PART 1, 2, & 3 ALONG WITH HOT WEATHER CONDITIONS RECOMMENDATIONS.

12. IF UTILIZING EXISTING CONCRETE FOR FOUNDATION, CONCRETE SHALL BE A MINIMUM OF 4" IN THICKNESS, 11. PREPARE & PLACE CONCRETE ACCORDING TO VISIBLY FREE OF ANY STRUCTURAL EXCESSIVE CRACKING, SPALLING OR OTHER DETERIORATION. 8

B. MASONRY:

1. CONCRETE MASONRY UNITS (CMU) SHALL BE

STANDARD HOLLOW UNITS AND SHALL BE 2000 PSI MINIMUM BASED ON TYPE M OR S MORTAR. ALL MORTAR SHALL BE OF TYPE M OR S. ALL GROUT SHALL BE 2000 PSI MINIMUM AND HAVE 9. ALL FASTENERS SHALL COMPLY WITH ASTM A653
10. ALL CONNECTORS SHALL COMPLY WITH ASTM A653
CLASS G-185. STAINLESS STEEL TYPE 300 18-8, UNLESS OTHERWISE NOTED ON PLANS. USE WITH ACQ PRESSURE TREATED WOOD, OR

SPACING SHALL BE 3/4" AND MINIMUM CENTER-TO-EDGE SHALL BE 1/2" UNLESS NOTED

E. REFERENCE STANDARDS: (CURRENT EDITIONS OF)
ASTM E 119 ASCE 7 **ASTM E 1300** OTHER WISE.

ALUMINUM DESIGN MANUAL-AA ASM35, AND SPEC. FOR

PROVIDE CLEAN-OUTS FOR REINFORCED CELLS

MAXIMUM COARSE AGGREGATE SIZE OF 3/8".

CONTAINING REINFORCEMENT WHEN GROUT POUR

ASTM C33 ASTM C260 ASTM C494 ASTM C94 ASTM C150 ALUMINUM PART 1-A, & 1-B

STRUCTURAL ALUMINUM DESIGN CONFORMS TO "PART 1-A - SPECIFICATIONS FOR ALUMINUM STRUCTURES - ALLOWABLE STRESS DESIGN" OR

ASTM A615 ASTM A185

THE FLORIDA BUILDING CODE 8TH EDITION

'PART 1-B - SPECIFICATIONS FOR ALUMINUM

WHERE KICK PLATES ARE USED A MINIMUM

SUPPORTING MEMBERS

THICKNESS OF 0.024" SHALL APPLY.

ALL STRUCTURAL ALUMINUM SHALL CONFORM TO THE MINIMUM REQUIREMENTS OF 6005-T5 FOR ALLOY WITH A MINIMUM THICKNESS OF 0.040" FOR

C. ALUMINUM

EXCEEDS 5'-0" IN HEIGHT.

STRUCTURES - BUILDING LOAD AND RESISTANCE FACTOR DESIGN" OF THE ALUMINUM DESIGN MANUAL INC.WASHINGTON D.C. <u>THE FLORIDA BUILDING CODE</u> 8TH EDITION (CHAPTER 16 STRUCTURAL DESIGN & F. ABBREVIATIONS:
THE FOLLOWING LIST OF ABBREVIATIONS IS NOT
INTENDED TO REPRESENT ALL THOSE USED ON THESE
DRAWINGS, BUT TO SUPPLEMENT THE MORE COMMON ABBREVIATIONS. CHAPTERS 16, 20 & 23).

4. 72 CONT -- CONTINUOUS **UON -- UNLESS OTHERWISE NOTED** SIM -- SIMILAR

VIF -- VERIFY IN FIELD

DIELECTRIC SEPARATION.

ALUMINUM MEMBERS SHALL BE STITCHED WITH NO STEEL, OR PRESSURE TREATED LUMBER PROVIDE

.ESS THAN #10 SMS 6" FROM THE ENDS AND 12" ON

CENTER, IF USING #12 SPACING MAY BE 24" ON

WHERE ALUMINUM COMES INTO CONTACT WITH

CHAPTER 20 ALUMINUM)

PREPARED BY THE ALUMINUM ASSOCIATION

G. RESPONSIBILITY:

1. ALL SITE WORK SHALL BE PERFORMED BY A
LICENSED CONTRACTOR IN ACCORDANCE WITH
APPLICABLE BUILDING CODES, LOCAL ORDINANCES,

VINYL AND ACRYLIC PANELS SHALL BE REMOVABLE.

THEY SHALL BE IDENTIFIED WITH A DECA

DECAL SHALL BE PLACED SO IT IS VISIBLE WHEN PANEL IS INSTALLED. VINYL AND ACRYLIC PANELS

BE REMOVED WHEN WIND SPEEDS EXCEED 75 MPH" ESSENTIALLY STATING "REMOVABLE PANEL SHALL

MAY NOT BE USED IN FLOOD ZONE A.

w. 2 DISCREPANCIES BETWEEN DRAWINGS, FABRICATED ITEMS, OR ACTUAL FIELD CONDITIONS.
THESE DRAWINGS REPRESENT THE ACCEPTABILITY CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND DETAILS, NOTIFYING ENGINEER OF ANY

I

TUBE SECTIONS

2" X 2" X 0.090"

2 X 5 SMB:-2 X 6 SMB:-2 X 7 SMB:-2 X 8 SMB:-

2 X 4 SMB:

SELF MATING (SMB)

2" X 5" X 0.050" X 0.118" "X 6" X 0.050" X 0.120"

044" X 0.100"

2 X 9 SMB;---2 X 10 SMB;--

-2" X 10" X 0.092" X 0.374" --2" X 7" X 0.057" X 0.120" --2" X 8" X 0.072" X 0.224" --2" X 9" X 0.072" X 0.224" 2 X Z SMS:-2 X 3 SMS:-2 X 4 SMS:-3 X 3 SMS:-

--2" X 2" X 0.045" --2" X 3" X 0.072" --2" X 4" X 0.045" --3" X 3" X 0.090"

JOB NUMBER: 24\_0304\_014

DRAW DATE: 03/04/2024

REVISION 1:

REVISION 2:

**REVISION 3:** 

REVISION 4:

SNAP SECTIONS

1"X2"X0.045" NON-STRUCTURAL MEMBERS SHALL BE SCREWS IN ALUMINUM MEMBERS TYPICAL. IN WOOD & #10X 1/2" EMBEDMENT SMS OR TEK CONCRETE & EQUIVALENT SIZE WOOD SCREW WHEN EMBEDMENT & 24" O.C. MASONRY SCREW FOR ATTACHED TO HOST WITH 1/4"Ø X 1-3/4" ŗ 4.

TREATED WOOD. BOLTS SPECIFIES FOR USE WITH ACQ PRESSURE STEEL TYPE 300 18-8, WITH STANDARD FLAT WASHER UNLESS MANUFACTURER GALVANIZES ALL LAG BOLTS SHALL CONFORM TO STAINLESS

HEX BOLTS HAS TO BE ASTM A 325, PLATED WITH STANDARD FLAT WASHERS AND NUTS.
ALL CONCRETE SCREWS SHALL BE, SIMPSON, HILTI, RAWL, TAPCON, REDHEAD, DYNABOLT, PORTECT OR

APPROVED EQUAL.
ALL METAL TIES AND ASSOCIATED ACCESSORIES SHALL BE HOT DIPPED GALVANIZED.

Ş

4.

ÿ 12

6

ALL LAG BOLTS SHALL HAVE A MINIMUM EMBEDMENT OF 8X BOLT DIAMETER INTO

STRUCTURAL FRAMING (G=.42 MIN.). LAG BOLTS AND SCREWS INTO WOOD FRAMING SHALL THREAD DIAMETER OF THE BOLT OR SCREW. ALL LAG BOLTS AND SCREWS SHALL BE INSERTED IN PILOT HOLES BY TURNING AND UNDER NO CIRCUMSTANCES DIAMETER NOT GREATER THAN 70 PERCENT OF THE BE PROVIDED WITH PILOT HOLES HAVING A

BY DRIVING WITH A HAMMER.
ALL EXPANSION ANCHORS SHALL BE DESIGNED IN
ACCORDANCE WITH THE SPECIFIC MANUFACTURER'S
REQUIREMENTS AND ALLOWABLE LOADS AND SHALL ONLY BE APPLIED IN CONDITIONS ACCEPTABLE TO MANUFACTURER. FASTENERS SHALL BE A MINIMUM

w.

OF SAE GRADE #5 OR BETTER ZINC PLATED. ALL FASTENERS CONNECTING ALUMINUM COMPONENTS OR PRESSURE TREATED LUMBER ARE MANUFACTURER GALVANIZED BOLTS SPECIFIES FOR

6. SCREENING MATERIAL SHALL BE 18X14X0.013 OR EQUIVALENT DENSITY SCREEN MESH CNLY UNLESS ALL STRUCTURAL POST SHALL BE ANCHORED TO AN NOTED ON DRAWING S-2.

SHALL HAVE EPOXY ADHESIVE TO CONCRETE OR IF USING GROUT, ENSURE BONDING AGENT IS USED IF PAVERS ARE UNDER ALUMINUM MEMBERS THEY DOOR LOCATIONS MAY BE DETERMINED IN THE FIELD BY CONTRACTOR. FIRST AND ADHERED WITH MINIMUM 3000 PSI

EXISTING/PROPOSED CONCRETE FOUNDATION FOR 6. ū LIVE LOAD:

7 STRESS DESIGN:

THE UPLOADS FOR THE PROPOSED STRUCTURE SHALL BE ADEQUATE TO RESIST

ALL DETAILS ON THESE DRAWINGS ARE ENGINEERED BASED ON INFORMATION PROVIDED BY THE CONTRACTOR AND MANUFACTURER

WHEN ATTACHING TO FASCIA, THE HOST STRUCTURE ANY DETAILS NOT SHOWN ARE TO BE ENGINEERED BY A LICENSED P.E. IN ACCORDANCE WITH STANDARD

FBC PLANS & ENGINEERING SERVICES INC. DOES NOT THAN A 2'-0" OVERHANG AND IF SMALLER, CONTRACTOR SHALL BRING STRUCTURE UP TO A 2"X4" FASCIA AND ENSURE LESS TRUSS SYSTEM. CONTRACTOR SHALL VERIFY THIS FASCIA AND ROOF

QUALITY OF THE CONSTRUCTION, AND IS NOT RESPONSIBLE FOR THE INTERPRETATION OF DESIGNS WARRANT, EITHER EXPRESSLY OR IMPLIED, THE

AND END USE BY THE CLIENT/CONTRACTOR.

H. MISCELLANEOUS:

1. ALUMINUM ADDITIONS ARE NOT TO BE INSTALLED ON A MANUFACTURED HOME, TRAILER HOME, OR PRE-FAB HOME IF THE EXISTING STRUCTURE IS ONE OF THESE, A SEPARATE 4TH WALL SUPPORT SYSTEM

MUST BE ENGINEERED SO THAT NO ADDITIONAL LOADING IS PLACED ON THE MANUFACTURED HOME. IF ENCLOSURE CONTAINS A SWIMMING POOL OR SPA, THE ENCLOSURE SHALL COMPLY WITH RESIDENTIAL SWIMMING BARRIER REQUIREMENTS OF THE FLORIDA BUILDING CODE 8TH EDITION RESIDENTIAL R 4501.17 IN ITS ENTIRETY. DESIGN DATA: (SITE SPECIFIC DESIGN INFORM 1. ULTIMATE DESIGN WIND SPEED Vult, (3 SECOND GUST): SCREEN ENCLOSURE

WIND EXPOSURE: NOMINAL DESIGN WIND SPEED Vasd: RISK CATEGORY:

WIND LOADS: SCREEN ROOF:

SCREEN WALLS (WINDWARD): SCREEN WALLS (LEEWARD): SOLID ROOF:

FACTOR APPLIED TO SCREEN WIND LOADS FOR 18X14X0.013 OR EQUIVALENT DENSITY SCREEN MESH: FACTOR APPLIED TO SCREEN WIND LOADS FOR ALLOWABLE

200 Ib. VERTICAL DOWNLOAD ON SCREEN ENCLOSURE PURLINS.
10 PSF VERTICAL DOWNLOAD ON SOLID ROOF.
REEN ROOF TYPE: HIDDED CAPIT

8. SCREEN ROOF TYPE: HIPYEU GADLE
9. SOLID ROOF TYPE: N/A
10. PROPOSED FOUNDATION (SEE S-2 FOR SIZE AND LOCATION)

Building

Code

UMBIA Aeceived Complie LANS E Code O

## ALUMINUM STRUCTURAL **MEMBERS**

HOLLOW SECTIONS -2" X 4" X 0.050" -2" X 5" X 0.050" -2" X 2" X 0,044" -2" X 3" X 0,050" 3" X 3" X 0.125"

OPEN BACK SECTIONS 1" X 3" X 0.045" " X 2" X 0.040" S-3 S-5

NOTES DRAWII DRAWING DETAILS DETAILS

PROJECT DELGADO 1047 NW SCENIC LAKE DR LAKE CITY, FLORIDA, 32055 CONTRACTOR LAKESIDE ALUMINUM

FBC PLANS & ENGINEERING SERVICES, INC.

PHONE: FAX: E-MAIL: PLANS & ENGINEERING SERVICE, INC C.O.A.:


ADDRESS: 5344 9th Street Zephryhills, FL 33542 (813)838-0735 1-(866)824-7894 erb@fbcplans.com WEBSITE: www.fbcplans.com #29054


6 PSF 23 PSF 20 PSF N/A


P.E. OF RECORD DAVID W. SMITH THOMAS L. HANSON FL 3865 IAN J. FOSTER FL 93654 JOEL FALARDEAU FL 70667 **ERIK STUART** FL 77605

(ATION

130 101 1 MPH MPH









FOUNDATION DETAIL SCALE: N.T.S.

NOTES FOR ALL FOUNDATION TYPES:

1. THE FOUNDATIONS SHOWN ARE BASED ON A MINIMUM SOIL BEARING PRESSURE OF 1,500 PSF, THE BEARING CAPACITY OF THE SOIL VERIFIED BY A LICENSED CONTRACTOR PRIOR TO ANY POURING OF CONCRETE.

2. THE SLAB/FOUNDATION MUST BE CLEARED OF ALL DEBRIS, AND COMPACTED PRIOR TO POURING OF ANY CONCRETE.

3. CONCRETE MEET THE SPECIFICATIONS IN THE S-1 NOTES PAGE.

4. HEIGHT AND WIDTH ARE INTERCHANGEABLE EXCEPTION 12" WIDTH X 16" HEIGHT IS NOT APPLICABLE

5. WHEN PINNING USE A MINIMUM OF (1) 12" #5 REBAR W/ 6" EMBEDMENT @ 48" O.C. REQUIRED FOR ACCESSORY STRUCTURE TO ACCESSORY STRUCTURE TO HOST STRUCTURE CONCRETE, HOWEVER SLAB ONLY MUST BE PINNED TO HOST STRUCTURE.

LINEAL RIBBON FOOTING -"W"-

REBAR CONTINUOUS W/ 25" OVERLAP AT ALL JOINTS ON 3" CHAIRS (SEE CHART FOR REBAR SIZE & QUANTITY) 8",10",12" 8" 1 1 8",10",12" 10" 1 1 8",10",12" 12" 1 2 8",10",12" 12" 1 2 8",10",12" 16" 3 4 REBAR SIZES ARE NOT TO BE MIXED (CONTRACTOR MAY USE #5 OR #4)

H, Ψ. #5 REBAR#4 REBAR QTY. QTY. SLAB

REBAR CONTINUOUS W/ 25"
OVERLAP AT ALL JOINTS ON
3" CHAIRS (SEE CHART FOR
REBAR SIZE & QUANTITY) SLAB HEIGHT TYP. (MIN.

SEE NOTE 5

W

1" PER FT. MAX FOR 2'-0"

MIN BEFORE STEEPER
SLOPE

SEE SHEET S-2 FOR FOOTING & SLAB SIZE

FOOTING

4

SEE NOTE 5

SLAB HEIGHT TYP. (MIN. 4")-

| S-5 |       | JOB NUMBER: 24_0304_014 | PROJECT DELGADO 1047 NW SCENIC LAKE DR LAKE CITY, FLORIDA, 3205 |
|-----|-------|-------------------------|---|
|     |       | DRAW DATE: 03/04/2024   |   |
|     | DET   | REVISION 1:             |   |
|     | [AILS | REVISION 2:             | CONTRACTOR<br>LAKESIDE ALUMINUM                                 |
|     | E-man | REVISION 3:             | LAKESIDE ALOMINOM   |
|     |       | REVISION 4:             |   |

| FBC PLANS & ENGINEERING SERVICES, INC. |
|--|
| SERVICES, INC.                         |



| ADDRESS: | 5344  |
|----------|-------|
|          | Zeph  |
| PHONE:   | (813) |
| FAX:     | 1-(86 |
| E-MAIL:  | erb@  |
| WEBSITE: | www   |
| COA.     | 4200  |

| 5: | 5344 9th Street       | тном                                    |
|----|-----------------------|---|
|    | Zephryhills, FL 33542 |   |
|    | (813)838-0735         | IAN J.                                  |
|    | 1-(866)824-7894       |   |
|    | erb@fbcplans.com      | JOEL F                                  |
| :  | www.fbcplans.com      | 198000000000000000000000000000000000000 |
|    | #29054                | ERIKS                                   |
|    |                       |   |

| P.E. OF REC      | ORD      |          |
|------------------|----------|----------|
| DAVID W. SMITH   | FL 53608 | FAULE    |
| THOMAS L. HANSON | FL 38654 | STANDICE |
| IAN J. FOSTER    | FL 93654 | ENGINE   |
| JOEL FALARDEAU   | FL 70667 | TWEENT   |
| ERIK STUART      | FL 77605 |          |

