Columbia County Building Permit Application CC# 7786

Revised 9-23-(

For Office Use Only Application # 0601-27 Date Received 1-10-06 By G Permit # FAX 755-218 24044 /9

Application Approved by - Zoning Official BLK Date 1.01.06 Plans Examiner OK JTH Date 1-13-06

Flood Zone X Development Permit N/A Zoning A-3 Land Use Plan Map Category A-3 9

Comments

~~CC#~~

Applicants Name Matt Cason Phone 752 5152

Address 853 SW Sisters Welcome Rd LC FL 32025

Owners Name Russell & Joann Whitehead Phone 752-5152

911 Address 1007 SW Watson St. Ft. White FL 32038

Contractors Name Stanley Crawford Const. Phone 752-5152

Address 853 SW Sisters Welcome Rd. LC FL 32025

Fee Simple Owner Name & Address

Bonding Co. Name & Address

Architect/Engineer Name & Address

Mortgage Lenders Name & Address N/A

Circle the correct power company - FL Power & Light - (Clay Elec.) - Suwannee Valley Elec. - Progressive Energy

Property ID Number 26-55-16-03717-126 Estimated Cost of Construction 92,000

Subdivision Name Big Oaks Lot 26 Block ____ Unit ____ Phase ____

Driving Directions State Road 47 South 3 miles past Columbia City, TL on Watson St, 0.8 miles on left.

Type of Construction Single Family / Res. Number of Existing Dwellings on Property 0

Total Acreage 10 Lot Size ____ Do you need a - Culvert Permit or (Culvert Waiver) or Have an Existing Drive

Actual Distance of Structure from Property Lines - Front 549' Side 335' Side 200' Rear 145'

Total Building Height 15' 7" Number of Stories 1 Heated Floor Area 1520 Roof Pitch 6/12

Porch 184 GARAGE 484 TOTAL 2188

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Stanley Crawford
Owner Builder or Agent (Including Contractor)

STATE OF FLORIDA
COUNTY OF COLUMBIA

JANET L. CHEEK
MY COMMISSION # DD 226496
EXPIRES: June 25, 2007
Bonded thru Notary Public Underwriters

Sworn to (or affirmed) and subscribed before me
this ____ day of ____ 20____.
Personally known____ or Produced Identification____

Stanley Crawford
Contractor Signature
Contractors License Number RG-0042896
Competency Card Number 5627
NOTARY STAMP/SEAL

Janet L. Cheek
Notary Signature


WHITEHEAD RESIDENCE
145'
well
septic
65
41
200'
362'
335'
Drive
N
W
E
S
176
600'
Fenceline
Fenceline
373' to Watson St.

Columbia County Property Appraiser

J. Doyle Crews, CFA - Lake City, Florida - 386-758-1083

PARCEL: 26-5S-16-03717-126 - NO AG ACRE (009900)

AKA LOT 26 BIG OAKS UNREC: COMM NW COR SEC, RUN S 1441.02 FT FOR POB, RUN S 735.83 FT TO

Name:	WHITEHEAD RUSSELL W SR &	LandVal	$59,057.00
Site:		BldgVal	$0.00
	JOANNE M & RUSSELL W JR &	ApprVal	$59,057.00
Mail:	KIMBERLY L BENNETT	JustVal	$59,057.00
	239 SE LOXLEY GLN	Assd	$59,057.00
	LAKE CITY, FL 32024	Exmpt	$0.00
Sales Info	6/22/2005 $25,000.00 V / Q	Taxable	$59,057.00

This information, GIS Map Updated: 8/3/2005, was derived from data which was compiled by the Columbia County Property Appraiser Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data herein, it's use, or it's interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.



N

APPROXIMATE SCALE IN FEET

2000 0 2000

NATIONAL FLOOD INSURANCE PROGRAM

FIRM

FLOOD INSURANCE RATE MAP

COLUMBIA COUNTY, FLORIDA
(UNINCORPORATED AREAS)

PANEL 225 OF 290

PANEL LOCATION



COMMUNITY-PANEL NUMBER
120070 0225 B

EFFECTIVE DATE:
JANUARY 6, 1988

Federal Emergency Management Agency

Print Date: 1/13/2006 (printed at scale and type A)

Columbia County Property Appraiser

DB Last Updated: 12/8/2005

2006 Proposed Values

Parcel: 26-5S-16-03717-126

Tax Record | Property Card | Interactive GIS Map | Print

Owner & Property Info

<< Prev Search Result: 10 of 10

Owner's Name	WHITEHEAD RUSSELL W SR &
Site Address	
Mailing Address	JOANNE M & RUSSELL W JR & KIMBERLY L BENNETT 239 SE LOXLEY GLN LAKE CITY, FL 32024
Brief Legal	AKA LOT 26 BIG OAKS UNREC: COMM NW COR SEC, RUN S 1441.02 FT FOR POB, RUN S 735.83 FT TO

Use Desc. (code)	NO AG ACRE (009900)
Neighborhood	26516.01
Tax District	3
UD Codes	MKTA02
Market Area	02
Total Land Area	10.010 ACRES

Property & Assessment Values

Mkt Land Value	cnt: (2)	$59,057.00
Ag Land Value	cnt: (0)	$0.00
Building Value	cnt: (0)	$0.00
XFOB Value	cnt: (0)	$0.00
Total Appraised Value		$59,057.00

Just Value	$59,057.00
Class Value	$0.00
Assessed Value	$59,057.00
Exempt Value	$0.00
Total Taxable Value	$59,057.00

Sales History

Sale Date	Book/Page	Inst. Type	Sale Vlmp	Sale Qual	Sale RCode	Sale Price
6/22/2005	1052/743	CD	V	Q		$25,000.00

Building Characteristics

Bldg Item	Bldg Desc	Year Blt	Ext. Walls	Heated S.F.	Actual S.F.	Bldg Value
NONE						

Extra Features & Out Buildings

Code	Desc	Year Blt	Value	Units	Dims	Condition (% Good)
NONE						

Land Breakdown

Lnd Code	Desc	Units	Adjustments	Eff Rate	Lnd Value
009900	AC NON-AG (MKT)	10.010 AC	1.00/1.00/1.00/1.00	$5,700.00	$57,057.00
009945	WELL/SEPT (MKT)	1.000 UT - (.000AC)	1.00/1.00/1.00/1.00	$2,000.00	$2,000.00

Columbia County Property Appraiser DB Last Updated: 12/8/2005

<< Prev 10 of 10

Application for Onsite Sewage Disposal System Construction Permit. Part II Site Plan

Permit Application Number: 06-0003N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT



Site Plan Submitted By Paul Lloyd **Date** 12/27/05

Plan Approved ✓ **Not Approved** ____ **Date** 1-4-06

By [signature] Columbia **CPHU**

Notes: _____

This instrument was Prepared By:
STANLEY CRAWFORD CONSTRUCTION, INC.
853 S.W. Sisters Welcome Rd.
Lake City, Florida 32025

PERMIT NO._____ TAX FOLIO NO.: _____

NOTICE OF COMMENCEMENT

STATE OF FLORIDA
COUNTY OF COLUMBIA

The undersigned hereby gives notice that improvement will be made to certain real Property, and in accordance with Chapter 713, Florida Statutes, the following information Is provided in this Notice of Commencement.

1. Description of property: Big Oaks Lot 26

2. General description of improvement: Construction of Dwelling

3. Owner information:
   Name and address: Russell and JoAnne Whitehead
   239 S.E. Loxley Glen
   Lake City, FL 32024

   b. Interest in property: Fee Simple

   c. Name and address of fee simple title holder (if other Than owner): NONE

4. Contractor: Stanley Crawford Construction, Inc.
   853 S.W. Sisters Welcome Rd ,Lake City, FL 32025

5. Surety N/A
   a. Name and address:
   b. Amount of bond:

Inst:200600229 Date:01/05/2006 Time:16:23
DC,P.Dewitt Cason,Columbia County B:1070 P:8

MEMBER OF The North Central Florida Water Well

Clyatt Well Drilling, Inc.
(Established in 1971)
POST OFFICE BOX 180
WORTHINGTON SPRINGS, FLORIDA 32697

Telephone Number (386)496-2488
FAX Number (386)496-4640

K. Melaine "Red" Clyatt

June 18, 2002

Columbia County Building Department
Post Office Box 1529
Lake City, Florida 32056

To Whom It May Concern:

As required by building code regulations for Columbia County in order that a building permit can be issued, the following well information is provided with regard to the above-referenced well:

Size of Pump Motor:	1-1/2 Horse Power
Size of Pressure Tank:	220 Gallon Equivalent
Cycle Stop Valve Used:	No

Should you require any additional information, please do not hesitate to contact us.

Respectfully,

CLYATT WELL DRILLING, INC.

K. Melaine "Red" Clyatt
President

MEMBER OF
The
North Central
Florida Water
Well

Clyatt Well Drilling, Inc.
(Established in 1971)
POST OFFICE BOX 180
WORTHINGTON SPRINGS, FLORIDA 32697

Telephone Number (386)496-2488
FAX Number (386)496-4640

K. Melaine
"Red" Clyatt

PUMP AND TANK SPECIFICATIONS FOR
STANDARD 4" RESIDENTIAL WELLS

PUMPS

1 Horse Power Submersible Pump
20 Gallons Per Minute
Voltage: 240
Phase: (Single) 1

1.5 Horse Power Submersible Pump
25 Gallons Per Minute
Voltage: 240
Phase: (Single) 1

TANK

WF-255 Captive Air Tank
Capacity 81 Gallons
Equivalent 220 Gallons
Draw Down 25 Gallons

FORM 600A-2004

EnergyGauge® 4.0

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs

Residential Whole Building Performance Method A

Project Name:	WHITEHEAD	Builder:	STANLEY CRAWFORD
Address:		Permitting Office:	Columbia
City, State:	,	Permit Number:	24044
Owner:		Jurisdiction Number:	221000
Climate Zone:	North		

1. New construction or existing	New	___
2. Single family or multi-family	Single family	___
3. Number of units, if multi-family	1	___
4. Number of Bedrooms	3	___
5. Is this a worst case?	Yes	___
6. Conditioned floor area (ft²)	1520.5 ft²	___
7. Glass type [1] and area: (Label reqd. by 13-104.4.5 if not default)		
a. U-factor:	Description Area	
(or Single or Double DEFAULT) 7a.	(Dble Default) 205.0 ft²	___
b. SHGC:		
(or Clear or Tint DEFAULT) 7b.	(Clear) 205.0 ft²	___
8. Floor types		
a. Slab-On-Grade Edge Insulation	R=4.0, 217.0(p) ft	___
b. N/A		___
c. N/A		___
9. Wall types		
a. Frame, Wood, Exterior	R=13.0, 1326.0 ft²	___
b. Frame, Wood, Adjacent	R=13.0, 158.0 ft²	___
c. N/A		___
d. N/A		___
e. N/A		___
10. Ceiling types		___
a. Under Attic	R=30.0, 1520.5 ft²	___
b. Under Attic	R=19.0, 120.0 ft²	___
c. N/A		___
11. Ducts		___
a. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 228.0 ft	___
b. N/A		___

12. Cooling systems		
a. Central Unit	Cap: 30.0 kBtu/hr	___
	SEER: 13.00	___
b. N/A		___
c. N/A		___
13. Heating systems		
a. Electric Heat Pump	Cap: 31.0 kBtu/hr	___
	HSPF: 7.40	___
b. N/A		___
c. N/A		___
14. Hot water systems		
a. Electric Resistance	Cap: 40.0 gallons	___
	EF: 0.92	___
b. N/A		___
c. Conservation credits (HR-Heat recovery, Solar DHP-Dedicated heat pump)		___
15. HVAC credits (CF-Ceiling fan, CV-Cross ventilation, HF-Whole house fan, PT-Programmable Thermostat, MZ-C-Multizone cooling, MZ-H-Multizone heating)		___

Glass/Floor Area: 0.13

Total as-built points: 21219
Total base points: 24238

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: SUNCOAST INSULATORS [illegible] NW 2[illegible] Terrace Newberry, FL [illegible] (3[illegible]) 472-[illegible] Fax ([illegible]) 472-[illegible]

DATE: 12/22/08

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: ____________________

DATE: ____________________

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL: ____________________

DATE: ____________________

1 Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.

EnergyGauge® (Version: FLRCSB v4.0)

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , , PERMIT #:

BASE				AS-BUILT								
GLASS TYPES .18 X Conditioned Floor Area	X BSPM	= Points		Type/SC	Overhang Ornt	Len	Hgt	Area X	SPM X	SOF	= Points	
.18	1520.5	20.04	5484.7	Double, Clear	E	2.0	6.0	84.0	42.06	0.85	2996.4	
				Double, Clear	N	2.0	6.0	32.0	19.20	0.90	553.0	
				Double, Clear	W	2.0	6.0	89.0	38.52	0.85	2912.3	
				As-Built Total:				**205.0**			**6461.7**	
WALL TYPES	Area X	BSPM =	Points	Type			R-Value	Area X	SPM =	Points		
Adjacent	158.0	0.70	110.6	Frame, Wood, Exterior			13.0	1326.0	1.50	1989.0		
Exterior	1326.0	1.70	2254.2	Frame, Wood, Adjacent			13.0	158.0	0.60	94.8		
Base Total:	**1484.0**		**2364.8**	**As-Built Total:**				**1484.0**		**2083.8**		
DOOR TYPES	Area X	BSPM =	Points	Type				Area X	SPM =	Points		
Adjacent	18.0	2.40	43.2	Exterior Insulated				28.0	4.10	114.8		
Exterior	28.0	6.10	170.8	Adjacent Insulated				18.0	1.60	28.8		
Base Total:	**46.0**		**214.0**	**As-Built Total:**				**46.0**		**143.6**		
CEILING TYPES	Area X	BSPM =	Points	Type			R-Value	Area X	SPM X SCM =	Points		
Under Attic	1520.5	1.73	2630.5	Under Attic			30.0	1520.5	1.73 X 1.00	2630.5		
				Under Attic			19.0	120.0	2.34 X 1.00	280.8		
Base Total:	**1520.5**		**2630.5**	**As-Built Total:**				**1640.5**		**2911.3**		
FLOOR TYPES	Area X	BSPM =	Points	Type			R-Value	Area X	SPM =	Points		
Slab	217.0(p)	-37.0	-8029.0	Slab-On-Grade Edge Insulation			4.0	217.0(p	-36.70	-7963.9		
Raised	0.0	0.00	0.0									
Base Total:			**-8029.0**	**As-Built Total:**				**217.0**		**-7963.9**		
INFILTRATION	Area X	BSPM =	Points					Area X	SPM =	Points		
	1520.5	10.21	15524.3					1520.5	10.21	15524.3		

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: , , , PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum:.3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,	PERMIT #:

BASE				AS-BUILT							
WATER HEATING											
Number of Bedrooms	X	Multiplier	= Total	Tank Volume	EF	Number of Bedrooms	X Tank Ratio	X Multiplier	X Credit Multiplier	= Total	
3		2635.00	7905.0	40.0	0.92	3	1.00	2635.00	1.00	7905.0	
				As-Built Total:						***7905.0***	

CODE COMPLIANCE STATUS

BASE				AS-BUILT			
Cooling Points	+ Heating Points	+ Hot Water Points	= Total Points	Cooling Points	+ Heating Points	+ Hot Water Points	= Total Points
7760	**8573**	**7905**	**24238**	**5723**	**7591**	**7905**	**21219**

PASS

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,	PERMIT #:

BASE				AS-BUILT						
Winter Base Points:			**13664.4**	**Winter As-Built Points:**						**14174.6**
Total Winter Points	X	System Multiplier	= Heating Points	Total Component (System - Points)	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Heating Points
				(sys 1: Electric Heat Pump 31000 btuh ,EFF(7.4) Ducts:Unc(S),Unc(R),Int(AH),R6.0						
				14174.6		1.000	(1.069 x 1.169 x 0.93)	0.461	1.000	7591.2
13664.4		**0.6274**	**8573.1**	**14174.6**		**1.00**	**1.162**	**0.461**	**1.000**	**7591.2**

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , , PERMIT #:

BASE				AS-BUILT								
GLASS TYPES .18 X Conditioned Floor Area	X BWPM	= Points		Type/SC	Overhang Ornt	Len	Hgt	Area X	WPM X	WOF	= Points	
.18	1520.5	12.74	3486.8	Double, Clear	E	2.0	6.0	84.0	18.79	1.06	1674.2	
				Double, Clear	N	2.0	6.0	32.0	24.58	1.00	790.2	
				Double, Clear	W	2.0	6.0	89.0	20.73	1.04	1923.6	
				As-Built Total:				**205.0**			**4388.0**	
WALL TYPES	Area X	BWPM	= Points	Type			R-Value	Area X	WPM	=	Points	
Adjacent	158.0	3.60	568.8	Frame, Wood, Exterior			13.0	1326.0	3.40		4508.4	
Exterior	1326.0	3.70	4906.2	Frame, Wood, Adjacent			13.0	158.0	3.30		521.4	
Base Total:	**1484.0**		**5475.0**	**As-Built Total:**				**1484.0**			**5029.8**	
DOOR TYPES	Area X	BWPM	= Points	Type				Area X	WPM	=	Points	
Adjacent	18.0	11.50	207.0	Exterior Insulated				28.0	8.40		235.2	
Exterior	28.0	12.30	344.4	Adjacent Insulated				18.0	8.00		144.0	
Base Total:	**46.0**		**551.4**	**As-Built Total:**				**46.0**			**379.2**	
CEILING TYPES	Area X	BWPM	= Points	Type			R-Value	Area X	WPM X	WCM =	Points	
Under Attic	1520.5	2.05	3117.0	Under Attic			30.0	1520.5	2.05 X 1.00		3117.0	
				Under Attic			19.0	120.0	2.70 X 1.00		324.0	
Base Total:	**1520.5**		**3117.0**	**As-Built Total:**				**1640.5**			**3441.0**	
FLOOR TYPES	Area X	BWPM	= Points	Type			R-Value	Area X	WPM	=	Points	
Slab	217.0(p)	8.9	1931.3	Slab-On-Grade Edge Insulation			4.0	217.0(p	8.45		1833.6	
Raised	0.0	0.00	0.0									
Base Total:			**1931.3**	**As-Built Total:**				**217.0**			**1833.6**	
INFILTRATION	Area X	BWPM	= Points					Area X	WPM	=	Points	
	1520.5	-0.59	-897.1					1520.5	-0.59		-897.1	

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,	PERMIT #:

BASE				AS-BUILT						
Summer Base Points: 18189.3				**Summer As-Built Points:**						**19160.7**
Total Summer Points	X System Multiplier	= Cooling Points		Total Component (System - Points)	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Cooling Points	
				(sys 1: Central Unit 30000 btuh ,SEER/EFF(13.0) Ducts:Unc(S),Unc(R),Int(AH),R6.0(INS)						
18189.3	**0.4266**	**7759.6**		19161 **19160.7**	1.00 **1.00**	(1.09 x 1.147 x 0.91) **1.138**	0.263 **0.263**	1.000 **1.000**	5723.2 **5723.2**	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 85.4

The higher the score, the more efficient the home.

1.	New construction or existing	New	12.	Cooling systems	
2.	Single family or multi-family	Single family	a.	Central Unit	Cap: 30.0 kBtu/hr
3.	Number of units, if multi-family	1			SEER: 13.00
4.	Number of Bedrooms	3	b.	N/A	
5.	Is this a worst case?	Yes			
6.	Conditioned floor area (ft²)	1520.5 ft²	c.	N/A	
7.	Glass type [1] and area: (Label reqd. by 13-104.4.5 if not default)				
a.	U-factor:	Description Area	13.	Heating systems	
	(or Single or Double DEFAULT) 7a.	(Dble Default) 205.0 ft²	a.	Electric Heat Pump	Cap: 31.0 kBtu/hr
b.	SHGC:				HSPF: 7.40
	(or Clear or Tint DEFAULT) 7b.	(Clear) 205.0 ft²	b.	N/A	
8.	Floor types				
a.	Slab-On-Grade Edge Insulation	R=4.0, 217.0(p) ft	c.	N/A	
b.	N/A				
c.	N/A		14.	Hot water systems	
9.	Wall types		a.	Electric Resistance	Cap: 40.0 gallons
a.	Frame, Wood, Exterior	R=13.0, 1326.0 ft²			EF: 0.92
b.	Frame, Wood, Adjacent	R=13.0, 158.0 ft²	b.	N/A	
c.	N/A				
d.	N/A		c.	Conservation credits	
e.	N/A			(HR-Heat recovery, Solar	
10.	Ceiling types			DHP-Dedicated heat pump)	
a.	Under Attic	R=30.0, 1520.5 ft²	15.	HVAC credits	
b.	Under Attic	R=19.0, 120.0 ft²		(CF-Ceiling fan, CV-Cross ventilation,	
c.	N/A			HF-Whole house fan,	
11.	Ducts			PT-Programmable Thermostat,	
a.	Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 228.0 ft		MZ-C-Multizone cooling,	
b.	N/A			MZ-H-Multizone heating)	

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____ Date: _____

Address of New Home: _____ City/FL Zip: _____

NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStar™ designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.

1 Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.

From: The Columbia County Building Department
Plans Review
135 NE Hernando Av.
P. O Box 1529
Lake City Florida, 32056-1529

Reference to: Build permit application Number: 0601-27

Stanley Crawford Russell Whitehead 1007 SW Watson Road

On the date of January 13, 2006 application 0601-27 and plans for construction of a single family dwelling were reviewed and the following information or alteration to the plans will be required to continue processing this application. If you should have any question please contact the above address, or contact phone number (386) 758-1163 or fax any information to (386) 754-7088.

Please include application number 0601-27 when making reference to this application.

1/13/06

1. On the electrical plan show the location of the electrical panel and include the total amperage rating of the electrical service panel.

1/13/06

2. Please submit the required forms to show compliance with the FBC-2004 chapter 13energy effiency Sections 13-101.2.1 New construction: new residential construction shall comply with this code by using the following compliance methods: Subchapter 13-6, Residential buildings compliance methods. Single-family residential buildings and Multiple-family buildings of three stories or less shall comply with this chapter of the code. This subchapter contains three compliance methods:

Method A: Whole Building Performance Method

Method B: Component Prescriptive Method

Method C: Limited Applications Prescriptive Method

Thank you,

Joe Haltiwanger
Plan Examiner
Columbia County Building Department

COLUMBIA COUNTY BUILDING DEPARTMENT

RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR FLORIDA BUILDING CODE 2001 ONE (1) AND TWO (2) FAMILY DWELLINGS

ALL REQUIREMENTS ARE SUBJECT TO CHANGE
EFFECTIVE MARCH 1, 2002

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 1606 OF THE FLORIDA BUILDING CODE 2001 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1606 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE -------- 100 MPH
2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE --------110 MPH
3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERAL REQUIREMENTS: Two (2) complete sets of plans containing the following:

Applicant	Plans Examiner	
☑	☐	All drawings must be clear, concise and drawn to scale ("Optional " details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.
☑	☐	Designers name and signature on document (FBC 104.2.1). If licensed architect or engineer, official seal shall be affixed.
☑	☑	**Site Plan including:** a) Dimensions of lot b) Dimensions of building set backs c) Location of all other buildings on lot, well and septic tank if applicable, and all utility easements. d) Provide a full legal description of property.
☑	☐	**Wind-load Engineering Summary, calculations and any details required** a) Plans or specifications must state compliance with FBC Section 1606 b) The following information must be shown as per section 1606.1.7 FBC a. Basic wind speed (MPH) b. Wind importance factor (I) and building category c. Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated d. The applicable internal pressure coefficient e. Components and Cladding. The design wind pressure in terms of psf (kN/m²), to t used for the design of exterior component and cladding materials not specifically designed by the registered design professional
☑	☑	**Elevations including:**
☑	☑	a) All sides
☑	☐	b) Roof pitch
☑	☑	c) Overhang dimensions and detail with attic ventilation
☑	☑	d) Location, size and height above roof of chimneys
☑	☑	e) Location and size of skylights
☑	☐	f) Building height
☑	☐	e) Number of stories

Floor Plan including:

- a) Rooms labeled and dimensioned
- b) Shear walls
- c) Windows and doors (including garage doors) showing size, mfg., approval listing and attachment specs. (FBC 1707) and safety glazing where needed (egress windows in bedrooms to be shown)
- d) Fireplaces (gas appliance) (vented or non-vented) or wood burning with hearth
- e) Stairs with dimensions (width, tread and riser) and details of guardrails and handrails
- f) Must show and identify accessibility requirements (accessible bathroom)

Foundation Plan including:

- a) Location of all load-bearing wall with required footings indicated as standard Or monolithic and dimensions and reinforcing
- b) All posts and/or column footing including size and reinforcing
- c) Any special support required by soil analysis such as piling
- d) Location of any vertical steel

Roof System:

- a) Truss package including:
  1. Truss layout and truss details signed and sealed by Fl. Pro. Eng.
  2. Roof assembly (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
- b) Conventional Framing Layout including:
  1. Rafter size, species and spacing
  2. Attachment to wall and uplift
  3. Ridge beam sized and valley framing and support details
  4. Roof assembly (FBC 104.2.1 Roofing systems, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)

Wall Sections including:

- a) Masonry wall
  1. All materials making up wall
  2. Block size and mortar type with size and spacing of reinforcement
  3. Lintel, tie-beam sizes and reinforcement
  4. Gable ends with rake beams showing reinforcement or gable truss and wall bracir details
  5. All required connectors with uplift rating and required number and size of fastener for continuous tie from roof to foundation
  6. Roof assembly shown here or on roof system detail (FBC 104.2.1 Roofing system materials, manufacturer, fastening requirements and product evaluation with resistance rating)
  7. Fire resistant construction (if required)
  8. Fireproofing requirements
  9. Shoe type of termite treatment (termicide or alternative method)
  10. Slab on grade
      a. Vapor retardant (6mil. Polyethylene with joints lapped 6 inches and sealed)
      b. Must show control joints, synthetic fiber reinforcement or Welded fire fabric reinforcement and supports
  11. Indicate where pressure treated wood will be placed
  12. Provide insulation R value for the following:
      a. Attic space
      b. Exterior wall cavity
      c. Crawl space (if applicable)

☑ ☑ **b) Wood frame wall**

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termicide or alternative method)
11. Slab on grade
    a. Vapor retardant (6Mil. Polyethylene with joints lapped 6 inches and sealed
    b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
    a. Attic space
    b. Exterior wall cavity
    c. Crawl space (if applicable)

☐ ☐ c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)

Floor Framing System:

☐ ☐ a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer

☐ ☐ b) Floor joist size and spacing

☐ ☐ c) Girder size and spacing

☐ ☐ d) Attachment of joist to girder

☐ ☐ e) Wind load requirements where applicable

☑ ☐ **Plumbing Fixture layout**

Electrical layout including:

☑ ☐ a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified

☑ ☐ b) Ceiling fans

☑ ☐ c) Smoke detectors

☑ ☐ d) Service panel and sub-panel size and location(s)

☑ ☐ e) Meter location with type of service entrance (overhead or underground)

☑ ☐ f) Appliances and HVAC equipment

☑ ☐ g) Arc Fault Circuits (AFCI) in bedrooms

HVAC Information

☑ ☐ a) Manual J sizing equipment or equivalent computation

☑ ☐ b) Exhaust fans in bathroom

☑ ☐ **Energy Calculations** (dimensions shall match plans)

☑ ☐ **Gas System** Type (LP or Natural) Location and BTU demand of equipment

☑ ☐ **Disclosure Statement for Owner Builders**

☑ ☐ ***Notice Of Commencement Required Before Any Inspections Will Be Done

☑ ☑ **Private Potable Water**

a) Size of pump motor

b) Size of pressure tank

c) Cycle stop valve if used

RIGHT-J LOAD AND EQUIPMENT SUMMARY
Entire House

Touchstone Heating and Air, Inc.
490 SE 3rd Ave , Lake Butler, FL 32054 Phone: 386-496-3467 Fax: 386-496-3147

Job: Whitehead Residence
12/21/05

Project Information

For: Stanley Crawford Construction
853 SW Sisters Welcome Road, Lake City, FL 32025
Phone: 386-752-5152 Fax: 386-755-2165

Notes:

Design Information

Weather: Gainesville, FL , US

Winter Design Conditions

Outside db	33	°F
Inside db	70	°F
Design TD	37	°F

Summer Design Conditions

Outside db	92	°F
Inside db	75	°F
Design TD	17	°F
Daily range	M	
Relative humidity	50	%
Moisture difference	52	gr/lb

Heating Summary

Building heat loss	39661	Btuh
Ventilation air	7	cfm
Ventilation air loss	276	Btuh
Design heat load	39937	Btuh

Infiltration

Method	Simplified
Construction quality	Average
Fireplaces	0

	Heating	Cooling
Area (ft²)	***1521***	***1521***
Volume (ft³)	***12929***	***12929***
Air changes/hour	***0.10***	***0.30***
Equiv. AVF (cfm)	22	65

Sensible Cooling Equipment Load Sizing

Structure	21331	Btuh
Ventilation	935	Btuh
Design temperature swing	3.0	°F
Use mfg. data	n	
Rate/swing multiplier	0.97	
Total sens. equip. load	21698	Btuh

Latent Cooling Equipment Load Sizing

Internal gains	230	Btuh
Ventilation	1753	Btuh
Infiltration	2266	Btuh
Total latent equip. load	4249	Btuh
Total equipment load	25847	Btuh
Req. total capacity at 0.70% SHR	2.6	ton

Heating Equipment Summary

Make Trane
Trade E. XE 1200 Weathertron
TWP030D

Efficiency	8.5 HSPF	
Heating input		
Heating output	28400	Btuh @ 47°F
Heating temp rise	25	°F
Actual heating fan	1025	cfm
Heating air flow factor	0.026	cfm/Btuh

Space thermostat

Cooling Equipment Summary

Make Trane
Trade E. XE 1200 Weathertron
TWP030D
TWE031E13

Efficiency	13.0 SEER	
Sensible cooling	21000	Btuh
Latent cooling	9000	Btuh
Total cooling	30000	Btuh
Actual cooling fan	1025	cfm
Cooling air flow factor	0.048	cfm/Btuh
Load sensible heat ratio	64	%

Bold/Italic values have been manually overridden

Printout certified by ACCA to meet all requirements of Manual J 7th Ed.

CERTIFIED TESTING LABORATORIES

Architectural Division • 7252 Narcoossee Rd. • Orlando, Fl. 32822
(407) 384-7744 • Fax (407) 384-7751
Web Site: www.ctlarch.com
E-mail: ctlarch.com



Report Number: CTLA-991W-1-AWT
Report Date: February 18, 2003

STRUCTURAL PERFORMANCE TEST REPORT

Client: ACTION WINDOOR TECHNOLOGY INC
1312 W. CROSBY ROAD
CARROLLTON, TX 75006

Product Type and Series: **AWT Series 3950 Vinyl Fin Frame Single Hung Window with Reinforced Sash Top Rail, Stiles & Meeting Rail H-R40 (36"x 72")**

Test Specifications: AAMA/NWWDA 101/I.S.2-97 "Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors"

Frame: Vinyl Fin frame measured 35.50" wide x 71.50" high overall. Mitered corner weld construction. Fixed meeting rail secured to each frame jamb with one (1) #8 x 2" PH., PH. screw.

Ventilator: Operable sash measured 33.375" wide x 35.25" high overall. Mitered corner weld construction. Clear lite measured 31.5625" high x 33.5625" high. Fixed lite measured 32.50" wide x 33.4375"high.

Weather Stripping: One (1) strip of woolpile .220" high with integral plastic fin frame sill. One (1) strip of woolpile .250" high with integral plastic fin sash top rail exterior. One (1) strip of woolpile .250" high each sash stile exterior leg. One (1) strip of woolpile .250" high with integral plastic fin each sash stile interior leg. One (1) strip of foam filled bulb weatherstrip sash bottom rail.

Hardware & Location: Two (2) metallic sweep locks located on sash top rail approx 8" from each end of rail. Two (2) metallic keepers located on fixed meeting rail. One (1) tilt latch at each end of sash top rail. One (1) block and tackle at each frame jamb. One (1) pivot bar at each end of sash bottom rail.

Glazing: 5/8" insulated annealed glass consisting of .125" glass .375" air space with swiggle .125" glass. Sash exterior glazed. Fixed lite interior glazed adhesive foam strip backbedding and vinyl snap in glazing bead.

Sealant: A silicone type sealant was used on sill and to seal specimen to test buck.

Weep System: Weep notch measuring 2.25" x leg height located each end of sill weeping to the exterior
Muntins: N/A
Reinforcement: Fixed meeting rail has one (1) piece of extruded aluminum reinforcement measuring .662" wide x .755" high x .099" thick x full length. Top rail, and sash stiles has one (1) piece of extruded aluminum reinforcement measuring .590" wide x .995" high x .115" thick x full length.

Additional Description: N/A

Screen: Roll formed aluminum frame, fiberglass mesh with vinyl spline. Two (2) metallic retainer clips and two (2) metallic plungers. Corners secured with plastic corner keys

Installation: Twenty-six (26) 1.75" roofing nails were used to secure the specimen to the wood test buck. Five (5) were located in head and sill measuring 4", 13", 21", 29", and 33" from left jamb. Eight (8) were located in each jamb measuring 4.50", 14.25", 24", 32.75", 42", 57.25", 60.50" and 70" from sill.

Surface Finish: White Vinyl

Comment: Nominal 2 mil polyethylene film was used to seal against air leakage during structural loads. The film was used in a manner that did not influence the test results

Performance Test Results

Paragraph No	Title of Test	Method	Measured	Allowed
2.1.2	Air Infiltration @1.57 psf	ASTM E283-91	.18 cfm/ft²	.34 cfm/ft²
	The tested specimen meets or exceeds the performance levels specified in AAMA/NWWDA 101/I.S.2-97. Results recorded in two (2) decimals at the clients request. Unit tested with shims installed under cam locks.			
2.1.3	Water Resistance @ 5.0 gph/ft²	ASTM E547-93 Four (4) five (5) minute cycles	No Entry	No Entry
	WTP= 6.75 psf	ASTM E331-93 Fifteen (15) minute duration	No Entry	No Entry
	Unit tested with insect screen.			
2.1.3	Water Resistance @ 5.0 gph/ft²	ASTM E547-93 Four (4) five (5) minute cycles	No Entry	No Entry
	WTP= 6 psf	ASTM E331-93 Fifteen (15) minute duration	No Entry	No Entry
	Unit tested without insect screen.			
2.1.4.2	Uniform Load Structural Permanent Deformation	ASTM E330-90 Ten (10) second load		
	@ 60 psf positive		.015"	134"
	@ 60 psf negative		.005"	.134"
2.1.8	Forced Entry Resistance	AAMA 1302.5-76		
	Test A		0"	½"
	Test B		0"	½"
	Test C		0"	½"
	Test D, E and F		0"	½"
	Test G		0"	½"

Performance Test Results (continued)

Paragraph No	Title of Test		Method	Measured	Allowed
2.2.2.5.1	Operating Force Sash		AAMA/NWWDA 101/I.S.2-97	18 lbs.	30 lbs.
2.2.2.5.2	Deglazing		ASTM E987-88		
	Top Rail	70 lbs		.039" = 7.8%<100%	
	Bottom Rail	70 lbs.		.038" = 7.6%<100%	
	Left Side	50 lbs.		.050" = 10%<100%	
	Right Side	50 lbs.		.035" = 7.0%<100%	
2.1.7	Welded Corner Test		AAMA/NWWDA 101/ IS2-97	Passed	

Test Date November 21, 2002

Test Completion Date: November 21, 2002

Remarks: Detailed drawings were available for laboratory records and comparison to the test specimen at the time of this report. A copy of this report along with representative sections of the test specimen will be retained by CTL for a period of four (4) years. The results obtained apply only to the specimen tested.

This test report does not constitute certification of this product, but only that the above test results were obtained using the designated test methods and they indicate compliance with the performance requirements (paragraphs as listed) of the above referenced specifications.

Certified Testing Laboratories assumes that all information provided by the client is accurate and that the physical and chemical properties of the components are as stated by the manufacturer.

Certified Testing Laboratories, Inc

James W. Blakely
Vice President
Architectural Division

cc: Action Windoor Technology Inc. (3)
File (1)

Report Number: ETC-04-034-14644.0
Test Start Date: 04/10/03
Test Finish Date: 03/16/04
Report Date: 03/18/04
Expiration Date: 03/18/08

Fenestration Structural Test Report

Rendered To:

Vinyl Building Products, Inc.
One Raritan Road
Oakland, NJ 07436

Series/Model

2900 Horizontal Slider (OX)

Description: The product tested was a vinyl Horizontal Sliding window. The test specimen was glazed with 5/8-inch thick insulating glass units constructed with double strength annealed glass. The frame size was 69 inches wide by 48 inches high by 2-3/4 inches deep. See Appendix A.

Test Specification: ANSI/AAMA/NWWDA 101/I.S.2

Summary of Results

Overall Design Pressure	35.0 psf
Air Leakage Rate	0.18 scfm/ft^2
Maximum Water Pressure Achieved	5.25 psf
Maximum Structural Pressure Achieved	60.0 psf
Forced Entry Resistance – (ASTM)	Grade 10
Product Designation	**H–R35 69 x 48**

TEST REPORT

ETC Laboratories

Specifications: The test specimen was evaluated in accordance with ANSI/AAMA/NWWDA 101/I.S.2 "Voluntary Specification for Aluminum, Vinyl and Wood Windows and Glass Doors". Sections 1, 2 and 4 only. All performance specifications in this standard shall be met for full compliance to the standard and for product certification, labeling or represented as conforming to this standard.

Referenced Test Reports: NONE
Note – The test data in any section below with an "RTR" comment have not been obtained from this specimen but from the Referenced Test Report with a specimen of the same or larger size and identical construction.

Design Pressure (DP): The product tested herein has been first evaluated to the Gateway pressure in the referenced specification for the performance class rating achieved.

Gateway Performance Tests

Specification Paragraph	Title of Test	Results	Allowed
2.1.2	*Air Infiltration – ASTM E283*		
	Test Pressure - 1.57 psf	0.18 scfm/ft^2	0.30 scfm/ft^2
	The tested specimen exceeds the performance levels specified in ANSI/AAMA/NWWDA 101/I.S.2 for air infiltration.		
2.1.3	*Water Resistance -- ASTM E547*		
	5 gal/hr-ft^2 – 4 Test cycles – 24 Minutes		
	Design Pressure - 15.0 psf		
	Test Pressure – 2.86 psf		
	With and Without Screen	Pass	No Leakage
2.1.4.2	*Uniform Structural Load - ASTM E330*		
	Design Pressure - 15.0 psf		
	Test Pressure		
	Positive Load – 22.5 psf (150% x DP)	0.033 in.	0.177 in.
	Negative Load – 22.5 psf (150% x DP)	0.020 in.	0.177 in.
	Note: Measurement taken after load from center of the meeting stile		
2.1.7	*Corner Weld*		
	Frame – 4 Corners	Pass	< 100%
	Sashes – 4 Corners	Pass	< 100%
2.1.8	*Forced Entry Resistance - ASTM F588*		
	Lock/Tool Manipulation	Pass	No Entry
	Tests A1 through A7	Pass	No Entry
	Lock/Tool Manipulation	Pass	No Entry
2.2.1.6.1	*Operating Force -- No Standardized Method*		
	Right Sash -- Open/Close	18/18 lbf	20 lbf
2.2.1.6.2	*Deglazing – ASTM E987*		
	Right Sash: Left Stile - 70 lbf	0.0%	<100%
	Right Stile - 70 lbf	0.0%	<100%
	Top Rail - 50 lbf	0.0%	<100%
	Bottom Rail - 50 lbf	0.0%	<100%

TEST REPORT

ETC Laboratories

Optional Performance Tests

The manufacturer specified herein has successfully achieved all the required criteria in Section 2 of the referenced specification for the Gateway size of the achieved Performance Rating and has further successfully tested the product to higher performance levels as indicated below.

Design Pressure (DP): The product tested herein has been additionally evaluated to the Design Pressure referenced below.

Specification Paragraph	Title of Test	Results	Allowed
4.3	*Water Resistance - ASTM E547* 5 gal/hr-ft^2 – 4 Test cycles – 24 Minutes Design Pressure - 35.0 psf Test Pressure – 5.25 psf (15% x DP) With and Without Screen	Pass	No Leakage
4.4	*Uniform Structural Load - ASTM E330* Design Pressure - 40.0 psf Test Pressure Positive Load – 60.0 psf (150% x DP) Negative Load – 60.0 psf (150% x DP) Note: Measurement taken after load from center of meeting stile	 0.069 in. 0.066 in.	 0.177 in. 0.177 in.

TEST REPORT

ETC Laboratories

Conditions, Terms, and General Notes Regarding These Tests

The product tested **Has Been** compared to the detailed drawings, bill of materials and fabrication information supplied by the client so named herein. Our analysis, which includes dimensional and component description comparisons, indicate the tested product and engineering information supplied by the client **"Are Equivalent"**. **See Appendix A.** The report and representative samples will be retained for four years from the date of initial test.

These test results were obtained by employing all requirements of the designated test methods with no deviations. The test results and specimen supplied for testing are in compliance with the referenced specifications.

The test results are specific to the product tested by this laboratory and of the sample supplied by the client named herein, and they relate to no other product either manufactured by the client, a Fabricator of the client or of installed field performance.

This report does not constitute an AAMA or NWWDA certified product under the certification programs of these organizations. The program administrator of these programs and organizations may only grant product certification.

ETC Laboratories makes no opinions or endorsements regarding this product and its performance. This report may not be reproduced or quoted in partial form without the expressed written approval of ETC Laboratories.

No conclusions of any kind regarding the adequacy of the glass in the test specimen may be drawn from the test. Procedure "A" in ASTM E330 was used for this test.

ETC Laboratories letters, reports, its name or insignia or mark are for the exclusive use of the client so named herein and any other use is strictly prohibited. The report, letters and the name of ETC Laboratories, its seal or mark shall not be used in any circumstance to the general public or in any advertising.

Limitation of Liability: Due diligence was used in rendering this professional opinion. By acceptance of this report, this client agrees to hold harmless and indemnify ETC Laboratories, its employees and offices and owners against all claims and demands of any kind whatsoever, which arise out of or in any manner connected with the performance of work referred to herein.

FOR ETC LABORATORIES

Mark Sennett
AWS Supervisor

Arthur Murray, VP
Manager, Wind Engineering Laboratory

TEST REPORT

ETC Laboratories

ELK
Premium Roofing

March 6, 2002

Subject: Elk Product Approval Information

All Prestique® and Capstone® products manufactured in Tuscaloosa, AL are certified under the Miami – Dade County Building Code Office (BCCO). These products also meet the requirements for the Florida Building Code since they are MD approved. The following test protocols must be passed by each of the products in order for MD product certification:
ASTM D3462
PA 100 (110 mph uplift and wind driven rain resistance)
PA 107 (Modified ASTM D3161 - 110 mph wind uplift resistance)

The nailing patterns that were used during the PA 100 and PA 107 wind test protocols for the Prestique and Capstone products are listed below. Also listed below are the Miami – Dade Notice of Acceptance Numbers (NOA).

Raised Profile, Prestique High Definition, Prestique 25, or Prestique 30 –
PA 100 = 4 nails
PA 107 = 5 nails
MD NOA# = 01-1226.04

Prestique I 35 or Prestique I* –
PA 100 = 4 nails
PA 107 = 5 nails
MD NOA# = 01-1226.05

Prestique Plus or Prestique Gallery Collection* –
PA 100 = 4 nails
PA 107 = 4 nails
MD NOA# = 01-1226.03

Capstone*
PA 100 = 4 Nails
PA 107 = 4 Nails
MD NOA# = 01-0523.01
* As per the Elk Limited Warranty, six nails are required for the Elk high wind warranty.

If there are any questions please contact:

Mike Reed – Technical Manager
(205) 342-0287

or

Daniel DeJarnette – QA Engineer
(205) 342-0298

ROOFING PRODUCTS SPECIFICATIONS – TUSCALOOSA, AL

PRESTIQUE® HIGH DEFINITION®

High Definition

Product size	13¼"x 39⅜"
Exposure	5⅛"
Pieces/Bundle	16
Bundles/Square	4/98.5 sq.ft.
Squares/Pallet	11

50-year limited warranty period: non-prorated coverage for shingles and application labor for the initial 5 years, plus an option for transferability*; prorated coverage for application labor and shingles for balance of limited warranty period; 5-year limited wind warranty*.

High Definition

Product size	13¼"x 39⅜"
Exposure	5⅛"
Pieces/Bundle	16
Bundles/Square	4/98.5 sq.ft.
Squares/Pallet	14

40-year limited warranty period: non-prorated coverage for shingles and application labor for the initial 5 years, plus an option for transferability*; prorated coverage for application labor and shingles for balance of limited warranty period; 5-year limited wind warranty*.

High Definition

Product size	13¼"x 38¾"
Exposure	5⅛"
Pieces/Bundle	22
Bundles/Square	3/100 sq.ft.
Squares/Pallet	16

30-year limited warranty period: non-prorated coverage for shingles and application labor for the initial 5 years, plus an option for transferability*; prorated coverage for application labor and shingles for balance of limited warranty period; 5-year limited wind warranty*.

RAISED PROFILE™

Product size	13¼"x 38¾"
Exposure	5⅛"
Pieces/Bundle	22
Bundles/Square	3/100 sq.ft.
Squares/Pallet	16

30-year limited warranty period: non-prorated coverage for shingles and application labor for the initial 5 years, plus an option for transferability*; prorated coverage for application labor and shingles for balance of limited warranty period; 5-year limited wind warranty*.

HIP AND RIDGE SHINGLES

Size: 12"x 12"
Exposure: 6⅛"
Pieces/Bundle: 45
Coverage: 4 Bundles = 100 linear feet

52 Bundles/Pallet
18 Pallets/Truck
936 Bundles/Truck
19 Pieces/Bundle
1 Bundle = 120.33 linear feet

Available Colors: Antique Slate, Weatheredwood, Shakewood, Sablewood, Hickory, Barkwood**, Forest Green, Wedgewood**, Birchwood**, Sandalwood. Gallery Collection: Balsam Forest**, Weathered Sage**, Sienna Sunset**.

All Prestique, Raised Profile and Seal-A-Ridge roofing products contain Elk WindGuard® sealant. WindGuard activates with the sun's heat, bonding shingles into a wind and weather resistant cover that resists blow-offs and leaks.

Check for availability with built-in StainGuard® treatment to inhibit the discoloration of roofing granules caused by the growth of certain types of algae. Not available in Sablewood.

All Prestique and Raised Profile shingles meet UL® Wind Resistant (UL 997) and Class "A" Fire Ratings (UL 790); and ASTM Specifications D 3018, Type-I; D 3161, Type-I; E 108 and the requirements of ASTM D 3462.

All Prestique and Raised Profile shingles meet the latest Metro Dade building code requirements.

***See actual limited warranty for conditions and limitations.**
****Check for product availability.**

SCOPE: Work includes furnishing all labor, materials and equipment necessary to complete installation of (name) shingles specified herein. Color shall be (name of color). Hip and ridge type to be Elk Seal-A-Ridge with formula *FLX*.

All exposed metal surfaces (flashing, vents, etc.) to be painted with matching Elk roof accessory paint.

PREPARATION OF ROOF DECK: Roof deck to be dry, well-seasoned 1" x 6" (25.4mm x 152.4mm) boards; exterior-grade plywood (exposure 1 rated sheathing) at least 3/8" (9.525mm) thick conforming to the specifications of the American Plywood Association; 7/16" (11.074mm) oriented strandboard; or chipboard. Most fire retardant plywood decks are NOT approved substrates for Elk shingles. Consult Elk Field Service for application specifications over other decks and other slopes.

MATERIALS: Underlayment for standard roof slopes, 4" per foot (101.6/304.8mm) or greater: apply non-perforated No. 15 or 30 asphalt-saturated felt underlayment. For low slopes [4" per foot (101.6/304.8mm) to a minimum of 2" per foot (50.8/304.8mm)], use two plies of underlayment overlapped a minimum of 19". Fasteners shall be of sufficient length and holding power for securing material as required by the application instructions printed on shingle wrapper.

For areas where algae is a problem, shingles shall be (name) with StainGuard treatment, as manufactured by the Elk Tuscaloosa plant. Hip and ridge type to be Seal-A-Ridge with formula *FLX* with StainGuard treatment.

Complete application instructions are published by Elk and printed on the back of every shingle bundle. All warranties are contingent upon the correct installation as shown on the instructions. These instructions are the minimum required to meet Elk application requirements. In some areas, building codes may require additional application techniques or methods beyond our instructions. In these cases, the local code must be followed. Under no circumstances will Elk accept application requirements less than those contained in its application instructions.

For specifications in CSI format, call 800.354.SPEC (7732) or e-mail specinfo@elkcorp.com.

SOUTHEAST & ATLANTIC OFFICE:
800.945.5551

CORPORATE HEADQUARTERS:
800.354.7732

PLANT LOCATION:
800.945.5545

ELK
www.elkcorp.com

DIRECTIONS FOR APPLICATION

Please read carefully. Failure to follow these instructions may void the product warranty.
See specific application instructions for Prestique® Plus and Prestique Gallery Collection™ 110 MPH and Prestique I 90 MPH limited wind warranty requirements.



❺ **VALLEY CONSTRUCTION OPTION** (California Open and California Closed are also acceptable) NOTE: For complete ARMA valley installation details, see ARMA Residential Asphalt Roofing Manual.







DIRECTIONS FOR APPLICATION

These application instructions are the minimum required to meet Elk's application requirements. Your failure to follow these instructions may void the product warranty. In some areas, the building codes may require additional application techniques or methods beyond our instructions. In these cases, the local code must be followed. Under no circumstances will Elk accept application requirements that are less than those printed here. Shingles should not be jammed tightly together. All attics should be properly ventilated. Note: It is not necessary to remove tape on back of shingle.

❶ DECK PREPARATION

Roof decks should be dry, well-seasoned 1" x 6" boards or exterior grade plywood minimum 3/8" thick and conform to the specifications of the American Plywood Association or 7/16" oriented strandboard, or 7/16" chipboard.

❷ UNDERLAYMENT

Apply underlayment (Non-Perforated No. 15 or 30 asphalt saturated felt). Cover drip edge at eaves only.

For low slope (2/12 up to 4/12), completely cover the deck with two plies of underlayment overlapping a minimum of 19". Begin by fastening a 19" wide strip of underlayment placed along the eaves. Place a full 36" wide sheet over the starter, horizontally placed along the eaves and completely overlapping the starter strip.

EAVE FLASHING FOR ICE DAMS (ASK A ROOFING CONTRACTOR, REFER TO ARMA MANUAL OR CHECK LOCAL CODES)

For standard slope (4/12 to less than 21/12), use coated roll roofing of no less than 50 pounds over the felt underlayment extending from the eave edge to a point at least 24" beyond the inside wall of the living space below or one layer of a self-adhered eave and flashing membrane.

For low slope (2/12 up to 4/12), use a continuous layer of asphalt plastic cement between the two plies of underlayment from the eave edge up roof to a point at least 24" beyond the inside wall of the living space below or one layer of a self-adhered eave and flashing membrane.

Consult the Elk Field Service Department for application specifications over other decks and other slopes.

❸ STARTER SHINGLE COURSE

USE AN ELK STARTER STRIP OR A STRIP SHINGLE INVERTED WITH THE HEADLAP APPLIED AT THE EAVE EDGE. With at least 4" trimmed from the end of the first shingle, start at the rake edge overhanging the eave 1/2" to 3/4". Fasten 2" from the lower edge and 1" from each side. Shingles may be applied with a course alignment of 45° on the roof.

❶ FIRST COURSE

Start at rake and continue course with full shingles laid flush with the starter course.

❷ SECOND COURSE

Start at the rake with the shingle having 10" trimmed off and continue across roof with full shingles.

❸ THIRD COURSE

Start at the rake with the shingle having 20" trimmed off and continue across roof with full shingles.

❹ FOURTH COURSE

Start at the rake and continue with full shingles across roof.

FIFTH AND SUCCEEDING COURSES.

Repeat application as shown for second, third, and fourth courses. Do not rack shingles straight up the roof

❺ VALLEY CONSTRUCTION

Open, woven and closed cut valleys are acceptable when applied by Asphalt Roofing Manufacturing Association (ARMA) recommended procedures. For metal valleys, use 36" wide vertical underlayment prior to applying 18" metal flashing (secure edge with nails). No nails are to be within 6" of valley center.

❻ RIDGE CONSTRUCTION

For ridge construction use Class "A" Seal-A-Ridge® with formula *FLX™* (See ridge package for installation instructions.)

FASTENERS

While nailing is the preferred method for Elk shingles, Elk will accept fastening methods according to the following instructions.

Always nail or staple through the fastener line or on products without fastener lines, nail or staple between and in line with sealant dots.

NAILS: Corrosive resistant, 3/8" head, minimum 12-gauge roofing nails. Elk recommends 1-1/4" for new roofs and 1-1/2" for roof-overs. In cases where you are applying shingles to a roof that has an exposed overhang, for new roofs only, 3/4" ring shank nails are allowed to be used from the eave's edge to a point up the roof that is past the outside wall line. 1" ring shank nails allowed for re-roof.

STAPLES: Corrosive resistant, 16-gauge minimum, crown width minimum of 15/16". Note: An improperly adjusted staple gun can result in raised staples that can cause a fish-mouthed appearance and can prevent sealing.

Fasteners should be long enough to obtain 3/4" deck penetration or penetration through deck, whichever is less.

MANSARD APPLICATIONS

Correct fastening is critical to the performance of the roof. For slopes exceeding 60° (or 21/12) use six fasteners per shingle. Locate fasteners in the fastener area 1" from each side edge with the remaining four fasteners equally spaced along the length of the double thickness (laminated) area. Only fastening methods according to the above instructions are acceptable.

LIMITED WIND WARRANTY

- For a Limited Wind Warranty, all Prestique and Raised Profile™ shingles must be applied with 4 properly placed fasteners, or in the case of mansard applications, 6 properly placed fasteners per shingle.
- For a Limited Wind Warranty up to 110 MPH for Prestique Gallery Collection or Prestique Plus or 90 MPH for Prestique I, shingles must be applied with 6 properly placed NAILS per shingle. SHINGLES APPLIED WITH STAPLES WILL NOT QUALIFY FOR THIS ENHANCED LIMITED WIND WARRANTY. Also, Elk Starter Strip shingles must be applied at the eaves and rake edges to qualify Prestique Plus, Prestique Gallery Collection and Prestique I shingles for this enhanced Limited Wind Warranty. Under no circumstances should the Elk Shingles or the Elk Starter Strip overhang the eaves or rake edge more than 3/4 of an inch.



HELP STOP BLOW-OFFS AND CALL-BACKS

A minimum of four fasteners must be driven into the DOUBLE THICKNESS (laminated) area of the shingle. Nails or staples must be placed along – and through – the "fastener line" or on products without fastener lines, nail or staple between and in line with sealant dots. CAUTION: Do not use fastener line for shingle alignment.



Refer to local codes which in some areas may require specific application techniques beyond those Elk has specified.
All Prestique and Raised Profile shingles have a U.L.® Wind Resistance Rating when applied in accordance with these instructions using nails or staples on re-roofs as well as new construction.

CAUTION TO WHOLESALER: Careless and improper storage or handling can harm fiberglass shingles. Keep these shingles completely covered, dry, reasonably cool, and protected from the weather. Do not store near various sources of heat. Do not store in direct sunlight until applied. DO NOT DOUBLE STACK. Systematically rotate all stock so that the material that has been stored the longest will be the first to be moved out.

ELK

www.elkcorp.com

333 Pfingsten Road
Northbrook, Illinois 60062-2096
United States Country Code (1)
(847) 272-8800
FAX No. (847) 272-8129
http://www.ul.com

Underwriters Laboratories Inc.®

March 4, 2002

GAF Materials Corporation
Mr Randall Ziegler
1361 Alps Road
Wayne, NJ 07470

Our Reference: R21

Subject: UL Listed products

Dear Mr Ziegler:

This is is response to your request to identify some of the products that are curently Listed with Underwriters Laboratories relating to various Standards. Following are those products:

Royal Sovereign®
Marquis®/Marquis® WeatherMax®
SLATELINE®
Grand canyon™
Grand Sequoia®
Country Mansion™
Country Estates™
Timberline 30™
Timberline Select™ 40
Timberline Ultra™
Sentinel®
The above products have been tested to ASTM D3462 , Class A UL790/ASTM E108 and UL 997/ ASTM D3161(secured with 4 nails)with velocities up to 110 mph and have successfully met those test criteria.

If you have any questions please feel free to contact the writer.

Very truly yours,

Roger Anderson (Ext. 43283)
Senior Engineering Associate
Conformity Assessment Services- 3011E-NBK

Reviewed by,

Douglas C. Miller (Ext. 43262)
Engineering Group Leader
Conformity Assessment Services- 3011E-NBK

** TOTAL PAGE.01 **

GAF®
GAF MATERIALS CORPORATION

MARQUIS® WeatherMax® SHINGLES

ROYAL SOVEREIGN® SHINGLES

SENTINEL® SHINGLES

APPLICATION INSTRUCTIONS

Note: These shingles must be nailed a nominal 5 5/8" (143mm) from bottom of shingles, not in or above self seal, as shown. Nails should remain unexposed.



Standard Nailing Pattern - four nails per shingle

Six Nail Pattern - where required by local code

GENERAL INSTRUCTIONS

• **ROOF DECKS:** For use on new or reroofing work over well-seasoned, supported wood deck, tightly-constructed with maximum 6" (152mm) wide lumber, having adequate nail-holding capacity and smooth surface. Plywood decking as recommended by The Engineered Wood Assn. is acceptable. Plywood decks for Class A installations must be 3/8" (10mm) thick or greater with underlayments as noted below. Shingles must not be fastened directly to insulation or insulated deck unless authorized in writing by GAF Materials Corporation. Roof decks and existing surfacing material must be dry prior to application of shingles.

• **UNDERLAYMENT:** Underlayment is required on new construction and required for reroofing when old roof is removed from the deck. Use only "breather type" material like GAF Materials Corporation Shingle-Mate® Underlayment or equivalent. Underlayments must be installed flat, without wrinkles.

• **FASTENERS:** Use of nails is recommended. (Staple specifications and application instructions are available from GAF Materials Corporation, Contractor Services Dept., 1361 Alps Road, Wayne, NJ 07470.) Use only zinc coated steel or aluminum, 10-12 gauge, barbed, deformed or smooth shank roofing nails with heads 3/8" (10mm) to 7/16" (12mm) in diameter. Fasteners should be long enough to penetrate at least 3/4" (19mm) into wood decks or just through the plywood decks. Fasteners must be driven flush with the surface of the shingle. Over driving will damage the shingle. Raised fasteners will interfere with the sealing of the shingles. For normal installation, four fasteners must be installed per shingle, a nominal 5 5/8" (143mm) up from the bottom of the shingle. Fasteners must be installed approximately 1"-1 1/2" (25-38mm) and 11 1/2"-12 1/2" (292-318mm) from each side.

• **WIND RESISTANT:** These shingles have a special thermal sealant that firmly bonds the shingles together after application when exposed to sun and warm temperatures. Shingles installed in Fall or Winter may not seal until the following Spring. If shingles are damaged by winds before sealing or are not exposed to adequate surface temperatures, or if the self-sealant gets dirty, the shingles may never seal. Failure to seal under these circumstances results from the nature of self-sealing shingles and is not a manufacturing defect. To insure immediate sealing, apply 2 quarter-sized dabs of shingle tab adhesive on the back of each tab, approximately 1" (25mm) from end and 1" (25mm) up from bottom of each tab corner. The shingle must be pressed firmly into the adhesive.
NOTE: Application of excess tab adhesive can cause blistering of the shingle.
For maximum wind resistance along rakes, cement shingles to underlayment and each other in a 4" (102mm) width of asphalt plastic roof cement.
NOTE: The film strips on the back of each shingle are to prevent sticking together of the shingles while in the bundle. Their removal is NOT required during application.

• **CANADIAN COLD WEATHER APPLICATIONS:** CSA A123.5-M90 mandates that shingles applied between September 1 and April 30 shall be adhered with a compatible field-applied adhesive. See Wind Resistant for GAF Materials Corporation's recommendations for the application of that adhesive.

• **MANSARD AND STEEP SLOPE APPLICATIONS:** For roof slopes greater than 21" (1750mm/m) per foot (do NOT use on vertical side walls), shingle sealing must be enhanced by hand sealing. After fastening the shingle in place, apply 2 quarter-sized dabs of shingle tab adhesive as indicated in Wind Resistant above. The shingle must be pressed firmly into the adhesive.

• **EXPOSURE:** 5" (127mm)

• **THROUGH VENTILATION:** All roof structures must be provided with through ventilation to prevent entrapment of moisture laden air behind roof sheathing. Ventilation provisions must at least meet or exceed current F.H.A., H.U.D. or local code minimum requirements.

• **NON-CORRODING METAL DRIP EDGES:** Recommended along rake and eave edges on all decks, especially plywood decks.

• **ASPHALT PLASTIC CEMENT:** For use as shingle tab adhesive. Must conform to ASTM D4586 Type I or II.

1 Underlayment: Standard Slope–4/12 (333mm/m) or more

Application of underlayment: Cover deck with one layer of underlayment installed without wrinkles. Use only enough nails to hold underlayment in place until covered by shingles.

Application of eave flashing: Install eave flashing such as GAF Materials Corporation Weather Watch® or StormGuard® Leak Barrier in localities where leaks may be caused by water backing up behind ice or debris dams. Eave flashing must overhang the roof edge by 3/8" (10mm) and extend 24" (610mm) beyond the inside wall line.



1a Underlayment: Low Slope 2/12-4/12 (167mm-333mm/m)

Application of underlayment and eave flashing: Completely cover the deck with two layers of underlayment as shown. Use only enough nails to hold underlayment in place until covered by shingles. Use blind nailing for eave flashings. At eaves and where ice dams can be expected, use one layer of GAF Materials Corporation Weather Watch® or StormGuard® Leak Barrier. Eave flashing must overhang the roof edge by 3/8" (10mm) and extend 24" (610mm) beyond the inside wall line. Where ice dams or debris dams are not expected, install 2 plies of Shingle-Mate® underlayment.



2 Starter Course

Use of any GAF MC 3-tab Shingle is recommended. Apply as shown.



3 First Course

Start and continue with full shingles laid flush with the starter course. Shingles may be laid from left to right or right to left. DO NOT lay shingles straight up the roof since this procedure can cause an incorrect color blend on the roof and may damage the shingles.



4 Second Course

Start and continue second course and all even numbered courses as shown. Position the shingle on the top of the cutouts of the underlying shingle so that there will be 5" (127mm) of each shingle exposed. Strike a chalk line about every 6 courses to check parallel alignment with eaves. Factory applied self-sealing dots on lower courses are designed to seal down the shingle tabs in an upper course.

NOTE: Shingles may be laid from either left or right hand side. Start at either rake edge with shingles having 6" (152mm) trimmed from rake.



5 Hip and Ridge

Use GAF hip & ridge shingles, or cut hip & ridge shingles from these full shingles, and apply as shown. Position laps away from prevailing wind direction.



6 Wall Flashing (Sloped Roof to Vertical Wall)



7 Chimney Flashing



8 Valley Construction - Closed or Woven Valley



9 Valley Construction–Open Cut



10 Valley Construction–Closed Cut



Precautionary Notes

These shingles are fiberglass, self-sealing asphalt shingles. Because of the natural characteristics of the high quality waterproofing material used, these shingles will be stiff in cold weather and flexible in hot weather.

1. Bundles should not be dropped on edge nor should attempt be made to separate shingles by "breaking" over ridge or other bundles.
2. Handle carefully. Shingles can easily be broken in cold weather or their edges damaged in hot weather.
3. All exposed materials must be of Class A type.
4. Storage should be in a covered, ventilated area–maximum temperature 110°F (43°C.) Store on flat surface and use weight equalization boards if pallets are to be double stacked. Shingles must be protected from weather when stored at job site. Do not store near steam pipes, radiators, etc., or in sunlight. All rolled product must be stored on ends.
5. If shingles are to be applied during PROLONGED COLD periods or in areas where airborne dust or sand can be expected before sealing occurs, the shingles MUST be hand sealed. See Wind Resistant instructions.

Re-Roofing

If old asphalt shingles are to remain in place, nail down or cut away all loose, curled or lifted shingles; replace with new; and just before applying the new roofing, sweep the surface clean of all loose debris. Since any irregularities may show through the new shingles, be sure the underlying shingles provide a smooth surface. Fasteners must be of sufficient length to penetrate the wood deck at least 3/4" (19mm) or just through plywood. Follow other above instructions for application. *Note:* Shingles can be applied over wood shingles when precautions have been taken to provide an acceptable smooth surface. This includes cutting back old shingles at eaves and rakes and installing new wood edging strips as needed. Make surface smooth and use beveled wood strips if necessary. Install #30 underlayment to maintain Class A rating.

This product is sold with an express LIMITED WARRANTY only. A copy of the LIMITED WARRANTY stating its terms and restrictions is printed on the product wrapper or may be obtained from the distributor of this product or directly from GAF Materials Corporation. Any deviation from printed instructions shall be the responsibility of applicator and/or specifier.

ENGLISH 110600

GAF®
GAF MATERIALS CORPORATION

TIMBERLINE® Ultra® SHINGLES
TIMBERLINE® 40 SHINGLES
TIMBERLINE® 30 SHINGLES

APPLICATION INSTRUCTIONS

Timberline® Series shingles come in either 36" (914mm) or 36-15/16" (938mm) lengths, depending on shingle brand. Application instructions apply to both.

These shingles must be nailed a nominal 5-5/8" (143mm) from bottom of shingles, as shown, to allow for penetration through the double ply area just above the tabs. Nails should remain unexposed.



GENERAL INSTRUCTIONS

• **ROOF DECKS:** For use on new or reroofing work over well-seasoned, supported wood deck, tightly-constructed with maximum 6" (152mm) wide lumber, having adequate nail-holding capacity and smooth surface. Plywood decking as recommended by The Engineered Wood Assn. is acceptable. Plywood decks for Class A installations must be 3/8" (10mm) thick or greater with underlayments as noted below. Shingles must not be fastened directly to insulation or insulated deck unless authorized in writing by GAF Materials Corporation. Roof decks and existing surfacing material must be dry prior to application of shingles.

• **UNDERLAYMENT:** Underlayment beneath shingles has many benefits, including preventing wind driven rain from reaching the interior of the building and preventing sap in some wood decking from reacting with asphalt shingles. Underlayment is also required by many code bodies. Consult your local building department for its requirements. Where an underlayment is to be installed, a breather-type underlayment such as GAFMC's Shingle-Mate™ underlayment is recommended. Underlayment must be installed flat, without wrinkles.

• **FASTENERS:** Use of nails is recommended. (Staple specifications and application instructions are available from GAF Materials Corporation, Contractor Services Dept., 1361 Alps Road, Wayne, NJ 07470.) Use only zinc coated steel or aluminum, 10-12 gauge, barbed, deformed or smooth shank roofing nails with heads 3/8" (10mm) to 7/16" (12mm) in diameter. Fasteners should be long enough to penetrate at least 3/4" (19mm) into wood decks or just through the plywood decks. Fasteners must be driven flush with the surface of the shingle. Over driving will damage the shingle. Raised fasteners will interfere with the sealing of the shingles. For normal installation, four fasteners must be installed per shingle, a nominal 5-5/8" (143mm) up from the bottom of the shingle, to penetrate both layers of the shingle. Fasteners must be installed approximately 1"- 1 1/2" (25-38mm) and 11-1/2"-12-1/2" (292-318mm) from each side.

• **WIND RESISTANT:** These shingles have a special thermal sealant that firmly bonds the shingles together after application when exposed to sun and warm temperatures. Shingles installed in Fall or Winter may not seal until the following Spring. If shingles are damaged by winds before sealing or are not exposed to adequate surface temperatures, or if the self-sealant gets dirty, the shingles may never seal. Failure to seal under these circumstances results from the nature of self-sealing shingles and is not a manufacturing defect. To insure immediate sealing, apply 4 quarter-sized dabs of shingle tab adhesive on the back of the shingle 1" (25mm) and 13" (330mm) in from each side and 1" (25mm) up from bottom of the shingle. The shingle must be pressed firmly into the adhesive.

NOTE: Application of excess tab adhesive can cause blistering of the shingle.

For maximum wind resistance along rakes, cement shingles to underlayment and each other in a 4" (102mm) width of asphalt plastic roof cement.

NOTE: The film strips on the back of each shingle are to prevent sticking together of the shingles while in the bundle. Their removal is NOT required during application.

• **CANADIAN COLD WEATHER APPLICATIONS:** CSA 123.5-M90 mandates that shingles applied between September 1 and April 30 shall be adhered with a compatible field-applied adhesive. See Wind Resistant for GAF Materials Corporation's recommendations for the application of that adhesive.

• **MANSARD AND STEEP SLOPE APPLICATIONS:** For roof slopes greater than 21" (1750mm/m) per foot (do NOT use on vertical side walls), shingle sealing must be enhanced by hand sealing. After fastening the shingle in place, apply 4 quarter-sized dabs of shingle tab adhesive as indicated in Wind Resistant above. The shingle must be pressed firmly into the adhesive.

• **EXPOSURE:** 5" (127mm)

• **THROUGH VENTILATION:** All roof structures must be provided with through ventilation to prevent entrapment of moisture laden air behind roof sheathing. Ventilation provisions must at least meet or exceed current F.H.A., H.U.D. or local code minimum requirements.

• **NON-CORRODING METAL DRIP EDGES:** Recommended along rake and eave edges on all decks, especially plywood decks.

• **ASPHALT PLASTIC CEMENT:** For use as shingle tab adhesive. Must conform to ASTM D4586 Type I or II.

1 Underlayment: Standard Slope–4/12 (333mm/m) or more

Application of underlayment: Cover deck with one layer of underlayment installed without wrinkles. Use only enough nails to hold underlayment in place until covered by shingles.

Application of eave flashing: Install eave flashing such as GAF Materials Corporation Weather Watch® or StormGuard® Leak Barrier in localities where leaks may be caused by water backing up behind ice or debris dams. Eave flashing must overhang the roof edge by 3/8" (10mm) and extend 24" (610mm) beyond the inside wall line.



1a Underlayment: Low Slope 2/12-4/12 (167mm-333mm/m)

Application of underlayment and eave flashing: Completely cover the deck with two layers of underlayment as shown. Use only enough nails to hold underlayment in place until covered by shingles. Use blind nailing for eave flashings. At eaves and where ice dams can be expected, use one layer of GAF Materials Corporation Weather Watch® or StormGuard® Leak Barrier. Eave flashing must overhang the roof edge by 3/8" (10mm) and extend 24" (610mm) beyond the inside wall line. Where ice dams or debris dams are not expected, install 2 plies of Shingle-Mate® underlayment.



2 Starter Course

Apply as shown.



3 First Course

Start and continue with full shingles laid flush with the starter course. Shingles may be laid from left to right or right to left. DO NOT lay shingles straight up the roof since this procedure can cause an incorrect color blend on the roof and may damage the shingles.



4 Second Course

Start and continue second course as shown. Trim 6" (152mm) from the end of the shingle. Position the shingles in the second and subsequent courses flush with the tops of the wide cutouts. This results in a 5" (127mm) exposure. Continue with full width shingles across the roof. Strike a chalk line about every 6 courses to check parallel alignment with eaves. NOTE: Shingles may be laid from either left or right hand side. Start at either rake edge with shingles having 6" (152mm) trimmed from rake.



5 Third Course

Trim 11" (279mm) from the first shingle in the course then continue with full shingles across the roof.



6 Fourth Course and Remaining Courses

Trim 17" (432 mm) from first shingle in the course, then continue with full shingles across the roof. Fifth and subsequent courses repeat full shingle instructions from Step 3.



7 Hip and Ridge

For single layer application, use hip and ridge shingles and apply as shown. To enhance appearance, use GAF TIMBERTEX® or a double layer application of Universal Hip & Ridge. (One bundle of TIMBERTEX® Hip & Ridge covers 20 lineal ft.–6.1 meters.) For double application, start with triple thickness of precut Hip & Ridge shingles and continue remainder with double thickness. Fasten in same manner as single application shown. Apply laps away from prevailing wind direction.



8 Wall Flashing (Sloped Roof to Vertical Wall)



9 Chimney Flashing



10 Valley Construction–Closed Cut



11 Valley Construction–Open



Precautionary Notes

Timberline® Series shingles are fiberglass, self-sealing asphalt shingles. Because of the natural characteristics of the high quality waterproofing material used, these shingles will be stiff in cold weather and flexible in hot weather.

1. Bundles should not be dropped on edge nor should attempt be made to separate shingles by "breaking" over ridge or other bundles.
2. Handle carefully. Shingles can easily be broken in cold weather or their edges damaged in hot weather.
3. All exposed materials must be of Class A type.
4. Storage should be in a covered, ventilated area–maximum temperature 110°F (43°C.) Store on flat surface and use weight equalization boards if pallets are to be double stacked. Shingles must be protected from weather when stored at job site. Do not store near steam pipes, radiators, etc., or in sunlight. All rolled product must be stored on ends.
5. If shingles are to be applied during PROLONGED COLD periods or in areas where airborne dust or sand can be expected before sealing occurs, the shingles MUST be hand sealed. See Wind Resistant instructions.

Re-Roofing

If old asphalt shingles are to remain in place, nail down or cut away all loose, curled or lifted shingles; replace with new; and just before applying the new roofing, sweep the surface clean of all loose debris. Since any irregularities may show through the new shingles, be sure the underlying shingles provide a smooth surface. Fasteners must be of sufficient length to penetrate the wood deck at least 3/4" (19mm) or just through plywood. Follow other above instructions for application.

Note: Shingles can be applied over wood shingles when precautions have been taken to provide an acceptable smooth surface. This includes cutting back old shingles at eaves and rakes and installing new wood edging strips as needed. Make surface smooth and use beveled wood strips if necessary. Install #30 underlayment to maintain Class A rating.

ENGLISH 121201


GLAZING OPTION CROSS SECTION
SECTION B-B
TRACK CONFIGURATION FOR 8'0" UP TO 14' TALL DOORS
N.T.S.
SECTION A-A (SIDE VIEW)
N.T.S.
TYPICAL TOP FIXTURES
N.T.S.
TYPICAL DURASAFE CENTER HINGE
N.T.S.
TYPICAL STILE STIFFENER
N.T.S.
INSIDE ELEVATION
N.T.S.
TYPICAL DURASAFE END HINGE
N.T.S.
TYPICAL BOTTOM BRACKET
N.T.S.
TRACK MOUNTING DETAIL
WOOD JAMB ATTACHMENT TO STRUCTURE
SPECIFICATIONS AND NOTES
2" 7 BALL STEEL SHORT STEM ROLLER
CONT. STEEL RETAINER W/ CONT. BTM SEAL
2 X 6 SOUTHERN YELLOW PINE (NO. 2 OR BETTER)
MAX SIZE 16' x 14'
DESIGN LOADS +18.3 PSF -20.8 PSF
TEST LOADS +27.5 PSF -31.3 PSF
JUN 03 2003
Amarr GARAGE DOORS
MODEL #600 STRATFORD w/DuraSafe
MODEL #950 HERITAGE w/DuraSafe
Short Panel, long Panel, and Flush Panel
IRC-6016-110-15
SHEET 1 OF 1

MIAMI-DADE

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING

BUILDING CODE COMPLIANCE OFFICE
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

CONTRACTOR LICENSING SECTION
(305) 375-2527 FAX (305) 375-2558

CONTRACTOR ENFORCEMENT DIVISION
(305) 375-2966 FAX (305) 375-2908

PRODUCT CONTROL DIVISION
(305) 375-2902 FAX (305) 372-6339

PRODUCT CONTROL NOTICE OF ACCEPTANCE

Premdor Entry Systems
911 E. Jeferson, P.O. Box 76
Pittsburgh ,KS 66762

Your application for Notice of Acceptance (NOA) of:
Entergy 6-8 S/E Inswing Opaque Double w/sidelites Residential Insulated Steel Door
under Chapter 8 of the Code of Miami-Dade County governing the use of Alternate Materials and Types of Construction, and completely described herein, has been recommended for acceptance by the Miami-Dade County Building Code Compliance Office (BCCO) under the conditions specified herein.

This NOA shall not be valid after the expiration date stated below. BCCO reserves the right to secure this product or material at any time from a jobsite or manufacturer's plant for quality control testing. If this product or material fails to perform in the approved manner, BCCO may revoke, modify, or suspend the use of such product or material immediately. BCCO reserves the right to revoke this approval, if it is determined by BCCO that this product or material fails to meet the requirements of the South Florida Building Code.

The expense of such testing will be incurred by the manufacturer.

ACCEPTANCE NO.: 01-0314.23
EXPIRES: 04/02/2006

Raul Rodriguez
Chief Product Control Division

THIS IS THE COVERSHEET, SEE ADDITIONAL PAGES FOR SPECIFIC AND GENERAL CONDITIONS
BUILDING CODE & PRODUCT REVIEW COMMITTEE

This application for Product Approval has been reviewed by the BCCO and approved by the Building Code and Product Review Committee to be used in Miami-Dade County, Florida under the conditions set forth above.

Francisco J. Quintana, R.A.
Director
Miami-Dade County
Building Code Compliance Office

APPROVED: 06/05/2001

Premdor Entry Systems

ACCEPTANCE No: 01-0314.23

APPROVED : JUN 05 2001

EXPIRES : April 02, 2006

NOTICE OF ACCEPTANCE: SPECIFIC CONDITIONS

1. SCOPE

1.1 This renews the Notice of Acceptance No. 00-0321.25 which was issued on April 28, 2000. It approves a residential insulated door, as described in Section 2 of this Notice of Acceptance, designed to comply with the South Florida Building Code (SFBC), 1994 Edition for Miami-Dade County, for the locations where the pressure requirements, as determined by SFBC Chapter 23, do not exceed the Design Pressure Rating values indicated in the approved drawings.

2. PRODUCT DESCRIPTION

2.1 The **Series Entergy 6-8 S/E Inswing Opaque Double Residential Insulated Steel Doors with Sidelites-Impact Resistant Door Slab Only** and its components shall be constructed in strict compliance with the following documents: Drawing No **31-1029-EM-I**, Sheets 1 through 6 of 6, titled "Premdor (Entergy Brand) Double Door with Sidelites in Wood Frames with Bumper Threshold (Inswing)," prepared by manufacturer, dated 7/29/97 with revision C dated 01/11/00, bearing the Miami-Dade County Product Control approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Division. These documents shall hereinafter be referred to as the approved drawings.

3. LIMITATIONS

3.1 This approval applies to single unit applications of pair of doors and single door only, as shown in approved drawings. Single door units shall include all components described in the active leaf of this approval.

3.2 Unit shall be installed only at locations protected by a canopy or overhang such that the angle between the edge of canopy or overhang to sill is less than 45 degrees. Unless unit is installed in non-habitable areas where the unit and the area are designed to accept water infiltration.

4. INSTALLATION

4.1 The residential insulated steel door and its components shall be installed in strict compliance with the approved drawings.

4.2 Hurricane protection system (shutters):

4.2.1 Door: the installation of this unit **will not require** a hurricane protection system.

4.2.2 Sidelite: the installation of this unit **will require** a hurricane protection system.

5. LABELING

5.1 Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved".

6. BUILDING PERMIT REQUIREMENTS

6.1 Application for building permit shall be accompanied by copies of the following:

6.1.1 This Notice of Acceptance

6.1.2 Duplicate copies of the approved drawings, as identified in Section 2 of this Notice of Acceptance, clearly marked to show the components selected for the proposed installation.

6.1.3 Any other documents required by the Building Official or the South Florida Building Code (SFBC) in order to properly evaluate the installation of this system.

Manuel Perez, P.E. Product Control Examiner
Product Control Division

Premdor Entry Systems

ACCEPTANCE No.: 01-0314.23

APPROVED : JUN 05-2001

EXPIRES : April 02, 2006

NOTICE OF ACCEPTANCE: STANDARD CONDITIONS

1. Renewal of this Acceptance (approval) shall be considered after a renewal application has been filed and the original submitted documentation, including test supporting data, engineering documents, are no older than eight (8) years.

2. Any and all approved products shall be permanently labeled with the manufacturer's name, city, state, and the following statement: "Miami-Dade County Product Control Approved", or as specifically stated in the specific conditions of this Acceptance.

3. Renewals of Acceptance will not be considered if:
   a. There has been a change in the South Florida Building Code affecting the evaluation of this product and the product is not in compliance with the code changes.
   b. The product is no longer the same product (identical) as the one originally approved.
   c. If the Acceptance holder has not complied with all the requirements of this acceptance, including the correct installation of the product.
   d. The engineer who originally prepared, signed and sealed the required documentation initially submitted, is no longer practicing the engineering profession.

4. Any revision or change in the materials, use, and/or manufacture of the product or process shall automatically be cause for termination of this Acceptance, unless prior written approval has been requested (through the filing of a revision application with appropriate fee) and granted by this office.

5. Any of the following shall also be grounds for removal of this Acceptance:
   a. Unsatisfactory performance of this product or process.
   b. Misuse of this Acceptance as an endorsement of any product, for sales, advertising or any other purposes.

6. The Notice of Acceptance number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the Notice of Acceptance is displayed, then it shall be done in its entirety.

7. A copy of this Acceptance as well as approved drawings and other documents, where it applies, shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at all time. The engineer needs not reseal the copies.

8. Failure to comply with any section of this Acceptance shall be cause for termination and removal of Acceptance.

9. This Notice of Acceptance consists of pages 1, 2 and this last page 3.

END OF THIS ACCEPTANCE

Manuel Perez

Manuel Perez, P.E., Product Control Examiner
Product Control Division



SECTION A-A
INSWING



OTHER CONFIGURATIONS



APPROVED AS COMPLYING WITH THE SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2001
BY [signature]
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314.23

C	DADE COUNTY MODIFICATIONS	JD
B	ADDED PAGE 5 (DOOR OPTIONS)	RS
A	ADD SCREWS TO LITE FRAMES & ADD OTHER DOOR CONFIGURATIONS	
LTR	REVISIONS	DATE / BY

PART NAME: ENTERGY DOOR W/SIDELITES (A-A)
SCALE: NTS
DR. BY RS | DATE 7-29-97
ENGINEER:

PREMDOR ENTRY SYSTEMS

31-1029-EM-1
SHEET 2 OF 6
REVISION LETTER C



SECTION B-B

MATERIALS LIST

ITEM NO.	DESCRIPTION	PART NUMBER	COMMENTS
①	WOOD HEAD JAMB	EM-14	1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT
②	COMPRESSION WEATHERSTRIP	EM-25	LOCKSCREEN BRAND LOXSEAL 9650 (BRONZE)
③	ALUMINUM ASTRAGAL	EM-12	PREMDOR BRAND OR EQUIVALENT- 5/8" ALUMINUM ASTRAGA
④	ALUMINUM-BUMPER THRESHOLD	EM-15	PREMDOR BRAND OR EQUIVALENT - 1 1/4" x 4 9/16"
⑤	TOP CHANNEL	EM-08	PREMDOR BRAND - 1 11/16" - 20 GA STEEL
⑥	STEEL SKIN	26 ga. (.017 +.004 -.000)	MIN YIELD STRENGTH 33,000 PSI MIN. THICKNESS PER TENSILE TEST REPORT IS .021"
⑦	POLYURETHANE FOAM CORE	BASF FOAM - DENSITY 2.0 TO 2.5 lbs./Ft³	
⑧	BOTTOM CHANNEL	EM-07	PREMDOR BRAND - 1 11/16" - 20 GA STEEL
⑨	WOOD LOCK BLOCK	EM-09	4" X 9 1/2" MTL. TO BE PINE OR EQUIVALENT
⑩	STRIKE STILE	EM-06	PREMDOR BRAND - 1 11/16" - 20 GA STEEL
⑪	HINGE STILE	EM-05	PREMDOR BRAND - 1 11/16" - 20 GA STEEL
⑫	LOCK PREP FILLER PLATE	EM-10	PREMDOR BRAND - .050" THICK- MTL. TO BE POLYETHYLEN
⑬	4"x4" HINGE	EM-16	HAGER BRAND HINGE OR EQUIVALENT - .097 THICK (STEEL
⑭	WOOD HINGE JAMB	EM-13	1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT
⑮	#10-24 x 1/2" F.H.M.S.		(4) SCREWS PER HINGE INTO DOOR
⑯	#10 X 2" F.H.W.S.		(5) SCREWS THROUGH HINGE JAMB INTO SIDELITE JAMB, 8" DOWN FROM TO MAX 18" O.C. THEREAFTER (10) SCREWS THROUGH STRIKE JAMB INTO SIDELITE JAMB, 4" DOWN FROM TI MAX 8" O.C. THEREAFTER (6) SCREWS THROUGH EACH SIDELITE JAMB INTO SIDELITE, 4" DOWN FROM TOP, MAX 15" O.C. THEREAFTER
⑰	#10 F.H.W.S. W/MINIMUM 1 1/2 EMBEDMENT OR 3/16" PFH TAPCONS W/MINIMUM 1 1/2" EMBEDMENT		REFER TO ELEVATION VIEW, FOR # OF SCREWS USED AND LOCATIONS
⑱	#10 X 3/4" F.H.W.S.		(2) SCREWS PER HINGE INTO JAMB
⑲	#8 x 2" F.H.W.S.		(2) SCREWS AT EACH STRIKE PLATE
⑳	LOCKSET		KWIKSET BRAND 200 LOCK OR HARLOC BRAND 100 LOCK
㉑	#10 X 1 3/4" F.H.W.S.		(2) SCREWS PER HINGE INTO JAMB
㉒	WOOD SIDELITE JAMB	EM-18	1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT
㉓	22" X 64" SINGLE PANEL GLASS	EM-19	TEMPERED GLASS IN POLYPROPYLENE FRAME- DC-1643 - (ODL-1/8" CLEAR TEMPERED GLASS
㉔	SIDELITE TRIM (WOOD)	EM-20	5/16 x 1/2" MTL. TO BE PINE OR EQUIVALENT
㉕	WOOD CASING	EM-21	1/8" x 1" MTL. TO BE PINE OR EQUIVALENT - ITEMS ARE MOLDINGS USE FOR "SIDE BY SIDE JAMBS" AS MULLIONS
㉖	WOOD SIDELITE HEAD JAMB	EM-22	1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT
㉗	WOOD SIDELITE BASE	EM-23	1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT
㉘	POLYPROPYLENE LITE FRAME	DC-1643, ODL-2	HP Polypropylene by ODL
㉙	#6 X 1 1/2" PAN HEAD SCREWS		18 PER FRAME SCREW SPACING TO BE 3" IN FROM EACH CORNER AND NO TO EXCEED 14" OC THERE AFTER.
㉚	SIDELITE STILES	EM-26	15/16" X 1 11/16" MTL. TO BE PINE OR EQUIVALENT
㉛	PIN NAIL		3/4" LONG NAIL, 4" IN FROM END, MAX 8" O.C. THEREAFTER, USED ON MULLIONS AND TRI

APPROVED AS COMPLYING WITH THE SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2001
BY
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314.23

UNITS: UNLESS NOTED, FRAC. : DEC. : ANG. : EXTRUSIONS: UNLESS NOTED, STD. COMM. TOL'S.	B	DADE COUNTY MODIFICATIONS	1/11/01	JD
	A	ADDED PAGE 5 (DOOR OPTIONS)	10-1-98	RS
ENGINEER:	LTR	REVISIONS	DATE	BY
	PART NAME: ENTERGY STEEL EDGE DOOR (B-B)			
DR. BY R.S. DATE 7-29-97	MAT'L:		SCALE:	

PREMDOR ENTRY SYSTEMS
911 E. JEFFERSON
PITTSBURG, KS. 66762

A

31-1029-EM-I
SHEET 3 OF 6

REVISION LETTER B



SECTION C-C

APPROVED AS COMPLYING WITH THE SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2001
BY
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314.23

D	DADE COUNTY MODIFICATIONS	5/11/01	JD
C	MATERIAL WAS POLYSTYRENE	6-2-99	RS
B	ADDED PAGE 5 (DOOR OPTIONS)	10-1-98	RS
A	ADD SCREWS TO LITE FRAME & MATERIAL LIST	12-18-97	R.S.
LTR.	REVISIONS	DATE	BY

LIMITS: UNLESS NOTED, FRAC. : DEC. : ANG. :
EXTRUSIONS: UNLESS NOTED, STD. COML. TOL'S.

ENGINEER:

DR. BY R.S. | DATE 7-29-97

PART NAME: ENTERGY METAL EDGE SIDELITE (C-C)

MAT'L: | SCALE:

PREMDOR ENTRY SYSTEMS
911 E. JEFFERSON
PITTSBURG, KS. 66762

31-1029-EM-I
SHEET 4 OF 6

REVISION LETTER D

OTHER DOOR CONFIGURATIONS



OXXO



OXX



XXO



XX



OX



XO



OXO



X

APPROVED AS COMPLYING WITH THE SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2001
BY
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314.23

LIMITS: UNLESS NOTED, FRAC. : DEC. : ANG. :
EXTRUSIONS: UNLESS NOTED, STD COML. TOL'S

ENGINEER:

LTR	REVISIONS	DATE	BY

DR. BY J.D. | DATE 1-11-01

PART NAME:

MAT'L: | SCALE:

PREMDOR ENTRY SYSTEMS
911 E. JEFFERSON
PITTSBURG, KS. 66762

31-1029-EM-I
SHEET 5 OF 6

REVISION LETTER

OTHER DOOR PANEL STYLES



OTHER SIDELITE STYLES









APPROVED AS COMPLYING WITH THE SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2001
BY
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO 01-0314.23

LIMITS: UNLESS NOTED, FRAC. : DEC. : ANG. :
EXTRUSIONS: UNLESS NOTED, STD. COMM. TOL'S.
ENGINEER:
DR. BY J.D. | DATE 1/15/01

LTR	REVISIONS	DATE	BY

PART NAME: PREMDOR DOOR OPTIONS
MAT'L: | SCALE:

PREMDOR ENTRY SYSTEMS
911 E. JEFFERSON
PITTSBURG, KS. 66762

31-1029-EM-I
SHEET 6 OF 6
REVISION LETTER

PREMDOR (ENTERGY BRAND) DOUBLE DOOR WITH SIDELITES IN WOOD FRAMES WITH BUMPER THRESHOLD (INSWING)



ATTACH ASTRAGAL THROW BOLT STRIKE PLATE TO THE HEADER AND THRESHOLD WITH #10 x 1 3/4" FLATHEAD SCREWS



ASTRAGAL



NOTES:

1.) WOOD BUCKS BY OTHERS. MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.

2.) THE PRECEDING DRAWINGS ARE INTENDED TO QUALIFY THE FOLLOWING INSTALLATIONS.

A. WOOD FRAME CONSTRUCTION WHERE DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD OPENING.

B. MASONRY OR CONCRETE CONSTRUCTION WHERE DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY STRUCTURAL WOOD BUCK.

C. MASONRY OR CONCRETE CONSTRUCTION WHERE DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL LINE BY WOOD BUCK.

D. ALL ANCHORING SCREWS TO BE #10 WITH MINIMUM 1 1/2" EMBEDMENT INTO WOOD SUBSTRATE OR 3/16" PFH TAPCONS WITH 1 1/2" MINIMUM EMBEDMENT INTO MASONRY.

3. UNIT MUST BE INSTALLED WITH 'MIAMI-DADE COUNTY APPROVED' SHUTTERS

4. THREE STAPLES PER SIDE JAMB INTO HEADER ON SIDELITES AND DOOR, THREE STAPLES PER JAMB INTO THRESHOLD ON SIDELITES AND DOOR.

5. LATEX SEALANT TO BE APPLIED AT SIDE BY SIDE JAMBS AND SIDELITES.

6. DOOR/SIDELITE HEADER, DOOR/SIDELITE JAMBS, AND SIDELITE BASE CORNERS ARE COPED AND BUTT JOINED.

7. DOORS SHALL BE PRE-PAINTED WITH A WATER-BASED EPOXY RUST INHIBITIVE PRIMER PAINT WITH A DRY FILM THICKNESS OF 0.8 TO 1.2 MIL.

8. FRAMES SHALL BE PRE-PAINTED WITH AN ACRYLIC LATEX WATER-BASED/ WATER-REDUCIBLE WHITE PRIMER WITH A DRY FILM THICKNESS OF 0.8 TO 1.2 MIL.

DESIGN PRESSURE RATINGS		
	WHERE WATER INFILTRATION REQUIREMENT IS NEEDED *	WHERE WATER INFILTRATION REQUIREMENT IS NOT NEEDED
Positive	NOT APPROVED *	+55.0 psf
Negative	NOT APPROVED *	-55.0 psf

* UNITS SHALL BE INSTALLED ONLY AT LOCATIONS PROTECTED BY A CANOPY OR OVERHANG SUCH THAT THE ANGLE BETWEEN THE EDGE OF CANOPY OR OVERHANG TO SILL IS LESS THAN 45 DEGREES. UNLESS UNIT IS INSTALLED IN NON-HABITABLE AREAS WHERE THE UNIT AND THE AREA ARE DESIGNED TO ACCEPT WATER INFILTRATION.

APPROVED AS COMPLYING WITH THE SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2001
BY [signature]
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314.23

C	DADE COUNTY MODIFICATIONS	1/11/00	JO
B	ADDED PAGE 5 (DOOR OPTIONS)	10-1-98	RS
A	ADD OTHER DOOR CONFIGURATIONS	12/18/97	RS
LTR	REVISIONS	DATE	BY

UNITS UNLESS NOTED, FRAC. ± DEC. ± ANG. ±
EXTRUSIONS UNLESS NOTED, STD. COMM. TOL.'S
ENGINEER:
BY R.S. | DATE 7-29-97
PART NAME: ENTERGY METAL CLAD DOUBLE DOOR W/SIDELITES
MAT'L: | SCALE: N.T.S.

PREMDOR ENTRY SYSTEMS
911 E. JEFFERSON
PITTSBURG, KS 66762

31-1029-EM-I
SHEET 1 OF 6

Notice of Treatment 11875

Applicator: Florida Pest Control & Chemical Co. (www.flapest .com)
Address: 13 AVE
City LC Phone 752-1765

Site Location: Subdivision
Lot # 26 Block# Permit # 124044
Address 1007 SW WATSON RD

Product used	Active Ingredient	% Concentration
☐ Premise	Imidacloprid	0.1%
☐ Termidor	Fipronil	0.12%
☑ Bora-Care	Disodium Octaborate Tetrahydrate	23.0%

Type treatment: ☐ Soil ☑ Wood

Area Treated	Square feet	Linear feet	Gallons Applied
Dwelling	2188	681	6

As per Florida Building Code 104.2.6 – If soil chemical barrier method for termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial this line _____.

4-6-06 1430 F254 Gunny
Date Time Print Technician's Name

Remarks: _____

Applicator - White Permit File - Canary Permit Holder - Pink
10/05 ©

Weggie

Columbia County Building Department
Culvert Waiver

Culvert Waiver No. 000000950

DATE: 01/17/2006 BUILDING PERMIT NO. 24044

APPLICANT MATT CASON PHONE 752-5152

ADDRESS 853 SW SISTERS WELCOME ROAD LAKE CITY FL 32025

OWNER RUSSELL & JEANN WHITEHEAD PHONE 752-5152

ADDRESS 1007 SW WATSON STREET FT. WHITE FL 32038

CONTRACTOR STANLEY CRAWFORD PHONE 752-5152

LOCATION OF PROPERTY 47S, TL ON WATSON STREET, .8 MILES ON LEFT

SUBDIVISION/LOT/BLOCK/PHASE/UNIT BIG OAKS 26

PARCEL ID # 26-5S-16-03717-126

I HEREBY CERTIFY THAT I UNDERSTAND AND WILL FULLY COMPLY WITH THE DECISION OF THE COLUMBIA COUNTY PUBLIC WORKS DEPARTMENT IN CONNECTION WITH THE HEREIN PROPOSED APPLICATION.

SIGNATURE: [signature]

A SEPARATE CHECK IS REQUIRED
MAKE CHECKS PAYABLE TO BCC

Amount Paid 50.00

PUBLIC WORKS DEPARTMENT USE ONLY

I HEREBY CERTIFY THAT I HAVE EXAMINED THIS APPLICATION AND DETERMINED THAT THE CULVERT WAIVER IS:

✓ APPROVED _____ NOT APPROVED - NEEDS A CULVERT PERMIT

COMMENTS: _____

SIGNED: [signature] DATE: 1/20/06

ANY QUESTIONS PLEASE CONTACT THE PUBLIC WORKS DEPARTMENT AT 386-752-5955.

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160

JAN 20 2006

COLUMBIA COUNTY FLORIDA

CERTIFICATE OF OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 26-5S-16-03717-126 **Building permit No.** 000024044

Use Classification SFD,UTILITY **Fire:** 24.78

Permit Holder STANLEY CRAWFORD **Waste:** 36.75

Owner of Building RUSSELL & JEANN WHITEHEAD **Total:** 61.53

Location: 1007 SW WATSON STREET(BIG OAKS, LOT 26)

Date: 07/27/2006

Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)