

BEARING HEIGHT SCHEDULE

8'-0"

OVERHANG

1'-0"

ROOF PITCH(S)

6/12

NOTES:

- 1) REFER TO HB 91 RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING. REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED.
- 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V05 FOR ALTERNATE BRACING REQUIREMENTS.
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.
- 4) ALL TRUSSES ARE DESIGNED FOR 2 o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
- 6) 5X42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.
- 7) ALL ROOF TRUSSES HANGERS TO BE SIMPSON HUS26 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSSES HANGERS TO BE SIMPSON THA422 UNLESS OTHERWISE NOTED.
- 8) DEBRIDGE/DEBRIDGE/INTEL (HDR) TO BE FURNISHED BY BUILDER.

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND V05S. ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

Expedited Delivery Date _____

Approved By: _____ Date: _____



PHONE 904-437 3349 FAX 904 437 3994

Bunnell

PHONE 904-772-6100 FAX 904-772-1973

Jacksonville

PHONE 904-755-6894 FAX 904-755-7973

Lake City

PHONE 407-322-0054 FAX 407 322 5553

Sanford

BUILDER: PENNNYWORTH-JARRELL

LEGAL ADDRESS: COLUMBIA, FL

MODEL: WESTWIND REVISION: SCALE: NTS

DATE: 06/21/06 AM DRAWN BY: L169692

HANGER SCHEDULE

(9) HTU26

