

Columbia County Building Permit Application Lift Mexage 3-16-56 LH
Revised 9-23-04

For Office Use Only Application # 0602 · 101 Date Received 2/28/0 6 By 67 Permit # 24275
Application Approved by - Zoning Official BLK Date 08-03.06 Plans Examiner OK 57H Date 3-7-06
Flood Zone Development Permit Zoning R SF-1 _ Land Use Plan Map Category Res. U. L. DEV.
Comments
Applicants Name Keun Bedensaugh Phone 386 938 5588
Address PO BOX 1414 Live Onk FL 32064
Owners Name Chaeles Parish Phone 719-7300
911 Address 433 SW Brodersk Lone Lake CAy IC
Contractors Name Plumb Level construction Phone 386-988-5588
Address PO BOD 1416 Live Oak, FC 32064
Fee Simple Owner Name & Address
Bonding Co. Name & Address
Architect/Engineer Name & Address John K. Gentry 114-BWEST Green STELET, PERFY, FL 32
Mortgage Lenders Name & Address
Circle the correct power company — FL Power & Light — Clay Elec. — Suwannee Valley Elec. — Progressive Energy
Property ID Number 208446 - 118 Estimated Cost of Construction \$ 20,000
Subdivision Name Sapple of the South Lot 1/2 Block Unit Phase
Driving Directions 47 South to Beodeer K Lane, Then @ About the
5th house one Right 433 on house & mail box. 9th lot on right
ACLOSS from Chuck Rd.
Type of Construction Add throw to SED Number of Existing Dwellings on Property /
Total Acreage 1 18 4 Lot Size Do you need a - <u>Culvert Permit</u> or <u>Culvert Walver</u> or <u>Have an Existing Drive</u>
Actual Distance of Structure from Property Lines - Front 35 Side 30 Side 30 Rear 550
Total Building Height/3 Number of Stories/ _ Heated Floor Area3z\(\delta\) _ Roof Pitch/_ \(\geq \)
Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.
OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.
<u>WARNING TO OWNER:</u> YOUR FAILURE TO RECORD A NOTICE OF COMMENCMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.
Kenin Bodenbaugh.
Owner Builder or Agent (Including Contractor) Contractor Signature Contractors License Number RBook 697
COUNTY OF COLUMBIA
Sworn to (or affirmed) and subscribed before me
this 78th day of tebruary 2006. The redain
Personally known or Produced Identification Notary Signature


- 1. A PLAT, PLAN, OR DRAWING SHOWING THE PROPERTY LINES OF THE PARCEL.
- 2. LOCATION OF PLANNED RESIDENT OR BUSINESS STRUCTURE ON THE PROPERTY WITH DISTANCES FROM AT LEAST TWO OF THE PROPERTY LINES TO THE STRUCTURE (SEE SAMPLE BELOW).
- 3. LOCATION OF THE ACCESS POINT (DRIVEWAY, ETC.) ON THE ROADWAY FROM WHICH LOCATION IS TO BE ADDRESSED WITH A DISTANCE FROM A PARALLEL PROPERTY LINE AND OR PROPERTY CORNER (SEE SAMPLE BELOW).
- 4. TRAVEL OF THE DRIVEWAY FROM THE ACCESS POINT TO THE STRUCTURE (SEE SAMPLE BELOW).




SITE PLAN BOX:



Page 2 of 2



This information, GIS Map Updated: 8/3/2005, was derived from data which was compiled by the Columbia County Property Appraiser
Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a
determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data
herein, it's use, or it's interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the
Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad
valorem assessment purposes.



Inst:2006004825 Date:02/28/2006 Time:14:31
______DC,P.DeWitt Cason,Columbia County B:1075 P:1289

SPACE AROVE THIS I BUT FOR PROCESSING DATA			
SPACE ABOVE THIS LINE FOR PROCESSING DATA NOTICE OF C	OMMEN		ne fur recurding da i a
Permit No		OLWILI41	Tax Folio No RO8466
State of Florida		*1	- W. XII
State of Florida} County of Columbia			
The undersigned hereby gives notice that improvements will 713 of the Florida Statutes, the following information is prov	l be made to d ided in this N	ertain real property OTICE OF COMMEN	r, and in accordance with chapter
Legal description of property (include Street Address, if availab	le) <i>N/1</i>		
General description of improvements ADDITICAL			
Owner's Name Charles Pareish			
Address 433 Sw BROWERCK LANCE	10/10 (7 FL 3	2025
Owner's Interest in site of the improvement 100 150	1	311 10 3	W
Fee Simple Title holder (if other than owner)			
	Phone:		Fax:
Contractor Plumb Level Constanctor	7 110110.		гах
Address PO BUX 1416 Live Oak FC 3200	Y Phone:	925-5388	Eavi
SuretyN/A			_ Fax:
Address			
Lender's Name N/A			
			_ Fax:
Persons within the State of Florida designated by owner up	on whom not	ices or other docur	nents may be served as pro-
vided by Section 713.13(1)(a)7, Florida Statutes.			•
Name Kevin Redenbaugh			
Address Poly16 Live Oat F1 32064	Phone:	386 93B-558-1	ි Fax:
In addition to himself, owner designates			
Of	Phone:		Fax:
to receive a copy of the Lienor's Notice as provided in Section 7	13.13(1)(b), Fl	orida Statutes.	
Expisation date of Notice of Commencement (the expiration date in			unless a different date is specified)
Kevin Bodenbraugh	را	. 0 .	1 /
	\mathcal{I}		bau 0/1 ed Name of Owner
Signature of Owner NOTARY RUBBER STAMP SEAL I hav	relied upon the f	ollowing identification of	·
ROSE AINN ATELLO			
M. CONTRESTON # DD341344 \$	to and subscribe	d before me thisk	brung day of \$ 1006
EXPIRES: February 17, 2009 Helio-Northery Ft. Neury Discorat Assoc Co. 2 Notary Control of the	Signature Rose	Ann Aiello	

Inst:2005019702 Date:08/15/2005 Time:13:57 Doc Stamp-Deed: 1046.50 _DC,P.DeWitt Cason,Columbia County B:1055 P:213 RETURN TO: STONE TITLE AGENCY, INC. 9735 U.S. Hwy. 19 Port Richey, FL 34668

Prepared by and Return to: Virlyn Willis Gateway Title Agency, LLC 4255 SW Cambridge Glen Lake City, Florida 32024

File Number: 31731GW Parcel I.D. Number: R08466-118

incidental to the issuance of a Title Insurance Policy

General Warranty Deed

A.D. By Dolores Collins a single person, whose address is: 2023 St. Lucie Blvd. Lot 172, Ft. Pierce, FL 34946 hereinafter called the grantor, to Charles Parrish and Barbara J. Parrish, husband and wife, whose post office address is: 3410 Benson Ct, Mims, FL 32754, hereinafter called the grantee:

(Whenever used herein the term "grantor" and "grantoe" include all the parties to this instrument and the heirs, legal representatives and assigns of individuals, and the successors and assigns of corporations)

Witnesseth, that the grantor, for and in consideration of the sum of One Hundred Forty Nine Thousand Five Hundred dollars & no cents, (\$149,500.00) and other valuable considerations, receipt whereof is hereby acknowledged, hereby grants, bargains, sells, aliens, remises, releases, conveys and confirms unto the grantee, all that certain land situate in Columbia County, Florida, viz:

Lot 18, of Saddle of the South Estates, according to the Plat thereof, as recorded in Plat Book 6, at Page 64, of the Public Records of Columbia County, Florida.

Subject to covenants, conditions, restrictions, reservations, limitations, easements and agreements of record, if any; taxes and assessments for the year 2005 and subsequent years; and to all applicable zoning ordinances and/or restrictions and prohibitions imposed by governmental authorities, if any

Together with all the tenements, hereditaments and appurtenances thereto belonging or in anywise appertaining.

To Have and to Hold, the same in fee simple forever.

And the grantor hereby covenants with said grantee that the grantor is lawfully seized of said land in fee simple; that the grantor has good right and lawful authority to sell and convey said land; that the grantor hereby fully warrants the title to said land and will defend the same against the lawful claims of all persons whomsoever.

In Witness Whereof, the said grantor has signed and sealed these presents the day and year first above written.

REQUIRES AND DIFFERENT WITNESSES Witness #1 signature Print Witness #1 name	Dolores Collins	(Seal)
Witness #2 signature Owen Print Witness #2 name		(Seal)
State of Ronda Country of Columbia	7.0	
The foregoing instrument was acknowledged before me this	by Dolpres Collins a single p	erson, who has
Notary Seal	Notary Public my commission expires	
	VIFIL'YN B. WILLIB, JR. MY COMMISSION # DD 372469 EXPIRES: November 10, 2008 Bonied Thru Notery Praise University	46

χ

FORM 600B-01

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION Residential Component Prescriptive Method B

NORTH 123

Compliance with Method B Chapter 6 of the Florida Energy Efficiency Code may be demonstrated by the use of Form 600B for single and multifamily residences of 3 stones or less in height, and additions to existing residential buildings. To comply, a building must meet or exceed all of the energy efficiency prescriptives in any one of the prescriptive component packages and comply with the prescriptive measures listed in Table 6B-1 of this form. An alternative method is provided for additions of 600 square feet or less by use of Form 600C. If a building does not comply with this method, it may still comply under other sections in Chapter 6 of the Code.

PROJECT NAME: PARe 15H	BUILDER: Plumb Level	construction
AND ADDRESS: 433 SW Broolewek CAME		CLIMATE
Lake CAy, FC	OFFICE: Olumbia	ZONE: 1 2 3
OWNER: Charles Paceish	PERMIT NO. 24275	JURISDICTION NO.: ZZIOOO
GENERAL DIRECTIONS		

- 1. New construction including additions which incorporates any of the following features cannot comply using this method; steel stud walls, single assembly roof/ceiling construction, or skylights or other non-vertical roof glass.
- 2 Choose one of the component packages "A" through "E" from Table 6B-1 by which you intend to comply with the Code. Circle the column of the package you have chosen.
- 3. Fill in all the applicable spaces of the "To Be Installed" column on Table 6B-1 with the information requested. All "To Be Installed" values must be equal to or more efficient than the required levels.

5, R	omplete page 1 based on the "To Be Installed" column information, lead "Minimum Requirements for All Packages", Table 68-2 and check each box to indicate your intent to comply with all appl and sign and date the "Despect Or " and Section to the part of the burner to the control of the contr	licable items.
0, 1	ead, sign and date the "Prepared By" certification statement at the bottom of page 1. The owner or owner's agent must also	
1.	Compliance realizate chance (A.F.)	Please Print CK
2.	Compliance package chosen (A-F) New construction or addition	
3.		2. <u>A DOITIC.J</u>
	Single family detached or Multifamily attached	3. <u>SF</u>
4.	If Multifamily—No. of units covered by this submission	4
5.	Is this a worst case? (yes / no)	5.
6.	(04. 1)	6. 320
7.	(i)	7. 2
8.	Glass type and area :	Single Pane Double Pane
	a. Clear glass	8 a sq. ft. <u>64,95</u> sq. ft
	b. Tint, film or solar screen	8b sq. ftsq. ft
9.	3	9. 20 %
10	. Floor type, area or perimeter, and insulation:	_
	a. Slab on grade (R-value)	10a. R= 0 56 lin. ft.
	b. Wood, raised (R-value)	10b. R= sq. ft
	c. Wood, common (R-value)	10c. R= sq. ft
	d. Concrete, raised (R-value)	10d. R= sq. ft
	e. Concrete, common (R-value)	10e. R= sq. ft
11	. Wall type, area and insulation:	
	a. Exterior: 1. Masonry (Insulation R-value)	11a-1 R= sq. ft
	2. Wood frame (Insulation R-value)	11a-2 R= 13 383 sq. ft.
	b. Adjacent: 1. Masonry (Insulation R-value)	11b-1 R= sq. ft
	2. Wood frame (Insulation R-value)	11b-2 R= sq. ft.
12	Ceiling type, area and insulation:	5q. n.
	a. Under attic (Insulation R-value)	12a. R= 30 320 sq. ft.
	b. Single assembly (Insulation R-value)	12b. R= sq. ft
13.	Air Distribution System: Duct insulation, location	13. R=
	Test report (attach if required)	14a. Type: <u>Centerl</u>
14.	Cooling system	14b. SEER/EER: 10.5 +
	(Types: central, room unit, package terminal A.C., gas, none)	14c. Capacity:
15.	Heating system:	15a. Type: Heat Parage
	(Types: heat pump, elec. strip, nat. gas, L.P. gas, gas h.p., room or PTAC, none)	15b. HSPF/COP/AFUE:
	(1.77-2-11-2-11-2-11-2-11-2-11-2-11-2-11-	15c. Capacity: 7.4+
16	Hot water system:	16a. Type: £2.50
	(Types: elec., nat. gas, L.P. gas, solar, heat rec., ded. heat pump, other, none)	16b. EF: 4/ 2
	(17) to the transfer of the tr	100. Er:
_		

I hereby certify that the plans and specifications covered by the calculation are in compliance with the Florida Energy Code PREPARED BY: KEYIN BEDU DAWS # DATE: 2-28-3 C	Review of plans and specifications covered by this calculation indicates compliance with the Florida Energy Code Before construction is completed, this building will be inspected for compliance in accordance with Section 553 908, F.S.	
I hereby certify that this building, as designed, is in compliance with the Florida Energy Code	BUILDING OFFICIAL:	
OWNER AGENT: DATE	DATE:	

COLUMBIA COUNTY BUILDING DEPARTMENT

RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR FLORIDA BUILDING CODE 2001

ONE (1) AND TWO (2) FAMILY DWELLINGS

ALL REQUIREMENTS ARE SUBJECT TO CHANGE EFFECTIVE MARCH 1, 2002

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 1606 OF THE FLORIDA BUILDING CODE 2001 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1606 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

- 1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ------ 100 MPH
- 2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE -----110 MPH
- 3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERAL REQUIREMENTS; Two (2) complete sets of plans containing the following:

Applicant Plans Examiner

All drawings must be clear, concise and drawn to scale ("Optional " details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.

Designers name and signature on document (FBC 104.2.1). If licensed architect or engineer, official seal shall be affixed.

Site Plan including:

- a) Dimensions of lot
- b) Dimensions of building set backs
- c) Location of all other buildings on lot, well and septic tank if applicable, and all utility easements.
- d) Provide a full legal description of property.


Wind-load Engineering Summary, calculations and any details required

- a) Plans or specifications must state compliance with FBC Section 1606
- b) The following information must be shown as per section 1606.1.7 FBC
 - a. Basic wind speed (MPH)
 - b. Wind importance factor (I) and building category
 - c. Wind exposure if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated
 - d. The applicable internal pressure coefficient
 - e. Components and Cladding. The design wind pressure in terms of psf (kN/m²), to be used for the design of exterior component and cladding materials not specifically designed by the registered design professional

Elevations including:

- a) All sides
- b) Roof pitch
- c) Overhang dimensions and detail with attic ventilation
- d) Location, size and height above roof of chimneys
- e) Location and size of skylights
- f) Building height
- e) Number of stories





c. Crawl space (if applicable)

	1 2 3 4 5 6 7 8 9 1 1	frame wall All materials making up wall Size and species of studs Sheathing size, type and nailing schedule Headers sized Gable end showing balloon framing detail or gable truss and wall hinge bracing detail All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers) Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating) Fire resistant construction (if applicable) Fireproofing requirements Show type of termite treatment (termicide or alternative method) Slab on grade a. Vapor retardant (6Mil. Polyethylene with joints lapped 6 inches and sealed b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports Indicate where pressure treated wood will be placed Provide insulation R value for the following: a. Attic space b. Exterior wall cavity
	Engine	c. Crawl space (if applicable) rame wall and roof (designed, signed and sealed by Florida Prof. eer or Architect) ming System:
	a) Floor to	russ package including layout and details, signed and sealed by Florida
	-	ered Professional Engineer
		oist size and spacing size and spacing
		ment of joist to girder
		pad requirements where applicable
Ξ, Ξ		Fixture layout
7		layout including:
		es, outlets/receptacles, lighting and all required GFCI outlets identified
	•	
		vice panel and sub-panel size and location(s)
		ocation with type of service entrance (overhead or underground)
g o		ces and HVAC equipment
	g) Arc Fai HVAC inf	ult Circuits (AFCI) in bedrooms
		J sizing equipment or equivalent computation
4 0 0	•	t fans in bathroom
4 0		alculations (dimensions shall match plans)
		em Type (LP or Natural) Location and BTU demand of equipment
		sure Statement for Owner Builders
	*** <u>Notice</u>	Of Commencement Required Before Any Inspections Will Be Done
	a) Size of b) Size of	pump motor pressure tank top valve if used

8. 7

THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

- 1. <u>Building Permit Application:</u> A current Building Permit Application form is to be completed and submitted for all residential projects.
- 2. <u>Parcel Number:</u> The parcel number (Tax ID number) from the Property Appraiser (386) 758-1084 is required. A copy of property deed is also requested.
- 3. <u>Environmental Health Permit or Sewer Tap Approval:</u> A copy of the Environmental Health permit, existing septic approval or sewer tap approval is required before a building permit can be issued.

 (386) 758-1058 (Toilet facilities shall be provided for construction workers)
- 4. <u>City Approval:</u> If the project is to be located within the city limits of the Town of Fort White, prior approval is required. The Town of Fort White approval letter is required to be submitted by the owner or contractor to this office when applying for a Building Permit. (386) 497-2321
- 5. Flood Information: All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.8 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.7 of the Columbia County Land Development Regulations. CERTIFIED FINISHED FLOOR ELEVATIONS WILL BE REQUIRED ON ANY PROJECT WHERE THE BASE FLOOD ELEVATION (100 YEAR FLOOD) HAS BEEN ESTABLISHED.

A development permit will also be required. Development permit cost is \$50.00

- 6. <u>Driveway Connection:</u> If the property does not have an existing access to a public road, then an application for a culvert permit (\$25.00) must be made. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (\$50.00). All culvert waivers are sent to the Columbia County Public Works Department for approval or denial.
- 7. <u>911 Address:</u> If the project is located in an area where the 911 address has been issued, then the proper paperwork from the 911 Addressing Department must be submitted. (386) 752-8787

ALL REQUIRED INFORMATION IS TO BE SUBMITTED FOR REVIEW. YOU WILL BE NOTIFIED WHEN YOUR APPLICATION AND PLANS ARE APPROVED AND READY TO PERMIT. <u>PLEASE DO NOT EXPECT OR REQUEST THAT PERMIT APPLICATIONS BE REVIEWED OR APPROVED WHILE YOU ARE HERE – TIME WILL NOT ALLOW THIS –PLEASE DO NOT ASK</u>

NOTICE:

ADDRESSES BY APPOINTMENT ONLY!

TO OBTAIN A 9-1-1 ADDRESS THE REQUESTER MUST CONTACT THE COLUMBIA COUNTY 9-1-1 ADDRESSING DEPARTMENT AT (386) 752-8787 FOR AN APPOINTMENT TIME AND DATE:

YOU CAN NOT OBTAIN A NEW ADDRESS OVER THE


TELEPHONE. MUST MAKE AN APPOINTMENT!

THE ADDRESSING DEPARTMENT IS LOCATED AT 263 NW LAKE CITY AVENUE (OFF OF WEST U.S. HIGHWAY 90 WEST OF INTERSTATE 75 AT THE COLUMBIA COUNTY EMERGENCY OPERATIONS CENTER).

THE REQUESTER WILL NEED THE FOLLOWING:

- 1. THE PARCEL OR TAX ID NUMBER (SAMPLE: "25-4S-17-12345-123" OR "R12345-123) FOR THE PROPERTY.
- 2. A PLAT, PLAN, SITE PLAN, OR DRAWING SHOWING THE PROPERTY LINES OF THE PARCEL.
 - a. LOCATION OF PLANNED RESIDENT OR BUSINESS STRUCTURE ON THE PROPERTY WITH DISTANCES FROM TWO OF THE PROPERTY LINES TO THE STRUCTURE (SEE SAMPLE BELOW).
 - b. LOCATION OF THE ACCESS POINT (DRIVEWAY, ETC.) ON THE ROADWAY FROM WHICH LOCATION IS TO BE ADDRESSED WITH A DISTANCE FROM A PARALLEL PROPERTY LINE AND OR PROPERTY CORNER (SEE SAMPLE BELOW).
 - c. TRAVEL OF THE DRIVEWAY FROM THE ACCESS POINT TO THE STRUCTURE (SEE SAMPLE BELOW).

SAMPLE:



NOTE: 5 TO 7 WORKING DAYS MAY BE REQUIRED IF ADDRESSING DEPARTMENT NEEDS TO CONDUCT AN ON SITE SURVEY.



AAMA/NWWDA 101/I.S.2-97 TEST REPORT SUMMARY

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 450 /650 TYPE: Aluminum Single Hung Window RATING: H-C30 54 x 90; H-C45 52 x 72*

Title of Test	Results	
Overall Design Pressure	Test Specimen #1	Test Specimen #2
Operating Force	30 psf	47 psf
Air Infiltration	20 lb max, 0.27 cfm/ft ²	N/A
Water Resistance	5.25 psf	N/A
Structural Test Pressure	±45,0 psf	6.0 psf
Deglazing Forced Entry Resistance	Passed	±70.5 psf
- steed Entity Resistance	Grade 10	N/A N/A

Reference should be made to Report No. 01-37589.01 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Adam A. Fodor, Technician

130 Derry Court York, PA 17402-9405

phone: 717.764.7700 fax: 717.764.4129 www.testoci.com

AAF:tjp



AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to:

MI HOME PRODUCTS, INCORPORATED 650 West Market Street Gratz, Pennsylvania 17030-0370

Report No: 01-37589.01

Test Date:

06/29/00

Report Date:

09/11/00

Expiration Date:

06/29/04

Project Summary: Architectural Testing, Inc. (ATI) was contracted to witness tests on a Series/Model 450, aluminum single hung window at the MI Home Products in-plant test facility The samples tested successfully met the performance requirements for the following ratings: Test Specimen #1 H-C30 54 x 90; Test Specimen #2 H-C40 52 x 72*. Test specimen descriptions and results are reported herein.

General Note: An asterisk (*) next to the performance grade indicates that the size tested for optional performance was smaller than the minimum test size for the product type and class.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass

Test Specimen Description

Series/Model: 450

Type: Aluminum Single Hung Window

Test Specimen #1 H-C30 54 x 90

Overall Size: 4' 6-1/2" wide by 7' 6-1/2" high

Sash Size: 4' 4" wide by 3' 9-3/4" high

Fixed Daylight Opening Size: 4' 1-1/2" wide by 3' 6-1/2" high

Screen Size: 4' 2-1/4" wide by 3' 8-1/2" high

130 Derry Court Yerk, PA 17402-9405 phone: 717.764.7700 fax: 717.764.4129 www.testati.com



Test Specimen Description: (Continued)

Test Specimen #2: H-C40 52 x 72*

Overall Size: 4' 4-1/4" wide by 6' 0" high

Sash Size: 4'2" wide by 3'0-1/2" high

Fixed Daylight Opening Size: 3' 11-1/2" wide by 2' 9-1/2" high

Screen Size: 4'0" wide by 2'11" high

The following descriptions apply to all specimens.

Finish: All aluminum was painted.

Glazing Details: The lites utilized 5/8" thick sealed insulating glass units fabricated from two sheets of 3/32" thick clear annealed glass and an InterceptTM spacer system. The sash was channel glazed with a flexible gasket. The fixed lite was interior glazed onto single-sided adhesive foam tape and secured with extruded PVC glazing beads.

Weatherstripping:

Description 0.210" high by 0.270" backed polypile with center fin	<u>Quantity</u> Row	Location Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Stiles
0.300" diameter by 0.187" backed foam-filled vinyl bulb gasket	Row	Bottom rail
0.400' high by 1/2" square polypile dust plug	4	One on each sash corner

Frame Construction: The main frame was constructed of thermally-broken extruded aluminum members with coped, butted and sealed corners. The fixed meeting rail was constructed of an extruded aluminum member with coped, butted and sealed ends fastened with two screws each.



Test Specimen Description: (Continued)

Sash Construction: The sash members were constructed of thermally-broken extruded aluminum members with coped, butted and sealed corners fastened with one screw each.

Screen Construction: The screen was constructed of rolled aluminum members with plastic keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

<u>Description</u>	Quantity	Logaria
Plastic snap latch	1	Location
Block and tackle balance system	2	Midspan of bottom rail
Plastic tilt latch		One per jamb
Metal pivot har	2	One on each end of sash meeting rail
Drainage: Sloped sill	2	One on each end of bottom rail
Probed 200		

Reinforcement: No reinforcement was utilized.

Installation: The test unit was installed into the nominal 2" x 8" Spruce-Pine-Fir #2 wood test buck utilizing the integral nailing fin secured with I" long galvanized roofing nails, 6" from each corner and every 18" on center. The nailing fin was also bedded in polyurethane. The exterior perimeter was blindstopped with wood members and secured with #8 x 3"



Test Results:

The results are tabulated as follows:

Paragraph	Title of Test - Test Method	Results		
Test Specime	e <u>n #1</u> : H-C30 54 x 90		Allowed	
2.2.1.6.1	Operating Force	20 lbs	45 lbs max.	
NY	Air Infiltration per ASTM E 283 @ 1.57 psf (25 mph)	0.27 cfm/ft [*]	0.3 cfm/ft ² max	
Note #1: Th AAMA/NWWL	ne tested specimen meets (or exced) A 101/1.S. 2-97 for air infiltration,	eds) the performance	e levels specified in	
	Water Resistance per ASTM E 54 (with and without screen) WTP = 4.5 psf			
2.1.4.2	Uniform Load Structural per ASTI (Measurements reported were take @ 45.0 psf (exterior) @ 45.0 psf (interior)	No leakage M E 330 n on the fixed meetin 0.03" 0.04"	0.22" max.	
2.2.1.6.2	Deglazing Test per ASTM E 987 In operating direction at 70 lbs		0.22" max.	
	Meeting rail Bottom rail	0.06"/12% 0.06"/12%	0.50"/100% 0.50"/100%	
	In remaining direction at 50 lbs			
	Left stile Right stile	0.06"/12% 0.06"/12%	0.50"/100% 0.50"/100%	
	Forced Entry Resistance per ASTM	F 588-97	7100/0	
	Type: A Grade: 10			

No entry

No entry No entry

No entry

No entry

No entry No entry

No entry

Lock Manipulation Test

Lock Manipulation Test

Test A1 through A5 Test A7



Test Results:

	Paragraph	Title of Test - Test Method	_	
	Test Specimen	#1: (Continued)	Results	Allowed
	Optional Perfor			
	4.3	Water Resistance per ASTM E 547 (with and without screen) WTP = 5.25 psf	No leakage	
	Test Specimen	#2: H-C40 52 X 72*	TTO TERRABE	No leakage
	<u>Ομτίοπαl Perfor</u>	nance		
	4.3	Water Resistance per ASTM E 547 (with and without screen)	and 331	
	4.0	H = 0.0 ps	No leakage	No leakage
		Uniform Load Structural per ASTM (Measurements reported were taken (Loads held for 33 seconds)	E 330 on the fixed meeting	_
	l	@ 47.0 psf (exterior) @ 47.0 psf (interior)	0.04" 0.03"	N/A N/A
etai	((Loads held for 10 seconds) (2) 70.5 psf (exterior) (3) 70.5 psf (interior)	0.07" 0.04"	0.21" max. 0.21" max.
	THAT THE PARTITION FOR	T) = 2 =		

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:

Adam A. Fodor

Technician

Bruce W. Croak

Director - Product/Physical Testing

AAF: 01-37589.01



AAMA/NWWDA 101/I.S.2-97 TEST REPORT SUMMARY

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 450/480/650/680 TYPE: Aluminum Fixed Window RATING: F-C80 72 x 96

Title of Test	
	Results
Overall Design Pressure	80 psf
Air Infiltration	$< 0.01 \text{ cfm/ft}^2$
Water Resistance	12.0 psf
Structural Test Pressure	
Forced Entry Resistance	±120.0 psf
, resistance	Grade 10

Reference should be made to Report No. 01-38781.01 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Adam Fodor, Technician

AF:tjp



AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC. 650 West Market Street Gratz, Pennsylvania 17030-0370

Report No: 01-38781.01

Test Date: 01/23/01

Report Date: 02/22/01 Expiration Date: 01/23/05

Project Summary: Architectural Testing, Inc. (ATI) was contracted to witness tests on a Series/Model 450/480/650/680, aluminum fixed window at the MI Home Products, Inc. in-plant requirements for an F-C80 72 x96 rating. Test specimen description and results are reported herein.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.

Test Specimen Description:

Series/Model: 450/480/650/680

Type: Aluminum Fixed Window

Overall Size: 6' 0-1/4" wide by 8' 0" high

Fixed Daylight Opening Size: 5' 9-1/2" wide by 7' 9-1/2" high

Finish: All aluminum was painted.

Glazing Details: The window utilized a 7/8" thick sealed insulating glass unit fabricated from two sheets of 3/16" thick, clear, tempered glass and a spacer system. The lite was interior glazed onto silicone bedding and dual-sided adhesive foam tape, while secured with aluminum snap-fit glazing beads and polypile weatherstrip.



Test Specimen Description: (Continued)

Frame Construction: The frame was constructed of thermally broken extruded aluminum members with coped, butted and sealed corners fastened with two screws each.

Drainage: No fabricated drainage was utilized.

Reinforcement: No reinforcement was utilized.

Installation: The test unit was installed into the 2" x 8" Spruce-Pine-Fir #2 wood test buck unilizing the integral nailing fin bedded in polyurethane sealant. The nailing fin was secured to the buck with a 1" roofing nail at each corner, midspan of the head and sill, and two spaced evenly at the jambs.

Test Results:

The results are tabulated as follows:

Paragraph	Title of Teat T		
	Title of Test - Test Method	Results	Allowed
2.1.2	Air Infiltration per ASTM E 283	(See Note #1)	
	C	-0.01 c /c2	0.3 cfm/ft ² max.
AAMA/NWWDA	tested specimen meets (or excell 101/I.S. 2-97 for air infiltration.	eds) the performanc	ce levels specified in
	2 27 Joi un injuration.		specifica in

	Water Resistance per ASTM WTP = 4.5 psf	E 547 No leakage	No leakage
2.1.4.2	Uniform Load Structural per (Measurements reported were @ 45.0 psf (exterior) @ 45.0 psf (interior)	ASTM E 330 e taken on the jamb) 0.02" 0.02"	0.38" max. 0.38" max.
	Forced Entry Resistance per	ASTM F 588 07	
	Type: D		

Grade: 10

Hand Manipulation Test

No entry

No entry

Optional Performance

4.3	Water Resistance per ASTM E 547 and 331 WTP = 12.0 psf No leakage	No leakage
	Uniform Load Structural per ASTM E 330 (Measurements reported were taken on the jamb) @ 120.0 psf (exterior) 0.03" @ 120.0 psf (interior) 0.04"	0.38" max. 0.38" max.




Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product which may only be granted by the certification program administrator.


For ARCHITECTURAL TESTING, INC:


Adam Fodor Technician


AF:tjp 01-38781.01 Bruce W. Croak

Director - Product/Physical Testing









Report No. ETC 01-741-10622.0 DC Notification Number ETC 01018 - Date: May 25, 2001

ETC Certification # 99-0416.01

Test Start Date: March 23, 2001 Test End Date: May 1, 2001

Test Requested By: THERMA TRU CORP

108 Mutzfeld Rd.

Butler, IN 46721

Phone 219 - 868 - 5811 Facsimile 219 - 868 - 5190

Tests Conducted: PA 201, PA 202 & PA 203 (with no deviations)

Design Pressures: Specimen I (PA 202) Out-swing +67.0 psf. Specimen 2, -67.0 psf. (PA 202) In-swing +67.0 psf. Specimen 5 -67.0 psf. (PA 201 & 203) In-swing

+67.0 psf. Specimens 3 & 4 -67.0 psf. (PA 201 &203) Out-swing + 67.0 psf. -67.0 psf.

Section 1 - DESCRIPTION OF SERIES:

Model Designation - Therma-Tru Construction Series Opaque Wood Edge Steel Door

Overall Size:

Specimens 1, 3 & 4 - Out-swing Bumper Threshold - 37.5 in. W. x 80.5 in. H. x 4.6 in. D - In-swing Saddle Threshold - 37.5 in. W x 82.0 in. H x 4.6 in. D

Configuration: All Specimens are operable (X)

No. & Size of Boors: All Specimens are opaque door panels 1 active leaf - 36.0 in. W x 79.25 in.H

Section 2 - MATERIAL CHARACTERISTICS:

Frame and Door Material: Finger jointed pine jambs and steel panels.

Florida Registered Professional Engineers Review:

-Joseph L. Doldon .

Signiture:

Section 2 - MATERIAL CHARACTERISTICS Cont.;

Frame Construction:

The head jambs and side jambs are finger jointed pine measuring 4.656 in.W. x 1.211 in. Thk. The head jamb and side jambs are mortised, butted and joined using (3) 0.5 in. Crown x 2 in. - 16 ga. wire staples at each end. The following thresholds were tested, specimens 1, 3 & 4 - Therma-Tru Aluminum Out-swing Bump measuring 4.602 in. x 0.837 in. and attached to the jamb with (2) 0.5 in. Crown x 2.5 in. - 16 ga. wire staples at each end. Specimen 1A was affixed with an add-on high dam sill that increased the height of the original bump threshold to 1.878 in. at the inner most plane of the frame system. Specimens 2 & 5 - Selfadjusting In-swing saddle threshold (Alum/Wood/Vinyl) measuring 5.767 in. x 1.548 in, and attached to the jamb with (2) 0.5 in. Crown x 2.5 in. - 16 ga. wire staples at each end. The hinge jamb was mortised to receive Therma-Tru 4.0 in. x 4.0 in. self-locating hinges located at 9.25 in., 38.5 in. and 67.75 in. from the

Panel Construction:

The panel is constructed from 25 Ga. (0.018 in. min. thick) galvanized and primed coated steel face sheets. The interior cavity of each door is filled with BASF polyurethane foam. The face sheet edges are roll formed to form a mechanical interlock with the hinge (1.234 in. thick x 1,660 in. wide) and latch finger jointed pine stiles (1.242 in. thick x 1.660 in. wide). The stiles are machined to interlock with the steel face sheets. The top rail is finger jointed pine (0.789 in. thick x 1.660 in. wide) and the bottom rail is wood composite (0.892 in. thick by 1.660 in. wide) and kerfed to receive a door sweep (sweep used on in-swing models only). The stiles and rails are pressure fitted and contact cement is used to secure them to the steel face sheets. The hinge stile was mortised at 8.375 in., 37.625 in. and 66.875 in. from the top of the door panel to receive 3 Therma-Tru 4.0" x 4.0" butt type hinges.

Glazing:

N/A

Glazine Material:

N/A

Glazing Method:

N/A

Davlight Opening: N/A

Weather-stripping:

Specimens 1, 3 & 5 Hinge Jamb 1 pc Therma-Tru long reach foam compression weather-strip. Latch Jamb 1 pc Therma-Tru long reach foam compression weather-strip. Head Jamb 1 pc Therma-Tru long reach foam compression weather-strip.

Corner pad seals 2 - 1 at each side jamb at threshold

Specimens 2 & 4

Hinge Jamb 1 pc Therma-Tru short reach foam compression weather-strip. Latch Jamb 1 pc Therma-Tru short reach foam compression weather-strip. Head Jamb 1 pc Therma-Tru short reach foam compression weather-strip. Corner pad seals 2 - 1 at each side jamb at threshold

Specimens 1, 3 & 4 - Out-swing Bump threshold 1 row Thorma-Tru vinyl bulb weather-strip.

Specimens 2 & 5 -Therma-Tru vinyl fixed door bottom sweep.

Florida Registered Professional Engineers Review:

Reg. # 42929, May 25, 2901 - Joseph L. Doldan Signiture:

Section 2 - MATERIAL CHARACTERISTICS (Con't.):

All Specimens (1) Kwikset 700 Series Latchbolt at 44.0 in. from top of panel. Hardware:

(The strikeplate was attached to the jamb with (2) #8 x 2.5 in. PFH WS.)

(1) Kwikset 700 Deadbolt at 38.5 in. from top of panel.

(The strikeplate was attached to the jamb with (2) #8 x 2.5 in. PFH WS.)

(3) Therma-Tru 4 in. butt type hinges (The hinge was fastened to the door panel with (4) #10 x 0.75 in PFH WS and fastened to the jamb with (3) #10 x 0.75 in, PFH WS and (1) #10 x 2.0 in. PFH WS.)

Weepholes:

None

Muntins:

None

Reinforcement:

None

SEALANT:

Latex caulking as needed to seal unit into rough opening.

ADDITIONAL DESCRIPTION:

All specimens were installed in a wood test buck.

Section 3 - INSTALLATION:

Screws and Method of Attachment:

Specimens 1, 2, 3, 4 & 5

14 - # 8 x 2.5 in. PFH WS, used to fasten the frame to the wood buck at head and side jambs.

- (2) header one at 6.0 in. from each end.
- (6) hinge and latch jamb In-swing one at 6.0 in. from each end and (4) additional at 14.0 in. on center. Out-swing one at 6.0 in. from each end and (4) additional at 13.75 in. on center.
- (3) threshold 6.0 from each end and one in the center.

Note - Specimens 2 and 5 (in-swing) were not attached to the wood buck with any screws.

Florida Registered Professional Engineera Review:


Reg. # 42929, May 25, 2901 - Joseph L. Doldan

Signiture:

Section 4 - SEQUENCE OF TESTS PERFORMED:

Test Sequence: PA 202

- 1. Air Infiltration
- 2. 1/2 Test Pressure Positive
- 3. Design Pressure Positive
- 4. 1/2 Test Pressure Negative
- 5. Design Pressure Negative
- 6. Water Infiltration Positive Direction
- 7. Full Test Pressure Positive
- 8. Full Test Pressure Negative
- 9. Forced Entry



Deflection was measured with two (2) Aerospace 2.0" dial indicators: location # 1-SN 213293 and

TEST RESULTS:

AIR INFILTRATION

Air Infiltration Tests were conducted in accordance with DCBCCD PA 202-94

Air at 1.57 psf

Specimen 2

Actual

Allowable

Specimen 1 Out-swing

0.02 CFM/SQ FT

0.34 CFM/SQ FT

In-swing

0.17 CFM/SQ FT

0.34 CFM/SQ FT

WATER INFILTRATION TEST

Water Infiltration Test was conducted in accordance with DCBCCD PA 202 - 94

Specimen 1 Specimen 1A

Out-swing

Water @ 8.25 psf for 15 min.

No water penetration over sill.

Specimen 2

Out-swing In-swine

Water @ 10.0 psf for 15 min. Water @ 2.86 psf for 15 min.

No water penetration over sill. No water penetration over sill.

Note: Specimen 1(renamed 1A for water test) was affixed with an add on prototype threshold increasing the inner plane of the threshold to 1.875 in. above floor to achieve the higher water test pressure of 10.0 PSF.

Florida Registered Professional Engineers Review:

Signiture:

TEST RESULTS Cont.:

STATIC AIR PRESSURE TESTS

Static Tests were conducted in accordance with DCBCCD PA 202-94

	- 0500D 1A 202-94			
Specimen 1	(out-swing)	Design Loads	+ 67.0 psf, - 67.0 psf.	
Range of test Positive loads	Time (Sec.)	Load (psf)	Deflection (in.)	Perm. Set (in.)
1/2 Test Design Test	30 30	50.25 67.00		300 (m.)
	30	100.50	Door T (1) 0.389 Door B (2) 0.372	0.015 0.016
Range of test Negative loads	Time (Sec.)	Load (psf)	Deflection (in.)	Perm. Set (in.)
1/2 Test Design Test	30 30 30	50.25 67.00 100.50	Door T (1) 1 750	, ,
(1) Door T - Ma	IX allowable		Door T (1) 1.750 Door B (2) 1.650	0.281 0.257

(1) Door T - Max. allowable perm. set at completion of test load (0.4% of span) .004 x 79.25 in. = 0.317 in.

(-) DOOR I THIRA. AHOWADIC DOTTI	Set at completion of the second
(I) Done To M.	set at completion of test load $(0.4\% \text{ of span}) .004 \times 79.25 \text{ in.} = 0.317 \text{ in.}$ set at completion of test load $(0.4\% \text{ of span}) .004 \times 79.25 \text{ in.} = 0.317 \text{ in.}$
1) DOOF I - Max allowable name	$(0.476 \text{ OI Span}).004 \times 79.75 \text{ in } = 0.217$
	SCI AI COmpletion of test load (0.40) a " (1.40) III V.31 / III.
	1 1031 1031 (U.4% Of span) 004 - 70 25
	$(1.004 \text{ m}) \cdot 0.04 \text{ m} = (1.317 \text{ m})$
	0.517 111.

Specimen 2	(In-swing)	Design Loads	+ 67.0 psf, - 67.0 psf.	
Range of test Positive loads		Load (psf)	Deflection (in.)	Perm. Set (in.)
1/2 Test Design Test	30 30 30	50.25 67.00	_	(-)
		100.50	Door B (2) 1.510	0.274 0.251
Range of test Negative loads		Load (psf)	Deflection (in.)	Perm. Set (in.)
1/2 Test	30	50.25		
Design Total	30	67.00		
Test	30	100.50	Door T (1) 0.395 Door B (2) 0.365	0.012 0.010

(1) Door T - Max. allowable perm. set at completion of test load (0.4% of span) .004 x 79.25 in. = 0.317 in.

(1) Door T - Max. allowable perm. set at completion of test load (0.4% of span) .004 x 79.25 in. = 0.317 in.

Florida Registered Professional Engineers Review:

Reg. # 42929, May 25, 2001 - Joseph L. Doldan

TEST RESULTS Cont.:

FORCED ENTRY TEST

Forced Entry Test was conducted in accordance with DCBCCD PA202-94

Specimen

Size

Time

Result

Specimen 1

37.5 in. W x 80.5 in. H

30 seconds

(Doors remained locked & shut)

Specimen 2

37.5 in. W x 82.0 in. H

30 seconds

(Doors remained locked & shut)

NOTE: Active door panel remained engaged and was operable before and after all tests.

IMPACT TEST - LARGE MISSILE


Impact tests were conducted in accordance with DCBCCD PA 201-94.

Note:


X measurement from left edge of specimen.

Y measurement from top edge of test specimen.

Type and weight of missile: #2 Southern Yellow Pine, Nominal 2x4, Length approx. 88.25 in., Weight - 9 lb.



X (In-swing)



X (Out-swing)

Specimen 3 Opaque Single Door (Out-swing)

Impact No.	Impact Loc.	Speed (Ft/Sec)	X-Meas. (in.)	Y-Meas. (in.)
1.	1 2	50.1	16.75	40.25
2.		50.2	28.75	71.00

None of the impacts penetrated the specimen and all locks remained engaged.

Florida Registered Professional Engineers Review:

Reg. # 42929

Signiture:

TEST RESULTS Cont.:

IMPACT TEST - LARGE MISSILE Cont:

Specimen 4 Opaque Single Door (Out-swing)

Impact No.	Impact Loc.	Speed (Ft/Sec)	X-Meas (in.)	Y-Meas (in.)
1.	1 2	50.1	18.0	40.0
2.		50.0	28.5	72.5

None of the impacts penetrated the specimen and all locks remained engaged.

Specimen 5 Opaque Single Door (In-swing)

Impact No.	Impact Loc.	Speed (Ft/Sec)	X-Meas (in.)	Y-Meas (in.)
1.	1	50.2	16.75	39.50
2 .	2	50.1	8.0	72.0

None of the impacts penetrated the specimen and all locks remained engaged.

FATIGUE LOADING TEST

Cycle tests were conducted in accordance with DCBCCD PA 203

Specimen 3

Opaque Single Door (Out-swing)

Design Load psf = +67.0 psf, -67.0 psf

Positive	1004-
LOZITIVE	mans

Range of Test	# Cycles	Load (psf)	Cycles/Min. 23 23
+ 0 to 0.5	600	33.5	
+ 0 to 0.6	70	40.2	
+ 0 to 1.3	I	87.1	

671 cycles completed

Negative Loads

Range of Test + 0 to 0.5 + 0 to 0.6 + 0 to 1.3	# Cycles 600 70 1	Load (psf) 33.5 40.2 87.1	Cycles/Min. 23 23

Florida Registered Professional Engineers Review:

671 cycles completed

Reg. # 42929, May 25, 2001 - Joseph L. Doldan

Signiture: <

TEST RESULTS Cont.:

FATIGUE LOADING TEST (Con.L)

Specimen 4

Opaque Single Door (Out-swing)

Design Load paf = -57.0 paf, -67.0 paf

Range of Test	# Cycles	Load (psf)	Cycles/Min. 23 23
+ 0 to 0.5	600	33.5	
+ 0 to 0.6	70	40.2	
+ 0 to 1.3	1	87.1	
	•	8/.1	

671 cycles completed

Negative Loads

Range of Test + 0 to 0.5 + 0 to 0.6 + 0 to 1.3	# Cycles 600 70 1	Load (psf) 33.5 40.2 87.1	<u>Cycles/Min.</u> 23 23
---	----------------------------	------------------------------------	--------------------------------

671 cycles completed

Specimen 5

Opaque Single Door (In-swing)

Design Load psf = +67.0 psf, -67.0 psf

Positive loads

Range of Test + 0 to 0.5 + 0 to 0.6 + 0 to 1.3	# Cycles 600 70 1	Load (psf) 33.5 40.2 87.1	Cycles/Min. 23 23
---	----------------------------	------------------------------------	-------------------------

671 cycles completed

Negative Loads

### Range of Test	# Cycles	Load (psf)	<u>Cycles/Min.</u> 23 23
### 0 to 0.5	600	33.5	
## 0 to 0.6	70	40.2	
## 0 to 1.3	1	87.1	

671 cycles completed

Specimens showed no resultant failure or duress after cycle test. No failure of fasteners. Locks remained engaged. There were no cracks longer than 5 in. x 1/16 in. through which air could pass observed. The door was operable at end of test.

Florida Registered Professional Engineers Review:

8.7-01 Reg. # 42929, May 25, 2001 - Joseph L. Doldan

Signinure: Joseph J. Dola

Section 5 - DRAWINGS TO BE SUBMITTED:

- 1. L-2110 sheets 1 through 10 of 10
- 2. Laboratory Anchor Sketch

Comment:

Nominal 2 mil polyethylene film was used to seal against air leakage during structural loads. The film was used in a manner that did not influence the test results.

Observers:

Steve Kepler - Project Scientist, THERMA-TRU Corp. Rick Wright - Consultant, R.W. Building Consultants, Inc.

Dade County Witness:

Not present

All Tests Witnessed by:

Joseph L. Doldan, P.E. Arthur Murray, ETC Laboratories Bill Yanda, ETC Laboratories

cc: THERMA TRU CORP.

(2)

Rick Wright

(2)

File

(1)

8-7-01

Florida Registered Professional Engineers Review:

Reg. # 42929, May 25, 2001 - Joseph L. Doldan

Signiture:

ragle F. Dolon

Conditions, Terms, and General Notes Regarding These Tests

The product tested has been compared to the detailed drawings, bill of materials and fabrication information supplied by the client so named herein. Our analysis, which includes dimensional and component description comparisons, indicate the tested product and engineering information supplied by the client "Are Equivalent". The report and representative samples will be retained for four years from the date of intrial test.

These test results were obtained by employing all requirements of the designated test methods with no deviations. The test results and specimen supplied for testing are in compliance with the referenced specifications.

The test results are specific to the product tested by this laboratory and of the sample supplied by the client named herein, and they relate to no other product either manufactured by the client, a Fabricator of the client or of installed field performance.

This report does not constitute an AAMA, NWWDA or Dade County certified product under the certification programs of these organizations. The program administrator of these programs and organizations may only grant product certification.

ETC Laboratories makes no opinions or endorsements regarding this product and its performance. This report may not be reproduced or quoted in partial form without the expressed written approval of ETC Laboratories.

ETC Laboratories letters, reports, it's name or insignia or mark are for the exclusive use of the client so named herein and any other use is strictly probibited. The report, letters and the name of ETC Laboratories, its seal or mark shall not be used in any circumstance to the general public or in any advertising.

Limitation of Liability: Due diligence was used in rendering this professional opinion. By acceptance of this report, this client agrees to hold harmless and indemnify ETC Laboratories, it's employees and offices and owners against all claims and demands of any kind whatsoever, which arise out of or in any manner connected with the performance of work referred to herein. ETC laboratories reserves the right to subcontract any and all work for its clients in order to fulfill its contractual obligations for testing to these standards.

For ETC Laboratories

Bill Yanda

Test Technician

Arthur Murray

Laboratory Manager

Wind Engineering Laboratory


87-0

Florida Registered Professional Engineers Roview:

Reg. # 42929. May 25, 2001 - Joseph L. Doldan

Signiture:

uple f. Dold





January 31, 2002

TO: OUR FLORIDA CUSTOMERS:

Effective February 1, 2002, the following TAMKO shingles, as manufactured at TAMKO's Tuscaloosa, Alabama, facility, comply with ASTM D-3161, Type I modified to 110 mph. Testing was conducted using four nails per shingle. These shingles also comply with Florida Building

- Glass-Seal AR
- Elite Glass-Seal AR
- ASTM Heritage 30 AR (formerly ASTM Heritage 25 AR)
- Heritage 40 AR (formerly Heritage 30 AR)
- Heritage 50 AR (formerly Heritage 40 AR)

All testing was performed by Florida State certified independent labs.

Please direct all questions to TAMKO's Technical Services Department at 1-800-641-4691.

TAMKO Roofing Products, Inc.