

DATE 05/08/2006

Columbia County Building Permit

PERMIT
000024480

This Permit Expires One Year From the Date of Issue

APPLICANT J. RUSSELL NORTH PHONE 386.752.6806

ADDRESS 187 NW FOREST MEADOWS AVENUE LAKE CITY FL 32055

OWNER RICHARD HYNES PHONE 386.454.9322

ADDRESS 166 SW SMYRNA PLACE FT. WHITE FL 32038

CONTRACTOR J. RUSSELL NORTH PHONE 386.752.6806

LOCATION OF PROPERTY 47-S TO C-240,TL TO OLD WIRE ROAD,TR TO LANDRUM,TL TO BUCKHEAD,TR TO SMYRNA AND THE LOT IS ON THE R.

TYPE DEVELOPMENT SFD/UTILITY ESTIMATED COST OF CONSTRUCTION 73850.00

HEATED FLOOR AREA 1477.00 TOTAL AREA 2027.00 HEIGHT 18.00 STORIES 1

FOUNDATION CONC WALLS FRAMED ROOF PITCH 6'12 FLOOR CONC

LAND USE & ZONING A-3 MAX. HEIGHT 35

Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00

NO. EX.D.U. 0 FLOOD ZONE XPS DEVELOPMENT PERMIT NO.

PARCEL ID 25-5S-16-03716-120 SUBDIVISION BUCKHEADS

LOT 20 BLOCK PHASE UNIT TOTAL ACRES 10.00

CGC010421

Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor

PRIVATE 06-0383-N BLK JTH N

Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: NOC ON FILE. 1 FOOT ABOVE ROAD.

Check # or Cash 4371

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by

Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by

Framing date/app. by Rough-in plumbing above slab and below wood floor date/app. by

Electrical rough-in date/app. by Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by

Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by

M/H tie downs, blocking, electricity and plumbing date/app. by Pool date/app. by

Reconnection date/app. by Pump pole date/app. by Utility Pole date/app. by

M/H Pole date/app. by Travel Trailer date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 370.00 CERTIFICATION FEE \$ 10.13 SURCHARGE FEE \$ 10.13

MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$

FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ TOTAL FEE 465.26

INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVENIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

**WARRANTY DEED
INDIVID. TO INDIVID.**

Return to Gilchrist Title Services, Inc.
This Instrument Prepared by: Holly Randolph
Address: 204 E. Wade St.
Trenton FL 32693

Inst: 2005024022 Date: 09/28/2005 Time: 13:28
Doc Stamp-Deed : 637.00
SMK DC, P. Dewitt Cason, Columbia County B: 1059 P: 2729

Property Appraisers Parcel Identification Number(s):
R03716-120 2005-1801

This Warranty Deed Made the 16th day of September A.D. 2005 by Scott A. Bachman and Claudine Bachman, husband and wife hereinafter called the grantor, to Richard John Hynes, a married person and Richard Hynes and Barbara Hynes, husband and wife, as joint tenants with right of survivorship whose post office address is P.O. Box 2127, High Springs, FL 32655 hereinafter called the grantee:

(Wherever used herein the terms "grantor" and "grantee" include all the parties to this instrument and the heirs, legal representatives and assigns of individuals, and the successors and assigns of corporations)

Witnesseth: That the grantor, for and in consideration of the sum of \$10.00 and other valuable considerations, receipt whereof is hereby acknowledged, hereby grants, bargains, sells, aliens, remises, releases, conveys and confirms unto the grantee all that certain land situate in COLUMBIA County, State of Florida, viz:

SEE ATTACHED EXHIBIT A

Subject To covenants, conditions, restrictions, reservations, limitations, easements and agreements of record, if any; taxes and assessments for the year 2005 and subsequent years; and to all applicable zoning ordinances and/or restrictions and prohibitions imposed by governmental authorities, if any,

Together, with all the tenements, hereditament and appurtenances thereto belonging or in anywise appertaining.

To Have and to Hold, the same in fee simple forever.

And the grantor hereby covenants with said grantee that the grantor is lawfully seized of said land in fee simple; that the grantor has good right and lawful authority to sell and convey said land, and hereby warrants the title to said land and will defend the same against the lawful claims of all persons.

In Witness Whereof, the said grantor has signed and sealed these presents the day and year first above written.

Signed, sealed and delivered in the presence of:

Michelle Moore

Witness:

Printed Name: Michelle Moore

Scott A. Bachman

Signature Scott A. Bachman

P.O. Address: 3735 Tranquility Drive
Melbourne, FL 32934

Kathy A. Myers

Witness:

Printed Name: Kathy A Myers

Claudine Bachman

Signature Claudine Bachman

P.O. Address: 3735 Tranquility Drive
Melbourne, FL 32934

Linda Abbott

Witness:

Printed Name: Linda Abbott

Philip Silver


Witness:

Printed Name: Philip Silver

STATE OF FLORIDA

COUNTY OF Brevard

The foregoing instrument was acknowledged before me this 16th day of September, 2005 by Scott A. Bachman and Claudine Bachman, who produced as identification and who did not take an oath.



Notary Public, State and County Aforesaid

[Signature]

Notary Signature

Inst:2005024022 Date:09/28/2005 Time:13:28

Doc Stamp-Deed : 637.00

DC,P.DeWitt Cason,Columbia County B:1059 P:2730

EXHIBIT A

Lot No. 20 – BUCKHEAD WOODS (Unrecorded)


Commence at the SW corner of Section 25, Township 5 South, Range 16 East, COLUMBIA County, Florida and run S 89°36'44" E, along the South line of said Section 25, a distance of 1481.07 feet to the Point of Beginning; thence N 00°53'29" E, parallel to the East line of the West ½ of the Southeast ¼ of said Section 25, a distance of 1037.05 feet to a point on the Southerly line of Buckhead Woods Road (a private road); thence S 89°54'17" E, along said Southerly line, 420.06 feet; thence S 00°53'29" W, parallel to the East line of the West ½ of the Southeast ¼, a distance of 1039.20 feet to a point on the South line of said Section 25; thence N 89°36'44" W, along said South line, 420.04 feet to the Point of Beginning, all lying and being in COLUMBIA County, Florida.

SUBJECT TO a power line easement over and across the North 25.00 feet thereof.

ALSO:

TOGETHER WITH AND SUBJECT TO easements as described in O.R. Book 801, Page 68; O.R. Book 805, Page 225; O.R. Book 817, Page 996 and O.R. Book 821, Page 494.

37
THIS INSTRUMENT WAS PREPARED BY:
FIRST FEDERAL SAVINGS BANK OF FLORIDA
4705 WEST U.S. HIGHWAY 90
P.O. BOX 2029
LAKE CITY, FLORIDA 32056



STATE OF FLORIDA, COUNTY OF COLUMBIA
I HEREBY CERTIFY, that the above and foregoing
is a true copy of the original filed in this office.
P. DEWITT CASON, CLERK OF COURTS

By Dannie Dora
Deputy Clerk
Date April 3, 2006

PERMIT NO. _____

TAX FOLIO NO. _____

NOTICE OF COMMENCEMENT

STATE OF FLORIDA
COUNTY OF Columbia

The undersigned hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

1. Description of property: SEE EXHIBIT "A" ATTACHED HERETO
2. General description of improvement: Construction of Dwelling
3. Owner information:
 - a. Name and address: RICHARD JOHN HYNES, RICHARD HYNES and BARBARA HYNES
7219 NE 21st Place, High Springs, FL 32643
 - b. Interest in property: Fee Simple
 - c. Name and address of fee simple title holder (if other than Owner): NONE
4. Contractor (name and address): RUSSELL NORTH CONSTRUCTION
347 NW Streamside Court, Lake City, FL 32055
5. Surety:
 - a. Name and address: _____ Inst:2006008296 Date:04/05/2006 Time:13:28
_____ DC,P.Dewitt Cason,Columbia County B:1079 P:1771
 - b. Amount of bond: _____
6. Lender: **FIRST FEDERAL SAVINGS BANK OF FLORIDA**
4705 WEST U.S. HIGHWAY 90
P. O. BOX 2029
LAKE CITY, FLORIDA 32056
7. Persons within the State of Florida designated by Owner upon whom notices or other document may be served as provided by Section 713.13 (1) (a) 7., Florida Statutes: NONE
8. In addition to himself, Owner designates PAULA HACKER of FIRST FEDERAL SAVINGS BANK OF FLORIDA, 4705 West U.S. Highway 90 / P. O. Box 2029, Lake City, Florida 32056 to receive a copy of the Lienor's Notice as provided in Section 713.13 (1) (b), Florida Statutes.
9. Expiration date of notice of commencement (the expiration date is 1 year from the date of recording unless a different date is specified).

Richard J. Hynes, Barbara O. Hynes
Borrower Name

Richard J. Hynes, Barbara O. Hynes
Co-Borrower Name

The foregoing instrument was acknowledged before me this 30th day of March, 2006, by Richard J. Hynes, Richard Hynes & Barbara*, who is personally known to me or who has produced driver's license for identification.

* O. Hynes

Terry McDavid
Notary Public
My Commission Expires _____



EXHIBIT "A"

LOT 20 OF BUCKHEAD WOODS, UNRECORDED:

COMMENCE AT THE SW CORNER OF SECTION 25, TOWNSHIP 5 SOUTH, RANGE 16 EAST, COLUMBIA COUNTY, FLORIDA AND RUN S 89°36'44" E, ALONG THE SOUTH LINE OF SAID SECTION 25, A DISTANCE OF 1481.07 FEET TO THE POINT OF BEGINNING; THENCE N 00°53'29" E, PARALLEL TO THE EAST LINE OF THE WEST 1/2 OF THE SOUTHEAST 1/4 OF SAID SECTION 25, A DISTANCE OF 1037.05 FEET TO A POINT ON THE SOUTHERLY LINE OF BUCKHEAD WOODS ROAD (A PRIVATE ROAD); THENCE S 89°54'17" E, ALONG SAID SOUTHERLY LINE, 420.06 FEET; THENCE S 00°53'29" W, PARALLEL TO THE EAST LINE OF THE WEST 1/2 OF THE SOUTHEAST 1/4, A DISTANCE OF 1039.20 FEET TO A POINT ON THE SOUTH LINE OF SAID SECTION 25; THENCE N 89°36'44" W, ALONG SAID SOUTH LINE, 420.04 FEET TO THE POINT OF BEGINNING, ALL LYING BEING COLUMBIA COUNTY, FLORIDA.

TOGETHER WITH and SUBJECT TO Easements as described in OR Book 801, Page 68, OR Book 805, Page 225, OR Book 817, Page 996 and OR Book 821 Page 494, all of the public records of Columbia County, Florida.

Inst:2006008296 Date:04/05/2006 Time:13:28

DC,P.DeWitt Cason,Columbia County B:1079 P:1772

Columbia County Building Permit Application

Revised 9-23-04

For Office Use Only Application # 0604-92 Date Received 4/27/06 By CH Permit # 1069/24480
Application Approved by - Zoning Official BLK Date 04.25.06 Plans Examiner DKJH Date 5-5-06
Flood Zone X Per Survey Development Permit NIA Zoning A-3 Land Use Plan Map Category A-3
Comments _____

Applicants Name J. Russell North Phone 386-454-9322 Fax 758-4570
Address 182 NW Forest Meadows Ave. Cape Coral, FL 33914
Owners Name Richard Hynes Phone 386-454-9322
911 Address 166 Symra Pl. Ft. White, FL 32038
Contractors Name Russell North Phone 752-6806
Address 187 NW Forest Meadows Av.
Fee Simple Owner Name & Address Richard Hynes (See above)
Bonding Co. Name & Address _____
Architect/Engineer Name & Address Mark Disoway
Mortgage Lenders Name & Address First Federal
Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progressive Energy
Property ID Number 25-55-16E-03716-120 Estimated Cost of Construction \$100,000
Subdivision Name Buckhead Woods Unrec. Lot 20 Block _____ Unit _____ Phase _____
Driving Directions SR 47 South, TL on County Rd 240, TR on Old White Rd, TL on Landrum, TR on Buckhead, TL on Smyrna Place, Lot on Rt.
Type of Construction Single Family Number of Existing Dwellings on Property 10
Total Acreage 10 Lot Size 10 Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
Actual Distance of Structure from Property Lines - Front 220' Side 210' Side 160' Rear 910'
Total Building Height 18' Number of Stories 1 Heated Floor Area 1477 Roof Pitch 6/12
Porch 222 Garage 328 TOTAL 2,027

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Russell North
Owner Builder or Agent (Including Contractor)

STATE OF FLORIDA
COUNTY OF COLUMBIA

Sworn to (or affirmed) and subscribed before me
this 18th day of April 20 06
Personally known ✓ or Produced Identification _____

Russell North
Contractor Signature
Contractors License Number CGC 010421
Competency Card Number _____
NOTARY STAMP/SEAL
Notary Public for the State of Florida
Eloise Reynolds
My Commission DD47190
Expires 07/04/2009
Notary Signature

Columbia County Property Appraiser

DB Last Updated: 4/6/2006

Parcel: 25-5S-16-03716-120

2006 Proposed Values

Tax Record

Property Card

Interactive GIS Map

Print

Owner & Property Info

Search Result: 1 of 1

Owner's Name	HYNES RICHARD JOHN & (JTWRS)
Site Address	BUCKHEAD WOODS
Mailing Address	RICHARD & BARBARA HYNES P O BOX 2127 HIGH SPRINGS, FL 32655
Description	AKA LOT 20 BUCKHEAD WOODS UNR: COMM SW CORNER RUN E1481.07 TO POB, N 1037.05 FT TO A PTWD 1059-2729 JTWRS. RUN E ALONG R/W 420.06 FT, S TO POB, N 1037.05 FT TO A PT POB. ORB 819-227, DC PATSY 1039.20 FT, W 420.04 FT TO COMM SW CORNER RUN E1481.07 ON S R/W BUCKHEAD WOODS RD, HAYES 1023-1187, WD 1023-1188, AKA LOT 20 BUCKHEAD WOODS UNR:

Use Desc. (code)	NO AG ACRE (009900)
Neighborhood	25516.01
Tax District	3
UD Codes	MKTA02
Market Area	02
Total Land Area	10.010 ACRES

Property & Assessment Values

Mkt Land Value	cnt: (1)	\$64,064.00
Ag Land Value	cnt: (0)	\$0.00
Building Value	cnt: (0)	\$0.00
XFOB Value	cnt: (0)	\$0.00
Total Appraised Value		\$64,064.00

Just Value	\$64,064.00
Class Value	\$0.00
Assessed Value	\$64,064.00
Exempt Value	\$0.00
Total Taxable Value	\$64,064.00

Sales History

Sale Date	Book/Page	Inst. Type	Sale Vlmp	Sale Qual	Sale RCode	Sale Price
9/16/2005	1059/2729	WD	V	Q		\$91,000.00
7/30/2004	1023/1188	WD	V	Q		\$58,000.00
3/7/1996	819/227	WD	V	Q		\$23,500.00

Building Characteristics

Bldg Item	Bldg Desc	Year Blt	Ext. Walls	Heated S.F.	Actual S.F.	Bldg Value
			NONE			

Extra Features & Out Buildings

Code	Desc	Year Blt	Value	Units	Dims	Condition (% Good)
						NONE

Land Breakdown

Lnd Code	Desc	Units	Adjustments	Eff Rate	Lnd Value
009900	AC NON-AG (MKT)	10.010 AC	1.00/1.00/1.00/1.00	\$6,400.00	\$64,064.00

Columbia County Property Appraiser

DB Last Updated: 4/6/2006

1 of 1



Columbia County Property Appraiser

J. Doyle Crews, CFA - Lake City, Florida - 386-758-1083

PARCEL: 25-5S-16-03716-120 - NO AG ACRE (009900)

AKA LOT 20 BUCKHEAD WOODS UNR: COMM SW CORNER RUN E1481.07 TO POB, N 1037.05 FT TO A PT

Name:	HYNES RICHARD JOHN & (JTWS)	LandVal	\$64,064.00
Site:	BUCKHEAD WOODS	BldgVal	\$0.00
	RICHARD & BARBARA HYNES	ApprVal	\$64,064.00
Mail:	P O BOX 2127	JustVal	\$64,064.00
	HIGH SPRINGS, FL 32655	Assd	\$64,064.00
Sales	9/16/2005 \$91,000.00 V / Q	Exmpt	\$0.00
Info	7/30/2004 \$58,000.00 V / Q	Taxable	\$64,064.00
	3/7/1996 \$23,500.00 V / Q		

0 190 380 570 ft




This information, GIS Map Updated: 4/6/2006, was derived from data which was compiled by the Columbia County Property Appraiser Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data herein, it's use, or it's interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.

**Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan**
Permit Application Number: 060383N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

HYNES/CR 05-3474



Site Plan Submitted By Paul L. Lipp Date 4/14/06
Plan Approved ☒ Not Approved ☐ Date 4/24/06

By M. O. N. Columbia CPHU

Notes: _____

COLUMBIA COUNTY 9-1-1 ADDRESSING

P. O. Box 1787, Lake City, FL 32056-1787

PHONE: (386) 758-1125 * FAX: (386) 758-1365 * Email: ron_croft@columbiacountyfla.com

Addressing Maintenance

To maintain the Countywide Addressing Policy you must make application for a 9-1-1 Address at the time you apply for a building permit. The established standards for assigning and posting numbers to all principal buildings, dwellings, businesses and industries are contained in Columbia County Ordinance 2001-9. The addressing system is to enable Emergency Service Agencies to locate you in an emergency, and to assist the United States Postal Service and the public in the timely and efficient provision of services to residents and businesses of Columbia County.

DATE REQUESTED: 4/6/2006 DATE ISSUED: 4/12/2006

ENHANCED 9-1-1 ADDRESS:

166 SW SMYRNA

PL

FORT WHITE FL 32038

PROPERTY APPRAISER PARCEL NUMBER:

25-5S-16-03716-120

Remarks:

LOT 20 BUCKHEAD WOODS UNR S/D

Address Issued By: 

Columbia County 9-1-1 Addressing / GIS Department

NOTICE: THIS ADDRESS WAS ISSUED BASED ON LOCATION INFORMATION RECEIVED FROM THE REQUESTER. SHOULD, AT A LATER DATE, THE LOCATION INFORMATION BE FOUND TO BE IN ERROR, THIS ADDRESS IS SUBJECT TO CHANGE.

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs Residential Whole Building Performance Method A

Project Name:	604132NorthRussellHynes,RichardResidence	Builder:	
Address:	Lot: Lot 2, Sub: Buckhead Estate, Plat:	Permitting Office:	<i>Columbia</i>
City, State:	, FL	Permit Number:	<i>24980</i>
Owner:	Hynes Richard	Jurisdiction Number:	<i>221006</i>
Climate Zone:	North		

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 32.0 kBtu/hr
3. Number of units, if multi-family	1		SEER: 10.00
4. Number of Bedrooms	3	b. N/A	
5. Is this a worst case?	No	c. N/A	
6. Conditioned floor area (ft²)	1477 ft²	13. Heating systems	
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		a. Electric Heat Pump	Cap: 32.0 kBtu/hr
a. U-factor:	Description Area		HSPF: 7.00
(or Single or Double DEFAULT) 7a. (Dble Default)	85.0 ft²	b. N/A	
b. SHGC:		c. N/A	
(or Clear or Tint DEFAULT) 7b. (Clear)	85.0 ft²	14. Hot water systems	
8. Floor types		a. Electric Resistance	Cap: 40.0 gallons
a. Slab-On-Grade Edge Insulation	R=0.0, 214.0(p) ft		EF: 0.93
b. N/A		b. N/A	
c. N/A		c. Conservation credits	
9. Wall types		(HR-Heat recovery, Solar	
a. Frame, Wood, Exterior	R=13.0, 1347.0 ft²	DHP-Dedicated heat pump)	
b. Frame, Wood, Adjacent	R=13.0, 188.0 ft²	15. HVAC credits	
c. N/A		(CF-Ceiling fan, CV-Cross ventilation,	
d. N/A		HF-Whole house fan,	
e. N/A		PT-Programmable Thermostat,	
10. Ceiling types		MZ-C-Multizone cooling,	
a. Under Attic	R=30.0, 1477.0 ft²	MZ-H-Multizone heating)	
b. N/A			
c. N/A			
11. Ducts			
a. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 150.0 ft		
b. N/A			

Glass/Floor Area: 0.06

Total as-built points: 20789

Total base points: 24116

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: *YBen Smith*

DATE: *4-18-06*

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: _____

DATE: _____

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL: _____

DATE: _____



¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: Lot 2, Sub: Buckhead Estate, Plat: , , FL,

PERMIT #:

BASE				AS-BUILT										
GLASS TYPES														
.18 X Conditioned X BSPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt			Area X SPM X SOF = Points						
.18	1477.0	20.04	5327.8	Double, Clear	N	9.0	7.0	20.0	19.20	0.67	258.3			
				Double, Clear	W	23.0	7.0	20.0	38.52	0.37	288.6			
				Double, Clear	N	1.5	5.5	15.0	19.20	0.93	267.3			
				Double, Clear	E	1.5	5.5	15.0	42.06	0.90	565.5			
				Double, Clear	S	1.5	5.5	15.0	35.87	0.83	447.7			
				As-Built Total:						85.0			1827.5	
WALL TYPES				Area X BSPM = Points				Type	R-Value		Area X SPM		=	Points
Adjacent	188.0	0.70	131.6	Frame, Wood, Exterior			13.0	1347.0	1.50		2020.5			
Exterior	1347.0	1.70	2289.9	Frame, Wood, Adjacent			13.0	188.0	0.60		112.8			
Base Total:		1535.0	2421.5	As-Built Total:				1535.0		2133.3				
DOOR TYPES				Area X BSPM = Points				Type			Area X SPM		=	Points
Adjacent	20.0	1.60	32.0	Exterior Insulated			40.0		4.10		164.0			
Exterior	60.0	4.10	246.0	Exterior Insulated			20.0		4.10		82.0			
				Adjacent Insulated			20.0		1.60		32.0			
Base Total:		80.0	278.0	As-Built Total:				80.0		278.0				
CEILING TYPES				Area X BSPM = Points				Type	R-Value		Area X SPM X SCM		=	Points
Under Attic	1477.0	1.73	2555.2	Under Attic			30.0	1477.0	1.73 X 1.00		2555.2			
Base Total:		1477.0	2555.2	As-Built Total:				1477.0		2555.2				
FLOOR TYPES				Area X BSPM = Points				Type	R-Value		Area X SPM		=	Points
Slab	214.0(p)	-37.0	-7918.0	Slab-On-Grade Edge Insulation			0.0	214.0(p)	-41.20		-8816.8			
Raised	0.0	0.00	0.0											
Base Total:		-7918.0		As-Built Total:				214.0		-8816.8				
INFILTRATION				Area X BSPM = Points						Area X SPM		=	Points	
		1477.0	10.21	15080.2					1477.0	10.21	15080.2			

SUMMER CALCULATIONS**Residential Whole Building Performance Method A - Details**

ADDRESS: Lot: Lot 2, Sub: Buckhead Estate, Plat: , , FL,

PERMIT #:

BASE				AS-BUILT						
Summer Base Points: 17744.7				Summer As-Built Points: 13057.3						
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component (System - Points)	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Cooling Points	
17744.7		0.4266	7569.9	(sys 1: Central Unit 32000 btuh ,SEER/EFF(10.0) Ducts:Unc(S),Unc(R),Int(AH),R6.0(INS) 13057	1.00	(1.09 x 1.147 x 0.91)	0.341	1.000	5070.2	
				13057.3	1.00	1.138	0.341	1.000	5070.2	

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: Lot 2, Sub: Buckhead Estate, Plat: , , FL,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X WPM X WOF = Points				
.18	1477.0	12.74	3387.1	Double, Clear	N	9.0	7.0	20.0	24.58	1.02	502.0
				Double, Clear	W	23.0	7.0	20.0	20.73	1.24	513.1
				Double, Clear	N	1.5	5.5	15.0	24.58	1.00	369.8
				Double, Clear	E	1.5	5.5	15.0	18.79	1.04	293.5
				Double, Clear	S	1.5	5.5	15.0	13.30	1.15	228.8
				As-Built Total:				85.0	1907.2		
WALL TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	188.0	3.60	676.8	Frame, Wood, Exterior	13.0		1347.0	3.40		4579.8	
Exterior	1347.0	3.70	4983.9	Frame, Wood, Adjacent	13.0		188.0	3.30		620.4	
Base Total:				1535.0		5660.7					
				As-Built Total:		1535.0		5200.2			
DOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	20.0	8.00	160.0	Exterior Insulated			40.0	8.40		336.0	
Exterior	60.0	8.40	504.0	Exterior Insulated			20.0	8.40		168.0	
				Adjacent Insulated			20.0	8.00		160.0	
Base Total:				80.0		664.0					
				As-Built Total:		80.0		664.0			
CEILING TYPES Area X BWPM = Points				Type	R-Value		Area X WPM X WCM = Points				
Under Attic	1477.0	2.05	3027.8	Under Attic	30.0		1477.0	2.05 X 1.00		3027.8	
Base Total:				1477.0		3027.8					
				As-Built Total:		1477.0		3027.8			
FLOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Slab	214.0(p)	8.9	1904.6	Slab-On-Grade Edge Insulation	0.0		214.0(p)	18.80		4023.2	
Raised	0.0	0.00	0.0								
Base Total:				1904.6		4023.2					
				As-Built Total:		214.0		4023.2			
INFILTRATION Area X BWPM = Points								Area X WPM = Points			
1477.0 -0.59 -871.4								1477.0 -0.59 -871.4			

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: Lot 2, Sub: Buckhead Estate, Plat: , , FL,

PERMIT #:

BASE				AS-BUILT						
Winter Base Points:		13772.8		Winter As-Built Points:				13951.1		
Total Winter Points	X	System Multiplier	= Heating Points	Total Component (System - Points)	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Heating Points	
13772.8		0.6274	8641.0	(sys 1: Electric Heat Pump 32000 btuh ,EFF(7.0) Ducts:Unc(S),Unc(R),Int(AH),R6.0 13951.1 1.000 (1.069 x 1.169 x 0.93) 0.487 1.000 7898.4						
				13951.1	1.00	1.162	0.487	1.000	7898.4	

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: Lot 2, Sub: Buckhead Estate, Plat: , , FL,

PERMIT #:

BASE					AS-BUILT					
WATER HEATING										
Number of Bedrooms	X	Multiplier	=	Total	Tank Volume	EF	Number of Bedrooms	X	Tank X Ratio	Credit X Multiplier = Total Multiplier
3		2635.00		7905.0	40.0	0.93	3		1.00	2606.67
					As-Built Total:					7820.0

CODE COMPLIANCE STATUS									
BASE					AS-BUILT				
Cooling Points	+	Heating Points	+	Hot Water Points = Total Points	Cooling Points	+	Heating Points	+	Hot Water Points = Total Points
7570		8641		7905	5070		7898		7820

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: Lot 2, Sub: Buckhead Estate, Plat: , , FL,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 85.7

The higher the score, the more efficient the home.

Hynes Richard, Lot: Lot 2, Sub: Buckhead Estate, Plat: , , FL,

1. New construction or existing	New	___	12. Cooling systems	
2. Single family or multi-family	Single family	___	a. Central Unit	Cap: 32.0 kBtu/hr
3. Number of units, if multi-family	1	___		SEER: 10.00
4. Number of Bedrooms	3	___	b. N/A	___
5. Is this a worst case?	No	___	c. N/A	___
6. Conditioned floor area (ft²)	1477 ft²	___		___
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		___	13. Heating systems	
a. U-factor:	Description Area	___	a. Electric Heat Pump	Cap: 32.0 kBtu/hr
(or Single or Double DEFAULT)	7a. (Dble Default) 85.0 ft²	___		HSPF: 7.00
b. SHGC:		___	b. N/A	___
(or Clear or Tint DEFAULT)	7b. (Clear) 85.0 ft²	___	c. N/A	___
8. Floor types		___		___
a. Slab-On-Grade Edge Insulation	R=0.0, 214.0(p) ft	___	14. Hot water systems	
b. N/A	___	___	a. Electric Resistance	Cap: 40.0 gallons
c. N/A	___	___		EF: 0.93
9. Wall types		___	b. N/A	___
a. Frame, Wood, Exterior	R=13.0, 1347.0 ft²	___	c. Conservation credits	___
b. Frame, Wood, Adjacent	R=13.0, 188.0 ft²	___	(HR-Heat recovery, Solar	___
c. N/A	___	___	DHP-Dedicated heat pump)	___
d. N/A	___	___	15. HVAC credits	___
e. N/A	___	___	(CF-Ceiling fan, CV-Cross ventilation,	___
10. Ceiling types		___	HF-Whole house fan,	___
a. Under Attic	R=30.0, 1477.0 ft²	___	PT-Programmable Thermostat,	___
b. N/A	___	___	MZ-C-Multizone cooling,	___
c. N/A	___	___	MZ-H-Multizone heating)	___
11. Ducts		___		___
a. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 150.0 ft	___		___
b. N/A	___	___		___

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____

Date: _____

Address of New Home: _____

City/FL Zip: _____



**NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStarTM designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.*



**AAMA/NWWDA 101/LS.2-97
TEST REPORT SUMMARY**

Rendered to:

MI HOME PRODUCTS, INC.


SERIES/MODEL: 650

TYPE: Aluminum Picture Window


Title of Test	Results
Rating	F-R45 60 x 80
Overall Design Pressure	+45.0 psf -47.2 psf
Air Infiltration	0.04 cfm/ft ²
Water Resistance	8.25 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41135.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.


Mark A. Hess, Technician

MAH:nlb


Allen N. Reeves
1 APRIL 2002



Architectural Testing

AAMA/NWWDA 101/L.S.2-97 TEST REPORT

Rendered to:

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41135.01

Test Date: 03/07/02

Report Date: 03/26/02

Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650, aluminum picture window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a F-R45 60 x 80 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/L.S.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650

Type: Aluminum Picture Window

Overall Size: 5' 0" wide by 6' 8" high


Daylight Opening Size: 4' 9-1/4" wide by 6' 5-1/4" high

Finish All aluminum was white.

Glazing Details: The test specimen utilized 7/8" thick, sealed insulating glass constructed from two sheets of 3/16" thick, clear annealed glass and a metal reinforced butyl spacer system. The glass was interior glazed against double-sided adhesive foam tape and secured with aluminum snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen M. Reeves
1 APR 12 2002





Test Specimen Description: (Continued)

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss.


Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck. #8 x 2-1/2" installation screws were utilized 18" on center around the interior perimeter. Polyurethane was utilized to seal the exterior.


Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.04 cfm/ft ²	0.3 cfm/ft ² max.
<i>Note #1: The tested specimen meets the performance levels specified in AAMA/NWWDA 101/I.S. 2-97 for air infiltration.</i>			
	Water Resistance (ASTM E 547-00) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the jamb) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.01" 0.01"	0.41" max. 0.41" max.
2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the jamb) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.0" 0.01"	0.29" max. 0.29" max.



Allen H. Reeves
1 APRIL 2002



Test Results: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
	Forced Entry Resistance (ASTM F 588-97)		
	Type: D		
	Grade: 10		
	Hand and Tool Manipulation Test	No entry	No entry
<u>Optional Performance</u>			
4.3	Water Resistance (ASTM E 547-00)		
	WTP = 8.25 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97)		
	(Measurements reported were taken on the jamb)		
	(Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.02"	0.41" max.
	@ 47.2 psf (negative)	0.02"	0.41" max.
	Uniform Load Structural (ASTM E 330-97)		
	(Measurements reported were taken on the jamb)		
	(Loads were held for 10 seconds)		
	@ 67.5 psf (positive)	0.01"	0.29" max.
	@ 70.8 psf (negative)	0.02"	0.29" max.

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess
Technician


MAH:nlb
01-41135.01

Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002



WOOD-EDGE STEEL DOORS

APPROVED ARRANGEMENT:



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itssemko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Note:
Units of other sizes are covered by this report as long as the panels used do not exceed 3'0" x 6'8".

Single Door with 2 Sidelites
Maximum unit size = 9'0" x 6'8"

Design Pressure
+40.5/-40.5
Limited water unless special threshold design is used.

Large Missile Impact Resistance
Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed - see MAD-WL-MA0004-02 or MAD-WL-MA0007-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed - see MID-WL-MA0004-02.

APPROVED DOOR STYLES:

1/4 GLASS:



100 Series



133, 135 Series



136 Series



680 Series



822 Series

1/2 GLASS:



105 Series*



106, 160 Series*



129 Series*



200 Series*



12 R/L, 23 R/L, 24 R/L
Series*



107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

Johnson
EntrySystems

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite
Masonite International Corporation

WOOD-EDGE STEEL DOORS

APPROVED DOOR STYLES: 3/4 GLASS:



404 Series



410 Series



450 Series

FULL GLASS:



109 Series



114, 120, 122
Series



152 Series



149 Series



300 Series

APPROVED SIDELITE STYLES:



680 Series



129 Series



200 Series



12R, 12L, 23R,
23L, 24R, 24L
Series



450 Series



152 Series



149 Series



109 Series



120, 122 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12; NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab and sidelite panels glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. - License Number 56533



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itssemko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Johnson
EntrySystems™

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.




Exclusively from

Masonite International Corporation

XX

Glazed Inswing Unit

COP-WL-JH4142-02

WOOD-EDGE STEEL DOORS**APPROVED ARRANGEMENT:**

Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITSA/WH website (www.itsaemko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Note:

Units of other sizes are covered by this report as long as the panels used do not exceed 3'0" x 6'8".

Double Door

Maximum unit size = 6'0" x 6'8"

Design Pressure

+40.5/-40.5

Limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed - see MAD-WL-MA0002-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed - see MID-WL-MA0002-02.

APPROVED DOOR STYLES:**1/4 GLASS:**

100 Series



133, 135 Series



136 Series



680 Series



822 Series

1/2 GLASS:

105 Series*



106, 160 Series*



129 Series*



200 Series*



12 R/L, 23 R/L, 24 R/L Series*



107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

Johnson™
EntrySystems

June 17, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite®
Masonite International Corporation

XX

Glazed Inswing Unit

COP-WL-JH4142-02

WOOD-EDGE STEEL DOORS**APPROVED DOOR STYLES:****3/4 GLASS:**

404 Series



410 Series



450 Series

FULL GLASS:

109 Series

114, 120, 122
Series

152 Series



149 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12; NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. – License Number 56533



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.etsmko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Johnson
EntrySystems

June 17, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.




Exclusively from
Masonite
Masonite International Corporation

X

Opaque Inswing Unit

COP-WL-JH4101-02

WOOD-EDGE STEEL DOORS**APPROVED ARRANGEMENT:****Note:**

Units of other sizes are covered by this report as long as the panel used does not exceed 3'0" x 6'8".



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.etsmko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Single Door
Maximum unit size = 3'0" x 6'8"

Design Pressure
+66.0/-66.0

limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is NOT REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed - see MAD-WL-MA0001-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed - see MID-WL-MA0001-02.

APPROVED DOOR STYLES:

Flush



Arch Top 3-panel



3-panel



6-panel



New England 4-panel



Eyebrow 4-panel



8-panel



9-panel



15-panel



5-panel



5-panel with scroll



Eyebrow 5-panel



Eyebrow 5-panel with scroll

Johnson™
EntrySystems

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.

PREMDOR®
Premium Quality Doors



Exclusively from

Masonite®
Masonite International Corporation

Y

Opaque Inswing Unit

COP-WL-JH4101-02

WOOD-EDGE STEEL DOORS

CERTIFIED TEST REPORTS:

NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA201, PA202 and PA203.

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN ACCORDANCE WITH
MIAMI-DADE BCCO
PA201, PA202 & PA203

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

Kurt L Balthaz

State of Florida, Professional Engineer
Kurt Balthazor, P.E. – License Number 56533



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itssemko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Johnson
EntrySystems

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite International Corporation

Residential System Sizing Calculation

Summary

Hynes Richard

, FL

Project Title:
604132NorthRussellHynes, Richard Residence

Class 3 Rating
Registration No. 0
Climate: North


4/18/2006

Location for weather data: Gainesville - Defaults: Latitude(29) Altitude(152 ft.) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(54gr.)			
Winter design temperature	33 F	Summer design temperature	92 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	37 F	Summer temperature difference	17 F
Total heating load calculation	27395 Btuh	Total cooling load calculation	17333 Btuh
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	116.8 32000	Sensible (SHR = 0.75)	190.4 24000
Heat Pump + Auxiliary(0.0kW)	116.8 32000	Latent	169.3 8000
		Total (Electric Heat Pump)	184.6 32000

WINTER CALCULATIONS

Winter Heating Load (for 1477 sqft)


Load component		Load	
Window total	85 sqft	2736	Btuh
Wall total	1535 sqft	5041	Btuh
Door total	80 sqft	1036	Btuh
Ceiling total	1477 sqft	1740	Btuh
Floor total	214 sqft	9343	Btuh
Infiltration	185 cfm	7498	Btuh
Duct loss		0	Btuh
Subtotal		27395	Btuh
Ventilation	0 cfm	0	Btuh
TOTAL HEAT LOSS		27395	Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 1477 sqft)

Load component		Load	
Window total	85 sqft	3107	Btuh
Wall total	1535 sqft	3093	Btuh
Door total	80 sqft	784	Btuh
Ceiling total	1477 sqft	2446	Btuh
Floor total		0	Btuh
Infiltration	96 cfm	1796	Btuh
Internal gain		1380	Btuh
Duct gain		0	Btuh
Sens. Ventilation	0 cfm	0	Btuh
Total sensible gain		12606	Btuh
Latent gain(ducts)		0	Btuh
Latent gain(infiltration)		3527	Btuh
Latent gain(ventilation)		0	Btuh
Latent gain(internal/occupants/other)		1200	Btuh
Total latent gain		4727	Btuh
TOTAL HEAT GAIN		17333	Btuh



For Florida residences only

EnergyGauge® System Sizing

PREPARED BY: *Yhen*

DATE: *4-18-06*

System Sizing Calculations - Winter

Residential Load - Whole House Component Details

Hynes Richard

Project Title:

Class 3 Rating

604132NorthRussellHynes, RichardResidence

Registration No. 0

, FL

Climate: North

Reference City: Gainesville (Defaults) Winter Temperature Difference: 37.0 F

4/18/2006

Component Loads for Whole House

Window	Panes/SHGC/Frame/U	Orientation	Area(sqft)	X	HTM=	Load
1	2, Clear, Metal, 0.87	N	20.0		32.2	644 Btuh
2	2, Clear, Metal, 0.87	W	20.0		32.2	644 Btuh
3	2, Clear, Metal, 0.87	N	15.0		32.2	483 Btuh
4	2, Clear, Metal, 0.87	E	15.0		32.2	483 Btuh
5	2, Clear, Metal, 0.87	S	15.0		32.2	483 Btuh
	Window Total		85(sqft)			2736 Btuh
Walls	Type	R-Value	Area	X	HTM=	Load
1	Frame - Wood - Ext(0.09)	13.0	1347		3.3	4424 Btuh
2	Frame - Wood - Adj(0.09)	13.0	188		3.3	617 Btuh
	Wall Total		1535			5041 Btuh
Doors	Type		Area	X	HTM=	Load
1	Insulated - Adjacent		20		12.9	259 Btuh
2	Insulated - Exterior		20		12.9	259 Btuh
3	Insulated - Exterior		40		12.9	518 Btuh
	Door Total		80			1036Btuh
Ceilings	Type/Color/Surface	R-Value	Area	X	HTM=	Load
1	Vented Attic/D/Shin)	30.0	1477		1.2	1740 Btuh
	Ceiling Total		1477			1740Btuh
Floors	Type	R-Value	Size	X	HTM=	Load
1	Slab On Grade	0	214.0	ft(p)	43.7	9343 Btuh
	Floor Total		214			9343 Btuh
	Zone Envelope Subtotal:					19897 Btuh
Infiltration	Type	ACH X	Zone Volume	CFM=		
	Natural	0.94	11816	185.1		7498 Btuh
Ductload	Unsealed, R6.0, Supply(Attic), Return(Attic) (DLM of 0.00)					0 Btuh
Zone #1	Sensible Zone Subtotal					27395 Btuh

WHOLE HOUSE TOTALS

	Subtotal Sensible	27395 Btuh
	Ventilation Sensible	0 Btuh
	Total Btuh Loss	27395 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Hynes Richard

Project Title:

Class 3 Rating

Registration No. 0

Climate: North

, FL

604132NorthRussellHynes,RichardResidence

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear

(Frame types - metal, wood or insulated metal)

(U - Window U-Factor or 'DEF' for default)

(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)



For Florida residences only

System Sizing Calculations - Winter

Residential Load - Room by Room Component Details

Hynes Richard

Project Title:

Class 3 Rating

604132NorthRussellHynes, RichardResidence

Registration No. 0

Climate: North

, FL

Reference City: Gainesville (Defaults) Winter Temperature Difference: 37.0 F

4/18/2006

Component Loads for Zone #1: Main

Window	Panes/SHGC/Frame/U	Orientation	Area(sqft)	X	HTM=	Load
1	2, Clear, Metal, 0.87	N	20.0		32.2	644 Btuh
2	2, Clear, Metal, 0.87	W	20.0		32.2	644 Btuh
3	2, Clear, Metal, 0.87	N	15.0		32.2	483 Btuh
4	2, Clear, Metal, 0.87	E	15.0		32.2	483 Btuh
5	2, Clear, Metal, 0.87	S	15.0		32.2	483 Btuh
Window Total			85(sqft)			2736 Btuh
Walls	Type	R-Value	Area	X	HTM=	Load
1	Frame - Wood - Ext(0.09)	13.0	1347		3.3	4424 Btuh
2	Frame - Wood - Adj(0.09)	13.0	188		3.3	617 Btuh
Wall Total			1535			5041 Btuh
Doors	Type		Area	X	HTM=	Load
1	Insulated - Adjacent		20		12.9	259 Btuh
2	Insulated - Exterior		20		12.9	259 Btuh
3	Insulated - Exterior		40		12.9	518 Btuh
Door Total			80			1036Btuh
Ceilings	Type/Color/Surface	R-Value	Area	X	HTM=	Load
1	Vented Attic/D/Shin)	30.0	1477		1.2	1740 Btuh
Ceiling Total			1477			1740Btuh
Floors	Type	R-Value	Size	X	HTM=	Load
1	Slab On Grade	0	214.0	ft(p)	43.7	9343 Btuh
Floor Total			214			9343 Btuh
	Zone Envelope Subtotal:					19897 Btuh
Infiltration	Type	ACH X	Zone Volume	CFM=		
	Natural	0.94	11816	185.1		7498 Btuh
Ductload	Unsealed, R6.0, Supply(Attic), Return(Attic) (DLM of 0.00)					0 Btuh
Zone #1	Sensible Zone Subtotal					27395 Btuh

WHOLE HOUSE TOTALS

	Subtotal Sensible	27395 Btuh
	Ventilation Sensible	0 Btuh
	Total Btuh Loss	27395 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Hynes Richard
, FL

Project Title:
604132NorthRussellHynes, RichardResidence

Class 3 Rating
Registration No. 0
Climate: North

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear
(Frame types - metal, wood or insulated metal)
(U - Window U-Factor or 'DEF' for default)
(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)



For Florida residences only

System Sizing Calculations - Summer

Residential Load - Whole House Component Details

Hynes Richard

Project Title:

Class 3 Rating

604132NorthRussellHynes, RichardResidence

Registration No. 0

, FL

Climate: North

Reference City: Gainesville (Defaults)

Summer Temperature Difference: 17.0 F

4/18/2006

Component Loads for Whole House

Window	Type*	Ornt	Overhang		Window Area(sqft)			HTM		Load
	Pn/SHGC/U/InSh/ExSh/IS		Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded	
1	2, Clear, 0.87, None,N,N	N	9ft.	7ft.	20.0	0.0	20.0	29	29	579 Btuh
2	2, Clear, 0.87, None,N,N	W	23ft.	7ft.	20.0	20.0	0.0	29	80	579 Btuh
3	2, Clear, 0.87, None,N,N	N	1.5ft.	5.5ft.	15.0	0.0	15.0	29	29	434 Btuh
4	2, Clear, 0.87, None,N,N	E	1.5ft.	5.5ft.	15.0	2.2	12.8	29	80	1080 Btuh
5	2, Clear, 0.87, None,N,N	S	1.5ft.	5.5ft.	15.0	15.0	0.0	29	34	434 Btuh
Window Total					85 (sqft)					3107 Btuh
Walls	Type	R-Value/U-Value			Area(sqft)		HTM		Load	
1	Frame - Wood - Ext	13.0/0.09			1347.0		2.1		2810 Btuh	
2	Frame - Wood - Adj	13.0/0.09			188.0		1.5		284 Btuh	
Wall Total						1535 (sqft)				3093 Btuh
Doors	Type				Area (sqft)		HTM		Load	
1	Insulated - Adjacent				20.0		9.8		196 Btuh	
2	Insulated - Exterior				20.0		9.8		196 Btuh	
3	Insulated - Exterior				40.0		9.8		392 Btuh	
Door Total						80 (sqft)				784 Btuh
Ceilings	Type/Color/Surface	R-Value			Area(sqft)		HTM		Load	
1	Vented Attic/DarkShingle	30.0			1477.0		1.7		2446 Btuh	
Ceiling Total						1477 (sqft)				2446 Btuh
Floors	Type	R-Value			Size		HTM		Load	
1	Slab On Grade	0.0			214 (ft(p))		0.0		0 Btuh	
Floor Total						214.0 (sqft)				0 Btuh
	Zone Envelope Subtotal:									9430 Btuh
Infiltration	Type	ACH			Volume(cuft)		CFM=		Load	
	SensibleNatural	0.49			11816		96.5		1796 Btuh	
Internal gain	Occupants			Btuh/occupant			Appliance		Load	
	6			X 230 +			0		1380 Btuh	
Duct load	Unsealed, R6.0, Supply(Attic), Return(Attic) DGM = 0.00									0.0 Btuh
	Sensible Zone Load									12606 Btuh

Manual J Summer Calculations

Residential Load - Component Details (continued)

Hynes Richard
, FL

Project Title:
604132NorthRussellHynes, RichardResidence

Class 3 Rating
Registration No. 0
Climate: North

4/18/2006

WHOLE HOUSE TOTALS

Whole House Totals for Cooling	Sensible Envelope Load All Zones	12606 Btuh
	Sensible Duct Load	0 Btuh
	Total Sensible Zone Loads	12606 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	12606 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	3527 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	0 Btuh
	Latent occupant gain (6 people @ 200 Btuh per person)	1200 Btuh
	Latent other gain	0 Btuh
	Latent total gain	4727 Btuh
	TOTAL GAIN	17333 Btuh

*Key: Window types (Pn - Number of panes of glass)
(SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(U - Window U-Factor or 'DEF' for default)
(InSh - Interior shading device: none(N), Blinds(B), Draperies(D) or Roller Shades(R))
(ExSh - Exterior shading device: none(N) or numerical value)
(BS - Insect screen: none(N), Full(F) or Half(H))
(Ornt - compass orientation)



For Florida residences only

System Sizing Calculations - Summer

Residential Load - Room by Room Component Details

Hynes Richard
, FL

Project Title:
604132NorthRussellHynes, RichardResidence

Class 3 Rating
Registration No. 0
Climate: North

Reference City: Gainesville (Defaults) Summer Temperature Difference: 17.0 F

4/18/2006

Component Loads for Zone #1: Main

Window	Type*	Ornt	Overhang		Window Area(sqft)			HTM		Load
	Pn/SHGC/U/InSh/ExSh/IS		Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded	
1	2, Clear, 0.87, None,N,N	N	9ft.	7ft.	20.0	0.0	20.0	29	29	579 Btuh
2	2, Clear, 0.87, None,N,N	W	23ft.	7ft.	20.0	20.0	0.0	29	80	579 Btuh
3	2, Clear, 0.87, None,N,N	N	1.5ft.	5.5ft.	15.0	0.0	15.0	29	29	434 Btuh
4	2, Clear, 0.87, None,N,N	E	1.5ft.	5.5ft.	15.0	2.2	12.8	29	80	1080 Btuh
5	2, Clear, 0.87, None,N,N	S	1.5ft.	5.5ft.	15.0	15.0	0.0	29	34	434 Btuh
Window Total					85 (sqft)					3107 Btuh
Walls	Type	R-Value/U-Value		Area(sqft)		HTM		Load		
1	Frame - Wood - Ext	13.0/0.09		1347.0		2.1		2810 Btuh		
2	Frame - Wood - Adj	13.0/0.09		188.0		1.5		284 Btuh		
Wall Total					1535 (sqft)				3093 Btuh	
Doors	Type			Area (sqft)		HTM		Load		
1	Insulated - Adjacent			20.0		9.8		196 Btuh		
2	Insulated - Exterior			20.0		9.8		196 Btuh		
3	Insulated - Exterior			40.0		9.8		392 Btuh		
Door Total					80 (sqft)				784 Btuh	
Ceilings	Type/Color/Surface	R-Value		Area(sqft)		HTM		Load		
1	Vented Attic/DarkShingle	30.0		1477.0		1.7		2446 Btuh		
Ceiling Total					1477 (sqft)				2446 Btuh	
Floors	Type	R-Value		Size		HTM		Load		
1	Slab On Grade	0.0		214 (ft(p))		0.0		0 Btuh		
Floor Total					214.0 (sqft)				0 Btuh	
	Zone Envelope Subtotal:								9430 Btuh	
Infiltration	Type	ACH		Volume(cuft)		CFM=		Load		
	SensibleNatural	0.49		11816		96.5		1796 Btuh		
Internal gain	Occupants		Btuh/occupant		Appliance		Load			
	6		X 230 +		0		1380 Btuh			
Duct load	Unsealed, R6.0, Supply(Attic), Return(Attic)								0.0 Btuh	
	Sensible Zone Load								12606 Btuh	

Manual J Summer Calculations

Residential Load - Component Details (continued)

Hynes Richard
, FL

Project Title:
604132NorthRussellHynes, RichardResidence

Class 3 Rating
Registration No. 0
Climate: North

4/18/2006

WHOLE HOUSE TOTALS

Whole House Totals for Cooling	Sensible Envelope Load All Zones	12606 Btuh
	Sensible Duct Load	0 Btuh
	Total Sensible Zone Loads	12606 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	12606 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	3527 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	0 Btuh
	Latent occupant gain (6 people @ 200 Btuh per person)	1200 Btuh
	Latent other gain	0 Btuh
	Latent total gain	4727 Btuh
	TOTAL GAIN	17333 Btuh

*Key: Window types (Pn - Number of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(U - Window U-Factor or 'DEF' for default)

(InSh - Interior shading device: none(N), Blinds(B), Draperies(D) or Roller Shades(R))

(ExSh - Exterior shading device: none(N) or numerical value)

(BS - Insect screen: none(N), Full(F) or Half(H))

(Ornt - compass orientation)



For Florida residences only

Residential Window Diversity

MidSummer

Hynes Richard
, FL

Project Title:
604132NorthRussellHynes,RichardResidence


Class 3 Rating
Registration No. 0
Climate: North

4/18/2006

Weather data for: Gainesville - Defaults

Summer design temperature	92 F	Average window load for July	3325 Btuh
Summer setpoint	75 F	Peak window load for July	4669 Btuh
Summer temperature difference	17 F	Excursion limit(130% of Ave.)	4322 Btuh
Latitude	29 North	Window excursion (July)	347 Btuh

WINDOW Average and Peak Loads



Warning: This application has glass areas that produce relatively large heat gains for part of the day. Variable air volume devices may be required to overcome spikes in solar gain for one or more rooms. A zoned system may be required or some rooms may require zone control.

EnergyGauge® System Sizing for Florida residences only

PREPARED BY: Ben Gault

DATE: 4-18-06





**From: The Columbia County Building & Zoning Department
Plan Review
135 NE Hernando Av.
P.O. Box 1529
Lake City Florida 32056-1529**

Reference to a building permit application Number: **0604-92**

Russell North Contractor, Owner Richard Hynes 166 Symra Place

On the date of May 3, 2006 application 0604-92 and plans for construction of a single family dwelling were reviewed and the following information or alteration to the plans will be required to continue processing this application. If you should have any question please contact the above address, or contact phone number (386) 758-1163 or fax any information to (386) 754-7088.

Please include application number 0604-92 when making reference to this application.

1. Please provide for compliance with the FRC-2004 section R322.1.1

All new single-family houses, duplexes, triplexes, condominiums and townhouses shall provide at least one bathroom, located with maximum possible privacy, where bathrooms are provided on habitable grade levels, with a door that has a 29-inch (737 mm) clear opening. However, if only a toilet room is provided at grade level, such toilet rooms shall have a clear opening of not less than 29 inches (737 mm).

2. Please show compliance with the FRC-2004 sections R309 Garage: R309.1

A: Opening protection: Openings from a private garage directly into a room used for sleeping purposes shall not be permitted. Other openings between the garage and residence shall be equipped with solid wood doors not less than 13/8 inches (35 mm) in thickness, solid or honeycomb core steel doors not less than 13/8 inches (35 mm) thick, or 20-minute fire-rated doors.

B: R309.1.1 Duct penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel or other approved material and shall have no openings into the garage.

C: R309.2 Separation required. The garage shall be separated from the residence and its attic area by not less than 1/2-inch (12.7 mm) gypsum board applied to the garage side. Garages beneath habitable rooms shall be separated from all habitable rooms above by not less than 5/8-inch (15.9 mm) Type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2-inch (12.7 mm) gypsum board or equivalent.

3. For the garage area show the method of protecting the appliances as required by the Florida Mechanical Code, Sections: 303.4 Protection from damage: Appliances shall not be installed in a location where subject to mechanical damage unless protected by approved barriers.

4. Show on the electrical plans as required by the National Electrical Code article 210.12 that all branch circuits supplying outlets installed within a bedroom shall be protected by Arc-Fault interrupter devices.
5. The electrical plan shows the location of the electrical service please provide the total amperage rating overcurrent protection device. This device shall be installed on the exterior of structures to serve as a disconnecting means. Conductors used from the exterior disconnecting means to a panel or sub panel shall have four-wire conductors, of which one conductor shall be used as an equipment ground.
6. Please show compliance the FRC -2004 sections R313.1 Smoke alarms.

Smoke alarms shall be installed in the following locations:

1. In each sleeping room.
2. Outside each separate sleeping area in the immediate vicinity of the bedrooms.
3. On each additional story of the dwelling, including basements but not including crawl spaces and uninhabitable attics. In dwellings or dwelling units with split levels and without an intervening door between the adjacent levels, a smoke alarm installed on the upper level shall suffice for the adjacent lower level provided that the lower level is less than one full story below the upper level.

When more than one smoke alarm is required to be installed within an individual dwelling unit the alarm devices shall be interconnected in such a manner that the actuation of one alarm will activate all of the alarms in the

individual unit. The alarm shall be clearly audible in all bedrooms over background noise levels with all intervening doors closed.

All smoke alarms shall be listed and installed in accordance with the provisions of this code and the household fire warning equipment provisions of NFPA 72.

7.

Thank you,



Joe Haltiwanger
Plan Examiner
Columbia County Building Department

Notice of Treatment

12113

Applicator: **Florida Pest Control & Chemical Co. (www.flapest.com)**

Address: BAYVIEW

City FC Phone 7521703

Site Location: Subdivision N/A

Lot # 20 Block# Permit # 24480

Address 166 SW Smyrna Rd

Product used

Active Ingredient

% Concentration

☐ Premise Imidacloprid 0.1%

☐ Termidor Fipronil 0.12%

☒ Bora-Care Disodium Octaborate Tetrahydrate 23.0%

Type treatment:

☐ Soil

☒ Wood

Area Treated

Square feet

Linear feet

Gallons Applied

Dwelling

2027

585

4

As per Florida Building Code 104.2.6 – If soil chemical barrier method for termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial this line _____.

8/16/06
Date

0830
Time

F254
Print Technician's Name

Remarks: _____

Applicator - White

Permit File - Canary

Permit Holder - Pink

10/05

©

COLUMBIA COUNTY, FLORIDA

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 25-5S-16-03716-120

Building permit No. 000024480

Use Classification SFD/UTILITY

Fire: 107.90

Permit Holder J. RUSSELL NORTH

Waste: 167.50

Owner of Building RICHARD HYNES

Total: 275.40

Location: 166 SW SMYRNA PLACE

Date: 12/12/2006

Harry Dickie



Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)



A BOUNDARY SURVEY IN SECTION 25, TOWNSHIP 5 SOUTH,
RANGE 16 EAST, COLUMBIA COUNTY, FLORIDA.

NVA 7D SITE



NOTE: ALL PROPERTY CORNERS LOCATED ARE IDENTIFIED AS DONALD F. LEE, P.L.S. 3628.

POINT OF COMMENCEMENT
SW CORNER
OF SECTION 25,
TOWNSHIP 5 SOUTH,
RANGE 16 EAST

CERTIFIED TO:

VICEY ELIZABETH CLARY-PATTERSON & STEPHEN PATTERSON
HILDEN, RAPPENHEIMER & CLUBB, P.A.
FIRST AMERICAN TITLE INSURANCE COMPANY

FIELD BOOK 266 PAGE(S) 33

SURVEYOR'S CERTIFICATION

I HEREBY CERTIFY THAT THIS SURVEY WAS MADE UNDER MY RESPONSIBLE CHARGE AND MEETS THE MINIMUM
TECHNICAL STANDARDS AS SET FORTH BY THE FLORIDA BOARD OF PROFESSIONAL SURVEYORS AND MAPPERS
IN CHAPTER 61G17-6, FLORIDA ADMINISTRATIVE CODE, PURSUANT TO SECTION 472.027, FLORIDA STATUTES.
DATE OF SURVEY 03/29/04 DRAWING DATE 03/31/04
FIELD SURVEY DATE 03/29/04 DRAWING DATE 03/31/04
NOTE: UNLESS IT BEARS THE SIGNATURE AND THE ORIGINAL BASED SEAL OF A FLORIDA LICENSED SURVEYOR AND
MAPPER THIS DRAWING, SKETCH, PLAN OR MAP IS FOR INFORMATIONAL PURPOSES ONLY AND IS NOT VALID.

- SURVEYOR'S NOTES:
1. BOUNDARY BASED ON MONUMENTATION FOUND.
 2. BEARINGS ARE BASED ON A DEED OF RECORD AS HANDLED THIS OFFICE.
 3. SOME PORTIONS OF THIS PARCEL ARE IN ZONE 14 AND MAY BE SUBJECT TO FLOODING.
 4. HOWEVER, NO BASE FLOOD ELEVATION HAS BEEN DETERMINED FOR ZONE 14. SOME PORTIONS OF THIS PARCEL ARE IN ZONE 14 AND ARE DETERMINED TO BE OUTSIDE THE 500 YEAR FLOOD PLAIN AS PER FLOOD INSURANCE RATE MAP, DATED 6 JAN 1988 COMMUNITY PANEL NO 120070 0025. HOWEVER, THE FLOOD INSURANCE RATE MAPS ARE SUBJECT TO CHANGE.
 5. THE IMPROVEMENTS, IF ANY, INDICATED ON THIS SURVEY DRAWING ARE AS LOCATED ON DATE OF FIELD SURVEY AS SHOWN HEREIN.
 6. IF THEY EXIST, NO UNDERGROUND ENCROACHMENTS AND/OR UTILITIES WERE LOCATED FOR THIS SURVEY EXCEPT AS SHOWN HEREIN.
 7. THIS SURVEY WAS COMPLETED WITHOUT THE BENEFIT OF A TITLE COMMITMENT OR A TITLE POLICY.

DESCRIPTION:
LOT NO. 20, BUCKHEAD VILLAGES UNINCORPORATED
COMMENCE AT THE SOUTHWEST CORNER OF SECTION 25, TOWNSHIP 5 SOUTH, RANGE 16 EAST, COLUMBIA COUNTY, FLORIDA AND RUN S89°36'44\"/>

BRITT
LAND SURVEYORS AND MAPPERS

830 WEST DUVAL STREET
LAKE CITY, FLORIDA 32055

TELEPHONE: (386) 752-7163 FAX: (386) 752-5573 WORK ORDER # L-14758A

Alpine Engineered Products, Inc.

1950 Marley Drive Haines City, FL 33844
Florida Engineering Certificate of Authorization Number: 567
Florida Certificate of Product Approval # FL1999
Page 1 of 1 Document ID:1SVS487-Z0524135910

Truss Fabricator: Anderson Truss Company
Job Identification: 6-126--Russell North Constructio Hynes -- , **
Truss Count: 32
Model Code: Florida Building Code 2004
Truss Criteria: ANSI/TPI-2002(STD)/FBC
Engineering Software: Alpine Software, Version 7.24.
Structural Engineer of Record: The identity of the structural EOR did not exist as of
Address: the seal date per section 61G15-31.003(5a) of the FAC
Minimum Design Loads: Roof - 40.0 PSF @ 1.25 Duration
Floor - N/A
Wind - 110 MPH ASCE 7-02 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR487

Details: BRCLBSUB-

Seal Date: 03/24/2006

-Truss Design Engineer-

Arthur R. Fisher


Florida License Number: 59687

1950 Marley Drive

Haines City, FL 33844

#	Ref	Description	Drawing#	Date
1	09854--A1		06083031	03/24/06
2	09855--A2		06083025	03/24/06
3	09856--A3		06083046	03/24/06
4	09857--A4		06083047	03/24/06
5	09858--A5		06083032	03/24/06
6	09859--B1		06083033	03/24/06
7	09860--B2		06083034	03/24/06
8	09861--B3		06083035	03/24/06
9	09862--B4		06083036	03/24/06
10	09863--B5		06083037	03/24/06
11	09864--B6		06083038	03/24/06
12	09865--B7		06083039	03/24/06
13	09866--B8		06083040	03/24/06
14	09867--C1		06083041	03/24/06
15	09868--C2		06083042	03/24/06
16	09869--C3G		06083050	03/24/06
17	09870--C4		06083048	03/24/06
18	09871--C5G		06083045	03/24/06
19	09872--D1		06083044	03/24/06
20	09873--D2G		06083049	03/24/06
21	09874--D3		06083026	03/24/06
22	09875--D4		06083027	03/24/06
23	09876--HJ7		06083011	03/24/06
24	09877--EJ7		06083030	03/24/06
25	09878--EJA		06083029	03/24/06
26	09879--MAG		06083028	03/24/06
27	09880--J5		06083051	03/24/06
28	09881--J5D		06083043	03/24/06
29	09882--J3		06083052	03/24/06
30	09883--J1		06083053	03/24/06
31	09884--K1		06083054	03/24/06
32	09885--K2		06083055	03/24/06





#6-126 RUSSELL NORTH CONSTRUCTION - HYNES

Scale: 3/32" = 1'

752-6806
397-3075


Top chord 2x4 SP #2 Dense :T2, T3 2x6 SP #1 Dense:
Bot chord 2x8 SP #1 Dense
Webs 2x4 SP #3 :W13 2x4 SP #2 Dense:

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

SPECIAL LOADS

TEST	CONC.	LOAD	PLATE	DUR.	FAC.	PLATE	DUR.	FAC.
TC	-	From	62 PLF	at	-2.00	to	62 PLF	at 7.00
TC	-	From	122 PLF	at	7.00	to	122 PLF	at 21.00
TC	-	From	62 PLF	at	21.00	to	62 PLF	at 38.73
BC	-	From	4 PLF	at	-2.00	to	4 PLF	at 0.00
BC	-	From	20 PLF	at	0.00	to	20 PLF	at 7.00
BC	-	From	49 PLF	at	7.00	to	49 PLF	at 21.00
BC	-	From	20 PLF	at	21.00	to	20 PLF	at 38.73
TC	-	189 LB Conc.	Load	at	7.00			
BC	-	416 LB Conc.	Load	at	7.00			
BC	-	93 LB Conc.	Load	at	23.06		25.06	27.06
BC	-	562 LB Conc.	Load	at	29.06			

Provide connection for concentrated load(s) shown.



PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.13

Scale = .1875"/Ft.

FL/-/4/-/R/-

TY:1

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF

DUR. FAC. 1.25

SPACING SEE ABOVE

REF R487 - 9854

DATE 03/24/06

DRW HCUSR487 06083031

HC-ENG TCE/AF

SEQN- 12868 RE

JREF- 1SVS487_Z05



PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.13

Scale = .1875"/Ft.

FL/-/4/-/R/-

TY:1

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF

DUR. FAC. 1.25

SPACING SEE ABOVE

REF R487 - 9854

DATE 03/24/06

DRW HCUSR487 06083031

HC-ENG TCE/AF

SEQN- 12868 RE

JREF- 1SVS487_Z05



PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.13

Scale = .1875"/Ft.

FL/-/4/-/R/-

TY:1

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF

DUR. FAC. 1.25

SPACING SEE ABOVE

REF R487 - 9854

DATE 03/24/06

DRW HCUSR487 06083031

HC-ENG TCE/AF

SEQN- 12868 RE

JREF- 1SVS487_Z05



PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.13

Scale = .1875"/Ft.

FL/-/4/-/R/-

TY:1

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF

DUR. FAC. 1.25

SPACING SEE ABOVE

REF R487 - 9854

DATE 03/24/06

DRW HCUSR487 06083031

HC-ENG TCE/AF

SEQN- 12868 RE

JREF- 1SVS487_Z05



PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.13

Scale = .1875"/Ft.

FL/-/4/-/R/-

TY:1

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF

DUR. FAC. 1.25

SPACING SEE ABOVE

REF R487 - 9854

DATE 03/24/06

DRW HCUSR487 06083031

HC-ENG TCE/AF

SEQN- 12868 RE

JREF- 1SVS487_Z05



PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.13

Scale = .1875"/Ft.

FL/-/4/-/R/-

TY:1

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF

DUR. FAC. 1.25

SPACING SEE ABOVE

REF R487 - 9854

DATE 03/24/06

DRW HCUSR487 06083031

HC-ENG TCE/AF

SEQN- 12868 RE

JREF- 1SVS487_Z05



PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.13

Scale = .1875"/Ft.

FL/-/4/-/R/-

TY:1

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF

DUR. FAC. 1.25

SPACING SEE ABOVE

REF R487 - 9854

DATE 03/24/06

DRW HCUSR487 06083031

HC-ENG TCE/AF

SEQN- 12868 RE

JREF- 1SVS487_Z05



PLT TYP. 20 Gauge HS, Wave

Design Crit: TPI-2002(STD)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.13

Scale = .1875"/Ft.

FL/-/4/-/R/-

TY:1

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF

DUR. FAC. 1.25

SPACING SEE ABOVE

REF R487 - 9854

DATE 03/24/06

DRW HCUSR487 06083031

HC-ENG TCE/AF

SEQN- 12868 RE

JREF- 1SVS487_Z05



PLT TYP. 20 Gauge HS, Wave


Design Crit: TPI-2002(STD)/FBC

Cq/RT=1

Top chord	2x4	SP #2	Dense
Bot chord	2x4	SP #2	Dense
Webbs	2x4	SP #3	

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC. Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.




ALPINE Alpine Engineered Products, Inc. 1950 Marley Drive Haines City, FL 33844 FL Certificate of Authorization # 567	Design Crit: TPI-2002(STD)/FBC		Cq/RT= 1.00(1.25)/10(0)		7.24		
	WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 3-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 583 D'ONOFIO DR., SUITE 200, MADISON, WI 53719, AND MITCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING. **IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS AND THE CONNECTIONS BETWEEN THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/K) ASTM A653 GRADE 40/60 (M, K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ALL TRUSSES SHALL BE MANUFACTURED IN ACCORDANCE WITH TPI-2002.REC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY FOR THE TRUSS DESIGN. THE DRAWING SHOWS, THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANST/TPI 1 SEC. 2.						
							
	TYP. Wave		FL / - / - / - / R / -		Scale = .1875" / Ft.		
	TC LL	20.0	PSF	REF	R487 --	9856	
	TC DL	10.0	PSF	DATE	03/24/06		
BC DL	10.0	PSF	DRW	HCSR487	06083046		
BC LL	0.0	PSF	HC-ENG	TCE /AF			
TOT.LD.	40.0	PSF	SEQN-	5109			
DUR.FAC.	1.25		JREF-	1SVS487_Z05			
SPACING	24.0"						

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0) 7.24.1

Scale = .1875"/Ft.

TC LL	20.0 PSF	FL/-/4/-/-/R/-
TC DL	10.0 PSF	
BC DL	10.0 PSF	
BC LL	0.0 PSF	
TOT.LD.	40.0 PSF	
DUR.FAC.	1.25	
SPACING	24.0"	

REF R487 -- 9857
DATE 03/24/06
DRW HCUSR487 06083047
HC-ENG TCE/AF
SEQN- 5118
JREF- 1SVS487_205


WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D'ONOFIO DR., SUITE 200, MADISON, WI 53719) AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AFAPA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/1866A (N-H/STK) ASTM A653 GRADE 40/60 (N. K/H-S) GALV. STEEL. APPLY ANY INSPECTION OF JOINTS, BOLTS AND BRACING. UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 100A-Z. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY FOR THE TRUSS DESIGN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

RATHUR R. FISHER
LICENSE
No 59887
STATE OF
FLORIDA
Professional Engineer
Mar 22 '06

ALPINE
Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

LT TYP. Wave



ALPINE

Alpine Engineered Products, Inc.
1950 Harley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567

Design Crit: TPI-2002(SIU)/FBC

Cq/RT=1.00(1.25)/10(0) 7.24.10

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION). PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'AMORIO DR., SUITE 200, MADISON, WI 53719) AND AISC (AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 500 N. MICHIGAN, CHICAGO, IL 60611). FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED, ALL SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DAMAGE TO OR LOSS OF TRUSS OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES IN CONFORMANCE WITH TPI. UNLESS OTHERWISE INDICATED, ALL TRUSSES SHALL BE DESIGNED IN CONFORMANCE WITH TPI-2002(SIU)/FBC. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/16GA (W/H/S/K) ASTM A653 GRADE 40/60 (W. K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Scale = .1875"/Ft.

REF R487 - 9858

DATE 03/24/06

DRW HCUSR487 06083032

FL / - / 4 / - / R / -

TC LL 20.0 PSF

TC DL 10.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 40.0 PSF



DUR.FAC. 1.25

SPACING 24.0"



TY:1

JREF- 1SVS487_Z05



PLT TYP. Wave		QTY:1	FL / - / 4 / - / - / R / -	Scale = .375" / Ft.
Design Crit: TPI-2002(STD)/FBC		TC LL	20.0 PSF	REF R487 - - 9859
Cq/RT=1.00(1.25)/10(0) 7.24.1		TC DL	10.0 PSF	DATE 03/24/06
		BC DL	10.0 PSF	DRW HCUSR487 06083033
		BC LL	0.0 PSF	HC-ENG TCE/AF
		TOT.LD.	40.0 PSF	SEQN- 5240
		DUR.FAC.	1.25	
		SPACING	SEE ABOVE	JREF- 1SVS487_Z05


****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1.03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFIO DR., SUITE 200, MADISON, WI 53719) AND METCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE APPLIES TO EACH FACE OF TRUSS JOINTS. FASTENERS GRADE 40/60 (M, K/H/S) GALV. STEEL. APPLY PER DRAWING. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.


Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

110 mph wind, 15.00 ft mean hgt., ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT 11, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

in lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.




Design Crit: TPI-2002(STD)/FBC
CQ/DI-1 00/1 25/10/00



ALPINE
Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 583 D'AMORIO DR., SUITE 200, MADISON, WI 53719, AND WTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS, NATIONAL DESIGN SPEC, BY AIA/PAJ AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (M-H/S/K) ASTM A653 GRADE 40/60 (M, K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ALL TRUSS TOE PLATES USED SHALL BE PER ANSI A575-1-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES CLOSING PROCESS AND ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGNER. SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



NO. 59687
STATE OF FLORIDA
PROFESSIONAL ENGINEER
MAY 24 '06


SCALE = 3/8" = 1'-0"	T.C. LL	20.0 PSF	REF	R487 --	9860
	T.C. DL	10.0 PSF	DATE	03/24/06	
	B.C. DL	10.0 PSF	DRW	HCUR487	06083034
	B.C. LL	0.0 PSF	HC-ENG	TCE/AF	★
	TOT. LD.	40.0 PSF	SEQN-	5233	
	DUR. FAC.	1.25			
	SPACING	24.0"	JREF-	1SVS487	Z05

	Top	Bot	Dense
chord	2x4	2x4	#2
chord	2x4	2x4	#2
webs	2x4	2x4	#3

110 mph wind, 15.00 ft mean ht, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.




R=1729 U=180 W=3.5"

R=1719 U=180 W=3.5"

Design Crit: TPI-2002(STD)/FBC


Scale = .1875"/Ft.

TC LL	20.0 PSF	REF	R487-- 9861
TC DL	10.0 PSF	DATE	03/24/06
BC DL	10.0 PSF	DRW	HCUSR487 06083035
BC LL	0.0 PSF	HC-ENG	TCE/AF *
TOT.LD.	40.0 PSF	SEQN-	5227
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1SVS487_705



****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TP1 (TRUSS PULPIT INSTITUTE, 583 D'ORFIO DR., SUITE 200, MADISON, WI 53719) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED. TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT****FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS USING THE TP11-2002 SPECIFICATIONS FOR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONCERNING WITH APPLICABLE PERMITS AND/OR LOCAL CODES, SHALL BE THE RESPONSIBILITY OF THE DESIGNER. CONECTOR PLATES ARE MADE OF 2018/T16GA (H W/S)X3 ASTM A563 GRADE 40/60 KIN. STEEL. APPLICABLE PLATES TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, INSTALLATION PER DIMENSIONS 1604-2. AN INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX AS OF TP11-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUSTAINABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/APT 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.


R-1719 U=180 W=3.5"

TC LL	20.0	PSF	REF	R487 - -	9862
TC DL	10.0	PSF	DATE	03/24/06	
BC DL	10.0	PSF	DRW	HCUSR487	06083036
BC LL	0.0	PSF	HC-ENG	TCE/AF	*
TOT.LD.	40.0	PSF	SEQN-	5221	
DUR.FAC.	1.25				
SPACING	24.0"		JREF-	1SVS487_Z05	

Top chord 2x4 SP #2 Dense	110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not
Bot chord 2x4 SP #2 Dense	located within 4.50 ft from roof edge, CAT II, EXP B, wind TC
Webs 2x4 SP #3	DL=5.0 psf, wind BC DL=5.0 psf.

(A) 1x4 #3 or better "T" brace. 80% length of web member. Attach with 8d Box or Gun (0.113"x2.5",min.)nails @ 6" OC. BC @ 24" OC. In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



R=1729 U=180 W=3.5" R=1719 U=180 W=3.5"

Design Crit: TPI-2002(STD)/FBC

Scale = .1875"/Ft.


ALPINE Alpine Engineered Products, Inc. 1950 Marley Drive Haines City, FL 33844 FL Certificate of Authorization # 567	**WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 593 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719), AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719), FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.	 Mar 4 '06		TC LL	20.0 PSF	REF	R487 --	9863
	TC DL			10.0 PSF	DATE	03/24/06		
	BC DL			10.0 PSF	DRW	HCUSR487	06083037	
	BC LL			0.0 PSF	HC-ENG	TCE/AF	*	
	TOT.LD.			40.0 PSF	SEQN-	5214		
	DUR.FAC.			1.25				
SPACING				24.0"	JREF-	1SVS487_Z05		

Top chord	2x4	SP	#2	Dense
Bot chord	2x4	SP	#2	Dense
	Webbs	2x4	SP	#3

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

(A) 1x4 #3 or better "T" brace. 80% length of web member. Attach with 8d Box or Gun (0.113"x2.5", min.) nails @ 6" OC.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



R=1729 U=180 W=3.5" R=1729 U=180 W=3.5"

PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0) 7.24.18

THURMAN R. FISHER
SENSE
TY: 1

FL/-/4/-/-R/-
Scale = .1875"/Ft.


 Alpine Engineering Products, Inc. 1950 Marley Drive Haines City, FL 33844	**WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 O'DONOGHIE DR., SUITE 200, MADISON, WI 53719), AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING. **IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AFAPA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/K) ASTM A653 GRADE 40/60 (W, V/M/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANCH A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.	No. 59687  STATE OF FLORIDA PROFESSIONAL ENGINEER Mar 24 '06	TC LL	20.0 PSF	REF	R487 --	9864
			TC DL	10.0 PSF	DATE	03/24/06	
			BC DL	10.0 PSF	DRW	HCUSR487	06083038
			BC LL	0.0 PSF	HC-ENG	TCE/AF	*
			TOT.LD.	40.0 PSF	SEQN-	5196	
DUR.FAC.	1.25						
SPACING	24.0"	JREF-	1SVS487_Z05				
FL Certificate of Authorization # 367							

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

(A) Continuous lateral bracing equally spaced on member.
Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.




R=1729 U=180 W=3.5"

R=1729 U=180 W=3.5"


Design Crit: TPI-2002(STD)/FBC
Cg/RT=1.00(1.25)/10(0) 7.24.1

PLT TYP. Wave	Scale = .1875"/Ft.
TC LL 20.0 PSF	REF R487-- 9866
TC DL 10.0 PSF	DATE 03/24/06
BC DL 10.0 PSF	DRW HCUSR487 06083040
BC LL 0.0 PSF	HC-ENG TCE/AF *
TOT.LD. 40.0 PSF	SEQN- 5208
DUR.FAC. 1.25	
SPACING 24.0"	JREF- 1SVS487_Z05



****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (4-H/5K) ASTM A653 GRADE 40/60 (4. K/M-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DESIGN SHALL BE OBTAINED BY THE INSTALLATION CONTRACTOR. THE INSTALLATION CONTRACTOR SHALL BE RESPONSIBLE FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.




	Top	Bot	Dense
chord	2x4	2x4	#2
chord	2x4	2x4	#2
webs	2x4	2x4	#3

110 mph wind, 15.00 ft mean ht, ASCE 7-02, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

#1 hip supports 7-0-0 jacks with no webs.


Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



Design Crit: TPI-2002(STD)/FBC


Scale = .3125"/Ft.

TC LL	20.0 PSF	REF	R487 - -	9867
TC DL	10.0 PSF	DATE	03/24/06	
BC DL	10.0 PSF	DRW	HCUSR487	06083041
BC LL	0.0 PSF	HC-ENG	TCE/AF	
TOT.LD.	40.0 PSF	SEQN -	5029	
DUR.FAC.	1.25			
SPACING	SEE ABOVE	JREF -	1SVS487_Z05	




WARNING: THUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLATION AND BRACING. REFER TO 6C51-1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI TRUSS PLATE INSTITUTE, 583 D'ONOFIO DR., SUITE 200, MADISON, WI 53719, AND WICA GOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

*****IMPORTANT***** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS TO THE DESIGN REQUIREMENTS, INCLUDING THE BRACING OF TRUSSES, SHALL BE THE RESPONSIBILITY OF THE DESIGNER PROVIDING THE TRUSS. THE DESIGNER SHALL BE RESPONSIBLE FOR THE DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE NATIONAL DESIGN SPECIFICATION FOR STEEL. CONECTOR PLATES ARE MADE OF 20/18/16G6 (M.Y/S/K) ASTM A563 GRADE 40/60 (M.Y/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND OTHERWISE LOCATED ON THIS DESIGN. POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TP11-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF ALPINE ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT BEING SHOWN. THE SUSTAINABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP11 1 SEC. 2.



Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.



PLT TYP. Wave

Design Crit: TPI-2002(STD)/FBC
Cg/RT=1.00(1.25)/10(0) 7.24.1

Scale = .3125"/Ft.

TC LL 20.0 PSF
TC DL 10.0 PSF
BC DL 10.0 PSF
BC LL 0.0 PSF
TOT.LD. 40.0 PSF
DUR.FAC. 1.25
SPACING 24.0"

REF R487-- 9868
DATE 03/24/06
DRW HCUSR487 06083042
HC-ENG TCE/AF
SEQN- 5022
JREF- 1SVS487 Z05

ALPINE
Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

R. FISHER
No. 59687
STATE OF FLORIDA
PROFESSIONAL ENGINEER
Mar 24 '06

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 503 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719, AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/186A (N-H/S/K) ASTM A653 GRADE 40/60 (N, K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. (T) SHALL BE PER AMERICAN AS OF TPI 2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF THE PROJECT BY THE TRUSS COMPONENT BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Top chord 2x4 SP #2 Dense
Bot chord 2x8 SP #1 Dense
Webs 2x4 SP #3

2 COMPLETE TRUSSES REQUIRED

Nailing Schedule: (12d Box or Gun (0.128"x3.25", min.) nails)

Top Chord: 1 Row @12.00" o.c.

Bot Chord: 1 Row @ 5.00" o.c.
Jobs : 1 Row @ 4" o.c.

Webbs : 1 Row @ 4" o.c.
Use equal spacing between rows

Use equal spacing between rows and stagger nails in each row to avoid splitting.

110 mph wind, 15.00 ft mean hgt., ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.


Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

SPECIAL LOADS

(LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)			
TC	From	62 PLF at	-2.00 to
BC	From	4 PLF at	-2.00 to
BC	From	20 PLF at	0.00 to
BC	4069	LB Conc.	Load at 12.88
BC	1062	LB Conc.	Load at 14.94
BC	211	LB Conc.	Load at 16.91

Provide connection for concentrated load(s) shown.



R-2214 U-258 W-3.5"

—18-0-0 Over 2 Supports

R-4744 U-507 W-3.5^N

Design Crit: TPI-2002(STD)/FBC

PI-200Z (STD) / FBC
Cq/RT=1.00 (1.25) / 10 (0) 7.24.14


Scale = .375"/ft.

FL/-/4/-/-/R/-/-

QTY: 1

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLATION AND BRACING. REFER TO BCS1-1.03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY IPI (TRUSS PLATE INSTITUTE, 583 D'AMFROIR DR., SUITE 200, MADISON, WI 53719) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6200 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

***IMPORTANT**FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. THE CONTRACTOR SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. THE DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. IN STRUCTURAL DESIGN) AND ALL BRACING OF TRUSSES. CONNECTOR PLATES ARE MADE OF 20/10/16GA. M16/12K1 ASTM A563 GRADE 40 (60 (N/A) GALV. STEEL. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A.2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX 43 OF TP11-2002 SEC.3. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # S67

FL Certificate of Authorization # 567



ALPINE
Alpine Engineered Products, Inc.
 1950 Marley Drive
 Haines City, FL 33844
 FL Certificate of Authorization # 567

Top chord	2x4	SP #2	Dense
Bot chord	2x8	SP #1	Dense
webs	2x4	SP #3	

2 COMPLETE TRUSSES REQUIRED

Nailing Schedule: 12d Box or Gun (0.128"x3.25", min.) nails
 Top Chord: 1 Row @12.00" o.c.
 Bot Chord: 2 Rows @ 4.50" o.c. (Each Row)
 Webs : 1 Row @ 4" o.c.


Use equal spacing between rows and stagger nails
 in each row to avoid splitting

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.


Right end vertical not exposed to wind pressure.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Design Crit: $\text{TPI-2002(STD)}/\text{FBC}$
 $\text{Cq}/\text{RT}=1.00(1.25)/$

FL/-/4/-/-/R/-		Scale = .375"/Ft.
TC LL	20.0 PSF	REF R487 - - 9871
TC DL	10.0 PSF	DATE 03/24/06
BC DL	10.0 PSF	DRW HCU8R487 06083045
BC LL	0.0 PSF	HC-ENG TCE/AF
TOT.LD.	40.0 PSF	SEQN- 12872 RE
DUR.FAC.	1.25	
SPACING	SEE ABOVE	JREF- 1SVS487_Z05



****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT****FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS COMPONENTS ACCORDING TO THE DESIGN OR THE INSTALLING BRACING OF TRUSSES. THE DESIGN CONFORMS WITH THE FOLLOWING PROVISIONS OF THE NATIONAL DESIGN SPEC.:

CONNECTION PLATES ARE MADE OF 20/18/16GA (W/1/8"X1/4"X1/4") K155 GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THE TRUSS PER DRAWINGS 160A, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 80



ALPINE
Alpine Engineered Products, Inc.
 1350 Marley Drive
 Haines City, FL 33844
 FL Certificate of Authorization # 567

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3


In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

#1 hip supports 7-0-0 jacks with no webs.

Left side jacks have 7-0-0 setback with 0-0-0 cant and 2-0-0 overhang. End jacks have 7-0-0 setback with 0-0-0 cant and 2-0-0 overhang. Right side jacks have 7-0-0 setback with 0-0-0 cant and 2-0-0 overhang.



Design Crit: TPI-2002 (STD)/FBC


Cq/RT=1.00(1.25)/10(0)

7.24.1

TY:1 FL/-/4/-/-/R/-

Scale = .5" / Ft.

TC LL	20.0 PSF	REF	R487 -- 9872
TC DL	10.0 PSF	DATE	03/24/06
BC DL	10.0 PSF	DRW	HCUSR487 06083044
BC LL	0.0 PSF	HC-ENG	TCE/AF
TOT.LD.	40.0 PSF	SEQN-	5174
DUR.FAC.	1.25		
SPACING	SEE ABOVE	JREF-	1SVS487_Z05



****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI TRUSS PLATE, INSTITUTION D'ONORIO DR., SUITE 200, MADISON, WI 53719, AND NCA, WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (N-H/S/K) ASTM A653 GRADE 40/60 (M, K/M-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. A SEAL ON THIS PLATE SHALL BE PER ANNEK A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANS/PTI 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

— 100 —


2 COMPLETE TRUSSES REQUIRED

Nailing Schedule: (12d_Box_or_Gun_(0.128"x3.25",_min.)_nails)
Top Chord: 1 Row @12.00" O.C.
Bot Chord: 1 Row @ 4.25" O.C.
Webs : 1 Row @ 4" O.C.
Use equal spacing between rows and stagger nails
in each row to avoid splitting.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Design Crit: $\text{TPI-2002(STD)}/\text{FBC}$
 $\text{Cq}/\text{RT}=1.00(1.25)/$

Scale = .5"/Ft.

TC LL	20.0 PSF	REF	R487 -- 9873
TC DL	10.0 PSF	DATE	03/24/06
BC DL	10.0 PSF	DRW	HCUSR487 06083049
BC LL	0.0 PSF	HC-ENG	TCE/AF
TOT.LD.	40.0 PSF	SEQN-	12876 REV
DUR.FAC.	1.25		
SPACING	SEE ABOVE	JREF-	1SVS487_Z05

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 90 D'ORFIOLE DR., SUITE 200, MADISON, WI 53719, AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TP1 OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TP1. ALPINE CONNECTOR PLATES ARE MADE OF 2019/156GA (M/H/S/K) ASTM A653 GRADE 40/60 (M, K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A.3 OF TP1-2002 SEC.3. A SEAL ON THE DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.



Alpine Engineered Products, Inc.
 1950 Marley Drive
 Haines City, FL 33844
 FL Certificate of Authorization # 567


Top chord	2x4	SP	#2	Dense
Bot chord	2x4	SP	#2	Dense
Webbs	2x4	SP	#3	

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.


Right end vertical not exposed to wind pressure.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



ARTHUR R. FISHER
 LICENSED PROFESSIONAL ENGINEER
 STATE OF FLORIDA
 No. 59687
 Mar 24 '06

PLT TYP. Wave



Alpine Engineering Products, Inc.
1950 Hammer Drive
Haines City, FL 33844

FL Certificate of Authorization # 567

Cg/RT=1.00(1.5725)/10(0) 7.24.106

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719), AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.


****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AFAPA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/K) ASTM A653 GRADE 40/60 (W, K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Scale = .5"/Ft.

FL/-4/-/-R/-

REF R487 - -	9874	TC LL	20.0 PSF	FL/-4/-/-R/-	Scale = .5"/Ft.
DATE	03/24/06	TC DL	10.0 PSF		
DRW HCUSR487	06083026	BC DL	10.0 PSF		
HC-ENG TCE/AF	*	BC LL	0.0 PSF		
SEQN -	4995	TOT.LD.	40.0 PSF		
DUR.FAC.	1.25				
SPACING	24.0"				

JREF - 1SVS487_Z05




110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.


Right end vertical not exposed to wind pressure.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.





Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

PLT TYP. Wave


Design Crit: TPI-2002 (STD) /FBC
Cq/RT=1.00(1.25)/10(0) 7.24.12

Scale = .5" /Ft.

TC LL	20.0 PSF	REF	R487 - - 9875
TC DL	10.0 PSF	DATE	03/24/06
BC DL	10.0 PSF	DRW	HCUSR487 06083027
BC LL	0.0 PSF	HC-ENG	TCE/AF *
TOT.LD.	40.0 PSF	SEQN-	5006
DUR.FAC.	1.25		
SPACING	24.0"	JREF-	1SVS487_Z05

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSE 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AFAPA) AND TPI. ALPINE PLATES TO EACH FACE OF TRUSS AND/OR JOINTS. ASTM A572 GRADE 50 (M. 47/PL.5) GALV. STEEL. APPLY ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEA 3 OF TPI 1002 SEC. 2. THE DESIGNER'S DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.




110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.





Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

PLT TYP. Wave

Design Crit: TPI-2002 (STD) /FBC

Cq/RT=1.00(1.25)/10(0) 7.24.10

Scale = .5" /Ft.

PLT TYP. Wave

Scale = .5" /Ft.

TC LL	20.0 PSF
TC DL	10.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	40.0 PSF
DUR.FAC.	1.25
SPACING	24.0"

JREF - 1SVS487_Z05


Top	chord	2x4	SP	#2	Dense
3ot	chord	2x4	SP	#2	Dense
	webs	2x4	SP	#3	

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

1110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT 11, EXP 8, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.




Design Crit: TPI-2002(STD)/FBC

DESIGN CHART: 10/1/2002(310)/10/01
Cq/RT=1.00(1.25)/10(0) 7.2

[illegible]

PLT TYP. Wave



FL / - / 4 / - / - / R / -		Scale = .5" / Ft..
TC LL	20.0 PSF	REF R487 - - 9878
TC DL	10.0 PSF	DATE 03/24/06
BC DL	10.0 PSF	DRW HCURS487 06083029
BC LL	0.0 PSF	HC-ENG TCE / AF
TOT.LD.	40.0 PSF	SEQN - 5068
DUR.FAC.	1.25	
SPACING	24.0"	JREF - 1S\VS487_Z05

Top chord	2x4	SP	#2	Dense
Bot chord	2x6	SP	#1	Dense
Webs	2x4	SP	#3	


110 mph wind, 15.00 ft mean hgt. ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

SPECIAL LOADS

(LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25)

TC - From	62 PLF at 0.00 to	62 PLF at 7.00
8C - From	20 PLF at 0.00 to	20 PLF at 7.00
PLB-	413 LB Conc. Load at	(4.52,8.04), (6.52,8.04)


Provide connection for concentrated load(s) shown.



Design Crit: TPI-2002(STD)/FBC


PLT TYP. Wave

TC LL	20.0 PSF	REF	R487--	9879
TC DL	10.0 PSF	DATE	03/24/06	
BC DL	10.0 PSF	DRW	HCUR487	06083028
BC LL	0.0 PSF	HC-ENG	TCE/AF	
TOT.LD.	40.0 PSF	SEQN-	5060	
DUR.FAC.	1.25			
SPACING	see above	JREF-	1SVS487_Z05	




****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PRACTICE INSTITUTE, 583 D'ONOFIO RD., SUITE 200, MADISON, WI 53719) AND WTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED. TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT****FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE DESIGN CONFORMING WITH TP1 OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. CONNECTOR PLATES ARE MADE OF 2018/T16GA (W/1/2X) ASTM A575 GRADE 40/66K W/ALUMINUM ANODIZED AL-2C PLATES TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, JOINTS PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TP11-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.



Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
In lieu of structural panels or rigid ceiling use purlins to brace TC
@ 24" OC, BC @ 24" OC.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located
within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf,
wind BC DL=5.0 psf.
Deflection meets L/360 live and L/240 total load. Creep increase
factor for dead load is 1.50.



2'-0"-0"
5'-0"-0" Over 3 Supports
R=377 U=180 W=3.5"

Design Crit: TPI-2002 (STD) / FBC

PLT TYP. Wave Cq/RT=1.00(1.25)/10(0) 7.24.10 Scale = .5" / Ft.

ALPINE Alpine Engineered Products, Inc. 1950 Marley Drive Haines City, FL 33844 FL Certificate of Authorization # 567		**WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1.03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING. **IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/16GA (W.H/5/8) ASTM A653 GRADE 40/60 (W. K/H.5) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED AS THIS DESIGN, POSITION PER DRAWINGS 160A Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEK A3 OF TPII-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.										APPROVED SEAL ENGINEER STATE OF FLORIDA 6* No. 59687 MAR 24 '06		TC LL		20.0 PSF	REF R487 - - 9880
TC DL		10.0 PSF	DATE 03/24/06														
BC DL		10.0 PSF	DRW HCUSR487 06083051														
BC LL		0.0 PSF	HC-ENG TCE/AF *														
TOT.LD.		40.0 PSF	SEQN- 4979														
DUR.FAC.		1.25															
SPACING		24.0"	JREF- 1SVS487_Z05														


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.



5-0-0 Over 3 Supports
R=211 U=180

Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/

Scale = .5"/Ft.

ALPINE ALPINE Engineered Products, Inc. 1950 Marley Drive Gaines City, FL 33844 FL Certificate of Authorization # 567	**WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 O'CONNOR DR., SUITE 200, MADISON, WI 53719) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING. **IMPORTANT**FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC, BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (N-H/S/K) ASTM A653 GRADE 40/60 (N, K/N-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE ANNOTED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEK A3 OF IPT1-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANS1/TPI 1 SEC. 2.	NO. 59687 STATE OF FLORIDA PROFESSIONAL ENGINEER Ma [signature] '06	TC LL	20.0 PSF	REF	R487 -- 9881
	TC DL		10.0 PSF	DATE	03/24/06	
	BC DL		10.0 PSF	DRW	HCUSR487 06083043	
	BC LL		0.0 PSF	HC-ENG	TCE/AF *	
	TOT.L.D.		40.0 PSF	SEQN-	5179	
	DUR.FAC.		1.25			
SPACING		24.0"	JREF-	1SVS487_Z05		

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.

6'

10'-3"

R=49 U=180

R=15 U=180

2X4 (A1) ≡

3'-0-0 Over 3 Supports

R=317 U=180 W=3.5"

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Design Crit: TPI-2002(STD)/FBC

Cg/RT=1.00(1.25)/10(0)

7.24.18

Scale = .5"/Ft.

PLT TYP. Wave		TY:1		FL/-/4/-/-/R/-	
TC LL	20.0 PSF	REF	R487 - -	9882	
TC DL	10.0 PSF	DATE	03/24/06		
BC DL	10.0 PSF	DRW	HCUSR487	06083052	
BC LL	0.0 PSF	HC-ENG	TCE/AF	*	
TOT.LD.	40.0 PSF	SEQN	4982		
DUR.FAC.	1.25				
SPACING	24.0"	JREF	1SVS487_Z05		

ALPINE

Alpine Engineered Products, Inc.

1950 Marley Drive

Haines City, FL 33844

FL Certificate of Authorization # 567

WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSE 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2019/166A (W.H./S.K.) ASTM A553 GRADE 40/60 (W. K/H.S.) GALV. STEEL. APPLY ANY INSPECTION OF PLATES FOLLOWED BY TPI SHALL BE PERMANENT AND OF THE DESIGNER'S RESPONSIBILITY. ANY DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

PROFESSIONAL ENGINEER

DAVID R. FISHER



NO. 59887

STATE OF FLORIDA

Mar 24 '06


110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, Located anywhere in roof, CAT II, EXP 8, wind TC DL=5.0 psf, wind BC DL=5.0 psf.
Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.



Design Crit: TPI-2002(STD)/FBC
Cq/RT=1.00(1.25)/10(0)

Scale = .5"/Ft.



TC LL	20.0 PSF	FL/-/4/-/-/R/-
TC DL	10.0 PSF	REF R487 - - 9883
BC DL	10.0 PSF	DATE 03/24/06
BC LL	0.0 PSF	DRW HCUSR487 06083053
TOT.LD.	40.0 PSF	HC-ENG TCE/AF
DUR.FAC.	1.25	SEQN- 4984
SPACING	24.0"	JREF- 1SVS487_Z05

ALPINE
Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AFAPA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/166A (W.H./5X) ASTM A553 GRADE 40/60 (W. K/H.5) GALV. STEEL. APPLY ANY INSPECTION OF PLATES OWNED BY THE TRUSS MANUFACTURER. UNLESS OTHERWISE INDICATED, THE TRUSS MANUFACTURER SHALL BE RESPONSIBLE FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Top	chord	2x4	SP	#2	Dense
Bot	chord	2x4	SP	#2	Dense
	webs	2x4	SP	#3	


110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

In lieu of structural panels or rigid ceiling use purlins to brace TC @ 24" OC, BC @ 24" OC.

Deflection meets L/360 live and L/240 total load. Creep increase factor for dead load is 1.50.

Right end vertical not exposed to wind pressure.

#1 hip supports 7-0-0 jacks with no webs.



Design Crit: TPI-2002(STD)/FBC

PLT TYP. Wave


$$Ca/RT=1.00(1.25)/10(0)$$

SENSE

Scale = 5" / Ft.

*****WARNING***** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. TRUSSES ARE NOT TO BE USED FOR ANY OTHER PURPOSES. FOR BUILDING COMPONENTS INFORMATION, PUBLISHED BY IPI (TRUSS PLATE INSTITUTE, 583 KENWOOD BLVD., SUITE 100, WESTPORT, MA 01886) OR ITC (TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53717). FOR SAFETY PRACTICES, SAFETY PRACTICES PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

*****IMPORTANT****FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN: ANY FAILURE TO BUILD THE TRUSS COMPONENTS WITH PROPER FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING TO TRUSSES. THE DESIGNER SPECIFICALLY RELEASES AND PROVIDES SPECIFICATIONS (A/E/C) AND TYPICAL ALPINE CONNECTOR PLATES ARE MADE OF 2018/T16GAL OR W/16IN ASTM A572-50 STEEL. POSITION PER PARAGRAPHS 160A-2. IF AN INSPECTION OF PLATES FOLLOWED BY (1). SHALL BE PER ANNEX A3 OF TP11-2002 SEC 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANNEX (TP1) 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567


TC LL	20.0	PSF	REF	R487--	9884
TC DL	10.0	PSF	DATE	03/24/06	
BC DL	10.0	PSF	DRW	HCUSR487	06083054
BC LL	0.0	PSF	HC-ENG	TCE/AF	
TOT.LD.	40.0	PSF	SEQN-	5250	
DUR.FAC.	1.25				
SPACING	SEE ABOVE		JREF-	1SVS487	Z05

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3


In lieu of structural panels or rigid ceiling use purlins to
brace TC @ 24" OC, BC @ 24" OC.

110 mph wind, 15.00 ft mean hgt, ASCE 7-02, CLOSED bldg, not
located within 4.50 ft from roof edge, CAT II, EXP B, wind TC
DL=5.0 psf, wind BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.
Deflection meets L/360 live and L/240 total load. Creep increase
factor for dead load is 1.50.



9-3-8 Over 2 Supports
R=539 U=180 W=3.5"
R=360 U=180 W=3.5"



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

PLT TYP. Wave

Design Crit: TPI-2002 (STD) /FBC
Cq/RT=1.00(1.25)/10(0) 7.24.12

Scale = .375" /Ft.

TC LL	20.0 PSF	FL / - / 4 / - / - / R / -
TC DL	10.0 PSF	REF R487 - - 9885
BC DL	10.0 PSF	DATE 03/24/06
BC LL	0.0 PSF	DRW HCUSR487 06083055
TOT.LD.	40.0 PSF	HC-ENG TCE/AF *
DUR.FAC.	1.25	SEQN - 5245
SPACING	24.0"	JREF - 1SVS487_Z05

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSE 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/19/16GA (W,H/S/K) ASTM A653 GRADE 40/60 (N. K/P.H.S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 100A-Z. THIS DRAWING INDICATES ACCEPTABLE PROFESSIONAL ENGINEER RESPONSIBILITY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE R. FISHER
No. 59887
STATE OF FLORIDA
PROFESSIONAL ENGINEER
March 14 '06

CLB WEB BRACE SUBSTITUTION

THIS DETAIL IS TO BE USED WHEN CONTINUOUS LATERAL BRACING (CLB) IS SPECIFIED ON AN ALPINE TRUSS DESIGN BUT AN ALTERNATIVE WEB BRACING METHOD IS DESIRED.

NOTES:

THIS DETAIL IS ONLY APPLICABLE FOR CHANGING THE SPECIFIED CLB SHOWN ON SINGLE PLY SEALED DESIGNS TO T-BRACING OR SCAB BRACING.

ALTERNATIVE BRACING SPECIFIED IN CHART BELOW MAY BE CONSERVATIVE. FOR MINIMUM ALTERNATIVE BRACING, RE-RUN DESIGN WITH APPROPRIATE BRACING.


WEB MEMBER SIZE	SPECIFIED CLB BRACING	T OR L-BRACE	ALTERNATIVE BRACING SCAB BRACE
2X3 OR 2X4	1 ROW	2X4	1-2X4
2X3 OR 2X4	2 ROWS	2X6	2-2X4
2X6	1 ROW	2X4	1-2X6
2X6	2 ROWS	2X6	2-2X4(*)
2X8	1 ROW	2X6	1-2X8
2X8	2 ROWS	2X6	2-2X6(*)

T-BRACE, L-BRACE AND SCAB BRACE TO BE SAME SPECIES AND GRADE OR BETTER THAN WEB MEMBER UNLESS SPECIFIED OTHERWISE ON ENGINEER'S SEALED DESIGN.

(*) CENTER SCAB ON WIDE FACE OF WEB. APPLY (1) SCAB TO EACH FACE OF WEB.



T-BRACING
OR
L-BRACING:

APPLY TO EITHER SIDE OF WEB
NARROW FACE
ATTACH WITH 16d NAILS AT 6" O.C.
BRACE IS A MINIMUM 80% OF WEB
MEMBER LENGTH




SCAB BRACING:

APPLY SCAB(S) TO WIDE FACE OF WEB.
NO MORE THAN (1) SCAB PER FACE.
ATTACH WITH 10d OR .128"x3" GUN
NAILS AT 6" O.C. BRACE IS A MINIMUM
80% OF WEB MEMBER LENGTH



WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 583 DIONDRID DR., SUITE 200, MADISON, VI 53719 AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, VI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN, ANY FAILURE TO BRACE OR TO FOLLOW THE DESIGN. THIS DESIGN IS THE PROPERTY OF ALPINE ENGINEERED PRODUCTS, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN INCHES. UNLESS OTHERWISE SPECIFIED, ALL MATERIALS SHALL BE GRADE 40/60 (W/K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI 1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.



ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA

THIS DRAWING REPLACES DRAWING 579.640					
TC LL	PSF	REF	CLB	SUBST.	
TC DL	PSF	DATE	11/26/03		
BC DL	PSF	DRWG	BRLCBSUB1103		
BC LL	PSF	-ENG	MLH/KAR		
TOT. LD.	PSF				
DUR. FAC.					
SPACING					