



Lumber design values are in accordance with ANSI/TPI 1 section 6.3  
These truss designs rely on lumber values established by others.

RE: Water - Water

**MiTek USA, Inc.**

6904 Parke East Blvd.  
Tampa, FL 33610-4115

**Site Information:**

Customer Info: SCCI Project Name: . Model: .  
Lot/Block: . Subdivision: .  
Address: ., .  
City: Columbia County State: FL

**Name Address and License # of Structural Engineer of Record, If there is one, for the building.**

Name: License #:  
Address:  
City: State:

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: FBC2017/TPI2014 Design Program: MiTek 20/20 8.2  
Wind Code: ASCE 7-10 Wind Speed: 130 mph  
Roof Load: 40.0 psf Floor Load: N/A psf

This package includes 12 individual, Truss Design Drawings and 0 Additional Drawings.  
With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.


No.	Seal#	Truss Name	Date
1	T19270605	A1GE	1/29/20
2	T19270606	A2	1/29/20
3	T19270607	A3	1/29/20
4	T19270608	A4	1/29/20
5	T19270609	A5	1/29/20
6	T19270610	A6GE	1/29/20
7	T19270611	A7GIR	1/29/20
8	T19270612	B1GE	1/29/20
9	T19270613	B2	1/29/20
10	T19270614	C1GE	1/29/20
11	T19270615	C2	1/29/20
12	T19270616	GIR1	1/29/20

The truss drawing(s) referenced above have been prepared by MiTek USA, Inc.  
under my direct supervision based on the parameters  
provided by Mayo Truss Company, Inc..

Truss Design Engineer's Name: Albani, Thomas

My license renewal date for the state of Florida is February 28, 2021.

**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.




Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29, 2020

Job	Truss	Truss Type	Qty	Ply	Water	T19270605
Water	A1GE	Roof Special Structural Gable	1	1		
Mayo Truss Company, Inc., Mayo, FL - 32066,						Job Reference (optional)

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:25 2020 Page 1  
ID:0f98w1jLwCiaB7RXpbIY3QzqthM-hGp6caO6DXGMhrTZ06f\_YEvHxZCWfllJePwpJfzqXnS



Scale = 1:65.0




Plate Offsets (X,Y) --	[2:0-3-8,Edge], [2:0-1-8,Edge], [12:0-3-8,Edge], [12:0-6-0,Edge], [12:0-0-4,0-0-12], [23:0-1-13,0-0-12], [26:0-1-13,0-0-12], [43:0-1-8,0-0-12]
------------------------	--

<b>LOADING</b> (psf)	<b>SPACING-</b>	<b>2-0-0</b>	<b>CSI.</b>	<b>DEFL.</b>	<b>in (loc)</b>	<b>l/def</b>	<b>L/d</b>	<b>PLATES</b>	<b>GRIP</b>
TCLL 20.0	Plate Grip DOL	1.25	TC 0.60	Vert(LL)	-0.10 15-16	>999	240	MT20	244/190
TCDL 10.0	Lumber DOL	1.25	BC 0.49	Vert(CT)	-0.21 15-16	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.28	Horz(CT)	0.03 52	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-AS					Weight: 219 lb	FT = 0%

#### LUMBER-

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.2  
OTHERS 2x4 SP No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied.  
BOT CHORD Rigid ceiling directly applied.

#### REACTIONS.

All bearings 8-8-0 except (jt=length) 12=8-3-8, 15=8-3-8, 15=8-3-8, 14=8-3-8, 12=8-3-8.  
(lb) - Max Horz 2=-114(LC 10)  
Max Uplift All uplift 100 lb or less at joint(s) 2, 12, 15 except 21=-340(LC 22)  
Max Grav All reactions 250 lb or less at joint(s) 2, 14, 22, 2 except 12=281(LC 22), 20=1644(LC 1), 20=1644(LC 1), 15=986(LC 1), 15=986(LC 1), 12=281(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-4=-48/374, 4-5=-137/1079, 7-8=-554/160, 8-9=-955/218, 9-10=-20/329  
BOT CHORD 2-22=-290/100, 21-22=-290/100, 19-20=-1608/345, 5-19=-1181/283, 18-19=-940/261, 17-18=0/460, 16-17=-86/899, 15-16=-389/127  
WEBS 4-21=0/433, 4-19=-658/164, 5-18=-93/1030, 7-18=-589/123, 7-17=-72/542, 8-17=-488/167, 9-16=-174/1226, 9-15=-707/276, 10-15=-294/57

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=35ft; eave=5ft; Cat. II; Exp B; Encl. GCpl=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 1.5x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 12, 15, 2, 12 except (jt=lb) 21=340.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020



**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610




Mayo Truss Company, Inc., Mayo, FL - 32066, 8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:26 2020 Page 1

ID:0198w1jLwCIAB7RXpbiY3QzqtHm-9TNUpwPk\_rODI?2maqAD4RSRkzVqO3lSt3gMrSzgXnR

-1-6-0	4-7-4	8-8-0	13-6-0	16-6-0	19-1-4	26-8-8	30-3-12	35-0-0	36-6-0
1-6-0	4-7-4	4-0-12	4-10-0	3-0-0	2-7-4	7-7-4	3-7-4	4-8-4	1-6-0

Scale: 3/16"=1'



<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied.
WEBS	2x4 SP No.2		

**REACTIONS.** (lb/size) 2=-377/0-3-8, 18=2468/0-3-8, 10=889/0-3-8  
Max Horz 2=-131(LC 10)  
Max Uplift 2=-571(LC 22), 18=-417(LC 12), 10=-218(LC 12)  
Max Grav 2=108(LC 9), 18=2468(LC 1), 10=889(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**TOP CHORD** 2-3=-1557/1502, 3-4=-1900/2137, 4-5=-139/348, 5-6=-119/365, 6-7=-476/526,  
7-8=-1438/1569, 8-9=-2026/2022, 9-10=-2393/2164

**BOT CHORD** 2-19=-1319/1497, 18-19=-195/295, 17-18=-2454/2210, 4-17=-1887/1673,  
16-17=-1925/1986, 15-16=-89/387, 14-15=-1193/1355, 13-14=-1864/2027,  
12-13=-2048/2294, 10-12=-2051/2300

**WEBS** 3-19=-201/352, 17-19=-1152/1227, 3-17=-681/439, 4-16=-1654/1799, 5-16=-503/231,  
6-16=-964/930, 6-15=-936/956, 7-15=-1079/1244, 7-14=-572/408, 8-14=-621/490,  
8-13=-251/98, 9-13=-352/194

**NOTES-**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCFL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=35ft; eave=5ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) All plates are MT20 plates unless otherwise indicated.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=571, 18=417, 10=218.
- 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29, 2020

 **WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE


**WARNING – Verify design parameters and READ NOTES ON THIS AND INCLUDED MITER REFERENCE PAGE MM-1473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 36610

Mayo Truss Company, Inc., Mayo, FL - 32066, 8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:27 2020 Page 1  
ID:0I98w1jLwCIAB7RXpbiY3QzqthM-dfws1GQMl8W3w9cy8XhSdf?Z2Nru7Yqb5jPvNXzqXnQ  
1-6-0 7-1-15 13-6-0 19-1-4 26-8-8 30-3-12 35-0-0 36-6-0  
1-6-0 7-1-15 6-4-1 5-7-4 7-7-4 3-7-4 4-8-4 1-6-0  
Scale: 3/16"=1'



**REACTIONS.** (lb/size) 2=1017/0-3-8, 11=1997/0-3-8, 8=-34/0-3-8  
 Max Horz 2=-119(LC 10)  
 Max Uplift 2=-39(LC 12), 11=-63(LC 12), 8=-147(LC 10)  
 Max Grav 2=1017(LC 1), 11=1997(LC 1), 8=61(LC 22)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**TOP CHORD** 2-3=-2868/591, 3-4=-1797/332, 4-5=-1783/335, 5-6=-1589/304, 6-7=-376/1720,  
7-8=-5/1244

**BOT CHORD** 2-14=-429/2587, 13-14=-432/2580, 12-13=-166/1595, 11-12=-1791/488, 10-11=-1185/68,  
8-10=-1175/56

**WEBS** 3-14=0/274, 3-13=-994/379, 4-13=-113/1181, 5-12=-770/262, 6-12=-594/3201,  
6-11=-1292/386, 7-11=-469/403

**NOTES-**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=35ft; eave=5ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 11 except (jt=lb) 8=147.
- 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Thomas A. Albani PE No.39380  
MITek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.

**MiTek**  
6904 Parke East Blvd.




Job	Truss	Truss Type	Qty	Ply	Water	T19270608
Water	A4	Roof Special	6	1		

Mayo Truss Company, Inc., Mayo, FL - 32066,

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:28 2020 Page 1

ID:0198w1jLwCIAb7RXpbY3QzqthM-5rUEEcR\_WSewYJB8hFCh9sXrenExs1jIKN9Tv\_zqXnP



Scale = 1:45.8




Plate Offsets (X,Y)-- [3:0-2-8,0-3-0], [9:0-4-8,0-3-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/def	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.44	Vert(LL)	-0.06 10-13	>999	240	MT20	244/190
TCDL 10.0	Lumber DOL	1.25	BC 0.50	Vert(CT)	-0.14 10-13	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.62	Horz(CT)	0.03 7	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-AS					Weight: 119 lb	FT = 0%

#### LUMBER-

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals.  
BOT CHORD Rigid ceiling directly applied.

#### REACTIONS.


(lb/size) 2=916/0-3-8, 7=819/Mechanical  
Max Horz 2=168(LC 11)  
Max Uplift 2=37(LC 12)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1364/314, 3-4=-750/252, 4-5=-726/252, 5-6=-285/129, 6-7=-818/194  
BOT CHORD 2-10=-387/1154, 9-10=-389/1151, 8-9=-119/305  
WEBS 3-10=0/287, 3-9=-658/243, 4-9=-30/330, 5-9=-71/346, 5-8=-678/278, 6-8=-214/803

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=24ft; eave=4ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	Water	T19270609
Water	A5	Roof Special	2	1		

Mayo Truss Company, Inc., Mayo, FL - 32066,

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:29 2020 Page 1

ID:0198w1jLwCIAb7RXpbY3QzqthM-Z22cSyRcHmnm9TmkFyjiw44y5AVVbUTuZ1u0SQzqXnO

-1-6-0	7-1-15	13-6-0	19-1-4	24-0-8	28-11-12	35-0-0	36-0-0
1-6-0	7-1-15	6-4-1	5-7-4	4-11-4	4-11-4	6-0-4	1-0-0

Scale = 1:62.1




Plate Offsets (X,Y)---	[2:0-0-4,Edge], [3:0-2-8,0-3-0], [7:0-2-8,0-3-0], [12:0-2-4,0-3-0], [13:0-4-8,0-3-0]
------------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.65	Vert(LL)	-0.33	11-12	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.25	BC 0.80	Vert(CT)	-0.67	11-12	>629		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.59	Horz(CT)	0.17	8	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-AS					Weight: 173 lb	FT = 0%

#### LUMBER-

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2 \*Except\*  
8-12: 2x4 SP No.1  
WEBS 2x4 SP No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied.  
BOT CHORD Rigid ceiling directly applied.  
WEBS 1 Row at midpt 5-13

#### REACTIONS.

(lb/size) 2=1491/0-3-8, 8=1459/0-3-8  
Max Horz 2=-117(LC 10)  
Max Uplift 2=-37(LC 12), 8=-23(LC 12)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2617/622, 3-4=-2029/559, 4-5=-2003/556, 5-6=-3224/805, 6-7=-3992/959,  
7-8=-4721/1100  
BOT CHORD 2-14=-444/2270, 13-14=-445/2267, 12-13=-615/3052, 11-12=-822/3841,  
10-11=-1017/4548, 8-10=-1013/4555  
WEBS 3-14=0/280, 3-13=-639/236, 4-13=-307/1378, 5-13=-1623/453, 5-12=-57/550,  
6-12=-872/237, 6-11=-10/362, 7-11=-758/205

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=35ft; eave=5ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020



**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610



Job	Truss	Truss Type	Qty	Ply	Water	T19270610
Water	A6GE	Roof Special Supported Gable	1	1		
Mayo Truss Company, Inc., Mayo, FL - 32066,						Job Reference (optional)

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:30 2020 Page 1  
ID:0198w1jLwCIAb7RXpbY3QzqthM-1Ec?flSE23uendLXpgF9FHdDMa\_vK3U2nhea\_szzXnN

-1-6-0 13-6-0 19-0-0 35-0-0 36-0-0  
1-6-0 13-6-0 5-6-0 16-0-0 1-0-0

Scale: 3/16"=1'




Plate Offsets (X,Y)=-		[2:0-4-0,0-2-1], [20:0-3-8,Edge], [20:0-6-0,Edge]	
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>
TCLL 20.0	Plate Grip DOL	1.25	TC 0.30
TCDL 10.0	Lumber DOL	1.25	BC 0.22
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.09
BCDL 10.0	Code	FBC2017/TPI2014	Matrix-S
			<b>DEFL.</b>
			in (loc) l/defl L/d
			Vert(LL) 0.00 21 n/r 120
			Vert(CT) 0.01 21 n/r 120
			Horz(CT) 0.00 20 n/a n/a
			<b>PLATES</b>
			MT20
			<b>GRIP</b>
			244/190
			Weight: 186 lb FT = 0%

#### LUMBER-

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.

All bearings 35-0-0.

(lb) - Max Horz 2=-114(LC 10)

Max Uplift All uplift 100 lb or less at joint(s) 2, 12, 20, 33, 34, 35, 36, 31, 29, 26, 25, 23

Max Grav All reactions 250 lb or less at joint(s) 2, 12, 32, 33, 34, 35, 36, 37, 31, 29, 27, 26, 25, 24, 23  
except 20=289(LC 1), 22=407(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**WEBS** 18-22=-291/146

#### NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=35ft; eave=2ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 1.5x4 MT20 unless otherwise indicated.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 2-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 12, 20, 33, 34, 35, 36, 31, 29, 26, 25, 23.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	Water	T19270611
Water	A7GIR	ROOF SPECIAL GIRDER	1	3		

Mayo Truss Company, Inc., Mayo, FL - 32066,

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:39 2020 Page 1  
ID:0198w1jLwCIAb7RXpbY3QzqthM-HzfOYNZuwq1NM?XFr3vG6BUdWCwox1BNsaJYorzqXnE

-1-6-0	5-1-0	9-3-8	13-6-0	19-1-4	22-7-11	26-2-2	29-8-9	35-0-0	36-0-0
1-6-0	5-1-0	4-2-8	4-2-8	5-7-4	3-6-7	3-6-7	3-6-7	5-3-7	1-0-0

Scale = 1:66.5




Plate Offsets (X,Y)-		5-1-0	9-3-8	13-6-0	19-1-4	22-7-11	26-2-2	29-8-9	35-0-0
		5-1-0	4-2-8	4-2-8	5-7-4	3-6-7	3-6-7	3-6-7	5-3-7
		[3:0-2-8,0-3-0], [8:0-3-4,0-3-4], [10:0-3-7,0-0-8], [14:0-3-8,0-4-0], [15:0-3-0,0-4-12], [16:0-4-0,0-4-8]							
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.78	Vert(LL)	-0.39 14-15	>999	240	MT20	244/190
TCDL 10.0	Lumber DOL	1.25	BC 0.74	Vert(CT)	-0.76 14-15	>549	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.51	Horz(CT)	0.13 10	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-MS					Weight: 649 lb	FT = 0%

#### LUMBER-

TOP CHORD 2x4 SP No.2 \*Except\*  
8-11: 2x4 SP No.1  
BOT CHORD 2x6 SP No.2 \*Except\*  
10-15: 2x6 SP SS  
WEBS 2x4 SP No.2

REACTIONS. (lb/size) 2=3362/0-3-8, 10=5754/0-3-8  
Max Horz 2=-118(LC 6)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-6944/0, 3-4=-6591/0, 4-5=-6199/0, 5-6=-6245/0, 6-7=-13044/0, 7-8=-16527/0,  
8-9=-18601/0, 9-10=-20388/0  
BOT CHORD 2-18=0/6175, 17-18=0/6172, 16-17=0/5844, 15-16=0/12276, 14-15=0/16012,  
13-14=0/17966, 12-13=0/19752, 10-12=0/19752  
WEBS 3-17=-401/37, 4-17=0/333, 4-16=-522/33, 5-16=0/5179, 6-16=-8252/0, 6-15=0/4890,  
7-15=-4617/0, 7-14=0/3819, 8-14=-2315/0, 8-13=0/1464, 9-13=-1838/0, 9-12=0/928

#### NOTES-

- 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-7-0 oc.  
Bottom chords connected as follows: 2x6 - 3 rows staggered at 0-4-0 oc.  
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=35ft; eave=5ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Use USP THD26-2 (With 18-16d nails into Girder & 12-10d nails into Truss) or equivalent at 20-10-0 from the left end to connect truss(es) to back face of bottom chord.
- Use USP HUS26 (With 14-16d nails into Girder & 6-16d nails into Truss) or equivalent spaced at 2-0-0 oc max. starting at 21-11-4 from the left end to 32-11-4 to connect truss(es) to back face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610



Job	Truss	Truss Type	Qty	Ply	Water	T19270611
Water	A7GIR	ROOF SPECIAL GIRDER	1	3	Job Reference (optional)	

Mayo Truss Company, Inc., Mayo, FL - 32066,

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:39 2020 Page 2  
ID:0I98w1jLwCIAb7RXpbiY3QzqthM-HzfOYNZuwq1NM?XFr3vG6BUdWCwox1BNsaJYorqzXnE

#### LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-5=-60, 5-6=-60, 6-11=-60, 2-10=-20

Concentrated Loads (lb)

Vert: 14=-485(B) 23=-2774(B) 24=-485(B) 25=-485(B) 26=-485(B) 27=-485(B) 28=-485(B) 29=-485(B)

#### WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	Water	T19270612
Water	B1GE	Common Supported Gable	1	1		
Mayo Truss Company, Inc., Mayo, FL - 32066,						Job Reference (optional)

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:40 2020 Page 1  
ID:0198w1jLwCIAb7RXpbY3QzqthM-I9DnlaWh89D\_96SOMQVIO1ylcRygbfW5E35KHqXnD





Plate Offsets (X,Y)--	[2:0-4-0,0-2-1], [3:0-0-0,0-1-15], [13:0-0-0,0-1-15], [14:0-4-0,0-2-1], [16:0-0-13,0-1-9], [16:0-1-9,1-9-1], [20:0-2-8,0-3-0], [24:0-0-13,0-1-9], [24:0-1-9,1-9-1]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.14	Vert(LL)	-0.01	15	n/r	120	MT20	244/190
TCDL 10.0	Lumber DOL	1.25	BC 0.04	Vert(CT)	-0.01	15	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	14	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-S						Weight: 113 lb	FT = 0%

**LUMBER-**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** All bearings 21-0-0.  
(lb) - Max Horz 2=-94(LC 10)  
Max Uplift All uplift 100 lb or less at joint(s) 2, 14, 21, 22, 23, 19, 18, 17  
Max Grav All reactions 250 lb or less at joint(s) 2, 14, 20, 21, 22, 23, 24, 19, 18, 17, 16

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=24ft; eave=2ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 1.5x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 14, 21, 22, 23, 19, 18, 17.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610




Job	Truss	Truss Type	Qty	Ply	Water	T19270613
Water	B2	Scissor	6	1		

Mayo Truss Company, Inc., Mayo, FL - 32066,

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:41 2020 Page 1  
ID:0l98w1jLwCIAB7RXpbY3QzqthM-DLn9z2b8SSH4cJheyTxkBca1f0f\_P\_tfJuoftjqzXnC



Scale = 1:40.3



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.55	Vert(LL)	0.32	9-10	>796	MT20	244/190
TCDL 10.0	Lumber DOL	1.25	BC 0.57	Vert(CT)	-0.33	9-10	>757		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.30	Horz(CT)	0.23	6	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-AS					Weight: 94 lb	FT = 0%

#### LUMBER-

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied.  
BOT CHORD Rigid ceiling directly applied.

#### REACTIONS.

(lb/size) 2=930/0-3-8, 6=930/0-3-8  
Max Horz 2=-99(LC 10)  
Max Uplift 2=-218(LC 12), 6=-218(LC 12)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2609/2687, 3-4=-1894/1835, 4-5=-1894/1835, 5-6=-2609/2706  
BOT CHORD 2-10=-2317/2351, 9-10=-2232/2358, 8-9=-2251/2358, 6-8=-2338/2351  
WEBS 4-9=-1470/1336, 5-9=-683/884, 5-8=-298/189, 3-9=-683/887, 3-10=-298/189

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=24ft; eave=4ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 2, 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=218, 6=218.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	Water	T19270614
Water	C1GE	Common Supported Gable	1	1		

Mayo Truss Company, Inc., Mayo, FL - 32066,

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:42 2020 Page 1  
ID:0I98w1jLwCIAb7RXpbIY3QzqthM-hYKXA0cmDIPxDTGqWBSzKp6KOQ7T8VYpYYYCPAzqXnB




Plate Offsets (X,Y)---	[1:0-4-0,0-2-1], [2:0-0-0,0-1-15], [8:0-0-0,0-1-15], [9:0-4-0,0-2-1], [10:0-0-13,0-1-9], [10:0-2-9,1-7-1], [14:0-0-13,0-1-9], [14:0-2-9,1-7-1]
------------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.04	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.25	BC 0.04	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.02	Horz(CT)	0.00	9	n/a	n/a		
BCDL 10.0	Code FBC2017/TPI2014		Matrix-S						Weight: 57 lb	FT = 0%

#### LUMBER-

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

All bearings 12-7-8.  
(lb) - Max Horz 1=47(LC 10)  
Max Uplift All uplift 100 lb or less at joint(s) 13, 14, 11, 10  
Max Grav All reactions 250 lb or less at joint(s) 1, 9, 12, 13, 14, 11, 10

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=24ft; eave=2ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 13, 14, 11, 10.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



6904 Parke East Blvd.  
Tampa, FL 33610



Job	Truss	Truss Type	Qty	Ply	Water	T19270615
Water	C2	Scissor	7	1		

Mayo Truss Company, Inc., Mayo, FL - 32066,

8.240 s Dec 6 2019 MiTek Industries, Inc. Wed Jan 29 09:26:43 2020 Page 1  
ID:0198w1jLwCIAb7RXpbiY3QzqthM-9kuvOkcO\_3Xorcr14uzCG1fPZqMStwcynCHmxczqXnA




Plate Offsets (X,Y)-- [1:0-1-11,0-0-9], [3:0-1-11,0-0-9]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.40	Vert(LL)	-0.06	4-10	>999	240	244/190
TCDL 10.0	Lumber DOL	1.25	BC 0.44	Vert(CT)	-0.13	4-10	>999	180	
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.16	Horz(CT)	0.06	3	n/a	n/a	
BCDL 10.0	Code FBC2017/TPI2014		Matrix-AS						
								Weight: 43 lb	FT = 0%

#### LUMBER-

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied.  
BOT CHORD Rigid ceiling directly applied.

**REACTIONS.** (lb/size) 1=505/Mechanical, 3=505/0-3-8  
Max Horz 1=52(LC 11)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1252/329, 2-3=-1252/329  
BOT CHORD 1-4=-221/1129, 3-4=-221/1129  
WEBS 2-4=-72/700

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=101mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; B=45ft; L=24ft; eave=4ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (directional) and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 3 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Thomas A. Albani PE No.39380  
MiTek USA, Inc. FL Cert 6634  
6904 Parke East Blvd. Tampa FL 33610  
Date:

January 29,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




6904 Parke East Blvd.  
Tampa, FL 33610






# Symbols

## PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{1}{16}$ " from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in **MiTek 20/20** software or upon request.

## PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

## BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

## Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.  
DSB-89: Design Standard for Bracing.  
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

# Numbering System

6-4-8  
dimensions shown in ft-in-sixteenths  
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

## PRODUCT CODE APPROVALS

ICC-ES Reports:  
ESR-1311, ESR-1352, ESR1988  
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.  
Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MiTek® All Rights Reserved



MiTek Engineering Reference Sheet: ML-7473 rev. 10/03/2015



# General Safety Notes


Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.

Water

Client: SCCI  
Date: 1/29/2020  
Quote Date: /  
Seal Date: /  
Designer: Stephanie Ramirez  
Job Number: 0120-067  
Roof Loading  
TC Live: 20.00 psf  
TC Dead: 10.00 psf  
BC Live: 0.00 psf  
BC Dead: 10.00 psf  
Spacing: 2.00 O.C.

Mayo Truss Company Inc.  
Ph. (386) 294-3988  
Fax (386) 294-3981  
mayotruss@windstream.net



add load-bearing wall  
in bedroom #1