

"PROPERTY SIDE FACING STREET"

1 SAFETY PLAN
N.T.S.

LOCATION OF NEAREST URGENT CARE FACILITY	
NAME:	
ADDRESS:	
PHONE NUMBER:	
NOTES:	
1.	INSTALLERS SHALL DRAW IN DESIGNATED SAFETY AREA AROUND HOME
2.	INSTALLERS SHALL UPDATE NAME ADDRESS AND PHONE NUMBER OF NEAREST URGENT CAR FACILITY RELATIVE TO THE SITE BEFORE STARTING WORK

DOCUMENT CONTROL			
ISSUED FOR PERMIT	DATE	CAD	QC
	12-27-2021	BW	JG
REV	DESCRIPTION	DATE	CAD

ENGINEER CONTACT INFORMATION
ENGIPARTNERS LLC
 C.A. 32661
 255 GIRALDA AVE
 CORAL GABLES, FL 33134
 DESIGN@ENGIPARTNERS.COM
 833 - 888 - 3644

ENGINEERING STAMP
 Digitally signed
 by Rafael A
 Gonzalez Soto
 Date:
 2022.01.17
 05:14:50 -05'00'


CONTRACTOR CONTACT INFORMATION
TITAN SOLAR POWER FL
 12221 N US HIGHWAY 301
 THONOTASASSA, FL 33592
 (813) 982 -9001
 #EC13008093



CUSTOMER: SANDY FIROOZ
PROJECT ADDRESS:
 161 NORTHWEST SPARR LANE
 LAKE CITY FL 32055
PARCEL NUMBER: 22-2S-16-01716-002

SHEET NAME: SAFETY PLAN		
PROJECT ID: TSP110728	ENGINEER OF RECORD: ENG. RAFAEL A. GONZALEZ SOTO, PE	SHEET TITLE: C-2
	DATE: 12-27-2021	SHEETS: 2 OF 9

WIRE TAG	WIRE SIZES, QUANTITY & TYPE			RACEWAY SIZE, TYPE, LOCATION & INFO.			WIRE AMPACITY CALCULATIONS				ADDITIONAL INFORMATION						
	CONDUCTOR QTY. SIZE & TYPE	NEUTRAL QTY. SIZE & TYPE	GROUND QTY. SIZE & TYPE	RACEWAY SIZE & TYPE	RACEWAY LOCATION	RACEWAY HEIGHT ABOVE ROOF	OUTPUT CURRENT	125% OF OUTPUT CURRENT	MIN OCPD	WIRE DE-RATED CALCULATION				DIST.	VOLTAGE	VOLTAGE DROP %	CONDUIT FILL %
										WIRE RATING	AMBIENT TEMP	# OF COND.	FINAL AMPACITY				
DC (BEFORE JB)	(4) #10 AWG PV WIRE	N/A	(1) #8 AWG BARE COPPER	NOT APPLICABLE	UNDER ARRAY	1/2" TO 3-1/2"	15A	18.8A	20A	40A X 0.76 X 1 = 30.4 A				10 FT.	350V	0.11%	6.4%
DC (AFTER JB)	(4) #10 AWG THWN-2	N/A	(1) #8 AWG THWN-2	3/4" EMT CONDUIT	ABOVE ROOF	1/2" TO 3-1/2"	15A	18.8A	20A	40A X 0.76 X 0.8 = 24.3 A				20 FT.	350V	0.21%	8.1%
AC (INVERTER TO METER)	(2) #10 AWG THWN-2	(1)#10AWG THWN-2	(1) #8 AWG THWN-2	3/4" EMT CONDUIT	EXTERIOR WALL	"N/A"	16A	20.0A	20A	40A X 0.76 X 1 = 30.4 A				5 FT.	240V	0.1%	7.7%



EXISTING UNDERGROUND SERVICE
240V/120V 200A BUS BAR
3 #3/0 THWN-2

INVERTER TOTAL OUTPUT: 16A
SAFETY RATING (125%): 20A
TOTAL PV SYSTEM OCPD: 20A

MAIN BREAKER RATING: 200A
BUS BAR RATING: 200A
120% BACKFEED RATING: 40A

1 ONE LINE RISER DIAGRAM

N.T.S.

LEGEND:

1	(13) Q.PEAK DUO BLK ML-G10+395W BY Q CELL REFER TO D-1 SHEET	2	2 #10 PV WIRE PER STRING 1 #8 BARE WIRE GROUND 3/4" EMT CONDUIT	3	NEMA3R JUNCTION BOX
4	2 #10 THWN-2 PER STRING 1 #8 THWN-2 GROUND 3/4" EMT CONDUIT	5	SE3800H-US BY SOLAREEDGE REFER TO D-3 SHEET	6	2 #10 L1,L2 THWN-2 1 #10 THWN-2 NEUTRAL 1 #8 THWN-2 GROUND 3/4" EMT CONDUIT
7	PV SYSTEM DISCONNECT - 30A RATED	8	PV INTERCONNECTION POINT - PV BREAKER	9	UTILITY ELECTRICAL SERVICE


DOCUMENT CONTROL		DATE	CAD	QC	ENGINEER CONTACT INFORMATION		ENGINEERING STAMP		CONTRACTOR CONTACT INFORMATION		CONTRACTOR LOGO	CUSTOMER:	SHEET NAME:	
ISSUED FOR PERMIT	12-27-2021	BW	JG		ENGPARTNERS LLC		Digitally signed by Rafael A. Gonzalez Soto Date: 2022.01.17 05:14:59 -05'00'		TITAN SOLAR POWER FL 12221 N US HIGHWAY 301 THONOTASASSA, FL 33592			SANDY FIROOZ	ONE LINE RISER DIAGRAM	
REV	DESCRIPTION	DATE	CAD	QC	C.A. 32661 255 GIRALDA AVE CORAL GABLES, FL 33134 DESIGN@ENGPARTNERS.COM 833 - 888 - 3644		(813) 982 - 9001 #EC13008093		PROJECT ADDRESS: 161 NORTHWEST SPARR LANE LAKE CITY FL 32055	PROJECT ID: TSP110728		ENGINEER OF RECORD: ENG. RAFAEL A. GONZALEZ SOTO, PE DATE: 12-27-2021		
												PARCEL NUMBER: 22-2S-16-01716-002		



LEGEND & SYMBOLS

- OBS
 ROOF OBSTRUCTIONS
- ARRAY #
MODULE #
STRING #
- PV MODULES
- TRUSSES OR RAFTERS
- ROOF MOUNTS & RAIL
- ROOF SLOPE
- EXT.
 EXTERIOR PV MODULE

SOLAR MODULE



UL 1703 CERTIFIED
MAX. DESIGN LOAD: 83.54 psf
APPLIED WIND LOAD : 34.12 psf

NOTES:
-INSTALL MID CLAMPS BETWEEN MODULES AND ENDS CLAMPS AT THE END OF EACH ROW OF MODULES.
-ALUMINUM RAILS SHOULD ALWAYS BE SUPPORTED BY MORE THAN ONE FOOTING ON BOTH SIDES OF THE SPLICE.

WEIGHTED AVERAGE

WORST CASE MODULE:

ZONE 1: 21%
ZONE 2e: 64%
ZONE 2r: 15%



$$25.49(0.21) + 36.41(0.64) + 36.41(0.15) = 34.12\text{psf}$$

ULTIMATE WIND SPEED	120 mph
DESIGN WIND SPEED	117 mph
RISK CATEGORY	II
EXPOSURE CATEGORY	C
ROOF SLOPE (°)	26
ROOF TYPE	HIPPED
MATERIAL ROOF TYPE	ASPHALT SHINGLES
PRESSURE ZONE:	1&2
MEAN ROOF HEIGHT:	13.73
PERIMETER WIDTH:	3.0
K _D	0.85
K _{ZT}	1.00
K _H	0.850

ROOF'S GENERAL NOTES:
1- CONTRACTOR/INSTALLER TO VERIFY ROOF CONDITIONS FOR PROPER INSTALLATION OF THE PV SYSTEM.
2- CONTRACTOR/INSTALLER TO NOTIFY THE OWNER IMMEDIATELY OF ANY ROOF DEFICIENCIES AND/OR REPAIR REQUIRED TO INSTALL THE PV SYSTEM.
3- EOR DOES NOT ASSUME ANY RESPONSIBILITY FOR THE INSTALLATION OF ANY PV SYSTEM ON DEFICIENT ROOFS.
4- CONTRACTOR/INSTALLER ASSUMES ALL RESPONSIBILITY TO INSTALL AS PER MANUFACTURER STANDARDS.

ROOF INSPECTION NOTE:
PV MODULE IN LAYOUT IS CONSIDERED NON-EXPOSED AFTER COMPLYING WITH THE FOLLOWING STATEMENTS BASED ON ASCE7-16:
-NO INDIVIDUAL PV MODULE IS MORE THAN 0.5(MEAN ROOF HEIGHT) AWAY FROM ROOF EDGE OR ANOTHER MODULE.
-NO INDIVIDUAL PV MODULE IS MORE THAN 4 FT AWAY FROM ROOF EDGE OR ANOTHER MODULE.
-INDIVIDUAL PV MODULE IS MORE THAN 1.5(MODULE LENGTH) AWAY FROM CLOSEST EXPOSED EDGE

ASCE 7.16 - 29.4-7
DESIGNED WIND PRESSURES:
$$p = q_h (GC_p)(\gamma_E)(\gamma_a)$$



VELOCITY PRESSURE (q) = 0.60*0.00256* K _H K _{ZT} K _D V ²	15.17				
VELOCITY PRESSURE (ASD)	15.17				
INTERIOR EDGE FACTOR: $\gamma_E = 1.0$	EXTERIOR EDGE FACTOR: $\gamma_E = 1.5$	ARRAY EQUALIZATION FACTOR: $\gamma_a = 0.8$			
EXTERNAL PRESSURE COEFFICIENT Z1	0.7	-1.4			
EXTERNAL PRESSURE COEFFICIENT Z2e	0.7	-2.0			
EXTERNAL PRESSURE COEFFICIENT Z2r	0.7	-2.0			
EXTERNAL PRESSURE COEFFICIENT Z3	0.7	-2.0			
INTERNAL PRESSURE COEFFICIENT	0.18				
ZONES	PRESSURES (PSF)	INTERIOR PRESSURES (PSF)	EXTERIOR PRESSURES (PSF)	MAX SPAN (FT)	MAX CANTI-LEVER (IN)
1	-23.97	-16.99	-25.49	6'	24"
2e	-33.07	-24.27	-36.41	6'	24"
2r	-33.07	-24.27	-36.41	4'	16"
3	-33.07	-24.27	-36.41	4'	16"
TOTAL ROOF AREA	1961.57 sq.-ft				
TOTAL MODULES:	13				
TOTAL PHOTOVOLTAIC AREA:	274.69 sq.-ft				
WIND LOAD (PSF):	34.12				
TOTAL WIND LOAD (LBS):	9,372.42				
TOTAL ROOF MOUNTS:	44				
TENSION FORCE PER MOUNT (LBS):	213.01				


1 STRUCTURAL ROOF PLAN & PV MODULES LAYOUT

N.T.S.

DOCUMENT CONTROL				ENGINEER CONTACT INFORMATION				ENGINEERING STAMP				CONTRACTOR CONTACT INFORMATION				CONTRACTOR LOGO				CUSTOMER:				SHEET NAME:							
ISSUED FOR PERMIT				ENGINEPARTNERS LLC												SANDY FIROOZ				STRUCTURAL PLAN											
REV DESCRIPTION				C.A. 32661 255 GIRALDA AVE CORAL GABLES, FL 33134 DESIGN@ENGIPARTNERS.COM 833 - 888 - 3644												TITAN SOLAR POWER FL 12221 N US HIGHWAY 301 THONOTASASSA, FL 33592 (813) 982 - 9001 #EC13008093								PROJECT ADDRESS: 161 NORTHWEST SPARR LANE LAKE CITY FL 32055							
																				PROJECT ID: TSP110728				ENGINEER OF RECORD: ENG. RAFAEL A. GONZALEZ SOTO, PE				SHEET TITLE: S-1			
																								DATE: 12-27-2021				SHEETS: 5 OF 9			

We support PV systems
Primarily Eversol Solar Systems®

CROSSRAIL 44-X




Mechanical Properties

Material	6061-T6 ALU.
Weight	0.7118 (25.65 oz/in)
Ultimate Tensile Strength	87.7 ksi (608 MPa)
Tensile Yield	36.2 ksi (251 MPa)
Height	1.40 (35.41 mm)
Finish	Mt or Sat Anodized

Sectional Properties

Material	6061-T6 ALU.
E _x	10.603E+06 (3.09E+11)
I _x	0.4868 (0.01295 cm ⁴)
S _x	0.4468 (0.011253 cm ³)
J _x	0.0000 (0.0000 cm ⁴)


Units [mm] in



1. See data sheet for dimensions and tolerances. 2. See data sheet for material properties. 3. See data sheet for material properties. 4. See data sheet for material properties.

We support PV systems
Primarily Eversol Solar Systems®

Yeti Clamp



TECHNICAL SHEET


Item Number	Description	Part Number
1	Yeti Clamp Base	44-000001-01 (1/2" x 1/2" x 1/2")
2	Spring	1/2" x 1/2" x 1/2"
3	Yeti Clamp Top	44-000002-01 (1/2" x 1/2" x 1/2")
4	Washer	1/2" x 1/2" x 1/2"
5	Washer	1/2" x 1/2" x 1/2"

Technical Data

Material	6061-T6 ALU.
Weight	0.7118 (25.65 oz/in)
Ultimate Tensile Strength	87.7 ksi (608 MPa)
Tensile Yield	36.2 ksi (251 MPa)
Height	1.40 (35.41 mm)
Finish	Mt or Sat Anodized

We support PV systems
Primarily Eversol Solar Systems®

CrossRail Mid Clamp



TECHNICAL SHEET


Item Number	Description	Part Number
1	CrossRail Mid Clamp Base	44-000003-01 (1/2" x 1/2" x 1/2")
2	Spring	1/2" x 1/2" x 1/2"
3	CrossRail Mid Clamp Top	44-000004-01 (1/2" x 1/2" x 1/2")
4	Washer	1/2" x 1/2" x 1/2"
5	Washer	1/2" x 1/2" x 1/2"

Technical Data

Material	6061-T6 ALU.
Weight	0.7118 (25.65 oz/in)
Ultimate Tensile Strength	87.7 ksi (608 MPa)
Tensile Yield	36.2 ksi (251 MPa)
Height	1.40 (35.41 mm)
Finish	Mt or Sat Anodized

We support PV systems
Primarily Eversol Solar Systems®

Splice Foot X



TECHNICAL SHEET

Item Number	Description	Part Number
1	Splice Foot X	44-000005-01 (1/2" x 1/2" x 1/2")
2	Spring	1/2" x 1/2" x 1/2"
3	Washer	1/2" x 1/2" x 1/2"
4	Washer	1/2" x 1/2" x 1/2"

Technical Data

Material	6061-T6 ALU.
Weight	0.7118 (25.65 oz/in)
Ultimate Tensile Strength	87.7 ksi (608 MPa)
Tensile Yield	36.2 ksi (251 MPa)
Height	1.40 (35.41 mm)
Finish	Mt or Sat Anodized

Bostik
smart adhesives



915
POLYURETHANE SEALANT & ADHESIVE

KEY FEATURES

- Easy to use, one-part adhesive
- High strength, long-term durability
- Excellent adhesion to a wide range of substrates
- Excellent weatherability
- Excellent UV stability
- Excellent resistance to mold and mildew
- Excellent resistance to water and moisture
- Excellent resistance to salt crystallization
- Excellent resistance to acid rain
- Excellent resistance to alkali
- Excellent resistance to oil and grease
- Excellent resistance to dirt and grime
- Excellent resistance to staining
- Excellent resistance to discoloration
- Excellent resistance to fading
- Excellent resistance to chalking
- Excellent resistance to cracking
- Excellent resistance to peeling
- Excellent resistance to delamination
- Excellent resistance to blistering
- Excellent resistance to bubbling
- Excellent resistance to voiding
- Excellent resistance to porosity
- Excellent resistance to permeability
- Excellent resistance to absorption
- Excellent resistance to desiccation
- Excellent resistance to shrinkage
- Excellent resistance to expansion
- Excellent resistance to warping
- Excellent resistance to distortion
- Excellent resistance to deformation
- Excellent resistance to damage
- Excellent resistance to wear
- Excellent resistance to abrasion
- Excellent resistance to erosion
- Excellent resistance to corrosion
- Excellent resistance to oxidation
- Excellent resistance to reduction
- Excellent resistance to neutralization
- Excellent resistance to acidification
- Excellent resistance to alkalization
- Excellent resistance to salinization
- Excellent resistance to sulfatization
- Excellent resistance to nitratization
- Excellent resistance to phosphatization
- Excellent resistance to silicification
- Excellent resistance to carbonatization
- Excellent resistance to bicarbonatization
- Excellent resistance to sulfidation
- Excellent resistance to selenidation
- Excellent resistance to telluridation
- Excellent resistance to iodidation
- Excellent resistance to bromidation
- Excellent resistance to fluoridation
- Excellent resistance to chloridation
- Excellent resistance to fluoridation
- Excellent resistance to chloridation
- Excellent resistance to bromidation
- Excellent resistance to iodidation
- Excellent resistance to selenidation
- Excellent resistance to telluridation
- Excellent resistance to nitratization
- Excellent resistance to phosphatization
- Excellent resistance to silicification
- Excellent resistance to carbonatization
- Excellent resistance to bicarbonatization
- Excellent resistance to sulfidation
- Excellent resistance to selenidation
- Excellent resistance to telluridation
- Excellent resistance to iodidation
- Excellent resistance to bromidation
- Excellent resistance to fluoridation
- Excellent resistance to chloridation

INSTALLATION PROTOCOL

1. Prepare the substrate by cleaning it with a suitable solvent. 2. Apply the adhesive to the substrate. 3. Press the substrate against the adhesive. 4. Cure the adhesive for the recommended time.



LAG BOLT PULL OUT CALCULATIONS

Spruce, Pine,	Per inch Thread Depth	266lbs
SS Lag Bolt 5/16" x 4"	Min. Thread Depth	0'-3"
Wood Strength x Thread Depth = Pull Out Strength		
266 lbs. x 3 in =		798 lbs.
Allowable Pull Out Strength per Lag Bolt		798 lbs.
Max. Pull Out Strength Required per Lag Bolt		213.01
Lag Bolt Pull Out Strength Safety Factor		3.75

K2 SYSTEM 44-X Landscape 60-Cell

Ground Snow Load	Exposure Category	Panel Angle	Wind Speed	120 mph						
				Roof Zone	1'	1	2e	2r	2n	3e
0 psf	C	20 to 27	Array Interior	88	88	88	74	74	74	72
			Array Edge	76	76	76	64	64	64	62

DISTRIBUTED LOAD CALCULATIONS

PV MODULES & RACKING WEIGHT = (INDIVIDUAL MODULE WEIGHT + 3.5 LBS) * (MODULE QTY) = (62 LBS) * (13) = 676 LBS

PER SQUARE FEET (PSF) ARRAY LOAD = PV MODULES & RACKING WEIGHT / TOTAL ARRAY AREA = 676 LBS / 274 SQFT = 2.46 PSF


HENCE, ROOF WILL CARRY THE ADDITIONAL SOLAR SYSTEM LOAD

- Lag Screw Installation Guidelines**
1. Determine location for the Mount on roof by drilling through the center of truss from bottom with 5/32" drill bit.
 2. Mark mounting holes for Mount on underlayment. Mounting holes should be centered on the trusses.
 3. Drill 15/64" pilot hole.
 4. Apply sealant to bottom of Mount.
 5. Place Mount over roof underlayment with holes in roof.
 6. Apply sealant to bottom of Mount, apply sealant to lag screws and fasten Mount securely to trusses.
 7. Apply additional sealant to top assembly to be sure all penetrations are sealed.


Lag pull-out (withdrawal) capacities (lbs) in typical roof lumber (ASD)

Specific gravity	STAINLESS STEEL Lag screw specifications	
	5/16" shaft, *	per inch thread depth
Douglas Fir, Larch	0.50	266
Douglas Fir, South	0.46	235
Engelman Spruce, Lodgepole Pine (MSR 1650 f & higher)	0.46	235
Hem, Fir, Redwood (close grain)	0.43	212
Hem, Fir (North)	0.46	235
Southern Pine	0.55	307
Spruce, Pine, Fir	0.42	205
Spruce, Pine, Fir (E of 2 million psi and higher grades of MSR and MEL)	0.50	266

Thread depth



1 SHINGLE ROOF MOUNT DETAIL & DATA
N.T.S.

DOCUMENT CONTROL	DATE 12-27-2021	CAD BW	QC JG	ENGINEER CONTACT INFORMATION	ENGINEERING STAMP	CONTRACTOR CONTACT INFORMATION	CONTRACTOR LOGO	CUSTOMER: SANDY FIROOZ	SHEET NAME: RACKING PLAN
ISSUED FOR PERMIT	DATE 12-27-2021	CAD BW	QC JG	ENGINEPARTNERS LLC C.A. 32661 255 GIRALDA AVE CORAL GABLES, FL 33134 DESIGN@ENGINEPARTNERS.COM 833 - 888 - 3644	Digitally signed by Rafael A Gonzalez Soto Date: 2022.01.17 05:15:23 -05'00'	TITAN SOLAR POWER FL 12221 N US HIGHWAY 301 THONOTASSA, FL 33592 (813) 982 - 9001 #EC13008093		PROJECT ADDRESS: 161 NORTHWEST SPARR LANE LAKE CITY FL 32055	PROJECT ID: TSP110728
REV	DESCRIPTION	DATE	CAD	QC				PARCEL NUMBER: 22-2S-16-01716-002	ENGINEER OF RECORD: ENG. RAFAEL A. GONZALEZ SOTO, PE DATE: 12-27-2021
									SHEET TITLE: S-2 SHEETS: 6 OF 9

Q.PEAK DUO BLK ML-G10+ 385-410

ENDURING HIGH PERFORMANCE



BREAKING THE 20% EFFICIENCY BARRIER

Q.ANTUM DUO Z Technology with zero gap cell layout boosts module efficiency up to 21.1%.



THE MOST THOROUGH TESTING PROGRAMME IN THE INDUSTRY

Q CELLS is the first solar module manufacturer to pass the most comprehensive quality programme in the industry. The new "Quality Controlled PV" of the independent certification institute TÜV Rheinland.



INNOVATIVE ALL-WEATHER TECHNOLOGY

Optimal yields, whatever the weather with excellent low-light and temperature behaviour.



ENDURING HIGH PERFORMANCE

Long-term yield security with Anti-LID Technology, Hot-Spot Protect and Traceable Quality Tra.Q™.



EXTREME WEATHER RATING

High-tech aluminium alloy frame, certified for high snow (5400 Pa) and wind loads (4000 Pa).




A RELIABLE INVESTMENT

Inclusive 25-year product warranty and 25-year linear performance warranty.

¹ See data sheet on rear for further information.


THE IDEAL SOLUTION FOR:



Engineered in Germany




MECHANICAL SPECIFICATION	
Format	1879mm x 1045mm x 32mm (including frame)
Weight	22.0 kg
Front Cover	3.2mm thermally pre-stressed glass with anti-reflection technology
Back Cover	Composite film
Frame	Black anodised aluminium
Cell	6 x 22 monocrystalline Q.ANTUM solar half cells
Junction box	53-101 mm x 32-60 mm x 15-18 mm Protection class IP67, with bypass diodes
Cable	4mm ² Solar cable; (+) ±1250mm, (-) ±1250mm
Connector	Stäubli MC4, IP68




ELECTRICAL CHARACTERISTICS		385	390	395	400	405	410	
MINIMUM PERFORMANCE AT STANDARD TEST CONDITIONS, STC ¹ (POWER TOLERANCE ±5W / -0.0W)								
Minimum	Power at MPP ¹	P_{MPP} [W]	385	390	395	400	405	410
	Short Circuit Current ¹	I_{SC} [A]	11.04	11.07	11.10	11.14	11.17	11.20
	Open Circuit Voltage ¹	V_{OC} [V]	45.19	45.23	45.27	45.30	45.34	45.37
	Current at MPP	I_{MPP} [A]	10.59	10.65	10.71	10.77	10.83	10.89
	Voltage at MPP	V_{MPP} [V]	36.36	36.62	36.88	37.13	37.39	37.64
	Efficiency ¹	η [%]	≥19.6	≥19.9	≥20.1	≥20.4	≥20.6	20.9
MINIMUM PERFORMANCE AT NORMAL OPERATING CONDITIONS, NMOT ²								
Minimum	Power at MPP	P_{MPP} [W]	288.8	292.6	296.3	300.1	303.8	307.6
	Short Circuit Current	I_{SC} [A]	8.90	8.92	8.95	8.97	9.00	9.03
	Open Circuit Voltage	V_{OC} [V]	42.62	42.65	42.69	42.72	42.76	42.79
	Current at MPP	I_{MPP} [A]	8.35	8.41	8.46	8.51	8.57	8.62
	Voltage at MPP	V_{MPP} [V]	34.59	34.81	35.03	35.25	35.48	35.68
	¹ Measurement tolerances P_{MPP} ±3%; I_{SC} , V_{OC} ±5% at STC: 1000 W/m ² , 25±2°C, AM 1.5 according to IEC 60904-3 • 2000 W/m ² , NMOT: spectrum AM 1.5							

Q CELLS PERFORMANCE WARRANTY PERFORMANCE AT LOW IRRADIANCE



At least 88% of nominal power during first year. Thereafter max. 0.5% degradation per year. At least 88.5% of nominal power up to 10 years. At least 86% of nominal power up to 25 years.

All data within measurement tolerances. Full warranties in accordance with the warranty terms of the Q CELLS sales organisation of your respective country.



Typical module performance under low irradiance conditions in comparison to STC conditions (25°C, 1000 W/m²).

TEMPERATURE COEFFICIENTS					
Temperature Coefficient of I_{SC}	α [%/K]	+0.04	Temperature Coefficient of V_{OC}	β [%/K]	-0.27
Temperature Coefficient of P_{MPP}	γ [%/K]	-0.34	Nominal Module Operating Temperature	NMOT [°C]	43±3

PROPERTIES FOR SYSTEM DESIGN				
Maximum System Voltage	V_{SYS} [V]	1000	PV module classification	Class II
Maximum Reverse Current	I_R [A]	20	Fire Rating based on ANSI / UL 61730	C / TYPE 2
Max. Design Load, Push / Pull	[Pa]	3600 / 2600	Permitted Module Temperature on Continuous Duty	-40°C - +85°C
Max. Test Load, Push / Pull	[Pa]	5400 / 4000		

QUALIFICATIONS AND CERTIFICATES Quality Controlled PV - TÜV Rheinland, IEC 61215:2016, IEC 61730:2016. This datasheet complies with DIN EN 50380. QCPV Certification ongoing. Certification holder: Hanwha Q CELLS GmbH.		PACKAGING INFORMATION Horizontal packaging: 1940mm x 1100mm x 1220mm, 75Lkg, 28 pallets, 24 pallets, 32 modules.
--	--	--

Note: Installation instructions must be followed. See the installation and operating manual or contact our technical service department for further information on approved installation and use of this product.

Made in Korea
Hanwha Q CELLS Australia Pty Ltd
 Suite 1, Level 1, 15 Blue Street, North Sydney, NSW 2060, Australia | TEL +61 (0)2 9016 3033 | FAX +61 (0)2 9016 3032 | EMAIL q-cells-australia@q-cells.com | WEB www.q-cells.com/au

Engineered in Germany



DOCUMENT CONTROL		DATE	CAD	QC
ISSUED FOR PERMIT		12-27-2021	BW	JG
REV	DESCRIPTION	DATE	CAD	QC

ENGINEER CONTACT INFORMATION	ENGINEERING STAMP	CONTRACTOR CONTACT INFORMATION
ENGIPARTNERS LLC C.A. 32661 255 GIRALDA AVE CORAL GABLES, FL 33134 DESIGN@ENGIPARTNERS.COM 833 - 888 - 3644	Digitally signed by Rafael A Gonzalez Soto Date: 2022.01.17 05:15:32 -05'00	TITAN SOLAR POWER FL 12221 N US HIGHWAY 301 THONOTASSA, FL 33592 (813) 982 - 9001 #EC13008093

CONTRACTOR LOGO

CUSTOMER:	
SANDY FIROOZ	
PROJECT ADDRESS:	161 NORTHWEST SPARR LANE LAKE CITY FL 32055
PARCEL NUMBER:	22-2S-16-01716-002

SHEET NAME:		
PV MODULES DATA SHEET		
PROJECT ID:	ENGINEER OF RECORD:	SHEET TITLE:
TSP110728	ENG. RAFAEL A. GONZALEZ SOTO, PE	D-1
DATE:		SHEETS:
12-27-2021		7 OF 9

Specifications subject to technical changes © Q CELLS Q.PEAK DUO BLK ML-G10+ 385-410 2021-06_Prev01_AU

Power Optimizer

For North America

P320 / P340 / P370 / P400 / P401 / P405 / P485 / **P505**



POWER OPTIMIZER

PV power optimization at the module-level

- Specifically designed to work with SolarEdge inverters
- Up to 25% more energy
- Superior efficiency (99.5%)
- Mitigates all types of module mismatch losses, from manufacturing tolerance to partial shading
- Flexible system design for maximum space utilization
- Fast installation with a single bolt
- Next generation maintenance with module-level monitoring
- Meets NEC requirements for arc fault protection (AFCI) and Photovoltaic Rapid Shutdown System (PVRSS)
- Module-level voltage shutdown for installer and firefighter safety

solaredge.com



Power Optimizer

For North America

P320 / P340 / P370 / P400 / P401 / P405 / P485 / **P505**

Optimizer model (typical module compatibility)	P320 (for 60-cell modules)	P340 (for high-power 60-cell modules)	P370 (for higher-power 60 and 72-cell modules)	P400 (for 72 & 96-cell modules)	P401 (for high power 60 and 72 cell modules)	P405 (for high-voltage modules)	P485 (for high voltage modules)	P505 (for higher current modules)		
INPUT										
Rated Input DC Power ⁽¹⁾	320	350	370	400	405	485	505	W		
Absolute Maximum Input Voltage (Voc at lowest temperature)	48	60	80	60	125 ⁽²⁾	83 ⁽³⁾		Vdc		
MPPT Operating Range	8 - 48	8 - 60	8 - 80	8 - 60	12.5 - 105	12.5 - 83		Vdc		
Maximum Short Circuit Current (Isc)	11	11.02	11	10.1	11.75	11	14	Aac		
Maximum DC Input Current		13.75		12.5	14.65	12.5	17.5	Aac		
Maximum Efficiency	99.5								%	
Weighted Efficiency	98.8								%	
Overvoltage Category	II									
OUTPUT DURING OPERATION (POWER OPTIMIZER CONNECTED TO OPERATING SOLAREEDGE INVERTER)										
Maximum Output Current	15								Aac	
Maximum Output Voltage	60								Vdc	
OUTPUT DURING STANDBY (POWER OPTIMIZER DISCONNECTED FROM SOLAREEDGE INVERTER OR SOLAREEDGE INVERTER OFF)										
Safety Output Voltage per Power Optimizer	1 = 0.1								Vdc	
STANDARD COMPLIANCE										
EMC	FCC Part 15 Class B, IEC61000-6-2, IEC61000-6-3									
Safety	IEC62109-1 (class II safety), UL1741									
Material	UL94 V-0, UV Resistant									
RoHS	Yes									
INSTALLATION SPECIFICATIONS										
Maximum Allowed System Voltage	1000								Vdc	
Compatible inverters	All SolarEdge Single Phase and Three Phase inverters									
Dimensions (W x L x H)	129 x 153 x 27.5 / 5.1 x 6 x 1.1	129 x 153 x 33.5 / 5.1 x 6 x 1.3	129 x 153 x 29.5 / 5.1 x 6 x 1.16	129 x 159 x 49.5 / 5.1 x 6.3 x 1.9	129 x 162 x 59 / 5.1 x 6.4 x 2.3			mm / in		
Weight (including cables)	630 / 1.4	750 / 1.7	655 / 1.5	845 / 1.9	1064 / 2.3			gr / lb		
Input Connector	MC4 ⁽⁴⁾									
Input Wire Length	0.16 / 0.52				0.16 or 0.9 / 0.52 or 2.95 ⁽⁵⁾		0.16 / 0.52		m / ft	
Output Wire Type / Connector	Double Insulated / MC4									
Output Wire Length	0.9 / 2.95				1.2 / 3.9					m / ft
Operating Temperature Range ⁽⁶⁾	-40 to +85 / -40 to +185								°C / °F	
Protection Rating	IP68 / NEMA6P									
Relative Humidity	0 - 100								%	

(1) Rated power of the module at STC will not exceed the optimizer "Rated Input DC Power". Modules with up to +5% power tolerance are allowed.
 (2) NEC 2017 requires max input voltage be not more than 80V.
 (3) For other connector types please contact SolarEdge.
 (4) For dual version for parallel connection of two modules use P485-4NMDMM. In the case of an odd number of PV modules in one string, installing one P485 dual version power optimizer connected to one PV module. When connecting a single module seal the unused input connectors with the supplied pair of seals.
 (5) Longer input wire lengths are available for use for 0.9m total wire length on the P401 and P405.
 (6) For ambient temperature above +85°C / +185°F power derating is applied. Refer to Power Optimizers Temperature Derating Technical Note for more details.

PV System Design Using a SolarEdge Inverter ⁽⁷⁾⁽⁸⁾	P320, P340, P370, P400, P401, P405, P485, P505	Single Phase HD-Wave	Single phase	Three Phase for 208V grid	Three Phase for 277/480V grid	W
Minimum String Length (Power Optimizers)		8		10	18	
Maximum String Length (Power Optimizers)		6	25	8	14	
Maximum Power per String		5700 (6000 with SE7600-US - SE11400-US)	5250	6000 ⁽⁹⁾	12750 ⁽¹⁰⁾	
Parallel Strings of Different Lengths or Orientations	Yes					

(7) For detailed string sizing information refer to: http://www.solaredge.com/sites/default/files/string_sizing_na.pdf
 (8) It is not allowed to mix P25/P25/P505 with P320/P340/P370/P400/P401 in one string.
 (9) A string with more than 30 optimizers does not meet NEC rapid shutdown requirements, safety voltage will be above the 30V requirement.
 (10) For 208V grid: it is allowed to install up to 6,500W per string when the maximum power difference between each string is 1,000W.
 (11) For 277/480V grid: it is allowed to install up to 15,000W per string when the maximum power difference between each string is 2,000W.

© SolarEdge Technologies Ltd. All rights reserved. SOLAREEDGE, the SolarEdge logo, OPTIMIZED BY SOLAREEDGE are trademarks or registered trademarks of SolarEdge Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: 08/2021 DS-00044-12-NA. Subject to change without notice.



DOCUMENT CONTROL		DATE	CAD	QC
ISSUED FOR PERMIT		12-27-2021	BW	JG
REV	DESCRIPTION	DATE	CAD	QC

ENGINEER CONTACT INFORMATION
ENGIPARTNERS LLC C.A. 32661 255 GIRALDA AVE CORAL GABLES, FL 33134 DESIGN@ENGIPARTNERS.COM 833 - 888 - 3644

ENGINEERING STAMP
Digitally signed by Rafael A Gonzalez Soto Date: 2022.01.17 05:15:41 -05'00'

CONTRACTOR CONTACT INFORMATION
TITAN SOLAR POWER FL 12221 N US HIGHWAY 301 THONOTASASSA, FL 33592 (813) 982 - 9001 #EC13008093



CUSTOMER:
SANDY FIROOZ
PROJECT ADDRESS:
161 NORTHWEST SPARR LANE LAKE CITY FL 32055
PARCEL NUMBER:
22-2S-16-01716-002

SHEET NAME:		
SMART MONITORING DATA SHEET		
PROJECT ID:	ENGINEER OF RECORD:	SHEET TITLE:
TSP110728	ENG. RAFAEL A. GONZALEZ SOTO, PE	D-2
DATE:	SHEETS:	
12-27-2021	8 OF 9	

