



BEARING HEIGHT SCHEDULE

	8'-0"
	10'-0"

NOTES:

- 1) REFER TO HD 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING) REFER TO ENGINEER DRAWINGS FOR PERMANENT BRACING REQUIRED
- 2) ALL TRUSSES, INCLUDING TRUSSES UNDER VALLEY FRAMING, MUST BE CONSIDERED ELEVATED OR REFER TO DETAIL VDS FOR ALTERNATE BRACING REQUIREMENTS
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER
- 4) ALL TRUSSES ARE DESIGNED FOR 2 OC MAXIMUM SPACING, UNLESS OTHERWISE NOTED
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED
- 6) S142 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP
- 7) ALL ROOF TRUSSES HANGERS TO BE SIMPSON HUSO TRUSSES, OTHERWISE NOTED ALL FLOOR TRUSSES HANGERS TO BE SIMPSON TH4422 UNLESS OTHERWISE NOTED
- 8) BEAMHANGER/INTEL (HORI) TO BE FURNISHED BY BUILDER

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND VDS. ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

Expenditure History Date _____

Approved by _____ Date _____



Builders FirstSource
Bunnell
PHONE 904-437-3349 FAX 904-437-3994
Lake City
PHONE 904-772-6100 FAX 904-772-1973
Sanford
PHONE 904-755-6894 FAX 904-755-7473
PHONE 407-322-0059 FAX 407-322-5553

BUILDER
HUGO ESCALANTE

DEVELOPER
LOT 6 FT. WHITE HEIGHTS

OWNER
NICOLAS

DATE 12/19/05 **SCALE** NTS **PROJECT** L143648