

SHEET LIST - CONSTRUCTION	
Sheet Number	Sheet Name
C-0	COVER SHEET
E-1	FRONT & REAR ELEVATIONS
E-2	LEFT & RIGHT ELEVATIONS
E-3	ROOF OVERVIEW
F-1	FOUNDATION PLAN
F-1.1	MONOSLAB FOUNDATION DETAILS
F-2	FIRST FLOOR PLAN
F-3	SECOND FLOOR PLAN
H-1	FIRST FLOOR ELECTRICAL & HVAC PLAN
H-2	SECOND FLOOR ELECTRICAL & HVAC PLAN
S-1	DETAILS & SECTIONS
S-1.1	DETAILS
S-1.2	STAIR DETAILS
S-2	MONOSLAB WALL SECTIONS
S-3	8" KDAT COLUMN DETAILS - FL
S-4	DETAILS
S-5	FL-COLUMN HOLD DOWN DETAILS
S-6	FL- HOLD DOWN DETAILS



GENERAL NOTES


- MIN 9'-1 1/8" CEILING HEIGHT ON FIRST FLOOR
- ALL WALL OPENINGS ON FIRST FLOOR ONLY TO HAVE MINIMUM (2) 2X10 HEADERS. SECOND FLOOR TO BE IN LOAD BEARING WALLS ONLY.STANDARD FIRST FLOOR WINDOW HEADERS SHALL BE FRAMED DOWN 2'-2" FROM T.O.P., U.N.O.
- WINDOW HEADERS FOR WINDOWS LOCATED ABOVE KITCHEN SINK SHALL BE FRAMED DOWN 1'-5" FROM T.O.P., U.N.O.
- STANDARD SECOND FLOOR WINDOW HEADERS SHALL BE FRAMED DOWN 1'-2" FROM T.O.P., U.N.O.
- 7/16" O.S.B. AND HOUSEWRAP REQUIRED
- DIMENSIONS ARE TO SHEATHING EXTERIOR; SUBTRACT 1/2" FROM DIMENSIONS FOR EXTERIOR WINDOW AND DOOR FRAMING LOCATION IF OPENINGS ARE FRAMED BEFORE SHEATHING INSTALLATION
- ALL INTERIOR DOORS ARE EITHER CENTERED ON WALLS OR R.O. STARTED MIN OF4" FROM ADJOINING WALL UNLESS OTHERWISE DIMENSIONED
- NUMBER OF STAIR TREADS & RISERS MAY VARY AS A RESULT OF LOCAL BUILDING CODES, STANDARDS AND FINAL GRADE
- ALL SHELING TO BE 12" DEEP U.N.O.
- HEIGHT OFF FLOOR:
SINGLE-68"
DOUBLE 42" & 84"
- ALL PLUMBING FIXTURES SHOWN ARE A REPRESENTATION OF SIZE AN LOCATION ONLY. ACTUAL STYLE AND BRAND OF FIXTURES MAY VARY PER OFFICE LOCATION
- ALL TUBS/SHOWERS ARE TO HAVE NAILERS AT FLANGE
- INSTALL A 24" WIDE WALKWAY FROM ATTIC ACCESS TO FURNACE PLATFORM
- PORCH, STOOP, & DECK HANDRAILS NOT INCLUDED W/ SLAB FOUNDATION
- RAILINGS ARE A FORCED OPTION WHEN PORCH IS OVER 30" HIGH FROM FINISHED GRADE

Revision Schedule	
Revision Number	Revision Description
1	FINALS

AREAS:	
FIRST FLOOR HEATED	1,317 SF
SECOND FLOOR HEATED	515 SF
FRONT PORCH	1,832 SF
REAR PORCH	162 SF
	20 SF
TOTAL UNDER ROOF	182 SF
	2,014 SF

THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
	SW DON COOK WAY FORT WHITE, FL
OFFICE:	GAINESVILLE, FL
SOLD BY:	RD


DRAWN BY:	J. GENCHUR
CHECKED BY:	B. TOOMBS
PRINT DATE:	7/19/2021 4:59:39 PM
JOB#	59-21-039
	2x4 EXTERIOR WALLS
FOUNDATION TYPE:	MONOSLAB
G:\Shared drives\AHP Drafting\AHP Jobs\Doug Higgins 140 43 53 59 63 66 73 98 120 121 125 145\59 Gainesville, FL\59 Townsend-Nottley MEU\Meu\59-21-039-001.dwg	

PROPERTY OF:

SHEET NUMBER: C-0

© COPYRIGHT - 2021

COVER SHEET




2 FRONT ELEVATION
1/8" = 1'-0"

ELEVATION NOTES

- MIN 9'-1 1/8" CEILING HEIGHT ON FIRST FLOOR
- 7/16" O.S.B AND HOUSEWRAP REQUIRED
- ROOF OVERHANGS, AS NOTED, ARE FROM WALL SHEATHING TO OUTSIDE OF FASCIA
- FINAL GRADE TO BE DETERMINED ON SITE
- FOUNDATION DRAWN AS REPRESENTATION ONLY

REFER TO SECTIONS FOR RAFTER FRAMING
SEAT CUTS AND O.W.H. DIMENSIONS

PORCH, STOOP & DECK HANDRAILS NOT INCLUDED
WITH SLAB FOUNDATION.
RAILING IS A FORCED OPTION WHEN PORCH IS
OVER 32" HIGH



1 REAR ELEVATION
1/8" = 1'-0"

OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS


Revision Schedule		Revision Number	Revision Description	Revision Date
1	FINALS			7/19/21

AREAS:		1st FLOOR HEATED	2nd FLOOR HEATED	FRONT PORCH	REAR PORCH	TOTAL UNDER ROOF
		1,317 SF	515 SF	1,832 SF	162 SF	2,014 SF


THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
SW DON COOK WAY FORT WHITE, FL	
OFFICE:	GAINESVILLE, FL
SOLD BY:	RD

JOB#	59-21-039
DRAWN BY:	J. GENCHUR
CHECKED BY:	B. TOOMBS
PRINT DATE:	7/19/2021 4:59:40 PM
FOUNDATION TYPE:	MONOSLAB

PROPERTY OF:	AMERICA'S HOME PLACE
SHEET NUMBER:	E-1
FRONT & REAR ELEVATIONS	



1 LEFT ELEVATION
1/8" = 1'-0"



2 RIGHT ELEVATION
1/8" = 1'-0"

THESE FINAL DESIGN PLANS ARE INTENDED TO SHOW LAYOUT AND STYLE ONLY. ACTUAL DIMENSIONS MAY VARY SLIGHTLY. GRADE SHOWN IS FOR DEMONSTRATIONAL PURPOSES ONLY AND DOES NOT NECESSARILY REFLECT FINAL GRADE. SIGNATURE INDICATES APPROVAL AND ACCEPTANCE OF THESE FINAL DESIGN PLANS.

ELEVATION NOTES

- MIN 9'-1 1/8" CEILING HEIGHT ON FIRST FLOOR
- 7/16" O.S.B AND HOUSEWRAP REQUIRED
- ROOF OVERHANGS, AS NOTED, ARE FROM WALL SHEATHING TO OUTSIDE OF FASCIA
- FINAL GRADE TO BE DETERMINED ON SITE

OWNER SIGNATURE
DRAWN AS REPRESENTATION
ONLY

REFER TO SECTIONS FOR RAFTER FRAMING
SEAL CUTS AND O.W.H. DIMENSIONS

OWNER SIGNATURE

CREATION DATE:

OWNER AND CONTRACTOR AGREE THAT THESE SIGNED FINAL DESIGN PLANS SHALL SUPERSEDE ANY PREVIOUSLY SIGNED FINAL DESIGN PLANS.

PORCH, STOOP & DECK HANDRAILS NOT INCLUDED
WITH SLAB FOUNDATION.
RAILING IS A FORCED OPTION WHEN PORCH IS
OVER 32" HIGH

Revision Schedule		Revision Schedule	
Revision Number	Revision Description	Revision Number	Revision Description


AREAS:		AREAS:	
FIRST FLOOR HEATED	1,317 SF	FRONT PORCH	162 SF
SECOND FLOOR HEATED	515 SF	REAR PORCH	20 SF
		TOTAL UNDER ROOF	2,014 SF

THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
SW DON COOK WAY FORT WHITE, FL	
OFFICE:	GAINESVILLE, FL
SOLD BY:	RD

JOB#	59-21-039
FOUNDATION TYPE:	MONOSLAB
DRAWN BY:	J. GENCHUR
CHECKED BY:	B. TOOMBS
PRINT DATE:	7/19/2021 4:59:40 PM

PROPERTY OF:	AMERICA'S HOME PLACE
SHEET NUMBER:	E-2
LEFT & RIGHT ELEVATIONS	

REFER TO SECTIONS FOR RAFTER FRAMING
SEAT CUTS AND O.W.H. DIMENSIONS



1 ROOF OVERVIEW
1/8" = 1'-0"

OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%


FINAL CONSTRUCTION PLANS

Revision Schedule		
Revision Number	Revision Description	Revision Date

AREAS:		1,317 SF
FIRST FLOOR HEATED		515 SF
SECOND FLOOR HEATED		1,832 SF
FRONT PORCH		162 SF
REAR PORCH		20 SF
TOTAL UNDER ROOF		182 SF
		2,014 SF


THE:	NOTTELY MODERN FARMHOUSE	
FOR:	SUZANNE TOWNSEND	
	SW DON COOK WAY FORT WHITE, FL	
OFFICE:	GAINESVILLE, FL	SOLD BY: RD

DRAWN BY:	J. GENCHUR	JOB#	59-21-039
CHECKED BY:	B. TOOMBS	2x4 EXTERIOR WALLS	
PRINT DATE:	7/19/2021 4:59:40 PM	FOUNDATION TYPE: MONOSLAB	

PROPERTY OF:

© COPYRIGHT - 2021

SHEET NUMBER:
E-3

ROOF OVERVIEW



NOTE:
TURN OUT REBAR AT THE POWER
METER FOR ELECTRICAL GROUNDING
AS REQUIRED BY CODE

1 FOUNDATION PLAN
1/8" = 1'-0"

OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%


FINAL CONSTRUCTION PLANS

Revision Schedule		
Revision Number	Revision Description	Revision Date

AREAS:		1,317 SF
FIRST FLOOR HEATED	SECOND FLOOR HEATED	515 SF
FRONT PORCH	REAR PORCH	1,832 SF
TOTAL UNDER ROOF		2,014 SF

THE:	NOTTELY MODERN FARMHOUSE	
FOR:	SUZANNE TOWNSEND	
	SW DON COOK WAY FORT WHITE, FL	
OFFICE:	GAINESVILLE, FL	SOLD BY: RD


DRAWN BY:	J. GENCHUR	JOB#	59-21-039
CHECKED BY:	B. TOOMBS	2x4 EXTERIOR WALLS	FOUNDATION TYPE: MONOSLAB
PRINT DATE:	7/19/2021 4:59:40 PM	G:\Shared drives\AHP Drafting\AHP Jobs\Doug Higgins 40 43 53 59 63 66 73 98 120 121 125 145\59-Gainesville, FL\59-Townsend-Nattley MEHL Monoslab\59-Townsend-Nattley MEHL 070221.dwg	

PROPERTY OF: 


SHEET NUMBER: **F-1**

© COPYRIGHT - 2021


FOUNDATION PLAN



1 1 STORY MONOSLAB DETAIL
3/4" = 1'-0"




3 2 STORY MONOSLAB DETAIL
3/4" = 1'-0"



6 EDGE OF TURNED DOWN PATIO SLAB
3/4" = 1'-0"

- (1) ROW 2X BLOCKING AT MID HGT, FOR WALL LESS THAN 8'-6".
(2) ROWS OF BLOCKING AT 1/3 POINTS FOR WALL HGT ABOVE 8'-6"



5 BEARING WALL AT STEP
3/4" = 1'-0"

Revision Number	Revision Description	Revision Date

AREAS:	FIRST FLOOR HEATED	SECOND FLOOR HEATED	FRONT PORCH	REAR PORCH	TOTAL UNDER ROOF
	1,317 SF	515 SF	1,832 SF	162 SF	2,014 SF

THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
OFFICE:	SW DON COOK WAY FORT WHITE, FL GAINESVILLE, FL
SOLD BY:	RD


JOB#	59-21-039
FOUNDATION TYPE:	MONOSLAB
DRAWN BY:	J. GENCHUR
CHECKED BY:	B. TOOMBS
PRINT DATE:	7/19/2021 4:59:41 PM

PROPERTY OF:	AMERICA'S HOME PLACE
SHEET NUMBER:	F-1.1
MONOSLAB FOUNDATION DETAILS	

MONOSLAB FOUNDATION DETAILS FOR AREAS 43, 59, 66, 73

OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS



1 FIRST FLOOR PLAN
1/8" = 1'-0"

GENERAL NOTES

- MIN 9'-1 1/8" CEILING HEIGHT ON FIRST FLOOR
- ALL WALL OPENINGS ON FIRST FLOOR ONLY TO HAVE MINIMUM (2) 2X10 HEADERS. SECOND FLOOR TO BE IN LOAD BEARING WALLS ONLY. STANDARD FIRST FLOOR WINDOW HEADERS SHALL BE FRAMED DOWN 2'-2" FROM T.O.P., U.N.O.
- WINDOW HEADERS FOR WINDOWS LOCATED ABOVE KITCHEN SINK SHALL BE FRAMED DOWN 1'-5" FROM T.O.P., U.N.O.
- STANDARD SECOND FLOOR WINDOW HEADERS SHALL BE FRAMED DOWN 1'-2" FROM T.O.P., U.N.O.
- 7/16" O.S.B. AND HOUSEWRAP REQUIRED
- DIMENSIONS ARE TO SHEATHING EXTERIOR; SUBTRACT 1/2" FROM DIMENSIONS FOR EXTERIOR WINDOW AND DOOR FRAMING LOCATION IF OPENINGS ARE FRAMED BEFORE SHEATHING INSTALLATION
- ALL INTERIOR DOORS ARE EITHER CENTERED ON WALLS OR R.O. STARTED MIN OF 4" FROM ADJOINING WALL UNLESS OTHERWISE DIMENSIONED
- NUMBER OF STAIR TREADS & RISERS MAY VARY AS A RESULT OF LOCAL BUILDING CODES, STANDARDS AND FINAL GRADE
- ALL SHELING TO BE 12" DEEP U.N.O.
- HEIGHT OFF FLOOR:
SINGLE-68"
DOUBLE 42" & 84"
- ALL PLUMBING FIXTURES SHOWN ARE A REPRESENTATION OF SIZE AN LOCATION ONLY. ACTUAL STYLE AND BRAND OF FIXTURES MAY VARY PER OFFICE LOCATION
- ALL TUBS/SHOWERS ARE TO HAVE NAILERS AT FLANGE
- INSTALL A 24" WIDE WALKWAY FROM ATTIC ACCESS TO FURNACE PLATFORM
- PORCH, STOOP, & DECK HANDRAILS NOT INCLUDED W/ SLAB FOUNDATION
- RAILINGS ARE A FORCED OPTION WHEN PORCH IS OVER 30" HIGH FROM FINISHED GRADE


Revision Schedule		
Revision Number	Revision Description	Revision Date
1	FINALS	7/19/21

AREAS:	
FIRST FLOOR HEATED	1,317 SF
SECOND FLOOR HEATED	515 SF
FRONT PORCH	1,832 SF
REAR PORCH	162 SF
TOTAL UNDER ROOF	2,014 SF

THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
OFFICE:	SW DON COOK WAY FORT WHITE, FL
SOLD BY:	RD

DRAWN BY:	J. GENCHUR
CHECKED BY:	B. TOOMBS
PRINT DATE:	7/19/2021 4:59:41 PM
FOUNDATION TYPE:	MONOSLAB

PROPERTY OF:	AMERICA'S HOME PLACE
SHEET NUMBER:	F-2
FIRST FLOOR PLAN	



1 SECOND FLOOR PLAN
1/8" = 1'-0"

GENERAL NOTES


- MIN 9'-1 1/8" CEILING HEIGHT ON FIRST FLOOR
- ALL WALL OPENINGS ON FIRST FLOOR ONLY TO HAVE MINIMUM (2) 2X10 HEADERS. SECOND FLOOR TO BE IN LOAD BEARING WALLS ONLY. STANDARD FIRST FLOOR WINDOW HEADERS SHALL BE FRAMED DOWN 2'-2" FROM T.O.P., U.N.O.
- WINDOW HEADERS FOR WINDOWS LOCATED ABOVE KITCHEN SINK SHALL BE FRAMED DOWN 1'-5" FROM T.O.P., U.N.O.
- STANDARD SECOND FLOOR WINDOW HEADERS SHALL BE FRAMED DOWN 1'-2" FROM T.O.P., U.N.O.
- 7/16" O.S.B. AND HOUSEWRAP REQUIRED
- DIMENSIONS ARE TO SHEATHING EXTERIOR; SUBTRACT 1/2" FROM DIMENSIONS FOR EXTERIOR WINDOW AND DOOR FRAMING LOCATION IF OPENINGS ARE FRAMED BEFORE SHEATHING INSTALLATION
- ALL INTERIOR DOORS ARE EITHER CENTERED ON WALLS OR R.O. STARTED MIN OF 4" FROM ADJOINING WALL UNLESS OTHERWISE DIMENSIONED
- NUMBER OF STAIR TREADS & RISERS MAY VARY AS A RESULT OF LOCAL BUILDING CODES, STANDARDS AND FINAL GRADE
- ALL SHELVING TO BE 12" DEEP U.N.O.
- HEIGHT OFF FLOOR:
 - SINGLE-68"
 - DOUBLE 42" & 84"
- ALL PLUMBING FIXTURES SHOWN ARE A REPRESENTATION OF SIZE AN LOCATION ONLY. ACTUAL STYLE AND BRAND OF FIXTURES MAY VARY PER OFFICE LOCATION
- ALL TUBS/SHOWERS ARE TO HAVE NAILERS AT FLANGE
- INSTALL A 24" WIDE WALKWAY FROM ATTIC ACCESS TO FURNACE PLATFORM
- PORCH, STOOP, & DECK HANDRAILS NOT INCLUDED W/ SLAB FOUNDATION
- RAILINGS ARE A FORCED OPTION WHEN PORCH IS OVER 30" HIGH FROM FINISHED GRADE

Revision Schedule		
Revision Number	Revision Description	Revision Date
1	FINALS	7/19/21


AREAS:	
FIRST FLOOR HEATED	1,317 SF
SECOND FLOOR HEATED	515 SF
FRONT PORCH	1,832 SF
REAR PORCH	162 SF
	20 SF
TOTAL UNDER ROOF	182 SF
	2,014 SF

THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
	SW DON COOK WAY FORT WHITE, FL
OFFICE:	GAINESVILLE, FL
SOLD BY:	RD

DRAWN BY:	J. GENCHUR	JOB#	59-21-039
CHECKED BY:	B. TOOMBS		2x4 EXTERIOR WALLS
PRINT DATE:	7/19/2021 4:59:41 PM	FOUNDATION TYPE:	MONOSLAB

PROPERTY OF:	
SHEET NUMBER:	F-3
© COPYRIGHT - 2021	

SECOND FLOOR PLAN



1 FIRST FLOOR ELECTRICAL & HVAC PLAN
1/8" = 1'-0"

ELECTRICAL NOTES:

- BRANCH CIRCUITS THAT SUPPLY 125V, SINGLE PHASE, 15 & 20 AMP RECEPTACLE OUTLETS IN BEDROOMS SHALL BE PROTECTED BY ARC-FAULT CIRCUIT INTERRUPTER. ART. 210-12(b) 1999 NEC
- CONFORM ELECTRICAL WIRING & COMPONENTS TO CURRENT NEC PROVISIONS OF 1 & 2 FAMILY DWELLINGS AS REQUIRED BY CODE
- OUTLET LOCATIONS ARE REPRESENTATION ONLY
- ACTUAL OUTLET LOCATIONS MAY VARY PER LOCAL CODE

HVAC NOTES:

- FURNACE NOT LOCATED IN HEATED AREA TO BE AS CENTRALLY LOCATED AS POSSIBLE. IN ACCORDANCE WITH ALL APPLICABLE CODES
- BUILDER & HVAC CONTRACTOR RESERVE THE RIGHT TO LOCATE SUPPLY VENTS OR LINES
- RETURN AIR REGISTERS TO BE AS CLOSE TO FURNACE UNIT & CENTRALLY LOCATED AS POSSIBLE
- OUTSIDE COMPRESSOR UNIT TO BE LOCATED AS CLOSE TO INTERIOR AIR HANDLER AS POSSIBLE
- OUTSIDE COMPRESSOR UNIT TO BE LOCATED 10' AWAY MIN. FROM DRYER VENT

ELECTRICAL LEGEND	
LIGHTING FIXTURES	
Ceiling Fan	
Ceiling Fan w/ Light	
Ceiling Mounted Light	
Recessed Ceiling Light	
Pendent Ceiling Light	
Fluorescent Ceiling Light	
Ceiling Exhaust Fan/Light Combo	
Ceiling Exhaust Fan/Light Combo	
Emergency Exit Light	
Junction Box for Future Fixture	
Fluorescent Wall Mounted Light	
Wall Mounted Vanity 3 Light	
Wall Mounted Vanity 4 Light	
Wall Mounted Interior Sconce Light	
Wall Mounted Exterior Coach Light	
Exterior Flood Light	
ELECTRICAL FIXTURES	
Duplex Outlet	
Duplex Outlet - GFI	
Duplex Outlet - Water Proof GFI	
Duplex Outlet - 220v	
Duplex Outlet - Ceiling Mounted	
Duplex Outlet - Floor Mounted	
4-plex Outlet	
4-plex Outlet - Floor Mounted	
Outlet, Light and Switch (Attic/Crawl)	
2-Way Switch	
3-Way Switch	
4-Way Switch	
Dimmer Switch	
Rocker Switch	
Smoke Detector	
Smoke Detector/Carbon Monoxide	
Thermostat	
Door Bell	
Door Bell Chime	
Telephone Jack	
Television / Cable Jack	
Telephone / Data Jack	

Revision Schedule		Revision Number	Revision Description	Revision Date
1	FINALS			7/19/21

AREAS:		FIRST FLOOR HEATED	SECOND FLOOR HEATED	FRONT PORCH	REAR PORCH	TOTAL UNDER ROOF
		1,317 SF	515 SF	1,832 SF	162 SF	2,014 SF

THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
OFFICE:	SW DON COOK WAY FORT WHITE, FL GAINESVILLE, FL
SOLD BY:	RD

JOB#	59-21-039
DRAWN BY:	J. GENCHUR
CHECKED BY:	B. TOOMBS
PRINT DATE:	7/19/2021 4:59:42 PM
FOUNDATION TYPE:	MONOSLAB

PROPERTY OF:


SHEET NUMBER: **H-1**

© COPYRIGHT - 2021

FIRST FLOOR ELECTRICAL & HVAC PLAN

OPT. PAPER SIZE: for 1/4" =1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS



1 SECOND FLOOR ELECTRICAL & HVAC PLAN
1/8" = 1'-0"

ELECTRICAL NOTES:

- BRANCH CIRCUITS THAT SUPPLY 125V, SINGLE PHASE, 15 & 20 AMP RECEPTACLE OUTLETS IN BEDROOMS SHALL BE PROTECTED BY ARC-FAULT CIRCUIT INTERRUPTER. ART. 210-12(b) 1999 NEC
- CONFORM ELECTRICAL WIRING & COMPONENTS TO CURRENT NEC PROVISIONS OF 1 & 2 FAMILY DWELLINGS AS REQUIRED BY CODE
- OUTLET LOCATIONS ARE REPRESENTATION ONLY
- ACTUAL OUTLET LOCATIONS MAY VARY PER LOCAL CODE

HVAC NOTES:

- FURNACE NOT LOCATED IN HEATED AREA TO BE AS CENTRALLY LOCATED AS POSSIBLE. IN ACCORDANCE WITH ALL APPLICABLE CODES
- BUILDER & HVAC CONTRACTOR RESERVE THE RIGHT TO LOCATE SUPPLY VENTS OR LINES
- RETURN AIR REGISTERS TO BE AS CLOSE TO FURNACE UNIT & CENTRALLY LOCATED AS POSSIBLE
- OUTSIDE COMPRESSOR UNIT TO BE LOCATED AS CLOSE TO INTERIOR AIR HANDLER AS POSSIBLE
- OUTSIDE COMPRESSOR UNIT TO BE LOCATED 10' AWAY MIN. FROM DRYER VENT

ELECTRICAL LEGEND	
LIGHTING FIXTURES	
Ceiling Fan	
Ceiling Fan w/ Light	
Ceiling Mounted Light	
Recessed Ceiling Light	
Pendent Ceiling Light	
Fluorescent Ceiling Light	
Ceiling Exhaust Fan/Light Combo	
Ceiling Exhaust Fan/Light Combo	
Emergency Exit Light	
Junction Box for Future Fixture	
Fluorescent Wall Mounted Light	
Wall Mounted Vanity 3 Light	
Wall Mounted Vanity 4 Light	
Wall Mounted Interior Sconce Light	
Wall Mounted Exterior Coach Light	
Exterior Flood Light	
ELECTRICAL FIXTURES	
Duplex Outlet	
Duplex Outlet - GFI	
Duplex Outlet - Water Proof GFI	
Duplex Outlet - 220v	
Duplex Outlet - Ceiling Mounted	
Duplex Outlet - Floor Mounted	
4-plex Outlet	
4-plex Outlet - Floor Mounted	
Outlet, Light and Switch (Attic/Crawl)	
2-Way Switch	
3-Way Switch	
4-Way Switch	
Dimmer Switch	
Rocker Switch	
Smoke Detector	
Smoke Detector/Carbon Monoxide	
Thermostat	
Door Bell	
Door Bell Chime	
Telephone Jack	
Television / Cable Jack	
Telephone / Data Jack	

Revision Schedule

Revision Number	Revision Description	Revision Date
1	FINALS	7/19/21

AREAS:

FIRST FLOOR HEATED	SECOND FLOOR HEATED	FRONT PORCH	REAR PORCH	TOTAL UNDER ROOF
1,317 SF	515 SF	1,832 SF	162 SF	2,014 SF

THE: NOTTELY MODERN FARMHOUSE

FOR: SUZANNE TOWNSEND

SW DON COOK WAY FORT WHITE, FL

OFFICE: GAINESVILLE, FL

SOLD BY: RD

JOB# 59-21-039

2x4 EXTERIOR WALLS

FOUNDATION TYPE: MONOSLAB

DRAWN BY: J. GENCHUR



CHECKED BY: B. TOOMBS

PRINT DATE: 7/19/2021 4:59:42 PM

PROPERTY OF: AMERICA'S HOME PLACE

© COPYRIGHT - 2021

SECOND FLOOR ELECTRICAL HVAC PLAN



OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS

Revision Schedule		
Revision Number	Revision Description	Revision Date
1	FINALS	7/19/21

AREAS:	
FIRST FLOOR HEATED	1,317 SF
SECONDD FLOOR HEATED	515 SF
	1,832 SF
FRONT PORCH	162 SF
REAR PORCH	20 SF
	182 SF
TOTAL UNDER ROOF	2,014 SF

THE: **NOTTELY MODERN
FARMHOUSE**

SUZANNE TOWNSEND

SW DON COOK WAY
FORT WHITE, FL

OFFICE: GAINESVILLE, FL	SOLD BY: RD
----------------------------	----------------

SOLD BY:
RD

DRAWN BY: J. GENCHUR

JOB# 59-21-039

2x4 EXTERIOR WALLS

FOUNDATION TYPE:

MONOSLAB

G: Shared drives \AHP Drafting \AHP Jobs \Doug Higgins
 40 43 53 59 63 66 73 98 120 121 125
 45) \59-Gainesville, FL \59-Townsend-Nottley
 MEH: Monoslab \59-Townsend-Nottley MEH-070221.rvt

PROPERTY OF:



©COPYRIGHT - 2021

DETAILS & SECTIONS




SHEET NUMBER:

15

PAPER SIZE: 11" x 17"

SCALE: 1/4" = 1'-0"


TO REPORT COPYRIGHT VIOLATIONS CALL (770)532-1128 THE USE OF THIS PLAN BY ANYONE OTHER THAN AN AGENT OF "AMERICA'S HOME PLACE, INC." IS IN VIOLATION OF THE FEDERAL COPYRIGHT VIOLATION ACT. \$1000 REWARD FOR RECOVERING AN ACTUAL COPYRIGHT INFRINGEMENT.
© COPYRIGHT-ALL RIGHTS RESERVED NOTE:VIOLATORS OF THE COPYRIGHT WILL BE PROSECUTED TO THE FULLEST EXTENT OF THE LAW. THIS WORK IS THE INTELLECTUAL PROPERTY OF AMERICA'S HOME PLACE AND SHALL NOT BE REPRODUCED WITHOUT PERMISSION.



PROPERTY OF:

SHEET NUMBER:

S-1.1



© COPYRIGHT - 2020


AILS

FINAL CONSTRUCTION PLANS


SCALE: As indicated

DETAILS


3 900.5 STAIR SECTION THRU STRINGER
3/4" = 1'-0"




2 900.4 STAIR TRIM @ SLOPED WALL
1/2" = 1'-0"



4 900.7 STAIR SPINDLE DETAIL
1" = 1'-0"



1 900.3 STAIR SLOPED WALL AT RAILING
1/2" = 1'-0"



OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS

SHEET NUMBER:

S-1.2

PROPERTY OF:



© COPYRIGHT - 2021

DRAWN BY:

J. GENCHUR

JOB#

59-21-039

THE:

NOTTELY MODERN FARMHOUSE

FOR:

SUZANNE TOWNSEND

AREAS:

FIRST FLOOR HEATED

1,317 SF

SECOND FLOOR HEATED

515 SF

FRONT PORCH

1,832 SF

REAR PORCH

162 SF

TOTAL UNDER ROOF

2,014 SF

Revision Schedule

Revision Number


Revision Description

Revision Date

1

FINALS


7/19/21



ROOF SYSTEM
 ROOF COVERING AS SPECIFIED DOUBLE LAYER OF SYNTHETIC UNDERLAYMENT WITH 7/16" OSB SHEATHING NAILED AND CLIPPED PRE ENGINEERED ROOF TRUSSES PER PRINT R-33 INSULATION IN FLAT AREAS R-30 INSULATION IN SLOPED AREAS

UNDERLAYMENT MATERIALS
 UNDERLAYMENT MATERIALS TO COMPLY WITH ASTM D226, D4869 TYPE III OR TYPE IV SHALL BEAR A LABEL INDICATING COMPLIANCE TO THE STANDARD DESIGNATION.

UNDERLAYMENT APPLICATION
 UNDERLAYMENT SHALL BE APPLIED SHINGLE FASHION, PARALLEL TO AND STARTING FROM THE EAVE AND LAPPED 2 INCHES. DISTORTIONS IN THE UNDERLAYMENT SHALL NOT INTERFERE WITH THE ABILITY OF THE SHINGLES TO SEAL. END LAPS SHALL BE 4 INCHES AND SHALL BE OFFSET BY 6 FEET.



NOTE:
 1/2" X 10" ANCHOR BOLTS W/WASHERS, WITHIN 6" OF ALL CORNERS, PLATE ENDS AND EACH SIDE OF AN OPENING. THEN SPACED A MINIMUM OF 4'-0" O.C. OR AS REQUIRED.

1 STORY WALL SECTION ON SLAB - FL
 1/2" = 1'-0"

MONOSLAB WALL DETAILS FOR AREAS 43, 53, 59, 66, & 73

OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%
FINAL CONSTRUCTION PLANS


Revision Schedule		Revision Number	Revision Description	Revision Date
1	FINALS			7/19/21

AREAS:		FIRST FLOOR HEATED	SECOND FLOOR HEATED	FRONT PORCH	REAR PORCH	TOTAL UNDER ROOF
		1,317 SF	515 SF	1,832 SF	162 SF	2,014 SF


THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
OFFICE:	SW DON COOK WAY FORT WHITE, FL
SOLD BY:	RD

JOB#	59-21-039
DRAWN BY:	J. GENCHUR
CHECKED BY:	B. TOOMBS
PRINT DATE:	7/19/2021 4:59:43 PM
FOUNDATION TYPE:	MONOSLAB


PROPERTY OF:	AMERICA'S HOME PLACE
SHEET NUMBER:	S-2
MONOSLAB WALL SECTIONS	



1 PORCH 8" KDAT COLUMN FRAMING ON SLAB
1" = 1'-0"



2 8" KDAT Column - FL
1/2" = 1'-0"



3 8" KADT Column Eve Detail - FL
1" = 1'-0"

OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS

Revision Schedule		Revision Number	Revision Description	Revision Date
1	FINALS			7/19/21

AREAS:		FIRST FLOOR HEATED	1,317 SF
		SECOND FLOOR HEATED	515 SF
		FRONT PORCH	1,832 SF
		REAR PORCH	162 SF
		TOTAL UNDER ROOF	2,014 SF


THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
OFFICE:	SW DON COOK WAY FORT WHITE, FL
SOLD BY:	RD

DRAWN BY:	J. GENCHUR	JOB#	59-21-039
CHECKED BY:	B. TOOMBS	2x4 EXTERIOR WALLS	
PRINT DATE:	7/19/2021 4:59:43 PM	FOUNDATION TYPE:	MONOSLAB




SHEET NUMBER:	S-3
---------------	-----

8" KDAT COLUMN DETAILS - FL




1 KITCHEN CABINET WALL BLOCKING
1/2" = 1'-0"





TYPICAL FRAMING DETAILS

2 43.2 CORNER T FRAMING DETAIL
1" = 1'-0"



3 WINDOW INSTALLATION (TYPICAL)
3/16" = 1'-0"



4 470.1 Attic Wall Access Details
1/2" = 1'-0"

OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS

Revision Schedule		Revision Number		Revision Description	Revision Date
1	FINALS				7/19/21

AREAS:		FIRST FLOOR HEATED	SECOND FLOOR HEATED	FRONT PORCH	REAR PORCH	TOTAL UNDER ROOF
		1,317 SF	515 SF	1,832 SF	162 SF	2,014 SF


THE:	NOTTELY MODERN FARMHOUSE	FOR:	SUZANNE TOWNSEND
			SW DON COOK WAY FORT WHITE, FL
		OFFICE:	GANESVILLE, FL
		SOLD BY:	RD

JOB#	59-21-039	FOUNDATION TYPE:	MONOSLAB
DRAWN BY:	J. GENCHUR	CHECKED BY:	B. TOOMBS
PRINT DATE:	7/19/2021		4:59:43 PM


PROPERTY OF:	AMERICA'S HOME PLACE	© COPYRIGHT - 2018
SHEET NUMBER:	S-4	

PAPER SIZE:	11" x 17"	SCALE:	As indicated
-------------	-----------	--------	--------------


DETAILS



1 COLUMN DETAIL



COLUMN DETAIL BLOWUP



2 COLUMN DETAIL 2


OPT. PAPER SIZE: for 1/4" = 1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS

Revision Schedule		Revision		Revision	
Revision Number	Revision Description	Revision Number	Revision Description	Revision Number	Revision Date
1	FINALS				7/19/21


AREAS:		TOTAL UNDER ROOF	
FIRST FLOOR HEATED	1,317 SF		
SECOND FLOOR HEATED	515 SF		
FRONT PORCH	1,832 SF		
REAR PORCH	162 SF		
	20 SF		
	182 SF		
	2,014 SF		

THE: NOTTELY MODERN FARMHOUSE	FOR: SUZANNE TOWNSEND	SW DON COOK WAY FORT WHITE, FL
JOB#: 59-21-039	2x4 EXTERIOR WALLS	FOUNDATION TYPE: MONOSLAB
DRAWN BY: J. GENCHUR	CHECKED BY: B. TOOMBS	PRINT DATE: 7/19/2021 4:59:43 PM
PROPERTY OF: AMERICA'S HOME PLACE	© COPYRIGHT - 2021	FL-COLUMN HOLD DOWN DETAILS




Simpson Strong-Tie
H2.5

RAFTER WITH NO STUD BELOW
WHEN H2 ARE NOT USED PROVIDE
SIMPSON CS16 @ 48" O.C. STRAP OVER
TOP PLATE AND MIN. 10" LAP ON STUDS U.N.O.




Simpson Strong-Tie
H2

RAFTER ABOVE STUD
WHEN H2 ARE USED EVERY OTHER JOIST
SIMPSON CS16 STRAP OVER TOP PLATE
& MIN. 10" LAP ON STUDS ARE NOT REQUIRED U.N.O.




20" SIMPSON CS 16 TIE STRAP CONNECTS STUDS TO
FLOOR SYSTEM @ 48" O.C., 10d NAILS ALL HOLES
AND WOOD COLUMNS TO PORCH HEADERS
AND WOOD COLUMNS TO FLOOR RIM JOIST U.N.O.



AS REQ'D. BY 2018 IRC, FIGURE
R502.2 & SECTION R502.7

OPTIONAL RAFTER OR STUD/POST
TO DBL PLATE/HEADER CONNECTION:
6" FASTENMASTER TIMBERLOK
INSTALLED AT 22.5 DEGREE
MIN. 2.5" FROM CONNECTION
WWW.FASTENMASTER.COM



OPTIONAL SLAB/BOTTOM PLATE/WALL CONNECTIONS
SIMPSON H2.5, H3, OR SSP OR DSP BOTTOM PLATE TO STUDS

FULL DEPTH BLOCKING @ 4'-0"
O.C. FIRST (4) SPACES FROM
END. NOTCH FIRST BLOCK
AROUND NAILER

1/2" GYPSUM DRYWALL
(SEE GENERAL NOTES)

2x4 CONTINUOUS NAILER

1-1/4" TYPE S OR W #6 DRYWALL
SCREWS @ 7" (TYP. THROUGHOUT)

8d COMMON NAILS @ 4" O.C.

ENDWALL CEILING CONNECTION

USP RS200 ON EACH RAFTER PAIR, 12" MIN.
END LENGTH ON EACH RAFTER, (11)
8d FASTENERS REQ'D EACH END.

ALT: 1x6 COLLAR TIE EVERY OTHER RAFTER,
MIN. (9) 8d NAILS EACH END.

NOTE: DETAIL ABOVE NOT REQUIRED
FOR CONTINUOUS TRUSSES.

USP RT16 STRAP AT
ALL BEARING POINTS

TOP PLATE/GIRDER/BREAM

RT16 MUST BE INSTALLED ON OUTSIDE OF
STUD WALL. IF INSTALLED ON INSIDE OF
WALL, STUDS ON EITHER SIDE OF RT16
MUST BE ANCHORED TO TOP PLATE USING
RT7 STRAPS.

INTERIOR LOAD BEARING WALLS--
STRAP TRUSS/RAFTERS TO TOP PLATES
WITH USP RT16. ANCHOR TOP PLATES TO
STUDS WITH USP SPT24 STRAPS ON SAME
SIDE AS RT16 STRAPS. CONNECT 2ND
FLOOR WALL STUDS TO 1ST FLOOR WALL
STUDS OR BEAMS USING USP RS200
STRAPS @ 48" O.C. (MIN. 11 8d NAILS EACH
END). ATTACH 1ST FLOOR STUDS TO
SUPPORTING GIRDERS IN SIMILAR MANNER.
ANCHOR FLOOR JOISTS TO DROPPED
GIRDERS WITH USP RT 17. SEE DETAIL I
FOR DROPPED GIRDER ANCHORING.

OPTIONAL TIEDOWN IS THE QUICK TIE SYSTEM
WWW.QUICKTIEPRODUCTS.COM
CONTRACTOR SHALL SUBMIT TIEDOWN PLAN
FOR ENGINEER'S APPROVAL

RAFTER/TRUSS


STRAP OVERBUILT VALLEY
SET) TRUSSES/RAFTERS OVER
MAIN TRUSSES/RAFTERS WITH
USP MTW12 OR MTW18

USP STRAP RS200 -- WRAP
OVER TOP OF EVERY PIGGY
BACK RAFTER/TRUSS AND FASTEN
WITH (4) 8d COMMON NAILS
AT EACH MEMBER

OPTIONAL RAFTER TIEDOWN IS:
6" FASTENMASTER TIMBERLOK
2"-3" IN TOP AND 3"-4" IN BOTTOM

MIN. (4) 8d COMMON NAILS
ON EACH SIDE OF 2 MEMBER
CONNECTION

RAFTER TO HIP CONNECTION:
SIMPSON LS50 OR
(2) 1/4"x3.5" WOOD SCREWS PLACED
AT 1/3 DEPTH POINTS AND PASS
THROUGH THE INSIDE CORNER OF CONNECTION



USP RS200 STRAP--OVERLAP
TOP AND BOTTOM HEADER (USE
BLOCKING BETWEEN STUDS WHERE
HEADERS DON'T ALIGN) 12" MIN.
EACH SIDE. TYP. WITH CORNER
WALLS SHEATHED LESS THAT 3'-6"
EITHER WAY AND ALL BAY WINDOWS.

SEE WALL SECTIONS FOR VERICAL TIEDOWN

HORIZONTAL STRAPPING DETAIL @ CORNERS

OPT. PAPER SIZE: for 1/4" =1'-0" on 24"x36" PAPER SIZE ENLARGE PRINTS TO 200%

FINAL CONSTRUCTION PLANS

Revision Schedule		Revision Number	Revision Description	Revision Date
Revision	Number			
1	1	1	FINALS	7/19/21

AREAS:		FIRST FLOOR HEATED	SECOND FLOOR HEATED	FRONT PORCH	REAR PORCH	TOTAL UNDER ROOF
1,317 SF	515 SF	1,832 SF	162 SF	20 SF	182 SF	2,014 SF

THE:	NOTTELY MODERN FARMHOUSE
FOR:	SUZANNE TOWNSEND
OFFICE:	SW DON COOK WAY FORT WHITE, FL GAINESVILLE, FL
SOLD BY:	RD

JOB#	59-21-039
FOUNDATION TYPE:	MONOSLAB
2x4 EXTERIOR WALLS	

PROPERTY OF:	AMERICA'S HOME PLACE
SHEET NUMBER:	S-6
DATE:	7/19/2021 4:59:44 PM
© COPYRIGHT - 2018	

FL- HOLD DOWN DETAILS