DATE 07/1	0/2008	Colum This Permit Must B	bia County	Building Pe	rmit	struction	PERMIT 000027153	
APPLICANT	ASHLEY I		•		HONE	352.271.0980		
ADDRESS	1901	K NW 67TH PLACE	3	GAINESVILI	Æ		FL 32653	
OWNER	OUR RED	EEMER LUTHERAN	CHURCH	PI	HONE	800.653.0386		
ADDRESS	5056	SW SR 47		LAKE CITY			FL 32024	
CONTRACTO	OR RON	ALD SUTTON - MO	RTON BLDGS	PI	HONE	352.271.0980		
LOCATION O	OF PROPERT	TY 47-S TO 1	1/4 MILE PAST I-75	ON THE RIGHT.				6.
TYPE DEVEL	LOPMENT	COMM. SHELL	F	ESTIMATED COS	Γ OF CO	NSTRUCTION	172854.00	A .
HEATED FLC	OOR AREA	6480.00	TOTAL A	REA 6480.00		HEIGHT 20	5.31 STORIES 1	
FOUNDATIO	N CONC	WALI	LS METAL	ROOF PITCH	4'12	FL.	OOR CONC	- 85
LAND USE &	ZONING	A-3			MAX.	HEIGHT 3	5	_
Minimum Set	Back Requir	ments: STREET-	FRONT 30.0	00 R	EAR	25.00	SIDE 25.00	
NO. EX.D.U.	2	FLOOD ZONE	<u>X</u>	DEVELOPME	NT PERM	MIT NO	-	
PARCEL ID	36-4S-16-0	03300-010	SUBDIVIS	ION				
LOT	BLOCK	PHASE	UNIT		TOTA	L ACRES 11.	76	
			CBC036362	(M)	Mu	1 POTAL	175	
Culvert Permit	No.	Culvert Waiver C	ontractor's License N	A	F	Applicant/Owner/	Contractor	
FDOT-EXISTI		08-0455-M	BLK		_	/R	N	
Driveway Con		Septic Tank Number		ning checked by	***	roved for Issuanc	e New Resident	
COMMENTS: CONFIRMATI		FILE. SHELL ONLY.	MFE @ 96.5' PER F	LANS. ELEVATION	ON			_
CONFIRMATI	ION LETTER	CREQUIRED.				Check # or C	ash 97117,15427,97	747
		500.01		DED 4 DE		the first of the party	4511 / / / /	
T D		FOR BU	JILDING & ZON	ING DEPART	MENI		(footer/Slab)	
Temporary Pov	wer	date/app. by	Foundation	date/app. by		_ Monolithic _	date/app. by	-
Under slab rou	ıgh-in plumbi	150 (FA) 15	Slab			Sheathing/	Nailing	
	0 1	date/ap	p. by	date/app.			date/app. by	
Framing	1 4 7	•	Rough-in plumbing	above slab and bel	ow wood	floor		a
Electrical roug	date/app						date/app. by	
		date/app. by	Heat & Air Duct	date/app. by]	Peri. beam (Linte	date/app. by	
Permanent pow			C.O. Final			Culvert	and app. of	
0.0120.00.00		e/app. by	-	date/app. by		9	date/app. by	
M/H tie downs,	, blocking, ele	ectricity and plumbing		app. by		Pool	date/app. by	
Reconnection		ate/app. by	Pump pole	U	Itility Pol			
M/H Pole	d		vel Trailer	ite/app. by		date/app. by Re-roof		
	nte/app. by	-		date/app. by		1001	date/app. by	
BUILDING PE	ERMIT FEE \$	865.00	CERTIFICATION I	FEE \$32.40		SURCHARGE	FEE \$ 32.40	- 34
MISC. FEES \$								
moer i BBo p	0.00	ZONING	CERT. FEE \$ 50.	00 FIRE FEE S	0.00	WAST	E FEE \$	
FLOOD DEVE					-		E FEE \$ AL FEE _ 1004.80	

PERMIT

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED TO BE IN ACTIVE PROGESS WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

. 06/25/2008 00:40

3522710470

MORTON BUILDINGS

PAGE 02/02

Bringh;	MORTO	N HOME OFF NOREW HOME OFFI	- 0	ERIAL N 1310027	o. M	HRTON	BUILD	ING!	S. INC	131	-0732	1 OF 1
Canary: Pink: Of	CONST	RUCTION CE	MER	1310021					TO	, YOB M	UMBER	PAGE
Sold			deeme	r Luthera	n Church	Adams, P.O. Bo	Phone 800	0-653-03		D	ate 8/27/2008	1
Addr	DE 8	5056 S	W CD	17		des O's		V COOE			Sales Con	
		STREET, R	D.P.O. BOX		LE	ke City	FL 32024 STATE 2IP CODE			1.	Forrestel 13	1-1
Dellw	er To	Same					Phone	-	- 000	2.	Ross 131-4	
Addre	288						ARE	A CODE				
Direc	tions	erreer, ro			cir	· 	STATE	Zii	PCODE	SE	E PREPARED I	DATE
										— — —	PROX. DELIVE	TDATE
	BI	DJOB	Yes D	NO (CI	HECK ONE	PRE	VAILING W	AGE []V	ON IN SE	(CHECK C		CI DATE
BUILL	DING	USE CIE	arificatio	n		LASS NO	TAIL TO TO				AINT TYPE &	COLCID
					dimensions ar	(Innimor or		ROOF	SIDE/END	SLIDE/DOC	1	7***
QTY.	5TY	LE W	TH RTO	HEIGHT	LENGTH	TRUSS SPACE	NG PAINT	KYNAR	KYNAR	KYNAR	KYNAR	KYNAR
							COLOR				1	
	It is	understo	od that	Morton	Buildings, I	nc is providir	g Our Red	eemer Lu	theran Ch	urch with	the construct	ed shell
	porti	on of the	e churci	n. Our R	edeemer L	etheran Chu	rch underst:	ands that	they will	have to hir	e a licensed	contractor
	TOPU	ne remai	nder of	the work	t, which wil	I include inter	rior slab, ele	ectrical, r	nechanica	L and plur	Ilaw as polido	20
-	Imer	ior finish	end in	terior wal	ll framing.	An additiona	permit pull	led by a s	separate li	censed co	ntractor will b)P
	Puils	irea to p	errorm	any of th	is additions	al work outsid	e of the sca	ope of w	ork current	ly contrac	ed with Mort	on
	BUILD	lings, Ind	C,									
_	~											
\$ 0.00		Dieu	m Oare		-OK #		Price excit	iding subse	quent chang	e orders 5	0.00	
\$ 0.00	_			nent (CHE)				\$_		will be
\$ 0.00						rery of materia	ls.				added to the co f payment sche	niract price
		-		ayment d							s not met.	uuie at teit
\$ 0.00		Fins	il Paym	ent is to b	e paid to 0		upon	completio	on of this co	ontract.		***************************************
LE	AD S	OURCE						NO.				
of Montor Buildings periles the segments to be completed by the segment of the se	Buildi, line, undereto the acceptions in place included and place included the real included in place included in place included in place included in place	ngs, Inc.; It nder the com, at the Com, it delively of discoppled before com a not milicip to 125% per sonable am CCRBED ON THE SAND RY CHARGE THE OTHER CHARGE THE OTHER CHARGE THE OTHER CHARGE THE COMPANY CHARGE THE COMPA	hel pilor lo denel may peny result the merch by the ow pletten of l stret, and i month se ount of ea it THIS FO! FORM 3 IES AND is condi	such accepted be dischargement to flability and an amount of the project, if the project is and attention and attention are part CREDITS STATEMENT OF THE PA	offence on Invested by the return the first per failure of the process of the first per failure	rigative consumer of any monies we any monies we any monies we do not not the consumer of the	taporf may be hich the purchase liver the merchase ideas Risk thoundedging entities is required. It is contract will be a terms of this of AND, of TIRETY. ADDITIONAL CONTRACTY ADDITIONAL CONTRACTY.	try or the pur- ser may have ndise on any ance coverag- tory complet to agreed to o renegotiate o maximum n ontract. N ANY ACCO FIONS AND/ AND WARR.	d that prior to a deposited as a requested or sequested or sequested or sequested or the both se provided in the both state of the sequested or sequested or sequested or sequested or sequested or sequested in the sequested or	per to accept a condition of tenfativaly set ided by Morton ding and make than Morton E of default by i the customer: ORM 12S SER TO THIS AGR	EEMENT MUST BE	I, Minola officer filly of Morton agreed by the I the oustomer II construction If occupancy loyees and its Buildings, Inc.
DA ATE	, uic (יטו ונטווקי	aprice t	ne order i	delivery do	es not occur, t	nrough no fa	ult of MBI	, by this da	te.		
BANK		41										
Oran	angne Sete	i mereny w	ratesanda a	nd represty	nty that bound	in the owner of	record of the m	rembes upo	n which this	hullding is to	be erected.	~
O 17 III	30	-Eisunet	- X	MAKE	M/140	in	Vir		Da	te 6/	126/08	
			NOTE	E YOU THE	SS DAY AF	AY CANCEL THE THE DATE OR THE O	IIS TRANSAC	TION AT A		RIOR TO MID	NIGHT OF THE NOTICE OF	THIRD
orm 121	Voven	po redi				THE POR MINEX	LANATION	JE IMIS RI	GHI.	(1)	2001 Morton Bul	ldings. Inc
												Col mie.

r.q

Jun. 26. 2008 11:35AM 0806-43 Ce/2 Ce/ No. 3825 ATTN: Ashley Rich Hackt Derve av Lice President of over congregation at Dur Redeemer Sutheran Church. Prich Hackthalso own Orilling coordinator and has authoristion to handle any and all permits/forms or invoiced Concerning The new Drielding. please cell me evil any Freidend. Ditten Our Redeemen Lutteran Church 386/758-8454 (home)



SUPERIOR FIBERGLASS, INC. - WIND ANALYSIS OF STEEPLE NO: June 25, 2004

Revised 2/5/05

4217NV

OBJECTIVES: <u>l.</u>

- A. Compute the maximum loads at the base of the steeple 4217NV, including: 1) shear stresses due to wind loading, 2) moment due to wind pressure, and 3) vertical forces due to the total weight (dead load).
- B. Compute the maximum stresses in the anchor bolts and the steeple base.

note:


inputs are shown as: xxx

"^n" means raise to the nth power (example x^2 means x squared)


DIMENSIONAL DATA FOR COMBINATION 4217NV: <u>II.</u>

A. PLAN VIEW OF STEEPLE:

Note that the diagonal dimensions are computed and shown. These are important because the maximum wind loads are theoretically developed against the maximum "projected" area, which is at the diagonal. All dimensions are in feet.








ELEVATION - NOT TO SCALE

<u>III.</u>	COMPUTE	AREAS:				location	location of indiv.	
	Piece	height	base (ft)	type	area (sq ft)	of individ. centroids	centroids from btm	included angle
	A	(ft) 17.00	5.95	triangle	50.59	5.67	12.58	80.071
	В	3.60	5.31	square	19.11	1.80	5.12	N/A
	С	3.32	6.36	square	21.11	1.66	1.66	N/A
	TOTAL				90.81			

The projected area of the steeple is plotted below as a function of the height from the top of the roof:



IV. COMPUTE TOTAL HORIZONTAL FORCES and TOTAL MOMENT FROM WIND:

Assuming that the steeple acts as one continuous object, the base of the steeple will have the following reactions:

Downward Force (y direction) equal to the total weight Horizontal Force (x direction) equal to the total force from wind pressure Moment at the base equal to the total horizontal forces times a moment arm.

Horizontal Force from wind pressure = wind pressure x projected area

Moment at base = total horizontal force x length (where length = distance to centroid of the section)

The wind pressure is computed as: K x V^2, where K is a pressure coefficient for different heights (z), and V is air velocity. K may be computed as follows: K = .00357 x ((z/32.8) ^ 1/5) x 1.05. Assuming a maximum height of 2 times the steeple height, or 47.8 ft, wind pressures were computed for varying wind velocities (V), and are summarized below. The formulas for computing wind pressures were taken from Building Design and Construction Handbook, by Frederick S. Merritt, fourth edition, pages 3.5 - 3.6. Copies of these pages are attached in Section IX, and a Wind Map for the United States is shown in Section IX. A graph of wind pressures, as a function of wind velocity and steeple height above grade, are shown on page 5. Note that Exposure "D" was assumed for this generic stress calculation report, which is the "worst-case" assumption, and assumes a flat, coastal area. A 5% increase in wind pressure was assumed to account for hurricane conditions.

The moment of each steeple section is computed by taking the total horizontal force generated, and multiplying by the distance from the roof to the centroid of each section. The centroid was computed above (page 3).

The following table summarizes the forces and the moments generated by different wind speeds for each steeple section.

For overall height above grade =

47.8 ft:


Wind	Wind								
Speed	Pressure	Result	ing Forces ((lbs)	<u>F</u>	Resulting Mor	nents at Ba	se (ft-lbs)	
MPH	<u>#/sf</u>	A	<u>B</u>	<u>C</u>	TOTAL	A	<u>B</u>	<u>C</u>	TOTAL
30	3.64	184	70	77	330	2,316	356	127	2,799
40	6.47	327	124	137	587	4,117	633	227	4,976
50	10.11	511	193	213	918	6,433	988	354	7,775
60	14.55	736	278	307	1,322	9,263	1,423	510	11,196
70	19.81	1,002	379	418	1,799	12,609	1,937	694	15,240
80	25.87	1,309	494	546	2,349	16,468	2,530	906	19,905
90	32.74	1,656	626	691	2,973	20,843	3,202	1,147	25,192
100	40.42	2,045	773	853	3,671	25,732	3,954	1,416	31,101
110	48.91	2,474	935	1,033	4,442	31,135	4,784	1,713	37,632

Consequently, for a 110 MPH wind, the maximum loads at the base of the steeple are:


 Horizontal (shear) =
 4,442
 lbs

 Vertical (dead load) =
 1,000
 lbs

 Moment at base =
 37,632
 ft-lbs




A "freebody diagram" of the steeple is shown pictorially below (for a 110 MPH wind):




STRESSES AT BOTTOM OF EACH SECTION:

A. Anchor Bolt Pattern:

V.



- 1. The wind loading tends to tip the steeple over along line "A" shown in the sketch to the right and above.
- 2. Worst case loading for the anchor bolts is the minimum distance from "A" to the furthest bolt. a. = 0.67 b. = 3.17



reactions of anchor bolts

- 3. The horizontal shear forces are evenly distributed among the four anchor bolts.
- 4. The vertical weight forces are evenly distributed along the base.
- 5. The steeple base acts as one continuous member.
- 6. Thickness of the fiberglass at the base is approximately: 0.125
- 7. Anchor bolt diameter: 0.75 inches, area = 0.442 sq in # of anchor bolts = each, on "rows"
- 8. Anchor bolts do not loosen.


C. BENDING STRESSES IN FIBERGLASS SKIN AT BOTTOM OF EACH SECTION:

Assume a bending moment is developed as a result of the wind moment. Compute the moment of inertias at each of the section bases, then compute the bending stresses and average shear stresses:

				moment		total horiz	total	bending	average
Btm of	Base	width	length	of inertia	Area	force	moment	stress	shear
Section	Type	(ft)	(ft)	(in ^ 4)	(sq in)	(lbs)	(ft-lbs)	(psi)	(psi)
Α	Rectangular	4.21	4.21	10652.9	25.2	2474.3	14021.2	398.8	98.2
В	Rectangular	3.76	3.76	7562.2	22.5	934.8	24608.5	879.8	41.6
С	Rectangular	4.50	4.50	13031.2	26.9	1032.7	37632.3	935.7	38.3

Bending stresses are computed by: Bending Stress = Moment * (length/2) / Moment of Inertia Average Shear Stresses are computed by: Shear Stress = Horizontal Force / Area

D. Compute tension stress in the anchor bolts due to moment:



Calculations: (d1 x T1) + (d2 x T2) = M/n Bolt Stress (max) = T max/ Bolt Area

	total	number of	bolt						Max
Moment	# bolts	"arms"	diam	bolt area	d1	d2	T1	<u>T2</u>	Tensile Stress
(ft-lbs)	(each)	(n) each	<u>(in)</u>	(sq in)	<u>(ft)</u>	<u>(ft)</u>	(lbs)	(lbs)	(psi)
37632	4	2	0.750	0.442	0.67	3.83	2257.9	4515.9	10221.5

MAX STRESS IN SINGLE BOLT =	10221.5 PSI (tension)	{ 110 MPH Wind }

** see principal stresses below

E. Compute Shear Stresses in Anchor Bolts due to Horizontal Wind Load:

Total Horiz. Force =

4,442 lbs

Area of bolts =

1.77 sq inches

MAXIMUM AVG SHEAR PER BOLT =

2513.5 psi (shear)

{ 110 MPH Wind }

F. Compute Compressive stress in Steeple Base due to Weight:

Total weight =

1000.00 pounds

Perimeter of Base =

18.00 ft

Area of base =

27.0 sq inches

Compressive stress due to weight = Force / Area =

37.0 psi

MAX. COMPRESSIVE IN BASE DUE TO WEIGHT =

37.0 PSI

^{**} see principal stresses below

VI. SUMMARY OF STRESSES:

										Stresses in F		
				Max					Compres.			
				Bending	Shear				Stress	Bending	Bending	Bending
				Stress in	Stress in				in Base	Stress	Stress	Stress
		Total	Total	Bolts due	bolts due	PRIN	ICIPAL STRES	SSES	(FRP)	Base of	Base of	Base of
Wind	Wind	Horiz.	Moment	to Wind	to Horiz.		IN BOLTS **		due to	Section	Section	Section
Speed	Pressure	Force	at Base	Moment	Force	$\sigma 1$	σ 2	τ	Weight	"A"	"B"	"C"
(mph)	(#/sf)	(lbs)	(ft-lbs)	(psi)	(psi)	(psi)	(psi)	(psi)	(psi)	(psi)	(psi)	(psi)
30	3.64	330	2,799	760	187	804	-43	424	37	30	65	70
40	6.47	587	4,976	1,352	332	1,429	-77	753	37	53	116	124
50	10.11	918	7,775	2,112	519	2,233	-121	1,177	37	82	182	193
60	14.55	1,322	11,196	3,041	748	3,215	-174	1,695	37	119	262	278
70	19.81	1,799	15,240	4,139	1,018	4,376	-237	2,306	37	162	356	379
80	25.87	2,349	19,905	5,406	1,329	5,716	-309	3,012	37	211	465	495
90	32.74	2,973	25,192	6,843	1,683	7,234	-391	3,813	37	267	589	626
100	40.42	3,671	31,101	8,448	2,077	8,931	-483	4,707	37	330	727	773
110	48.91	4,442	37,632	10,222	2,514	10,806	-585	5,695	37	399	880	936

Principal stresses only computed for bolts because of higher stresses

NOTE: Computations have not been performed for the Steeple Frame

VII. CONCLUSIONS:

All of the computed stresses are within the acceptable ranges.

Anchor Bolts: The maximum stress allowable is 19,100 psi in tension (see Section IX). The maximum computed stress was found to be: 10,806.2 psi.

The maximum allowable shear stress is : computed shear stress was found to be

9,900.0 psi (see Section IX). The maximum

be 5,695.4 psi

FRP: The maximum allowable stress in the Fiberglass (FRP) is assumed to be approximately 12,000 psi. The maximum computed stress was found to be: 935.7 psi



May 17, 2008

Mr. Rick Hacht H&H Liquid Sludge Disposal, Inc. P.O. Box 390 Branford, FL 32008

RE:

Our Redeemer Lutheran Church

Lake City, Florida

Subject:

Geotechnical Exploration and Evaluation Report

Project No.: 08-G061-01

Dear Mr. Hacht:

Gyetec, Inc. has performed the authorized geotechnical exploration and laboratory testing for Our Redeemer Lutheran Church in Lake City, Florida. This report presents our understanding of the site and subsurface conditions along with our engineering evaluation and recommendations.

We have enjoyed working with you on this project and look forward to continued association with you on future projects. If you have any questions concerning this report, please contact our office.

Sincerely,

GYETEC, INC.

John A. Iya

President

Sur Those- godel

Vice President

GEOTECHNICAL EXPLORATION AND EVALUATION REPORT

Our Redeemer Lutheran Church Lake City, Florida

PREPARED FOR:

H&H Liquid Sludge Disposal, Inc. Lake City, Florida

Project No. 08-G061-01



1731 NW 6th Street, Suite B Gainesville, Florida 32609 phone: 352 375-7108 fax: 904 855-8092

May 17, 2008

TABLE OF CONTENTS

SE	CTION PAGE	NUMBER
1.0	Project Information 1.1 General Project Information 1.2 Existing Conditions and Project Description	1
	Geotechnical Exploration 2.1 Field Exploration 2.2 Laboratory Testing	2
3.0	Subsurface Conditions 3.1 General 3.2 Soil Conditions 3.3 Groundwater Conditions	3
4.0	Geotechnical Engineering Evaluation and Recommendations 4.1 Basis of Evaluation & Recommendations 4.2 Foundation System Evaluation	4
5.0	Foundation Design & Site Preparartion Recommendations 5.1 Shallow Foundation Design 5.1.1 Foundation Type 5.1.2 Bearing Pressure and Footing Depth 5.1.3 Foundation Size 5.1.4 Bearing Material 5.2 Floor Slab Design & Construction Recommendations 5.3 Site Preparation & Construction Recommendations 5.3.1 Shallow Groundwater Control 5.3.2 Initial Site Preparation 5.3.3 Surface Water Control 5.3.4 Site & Fill Compaction 5.3.5 Disturbed Soil Conditions 5.3.6 Foundation Bearing Surface Preparation	6
6.0	Quality Control & Testing Guidelines	10

TABLE OF CONTENTS (Continued)

APPENDIX

Boring Location Plan
Boring Profiles
SPT Boring Logs
Summary of Laboratory Test Results
Key to Soil Classification
Field and Laboratory Test Procedures

1.0 PROJECT INFORMATION

1.1 General Project Information

The purpose of the exploration was to develop information concerning the subsurface conditions in order to: (1) evaluate the site with respect to the construction of the proposed new building; (2) develop foundation design and construction recommendations for the new building; and (3) provide recommendations for earthwork and pavement construction.

This report describes the field activities performed and presents our findings. The enclosed guideline parameters represent results that will aid in your site improvement, and foundation design. Our evaluation required the collection of site and subsurface data and performance of geotechnical engineering analysis of the collected data.

1.2 Existing Conditions and Project Description

Information regarding this project was provided to Gyetec, Inc. by Mr. Rick Hacht. The site is located at 5056 SW State Road 47 Lake City in Florida. The existing site conditions generally consist of fairly flat grounds covered with short grass. No ponding was observed in the area during our investigation. According to the information provided to us, we understand that the improvements will consist of the construction of a new church building. We also understand that the new building will consist of a metal building structure. Information regarding the structural loading conditions for the new building was not available at the time of this report.

2.0 GEOTECHNICAL EXPLORATION

2.1 Field Exploration

To explore the subsurface conditions at the site, a total of five Standard Penetration Test (SPT) borings (B-1 through B-5) were performed within the limits of the proposed new building. Four SPT borings (B-1 through B-4) were performed at the four corners of the building and drilled to a depth of 25 feet below the existing ground surface. One SPT boring (B-5) was placed as close as possible to the center of the building and extended to a depth of 50 feet. The SPT boring test locations are shown on the Boring Location Plan presented in the Appendix.

The SPT Test Boring Logs are presented in the Appendix. They indicate the penetration resistance and present the soil description for each soil type encountered in the test borings. The stratification lines and depth designations on the boring logs represent the approximate boundaries between soil types. In some instances, the transition between soil types may be gradual. A brief description of the exploratory drilling and sampling techniques used is presented in the Field Test Procedures section presented in the Appendix.

2.2 Laboratory Testing

Quantitative laboratory testing was performed on selected samples of the soils recovered from the field exploration. The laboratory testing was necessary in order to better define the composition of the soils encountered. Laboratory tests were performed to determine the fines content, natural moisture content, organic content, and atterberg limits of the selected soil samples. The results of the laboratory testing are shown on the Summary of Laboratory Test Results also presented in the Appendix. The laboratory testing procedures used are also briefly presented in the Field and Laboratory Test Procedures sheets presented in the Appendix.

3.0 SUBSURFACE CONDITIONS

3.1 General

An illustrated representation of the subsurface conditions encountered in the building area is shown on the Boring Profiles presented in the Appendix. The profiles and the soil conditions outlined below highlight the major subsurface stratification. The SPT Boring Logs in the Appendix should be consulted for a detailed description of the subsurface conditions encountered at each boring location. When reviewing the Boring profiles, it should be understood that soil conditions may vary between boring locations.

3.2 Soil Conditions

Review of the SPT borings indicates that the building is generally underlain by suitable but very loose sands (SP) in the upper 4.0 to 4.5 feet of depth, followed by firm to hard plastic clayey sands (SC) and isolated sandy clays (CL) until the boring termination depth of 25 and 50 feet. below the existing ground surface.

Due to the very loose condition of the surficial soils, we recommend that the exposed soils be compacted using a vibratory roller, which has a static at-drum weight of at least eight tons and a drum diameter on the order of four feet. The compaction operations should consist of at least eight overlapping passes of vibratory roller in each direction. This compactive effort should help improve the overall uniformity and bearing conditions of the near surface and underlying soils.

3.3 Groundwater Conditions

At the time of drilling, the groundwater level was encountered at a depth ranging from 24.5 to 27 feet below the existing surface. It should be anticipated, however, that groundwater levels will fluctuate due to seasonal climate variations, surface water runoff patterns, construction operations, and other factors. Therefore, since groundwater level variations are anticipated, drainage design and specifications should accommodate such possibilities and construction planning should be based on the assumption that such variations will occur.

4.0 GEOTECHNICAL ENGINEERING EVALUATION AND RECOMMENDATIONS

4.1 Basis of Evaluation & Recommendations

The following recommendations are based on the project information and the data obtained in this exploration. If the locations of the structures are changed, Gyetec, Inc. should be contacted so that our recommendations can be reviewed. The discovery of site and/or subsurface conditions during construction that deviate from the data obtained in this exploration should also be reported to us for our review.

4.2 Foundation System Evaluation

We recommend that the exposed soils must first be compacted using a vibratory roller, which has a static at-drum weight of at least eight tons and a drum diameter on the order of four feet. The compaction operations should consist of at least eight overlapping passes of vibratory roller in each direction. This compactive effort should help improve the overall uniformity and bearing conditions of the near surface and underlying soils.

As mentioned earlier in this report, information regarding the structural loading conditions was not available at the time of this report. It is therefore recommended that Gyetec, Inc. be given the opportunity to review the final foundation designs in order to augment or re-evaluate some of the recommendations contained herein.

Based on our findings, the building area is generally underlain by plastic clayey sands (SC) and isolated sandy clays (CL/), which are expected to be sensitive to moisture variations. The results of our laboratory testing indicates that these soils have a potential to exhibit shrink / swell characteristics in response to water content fluctuation. However, based on the results of our findings, it is our opinion that the subsurface conditions are adaptable for use of shallow foundation system to support the planned building provided that a proper surface water control program is implemented to ensure that the natural water content of the existing plastic soils is not impacted during the service life of the building. The implemented water control program should include means of diverting surface water away from the building and its foundation system.

When plastic soils, such as clayey sands (SC) and sandy clays (CL) are encountered at the bottom of footings, they should be excavated a minimum depth of 2 feet below the bottom of footing excavations and replaced with clean sands placed and compacted as herein recommended.

Following the recommended initial compaction procedures, it is our opinion that the soil conditions can provide adequate support for the proposed building founded on shallow bearing footings and proportioned for a maximum allowable soil bearing capacity of 2,000 pounds per square foot (psf). At this bearing pressure, the foundations should be placed at least 24-inches below the exterior finished grades in order to provide necessary confinement to the foundation bearing level soils.

Using a maximum bearing pressure of 2,000 psf, we have estimated the total settlement of the structures will be on the order of 1 inch or less. This settlement is the result of elastic compression of the upper loose sandy soils and consolidation of the clayey soils. The elastic compression of the sandy soils should occur almost immediately upon the application of the structural dead load during construction. Consolidation settlement is expected to occur over time due to the consolidation of the clayey soils. Following site work and construction techniques in general accordance with our subsequent recommendations, we anticipate that differential settlements of the structures should be within tolerable magnitudes.

5.0 FOUNDATION DESIGN & SITE PREPARATION RECOMMENDATIONS

5.1 Shallow Foundation Design

5.1.1 Foundation Type

It is our opinion that conventionally designed and constructed isolated and continuous shallow bearing footings are applicable for the foundations of the new proposed building, provided that an adequate surface water control program is implemented to ensure that the natural water content of the underlying plastic soils is not impacted during the service life of the building. The implemented water control program should include means of diverting surface water away from the building and its foundation system.

5.1.2 Bearing Pressure and Footing Depth

The maximum allowable soil bearing pressure for use in shallow foundation design of the building should not exceed 2,000 psf. The foundations should be designed based on the maximum load that could be imposed by all loading conditions. At this bearing pressure, all footings should bear at least 24 inches below the exterior final grades. This minimum bearing depth should provide the necessary confinement of the foundation bearing level soils.

5.1.3 Foundation Size

The minimum width recommended for the isolated and continuous wall footings is 24 inches and 18 inches, respectively. Even though the maximum allowable soil bearing pressure may not be achieved, the minimum width recommendation should still control the size of the footings.

5.1.4 Bearing Material

The proposed building footings should bear in either the existing surficial sands, which will require compaction, or in compacted structural fill. The bearing level soils, after compaction, should exhibit densities equivalent to 95% of the Modified Proctor maximum dry density (ASTM D1557). When clayey sands classified as SC or sandy clays classified as CL, are encountered at the bottom of footings, they should be regarded as plastic materials which should be excavated a minimum depth of two feet below the bottom of footing excavations and replaced with clean compacted sands placed and compacted as herein recommended.

5.2 Floor Slab Design & Construction Recommendations

The floor slabs may be constructed directly on compacted fine sands, natural soils, or structural fill. The granular free-draining soils should be compacted to a density of at least 95 percent of the Modified Proctor maximum dry density. A gravel frost protection layer is not considered necessary, although a vapor barrier should be installed to help reduce dampness of the surface of the slab. In addition, a thin lift (three inches) of sand may be placed above the vapor barrier to minimize curling of the slab, which occurs due to the difference in curing rates between the top and bottom of the slabs.

5.3 Site Preparation & Construction Recommendations

5.3.1 Shallow Groundwater Control

Groundwater level was encountered at a depth ranging from 24.5 to 27 feet below the existing ground surface at the time of drilling. Groundwater control is therefore not anticipated. However, if required, groundwater drawdown for the building can probably best be achieved using temporary perimeter drainage ditches which are graded to a positive gravity outfall away from the site. The groundwater level should be maintained at least one foot below the bottom of any excavations made during construction and two feet below the surface of any vibratory compaction operations.

5.3.2 Initial Site Preparations

All vegetation, topsoils, roots, organic zones and construction debris should be removed from construction areas for a distance of at least 5 feet beyond the improvement footprint areas. The depth to which stripping will be required in unpaved areas will vary to some degree. Some localized areas may require more than 6 inches of stripping to remove significant root zones, if present, whereas, most areas may require 4 inches or less.

5.3.3 Surface Water Control

The need for surface water runoff control should be anticipated during the site preparation and foundation construction process. Lack of proper controls could result in ponding of surface water in shallow foundation bearing areas and on compacted surfaces. Ponded water, combined with machine or foot traffic during construction operations or other activities, could disturb

otherwise acceptable soils or previously compacted existing soils, causing instability, "pumping", and generally unacceptable conditions. The ponded water will also impede or prevent necessary soil compaction operations and make construction trafficability difficult. Surface water can be controlled by proper grading of the site and by the use of temporary drainage ditches, diversion berms, and/or pumping from drainage controlled collection points.

5.3.4 Site & Fill Compaction

After initial clearing and stripping operations have been completed, the exposed soils in the proposed improvement areas should be compacted to densities equivalent to 95 percent of the Modified Proctor maximum dry density (ASTM D1557). We further recommend that the exposed soils be compacted using a vibratory roller, which has a static at-drum weight of eight tons and a drum diameter on the order of four feet. The compaction operations should consist of at least eight overlapping passes of vibratory roller in each direction. This compactive effort should help improve the overall uniformity and bearing conditions of the near-surface and underlying soils.

Structural fill if needed may be placed in lifts not exceeding 12 inches. Each lift of fill should be compacted until densities equivalent to at least 95 percent of the Modified Proctor maximum dry density are uniformly obtained. Structural fill should consist of an inorganic, non-plastic, granular soil containing less than 10 percent material passing through the No. 200 mesh sieve (relatively clean sand with a Unified Soil Classification of SP, SP-SM, SP-SC).

5.3.5 Disturbed Soil Conditions

Should the soils experience "pumping" and subsequent soil strength loss during compaction operations, compaction work should be terminated and: (1) the disturbed soils removed and backfilled with "dry" structural fill soils, which are then compacted; or (2) the excess moisture content within the disturbed soils allowed to dissipate before re-compaction. Furthermore, the groundwater level should be checked and controlled as necessary in order to help ensure proper drawdown of any high groundwater conditions that may be causing the "pumping" conditions during comp action or construction activity upon these soils.

5.3.6 Foundation Bearing Surface Preparation


The upper 12 inches of bearing soils in the footing excavation bottoms should be compacted to densities equivalent to 95 percent of the Modified Proctor maximum dry density. Compaction or re-compaction of the footing excavation bearing level soils (if loosened by the excavation process) can be best achieved by making several passes with relatively lightweight, walk-behind compaction equipment. Concentrated root zones and unsuitable organic soils, if encountered at the footing bearing level should be completely removed and replaced with compacted structural fill material. When clayey sands classified as SC or sandy clays classified as CL, are encountered at the bottom of footings, they should be regarded as plastic materials which should be excavated a minimum depth of two feet below the bottom of footing excavations and replaced with clean compacted sands placed and compacted as herein recommended.

6.0 QUALITY CONTROL & TESTING GUIDELINES

Prior to initiating compaction operations, we recommend that representative samples of the structural fill material to be used and acceptable exposed in-place soils be collected and tested to determine their compaction and classification characteristics. The maximum dry density, optimum moisture content, gradation and plasticity characteristics should be determined. These tests are needed for compaction quality control of the structural fill and existing soils and to determine if the fill material is acceptable.

A representative number of in-place field density tests should be performed in the compacted existing soils and in each lift of structural fill or backfill to confirm that the required degree of compaction has been obtained. During general grading/filling operations, at least one test per lift should be made for every 2,000 square feet of fill. After fill placement and foundation excavation, in-place density tests should be performed at representative locations in the bearing level soils in the footing excavation bottoms. We recommend that one density test be performed for every 50 feet of continuous wall footings, with a minimum of one test per footing excavation.

APPENDIX





ROJEC	T:	Our F Chur	Redee ch, La	mer Lu ke City	itheran /, FL		JOB NO. 08-0	.: 3061-01	SHEET NO. 1 of 1	BORING NO. B-1		
EGUN		СОМР	LETED		DRILLE	R #OF	SAMPLES	DRILL RIG	TOTAL DEPTH	DEPTH TO GROUND WATER		
04/22/	08	0	4/22/0	8	PK/FS	5	8	55	25 Feet	24.5 Feet		
SAMPLE BLOWS "N"	1st 6"		RATION OWS 3rd 6"		SAMPLE NO.	DEPTH			son	L DESCRIPTION		
				75M10010		1 -						
4	1	2	2	2	1	2			Light G	Gray Fine SAND (SP)		
3	1	2	1	2	2	3 -						
						5						
8	3	4	4	6	3	6 -			Tan & Orang	e Clayey Fine SAND (SC)		
22	6 .	9	13	15	4	8		14				
27	9	12	15	18	5	9 —						
				10		11						
						12		ı	ight Tan & Ora	inge Clayey Fine SAND (SC)		
					-	13						
24	7	10	14		6	15						
						16						
						18						
19	7	. 8	11			19 20						
	n.					21			Light Tan (Clayey Fine SAND (SC)		
						22						
						23				*		
34	8	14	20	-		25 —			Boring	Terminated @ 25'		
						26						
4						28						
						29						
						30				Sterior Control of the Control of th		



OJEC	T:			mer Lu ke City	theran /, FL		JOB NO. 08-0	.: 3061-01	SHEET NO. 1 of 1	BORING NO.	B-2
GUN		СОМРІ	ETED		DRILLE	R # OF	SAMPLES	DRILL RIG	TOTAL DEPTH	DEPTH TO GROUND WATER	
04/22/			4/22/0		PK/FS	3	8	55	25 Feet	24.5 F	eet
MPLE		PENETI	RATION DWS		SAMPLE NO.	DEPTH			SOI	L DESCRIPTION	
"N"	1st 6"	2nd 6"		4th 6"	1,000.00						
						, –					
1945						1			**************************************		
7	3	4	3	3	1	2			Light C	Gray Fine SAND (SP)	
						3					
4	2	2	2	2	2	4					
	3					5		*************	18		
			_	_							
11	3	4	7	7	3	6					
						7					
25	6	11	14	17	4	8					
						9 —					
32	12	15	17	20	5	10			Gray & Orang	ge Clayey Fine SAND (SC)	
						11					
						12					
						13					
					-	14					
20	7	10	10		6	15					1.4
						16					
						17					
					- [
						18					
						19					
21	7	9	12	1	7	20					
	ri.					21			Tan & Orang	e Clayey Fine SAND (SC)	
1											
					ŀ	22					
- 1	- 1		-			23					
						24					
18	6	8	10	9	8	25					
								4	Boring	Terminated @ 25'	
						26					
						27					
						28					
					}	29					
						30		, , , , , , , , , , , , , , , , , , ,			1



JEC	T:			mer Lu ke City	theran /, FL		JOB NO	.: 3061-01	SHEET NO. 1 of 1	BORING NO.	B-3
N		сомрі			DRILLE	R # OF	SAMPLES	DRILL RIG		DEPTH TO GROUND WATER	
122/	08	0	4/22/0	8	PK/FS	i	8	55	25 Feet	Not Encoun	tered
PLE WS		PENETI	RATION DWS		SAMPLE NO.	DEPTH			soi	IL DESCRIPTION	
4	1st 6"	2nd 6"		4th 6"							
						1 -					1
3	1	2	1	2	1	2 —			Light (Gray Fine SAND (SP)	
_			-		-	- a_			Light	oray rino orang (or y	
						3			i		
1	1_	2	2	2	2	4			٠.		11 7
						5					
9	3	8	11	15	3	6					
						7 -					
7	12	1.7	20	22	4	8					
3-2		9				9 -					
0	14	19	21	20	5	10			Grav & Oran	ge Clayey Fine SAND (SC)	
	1-1-	10		-			8		olay a olah	ge c.e., c,	
						11					
						12					
						13					
						14					
7	8	12	15		6	15					2.4
						16					
						17					
						18					
						19					
		44	40		_						
4	9	11	13		7	20		L	ight Gray Sligh	tly Clayey Fine SAND (SP-SC	()
		,			-	21					
					-	22					
						23					
-						24					
0	8	10	10	-	8	25					
						26		4	Borin	g Terminated @ 25'	
						27					
					1						
	271					28					
						29					
						30					



ROJECT: Our Redeemer Lutheran Church, Lake City, FL							JOB NO.: 08-G061-01		SHEET NO. 1 of 1	BORING NO. B-4
GUN		COMPL			DRILLE	R #OF	SAMPLES	DRILL RIG	TOTAL DEPTH	DEPTH TO GROUND WATER
04/22/0	08	0.	4/22/0	8	PK/FS		8	55	25 Feet	Not Encountered
AMPLE		PENETRATION SA BLOWS " 2nd 6" 3rd 6" 4th 6"		SAMPLE NO.	DEPTH			soı	IL DESCRIPTION	
"N"	1st 6"	2nd 6"	3rd 6"	4th 6"		1888				
						1 -				
3	1	1	2	1	1	2			Light 0	Gray Fine SAND (SP)
						3 -				
			_	_	2	4				
4	2	2	2	2						
						5				
23	3	9	14	14	3	6				
						7 _				
37	10	17	20	24	4	8 -			Gray & Oran	ige Clayey Fine SAND (SC)
						9 -				
38	12	17	21	25	5	10				
30	14	- ' '	-			11				
						12				
						13				
						14				
62	16	25	37		6	15				4
						16				
					1	17				
						18	1			
							558		Tan & Oran	ge Clayey Fine SAND (SC)
						19	X A A A A A A A A A A A A A A A A A A A		Tan & Oran	ge clayey into example (e-e)
37	12	17	20	-	7	20				
	6					21				
						22				
						23				
		-	-	-	-	24				
25	9	11	14	1	8	25				
25	9	111	14	-	0		838		Borii	ng Terminated @ 25'
						26				
						27				
						28 -				
	-	-	-			29				
						30				· ·



ROJECT: Our Redeemer Lutheran Church, Lake City, FL							JOB NO.: SHEET NO. 1 OF 2			BORING NO. B-5			
GUN COMPLETED DRILLER # OF						# OF	SAMPLES	DRILL RIG	TOTAL DEPTH	DEPTH TO GROUND WATER			
04/22/0	าล	04/22/08 PK/FS 13 55 50 Feet 27 Feet				27 Feet							
MPLE		PENETE	RATION	ION SAMPLE				SOIL DESCRIPTION					
OWS	1st 6"	2nd 6"	3rd 6"	4th 6"	NO.	DEPIN							
	at Adore	SSS110				_							
						1				E CAMP (CP)			
5	2	3	2	2	1	2			Light (Gray Fine SAND (SP)			
						3							
4	2	2	2	3	2	4			*				
	-					5							
21	4	9	12	18	3	6							
						7 -							
34	10	16	18	23	4	8			Tan & Oran	ge Clayey Fine SAND (SC)			
						9 —				*			
37	11	17	20	24	5	10							
31	- 11	1,	20	-									
						11							
						12							
						13							
	+-	-	-			14			Cananial	h Gray Sandy CLAY (CL)			
18	5	8	-10		6	15			Greenisi	(OL)			
10	+	"	10						9				
						16							
						17							
	1					18							
	+	+	-	-	-	19							
16	7	7	9		7	20 -							
10	+ '	+ '	-										
						21							
						22			Gray & Ora	inge Clayey Fine SAND (SC)			
						23			record RCD (R)				
	-		-		-	24							
0.4	8	9	12		8	25							
21	8	9	12				*****			S #			
						26							
						27							
				*		28 -							
				_		29							
						20							



PROJECT: Our Redeemer Lutheran Church, Lake City, FL								: 6061-01	SHEET NO. 2 of 2		B-5	
EGUN		COMPL			DRILLE	R #OF	SAMPLES	DRILL RIG	TOTAL DEPTH	DEPTH TO GROUND WATER		
04/22/08 04/22/08					PK/FS		13	55	55 50 Feet 27 Feet			
SAMPLE BLOWS	PENETRATION BLOWS 1st 6" 2nd 6" 3rd 6" 4th 6"			SAMPLE NO.	DEPTH	4		SOIL DES	SCRIPTION			
"N"	1st 6"	2nd 6	310 6	4111 0		31		Gra	ay & Orange Cl	ayey Fine SAND (SC)		
						32						
						33						
						34		*.			20	
14	5	7	7		10	35						
						36						
						37						
	*					39			Light Gray Clay	rey Fine SAND (SC)		
19	6	9_	10		11	40						
	,					41						
						42						
,						44						
12	5	5	7		12	45						
						46						
						47 - 48						
		-		-	-	49						
11	4	5	6		. 13	50			Boring Te	erminated @ 50'		
ń						51	<u>.</u>		Doming 15			
						52						
	_	_				53						
						55						
						56						
						57						
						58	****					
						59 60						

SUMMARY OF LABORATORY TEST RESULTS

Our Redeemer Lutheran Church Lake City, Florida

) Atterberg	#200 LL PI			3.7 SP	21.4 21 16 SC	11.6 · SP-SC	23.3 ' 25 18 SC	51.8 42 27 CL	
	#10								
Natural Moisture Organic Confent Content	(%) (%)			11.3	290	22.22	24.7		
Approx.	Approx. Depth (ft)			00-40	45-60	0.0 - 0.7	8.0-10.0	11.5 - 17.5	
Samula	No.			-	, ,	4 1	· ·	9	
o di a	No.			- Z	2 0	D-7	D-3	B-5	

KEY TO SOIL CLASSIFICATION

Correlation of Penetration Resistance with Relative Density and Consistency

Sand and Gravel		Silts and Clays		
No. of Blows, N	Relative Density	No. of Blows, N	Consistency	
0 - 4 5 - 10 11 - 30 31 - 50 Over 50	Very Loose Loose Medium Dense Dense Very Dense	0 - 2 3 - 4 5 - 8 9 - 15 16 - 30 31 - 50 Over 50	Very Soft Soft Firm Stiff Very Stiff Hard Very Hard	

Particle Size Identification (Unified Classification System)

Boulders:

Diameter exceeds 8 inches

Cobbles: Gravel:

3 to 8 inches diameter

Coarse - 3/4 to 3 inches in diameter Fine - 4.76 mm to 3/4 inch in diameter

Sand:

Coarse - 2.0 mm to 4.76 mm in diameter Medium - 0.42 mm to 2.0 mm in diameter

Fine - 0.074 mm to 0.42 mm in diameter

Modifiers

These modifiers provide our estimate of the amount of fines (silt or clay size particles) in soil samples.

Approximate Fines Content

Modifiers

5% Fines 12%

Slightly silty or slightly clayey

12% Fines 30%

Silty or clayey

30% Fines 50%

Very silty or very clayey

These modifiers provide our estimate of shell, rock fragments, or roots in the soil sample.

Approximate Content, By Weight

Modifiers

1% to 5%

Trace

5% to 12%

Few

12% to 30%

Some

30% to 50%

Many

These modifiers provide our estimate of organic content in the soil sample.

Organic Content

Modifiers

1% to 3%

Trace

3% to 5%

Slightly Organic

5% to 30%

Organic

30%

Peat

FIELD AND LABORATORY TEST PROCEDURES

FIELD TEST PROCEDURES:

Standard Penetration Test (SPT) Borings - The Standard Penetration Test (SPT) borings were made in general accordance with ASTM D-1586, "Penetration Test and Split-Barrel Sampling of Soils". A rotary drilling process was used to drill the test boreholes. Bentonite drilling fluid was circulated in the boreholes to stabilize the sides and flush the cuttings. At regular intervals, the drilling tools were removed and soil samples were obtained with a standard 1.4-inch I.D., 2.0-inch O.D., split tube sampler. The sampler was first seated six inches and then driven an additional foot with blows of a 140 pound hammer (manual rope-cathead system) falling 30 inches. The number of hammer blows required to drive the sampler the final foot is designated the "Penetration Resistance". The penetration resistance, when properly interpreted, is an index to the soil strength and density. Representative portions of the soil samples, obtained from the sampler, were placed in glass jars and transported to our laboratory. The samples were then examined by an engineer in order to confirm the field classifications.


LABORATORY TEST PROCEDURES:

<u>Percent Organic Content</u> - This test is based on the percent of organics by weight of the total sample. This test was conducted in accordance with FM I - T 267.

<u>Percent Fine Content</u> - To determine the percentage of soils finer than No. 200 sieve, the dried samples were washed over a 200 mesh sieve. The material retained on the sieve was oven dried and then weighed and compared with the unwashed dry weight in order to determine the weight of the fines. The percentage of fines in the soil sample was then determined as the percent of weight of fines in the sample to the weight of the unwashed sample. This test was conducted in accordance with ASTM D 1140.

<u>Natural Moisture Content</u> - The water content is the ratio, expressed as a percentage, of the weight of water in a given mass of soil to the weight of the solid particles. This test was conducted in the general accordance with FM 1-T 265.

Plasticity (Atterberg Limits) - The soil's Plastic Index (PI) is bracketed by the Liquid Limit (LL) and Plastic Limit (PL). The LL is the moisture content at which the soil flows as a heavy viscous fluid and is determined in general accordance with FM 1-T 089. The PL is the moisture content at which the soil begins to crumble when rolled into a small thread and is also determined in general accordance with FM 1-T 090. The water-plasticity ratio is computed from the above test data. This ratio is an expression comparing the relative natural state of soil with its liquid and plastic consolidation characteristics.





January 23, 2009

27/53

Mr. Wayne Russ Columbia County Building Dept. 135 NE Hernando Ave. Lake City, FL 32055

RE: Our Redeemer Lutheran Church Lake City, FL MBI Job #131-0732

Dear Mr. Russ;

I am writing to advise that, on January 19, 2009, I was at the building site and inspected the construction of all 4 of the in-ground canopy footings.

I found that the construction was in accordance to or exceeded the requirements of my design dated 06-12-08.

I trust that your receipt of this report will permit the issuance of the Certificate of Occupancy without delay.

Thank you,

Yours truly,

Allied Design A & E Group, P.C.

Ronald L. Sutton, P.E.

President

NO. 34487

STATE OF

ORIOP.

100 S. Pershing

P.O. Box 110

Morton, IL 61550

309.263.4105

Columbia County Building Permit Application

Columbia Country Bullating 1 crimit Applica	
For Office Use Only Application # 0866 43 Date Received 623 108	1 -
Zoning Official Date Date Flood Zone Land Use	
FEMA Map #NA ElevationNA MFE 76.5 St River Plan	
Comments Devotes Continu	han letter tegund
NOC VEH ✓ Deed or PA ✓ Site Plan ✓ State Road Info ☐ Parent Parcel	I #
☐ Dev Permit # ☐ In Floodway ☐ Letter of Authorization from Co	
IMPACT FEES: EMS 41,296,00 Fire 2,268,00 Corr N/A	Road/Code 43,337.29560
School = TOTAL (90/20)	
Septic Permit No. 08-0455-M	Fax 352-271-0470
Name Authorized Person Signing Permit Ashley Poulos	Phone 352-271-0980
Address 1901k NW 67 th Place Gainesville, FL 32653	
Owners Name Our Redeemer Lutheran Church	Phone 800-653-0386
	3.0000000000000000000000000000000000000
911 Address 5056 SW SR 47 Lake City, FL 32024	
Contractors Name Morton Buildings	Phone 352-271-0980
Address 1901K NW 67 th Place, Gainesville, FI 32653	
Fee Simple Owner Name & Address	· · · · · · · · · · · · · · · · · · ·
Bonding Co. Name & Address	"1
Architect/Engineer Name & Address Ronald L Sutton 100 S Pershing PO Box	110, Morton IL 61550
Mortgage Lenders Name & Address n/a	
Circle the correct power company – FL Power & Light – Clay Elec. – Suwannee V	alley Elec. – Progressive Energy
Property ID Number 36-4S-16-03300-010 Estimated Cost of Cons	struction \$172,854
Subdivision Name Lot Bloc	:k <u>-</u> Unit <u>- Phase -</u>
Driving Directions I-75 to exit 432 (SR 47) I mile south on right	
	,
Number of Existing Dwe	llings on Property 2
Construction of Shell of new church Total Acreage	11.76 Lot Size
Do you need a - <u>Culvert Permit</u> or <u>Culvert Waiver</u> or <u>Have an Existing Drive</u>	Total Building Height 26.31'
Actual Distance of Structure from Property Lines - Front 225 Side	200 Side 200 Rear 700
Number of Stories 1 Heated Floor Area 6480 Total Floor Area	6480 Roof Pitch 4/12
Application is hereby made to obtain a permit to do work and installations as indinstallation has commenced prior to the issuance of a permit and that all work be of all laws regulating construction in this jurisdiction.	

- JW evilet 25they - 7.2.08 \$ 97117 \$2000

Columbia County Building Permit Application

TIME LIMITATIONS OF APPLICATION: An application for permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment

According to Florida Law, those who work on your property or provide materials, and are not paid –in- full, have a right to enforce their claim for payment against your property. This claim in known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look at your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

NOTICE OF RESPONSIBILITY TO BUIDING PERMITEE:

YOU ARE HEREBY NOTIFIED as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that in ponding of water, or other damage to roadway and other public infrastructure facilities caused by your or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCMENT MAY RESULT IN YOU PAYINGTWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECITON. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT

OWNERS CERTIFICATION: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning. I further understand the above written responsibilities in Columbia county for obtaining the Building Permit.

Owners Signature

<u>CONTRACTORS AFFIDAVIT:</u> By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit.

Karal & Julto	Contractors License Number
Contractor's Signature (Permitee)	Columbia
County	
Competency Card Number	

Affirmed under penalty or perjury to by the Contractor and subscribed before me this 18th day of 3une 20 08.

Personally known___X__ or Produced Identification_____

State of Florida Notary Signature (For the Contractor)

Иinois

Page 2 of 2 (Both Pages must be submitted together.)

OFFICIAL SEAL
CATHEY I EDWARDS
NOTARY PUBLIC - STATE OF ILLINOIS
MY COMMISSION EXPIRES 042010

Revised 1-10-08

STATE OF FLORIDA DEPARTMENT OF HEALTH

APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Permit Application Number 08-6455-M ----- PART II - SITEPLAN ------9∂0 Scale: 1 inch = \$0 feet.

Site Plan submitted by:

Plan Approved_

Notes:

Not Approved___

MASTER CONTRACTOR

Date 7-9-08

County Health Department


ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT

Columbia County Building Department 135 NE Hernando Ave. Lake City, FL 32055

Limited Power of Attorney

I, Ronald L. Sutton , hereby appoint Ashley Poulos/ Paul Forrestel ,	
(contractor name) (appointee name)	
to be my lawful attorney-in-fact to act for me and apply to the Columbia County Buildi	ng
Department for a permit to perform construction, at a location described as:	
Section 36 Township 4S Range 16	_
Lot Block Subdivision	
Job Address: 5056 SW State Rd 47, Lake City, FL 32024	**
Job Description: Shell for church	_
Property Owner: Our Redeemer Lutheran Church	_
and to sign my name, and do all things necessary to this appointment.	
Contractor: Ronald L. Sutton dba Morton Buildings, Inc.	
printed name	
Signature: Roral Lotto Date: 06.12.08	
contractor signature	
Contractor License #: CBC036362	
State of Illinois)	
County of <u>Tazewell</u>) Sworn to and subscribed before me this <u>12th</u> day of <u>June</u> , 20 <u>08</u>	
by Ronald L Sutton (name of person acknowledge	
who is personally known to me or who has produced (personally known)	-,
(identification).	
Cachest J. Edwards	
Notary Pyblic	
Commission expires: 4/20/2010	
OFFICIAL SEAL	

(seal)



STATE OF FLORIDA DEPARTMENT OF HEALTH

APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Permit Application Number_____

	PART II - SI	TEPLAN
ි Scale: 1 inch = 5 0 fc	eet.	TO BE REMOVED
	1112	
si sas	SZOPR	187 210 CHURUNDANDE
Sul	(610)	6480
	North	260
ļ	חחק'	Ditt
Notes:		

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT

Not Approved

Site Plan submitted by:

Plan Approved

By_____

MASTER CONTRACTOR

County Health Department

Date

NOTICE OF COMMENCEMENT		56 Date:6/23/2008 Time:1:20 PM Witt Cason,Columbia County Page 1 of 1 B:1153 P:82
Tax Parcel ID Number 36-4S-16-03300-010 02		
THE UNDERSIGNED hereby gives notice that improvement will be made to with Chapter 713, Florida Statutes, the following information is provided in t	mis NOTICE OF CC	SWINE RELIVERY
1 Description of property: (legal description): SR-47, SW ALONG RW 668.9	2 FT, W W 779.24 FT,	9 FT FOR POB, RUN E 1112 FT TO W R/W N 541.61 FT TO POB. ORB 557-196, 591-384
a) Street (job) Address: 5056 SW State Road 47, Lake Cit	y, FL 32024	
2. General description of improvement: Construct shell of church		
3. Owner Information		
a) Name and address: Our Redeemer Lutheran Church		5056 SW SR 47, Lake City, FL 32024
b) Name & Address of Fee Simple Owner (if other than owner): c)Interest in Property 100%	N/A	
4 Contractor Information		the state of the s
a) Name and Address: Morton Buildings, Inc.		1901K NW 67 th Place, Gainesville, FL
b) Telephone No.: 352-271-0980	Fax No. (Opt.)	352-271-0470
5. Surety Information		STATE OF FLORIDA, COUNTY OF COLUMBI
그리 시간에 가지를 가는 그는 그림, 그 사람들이 그리고 있다.	Fax No. (Opt.)	n/dHEREBY CERTIFY, that the above and foregoing
a) Name and Address n/a b) Amount of Bond n/a		is a true copy of the original filed in this office.
c) Telephone No. n/a	Fax No. (Opt.)	n/a Margu Fleagle
	The state of the s	Deputy Clérk
6. Lender		Date 06-23-2008
a) Name and Address n/a	Fax No. (Opt.)	n/a
b) Telephone No.: n/a		
7. Identity of person with in the State of Florida designated by owner upon	whom notice or other	er documents may be set received
a) Name and Address Paul Fortestel of Matthew Ross	Fax No. (Opt.)	
b) Telephone No.: 352-271-0980		
8. In addition to himself, owner designates the following person to receive a	copy of the Lienor's I	Notice as provided in second 113.13(1)(0)
Florida Statutes:		Manage Ma
a) Name and Address	Fax No. (Opt.)	
b) Telephone No.:		
 Expiration date of Notice of Commencement (the expiration date is or specified): 		
THE OWNER	AFTER THE EXP	IRATION OF THE NOTICE OF
COMMENCEMENT MUST BE RECORDED AND POSTED ON THE J INTEND TO OBTAIN FINANCING, CONSTULT YOUR LENDER OR	OB SITE BEFORE	REFORE COMMENCING WORK OR
INTEND TO OBTAIN FINANCING, CONSTULT TOUR LENDER OF	ANATIORNET	LI ORE CO
RECORDING YOUR NOTICE OF COMMENCEMENT.	1100110	. 111
STATE OF FLORIDA	Lelles Heall	L VP
COUNTY OF COLUMBIA	e of Owner or Owner's	Authorized Office/Director/Partner/Manager
Ri	ck D. Hacht	
Print N	ame	
The foregoing instrument was acknowledged before me, a Florida Notary, this 20	th day of Ju	ne ,20_08 ,by:
Rick D. Hacht as Vice Preside	nt (type of aut	hority, e.g. officer, trustee, attorney fact) for
Our Podeemer Lutheran Church (name)	of party on behalf of wh	nom instrument was executed).
Personally Known X OR Produced Identification Type	SH Co	EILA D. MORHISON mmission DD 672541 pires June 2, 2011
Notary Stamp or Seal:	EX EX	pires June 2, 2011

II. Verification pursuant to Section 92.525, Florida Statutes, Under penalties of perjury, I declare that I have read the foregoing and that the facts stated in it are true to the best of my knowledge and belief.

Signature of Natural Person Signing (in line # 10 above)

executive line

relude all genders and singular or plural as the context indicates.)

Prepared by and return to: 4 1 REGIONAL TITLE COMPANY 2015 South First Street P.O. Box 1672 Lake City, Florida 32056 Martha J. Tedder by:___

0 0	-
-17	CI
5	9
7	
19 77 .	Between
13 286	Chron
1.00	0
C	w
0	
70	00
0	
S	, grantor, and
	, Branton, and

J. Michael Tillotson and Sandra H. Tillotson, his wife of the County of Columbia

Made this

, State of The.

Our Redemmer Lutheran Church of Lake City, Florida, Inc., a corporation existing under the laws of the State of Florida

day of

whose post-office address is Pt 10, Box 208, Lake City, Fl. 32055. of the Country of Columbia, State of Fln. of the County of Columbia

6th

.grantee,

Bitnesseth: That said grantor, for and in consideration of the sum of TEN AND NO/100 Dollars, and other good and valuable considerations to said grantor in hand paid by said grantee, the receipt whereof is hereby acknowledged, has granted, bargained and sold to the said grantee, and grantee's heirs, successors and assigns forever, the following described land, situate, lying and being in COLUMBIA

Township 4 South - Range 16 East

Section 36: Commence at the Northeast corner of the NW 1/4 of Section 36, Township 4 South, Range 16 East, Columbia County, Florida and run S 87°55'41'' W along the North line of said NW 1/4 a distance of 300.00 feet; thence S 04°'26'55'' W, 762.59 feet to the POINT OF BEGINNING; thence N∞ 87°55'41'' E, 1112.00 feet to a point on the Westerly right of way line State Road No. 47; thence S 34°02'33'' W along said Westerly right of way line 668.92 feet to its intersection with the South line of the NW 1/470f the NE 1/4 of said Section 36; thence S 88°11'58' W along the South line of said NW 1/4 a distance of 479.24 feet to the Southwest corner of said NW 1/4 of the NE 1/4; thence S 87°55'41' W, 300.00 feet; thence N 04°26'55' E, 541.61 feet to the POINT OF BEGINNING. Said lands lying partly in the NW 1/4 and partly in the NE 1/4 of said Souther 26 1/4 and partly in the NE 1/4 of said Section 36.

> DOCUMENTARY STAMP INTANGIBLE TAX MARY B. CHILDS, CLERK OF COURTS, COLUMBIA COUNTY

and said grantor does hereby fully warrant the title to said land, and will defend the same nearing the latiful claims of all persons whomsoever.

Grantor has hereunto set grantor's hand and seal the day and year first above written. In Witness Whereof, Signed, sealed and delivered in our presence:

witness

(Seal)

witness

(Seal)

witness

Florida STATE OF

COUNTY OF Columbia

I HEREBY CERTIFY that on this day before me, an officer duly qualified to take acknowledgments, personally appeared

J. Michael Tillotson and Sandra H. Tillotson, his wife

to me known to be the person(s) described in and who executed the foregoing instrument and acknowledged before me WITNESS my hand and official seal in the County and State last aforesaid this 6 day of May, 1986.

Notary Public My commission expires: Aug. 10, 1987 . Notary Public

MIDSTATE LEGAL SUPPLY CO., INC. - ORLANDO, FLORIDA



LOUIS SHIVER Chairman Mayo, Florida

J.P. MAULTSBY Vice Chairman Madison, Florida

GEORGIA JONES Secretary/Treasurer Lake City, Florida

KELBY ANDREWS Chiefland, Florida

DON CURTIS Lake Bird, Florida

C. LINDEN DAVIDSON Lamont, Florida

N. DAVID FLAGG Gainesville, Florida

OLIVER J. LAKE Lake City, Florida

SYLVIA J. TATUM Lawtey, Florida

DAVID STILL Executive Director Lake City, Florida

SUWANNEE RIVER WATER MANAGEMENT DISTRICT

May 8, 2008

Mrs. Ashley Poulos Morton Buildings, Inc. 1901 NW 67th Place, Suite K Gainesville, FL 32653-1657

Subject: Requested Environmental Resource Permit (ERP) Exemption for ERP87-0004M, Our Redeemer Lutheran Church, Columbia County

Dear Mrs. Poulos:

The above mentioned proposed project of constructing a building and parking lot does not require a new ERP or a modification to the existing permit, 4-87-00004, by the Suwannee River Water Management District (District).

This decision was based on the existing permit and the letter and plans received on April 30, 2008, for this project. It has been determined that the proposed project follows subsection 40B-4.1070(1)(c) and 40B-4.1070(1)(f), Florida Administrative Code (F.A.C.), and provides reasonable assurance that:

- The existing stormwater system was designed for connections.
- 2. The existing stormwater system is functioning as permitted.
- 3. The master system will not change as a result of the connection.
- 4. The project will not exceed any thresholds established by the existing permit.

If this project does not comply with these terms, a permit will be required.

This exemption, however, does not exempt you from obtaining permits from any other regulatory agency. Any modification to the exempted plans that may be required shall require reconsideration by the District prior to commencement of construction.

If you have any questions, please call me at 386.362.1001, or toll free at 800.226.1066.

Sincerely,

Clay Coarsey

Resource Management Department

CC/rl

Water for Nature, Water for People

0806-43



Columbia County BUILDING DEPARTMENT

MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR THE FLORIDA BUILDING CODE, FLORIDA PLUMBING CODE, FLORIDA MECHINICAL CODE, FLORIDA FUEL AND GAS CODE 2004 with Supplements and Revision, NATIONAL ELECTRICAL 2005

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

COMMERCIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST

ALL BUILDING PLANS MUST INDICATE COMPLIANCE WITH THE CURRENT FLORIDA BUILDING CODES. ALL PLANS OR DRAWING SHALL PROVIDED CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION.

FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER FBC FIGURE 1609 STATE OF FLORIDA WIND-BORNE DEBRIS REGION & BASIC WIND SPEED MAP

	GENERAT: REQUIREMENTS AND THE SECOND OF THE	Item Each Each C	isolitic Bay da Iroled aplicab	nde åll:be s: le:
1	All drawings must be clear, concise and drawn to scale, details that are not used shall be marked void.	YES	NO	N/A
2	If the design professional is an architect or engineer legally registered under the laws of this state regulating the practice of architecture as provided for in Chapter 481, Florida Statutes, Part I, or engineering as provided for in Chapter 471, Florida Statutes, then he or she shall affix his or her official seal to said drawings, specifications and accompanying data, as required by Florida Statute.	(VE)	NO	N/A
3	The design professional signature shall be affixed to the plans	(YES)	NO	N/A
4	Two (2) complete sets of plans with the architecture or engineer signature and the date the affix embossed official seal was placed on the plans	YES	NO	N/A

Two (2) complete sets of plans containing the following information:

4	Building Site Plan Requirements 2.1	Each C	Box-si ircled oplical	ile
5	Fire access, showing all drive way which will be accessible for emergency vehicles	(Yes	No	N/A
_		Yes	No	NA
7	Driving/turning radius of parking lots	Yes	No	(N/A)
	Vehicle loading include truck dock loading or rail site loading	Yes	No	(N/A)
8	Nearest or number of onsite Fire hydrant/water supply/post indicator valve (PIV)	Yes	(No)	N/A
9	Set back of all existing or proposed structures from each structure and property boundaries, Show all separation including assumed property lines	(YES)	No	N/A
10	Location of specific tanks(above or under grown ,water lines and sewer lines and septic tank and drain fields	(Cs)	No	N/A
11	All structures exterior views include finished floor elevation	(Yes)	No	N/A
12	Total height of structure(s) form established grade	(res)	No	N/A
1124321	Occupancy: Group Group Group Group Group Group Group	Grou		roup
	B E F H I M R		ľ	D
	建设设施设施	10000		
13	Special occupancy requirements.	Yes	(No)	N/A
14	Incidental use areas (total square footage for each room of use area)	(Yes	No	N/A
15	Mixed occupancies	Yes	No	(A)
16	REQUIRED SEPARATION OF OCCUPANCIES IN HOURS FBC TABLE 302.3.2	Yes	No	W. C.
	Minihum type of permitted construction by code for occupancy use circle the construction			LV/ P
17		n type r	C2012	(Bishallace
17	Type I Type II Type III Type IV Type V		的社主的相引	Mark Charles
(Hitaesay		Promise systematical	Median May	mpas deservi.
18	Fire-resistant construction requirements shall be shown, include the following compo		(6.)	
19	Fire-resistant separations Fire-resistant protection for type of construction	Yes	(Na)	N/A N/A
20	Protection of openings and penetrations of rated walls	AND THE RESERVE THE PARTY OF TH	No Ow	N/A
21	Protection of openings and penetrations of rated walls	Yes	(N)	N/A
22		Yes	(No)	
	Fire blocking and draftstopping and calculated fire resistance Fireshippressionsystems shall belshown include:	Yes	1/140	N/A
	institute manatalassa assassa areas appression system sanate pelsnown ancida established		(2)	NO.
23	Early warning smoke evacuation systems Schematic fire sprinklers Standpipes	Yes	1	N/A
24	Standpipes Pre-engineered systems	Ves Ces	(NO)	N/A N/A
26	Riser diagram	WW.	(No	N/A
	Riser diagram Clife's afety systems Shall be shown include the following requirements:	Marie America	HARMITT GALLS	N/A BENEFICIAL
		(Yes)	No.	1
27	Occupant load and egress capacities Early warning	Yes	No	N/A N/A
	···	Yes	(No)	N/A N/A
29	Smoke control		-	
30	Stair pressurization Stair pressurization	Yes	No	N/A
31	Systems schematic	I CS	NO.	DATE OF THE PARTY
	Occupancy load/egress requirements shall be shown include: # # ###	V	(NI/A
32	Occupancy load	Yes	(3)	N/A
33	Gross occupancy load Net occupancy load	Yes	(Ng	N/A N/A
34		Yes	No	N/A
35	Means of egress	(CS)	No	N/A
36	Exit access			N/A N/A
37	Exit discharge	(Yes)	No	(N/A)
38	Stairs construction/geometry and protection	Yes	No	
39	Doors	(Ves	No	N/A
40	Emergency lighting and exit signs	(Yes)	No	N/A
41	Specific occupancy requirements	205	No	N/A
42	Construction requirements	(es)	No	NA)
43	Horizontal exits/exit passageways	Yes	No	(N/A)

44	Soil conditions/analysis	VES No	N/A
45	Termite protection	(Ces No	N/A
46	Design loads	Ces No	N/A
47	Wind requirements		N/A
48	Building envelope		N/A
49	Structural calculations (if required)		N/A
50	Foundation	No No	SIN
51	Wall systems		N/A
52	Floor systems		N/A
53	Roof systems		N/A
54	Threshold inspection plan		N/A
55	Stair systems		N/A)
, 可以被计算、适宜	Materials shall be shown include the followin		a service of
56	Wood		N/A
57	Steel		N/A
58	Aluminum		N/A
59	Concrete		N/A
60	Plastic		N/A
61	Glass		N/A
62	Masonry		N/A
63	Gypsum board and plaster	Yes (No)	N/A
64	Insulating (mechanical)		N/A
65	Roofing		N/A
66	Insulation		N/A
	Accessibility requirements shall be shown include the	following to the state of the s	orkanie.
67	Site requirements	A CONTRACT OF THE PARTY OF THE	N/A
68	Accessible route		N/A
69	Vertical accessibility	(es No	N/A
70	Toilet and bathing facilities	(Yes) No	N/A
71	Drinking fountains		N/A
72	Equipment		N/A-
73	Special occupancy requirements		N/A
74	Fair housing requirements		N/A
	literior requiesments shall anclude the following		Company (19)
75	Interior finishes (flame spread/smoke development)		NIA
76	Light and ventilation		QUA
77	Sanitation	Yes No	WA.
			EN SES
78	Elevators		NIA
79	Escalators		NIA
80	Lifts		WA
HERMINS		CARLLEGARING CONTRACTOR OF THE CALL	
81	Barrier requirements		N/A
82	Spas	Yes No	NA
83	Wading pools	Yes No	N/A

84	AND	Server for Sent take 2 to 1	a coverdantellar	
84		Biologia San Sales		
	Wiring	Yes	No	(N/A)
85	Services	Yes	No	NIA
86	Feeders and branch circuits	Yes	No	(N/A)
87	Overcurrent protection	Yes	No	(VA)
88	Grounding	Yes	No	(N/A)
89	Wiring methods and materials	Yes	No	(NA)
90	GFCls	Yes	No	NIA
91	Equipment	Yes	No	(N/A)
92	Special occupancies	Yes	No	QUAN
93	Emergency systems	Yes	No	(V/A)
94	Communication systems	Yes	No	SVA
95	Low voltage	Yes	No	(N/A)
96	Load calculations	Yes	No	(N/A)
化 域域	and the state of the	er er sik	n differ	Handle State
97	Minimum plumbing facilities	(ES)	No	N/A
98	Fixture requirements	Tes	No	N/A
99	Water supply piping	Yes	No	N/A
100	Sanitary drainage	Yes	No	(N/A)
101	Water heaters	Yes	No	(N/A)
102	Vents	Yes	No	(99)
103	Roof drainage	Yes	No	NA
104	Back flow prevention	Yes	No	(N/A)
105	Irrigation	Yes	No	IVA
106	Location of water supply line	Ycs	No	(N/A)
107	Grease traps	Yes	No	(N/A)
108	Environmental requirements	Yes	No	(N/A)
109	Plumbing riser	Yes	No	(N/A)
	ing and the second of the seco		13161	
110	Energy calculations	Yes	No	WA
111	Exhaust systems	Yes	No	(N/A)
112	Clothes dryer exhaust	Yes	No	SVA
113	Kitchen equipment exhaust	Yes	No	QUA
114	Specialty exhaust systems	Yes	No	(N/A)
SHAR	Specially exhaust systems		796	
115	Make-up air	Yes	No	(N/A)
116	Roof-mounted equipment	Yes	No	(N/A)
117	Duct systems	Yes	No	(N/A)
	Ventilation	Yes	No	NA
	Laboratory	Yes	No /	NA
120	Combustion air	Yes	No	(N/A)
121	Chimneys, fireplaces and vents	Yes	No	N/A
122	Appliances	Yes	No	(N/A)
123	Boilers	Yes	No	QUA
AMU	Refrigeration	Yes	No (WW
124	Watermention			

0806-43

FAX MEMORANDUM

MEMORANDUM

FLORIDA DEPARTMENT OF TRANSPORTATION

To: Mr. John Kerce, Dept. Director Columbia Co. Building & Zoning Dept.

Fax No: 386-758-2160

From: Dale L. Cray, FDOT Permits Insp. Date: 4-30-2008 Fax No. 386-961-7183

Attention: Col Co. Building Zoning Dept.

() Sign and return. () For your files. () Please call me. (XX) FYI () For Review

REF: Existing Comm. D/W / Inspected On:4-29-2008

PROJECT: Our Redeemer Lutheran Church

PARCEL ID No: N/A Permit No: N/A Sec No: 29020

MILE POST:N/A+-

Mr. Kerce:

Please accept this as our legal notice of final passing inspection for (OUR REDEEMER LUTHERAN CHURCH / PAUL FORREST) for a Existing Comm. Driveway. The project is located, 5056 SW SR. 47 Lake City. Fl.32024

The Existing Comm. Access has been inspected and (Approved) and, meets FDOT Standard Requirements.

If further information is required on this project please do not hesitate to contact this office for additional access permitting information details. My office number is 961-7193 or 961-7146.

Sincerely,

Dale L. Cray

Dr 2 20

Access Permits Inspector

Professional Surveying and Mapping

P.O. Box 1501 Lake City, Florida 32056

September 21, 2008

Our Redeemer Lutheran Church 5056 SW SR 47 Lake City, FL 32024

Subject: Elevation Letter

Dear Sir:

Daniel & Gore, LLC has performed a vertical survey from a FDOT TBM (ID # 2902007 – TBM 50) with an elevation of 85.102 feet (NGVD 1929 - Datum) to a TBM (60d nail in the North side of an 18" oak tree approximately 150 feet Southeast of the SE corner of the new building) on the Church property (Tax parcel # 03300-010). D&G, LLC hereby submits the following data:

- The elevation of said TBM is 92.24 feet.
- The elevation of the centerline of the adjacent SR 47 is 89.01 feet.
- The elevation of the proposed finish floor is 97.62 feet, being 8.61 feet above said adjacent SR 47.

Please feel free to contact me if you have any questions.

Sincerely,

Scott Daniel, PSM



PRODUCT APPROVAL SPECIFICATION SHEET

Location:	Project Name: DUE REDEEMEK LUTHEKAN CHURU
	2 and Florida Administrative Code 9B-72, please provide the information and the
product approval number(s) on the bu	ilding components listed below if they will be utilized on the construction project for
	g permit on or after April 1, 2004. We recommend you contact your local product
supplier should you not know the proc	duct approval number for any of the applicable listed products. More information
about statewide product approval can	he obtained at

Category/Subcategory	IV	lanufacturer	Product Description	Approval Number(s)
A. EXTERIOR DOORS				
Swinging	M	DETON BULDINGS	FIBELSTEEL FLAT SLAB MUSTER ECLINETE	FL 3073-121
2. Sliding		IA .		
3. Sectional	N	la .		
4. Roll up		1A		
5. Automatic		/IA		
6. Other		la		
B. WINDOWS		The state of the s		
Single hung	1	NA		
Horizontal Slider	N	100		
3. Casement	Pt	ILA	PCC2559 CUAD FIXED CASEMENT NINDOW	FL 3137.1
4. Double Hung	A	IA	I STATE OF THE STA	300,01
5. Fixed	N	A		
6. Awning		A		
7. Pass -through		IA		
8. Projected	Λ	1/100		
9. Mullion	N	I/A		
10. Wind Breaker	N			
11 Dual Action	N	70		
12. Other		uA	CIECLETOP WINSVLATING GLASS	FL 2307.2
C. PANEL WALL	T			
1. Siding	Mo	PRON BANDINGS	PIBBED METALSTRUTURAL WALLPANELS	FL 3072-R-1
2. Soffits	NI	A	P. C. C. M. C. M. C. C. M. C. M. C. M. C. M. C. C. M.	16.012
3. EIFS	NI			
4. Storefronts	NI			
5. Curtain walls	NI			
6. Wall louver	N	A		
7. Glass block	Ň	À		
8. Membrane	N			
9. Greenhouse	M	À		
10. Other	W	À	The state of the s	
D. ROOFING PRODUCTS	T			
Asphalt Shingles	VI V	A		
2. Underlayments	1	A		
Roofing Fasteners	Ň	A		
4. Non-structural Metal Rf			PIBLED . 020" STEEL ROOFPANELS	FL : 14250
5. Built-Up Roofing	Mi	X	A THE THE PARTY OF	
Modified Bitumen	M	A ·		
7. Single Ply Roofing Sys	M	A		
8. Roofing Tiles	N	A		
Roofing Insulation	N	A		
10. Waterproofing	N	À		
11. Wood shingles /shakes	N	IA		
The second secon				


Category/Subcategory (cont.)	Manufacturer	Product Description	Approval Number(s)
13. Liquid Applied Roof Sys	NIA	•	
14. Cements-Adhesives – Coatings	NA.		
15. Roof Tile Adhesive	NIA		
16. Spray Applied	/V/P		
Polyurethane Roof	NA		
17. Other			
E. SHUTTERS			
Accordion	NIA		
2. Bahama	NIA		
3. Storm Panels	NIA		
4. Colonial	NIA		•
5. Roll-up	NIA		
6. Equipment	NIA		
7. Others	NIA		
F. SKYLIGHTS			
1. Skylight	NIA		
2. Other	NIA		
G. STRUCTURAL	l Marian		
COMPONENTS			
Wood connector/anchor	ALLA		
	NIA		
Engineered lumber	NA		
4. Railing	NIA		
5. Coolers-freezers	NIA		
Concrete Admixtures	NA		
7. Material	NIA		
8. Insulation Forms	NIA		
9. Plastics	NIA		
10. Deck-Roof	NIA		
11. Wall	/V'IV)-		
12. Sheds	NIA		*
13. Other	NIA		
H. NEW EXTERIOR			
ENVELOPE PRODUCTS			
1.			
2.			-
The products listed below did time of inspection of these probsite; 1) copy of the production of the production comply with, 2	roducts, the follo ct approval, 2) th 3) copy of the ap	te product approval at plan review. wing information must be available e performance characteristics whice policable manufacturers installation	to the inspector on the ch the product was tested requirements.
understand these products	may nave to be	removed if approval cannot be dem	ionstrated during inspection
armus fonlos		ASHITEN FOLLOS	11/2/100
Contractor or Contractor's Authorized	Agent Signature	Print Name	Date
Location		Permit # (FOR STAF)	F USE ONLY)

02/02/04 - 2 of 2

A.V

Website:

Effective April 1, 2004



From: The Columbia County Building & Zoning Department Plan Review 135 NE Hernando Av.

P.O. Box 1529

Lake City Florida 32056-1529

Reference to a building permit application Number: 0806-43

Applicant: Ashley Poulos

Owner: Our Redeemer Lutheran Church

Contractor: Morton Builders

Property Identification # 34-4s-16-03300-010

On the date of June 25, 2008 building permit application number 0806-43 and the submitted plans for constructing a structure intended for worship were review. Chapter 3 of the Florida Building Codes classifies this structure as a group three assembly use.

The following information or alteration to the plans will be required to continue processing this application. If you should have any question please contact the above address, or contact phone number (386) 758-1163 or fax any information to (386) 754-7088.

Please refer and complete the attached Columbia County Building & Zoning Department Commercial Check List.

The submitted plans show the structural design requirement for exterior and interior walls and roof truss system of the structure only.

Addition design drawing will need to be submitted, showing the interior design for electrical, plumbing, mechanical air handling equipment, Florida energy code compliance, life safety devices, egress hardware, elevated pulpit framing information, steeple design with windload attachment information.

Please include application number 0805-01 and when making reference to this application.



Columbia County BUILDING DEPARTMENT

MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR THE FLORIDA BUILDING CODE, FLORIDA PLUMBING CODE, FLORIDA MECHINICAL CODE, FLORIDA FUEL AND GAS CODE 2004 with Supplements and Revision, NATIONAL ELECTRICAL 2005

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

COMMERCIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST

ALL BUILDING PLANS MUST INDICATE COMPLIANCE WITH THE CURRENT FLORIDA BUILDING CODES. ALL PLANS OR DRAWING SHALL PROVIDED CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION.

FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER FBC FIGURE 1609 STATE OF FLORIDA WIND-BORNE DEBRIS REGION & BASIC WIND SPEED MAP

	GENERAL REQUIREMENTS:			
1	All drawings must be clear, concise and drawn to scale, details that are not used shall be marked void.	YES	NO	N/A
2	If the design professional is an architect or engineer legally registered under the laws of this state regulating the practice of architecture as provided for in Chapter 481, Florida Statutes, Part I, or engineering as provided for in Chapter 471, Florida Statutes, then he or she shall affix his or her official seal to said drawings, specifications and accompanying data, as required by Florida Statute.	YES	NO	N/A
3	The design professional signature shall be affixed to the plans	YES	NO	N/A
4	Two (2) complete sets of plans with the architecture or engineer signature and the date the affix embossed official seal was placed on the plans	YES	NO	N/A

Two (2) complete sets of plans containing the following information:

			Buildi	ng Site Pla	an Requir	rements				Each C	Box	nclude- shall be d as able
4	Parking, inc	luding provi	sion FBC cl	napter 11 fo	r the requir	ed accessib	le parking s	site		Yes	No	N/A
5	Fire access,	ire access, showing all drive way which will be accessible for emergency vehicles								Yes	No	N/A
6	Driving/turn	riving/turning radius of parking lots							Yes	No	N/A	
7	Vehicle load	ehicle loading include truck dock loading or rail site loading							Yes	No	N/A	
8	Nearest or n	Nearest or number of onsite Fire hydrant/water supply/post indicator valve (PIV)						Yes	No	N/A		
9	separation in	Set back of all existing or proposed structures from each structure and property boundaries, Show all separation including assumed property lines								Yes	No	N/A
10	Location of drain fields	Location of specific tanks(above or under grown ,water lines and sewer lines and septic tank and						and	Yes	No	N/A	
11	All structure	s exterior vi	ews include	finished fl	oor elevatio	n				Yes	No	N/A
12	Total height	of structure	(s) form esta	ablished gra	ide					Yes	No	N/A
	Occupancy group use circle all uses:	Group A	Group B	Group E	Group F	Group H	Group I	Group M	Group R	Grou S	р	Group U D
13	Spec	cial occupano	cy requirem	ents.						Yes	No	N/A
14	Incie	Incidental use areas (total square footage for each room of use area)							Yes	N	N/A	
15	Mix	Mixed occupancies						Yes	N	N/A		
16	REC	UIRED SEI	PARATION	OF OCCL	PANCIES	IN HOURS	FBC TAE	BLE 302.3.2	W	Yes	N	N/A
Will	Mini	mum type o	of permitted	d construct	ion by cod	e for occup	ancy use c	ircle the co	nstruction	n type F	BC 6	02
17		Type II	Type III	Type IV	Type V							

	Fire-resistant construction requirements shall be shown, include the following comp		12 7 7 7 E	
18	Fire-resistant separations	Yes	No	N/A
19	Fire-resistant protection for type of construction	Yes	No	N/A
20	Protection of openings and penetrations of rated walls	Yes	No	N/A
21	Protection of openings and penetrations of rated walls	Yes	No	N/A
22	Fire blocking and draftstopping and calculated fire resistance	Yes	No	N/A
	Fire suppression systems shall be shown include:			
23	Early warning smoke evacuation systems Schematic fire sprinklers Standpipes	Yes	No	N/A
24	Standpipes	Yes	No	N/A
25	Pre-engineered systems	Yes	No	N/A
26	Riser diagram	Yes	No	N/A
Constitution of	Life safety systems shall be shown include the following requirements:			- Mass
27	Occupant load and egress capacities	Yes	No	N/A
28	Early warning	Yes	No	N/A
29	Smoke control	Yes	No	N/A
30	Stair pressurization	Yes	No	N/A
31	Systems schematic	Yes	No	N/A
VI TO PART SE	Occupancy load/egress requirements shall be shown include:			
32	Occupancy load	Yes	No	N/A
33	Gross occupancy load	Yes	No	N/A
34	Net occupancy load	Yes	No	N/A
35	Means of egress	Yes	No	N/A
36	Exit access	Yes	No	N/A
37	Exit discharge	Yes	No	N/A
38	Stairs construction/geometry and protection	Yes	No	N/A
39	Doors	Yes	No	N/A
40	Emergency lighting and exit signs	Yes	No	N/A
41	Specific occupancy requirements	Yes	No	N/A
42	Construction requirements	Yes	No	N/A
43	Horizontal exits/exit passageways	Yes	No	N/A

Items to Include-Each Box shall be Circled as Applicable

		Appi	icable	Design Color
	Structural requirements shall be shown include:		NAME OF TAXABLE PARTY.	1
44	Soil conditions/analysis	Yes	No	N/A
45	Termite protection	Yes	No	N/A
46	Design loads	Yes	No	N/A
47	Wind requirements	Yes	No	N/A
48	Building envelope	Yes	No	N/A
49	Structural calculations (if required)	Yes	No	N/A
50	Foundation	Yes	No	N/A
51	Wall systems	Yes	No	N/A
52	Floor systems	Yes	No	N/A
53	Roof systems	Yes	No	N/A
54	Threshold inspection plan	Yes	No	N/A
55	Stair systems	Yes	No	N/A
	Materials shall be shown include the following			
56	Wood	Yes	No	N/A
57	Steel	Yes	No	N/A
58	Aluminum	Yes	No	N/A
59	Concrete	Yes	No	N/A
60	Plastic	Yes	No	N/A
61	Glass	Yes	No	N/A
62	Masonry	Yes	No	N/A
63	Gypsum board and plaster	Yes	No	N/A
64	Insulating (mechanical)	Yes	No	N/A
65	Roofing	Yes	No	N/A
66	Insulation	Yes	No	N/A
	Accessibility requirements shall be shown include the fo			
67	Site requirements	Yes	No	N/A
68	Accessible route	Yes	No	N/A
69	Vertical accessibility	Yes	No	N/A
70	Toilet and bathing facilities	Yes	No	N/A
71	Drinking fountains	Yes	No	N/A
72	Equipment	Yes	No	N/A
73	Special occupancy requirements	Yes	No	N/A
74	Fair housing requirements	Yes	No	N/A
	Interior requirements shall include the following			
75	Interior finishes (flame spread/smoke development)	Yes	No	N/A
76	Light and ventilation	Yes	No	N/A
77	Sanitation	Yes	No	N/A
238 E85 T	Special systems	variable of the same of the		
78	Elevators	Yes	No	N/A
79	Escalators	Yes	No	N/A
80	Lifts	Yes	No	N/A
	Swimming pools			
81	Barrier requirements	Yes	No	N/A
82	Spas	Yes	No	N/A
83	Wading pools	Yes	No	N/A

	Items to Include-Each Box shall be Circled as Applicable			NAME OF THE OWNER, OWNE
0.4	Electrical	Yes	No	N/A
84 85	Wiring		No	N/A
86	Services Feeders and branch circuits		No	N/A
0.000			No	N/A
87	Overcurrent protection Grounding		No	N/A
88	Wiring methods and materials	1, 10, 120, 1	No	N/A
89	GFCIs		No	N/A
90	Equipment		No	N/A
91	Special occupancies		No	N/A
			No	N/A
93	Emergency systems		No	N/A
94	Communication systems		No	N/A
95	Low voltage		No	N/A
96	Load calculations	Yes	INO	IN/A
17	Minimum plumbing facilities	Yes	No	N/A
97	Minimum plumbing facilities Fixture requirements		No	N/A
99	Water supply piping		No	N/A
-	Sanitary drainage		No	N/A
100	Water heaters		No	N/A
101	Vents		No	N/A
102	Roof drainage		No	N/A
	Back flow prevention		No	N/A
104	Irrigation		No	N/A
	Location of water supply line		No	N/A
106	Grease traps		No	N/A
107	Environmental requirements		No	N/A
108	Plumbing riser		No	N/A
109	Mechanical	165	INU	INIA
110	Energy calculations	Yes	No	N/A
111	Exhaust systems		No	N/A
12	Clothes dryer exhaust		No	N/A
113	Kitchen equipment exhaust	The state of the s	No	N/A
114	Specialty exhaust systems	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	No	N/A
1.14	Equipment location		140	TVIT
115	Make-up air		No	N/A
116	Roof-mounted equipment		No	N/A
117	Duct systems		No	N/A
18	Ventilation		No	N/A
19			No	N/A
20	Combustion air		No	N/A
21	Chimneys, fireplaces and vents		No	N/A
22	Appliances		No	N/A
	Boilers		No	N/A
123	Refrigeration		No	N/A
124 125	Bathroom ventilation		No	N/A

-3000	Items to Include-Each Box shall be Circled as Applicable Gas	100000	100	
126	Gas piping	Yes	No	N/A
127	Venting	Yes	No	N/A
128	Combustion air	Yes	No	N/A
129	Chimneys and vents	Yes	No	N/A
130	Appliances	Yes	No	N/A
131	Type of gas	Yes	No	N/A
132	Fireplaces	Yes	No	N/A
133	LP tank location	Yes	No	N/A
134	Riser diagram/shutoffs	Yes	No	N/A
	Notice of Commencement		Markey	
135	A recorded (in the Columbia County Clerk Office) notice of commencement is required to be on file with the building department . Before Any Inspections Will Be Done	Yes	No	N/A
	Disclosure Statement for Owner Builders	Yes	No	N/A

	Private Potable Water						
136	Horse power of pump motor	Yes	No	N/A			
137	Capacity of pressure tank	Yes	No	N/A			
138	Cycle stop valve if used	Yes	No	N/A			

THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

139	Building Per Application	A current Building Permit Application form is to be completed and submitted for all construction projects. mit	Yes	No	N/A
140	Parcel Numb	The parcel number (Tax ID number) from the Property Appraiser is required. A copy of property deed is also requested. (386) 758-1084	Yes	No	N/A
141	Environmental Health Permit or Sewer Tap Approval	A copy of an approved Environmental Health (386) 758-1058 waste water disposal permit or an approved City of Lake City(386) 752-2031 sewer tap is required before a building permit can be issued. Toilet facilities shall be provided for construction workers	Yes	No	N/A
142	Driveway Connection	Toilet facilities shall be provided for construction workers If the property does not have an existing access to a public road, then an application for a culvert permit must be made (\$25.00). Culvert installation for commercial, industrial and other uses shall conform to the approved site plan or to the specifications of a registered engineer. Use or joint use of driveways will comply with Florida Department of Transportation specifications. If the project is to be located on an F.D.O.T. maintained road, then an F.D.O.T. access permit is required.		No	N/A
143	Suwannee River Water Management District Approval	All commercial projects must have an SRWMD permit issued or an exemption letter, before a building permit will be issued.	Yes	No	N/A

144	Flood Management	hean established shall meet the requirements of section 8.8 of the		No	N/A
145	Flood Management	A CERTIFIED FINISHED FLOOR ELEVATIONS WILL BE REQUIRED ON ANY PROJECT WHERE THE BASE FLOOD ELEVATION (100 YEAR FLOOD) HAS BEEN ESTABLISHED.	Yes	No	N/A
146	If the project is located in an area where a 911 address has n issued, then application for a 911address must be applied for received through the Columbia County Emergency Manager Office of 911 Addressing Department (386) 758-1125		Yes	No	N/A

Pursuant to Chapter one (administration) section R101.2.1 of the Florida Building Code: Section 105.3.2 **Time limitation of application**. An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

Pursuant to Chapter one (administration) section R101.2.1 of the Florida Building Code: Section 105.4.1 **Permit intent.** A permit issued shall be constructed to be a license to proceed with the work and not as authority to violate, cancel, alter or set aside any of the provisions of the technical codes, nor shall issuance of a permit prevent the building official from thereafter requiring a correction of errors in plans, construction or violations of this code. Every permit issued shall become invalid unless the work authorized by such permit is commenced within six months after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of six months after the time the work is commenced.

Section 105.4.1.1: If work has commenced and the permit is revoked, becomes null and void, or expires because of lack of progress or abandonment, a new permit covering the proposed construction shall be obtained before proceeding with the work.

Section 105.4.1.2: If a new permit is not obtained within 180 days from the date the initial permit became null and void, the building official is authorized to require that any work which has been commenced or completed be removed from the building site. Alternately, a new permit may be issued on application, providing the work in place and required to complete the structure meets all applicable regulations in effect at the time the initial permit became null and void and any regulations which may have become effective between the date of expiration and the date if issuance of the new permit.

Section 105.4.1.3: Work shall be considered to be in active progress when the permit has received an approved inspection within 180 days. This provision shall not be applicable in case of civil commotion or strike or when the building work is halted due directly to judicial injunction, order or similar process.

Section 105.4.1.4: The fee for renewal reissuance and extension of a permit shall be set forth by the administrative authority.

When the submitted application is approved for permitting the applicant will be notified by phone as to the date and time a building permit will be prepared and issued by the Columbia County Building & Zoning Department.



(D-2922) Nuclear

Cal-Tech Testing, Inc.

· Engineering

· Geotechnical

• Environmental Laboratories P.O. Box 1625 - Lake City, FL 32056-1626 - Tel(386)755-3633 - Fax(386)752-5456

Aire

4784 Rosselle St., Jacksonville, FL 32254 • Yel(904)381-8901 • Fax(904)381-8902

2230 Greensboro Hwy • Quincy, FL 32351 • Tel(850)442-3495 • Fax(850)442-4008

27153

JOB NO.: 08-00346-0

DATE TESTED:

7/10/0

DATE REPORTED:

7/11/0

REPORT OF IN-PLACE DENSITY TEST

PROJECT:	Lutheran Church Addition, Columbia County Richardson Site Prep. P() Box 549, Fort White, FL 32038 Richardson Site Prep			
CLIENT:				
GENERAL CONTRACTOR:				
EARTHWORK CONTRACTOR:	Richardson Site Prep			
INSPECTOR:	Chad Day			
ASTM METHO	DD SOIL USE			

BUILDING FILL

SPECIFIED REQUIREMENTS: 95% WET DRY TEST MOISTURE TEST NO. PROCTOR PROCTOR MAXIMUM TEST LOCATION DENSITY DENSITY DEPTH PERCENT TEST NO. VALUE DENSITY (lb/ft3) (lb/ft³) NE Corner 25'S x 35'W 0-12" 108.2 3.7 104.3 103.1 101% 2 NW Corner 25'S x 30'E 0-12" 108.8 3.4 105.2 103.1 102% 3 SW Corner 30'N x 30'E 0-12" 107.2 4,3 102.8 103.1 100% 4 SE Corner 30'W x 25'N 0-12" 111.5 3.5 107.7 103,1 104%

REMARKS:

The Above Tests Meet Specified Requirements.

PROCTORS									
PROCTOR NO.	SOIL DESCRIPTION	MAXIMUM DRY UNIT WEIGHT (lb/ft³)	OPT. MOIST.	TYPE					
*	Light Brown Sand (Richardson's Ft. White Pit)	103.1	10.8	MODIFIED (ASTM D-1557)					

Respectfully Submitted, CAL-TECH TESTING, INC.

Reviewed By:

Licensed, Florida No: 57842

Linda M. Greamer
President - GEO

\$W

The test results presented in this report are specific only to the samples tested at the time of testing. The tests were performed in accordance with generally accepted methods and standards. Since material conditions can vary between test locations and change with time, sound judgement should be exercised with regard to the use and interpretation of the date.

PAGE 02/02

MORTON BUILDINGS

3522710470

28:11 8002/82/80

	Firems in melling-rach Box shall be chicled as Applicable and the same and the		ii (eti	
145, 188				
84	Wiring	Yes	No	NA
85	Services	Yes	No	(N/A)
86	Feeders and branch circuits	Yes	No	WA
87	Overcurrent protection	Yes	No	(VIA)
88	Grounding	Yes	No	(N/A)
89	Wiring methods and materials	Yes	No	
90	GFCls	Yes	No	(N/A)
91	Equipment	Yes	No	(N/A)
92	Special occupancies	Yes	No	CVAR
93	Emergency systems	Yes	No	CVA
94	Communication systems	Yes	No	SVA
95	Low voltage	Yes	No	CNIA
96	Load calculations	Yes	No	CNIA
	A STATE OF THE PARTY OF THE PAR	of some	独物的	Hughel Halley
97	Minimum plumbing facilities	(Tes)	No	N/A
98	Fixture requirements	(Tes)	No	N/A
99	Water supply piping	Yes	No	N/A)
100	Sanitary drainage	Yes	No	(N/A)
101	Water heaters	Yes	No	(N/A)
102	Vents	Yes	No	
103	Roof drainage	Yes	No	N/A
104	Back flow prevention	Yes	No	NIA
105	Irrigation	Yes	No	NA
106	Location of water supply line	Yes	No	NA
107	Grease traps	Yes	No	(N/A)
108	Environmental requirements	Yes	No	(N/A)
109	Plumbing riser	Yes	No	(N/A)
INIS.	Promoting rise		11.5	Parent I
110	Energy calculations	Yes	No	(V/A)
111	Exhaust systems	Yes	No	SWA
112	Clothes dryer exhaust	Yes	No	NA
113	Kitchen equipment exhaust	Yes	No	QUA
114	Specialty exhaust systems	Yes	No	(N/A)
	The state of the s		2.23	
115	Make-up air	Yes	No	(N/A)
116	Roof-mounted equipment	Yes	No	(N/A)
117	Duct systems	Yes	No	(N/A)
118	Ventilation	Yes	No	(N/A)
119	Laboratory	Yes	No (NIA
120	Combustion air	Yes	No	(N/A)
121	Chimneys, fireplaces and vents	Yes	No	N/A
122	Appliances	Yes	No	(N/A)
123	Boilers	Yes	No	QUA
124	Refrigeration	Yes	No (NA
		Yes	No	N/A
125	Bathroom ventilation	102	140	1111

			新州级	的特別
	Items (brinchide Each Burshaltae Chroletens/Applicable 1 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	MARIT		特別國際
n/sa/ja	Temstoricine.	Yes	No	OVIA
126	Gas piping	Yes	No	CNTA
127	Venting	Yes	No	MA
128	Combustion air	Yes	No	NIA
129	Chimneys and vents	Yes	No	OVER
130	Appliances	Yes	No	BHK
131	Type of gas	Yes	No	NIA
132	Fireplaces	Yes	No	QUA
133	LP tank location	Yes	No	N/A
134	Riser diagram/shutoffs Notice of commencement is required to be on	加田村世	開放門	性學學學
135	A recorded (in the Columbia County Clerk Office) notice of commencement is required by the healthing department. Before Any Inspections Will Be Done	(CES	No	N/A
	file with the building department. Disclosure Statisment for Owner-Builder:	Yes	No	NIA
	THE WINDS TO SELECT THE SECOND SERVICE OF THE SECOND SECOND SECOND SECOND SECOND SECOND SECOND SECOND SECOND S	學的說明		ERST STATE
	BEST SECTION OF THE PROPERTY O		1	200
136	Horse power of pump motor	Yes	No	NA
137	Capacity of pressure tank	Yes	No	NA
138	Cycle stop valve if used	Yes	No	(N/A

THE FOLLOWING ITEMS MUST BE SUBMULTED AVIT HEULEDING PLANS A current Building Permit Application form is to be N/A No completed and submitted for all construction projects. Yes 139 **Building Permit** Application The parcel number (Tax ID number) from the Property Appraiser is required. A copy of property deed is also No N/A 140 Parcel Number requested. (386) 758-1084 A copy of an approved Environmental Health (386) 758-1058 waste water disposal permit or an approved City of Lake City(386) 752-2031 sewer tap Environmental is required before a building permit can be issued. Health Permit N/A Yes No 141 or Sewer Tap Toilet facilities shall be provided for construction workers Approval If the property does not have an existing access to a public road, then an application for a culvert permit must be made (\$25.00). Culvert installation for commercial, industrial and other uses shall conform to the approved Driveway site plan or to the specifications of a registered engineer. Use or joint N/A Yes No 142 Connection use of driveways will comply with Florida Department of Transportation specifications. If the project is to be located on an F.D.O.T. maintained road, then an F.D.O.T. access permit is required. Suwannee River Water All commercial projects must have an SRWMD permit issued or an 143 Management No N/A exemption letter, before a building permit will be issued. District Approval

144	Flood Management	All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of section 8.8 of the Columbia County Land Development Regulations. Any project that is located within a flood zone where the base flood elevation (100 year flood) has not been established shall meet the requirements of section 8.7 of Columbia County Land Development Regulations. A development permit will also be required. The development permit cost is \$50.00	100	No	N/A)
145	Flood Management	A CERTIFIED FINISHED FLOOR ELEVATIONS WILL BE REQUIRED ON ANY PROJECT WHERE THE BASE FLOOD ELEVATION (100 YEAR FLOOD) HAS BEEN ESTABLISHED.	Yes	No	(N/A)
146	911 Address	If the project is located in an area where a 911 address has not been issued, then application for a 911 address must be applied for and received through the Columbia County Emergency Management Office of 911 Addressing Department (386) 758-1125	Yes	No	(A)

Pursuant to Chapter one (administration) section R101.2.1 of the Florida Building Code: Section 105.3.2 **Time limitation** of application. An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

Pursuant to Chapter one (administration) section R101.2.1 of the Florida Building Code: Section 105.4.1 **Permit intent.** A permit issued shall be constructed to be a license to proceed with the work and not as authority to violate, cancel, alter or set aside any of the provisions of the technical codes, nor shall issuance of a permit prevent the building official from thereafter requiring a correction of errors in plans, construction or violations of this code. Every permit issued shall become invalid unless the work authorized by such permit is commenced within six months after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of six months after the time the work is commenced.

Section 105.4.1.1: If work has commenced and the permit is revoked, becomes null and void, or expires because of lack of progress or abandonment, a new permit covering the proposed construction shall be obtained before proceeding with the work.

Section 105.4.1.2: If a new permit is not obtained within 180 days from the date the initial permit became null and void, the building official is authorized to require that any work which has been commenced or completed be removed from the building site. Alternately, a new permit may be issued on application, providing the work in place and required to complete the structure meets all applicable regulations in effect at the time the initial permit became null and void and any regulations which may have become effective between the date of expiration and the date if issuance of the new permit.

Section 105.4.1.3: Work shall be considered to be in active progress when the permit has received an approved inspection within 180 days. This provision shall not be applicable in case of civil commotion or strike or when the building work is halted due directly to judicial injunction, order or similar process.

Section 105.4.1.4: The fee for renewal reissuance and extension of a permit shall be set forth by the administrative authority.

When the submitted application is approved for permitting the applicant will be notified by phone as to the date and time a building permit will be prepared and issued by the Columbia County Building & Zoning Department.

0806-43

FAX MEMORANDUM

MEMORANDUM

FLORIDA DEPARTMENT OF TRANSPORTATION

To: Mr. John Kerce, Dept. Director Columbia Co. Building & Zoning Dept.

Fax No: 386-758-2160

From: Dale L. Cray, FDOT Permits Insp. Date: 4-30-2008 Fax No. 386-961-7183

Attention: Col Co. Building Zoning Dept.

() Sign and return. () For your files. () Please call me. (XX) FYI () For Review

REF: Existing Comm. D/W / Inspected On:4-29-2008

PROJECT: Our Redeemer Lutheran Church

PARCEL ID No: N/A Permit No : N/A Sec No : 29020

MILE POST:N/A+-

Mr. Kerce:

Please accept this as our legal notice of final passing inspection for (OUR REDEEMER LUTHERAN CHURCH / PAUL FORREST) for a Existing Comm. Driveway. The project is located, 5056 SW SR. 47 Lake City. Fl.32024

The Existing Comm. Access has been inspected and (Approved) and, meets FDOT Standard Requirements.

If further information is required on this project please do not hesitate to contact this office for additional access permitting information details. My office number is 961-7193 or 961-7146.

Sincerely,

Dale L. Cray

Access Permits Inspector