

Florida Building Code, 8th Edition (2023) - Energy Conservation

EnergyGauge Summit® Fla/Com-2023, Effective Date: Dec 31, 2023

C407: FBC Total Building Performance Compliance Option

Compliance applying the requirements of Sections C402.5, C403.2, C404, C405.2, C405.4, C405.5, C407 and C408. The building energy cost shall be equal to or less than 85 percent of the standard reference design building.

Check List

Applications for compliance with the Florida Building Code, Energy Conservation shall include:

- ☒ The full compliance report generated by the software that contains the project summary, compliance summary, certifications and detailed component compliance reports.
- ☒ The compliance report must include the full input report generated by the software as contiguous part of the compliance report.
- ☒ Boxes appropriately checked in the Mandatory Section of the compliance report.

PROJECT SUMMARY

Short Desc: Aspen

Description: Aspen Pest Control

Owner: Aspen Pest Control

Address1: 215 SW Windswept GL

City: Lake City

Address2:

State: FL

Zip: 32024

Type: Office

Class: New Finished building

Jurisdiction: JACKSONVILLE, DUVAL COUNTY, FL (261300)

Conditioned Area: 901 SF

Conditioned & UnConditioned Area: 2400 SF

No of Stories: 1

Area entered from Plans 2400 SF

Permit No:

Max Tonnage 3

If different, write in: _____

Compliance Summary			
Component	Design	Criteria	Result
Gross Energy Cost (in \$)	816.00	1063.00	PASSED
LIGHTING CONTROLS			PASSES
EXTERNAL LIGHTING			PASSES
HVAC SYSTEM			PASSES
PLANT			No Entry
WATER HEATING SYSTEMS			PASSES
PIPING SYSTEMS			PASSES
Met all required compliance from Check List?			<input checked="" type="checkbox"/> Yes/No/NA
IMPORTANT MESSAGE Info 5009 -- -- -- An input report of this design building must be submitted along with this Compliance Report			

CERTIFICATIONS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code

Prepared By: *Rachel Miller*

Building _____
Official: _____

Date: 06/27/2025

Date: _____

I certify that this building is in compliance with the FLorida Energy Efficiency Code

Owner Agent: _____

Date: _____

If Required by Florida law, I hereby certify (*) that the system design is in compliance with the Florida Energy Efficiency Code

Architect: Nicholas P Geisler

Reg No: AR0007005 Signature _____

Electrical Designer: Nicholas P Geisler

Reg No: AR0007005 Signature _____

Lighting Designer: Nicholas P Geisler

Reg No: AR0007005 Signature _____

Mechanical Designer: Nicholas P Geisler

Reg No: AR0007005 Signature _____

Plumbing Designer: Nicholas P Geisler

Reg No: AR0007005 Signature _____

(*) Signature is required where Florida Law requires design to be performed by registered design professionals per C103.1.1.1.2

Rachel Miller

Certified Energy Rater #1494

Project: Aspen
Title: Aspen Pest Control
Type: Office
(WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Building End Uses

	1) Proposed	2) Baseline
Total	51.30	79.40
	\$816	\$1,251
ELECTRICITY(MBtu/kWh/\$)	51.30	79.40
	15036	23294
	\$816	\$1,251
AREA LIGHTS	8.10	12.30
	2370	3613
	\$129	\$194
MISC EQUIPMT	14.20	14.20
	4166	4166
	\$226	\$224
PUMPS & MISC	0.10	0.10
	44	40
	\$2	\$2
SPACE COOL	17.40	17.00
	5089	4972
	\$276	\$267
SPACE HEAT	5.70	8.20
	1667	2416
	\$91	\$130
VENT FANS	5.80	27.60
	1700	8087
	\$92	\$434

Credits Applied: None

Passing Criteria = 1063

Design (including any credits) = 816

Passing requires Proposed Building cost to be at most 85% of
Baseline cost. This Proposed Building is at 65.3%

PASSES

Project: Aspen
Title: Aspen Pest Control
Type: Office
(WEA File: FL JACKSONVILLE INTL ARPT.tm3)

External Lighting Compliance

Description	Category	Tradable?	Allowance (W/Unit)	Area or Length or No. of Units (Sqft or ft)	ELPA (W)	CLP (W)
Ext Light 1	Main entries	Yes	21.00	15.0	315	160

Tradable Surfaces: 160 (W) Allowance for Tradable: 815 (W)

PASSES

All External Lighting: 160 (W)

Compliance check includes a excess/Base allowance of 500.00(W)

Project: Aspen
Title: Aspen Pest Control
Type: Office
(WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Lighting Controls Compliance

Acronym	ID	Description	Area (sq.ft)	Compliance
<u>Lobby</u>	12	<u>Lobby (Lobby (General) - Reception and Waiting)</u>	110	COMPLIANCE: PASSES REQUIRED: All of 8 ; one of 3 CONTROLS IN SPACE: 3-Occupant Sensor (50%) 8-Occupant Sensor Auto Full OFF
<u>Conference</u>	15	<u>Conference (Conference/meeting (Multiple Functions))</u>	196	COMPLIANCE: PASSES REQUIRED: All of 1 ; one of 2 3 ; one of 8 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 8-Occupant Sensor Auto Full OFF
<u>Office 1</u>	17	<u>Office 1 (Office - Enclosed)</u>	131	COMPLIANCE: PASSES REQUIRED: All of 1 ; one of 2 3 ; one of 8 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 8-Occupant Sensor Auto Full OFF
<u>Corridor</u>	17	<u>Corridor (Office - Enclosed)</u>	95	COMPLIANCE: PASSES REQUIRED: All of 1 ; one of 2 3 ; one of 8 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 8-Occupant Sensor Auto Full OFF
<u>Office 2</u>	17	<u>Office 2 (Office - Enclosed)</u>	108	COMPLIANCE: PASSES REQUIRED: All of 1 ; one of 2 3 ; one of 8 CONTROLS IN SPACE: 1-Manual (Local Control) 2-Occupancy Sensor - Manual ON only 8-Occupant Sensor Auto Full OFF

Office 3**17 Office 3 (Office - Enclosed)****169 COMPLIANCE: PASSES****REQUIRED:**

All of |1|; one of |2|3|; one of |8|

CONTROLS IN SPACE:

1-Manual (Local Control)

2-Occupancy Sensor - Manual ON

only

8-Occupant Sensor Auto Full OFF

Storage**3 Storage (Storage & Warehouse - Bulky Active Storage)****1,591 COMPLIANCE: PASSES****REQUIRED:**

All of |1|7|; one of |9|

CONTROLS IN SPACE:

1-Manual (Local Control)

7-Occupant Sensor Auto OFF (Full or Partial)

9-Time-Switch: Auto Full Off or Scheduled Off

PASSES**Project: Aspen****Title: Aspen Pest Control****Type: Office****(WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)****System Report Compliance****AH-1 3 Ton Split System****Constant Volume Air Cooled
Split System < 65000 Btu/hr****No. of Units
1**

Component	Category	Capacity	Eff Design	Eff Criteria	Integrated Eff-Design	Integrated Eff-Criteria	Comp- liance
Cooling System	Air Conditioners Air Cooled Split System < 45000 Btu/h Cooling Capacity	36000	14.30	14.30	8.00		PASSES
Heating System	Electric Furnace	27304	1.00	1.00			PASSES
Air Handling System -Supply	Air Handler (Supply) - Constant Volume	1200	0.22	0.82			PASSES
Air Distribution System (Sup)	ADS System (Sup)		8.00	4.20			PASSES
Air Distribution System (Ret)	ADS System (Ret)		8.00	4.20			PASSES

PASSES

Plant Compliance								
Description	Installed No	Size	Design Eff	Min Eff	Design IPLV	Min IPLV	Category	Compliance
							None	

Project: Aspen
Title: Aspen Pest Control
Type: Office
(WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Water Heater Compliance								
Description	Type	Category	Design Eff	Min Eff	Design Loss	Max Loss	Compliance	
Water Heater 1	Electric Storage water heater	<= 12 [kW]	0.92	0.91			PASSES	
							PASSES	

Project: Aspen
Title: Aspen Pest Control
Type: Office
(WEA File: FL_JACKSONVILLE_INTL_ARPT.tm3)

Piping System Compliance								
Category	Pipe Dia [inches]	Is Runout?	Operating Temp [F]	Ins Cond [Btu-in/hr .SF.F]	Ins Thick [in]	Req Ins Thick [in]	Compliance	
Heating System (Steam, Steam Condensate, & Hot Water)	0.75	False	105.00	0.28	1.00	0.50	PASSES	
							PASSES	

Mandatory Requirements (as applicable)

Requirements compiled by US Department of Energy and Pacific Northwest National Laboratory. Adopted for FBC with permission. Not all may be applicable

Topic	Section	Component	Description	Yes	N/A	Exempt
1. To be checked by Designer or Engineer						
6037 Post Constructio	C401.3	Envelope	A thermal envelope certificate will be supplied and completed by an approved third party.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6031 Fenestration	C402.4.1	Envelope	The vertical fenestration area <= 30 percent of the gross above-grade wall area.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6033 Fenestration	C402.4.1	Envelope	The skylight area <= 3 percent of the gross roof area.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6036 Fenestration	C402.4.1.1	Envelope	Vertical Fenestration Area Allowance: A maximum of 40 percent of gross above-grade wall area is permitted to be vertical fenestration area provided in buildings not greater than two stories above grade, >= 50 percent of the conditioned floor area is within a daylight zone, in buildings three or more stories above grade, not less than 25 percent of the net floor area is within a daylight zone, daylight responsive controls are installed, and glazing assemblies within the scope of NFRC 200 have visible transmittance >= 1.1 times SHGC.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6038 Fenestration	C402.4.1.2	Envelope	A maximum of 6 percent of roof area is permitted to be skylight area provided daylight responsive controls are installed in daylight zones under skylights.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

6039 Fenestration	C402.4.2	Envelope	<p>In enclosed spaces > 2,500 ft2 directly under a roof with ceiling heights > 15 ft. and used as an office, lobby, atrium, concourse, corridor, storage, gymnasium/exercise center, convention center, automotive service, manufacturing, non-refrigerated warehouse, retail store, distribution/sorting area, transportation, or workshop, the following requirements apply: (a) the daylight zone under skylights is ≤ half the floor area; (b) the skylight area to daylight zone is ≥ 3 percent with a skylight VT ≥ 0.40; or a minimum skylight effective aperture ≥ 1 percent.</p> <p>[]- Exception 1:C402.4.2: Buildings in climate zones 6 through 8.</p> <p>[]- Exception 2:C402.4.2: Spaces where the proposed general lighting power densities < 0.5 W/ft2.</p> <p>[]- Exception 3:C402.4.2: Areas with obstructions that block direct beam sunlight on ≥ 1/2 of the roof over the enclosed area for more than 1,500 daytime hours per year between 8 am and 4 pm.</p> <p>[]- Exception 4:C402.4.2: Spaces where the daylight zone under rooftop monitors is > 50 percent of the enclosed space floor area.</p> <p>[]- Exception 5:C402.4.2: Spaces where the total area net of daylight zones adjacent to vertical fenestration < 2,500 s.f. and where the lighting is controlled.</p> <p>[]- Exception 6:C402.4.2: Requirement does not apply.</p>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6032 Fenestration	C402.4.3	Envelope	Vertical fenestration Maximum U-factor and SHGC value.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6034 Fenestration	C402.4.3	Envelope	Skylight SHGC value.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6040 Fenestration	C402.4.5	Envelope	U-factor of opaque swinging and nonswinging doors associated with the building thermal envelope meets requirements.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6046 Post Constructic	C402.5.11	Envelope	<p>Operable openings > 40 ft2 will be interlocked with heating and cooling systems to setback setpoint temperatures within 10 minutes of opening.</p> <p>[]- Exception 1:C402.5.11: Separately zoned areas.</p> <p>[]- Exception 2:C402.5.11: Warehouses with overhead doors for occupancy.</p> <p>[]- Exception 3:C402.5.11: Entrance doors located in exterior wall as part of a vestibule.</p>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6056 HVAC	C403.2.1	Mechanical	<p>HVAC systems and equipment design loads calculated in accordance with ANSI/ASHRAE/ACCA Standard 183 or by an approved equivalent computational procedure</p> <p>[]- Exception 1:C403.2.1: Mechanical systems are designed by a registered engineer</p>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6096 HVAC	C403.2.12.1	Mechanical	<p>HVAC fan systems at design conditions do not exceed allowable fan system motor nameplate hp or fan system bhp.</p> <p>[]- Exception 1:C403.2.12.1: Hospital and laboratory systems that utilize flow control devices on exhaust and/or return.</p> <p>[]- Exception 2:C403.2.12.1: Individual exhaust fans with motor nameplate horsepower less than or equal 1 hp.</p> <p>[]- Exception 3:C403.2.12.1: Requirement does not apply.</p>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6055 HVAC	C403.2.12.2	Mechanical	<p>HVAC fan motors not oversized beyond allowable limits.</p> <p>[]- Exception 1:C403.2.12.2: Fans equipped with electronic speed control devices</p> <p>[]- Exception 2:C403.2.12.2: Fans with fan nameplate electrical input power < 0.89 kW</p> <p>[]- Exception 3:C403.2.12.2: Fan system complying with Section C403.2.12.1 motor nameplate hp (Option 1).</p> <p>[]- Exception 4:C403.2.12.2: Fans with motor nameplate horsepower < 1 hp (746 W).</p> <p>[]- Exception 5:C403.2.12.2: Requirement does not apply.</p>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6141 SYSTEM_SPEC	C403.2.12.3	Mechanical	<p>Fans have a fan energy index (FEI) >= 1.00. Variable volume fans will have an FEI >= 0.95 at the design point of operation.</p> <p>[]- Exception 1:C403.2.12.3: Single not embedded fans with motor nameplate horsepower of less than 1 hp (0.89 kW).</p> <p>[]- Exception 2:C403.2.12.3: Embedded fans with motor nameplate horsepower exceeding 5 hp (4.1 kW).</p> <p>[]- Exception 3:C403.2.12.3: Multiple fans in series or parallel have a combined motor nameplate horsepower of less or equal 5 hp and are operated functionally as a single fan.</p> <p>[]- Exception 4:C403.2.12.3: Fans integral to equipment listed under Section C403.2.3.</p> <p>[]- Exception 5:C403.2.12.3: Fans included in equipment having certified seal for air or energy performance of the equipment package.</p> <p>[]- Exception 6:C403.2.12.3: Ceiling fans.</p> <p>[]- Exception 7:C403.2.12.3: Fans for gases at temperatures above 425F.</p> <p>[]- Exception 8:C403.2.12.3: Fans for operation in explosive atmospheres.</p> <p>[]- Exception 9:C403.2.12.3: Reversible fans for tunnel ventilation.</p> <p>[]- Exception 10:C403.2.12.3: Fans not covered by AMCA 208.</p> <p>[]- Exception 11:C403.2.12.3: Fans intended to operate only during emergency conditions.</p>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6057 HVAC	C403.2.2	Mechanical	<p>HVAC systems and equipment capacity does not exceed calculated loads.</p> <p>[]- Exception 1:C403.2.2: Required standby equipment with proper controls per code.</p> <p>[]- Exception 2:C403.2.2: Multiple units of the same type of equipment with sequencing controls.</p> <p>[]- Exception 3:C403.2.2: Living spaces in commercial buildings shall be sized in accordance with Section R403.7.1.1 and its exceptions</p>	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>
6087 HVAC	C403.2.7	Mechanical	<p>Exhaust air energy recovery on systems meeting Table C403.7.4(1) and C403.7.4(2).</p> <p>[]- Exception 1:C403.2.7: Where energy recovery systems are prohibited by the Florida Building Code, Mechanical</p> <p>[]- Exception 2:C403.2.7: Laboratory fume hood systems</p> <p>[]- Exception 3:C403.2.7: Systems serving spaces that are heated to less than 60°F (15.5°C) and are not cooled</p> <p>[]- Exception 4:C403.2.7: Where more than 60 percent of the outdoor heating energy is provided from site-recovered or site solar energy</p> <p>[]- Exception 5:C403.2.7: Heating energy recovery in Climate Zones 1 and 2</p> <p>[]- Exception 6:C403.2.7: Cooling energy recovery in Climate Zones 3C, 4C, 5B, 5C, 6B, 7 and 8</p> <p>[]- Exception 7:C403.2.7: Systems requiring dehumidification that employ energy recovery in series with the cooling coil</p> <p>[]- Exception 8:C403.2.7: Where the largest source of air exhausted at a single location at the building exterior is less than 75 percent of the design outdoor air flow rate.</p> <p>[]- Exception 9:C403.2.7: Systems expected to operate less than 20 hours per week at the outdoor air percentage covered by Table C403.2.7(1).</p> <p>[]- Exception 10:C403.2.7: Systems exhausting toxic, flammable, paint or corrosive fumes or dust.</p> <p>[]- Exception 11:C403.2.7: Commercial kitchen hoods used for collecting and removing grease vapors and smoke</p>	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/>
6047 HVAC	C403.3.2	Mechanical	<p>Economizer operation will not increase heating energy use during normal operation.</p> <p>[]- Exception 1:C403.3.2: Economizers on VAV systems.</p>	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/>

6093 HVAC	C403.3.3, C403.3.3.1, C403.3.3.2, C403.3.3.3, C403.3.3.4, C403.3.3.5	Mechanical	<p>Air economizers provided where required, meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off, integrated economizer control, and provide a means to relieve excess outside air during operation.</p> <p>[]- Exception 1:C403.3_C403.3.2: Buildings located in Climate Zones 1A and 1B.</p> <p>[]- Exception 2:C403.3_C403.3.2: Individual DX fan cooling units have a capacity is < 54 KBtu/h (15.8 kW) or total chilled water system capacity < minimum specified in Table C403.3(1).</p> <p>[]- Exception 3:C403.3_C403.3.2: Where more than 25 % of the air supplied to spaces that are designed to be humidified above 35°F (1.7°C) dewpoint temperature to satisfy process needs</p> <p>[]- Exception 4:C403.3_C403.3.2: Systems that serve residential spaces where the system capacity is < 270 KBtu/h</p> <p>[]- Exception 5:C403.3_C403.3.2: Systems expected to operate less than 20 hours per week</p> <p>[]- Exception 6:C403.3_C403.3.2: System serves supermarket areas with open refrigerated casework.</p> <p>[]- Exception 7:C403.3_C403.3.2: Where the minimum code required cooling efficiency of the HVAC unit rated with an IPLV, IEER or SEER is increased by at least 17 %.</p> <p>[]- Exception 8:C403.3_C403.3.2: Chilled-water cooling systems that are passive (without a fan) capacity is < the minimum specified in Table C403.3(1).</p> <p>[]- Exception 9:C403.3_C403.3.2: Systems that include a heat recovery system in accordance with Section C403.4.5</p> <p>[]- Exception 10:C403.3_C403.3.2: Economizers on VAV systems cause zone-level heating to increase due to a reduction in supply air temperature.</p>	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/>
6042 HVAC	C403.3.4, C403.3.4.1, C403.3.4.2, C403.3.1	Mechanical	<p>Water economizers provided where required, meet the requirements for design capacity, maximum pressure drop and integrated economizer control.</p> <p>[]- Exception 1:C403.2.12.5_C403.2.12.5.1_C403.2.12.5.2: Modulating fan control not required for chilled water and evaporative cooling units with fan motors of < 1 hp where the units are not used to provide ventilation air and the indoor fan cycles with the load.</p> <p>[]- Exception 2:C403.2.12.5_C403.2.12.5.1_C403.2.12.5.2: Requirement does not apply.</p>	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/>
6053 HVAC	C403.4.2.3.1	Mechanical	<p>Hydronic heat pump systems connected to a common water loop meet heat rejection and heat addition requirements.</p> <p>[]- Exception 1:C403.4.2.3.1: A deadband of less than 20°F is allowed where a temperature optimization controller is used.</p>	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/>

6144 Mandatory Addit	C406.6	Project	Dedicate outdoor air system efficiency energy credit - Building equipped with independent ventilation system designed to provide 100-percent outdoor air to each individual occupied space, as specified by the IMC. The ventilation system is capable of total energy recovery and includes HVAC system controls that manage temperature resets at least 25 percent of delta design supply-air / room-air temp.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2. To be checked by Plan Reviewer						
6004 Plan Review	C103.2	Mechanical	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical and service water heating systems and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks. Hot water system sized per manufacturer's sizing guide.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6011 Plan Review	C103.2	Interior Lighting	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the interior lighting and electrical systems and equipment and document where exceptions to the standard are claimed. The information provided should include lighting controls per sections C405.2 and C405.3.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6023 Plan Review	C103.2	Exterior Lighting	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the exterior lighting and electrical systems and equipment and document where exceptions to the standard are claimed. The information provided should include Exterior lighting power requirements (Mandatory) per section C405.4.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6001 Plan Review	C103.2, C103.2.1	Envelope	Plans and/or specifications provide all information with which compliance can be determined for the building envelope and document where exceptions to the standard are claimed.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6081 HVAC	C402.2.6	Mechanical	Thermally ineffective panel surfaces of sensible heating panels have insulation $\geq R-3.5$. []- Exception 1:C402.2.6: Heated slabs on grade insulated in accordance with Section C402.2.5 []- Exception 2:C402.2.6: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6100 HVAC	C403.2.13	Mechanical	Systems that heat outside the building envelope are radiant heat systems controlled by an occupancy sensing device or timer switch. []- Exception 1:C403.12.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6068 HVAC	C403.2.4.1.3	Mechanical	Reset static pressure setpoint for DDC controlled VAV boxes reporting to central controller based on the zones requiring the most pressure. []- Exception 1:C403.4.1.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6107 HVAC	C403.2.4.2	Mechanical	Each zone equipped with setback controls using automatic time clock or programmable control system. []- Exception 1:C403.2.4.2: Zones operated continuously. []- Exception 2:C403.2.4.2: Zones have a full HVAC load demand not exceeding 6,800 Btu/h (2 kW) and having a readily accessible manual shutoff switch. []- Exception 3:C403.2.4.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6123 HVAC	C403.2.4.4	Mechanical	Zone isolation devices and controls installed where applicable. []- Exception 1:C403.2.4.4: Exhaust and outdoor air connections having fan systems 5000 cfm or smaller. []- Exception 2:C403.2.4.4: Exhaust airflow less than 10% of design. []- Exception 3:C403.2.4.4: Zones and systems intended to operate continuously or are inoperative when all other zones are inoperative. []- Exception 4:C403.2.4.4: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6124 HVAC	C403.2.4.7	Mechanical	Fault detection and diagnostics installed with air-cooled unitary DX units or VRF units having economizers. []- Exception 1:C403.2.4.7: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6125 HVAC	C403.2.5	Mechanical	Hot water boilers supplying heat via one- or two-pipe systems include outdoor setback control. []- Exception 1:C403.2.5: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6089 HVAC	C403.2.6	Mechanical	Natural or mechanical ventilation is provided in accordance with International Mechanical Code Chapter 4. Mechanical ventilation has capability to reduce outdoor air supply to minimum per IMC Chapter 4. []- Exception 1:C403.2.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6090 HVAC	C403.2.6.1	Mechanical	Demand control ventilation provided for spaces >500 ft2 and >=25 people/1000 ft2 occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow >3,000 cfm. []- Exception 1:C403.2.6.1: Systems with energy recovery complying with Section C403.2.7. []- Exception 2:C403.2.6.1: Multiple-zone systems without DDC. []- Exception 3:C403.2.6.1: Multiple-zone systems with design outdoor air of less than 1200 cfm. []- Exception 4:C403.2.6.1: Spaces where the supply airflow rate minus any makeup or outgoing transfer air requirement is < 1,200 cfm []- Exception 5:C403.2.6.1: Ventilation provided for process loads only []- Exception 6:C403.2.6.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6098 HVAC	C403.4.2	Mechanical	The heating of fluids in hydronic systems that have been previously mechanically cooled, and the cooling of fluids that have been previously mechanically heated are limited in accordance with Sections C403.4.2.1-C403.4.2.3. Single boiler systems >500 kBtu/h have multistaged or modulating burner. []- Exception 1:C403.4.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6142 HVAC	C403.4.2.3.2	Mechanical	Closed-circuit cooling tower within heat pump loop have either automatic bypass valve or lower leakage positive closure dampers. Open-circuit tower within heat pump loop have automatic valve to bypass all heat pump water flow around the tower. Open- or closed-circuit cooling towers used in conjunction with a separate heat exchanger have heat loss by shutting down the circulation pump on the cooling tower loop. Open- or closed circuit cooling towers have a separate heat exchanger to isolate the cooling tower from the heat pump loop, and heat loss is controlled by shutting down the circulation pump on the cooling tower loop. []- Exception 1:C403.4.2.3.2: Heat pump system must reject heat throughout the year. []- Exception 2:C403.4.2.3.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6116 HVAC	C403.4.2.5	Mechanical	System turndown requirement met through multiple single-input boilers, one or more modulating boilers, or a combination of single-input and modulating boilers. Boiler shall comply with the turndown ratio specified in Table C403.4.2.5.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6071 HVAC	C403.4.2.6	Mechanical	Chilled water plants with multiple chillers have capability to reduce flow automatically through the chiller plant when a chiller is shut down. Boiler plants with multiple boilers have the capability to reduce flow automatically through the boiler plant when a boiler is shut down.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6099 HVAC	C403.4.3.1	Mechanical	Fan systems with total system motor capacity >=5 hp associated with heat rejection equipment configured to automatically modulate the fan speed to control the leaving fluid temperature or condensing temp/pressure of heat rejection device. []- Exception 1:C403.4.3.1: Fans serve multiple refrigerant or fluid cooling circuits. []- Exception 2:C403.4.3.1: Condenser fans serve flooded condensers. []- Exception 3:C403.4.3.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6120 HVAC	C403.4.3.4	Mechanical	Open-circuit cooling towers having water cooled chiller systems and multiple or variable speed condenser pumps, are designed so that tower cells can run in parallel with larger of flow criteria. []- Exception 1:C403.4.3.4: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6103 HVAC	C403.6.1	Mechanical	<p>Hydronic and multizone HVAC system controls are VAV fans driven by mechanical or electrical variable speed drive per Table C403.4.1.1.</p> <p>[]- Exception 1:C403.4.4: Zones or supply air systems where $\geq 75\%$ of the energy for reheating or for providing warm air in mixing systems is provided from a site-recovered or site-solar energy source</p> <p>[]- Exception 2:C403.4.4: Zones where special humidity levels are required to satisfy process needs</p> <p>[]- Exception 3:C403.4.4: Zones with a peak supply air of ≤ 300 cfm (142 L/s) and where the flow rate is $< 10\%$ of the total fan system supply airflow rate.</p> <p>[]- Exception 4:C403.4.4: Zones where the volume of air to be reheated, recooled or mixed is \leq the minimum ventilation requirements of Chapter 4 of the Florida Building Code, Mechanical</p> <p>[]- Exception 5:C403.4.4: Zones or supply air systems with thermostatic and humidistatic controls capable of preventing reheating, recooling, mixing or simultaneous supply of air that has been previously cooled</p> <p>[]- Exception 6:C403.4.4: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6122 HVAC	C404.2.1	Mechanical	<p>Gas-fired water-heating equipment installed in new buildings: where a singular piece of water-heating equipment $\geq 1,000$ kBtu/h serves the entire building, thermal efficiency ≤ 92 Et. Where multiple pieces of water-heating equipment serve the building with combined rating $\leq 1,000$ kBtu/h, the combined input-capacity-weighted-average thermal efficiency ≤ 90 Et. Exclude input rating of equipment in individual dwelling units and equipment ≤ 100 kBtu/h</p> <p>[]- Exception 1:C404.2.1: 25 percent or more of the annual service water heating requirement is provided by on-site renewable energy or site-recovered energy.</p> <p>[]- Exception 2:C404.2.1: Water heaters installed in individual dwelling units shall not be required to be included in the total input rating of service waterheating equipment</p> <p>[]- Exception 3:C404.2.1: Water heaters with an input rating of $\leq 100,000$ Btu/h (29.3 kW) not required to be included in the total input rating of service water-heating equipment</p> <p>[]- Exception 4:C404.2.1: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6114 HVAC	C404.4	Mechanical	<p>All piping insulated in accordance with section details and Table C403.12.3.</p> <p>[]- Exception 1:C404.4: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6019 HVAC	C404.5, C404.5.1, C404.5.2	Mechanical	<p>Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.</p> <p>[]- Exception 1:C404.5_C404.5.1_C404.5.2: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6022 HVAC	C404.6.3	Mechanical	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to ≤ 5 minutes after end of heating cycle. []- Exception 1:C404.6.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6026 HVAC	C404.7	Mechanical	Demand recirculation water systems have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F. []- Exception 1:C404.7: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6048 Plan Review	C405.5.2	Project	Group R-2 dwelling units have separate electrical meters. []- Exception 1:C405.5.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6030 Plan Review	C406	Project	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the additional energy efficiency package options.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6084 HVAC	C408.2.2.2	Mechanical	HVAC hydronic heating and cooling coils have means to balance and have pressure test connections. []- Exception 1:C408.2.2.2: Pumps with pump motors of 5 hp (3.7 kW) or less. []- Exception 2:C408.2.2.2: Where throttling results in no greater than 5 percent of the nameplate horsepower draw above that required if the impeller were trimmed.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3. To be checked by Inspector						
6016 Insulation	C104	Envelope	Installed above-grade wall insulation type and R-value consistent with insulation specifications reported in plans.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6006 Insulation	C104, C303.1.1	Envelope	Installed roof insulation type and R-value consistent with insulation specifications reported in plans. For some ceiling systems, verification may need to occur during Framing Inspection.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6008 Insulation	C104.2.1	Envelope	Installed slab-on-grade insulation type and R-value consistent with insulation specifications reported in plans.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6007 Insulation	C303.1, C303.1.1	Envelope	Roof insulation installed per manufacturer's instructions and is labeled with R-value or insulation certificate providing R-value and other relevant data. Blown or poured loose-fill insulation is installed only where the roof slope is > 3 in 12.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6035 Fenestration	C303.1.3	Envelope	Fenestration products rated in accordance with NFRC certified and as to performance labels or certificates provided. []- Exception 1:C303.1.3: Default values are used.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6020 Insulation	C303.2	Envelope	Above-grade wall insulation installed per manufacturer's instructions.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6005 Insulation	C303.2, C303.2.1	Envelope	Below-grade wall insulation installed per manufacturer's instructions.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6013 Insulation	C303.2, C303.2.1	Envelope	Slab edge insulation installed per manufacturer's instructions and the Florida Building Code, Building.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6027 Insulation	C303.2, C402.2.4	Envelope	<p>Floor insulation installed per manufacturer's instructions. Cavity or structural slab insulation installed in permanent contact with underside of decking or structural slabs.</p> <p>[]- Exception 1:C303.2_C402.2.4: All perimeter framing fully insulated at metal or wood framed prescriptive levels.</p> <p>[]- Exception 2:C303.2_C402.2.4: Concrete floor slab insulation turns up and contacts underside of floor under wall assembly.</p> <p>[]- Exception 3:C303.2_C402.2.4: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6015 Insulation	C303.2.1	Envelope	Exterior insulation protected against damage, sunlight, moisture, wind, landscaping and equipment maintenance activities.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6002 Insulation	C402.1.3	Envelope	Installed below-grade wall insulation type and R-value consistent with insulation specifications reported in plans.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6061 Insulation	C402.1.3	Envelope	<p>Non-swinging opaque doors have R-4.75 insulation.</p> <p>[]- Exception 1:C402.1.3: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6012 Insulation	C402.2.2	Envelope	<p>Skylight curbs are insulated to the level of roofs with insulation above deck or R-5, whichever is less.</p> <p>[]- Exception 1:C402.2.1.5: Unit skylight curbs included as a component of a skylight listed and labeled per NFRC 100.</p> <p>[]- Exception 2:C402.2.1.5: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6064 Insulation	C402.2.2	Envelope	<p>Roof assembly meets minimal thermal resistance installed between roof framing or in a continuous fashion on the roof assembly as stipulated in Table C402.1.3. Requirements for above deck insulation, minimum thickness, suspended ceilings, staggered joints and skylight curbs will be met.</p> <p>[]- Exception 1:C402.2.1: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6024 Insulation	C402.2.3	Envelope	Installed floor insulation type and R-value consistent with insulation specifications reported in plans.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6021 Insulation	C402.2.5, C402.2.5.1	Envelope	<p>Slab edge insulation depth/length. Slab insulation extending away from building is covered by pavement or \geq 10 inches of soil.</p> <p>[]- Exception 1:C402.2.5_C402.2.5.1: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6051 Insulation	C402.2.6	Envelope	<p>Radiant panels and associated components, designed for heat transfer from the panel surfaces to the occupants or indoor space are insulated with a minimum of R-3.5.</p> <p>[]- Exception 1:C402.2.6: Heated slab-on-grade.</p> <p>[]- Exception 2:C402.2.6: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6014 Insulation	C402.3	Envelope	<p>High-albedo roofs satisfy one of the following: 3-year-aged solar reflectance ≥ 0.55 (0.63 for Climate Zone 1A) and thermal emittance ≥ 0.75 or 3-year-aged solar reflectance index ≥ 64.0 (75 for Climate Zone 1A). []- Exception 1:C402.3: Roof Over Conditioned Space With No Cooling.</p> <p>[]- Exception 2:C402.3: Ballasted Roof.</p> <p>[]- Exception 3:C402.3: Vegetated Roof (75% coverage).</p> <p>[]- Exception 4:C402.3: Shaded or Covered Roof (75% coverage).</p> <p>[]- Exception 5:C402.3: Asphaltic Membrane Roof.</p> <p>[]- Exception 6:C402.3: Steep Sloped Roof.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6028 Fenestration	C402.4.3	Envelope	Installed skylight U-factor and SHGC consistent with label specifications and as reported in plans.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6025 Fenestration	C402.4.3, C402.4.3.4	Envelope	Installed vertical fenestration U-factor and SHGC consistent with label specifications and as reported in plans.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6043 Air Leakage	C402.5	Envelope	Building envelope contains a continuous air barrier that has been tested and deemed to limit air leakage ≤ 0.40 cfm/ft ² of the building thermal envelope area at a pressure differential of 0.3 inch water gauge (75 Pa).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6044 Air Leakage	C402.5.1	Envelope	<p>The building envelope contains a continuous air barrier that is sealed in an approved manner and either constructed or tested in an approved manner. Air barrier penetrations are sealed in an approved manner.</p> <p>[]- Exception 1:C402.5.1: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6003 Air Leakage	C402.5.1.1	Envelope	All sources of air leakage in the building thermal envelope are sealed, caulked, gasketed, weather stripped or wrapped with moisture vapor-permeable wrapping material to minimize air leakage.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6062 Air Leakage	C402.5.1.2.1	Envelope	<p>The building envelope contains a continuous air barrier that is sealed in an approved manner and material permeability ≤ 0.004 dfm/ft². Air barrier penetrations are sealed in an approved manner.</p> <p>[]- Exception 1:C402.5.1.2.1: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6065 Air Leakage	C402.5.1.2.2	Envelope	<p>The building envelope contains a continuous air barrier that is sealed in an approved manner and average assembly air leakage ≤ 0.04 cfm/ft². Air barrier penetrations are sealed in an approved manner.</p> <p>[]- Exception 1:C402.5.1.2.2: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6052 Air Leakage	C402.5.4	Envelope	<p>Factory-built fenestration and doors are labeled as meeting air leakage requirements. <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/></p> <p><input type="checkbox"/>- Exception 1:C402.5.4: Field fabricated fenestration assemblies.</p> <p><input type="checkbox"/>- Exception 2:C402.5.4: Fenestration in buildings that comply with air leakage requirements with a whole building air leakage test.</p> <p><input type="checkbox"/>- Exception 3:C402.5.4: Doors that comply with special International Building Code requirements.</p>			
6009 Air Leakage	C402.5.5, C402.5.11, 403.6	Envelope	<p>Stair and elevator shaft vents have motorized dampers that automatically close. Reference section C403.6 for operational details.</p> <p><input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/></p>			
6049 Air Leakage	C402.5.6	Envelope	<p>Weatherseals installed on all loading dock cargo door openings and provide direct contact along the top and sides of vehicles parked in the doorway. <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/></p> <p><input type="checkbox"/>- Exception 1:C402.5.6: Requirement does not apply.</p>			
6050 Air Leakage	C402.5.7	Envelope	<p>Vestibules are installed on all building entrances. Doors have self-closing devices. <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/></p> <p><input type="checkbox"/>- Exception 1:C402.5.7: Building entrances with revolving doors.</p> <p><input type="checkbox"/>- Exception 2:C402.5.7: Doors not intended to be used as a building entrance.</p> <p><input type="checkbox"/>- Exception 3:C402.5.7: Doors opening directly from a sleeping unit or dwelling unit.</p> <p><input type="checkbox"/>- Exception 4:C402.5.7: Doors that open directly from a space &lt;=3000 ft2.</p> <p><input type="checkbox"/>- Exception 5:C402.5.7: Doors with air curtain.</p> <p><input type="checkbox"/>- Exception 6:C402.5.7: Existing door is being replaced and existing vestibules not removed.</p> <p><input type="checkbox"/>- Exception 7:C402.5.7: Requirement does not apply.</p>			
6045 Air Leakage	C402.5.8	Envelope	<p>Recessed luminaires in thermal envelope to limit infiltration and be IC rated and labeled. Seal between interior finish and luminaire housing. <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/></p> <p><input type="checkbox"/>- Exception 1:C402.5.10: Requirement does not apply.</p>			
6086 HVAC	C403.2	Mechanical	<p>HVAC equipment efficiency verified.</p> <p><input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/></p>			

6092 HVAC	C403.2.10	Mechanical	<p>HVAC piping insulation insulated in accordance with Table C403.2.10. Insulation exposed to weather is protected from damage and is provided with shielding from solar radiation.</p> <p>[]- Exception 1:C403.2.10: Factory-installed piping within HVAC equipment</p> <p>[]- Exception 2:C403.2.10: Factory-installed piping within room fan-coils and unit ventilators tested under AHRI 440.</p> <p>[]- Exception 3:C403.2.10: Piping that conveys fluids that have a design operating temperature range between 60 and 105°F.</p> <p>[]- Exception 4:C403.2.10: Fluid not heated or cooled.</p> <p>[]- Exception 5:C403.2.10: Strainers and valves associated with 1 inch or smaller piping.</p> <p>[]- Exception 6:C403.2.10: Underground piping with fluids no hotter than 60°F.</p> <p>[]- Exception 7:C403.2.10: Piping design for radiant heating systems</p> <p>[]- Exception 8:C403.2.10: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6171 HVAC	C403.2.12.4	Mechanical	<p>Motors for fans that are not less than 1/12 hp and less than 1 hp are electronically commutated motors or have a minimum motor efficiency of 70 percent. These motors have the means to adjust motor speed for either balancing or remote control.</p> <p>[]- Exception 1:C403.2.12.4: Motors in the airstream within fan coils and terminal units only provide heating to the space served.</p> <p>[]- Exception 2:C403.2.12.4: Motors in space-conditioning equipment that comply with Section C403.2.3 or C403.2.12.</p> <p>[]- Exception 3:C403.2.12.4: Motors that comply with Section C405.7.</p> <p>[]- Exception 4:C403.2.12.4: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6173 HVAC	C403.2.12.5.1	Mechanical	<p>Each DX cooling system \geq 65 kBtu and chiller water/evaporative cooling system with fans \geq 1/4 hp are designed to vary the indoor fan airflow as a function of load and comply with detailed requirements of this section.</p> <p>[]- Exception 1:C403.2.12.5.1: Modulating fan control is not required for chilled water and evaporative cooling units with fan motors of less than 1 hp where the units are not used to provide ventilation air and the indoor fan cycles with the load.</p> <p>[]- Exception 2:C403.2.12.5.1: Where the volume of outdoor air required to comply with the ventilation requirements of the IMC at low speed exceeds the air that would be delivered per Section C403.2.12.5</p> <p>[]- Exception 3:C403.2.12.5.1: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6097 HVAC	C403.2.12.5.2	Mechanical	VAV fans have static pressure sensors located so controller setpoint <=1.2 w.c.. []- Exception 1:C403.2.12.5.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6168 HVAC	C403.2.12.5.2	Mechanical	Static pressure sensors used to control VAV fans located such that the controller setpoint is <= 1.2 inches w.c.. Where this results in one or more sensors being located downstream of major duct splits, not less than one sensor located on each major branch. []- Exception 1:C403.2.12.5.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6167 HVAC	C403.2.12.5.3	Mechanical	Systems with DDC of individual zones reporting to the central control panel configured to reset the static pressure setpoint based on zone requiring the most pressure. The DDC is capable of monitoring zone damper positions or have an alternative method of indicating the need for static pressure. See section for details. []- Exception 1:C403.2.12.5.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6178 HVAC	C403.2.12.6	Mechanical	Large diameter fans where installed shall be tested and labeled in accordance with AMCA 230. []- Exception 1:C403.2.12.6: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6155 HVAC	C403.2.14, C403.2.14.1, C403.2.14.2	Mechanical	Refrigeration equipment performance shall be determined in accordance with sections C403.2.14.1 and C403.2.14.2 for commercial refrigerators, freezers, refrigerator-freezers, walk-in coolers, walk-in freezers and refrigeration equipment. []- Exception 1:C403.5: Systems have working fluid in the refrigeration cycle that goes through both subcritical and supercritical states (transcritical). []- Exception 2:C403.5: Systems use ammonia refrigerant. []- Exception 3:C403.5: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6102 HVAC	C403.2.3	Mechanical	PTAC and PTHP with sleeves 16 in. by 42 in. labeled for replacement only as per Footnote b to Tables C403.2.3(1) and C403.2.3(2). []- Exception 1:C403.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6058 HVAC	C403.2.4.1	Mechanical	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system. []- Exception 1:C403.2.4.1: TRUE	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6059 HVAC	C403.2.4.1.1	Mechanical	Heat pump controls prevent supplemental electric resistance heat from coming on when not needed. []- Exception 1:C403.2.4.1.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6060 HVAC	C403.2.4.1.2	Mechanical	Thermostatic controls have a 5 °F deadband. []- Exception 1:C403.2.4.1.2: Manual changeover thermostats. []- Exception 2:C403.2.4.1.2: Precision indoor temperature control required.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6085 HVAC	C403.2.4.1.3	Mechanical	Temperature controls have setpoint overlap restrictions. []- Exception 1:C403.2.4.1.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6108 HVAC	C403.2.4.2.1, C403.2.4.2.2	Mechanical	Automatic Controls: Setback to 55°F (heat) and 85°F (cool); 7-day clock, 2-hour occupant override, 10-hour backup []- Exception 1:C403.2.4.2.1_C403.2.4.2.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6110 HVAC	C403.2.4.2.3	Mechanical	Systems include optimum start controls. []- Exception 1:C403.2.4.2.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6088 Air Leakage	C403.2.4.3	Mechanical	Outdoor air and exhaust systems have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Check gravity dampers where allowed. Reference section language for operational details. []- Exception 1:C403.2.4.3: Gravity dampers acceptable in buildings less than 3 stories. []- Exception 2:C403.2.4.3: Gravity dampers acceptable for exhaust and relief dampers in climate zones 0, 1, 2, or 3. []- Exception 3:C403.2.4.3: Gravity dampers acceptable in systems with outside or exhaust air flow rates less than or equal to 300 cfm. []- Exception 4:C403.2.4.3: Dampers no larger than 24 inches in any dimension are to have a leakage rate of 40 cfm/ft ² at 1.0 inch water gauge when tested with AMCA 500D. []- Exception 5:C403.2.4.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6029 HVAC	C403.2.4.5	Mechanical	Snow/ice melting system and freeze protection systems have sensors and controls configured to limit service for pavement temperature above 50°F and outdoor temperature above 40°F. []- Exception 1:C403.12.2_C403.12.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6170 HVAC	C403.2.4.8	Mechanical	HVAC systems serving guestrooms in Group R-1 buildings with < 50 guestrooms: Each guestroom is provided with controls that automatically manage temperature setpoint and ventilation (see sections C403.2.4.8.1 and C403.2.4.8.2). []- Exception 1:C403.2.4.8: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6128 HVAC	C403.2.6.2	Mechanical	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity. []- Exception 1:C403.2.6.2: Garages with no mechanical cooling or heating that have exhaust capacity < 8,000 cfm. []- Exception 2:C403.2.6.2: Garages with no mechanical cooling or heating that have a ratio of garage area ventilation to ventilation system motor nameplate hp exceed 1125 cfm/hp. []- Exception 3:C403.2.6.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6169 HVAC	C403.2.7	Mechanical	Units that provide ventilation air to multiple zones and operate in combination with zone heating and cooling systems do not use heating or heat recovery to warm supply air to a temperature greater than 60°F when representative building loads or outdoor air temperatures indicate that the majority of zones require cooling. []- Exception 1:C403.7.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6129 HVAC	C403.2.8	Mechanical	Kitchen exhaust systems comply with replacement air and conditioned supply air limitations, and satisfy hood rating requirements and maximum exhaust rate criteria. []- Exception 1:C403.2.8: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6091 HVAC	C403.2.9	Mechanical	HVAC ducts and plenums insulated in accordance with C403.2.9.1 and constructed in accordance with C403.2.9.2, Sealed in accordance with C403.2.9.3. verification may need to occur during Foundation Inspection. []- Exception 1:C403.2.9_C403.2.9.1: Factory-installed as part of HVAC equipment. []- Exception 2:C403.2.9_C403.2.9.1: Where the design temperature difference between the inside and outside of the duct or plenum is less than 15°F. []- Exception 3:C403.2.9_C403.2.9.1: Runouts less than 10 feet (3048 mm) in length to air terminals or air outlets, the rated R-value of insulation need not exceed R-5. []- Exception 4:C403.2.9_C403.2.9.1: Backs of air outlets and outlet plenums exposed to unconditioned spaces need not exceed R-2. []- Exception 5:C403.2.9_C403.2.9.1: Return air ducts meeting all the requirements for building cavities that will be used as return air plenums []- Exception 6:C403.2.9_C403.2.9.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6174 SYSTEM_SPEC	C403.3.2	Mechanical	Equipment minimum efficiency:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6175 SYSTEM_SPEC	C403.3.2	Mechanical	Equipment minimum efficiency:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6157 HVAC	C403.3.3.3	Mechanical	Air economizers automatically reduce outdoor air intake to the design minimum outdoor air quantity when outdoor air intake will not reduce cooling energy usage. See Table C403.3.3.3 for applicable device types and climate zones. []- Exception 1:C403.3.3.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6158 HVAC	C403.3.3.4	Mechanical	System capable of relieving excess outdoor air during air economizer operation to prevent over pressurizing the building. The relief air outlet located to avoid recirculation into the building. []- Exception 1:C403.3.3.4: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6159 HVAC	C403.3.3.5	Mechanical	Return, exhaust/relief and outdoor air dampers used in economizers have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Reference section C403.2.4.3 for details. []- Exception 1:C403.3.3.5: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6094 HVAC	C403.4.1.4	Mechanical	Heating for vestibules and air curtains with integral heating include automatic controls that shut off the heating system when outdoor air temperatures < 45F. Vestibule heating and cooling systems controlled by a thermostat in the vestibule with heating setpoint <= 60F and cooling setpoint <= 80F. []- Exception 1:C402.5.7: Buildings in Climate Zones 1 and 2. []- Exception 2:C402.5.7: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6082 HVAC	C403.4.2.1	Mechanical	Three-pipe hydronic systems using a common return for hot and chilled water are not used.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6095 HVAC	C403.4.2.2	Mechanical	Two-pipe hydronic systems using a common distribution system have controls to allow a deadband >=15 °F, allow operation in one mode for at least 4 hrs before changeover, and have reset controls to limit heating and cooling supply temperature to <=30 °F.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6072 HVAC	C403.4.2.3.3	Mechanical	Two-position automatic valve interlocked to shut off water flow when hydronic heat pump with pumping system > 10 hp is off.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6172 HVAC	C403.4.3.2	Mechanical	Multiple-cell heat rejection equipment with variable speed fan drives are controlled to operate the maximum number of fans allowed and so that all fans operate at the same fan speed required for the instantaneous cooling duty. The minimum fan speed will be the minimum allowable speed of the fan drive system in accordance with the manufacturer's recommendations. []- Exception 1:C403.4.3.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6118 SYSTEM_SPEC	C403.4.3.3	Mechanical	Centrifugal fan open-circuit cooling towers having combined rated capacity >= 1100 gpm meets minimum efficiency requirement: >=40.2 gpm/hp. []- Exception 1:C403.4.3.3: Centrifugal open-circuit cooling towers with external sound attenuation or that have ducted inlet or discharge. []- Exception 2:C403.4.3.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6160 HVAC	C403.4.4	Mechanical	Supply air systems serving multiple zones have VAV systems with controls configured to reduce the volume of air that is reheated, recooled or mixed in each zone. See section for details. []- Exception 1:C403.6.1: Zones or systems with at least 75% of energy used for heating or warming air Systems that prevent reconditioning, mixing or simultaneous supply of air that has previously been mechanically cooled (including via economizers) or heated. []- Exception 2:C403.6.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6161 HVAC	C403.4.4.1	Mechanical	Single-duct VAV systems use terminal devices configured to reduce the supply of primary supply air before reheating or recooling takes place. []- Exception 1:C403.4.4.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6162 HVAC	C403.4.4.2	Mechanical	Systems that have 1 warm air duct and 1 cool air duct use terminal devices configured to reduce the flow from one duct to a minimum before mixing of air from the other duct takes place. []- Exception 1:C403.4.4.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6163 HVAC	C403.4.4.3	Mechanical	Individual dual-duct or mixing heating and cooling systems with a single fan and with total capacities > 90,000 Btu/h not equipped with air economizers. []- Exception 1:C403.4.4.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6164 HVAC	C403.4.4.5	Mechanical	Multiple zone HVAC systems have supply air temperature reset controls based on building loads or outside temperatures. []- Exception 1:C403.4.4.5: Systems that prevent re-heating, re-cooling, or mixing of heated and cooled supply air. []- Exception 2:C403.4.4.5: Systems in which at least 75% of the energy for reheating is from site recovered or site solar energy resources. []- Exception 3:C403.4.4.5: Zones in climate zones 1A and 3A with less than 300 cfm design outside air. []- Exception 4:C403.4.4.5: Zones in climate zone 2A with with less than 10,000 cfm of design outside air. []- Exception 5:C403.4.4.5: Zones in climate zones 1A, 2A, and 3A with >= 80% outside air and employing exhaust air energy recovery. []- Exception 6:C403.4.4.5: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6165 HVAC	C403.4.4.6	Mechanical	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls. []- Exception 1:C403.4.4.6: VAV systems that recirculate air from other zones without directly mixing it with outdoor air or dual-duct dual-fan VAV systems, or VAV systems with fan-powered terminal units. []- Exception 2:C403.4.4.6: Systems where the design exhaust airflow is more than 70% of design outdoor air intake flow. []- Exception 3:C403.4.4.6: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6166 HVAC	C403.4.4.7	Mechanical	Parallel-flow fan-powered VAV air terminals have automatic controls configured to 1) turn off the terminal fan except when space heating is required or where required for ventilation, 2) turn on the terminal fan as the first stage of heating before the heating coil is activated, and 3) during heating for warmup or setback temperature control, either operate the terminal fan and heating coil without primary air or, reverse the terminal damper logic and provide heating from the central air handler by primary air. []- Exception 1:C403.4.4.7: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6076 HVAC	C403.4.5	Mechanical	Condenser heat recovery system that can heat water to 85 °F or provide 60% of peak heat rejection is installed for preheating of service hot water. []- Exception 1:C403.4.5: Facility operates < 24/7. []- Exception 2:C403.4.5: Total installed heat capacity of water cooled systems <= 6 MMBtu/h of heat rejection. []- Exception 3:C403.4.5: Design SWH load <= 1 MMBtu/h. []- Exception 4:C403.4.5: Facilities using condenser heat recovery for space heating with heat recovery exceeding 30% of the peak water-cooled condenser load. []- Exception 5:C403.4.5: Facilities providing 60% of their service water heating from site-solar, site-recovered, or other energy sources.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6080 HVAC	C403.4.6	Mechanical	Hot gas bypass limited to: <=240 kBtu/h – 50%; <240 kBtu/h – 25%	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6101 HVAC	C404.2	Mechanical	Service water heating equipment meets efficiency requirements.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6113 HVAC	C404.3	Mechanical	Heat traps installed on supply and discharge piping of non-circulating systems. []- Exception 1:C404.3: Tank inlets/outlets associated with solar water heating systems. []- Exception 2:C404.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6115 HVAC	C404.6.1	Mechanical	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank. System return pipe is a dedicated return pipe or a cold water supply pipe. []- Exception 1:C404.6.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6010 HVAC	C404.6.1, C404.6.2	Mechanical	Automatic time switches installed to automatically switch off the recirculating hot-water system or heat trace.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6126 HVAC	C404.9.1	Mechanical	Pool heaters are equipped with on/off switch and no continuously burning pilot light.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6127 HVAC	C404.9.2	Mechanical	<p>Time switches are installed on all pool heaters and pumps.</p> <p>[]- Exception 1:C404.9.2: Where 24-hr pump operation required for public health.</p> <p>[]- Exception 2:C404.9.2: Solar and waste heat recovery pool heating pumps.</p> <p>[]- Exception 3:C404.9.2: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6130 HVAC	C404.9.3	Mechanical	<p>Vapor retardant pool covers are provided for heated pools and permanently installed spas.</p> <p>[]- Exception 1:C404.9.3: Pools deriving > 75% of the energy for heating (of not fewer than 3 months) from heat pump or site-recovered energy.</p> <p>[]- Exception 2:C404.9.3: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6054 Controls	C405.2.1, C405.2.1.1	Interior Lighting	<p>Occupancy sensors installed in classrooms/lecture/training rooms, conference/meeting/multipurpose rooms, copy/print rooms, lounges/breakrooms, enclosed offices, open plan office areas, restrooms, storage rooms, locker rooms, corridors, warehouse storage areas, and other spaces <= 300 sqft that are enclosed by floor-to-ceiling height partitions. Reference section language C405.2.1.2 for control function in warehouses and section C405.2.1.3 for open plan office spaces.</p> <p>[]- Exception 1:C405.2.1_C405.2.1.1: Automatic-on controls are allowed in corridors, stairways, restrooms, primary building entrance areas and lobbies, and areas where manual-on controls could impact safety or security.</p> <p>[]- Exception 2:C405.2.1_C405.2.1.1: Areas such as security or emergency areas that need continuous lighting.</p> <p>[]- Exception 3:C405.2.1_C405.2.1.1: Emergency egress lighting.</p> <p>[]- Exception 4:C405.2.1_C405.2.1.1: Lighting that is related to means of egress in stairways, ramps, corridors.</p> <p>[]- Exception 5:C405.2.1_C405.2.1.1: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6063 Controls	C405.2.1.2	Interior Lighting	<p>Occupancy sensors control function in warehouses: In warehouses, the lighting in aiseways and open areas is controlled with occupant sensors that automatically reduce lighting power by 50% or more within 20 minutes of when the areas are unoccupied. The occupant sensors control lighting in each aisleway independently and do not control lighting beyond the aisleway being controlled by the sensor. Lights not turned off by occupant sensors is done so by time-switch.</p> <p>[]- Exception 1:C402.5.1.2: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6066 Controls	C405.2.1.3	Interior Lighting	<p>Occupant sensor control function in open plan office areas: Occupant sensor controls in open office spaces ≥ 300 sq.ft. have controls 1) configured so that general lighting can be controlled separately in control zones with floor areas ≤ 600 sq.ft. within the space, 2) general lighting in each zone permitted to turn on upon occupancy in control zone, 3) automatically turn off general lighting in all control zones within 20 minutes after all occupants have left the space, 4) are configured so that general lighting power in each control zone is reduced by $\leq 80\%$ of the full zone general lighting power within 20 minutes of all occupants leaving that control zone.</p> <p>[]- Exception 1:C405.2.1.3: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6067 Controls	C405.2.2, C405.2.2.1	Interior Lighting	<p>Each area not served by occupancy sensors (per C405.2.1.1) have time-switch controls and functions detailed in sections C405.2.2.1.</p> <p>[]- Exception 1:C405.2.2_C405.2.2.1: Luminaires requiring specific controls in accordance with C405.2.4.</p> <p>[]- Exception 2:C405.2.2_C405.2.2.1: Spaces with patient care.</p> <p>[]- Exception 3:C405.2.2_C405.2.2.1: Areas such as security or emergency areas that need continuous lighting.</p> <p>[]- Exception 4:C405.2.2_C405.2.2.1: Lighting that is related to means of egress in stairways, ramps, corridors, or emergency routes.</p> <p>[]- Exception 5:C405.2.2_C405.2.2.1: Shop and laboratory classrooms.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6069 Controls	C405.2.3.1	Interior Lighting	<p>Spaces required to have light-reduction controls have a manual control that allows the occupant to reduce the connected lighting load in a reasonably uniform illumination pattern using one of the following or another approved method: (1) Continuous dimming of all luminaires from full output to less than 20 percent of full power, (2) Switching all luminaires to a reduced output of not less than 30 percent and not more than 70 percent of full power, or (3) Switching alternate luminaires or alternate rows of luminaires to achieve a reduced output of not less than 30 percent and not more than 70 percent of full power.</p> <p>[]- Exception 1:C405.2: Areas designated as security or emergency areas that are required to be continuously lighted.</p> <p>[]- Exception 2:C405.2: Interior exit stairways, interior exit ramps, and exit passageways.</p> <p>[]- Exception 3:C405.2: Emergency egress lighting that is normally off.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6070 Controls	C405.2.4, C405.2.4.1, C405.2.4.2	Interior Lighting	Daylight zones provided with individual controls that control the lights independent of general area lighting. See code section C405.2.3 Daylight-responsive controls for applicable spaces, C405.2.3.1 Daylight responsive control function and section C405.2.3.2 Sidelit zone. []- Exception 1:C405.2.4: Spaces where health patient care is directly provided. []- Exception 2:C405.2.4: Lighting required to have specific application controls. []- Exception 3:C405.2.4: Sidelit zones on first floor in Group A-2 and M occupancies. []- Exception 4:C405.2.4: New buildings having total connected lighting power <= the adjusted interior lighting powered allowance (LPA adj, refer to section details and formula). []- Exception 5:C405.2.4: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6074 Wattage	C405.2.5	Interior Lighting	Additional interior lighting power allowed for special functions per the approved lighting plans and is automatically controlled and separated from general lighting. []- Exception 1:C405.7: Air-over electric motors. []- Exception 2:C405.7: Component sets of an electric motor. []- Exception 3:C405.7: Liquid-cooled electric motors. []- Exception 4:C405.7: Submersible electric motors. []- Exception 5:C405.7: Inverter-only electric motors. []- Exception 6:C405.7: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6077 Controls	C405.2.7	Exterior Lighting	Automatic lighting controls for exterior lighting installed. Controls will be daylight controlled, set based on business operation time-of-day, or reduce connected lighting > 50%. []- Exception 1:C405.2.7: Lighting for covered vehicle entrances and exits from buildings and parking structures where required for eye adaptation []- Exception 2:C405.2.7: Lighting controlled from within dwelling units []- Exception 3:C405.2.7: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6131 Wattage	C405.4.1	Exterior Lighting	Exterior lighting power is consistent with what is shown on the approved lighting plans, demonstrating proposed watts are less than or equal to allowed watts.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6132 Mandatory Addit	C406.10	Project	Energy Monitoring - the building is equipped with an energy management system to monitor, record, and report energy consumption for electrical energy, by end-use category, contain meters, a data acquisition system and employ graphical reports.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6133 Mandatory Addit	C406.11	Project	Fault Detection and Diagnostics - a fault detection and diagnostics system installed to monitor the HVAC operation and performance. Includes monitoring sensors and devices, sampling every 15 minutes, automatically report faults and provide recommendations for repair, and transmit recommendations to local authorized personnel.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6134 Mandatory Addit	C406.12	Project	Efficient Kitchen Equipment - the commercial kitchen has at least one fryer with all fryers, dishwashers, steam cookers and ovens complying with performance requirements of Tables C406.12(1) through C406.12(4).	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6185 Mandatory Addit	C406.2	Project	Equipment shall exceed the minimum efficiency requirements listed in Tables C403.2.3(1) through C403.2.3(7) by 10 %, in addition to the requirements of Section C403	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6135 Mandatory Addit	C406.2.1	Project	5% heating efficiency improvement - all HVAC and Plant heating equipment is 5% more efficient than required by 2021 IECC.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6136 Mandatory Addit	C406.2.2	Project	5% cooling efficiency improvement - all HVAC and Plant cooling equipment is 5% more efficient than required by 2021 IECC.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6137 Mandatory Addit	C406.2.3	Project	10% heating efficiency improvement - all HVAC and Plant heating equipment is 10% more efficient than required by 2021 IECC.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6138 Mandatory Addit	C406.2.4	Project	10% cooling efficiency improvement - all HVAC and Plant cooling equipment is 10% more efficient than required by 2021 IECC.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6139 Mandatory Addit	C406.3	Project	Reduced lighting power - this credit specifies that the connected lighting power is <= 10% more efficient than 2021 IECC requirements.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6140 Mandatory Addit	C406.4	Project	Enhanced Digital Lighting Controls - Interior lighting has the following enhanced lighting controls in accordance with Sections C405.2.1 through C405.2.3, Luminaires capable of continuous dimming and being addressed individually, at least 8 luminaires controlled in combination in a daylight zone, digital control system for fixtures with load shedding or occupancy sensors, Sequence of Operations documentation, and functional testing per Section C408.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6143 Mandatory Addit	C406.5	Project	On-site renewable energy credits - on-site renewable energy system supplies at least 1.71 Btuh or 0.5 watts per square foot of conditioned floor area OR provides at least 2 percent of the energy used within the building for mechanical and service water heating equipment and lighting regulated in Chapter 4.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6145 Mandatory Addit	C406.7.1	Project	Reduced energy use in service water heating - the hot water system contains waste heat recovery from service hot water, heat-recovery chillers, building equipment or process equipment or on-site renewable energy for water heating.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6146 Mandatory Addit	C406.7.3	Project	Reduced energy use in service water heating - the hot water heating system shall have a capacity weighted average fossil fuel water heating efficiency at least 95 thermal efficiency or 0.95 EF.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6147 Mandatory Addit	C406.7.4	Project	Reduced energy use in service water heating - the hot water system is served by heat pump water heaters with a minimum Energy Factor of 3.0. The heat pump does not draw conditioned air from within the building.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6148 Mandatory Addit	C406.8	Project	Enhanced envelope performance - the building thermal envelope UA value is >= 15% better than the total UA of the envelope specified by Section C402.1.5.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6149 Mandatory Addit	C406.9	Project	Reduced air infiltration energy - the measured air-leakage rate of the building envelope is lower than 0.25 cfm/ft2. Comprehensive report documentation will be submitted to the code official and the building owner. []- Exception 1:C406.9: Building is greater than 250,000 square feet.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6083 HVAC	C408.2.2.1	Mechanical	Air outlets and zone terminal devices have means for air balancing. []- Exception 1:C408.2.2.1: Fans with fan motors of 1 hp (0.74 kW) or less. []- Exception 2:C408.2.2.1: Where throttling results in no greater than 1/3 hp fan horsepower draw above that required if the fan speed were adjusted []- Exception 3:C408.2.2.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6153 Testing	C408.2.3.2	Mechanical	HVAC and service water heating control systems have been tested to ensure proper operation, calibration and adjustment of controls.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6104 SYSTEM_SPEC	Table_C403.2.3b	Mechanical	Heat Rejection Equipment - Propeller or Axial Fan Open-Circuit Cooling Tower: Minimum Efficiency Requirement >=40.2 gpm/hp .	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6105 SYSTEM_SPEC	Table_C403.2.3b	Mechanical	Heat Rejection Equipment - Centrifugal Fan Open-Circuit Cooling Tower: Minimum Efficiency Requirement >=20.0 gpm/hp.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6106 SYSTEM_SPEC	Table_C403.2.3c	Mechanical	Heat Rejection Equipment - Propeller or Axial Fan Closed-Circuit Cooling Tower: Minimum Efficiency Requirement >=16.1 gpm/hp.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6109 SYSTEM_SPEC	Table_C403.2.3c	Mechanical	Heat Rejection Equipment - Centrifugal Fan Closed-Circuit Cooling Tower: Minimum Efficiency Requirement >=7.0 gpm/hp	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6186 SYSTEM_SPEC	Table_C403.2.3d	Mechanical	Heat Rejection Equipment - Propeller or Axial Fan Dry Coolers (air-cooled fluid coolers): Minimum Efficiency Requirement >= 4.5 gpm/hp	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6111 SYSTEM_SPEC	Table_C403.2.3h	Mechanical	Heat Rejection Equipment - Propeller or Axial Evaporative Condenser: Minimum Efficiency Requirement >=134 kBtu/h-hp w/ Ammonia test fluid.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6112 SYSTEM_SPEC	Table_C403.2.3h	Mechanical	Heat Rejection Equipment - Centrifugal Evaporative Condenser: Minimum Efficiency Requirement >=110 kBtu/h-hp w/ Ammonia test fluid.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6117 SYSTEM_SPEC	Table_C403.2.3h	Mechanical	Heat Rejection Equipment - Propeller or Axial Evaporative Condenser: Minimum Efficiency Requirement >=160 kBtu/h-hp w/ R-448A test fluid.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6119 SYSTEM_SPEC	Table_C403.2.3h	Mechanical	Heat Rejection Equipment - Centrifugal Evaporative Condenser: Minimum Efficiency Requirement ≥ 137 kBtu/h-hp w/ R-448A test fluid.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6121 SYSTEM_SPEC	Table_C403.2.3h	Mechanical	Heat Rejection Equipment - Air-Cooled Condensers: Minimum Efficiency Requirement ≥ 176 kBtu/h-hp	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. To be checked by Inspector at Project Completion and Prior to Issuance of Certificate of Occupancy						
6041 Fenestration	C402.4.2.2	Envelope	Skylights in office, storage, automotive service, manufacturing, non-refrigerated warehouse, retail store, and distribution/sorting area have a measured haze value < 90 percent tested per ASTM D1003 unless designed to exclude direct sunlight. []- Exception 1:C402.4.2.2: Skylights designed to exclude direct sunlight entering the occupied space by the use of fixed or automated baffles, geometry of skylight and well, or optical diffusers. []- Exception 2:C402.4.2.2: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6179 Post Constructic	C405.1	Project	At least 90% of dwelling unit permanently installed lighting shall have lamp efficacy ≤ 65 lm/W or luminaires with efficacy ≤ 45 lm/W or comply with C405.2.4 or C405.3. []- Exception 1:C405.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6180 Post Constructic	C405.11, C405.11.1	Project	50% of 15/20 amp receptacles installed in enclosed offices, conference rooms, copy rooms, break rooms, classrooms and workstations and $< 25\%$ of branch circuit feeders for modular furniture will have automatic receptacle control in accordance with C405.11.1. []- Exception 1:C405.11_C405.11.1: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6181 Post Constructic	C405.12	Project	Buildings with gross conditioned floor area $\geq 25,000$ ft ² will be equipped with a energy monitoring system in compliance with C405.12.1 through C405.12.5. []- Exception 1:C405.12: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6079 Post Constructic	C405.5.3	Project	Total voltage drop across the combination of feeders and branch circuits $\leq 5\%$. []- Exception 1:C405.5.3: Requirement does not apply.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6073 Post Constructic	C405.6	Project	<p>Low-voltage dry-type distribution electric transformers meet the minimum efficiency requirements of Table C405.6.</p> <p>[]- Exception 1:C405.6: Transformers meet the Energy Policy Act of 2005 special purposes exclusions.</p> <p>[]- Exception 2:C405.6: Transformers meet the Energy Policy Act of 2005 non-general purpose exclusions.</p> <p>[]- Exception 3:C405.6: Transformers meet the Energy Policy Act of 2005 exclusions with multiple voltage taps where the highest tap is >= 20% more than the lowest tap.</p> <p>[]- Exception 4:C405.6: Drive transformers.</p> <p>[]- Exception 5:C405.6: Rectifier transformers.</p> <p>[]- Exception 6:C405.6: Auto-transformers.</p> <p>[]- Exception 7:C405.6: Uninterruptible power system transformers.</p> <p>[]- Exception 8:C405.6: Impedance transformers.</p> <p>[]- Exception 9:C405.6: Regulating transformers.</p> <p>[]- Exception 10:C405.6: Sealed and nonventilating transformers.</p> <p>[]- Exception 11:C405.6: Machine tool transformers.</p> <p>[]- Exception 12:C405.6: Welding transformers.</p> <p>[]- Exception 13:C405.6: Grounding transformers.</p> <p>[]- Exception 14:C405.6: Testing transformers.</p> <p>[]- Exception 15:C405.6: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6075 Post Constructic	C405.7	Project	<p>Electric motors meet the minimum efficiency requirements of Tables C405.7(1) through C405.7(4). Efficiency verified through certification under an approved certification program or the equipment efficiency ratings shall be provided by motor manufacturer (where certification programs do not exist).</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6078 Post Constructic	C405.8.1, C405.8.2	Project	<p>Escalators and moving walks comply with ASME A17.1/CSA B44 and have automatic controls configured to reduce speed to the minimum permitted speed in accordance with ASME A17.1/CSA B44 or applicable local code when not conveying passengers.</p> <p>[]- Exception 1:C405.8.1_C405.8.2: A variable voltage drive system that reduces operating voltage in response to light loading is installed.</p> <p>[]- Exception 2:C405.9.1_C405.9.2: Requirement does not apply.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6150 Post Constructic	C408.1.1	Project	<p>Building operations and maintenance documents will be provided to the owner. Documents will cover manufacturers' information, specifications, programming procedures and means of illustrating to owner how building, equipment and systems are intended to be installed, maintained, and operated.</p>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

6151 Post Constructic	C408.2.1	Mechanical	Commissioning plan developed by registered design professional or approved agency.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6152 Post Constructic	C408.2.3.1	Mechanical	HVAC equipment, systems and system-to-system relationships have been tested to ensure proper operation. []- Exception 1:C408.2.3.1: Unitary or packaged HVAC equipment without supply air economizers.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6154 Post Constructic	C408.2.3.3	Mechanical	Economizers have been tested to ensure proper operation.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6156 Post Constructic	C408.2.4	Mechanical	Preliminary commissioning report completed and certified by registered design professional or approved agency.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6176 Post Constructic	C408.2.5	Mechanical	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6018 Post Constructic	C408.2.5.2	Mechanical	Furnished Operation and Maintenance manuals for HVAC systems within 90 days of system acceptance.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6182 Post Constructic	C408.2.5.3	Mechanical	An air and/or hydronic system balancing report is provided for HVAC systems.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6183 Post Constructic	C408.2.5.4	Mechanical	Final commissioning report due to building owner within 90 days of receipt of certificate of occupancy.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6184 Post Constructic	C408.3	Interior Lighting	Lighting systems have been tested to ensure proper calibration, adjustment, programming, and operation.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6177 Post Constructic	C408.3.2	Interior Lighting	Furnished as-built drawings for electric power systems within 90 days of system acceptance.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6017 Post Constructic	C408.3.2.2	Interior Lighting	Furnished operation and maintenance manual for lighting equipment and lighting controls provided to the building owner or designated representative.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

EnergyGaugeSummit® 8.0
INPUT DATA REPORT

Project Information

Project Name: Aspen

Project Title: Aspen Pest Control

Address: 215 SW Windswept GL

State: FL

Zip: 32024

Owner: Aspen Pest Control

Orientation: 0 Deg Clockwise. Walls &

Windows will be rotated

Building Type: Office accordingly

Building Classification: New Finished building

No.of Stories: 1

GrossArea: 2400 SF

Zones

No	Acronym	Description	Type	Area [sf]	Multiplier	Total Area [sf]	
1	Office	Office	CONDITIONED	2400.0	1	2400.0	<input type="checkbox"/>

Spaces

No	Acronym	Description	Type	Depth [ft]	Width [ft]	Height [ft]	Multi plier	Total Area [sf]	Total Volume [cf]
----	---------	-------------	------	---------------	---------------	----------------	----------------	--------------------	----------------------

In Zone: Office										
1	Lobby	Lobby	Lobby (General) - Reception and Waiting	1.00	110.00	9.00	1	110.0	990.0	<input type="checkbox"/>
2	Conference	Conference	Conference/meeting (Multiple Functions)	1.00	196.00	9.00	1	196.0	1764.0	<input type="checkbox"/>
3	Office 1	Office 1	Office - Enclosed	1.00	131.00	9.00	1	131.0	1179.0	<input type="checkbox"/>
4	Corridor	Corridor	Office - Enclosed	1.00	95.00	9.00	1	95.0	855.0	<input type="checkbox"/>
5	Office 2	Office 2	Office - Enclosed	1.00	108.00	9.00	1	108.0	972.0	<input type="checkbox"/>
6	Office 3	Office 3	Office - Enclosed	1.00	169.00	9.00	1	169.0	1521.0	<input type="checkbox"/>
7	Storage	Storage	Storage & Warehouse - Bulky Active Storage	1.00	1591.00	12.00	1	1591.0	19092.0	<input type="checkbox"/>

Lighting							
No	Type	Category	No. of Luminaires	Watts per Luminaire	Power [W]	Control Type	
In Zone: Office							
In Space: Lobby							
1	LED	General Lighting	2	13	26	Occupant Sensor (50%)-Occupant Sensor (50%) Occupant Sensor Auto Full OFF-Occupant Sensor Auto Full OFF	<input type="checkbox"/>
2	LED	Exit Sign	1	5	5	None	<input type="checkbox"/>
In Space: Conference							
1	LED	General Lighting	2	41	82	Manual (Local Control)-Manual (Local Control) Occupancy Sensor - Manual ON only-Occupancy Sensor - Manual ON only Occupant Sensor Auto Full OFF-Occupant Sensor Auto Full OFF	<input type="checkbox"/>
In Space: Office 1							

In Space: Corridor	1	LED	General Lighting	2	41	82	Manual (Local Control)-Manual (Local Control) Occupancy Sensor - Manual ON only-Occupancy Sensor - Manual ON only Occupant Sensor Auto Full OFF-Occupant Sensor Auto Full OFF	<input type="checkbox"/>
	1	LED	General Lighting	2	41	82	Manual (Local Control)-Manual (Local Control) Occupancy Sensor - Manual ON only-Occupancy Sensor - Manual ON only Occupant Sensor Auto Full OFF-Occupant Sensor Auto Full OFF	<input type="checkbox"/>
	2	LED	Exit Sign	1	5	5	None	<input type="checkbox"/>
	1	LED	General Lighting	2	41	82	Manual (Local Control)-Manual (Local Control) Occupancy Sensor - Manual ON only-Occupancy Sensor - Manual ON only Occupant Sensor Auto Full OFF-Occupant Sensor Auto Full OFF	<input type="checkbox"/>
In Space: Office 2								
In Space: Office 3	1	LED	General Lighting	2	41	82	Manual (Local Control)-Manual (Local Control) Occupancy Sensor - Manual ON only-Occupancy Sensor - Manual ON only Occupant Sensor Auto Full OFF-Occupant Sensor Auto Full OFF	<input type="checkbox"/>
In Space: Storage								

1	LED	General Lighting	8	41	328	Manual (Local Control)-Manual (Local Control) Occupant Sensor Auto OFF (Full or Partial)-Occupant Sensor Auto OFF (Full or Partial) Time-Switch: Auto Full Off or Scheduled Off-Time-Switch: Auto Full Off or Scheduled Off	<input type="checkbox"/>
---	-----	------------------	---	----	-----	--	--------------------------

Walls (Walls will be rotated clockwise by building rotation value)

No	Description	Type	Width [ft]	H (Effec) [ft]	Multi plier	Area [sf]	Orientation	Conductance [Btu/hr. sf. F]	Heat Capacity [Btu/sf.F]	Dens. [lb/cf]	R-Value [h.sf.F/Btu]	
In Zone: Office												
1	North	Metal siding/2x4@24"+R1 1Batt/5/8"Gyp	40.00	9.00	1	360.0	North	0.0920	1.072	19.38	10.9	<input type="checkbox"/>
2	East	Metal siding/2x4@24"+R1 1Batt/5/8"Gyp	60.00	9.00	1	540.0	East	0.0920	1.072	19.38	10.9	<input type="checkbox"/>
3	South	Metal siding/2x4@24"+R1 1Batt/5/8"Gyp	40.00	12.00	1	480.0	South	0.0920	1.072	19.38	10.9	<input type="checkbox"/>

Windows (Windows will be rotated clockwise by building rotation value)

No	Description	Orientation	Shaded	U [Btu/hr sf F]	SHGC	Vis.Tra	W [ft]	H (Effec) [ft]	Multi plier	Total Area [sf]	
In Zone: Office											
In Wall: East											
1	Pr0Zo1Wa1Wi1	East	No	1.2500	0.82	0.76	3.00	5.00	4	60.0	<input type="checkbox"/>
In Wall: North											
1	Pr0Zo1Wa1Wi1	North	No	1.2500	0.82	0.76	3.00	5.00	4	60.0	<input type="checkbox"/>
2	Pr0Zo1Wa1Wi1	North	Yes	1.2500	0.82	0.76	6.00	6.67	1	40.0	<input type="checkbox"/>

Doors

No	Description	Type	Shaded?	Width [ft]	H (Effec) [ft]	Multi plier	Area [sf]	Cond. [Btu/hr. sf. F]	Dens. [lb/cf]	Heat Cap. [Btu/sf. F]	R-Value [h.sf.F/Btu]	
In Zone: Office												
In Wall: East												
1	Pr0Zo1Wa2Dr1	Solid core flush (2.25)	No	3.00	6.67	1	20.0	0.3504	0.00	0.00	2.85	<input type="checkbox"/>
In Wall: South												
1	Pr0Zo1Wa3Dr1	Solid core flush (2.25)	No	3.00	6.67	1	20.0	0.3504	0.00	0.00	2.85	<input type="checkbox"/>
2	Pr0Zo1Wa3Dr2	Solid core flush (2.25)	No	10.00	10.00	1	100.0	0.3504	0.00	0.00	2.85	<input type="checkbox"/>

Roofs

No	Description	Type	Width [ft]	H (Effec) [ft]	Multi plier	Area [sf]	Tilt [deg]	Cond. [Btu/hr. Sf. F]	Heat Cap [Btu/sf. F]	Dens. [lb/cf]	R-Value [h.sf.F/Btu]	
In Zone: Office												
1	Pr0Zo1Rf1	Mtl Bldg Roof/R-19 Batt	60.00	60.00	1	3600.0	0.00	0.0492	1.34	9.49	20.3	<input type="checkbox"/>

Skylights

No	Description	Type	U [Btu/hr sf F]	SHGC	Vis.Trans	W [ft]	H (Effec) [ft]	Multiplier	Area [Sf]	Total Area [Sf]	
In Zone:											
In Roof:											

Floors											
No	Description	Type	Width [ft]	H (Effec) [ft]	Multi plier	Area [sf]	Cond. [Btu/hr. sf. F]	Heat Cap. [Btu/sf. F]	Dens. [lb/cf]	R-Value [h.sf.F/Btu]	
In Zone: Office											
1	Pr0Zo1F11	1 ft. soil, concrete floor, carpet and rubber pad	60.00	40.00	1	2400.0	0.2681	34.00	113.33	3.73	<input type="checkbox"/>

Systems											
AH-1		3 Ton Split System			Constant Volume Air Cooled Split System < 65000 Btu/hr					No. Of Units 1	
Component	Category			Capacity		Efficiency		IPLV			
1	Cooling System			36000.00		14.30		8.00		<input type="checkbox"/>	
2	Heating System			27304.00		1.00				<input type="checkbox"/>	
3	Air Handling System -Supply			1200.00		0.22				<input type="checkbox"/>	
4	Air Distribution System (Sup)					8.00				<input type="checkbox"/>	
5	Air Distribution System (Ret)					8.00				<input type="checkbox"/>	

Plant					
Equipment	Category	Size	Inst.No	Eff.	IPLV

Water Heaters											
W-Heater Description			CapacityCap.Unit	I/P Rt.		Efficiency		Loss			
1	Electric Storage water heater (1 units)		40 [Gal]	5 [kW]		0.9200 [Ef]		Btu/h		<input type="checkbox"/>	

Ext-Lighting

Description	Category	No. of Luminaires	Watts per Luminaire	Area/Len/No. of units [sf/ft/No]	Control Type	Wattage [W]	
1 Ext Light 1	Main entries	5	32	15.00	Photo Sensor control	160.00	<input type="checkbox"/>

Piping

No	Type	Operating Temperature [F]	Insulation Conductivity [Btu-in/h.sf.F]	Nomonal pipe Diameter [in]	Insulation Thickness [in]	Is Runout?	
1	Heating System (Steam, Steam Condensate, & Hot Water)	105.00	0.28	0.75	1.00	No	<input type="checkbox"/>

Fenestration Used

Name	Glass Type	No. of Panels	Glass Conductance [Btu/h.sf.F]	SHGC	VLT	
ASHULSglClrAl lFrm	User Defined	1	1.2500	0.8200	0.7600	<input type="checkbox"/>

Materials Used

Mat No	Acronym	Description	Only R-Value Used	RValue [h.sf.F/Btu]	Thickness [ft]	Conductivity [Btu/h.ft.F]	Density [lb/cf]	SpecificHeat [Btu/lb.F]	
187	Matl187	GYP OR PLAS BOARD,1/2IN	No	0.4533	0.0417	0.0920	50.00	0.2000	<input type="checkbox"/>
178	Matl178	CARPET W/RUBBER PAD	Yes	1.2300					<input type="checkbox"/>
265	Matl265	Soil, 1 ft	No	2.0000	1.0000	0.5000	100.00	0.2000	<input type="checkbox"/>

48	Matl48	6 in. Heavyweight concrete	No	0.5000	0.5000	1.0000	140.00	0.2000	<input type="checkbox"/>
23	Matl23	6 in. Insulation	No	20.0000	0.5000	0.0250	5.70	0.2000	<input type="checkbox"/>
4	Matl4	Steel siding	No	0.0002	0.0050	26.0000	480.00	0.1000	<input type="checkbox"/>
271	Matl271	2x4@24" oc + R11 Batt	No	10.4179	0.2917	0.0280	7.11	0.2000	<input type="checkbox"/>
279	Matl279	Solid core flush (2.25")	Yes	2.8537					<input type="checkbox"/>
94	Matl94	BUILT-UP ROOFING, 3/8IN	No	0.3366	0.0313	0.0930	70.00	0.3500	<input type="checkbox"/>

Constructs Used

No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1055	Metal siding/2x4@24"+R11Batt/5/8"Gyp	No	No	0.09	1.07	19.38	10.9	<input type="checkbox"/>
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	4	Steel siding	0.0050	0.000			<input type="checkbox"/>
	2	271	2x4@24" oc + R11 Batt	0.2917	0.000			<input type="checkbox"/>
	3	187	GYP OR PLAS BOARD,1/2IN	0.0417	0.000			<input type="checkbox"/>
No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]	
1056	Mtl Bldg Roof/R-19 Batt	No	No	0.05	1.34	9.49	20.3	<input type="checkbox"/>
	Layer	Material No.	Material	Thickness [ft]	Framing Factor			
	1	94	BUILT-UP ROOFING, 3/8IN	0.0313	0.000			<input type="checkbox"/>
	2	23	6 in. Insulation	0.5000	0.000			<input type="checkbox"/>

No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]																			
1057	1 ft. soil, concrete floor, carpet and rubber pad	No	No	0.27	34.00	113.33	3.7	<input type="checkbox"/>																		
	<table border="1"> <thead> <tr> <th>Layer</th> <th>Material No.</th> <th>Material</th> <th>Thickness [ft]</th> <th>Framing Factor</th> <th></th> </tr> </thead> <tbody> <tr> <td>1</td> <td>265</td> <td>Soil, 1 ft</td> <td>1.0000</td> <td>0.000</td> <td><input type="checkbox"/></td> </tr> <tr> <td>2</td> <td>48</td> <td>6 in. Heavyweight concrete</td> <td>0.5000</td> <td>0.000</td> <td><input type="checkbox"/></td> </tr> <tr> <td>3</td> <td>178</td> <td>CARPET W/RUBBER PAD</td> <td></td> <td>0.000</td> <td><input type="checkbox"/></td> </tr> </tbody> </table>	Layer	Material No.	Material	Thickness [ft]	Framing Factor		1	265	Soil, 1 ft	1.0000	0.000	<input type="checkbox"/>	2	48	6 in. Heavyweight concrete	0.5000	0.000	<input type="checkbox"/>	3	178	CARPET W/RUBBER PAD		0.000	<input type="checkbox"/>	
Layer	Material No.	Material	Thickness [ft]	Framing Factor																						
1	265	Soil, 1 ft	1.0000	0.000	<input type="checkbox"/>																					
2	48	6 in. Heavyweight concrete	0.5000	0.000	<input type="checkbox"/>																					
3	178	CARPET W/RUBBER PAD		0.000	<input type="checkbox"/>																					
No	Name	Simple Construct	Massless Construct	Conductance [Btu/h.sf.F]	Heat Capacity [Btu/sf.F]	Density [lb/cf]	RValue [h.sf.F/Btu]																			
1058	Solid core flush (2.25)	No	Yes	0.35			2.9	<input type="checkbox"/>																		
	<table border="1"> <thead> <tr> <th>Layer</th> <th>Material No.</th> <th>Material</th> <th>Thickness [ft]</th> <th>Framing Factor</th> <th></th> </tr> </thead> <tbody> <tr> <td>1</td> <td>279</td> <td>Solid core flush (2.25")</td> <td></td> <td>0.000</td> <td><input type="checkbox"/></td> </tr> </tbody> </table>	Layer	Material No.	Material	Thickness [ft]	Framing Factor		1	279	Solid core flush (2.25")		0.000	<input type="checkbox"/>													
Layer	Material No.	Material	Thickness [ft]	Framing Factor																						
1	279	Solid core flush (2.25")		0.000	<input type="checkbox"/>																					

Aspen Pest Control

Location	215 SW Windswept GL Lake City, FL 32024
Building owner	Aspen Pest Control
Program user	Rachel Miller
Company	Go Green Engineering
Comments	
By	Go Green Engineering LLC
Dataset name	C:\Projects\Green Engineering Solutions\2025\Aspen Pest Control\Aspen Pest Control.TRC
Calculation time	03:14 PM on 06/27/2025
TRACE® 700 version	6.3.5
Location	Gainesville, Florida
Latitude	29.0 deg
Longitude	82.0 deg
Time Zone	5
Elevation	155 ft
Barometric pressure	29.7 in. Hg
Air density	0.0756 lb/cu ft
Air specific heat	0.2444 Btu/lb·°F
Density-specific heat product	1.1087 Btu/h·cfm·°F
Latent heat factor	4,880.3 Btu·min/h·cu ft
Enthalpy factor	4.5356 lb·min/hr·cu ft
Summer design dry bulb	96.2 °F
Summer design wet bulb	77.2 °F
Winter design dry bulb	31.0 °F
Summer clearness number	0.95
Winter clearness number	0.95
Summer ground reflectance	0.20
Winter ground reflectance	0.20
Carbon Dioxide Level	400 ppm
Design simulation period	January - December
Cooling load methodology	TETD-TA1
Heating load methodology	UATD



System Checksums

By Go Green Engineering LLC

HP-1

Constant Volume

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16					Mo/Hr: 8 / 17					Mo/Hr: Heating Design					Cooling Heating		
Outside Air: OADB/WB/HR: 96 / 77 / 113					OADB: 94					OADB: 31					SADB	55.0	74.0
Space	Plenum	Net	Percent		Space	Percent				Space Peak	Coil Peak	Percent			Ra Plenum	75.2	68.4
Sens. + Lat.	Sens. + Lat.	Total	Of Total		Sensible	Of Total				Space Sens	Tot Sens	Of Total			Return	75.2	68.4
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)				Btu/h	Btu/h	(%)			Ret/OA	77.5	64.3
Envelope Loads					Envelope Loads					Envelope Loads					Fn MtrTD	0.0	0.0
Skylite Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Fn BldTD	0.0	0.0
Skylite Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Fn Frict	0.0	0.0
Roof Cond	0	3,718	3,718	11	0	0	0	0	0	0	-1,578	12.98	0	0			
Glass Solar	3,249	0	3,249	9	3,725	18	7	0	0	0	0	0.00	0	0			
Glass/Door Cond	1,624	0	1,624	5	1,483	7	7	0	0	-2,685	-2,685	22.08	0	0			
Wall Cond	2,561	857	3,418	10	2,679	13	13	0	0	-1,880	-2,533	20.83	0	0			
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Floor	0	0	0	0	0.00	0	0	0	0	0	0	0.00	0	0			
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0.00	0.00	0.00	0	0			
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0			
Sub Total ==>	7,434	4,574	12,008	34	7,886	37	59	0	0	-4,565	-6,796	55.90	0	0			
Internal Loads					Internal Loads					Internal Loads					AIRFLOWS		
Lights	4,613	0	4,613	13	4,613	22	15	0	0	0	0	0.00	0	0	Cooling Heating		
People	6,500	0	6,500	19	3,250	15	22	0	0	0	0	0.00	0	0	Diffuser	1,124	1,124
Misc	4,613	0	4,613	13	4,613	22	59	0	0	0	0	0.00	0	0	Terminal	1,124	1,124
Sub Total ==>	15,725	0	15,725	45	12,475	59	0	0	0	0	0	0.00	0	0	Main Fan	1,124	1,124
Ceiling Load	919	-919	0	0	827	4	0	0	0	-457	0	0.00	0	0	Sec Fan	0	0
Ventilation Load	0	0	7,275	21	0	0	0	0	0	0	-5,362	44.10	0	0	Nom Vent	124	124
Adj Air Trans Heat	0	0	0	0	0	0	0	0	0	0	0	0	0	0	AHU Vent	124	124
Dehumid. Ov Sizing	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Infil	0	0
Ov/Undr Sizing	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	MinStop/Rh	0	0
Exhaust Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Return	1,000	1,000
Sup. Fan Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Exhaust	0	0
Ret. Fan Heat	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Rm Exh	124	124
Duct Heat Pkup	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Auxiliary	0	0
Underflr Sup Ht Pkup	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Leakage Dwn	0	0
Supply Air Leakage	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0	Leakage Ups	0	0
Grand Total ==>	24,078	3,655	35,009	100.00	21,189	100.00	0	0	0	-5,022	-12,157	100.00	0	0	ENGINEERING CKS		

COOLING COIL SELECTION										AREAS				HEATING COIL SELECTION					
	Total Capacity		Sens Cap.	Coil Airflow	Enter DB/WB/HR			Leave DB/WB/HR			Gross Total		Glass		Capacity	Coil Airflow	Ent	Lvg	
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb			ft²	(%)	MBh	cfm	°F	°F	
Main Clg	2.9	35.0	27.6	1,124	77.5	63.6	66.5	55.0	53.1	57.6	Floor	901			Main Htg	-12.2	1,124	64.3	74.0
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Part	0			Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Int Door	1			Preheat	0.0	0	0.0	0.0
											ExFlr	0							
											Roof	901	0	0	Humidif	0.0	0	0.0	0.0
											Wall	1,158	156	13	Opt Vent	0.0	0	0.0	0.0
											Ext Door	40	0	0	Total	-12.2			
Total	2.9	35.0																	

Room Checksums

By Go Green Engineering LLC

Conference

COOLING COIL PEAK					CLG SPACE PEAK			HEATING COIL PEAK				TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16					Mo/Hr: 8 / 14			Mo/Hr: Heating Design						
Outside Air: OADB/WB/HR: 96 / 77 / 113					OADB: 96			OADB: 31						
Space Sens. + Lat.	Plenum Sens. + Lat.	Net Total	Percent Of Total		Space Sensible	Percent Of Total		Space Peak	Coil Peak	Percent		Cooling	Heating	
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)		Space Sens	Tot Sens	Of Total				
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)		Btu/h	Btu/h	(%)				
Envelope Loads								Envelope Loads						
Skylite Solar	0	0	0	0	0	0	0	0	0	0.00	0	55.0	73.8	SADB
Skylite Cond	0	0	0	0	0	0	0	0	0	0.00	0	75.4	68.4	Ra Plenum
Roof Cond	0	872	872	8	0	0	0	0	-343	8.89	0	75.4	68.4	Return
Glass Solar	248	0	248	2	279	5	0	0	0	0.00	0	79.1	61.5	Ret/OA
Glass/Door Cond	431	0	431	4	407	8	0	-685	-685	17.75	0	0.0	0.0	Fn MtrTD
Wall Cond	400	132	532	5	456	9	0	-417	-563	14.58	0	0.0	0.0	Fn BldTD
Partition/Door	0	0	0	0	0	0	0	0	0	0.00	0	0.0	0.0	Fn Frict
Floor	0	0	0	0	0.00	0	0	0	0	0.00	0	0.0	0.0	
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
Infiltration	0	0	0	0	0	0	0	0	0	0.00	0			
Sub Total ==>	1,079	1,004	2,083	19	1,142	21	0	-1,103	-1,592	41.22	0			
Internal Loads								Internal Loads						
Lights	1,003	0	1,003	9	1,003	19	0	0	0	0.00	0			
People	4,000	0	4,000	36	2,000	37	0	0	0	0.00	0			
Misc	1,003	0	1,003	9	1,003	19	0	0	0	0.00	0			
Sub Total ==>	6,007	0	6,007	55	4,007	75	0	0	0	0.00	0			
Ceiling Load	214	-214	0	0	197	4	0	-99	0	0.00	0			
Ventilation Load	0	0	2,930	27	0	0	0	0	-2,248	58.23	0			
Adj Air Trans Heat	0		0	0	0	0	0	0	0	0	0			
Dehumid. Ov Sizing			0	0			0	0	0	0.00	0			
Ov/Undr Sizing	0		0	0	0	0	0	0	0	0.00	0			
Exhaust Heat		0	0	0			0	0	0	0.00	0			
Sup. Fan Heat			0	0			0	0	0	0.00	0			
Ret. Fan Heat		0	0	0			0	0	0	0.00	0			
Duct Heat Pkup		0	0	0			0	0	-21	0.55	0			
Underflr Sup Ht Pkup			0	0			0	0	0	0.00	0			
Supply Air Leakage		0	0	0			0	0	0	0.00	0			
Grand Total ==>	7,299	790	11,020	100.00	5,346	100.00	0	-1,202	-3,861	100.00	0			

AIRFLOWS		
	Cooling	Heating
Diffuser	284	284
Terminal	284	284
Main Fan	284	284
Sec Fan	0	0
Nom Vent	52	52
AHU Vent	52	52
Infil	0	0
MinStop/Rh	0	0
Return	232	232
Exhaust	0	0
Rm Exh	52	52
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	18.3	18.3
cfm/ft²	1.45	1.45
cfm/ton	308.87	
ft²/ton	213.43	
Btu/hr-ft²	56.23	-19.70
No. People	8.0	40.8/1000 ft²

COOLING COIL SELECTION										AREAS				HEATING COIL SELECTION					
	Total Capacity		Sens Cap.	Coil Airflow	Enter DB/WB/HR			Leave DB/WB/HR			Gross Total		Glass			Capacity	Coil Airflow	Ent	Lvg
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb			ft²	(%)		MBh	cfm	°F	°F
Main Clg	0.9	11.0	7.5	284	79.1	66.5	78.0	55.0	54.0	60.9	Floor	196			Main Htg	-3.9	284	61.5	73.8
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Part	0			Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Int Door	1			Preheat	0.0	0	0.0	0.0
											ExFlr	0							
											Roof	196	0	0	Humidif	0.0	0	0.0	0.0
											Wall	268	45	17	Opt Vent	0.0	0	0.0	0.0
											Ext Door	0	0	0	Total	-3.9			
Total	0.9	11.0																	

Room Checksums

By Go Green Engineering LLC

Corridor

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16					Mo/Hr: 8 / 16					Mo/Hr: Heating Design							
Outside Air: OADB/WB/HR: 96 / 77 / 113					OADB: 96					OADB: 31							
Space Sens. + Lat.	Plenum Sens. + Lat.	Net Total	Percent Of Total		Space Sensible	Percent Of Total				Space Peak	Coil Peak	Percent					
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)				Space Sens	Tot Sens	Of Total	(%)				
Envelope Loads					Envelope Loads					Envelope Loads							
Skylite Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Skylite Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Roof Cond	0	423	423	21	0	0	0	0	0	0	-166	27.50	0.00	0.00			
Glass Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Glass/Door Cond	95	0	95	5	95	8	0	0	-154	-154	25.49	0.00	0.00	0.00			
Wall Cond	57	36	93	5	57	5	0	0	-38	-63	10.38	0.00	0.00	0.00			
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Floor	0	0	0	0	0.00	0	0	0	0	0	0	0.00	0.00	0.00			
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Sub Total ==>	152	458	611	31	152	12			-193	-383	63.37						
Internal Loads					Internal Loads					Internal Loads							
Lights	486	0	486	25	486	40	0	0	0	0	0	0.00	0.00	0.00			
People	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Misc	486	0	486	25	486	40	0	0	0	0	0	0.00	0.00	0.00			
Sub Total ==>	973	0	973	49	973	79			0	0	0.00						
Ceiling Load	104	-104	0	0	104	8			-48	0	0.00						
Ventilation Load	0	0	396	20	0	0			0	-259	42.88						
Adj Air Trans Heat	0		0	0	0	0			0	0	0						
Dehumid. Ov Sizing			0	0					0	0	0.00						
Ov/Undr Sizing	0		0	0	0	0			0	0	0.00						
Exhaust Heat		0	0	0					0	0	0.00						
Sup. Fan Heat			0	0					0	0	0.00						
Ret. Fan Heat			0	0					0	0	0.00						
Duct Heat Pkup			0	0					38	-6.25	0.00						
Underflr Sup Ht Pkup			0	0					0	0.00	0.00						
Supply Air Leakage		0	0	0					0	0.00	0.00						
Grand Total ==>	1,229	355	1,980	100.00	1,229	100.00			-241	-605	100.00						

	Cooling	Heating
SADB	55.0	73.3
Ra Plenum	75.4	68.4
Return	75.4	68.4
Ret/OA	77.3	65.0
Fn MtrTD	0.0	0.0
Fn BldTD	0.0	0.0
Fn Frict	0.0	0.0

AIRFLOWS		
	Cooling	Heating
Diffuser	65	65
Terminal	65	65
Main Fan	65	65
Sec Fan	0	0
Nom Vent	6	6
AHU Vent	6	6
Infil	0	0
MinStop/Rh	0	0
Return	59	59
Exhaust	0	0
Rm Exh	6	6
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	9.2	9.2
cfm/ft²	0.69	0.69
cfm/ton	395.14	
ft²/ton	575.85	
Btu/hr-ft²	20.84	-6.37
No. People	0.0	0.0/1000 ft²

COOLING COIL SELECTION										AREAS				HEATING COIL SELECTION					
	Total Capacity		Sens Cap.	Coil Airflow	Enter DB/WB/HR			Leave DB/WB/HR			Gross Total		Glass			Capacity	Coil Airflow	Ent	Lvg
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb			ft²	(%)		MBh	cfm	°F	°F
Main Clg	0.2	2.0	1.7	65	77.3	62.5	61.4	55.0	52.0	53.3	Floor	95			Main Htg	-0.6	65	65.0	73.3
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Part	0			Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Int Door	1			Preheat	0.0	0	0.0	0.0
											ExFlr	0							
											Roof	95	0	0	Humidif	0.0	0	0.0	0.0
											Wall	25	0	0	Opt Vent	0.0	0	0.0	0.0
											Ext Door	20	0	0	Total	-0.6			
Total	0.2	2.0																	

Room Checksums

By Go Green Engineering LLC

Lobby

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16					Mo/Hr: 8 / 15					Mo/Hr: Heating Design							
Outside Air: OADB/WB/HR: 96 / 77 / 113					OADB: 96					OADB: 31							
Space Sens. + Lat.	Plenum Sens. + Lat.	Net Total	Percent Of Total		Space Sensible	Percent Of Total				Space Peak	Coil Peak	Percent					
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)				Space Sens	Tot Sens	Of Total	(%)				
Envelope Loads					Envelope Loads					Envelope Loads							
Skylite Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Skylite Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Roof Cond	0	489	489	11	0	0	0	0	0	0	-193	12.06	0.00	0.00			
Glass Solar	199	0	199	5	212	9	0	0	0	0	0	0.00	0.00	0.00			
Glass/Door Cond	345	0	345	8	343	15	0	0	0	-548	-548	34.32	0.00	0.00			
Wall Cond	62	38	99	2	60	3	0	0	0	-67	-110	6.90	0.00	0.00			
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Floor	0	0	0	0	0.00	0	0	0	0	0	0	0.00	0.00	0.00			
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Sub Total ==>	605	527	1,132	26	615	26				-615	-851	53.28					
Internal Loads					Internal Loads					Internal Loads							
Lights	563	0	563	13	563	24	0	0	0	0	0	0.00	0.00	0.00			
People	1,000	0	1,000	23	500	21	0	0	0	0	0	0.00	0.00	0.00			
Misc	563	0	563	13	563	24	0	0	0	0	0	0.00	0.00	0.00			
Sub Total ==>	2,126	0	2,126	50	1,626	69				0	0	0.00					
Ceiling Load	120	-120	0	0	118	5				-56	0	0.00					
Ventilation Load	0	0	1,027	24	0	0				0	-735	46.00					
Adj Air Trans Heat	0		0	0	0	0				0	0	0					
Dehumid. Ov Sizing			0	0						0	0	0.00					
Ov/Undr Sizing	0		0	0	0	0				0	0	0.00					
Exhaust Heat		0	0	0						0	0	0.00					
Sup. Fan Heat			0	0						0	0	0.00					
Ret. Fan Heat		0	0	0						0	0	0.00					
Duct Heat Pkup		0	0	0						0	0	0.00					
Underflr Sup Ht Pkup			0	0						0	0	0.00					
Supply Air Leakage		0	0	0						0	0	0.00					
Grand Total ==>	2,851	407	4,286	100.00	2,360	100.00				-671	-1,598	100.00					

	Cooling	Heating
SADB	55.0	74.8
Ra Plenum	75.4	68.4
Return	75.4	68.4
Ret/OA	78.2	63.3
Fn MtrTD	0.0	0.0
Fn BldTD	0.0	0.0
Fn Frict	0.0	0.0

AIRFLOWS		
	Cooling	Heating
Diffuser	125	125
Terminal	125	125
Main Fan	125	125
Sec Fan	0	0
Nom Vent	17	17
AHU Vent	17	17
Infil	0	0
MinStop/Rh	0	0
Return	108	108
Exhaust	0	0
Rm Exh	17	17
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	13.6	13.6
cfm/ft²	1.14	1.14
cfm/ton	350.55	
ft²/ton	308.00	
Btu/hr-ft²	38.96	-14.53
No. People	2.0	18.2/1000 ft²

COOLING COIL SELECTION										AREAS				HEATING COIL SELECTION				
	Total Capacity		Sens Cap.	Coil Airflow	Enter DB/WB/HR		Leave DB/WB/HR			Gross Total	Glass			Capacity	Coil Airflow	Ent	Lvg	
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb	ft²	(%)		MBh	cfm	°F	°F	
Main Clg	0.4	4.3	3.2	125	78.2	64.8	70.9	55.0	53.4	58.8	Floor	110		Main Htg	-1.6	125	63.3	74.8
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Part	0		Aux Htg	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Int Door	1		Preheat	0.0	0	0.0	0.0
											ExFlr	0						
Total	0.4	4.3									Roof	110	0	Humidif	0.0	0	0.0	0.0
											Wall	80	36	Opt Vent	0.0	0	0.0	0.0
											Ext Door	0	0	Total	-1.6			

Room Checksums

By Go Green Engineering LLC

Office 1

COOLING COIL PEAK					CLG SPACE PEAK			HEATING COIL PEAK				TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 12					Mo/Hr: 8 / 11			Mo/Hr: Heating Design						
Outside Air: OADB/WB/HR: 91 / 74 / 97					OADB: 88			OADB: 31						
Space Sens. + Lat.	Plenum Sens. + Lat.	Net Total	Percent Of Total		Space Sensible	Percent Of Total		Space Peak	Coil Peak	Percent		Cooling	Heating	
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)		Space Sens	Tot Sens	Of Total				
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)		Btu/h	Btu/h	(%)				
Envelope Loads					Envelope Loads			Envelope Loads						
Skylite Solar	0	0	0	0	0	0	0	0	0	0.00	0	55.0	73.7	SADB
Skylite Cond	0	0	0	0	0	0	0	0	0	0.00	0	74.3	68.4	Ra Plenum
Roof Cond	0	367	367	8	0	0	0	0	-229	15.11	0	74.3	68.4	Return
Glass Solar	699	0	699	16	908	29	0	0	0	0.00	0	75.6	65.5	Ret/OA
Glass/Door Cond	105	0	105	2	85	3	0	-228	-228	15.04	0	0.0	0.0	Fn MtrTD
Wall Cond	542	163	705	16	475	15	0	-391	-509	33.48	0	0.0	0.0	Fn BldTD
Partition/Door	0	0	0	0	0	0	0	0	0	0.00	0	0.0	0.0	Fn Frict
Floor	0	0	0	0	0.00	0	0	0	0	0.00	0	0.0	0.0	
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0	0.00	0.00	0.00	0			
Infiltration	0	0	0	0	0	0	0	0	0	0.00	0			
Sub Total ==>	1,346	530	1,876	43	1,468	47	0	-619	-967	63.63	0			
Internal Loads					Internal Loads			Internal Loads						
Lights	671	0	671	15	671	21	0	0	0	0.00	0			
People	500	0	500	11	250	8	0	0	0	0.00	0			
Misc	671	0	671	15	671	21	0	0	0	0.00	0			
Sub Total ==>	1,841	0	1,841	42	1,591	51	0	0	0	0.00	0			
Ceiling Load	94	-94	0	0	67	2	0	-66	0	0.00	0			
Ventilation Load	0	0	635	15	0	0	0	0	-562	37.00	0			
Adj Air Trans Heat	0		0	0	0	0	0	0	0	0	0			
Dehumid. Ov Sizing			0	0			0	0	0	0.00	0			
Ov/Undr Sizing	0		0	0	0	0	0	0	0	0.00	0			
Exhaust Heat		0	0	0			0	0	0	0.00	0			
Sup. Fan Heat			0	0			0	0	0	0.00	0			
Ret. Fan Heat		0	0	0			0	0	0	0.00	0			
Duct Heat Pkup		0	0	0			10	-0.63	0	0.00	0			
Underflr Sup Ht Pkup			0	0			0	0	0	0.00	0			
Supply Air Leakage		0	0	0			0	0	0	0.00	0			
Grand Total ==>	3,281	436	4,352	100.00	3,127	100.00	0	-686	-1,519	100.00	0			

AIRFLOWS		
	Cooling	Heating
Diffuser	166	166
Terminal	166	166
Main Fan	166	166
Sec Fan	0	0
Nom Vent	13	13
AHU Vent	13	13
Infil	0	0
MinStop/Rh	0	0
Return	153	153
Exhaust	0	0
Rm Exh	13	13
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	7.8	7.8
cfm/ft²	1.27	1.27
cfm/ton	457.47	
ft²/ton	361.22	
Btu/hr-ft²	33.22	-11.60
No. People	1.0	7.6/1000 ft²

COOLING COIL SELECTION										AREAS			HEATING COIL SELECTION			
	Total Capacity		Sens Cap.	Coil Airflow	Enter DB/WB/HR		Leave DB/WB/HR			Gross Total	Glass		Capacity	Coil Airflow	Ent	Lvg
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb	ft²	(%)	MBh	cfm	°F	°F
Main Clg	0.4	4.4	3.8	166	75.6	61.8	61.2	55.0	52.8	56.3	Floor	131	-1.5	166	65.5	73.7
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Part	0	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Int Door	1	0.0	0	0.0	0.0
											ExFlr	0				
Total	0.4	4.4									Roof	131	0.0	0	0.0	0.0
											Wall	216	15	0	0.0	0.0
											Ext Door	0	0	0		
											Total	-1.5				

Room Checksums

By Go Green Engineering LLC

Office 2

COOLING COIL PEAK					CLG SPACE PEAK			HEATING COIL PEAK				TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 17					Mo/Hr: 8 / 18			Mo/Hr: Heating Design						
Outside Air: OADB/WB/HR: 94 / 77 / 111					OADB: 92			OADB: 31						
Space Sens. + Lat.	Plenum Sens. + Lat.	Net Total	Percent Of Total		Space Sensible	Percent Of Total		Space Peak	Coil Peak	Percent		Cooling	Heating	
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)		Space Sens	Tot Sens	Of Total				
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)		Btu/h	Btu/h	(%)				
Envelope Loads					Envelope Loads			Envelope Loads						
Skylite Solar	0	0	0	0	0	0	0	0	0	0.00	0	55.0	73.6	SADB
Skylite Cond	0	0	0	0	0	0	0	0	0	0.00	0	75.3	68.4	Ra Plenum
Roof Cond	0	452	452	10	0	0	0	0	-189	12.70	0	75.3	68.4	Return
Glass Solar	903	0	903	19	960	30	0	0	0	0.00	0	76.6	65.8	Ret/OA
Glass/Door Cond	138	0	138	3	128	4	0	-228	-228	15.34	0	0.0	0.0	Fn MtrTD
Wall Cond	682	203	884	19	693	21	0	-404	-526	35.29	0	0.0	0.0	Fn BldTD
Partition/Door	0	0	0	0	0	0	0	0	0	0.00	0	0.0	0.0	Fn Frict
Floor	0	0	0	0	0.00	0	0	0	0	0.00	0	0.0	0.0	
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0	0.00	0.00	0.00	0			
Infiltration	0	0	0	0	0	0	0	0	0	0.00	0			
Sub Total ==>	1,723	654	2,377	50	1,781	55	0	-633	-943	63.32	0			
Internal Loads					Internal Loads			Internal Loads						
Lights	553	0	553	12	553	17	0	0	0	0.00	0			
People	500	0	500	11	250	8	0	0	0	0.00	0			
Misc	553	0	553	12	553	17	0	0	0	0.00	0			
Sub Total ==>	1,606	0	1,606	34	1,356	42	0	0	0	0.00	0			
Ceiling Load	112	-112	0	0	100	3	0	-55	0	0.00	0			
Ventilation Load	0	0	736	16	0	0	0	0	-519	34.83	0			
Adj Air Trans Heat	0		0	0	0	0	0	0	0	0	0			
Dehumid. Ov Sizing			0	0			0	0	0	0.00	0			
Ov/Undr Sizing	0		0	0	0	0	0	0	0	0.00	0			
Exhaust Heat		0	0	0			0	0	0	0.00	0			
Sup. Fan Heat			0	0			0	0	0	0.00	0			
Ret. Fan Heat		0	0	0			0	0	0	0.00	0			
Duct Heat Pkup		0	0	0			0	0	0	0.00	0			
Underflr Sup Ht Pkup			0	0			0	0	0	0.00	0			
Supply Air Leakage		0	0	0			0	0	0	0.00	0			
Grand Total ==>	3,441	542	4,719	100.00	3,237	100.00	0	-688	-1,490	100.00	0			

AIRFLOWS		
	Cooling	Heating
Diffuser	172	172
Terminal	172	172
Main Fan	172	172
Sec Fan	0	0
Nom Vent	12	12
AHU Vent	12	12
Infil	0	0
MinStop/Rh	0	0
Return	160	160
Exhaust	0	0
Rm Exh	12	12
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	7.0	7.0
cfm/ft²	1.59	1.59
cfm/ton	436.73	
ft²/ton	274.65	
Btu/hr-ft²	43.69	-13.79
No. People	1.0	9.3/1000 ft²

COOLING COIL SELECTION										AREAS			HEATING COIL SELECTION			
	Total Capacity	Sens Cap.	Coil Airflow	Enter DB/WB/HR			Leave DB/WB/HR			Gross Total	Glass		Capacity	Coil Airflow	Ent	Lvg
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb	ft²	(%)	MBh	cfm	°F	°F
Main Clg	0.4	4.7	4.0	172	76.6	62.4	62.2	55.0	53.0	57.1	Floor	108	-1.5	172	65.8	73.6
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Part	0	0.0	0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0	Int Door	1	0.0	0	0.0	0.0
											ExFlr	0				
Total	0.4	4.7									Roof	108	0.0	0	0.0	0.0
											Wall	223	15	0	0.0	0.0
											Ext Door	0	0	0		
											Total	-1.5				

Room Checksums

By Go Green Engineering LLC

Office 3

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 17					Mo/Hr: 6 / 18					Mo/Hr: Heating Design							
Outside Air: OADB/WB/HR: 94 / 77 / 111					OADB: 90					OADB: 31							
Space Sens. + Lat.	Plenum Sens. + Lat.	Net Total	Percent Of Total		Space Sensible	Percent Of Total				Space Peak	Coil Peak	Percent					
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)				Space Sens	Tot Sens	Of Total	(%)				
Envelope Loads					Envelope Loads					Envelope Loads							
Skylite Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Skylite Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Roof Cond	0	707	707	12	0	0	0	0	0	0	-296	14.32	0	0.00			
Glass Solar	1,200	0	1,200	20	1,366	31	0	0	0	0	0	0.00	0	0.00			
Glass/Door Cond	414	0	414	7	344	8	0	0	0	-685	-685	33.15	0	0.00			
Wall Cond	549	192	741	12	592	13	0	0	0	-381	-517	25.02	0	0.00			
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Floor	0	0	0	0	0.00	0	0	0	0	0	0	0.00	0	0.00			
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0.00	0.00	0.00	0	0.00			
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Sub Total ==>	2,163	899	3,062	51	2,301	52				-1,067	-1,499	72.49					
Internal Loads					Internal Loads					Internal Loads							
Lights	865	0	865	14	865	19	0	0	0	0	0	0.00	0	0.00			
People	500	0	500	8	250	6	0	0	0	0	0	0.00	0	0.00			
Misc	865	0	865	14	865	19	0	0	0	0	0	0.00	0	0.00			
Sub Total ==>	2,230	0	2,230	37	1,980	45				0	0	0.00					
Ceiling Load	176	-176	0	0	158	4				-86	0	0.00					
Ventilation Load	0	0	751	12	0	0				0	-519	25.09					
Adj Air Trans Heat	0		0	0	0	0				0	0	0					
Dehumid. Ov Sizing			0	0						0	0	0.00					
Ov/Undr Sizing	0		0	0	0	0				0	0	0.00					
Exhaust Heat		0	0	0						0	0	0.00					
Sup. Fan Heat			0	0						0	0	0.00					
Ret. Fan Heat		0	0	0						0	0	0.00					
Duct Heat Pkup		0	0	0						-50	2.42						
Underflr Sup Ht Pkup			0	0						0	0	0.00					
Supply Air Leakage		0	0	0						0	0	0.00					
Grand Total ==>	4,569	723	6,043	100.00	4,439	100.00				-1,153	-2,068	100.00					

	Cooling	Heating
SADB	55.0	74.4
Ra Plenum	75.3	68.4
Return	75.3	68.4
Ret/OA	76.2	66.5
Fn MtrTD	0.0	0.0
Fn BldTD	0.0	0.0
Fn Frict	0.0	0.0

AIRFLOWS		
	Cooling	Heating
Diffuser	236	236
Terminal	236	236
Main Fan	236	236
Sec Fan	0	0
Nom Vent	12	12
AHU Vent	12	12
Infil	0	0
MinStop/Rh	0	0
Return	224	224
Exhaust	0	0
Rm Exh	12	12
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	5.1	5.1
cfm/ft²	1.39	1.39
cfm/ton	467.66	
ft²/ton	335.58	
Btu/hr-ft²	35.76	-12.24
No. People	1.0	5.9/1000 ft²

COOLING COIL SELECTION										AREAS			HEATING COIL SELECTION				
	Total Capacity		Sens Cap.	Coil Airflow	Enter DB/WB/HR		Leave DB/WB/HR			Gross Total	Glass		Capacity	Coil Airflow	Ent	Lvg	
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F		ft²	(%)	MBh	cfm	°F	°F	
Main Clg	0.5	6.0	5.3	236	76.2	61.7	59.5	55.0	52.8	169			-2.1	236	66.5	74.4	
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0			0.0	0	0.0	0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	1			0.0	0	0.0	0.0	
										ExFlr	0						
										Roof	169	0	0	0	0.0	0.0	
										Wall	250	45	18	0	0.0	0.0	
										Ext Door	0	0	0	0	0.0	0.0	
Total	0.5	6.0											-2.1				

Room Checksums

By Go Green Engineering LLC

RR1

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16					Mo/Hr: 10 / 15					Mo/Hr: Heating Design							
Outside Air: OADB/WB/HR: 96 / 77 / 113					OADB: 85					OADB: 31							
Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total		Space Sensible	Percent Of Total				Space Peak	Coil Peak	Percent					
Btu/h	Btu/h	Btu/h	(%)		Btu/h	(%)				Space Sens	Tot Sens	Of Total	(%)				
Envelope Loads					Envelope Loads					Envelope Loads							
Skylite Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Skylite Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Roof Cond	0	205	205	16	0	0	0	0	0	0	-81	17.61	0.00	0.00			
Glass Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Glass/Door Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Wall Cond	173	46	219	17	226	31	0	0	0	-116	-148	32.38	0.00	0.00			
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Floor	0	0	0	0	0.00	0	0	0	0	0	0	0.00	0.00	0.00			
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Sub Total ==>	173	251	424	33	226	31	0	0	0	-116	-229	49.99	0.00	0.00			
Internal Loads					Internal Loads					Internal Loads							
Lights	236	0	236	18	236	32	0	0	0	0	0	0.00	0.00	0.00			
People	0	0	0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Misc	236	0	236	18	236	32	0	0	0	0	0	0.00	0.00	0.00			
Sub Total ==>	471	0	471	36	471	64	0	0	0	0	0	0.00	0.00	0.00			
Ceiling Load	50	-50	0	0	38	5	0	0	0	-23	0	0.00	0.00	0.00			
Ventilation Load	0	0	409	31	0	0	0	0	0	0	-259	56.70	0.00	0.00			
Adj Air Trans Heat	0		0	0	0	0	0	0	0	0	0	0	0.00	0.00			
Dehumid. Ov Sizing			0	0			0	0	0	0	0	0.00	0.00	0.00			
Ov/Undr Sizing	0		0	0	0	0	0	0	0	0	0	0.00	0.00	0.00			
Exhaust Heat		0	0	0			0	0	0		0	0.00	0.00	0.00			
Sup. Fan Heat			0	0			0	0	0		0	0.00	0.00	0.00			
Ret. Fan Heat		0	0	0			0	0	0		0	0.00	0.00	0.00			
Duct Heat Pkup		0	0	0			0	0	0		0	0.00	0.00	0.00			
Underflr Sup Ht Pkup			0	0			0	0	0		0	0.00	0.00	0.00			
Supply Air Leakage		0	0	0			0	0	0		0	0.00	0.00	0.00			
Grand Total ==>	694	201	1,304	100.00	735	100.00	0	0	0	-140	-458	100.00	0.00	0.00			

	Cooling	Heating
SADB	55.0	73.2
Ra Plenum	75.4	68.4
Return	75.4	68.4
Ret/OA	78.5	62.7
Fn MtrTD	0.0	0.0
Fn BldTD	0.0	0.0
Fn Frict	0.0	0.0

AIRFLOWS		
	Cooling	Heating
Diffuser	39	39
Terminal	39	39
Main Fan	39	39
Sec Fan	0	0
Nom Vent	6	6
AHU Vent	6	6
Infil	0	0
MinStop/Rh	0	0
Return	33	33
Exhaust	0	0
Rm Exh	6	6
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	15.4	15.4
cfm/ft²	0.85	0.85
cfm/ton	358.76	
ft²/ton	423.25	
Btu/hr-ft²	28.35	-9.95
No. People	0.0	0.0/1000 ft²

COOLING COIL SELECTION										
	Total Capacity	Sens Cap.	Coil Airflow	Enter DB/WB/HR			Leave DB/WB/HR			
	ton	MBh	MBh	cfm	°F	°F	gr/lb	°F	°F	gr/lb
Main Clg	0.1	1.3	1.1	39	78.5	63.1	62.4	55.0	51.6	51.9
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0
Total	0.1	1.3								

AREAS			
	Gross Total	Glass	(%)
		ft²	
Floor	46		
Part	0		
Int Door	1		
ExFlr	0		
Roof	46	0	0
Wall	59	0	0
Ext Door	0	0	0

HEATING COIL SELECTION				
	Capacity	Coil Airflow	Ent	Lvg
	MBh	cfm	°F	°F
Main Htg	-0.5	39	62.7	73.2
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Humidif	0.0	0	0.0	0.0
Opt Vent	0.0	0	0.0	0.0
Total	-0.5			

Room Checksums

By Go Green Engineering LLC

RR2

COOLING COIL PEAK					CLG SPACE PEAK					HEATING COIL PEAK					TEMPERATURES		
Peaked at Time: Mo/Hr: 8 / 16					Mo/Hr: 9 / 15					Mo/Hr: Heating Design							
Outside Air: OADB/WB/HR: 96 / 77 / 113					OADB: 93					OADB: 31							
Space Sens. + Lat.	Plenum Sens. + Lat	Net Total	Percent Of Total (%)		Space Sensible	Percent Of Total (%)				Space Peak Space Sens	Coil Peak Tot Sens	Percent Of Total (%)					
Btu/h	Btu/h	Btu/h			Btu/h					Btu/h	Btu/h						
Envelope Loads					Envelope Loads					Envelope Loads							
Skylite Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Skylite Cond	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Roof Cond	0	205	205	16	0	0	0	0	0	0	-81	14.42	0	0.00			
Glass Solar	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Glass/Door Cond	95	0	95	7	81	11	0	0	0	-154	-154	27.59	0	0.00			
Wall Cond	97	46	143	11	120	17	0	0	0	-65	-97	17.35	0	0.00			
Partition/Door	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Floor	0	0	0	0	0.00	0	0	0	0	0	0	0.00	0	0.00			
Adjacent Floor	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0.00	0.00	0.00	0	0.00			
Infiltration	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Sub Total ==>	192	251	443	34	201	28				-219	-332	59.36					
Internal Loads					Internal Loads					Internal Loads							
Lights	236	0	236	18	236	33	0	0	0	0	0	0.00	0	0.00			
People	0	0	0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Misc	236	0	236	18	236	33	0	0	0	0	0	0.00	0	0.00			
Sub Total ==>	471	0	471	36	471	66				0	0	0.00	0	0.00			
Ceiling Load	50	-50	0	0	46	6	0	0	0	-23	0	0.00	0	0.00			
Ventilation Load	0	0	391	30	0	0	0	0	0	0	-259	46.41	0	0.00			
Adj Air Trans Heat	0		0	0	0	0	0	0	0	0	0	0	0	0.00			
Dehumid. Ov Sizing			0	0			0	0	0	0	0	0.00	0	0.00			
Ov/Undr Sizing	0		0	0	0	0	0	0	0	0	0	0.00	0	0.00			
Exhaust Heat		0	0	0			0	0	0		0	0.00	0	0.00			
Sup. Fan Heat			0	0			0	0	0		0	0.00	0	0.00			
Ret. Fan Heat		0	0	0			0	0	0		0	0.00	0	0.00			
Duct Heat Pkup		0	0	0			0	0	0		0	0.00	0	0.00			
Underflr Sup Ht Pkup			0	0			0	0	0		0	0.00	0	0.00			
Supply Air Leakage		0	0	0			0	0	0		0	0.00	0	0.00			
Grand Total ==>	713	201	1,306	100.00	718	100.00				-243	-559	100.00					

TEMPERATURES		
	Cooling	Heating
SADB	55.0	75.8
Ra Plenum	75.4	68.4
Return	75.4	68.4
Ret/OA	78.6	62.5
Fn MtrTD	0.0	0.0
Fn BldTD	0.0	0.0
Fn Frict	0.0	0.0

AIRFLOWS		
	Cooling	Heating
Diffuser	38	38
Terminal	38	38
Main Fan	38	38
Sec Fan	0	0
Nom Vent	6	6
AHU Vent	6	6
Infil	0	0
MinStop/Rh	0	0
Return	32	32
Exhaust	0	0
Rm Exh	6	6
Auxiliary	0	0
Leakage Dwn	0	0
Leakage Ups	0	0

ENGINEERING CKS		
	Cooling	Heating
% OA	15.8	15.8
cfm/ft²	0.83	0.83
cfm/ton	349.96	
ft²/ton	422.79	
Btu/hr-ft²	28.38	-12.15
No. People	0.0	0.0/1000 ft²

COOLING COIL SELECTION										AREAS				HEATING COIL SELECTION				
Total Capacity	Sens Cap.	Coil Airflow	Enter DB/WB/HR		Leave DB/WB/HR					Gross Total	Glass			CapacityCoil Airflow	Ent	Lvg		
ton MBh	MBh	cfm	°F °F	gr/lb	°F °F	gr/lb	°F °F	gr/lb	°F °F		ft² (%)			MBh cfm	°F	°F		
Main Clg	0.1	1.3	1.1	38	78.6	64.0	66.2	55.0	52.3	54.6				-0.6	38	62.5	75.8	
Aux Clg	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0				0.0	0	0.0	0.0	
Opt Vent	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	0.0	0.0				0.0	0	0.0	0.0	
Total	0.1	1.3																

AREAS			
Floor	46		
Part	0		
Int Door	1		
ExFlr	0		
Roof	46	0	0
Wall	38	0	0
Ext Door	20	0	0

HEATING COIL SELECTION				
Main Htg	-0.6	38	62.5	75.8
Aux Htg	0.0	0	0.0	0.0
Preheat	0.0	0	0.0	0.0
Humidif	0.0	0	0.0	0.0
Opt Vent	0.0	0	0.0	0.0
Total	-0.6			