

DATE 10/27/2005

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000023785

APPLICANT MATT CASON PHONE 386.752.5152
ADDRESS 1531 SW COMMERCIAL GLEN LAKE CITY FL 32025
OWNER SAM DUNCAN PHONE
ADDRESS 461 SW QUAIL RIDGE CT LAKE CITY FL 32024
CONTRACTOR W. STANLEY CRAWFORD PHONE 752.5152
LOCATION OF PROPERTY 90-W TO SR-247-S TO QUAIL RIDGE CT,TR (JUST BEFORE C-240)
LOT IS ON R.

TYPE DEVELOPMENT SFD/UTILITY ESTIMATED COST OF CONSTRUCTION 69950.00
HEATED FLOOR AREA 1399.00 TOTAL AREA 2906.00 HEIGHT 17.80 STORIES 1
FOUNDATION CONC WALLS FRAMED ROOF PITCH 6'12 FLOOR CONC
LAND USE & ZONING A-3 MAX. HEIGHT 35
Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00
NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 11-5S-15-00431-219 SUBDIVISION PINE WIND ESTATES
LOT 19 BLOCK PHASE UNIT 2 TOTAL ACRES 4.01

000000871 RG0042896
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
18"X32'MITERED 05-1078-N BLK JTH Y
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: NOC ON FILE. 1 FOOT ABOVE RD.

Check # or Cash 7379

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by
Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by
Framing date/app. by Rough-in plumbing above slab and below wood floor date/app. by
Electrical rough-in date/app. by Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by
Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by
M/H tie downs, blocking, electricity and plumbing date/app. by Pool date/app. by
Reconnection date/app. by Pump pole date/app. by Utility Pole date/app. by
M/H Pole date/app. by Travel Trailer date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 350.00 CERTIFICATION FEE \$ 14.53 SURCHARGE FEE \$ 14.53
MISC. FEES \$.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ 25.00 TOTAL FEE 479.06
INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Columbia County Building Permit Application

Revised 9-23-04

For Office Use Only Application # 0510-61 Date Received 10/19/05 By LH Permit # 871/ 23785
 Application Approved by - Zoning Official BLK Date 25.10.05 Plans Examiner OK JTH Date 10-26-05
 Flood Zone X Development Permit N/A Zoning A-3 Land Use Plan Map Category A-3
 Comments EH Received 10-25-05 FAB 755-2165

Applicants Name Matt Cason Phone 752-5152
 Address 1531 SW Commercial Glen LC FL 32025
 Owners Name - Sam Duncan Phone 752-5152
 911 Address 461 SW Quail Ridge Ct. LC, FL 32024
 Contractors Name SCCT Phone 752-5152
 Address 1531 SW Commercial Glen LC FL 32025
 Fee Simple Owner Name & Address N/A
 Bonding Co. Name & Address N/A
 Architect/Engineer Name & Address Brian Crawford - First Impressions / Mark Lisowsky
 Mortgage Lenders Name & Address N/A - CASH
 Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progressive Energy
 Property ID Number 11 55 15 00431 219 Estimated Cost of Construction 121,000.00
 Subdivision Name Pine Wind Estates Lot 19 Block Unit 2 Phase
 Driving Directions Hwy 90 W, TL on CR 247, TR on Quail Ridge (Just before CR 240), Lot on Right.

Type of Construction Single Fam/Residential Number of Existing Dwellings on Property 0
 Total Acreage 4.01 Lot Size Do you need a Culvert Permit or Culvert Waiver or Have an Existing Drive
 Actual Distance of Structure from Property Lines - Front 180' Side 82' Side 75' Rear 385'+
 Total Building Height 17'8" Number of Stories 1 Heated Floor Area 1399 Roof Pitch 6/12
PORCHES 787 GARAGE 720 TOTAL 2906

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Stanley Crawford
 Owner Builder or Agent (Including Contractor)

STATE OF FLORIDA
 COUNTY OF COLUMBIA



Sworn to (or affirmed) and subscribed before me


this 19th day of October 2005.


Personally known ✓ or Produced Identification

Stanley Crawford
 Contractor Signature
 Contractors License Number RG-0042896
 Competency Card Number 5627
 NOTARY STAMP/SEAL


Janet L. Cheek
 Notary Signature

called 10-26-05 - MTH-CEU phone #479.06





APPROXIMATE SCALE IN FEET




NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

COLUMBIA
COUNTY,
FLORIDA
(UNINCORPORATED AREAS)

PANEL 225 OF 290

PANEL LOCATION



COMMUNITY-PANEL NUMBER

120070 0225 B

EFFECTIVE DATE:

JANUARY 6, 1988



Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT Version 1.0. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. Further information about National Flood Insurance Program flood hazard maps is available at www.fema.gov/mit/ted.

Prepared by and return to:
Mickie Salter

Home Town Title of North Florida
2744 US Highway 90 West
Lake City, FL 32055
386-754-7175
File Number: 2005-1020
Will Call No.:

Inst: 2005018380 Date: 08/02/2005 Time: 13:39

Doc Stamp-Deed : 252.00

znk DC, P. DeWitt Cason, Columbia County B:1053 P:1808

[Space Above This Line For Recording Data]

Warranty Deed

This Warranty Deed made this 15th day of July, 2005 between Michael J. Opalewski and Brenda Opalewski, husband and wife whose post office address is 397 SW Quail Ridge Ct., Lake City, FL 32024, grantor, and Samuel R. Duncan, a single person whose post office address is 4821 Bethel Creek Dr., Vero Beach, FL 32963-1416, grantee:

(Whenever used herein the terms "grantor" and "grantee" include all the parties to this instrument and the heirs, legal representatives, and assigns of individuals, and the successors and assigns of corporations, trusts and trustees)

Witnesseth, that said grantor, for and in consideration of the sum of TEN AND NO/100 DOLLARS (\$10.00) and other good and valuable considerations to said grantor in hand paid by said grantee, the receipt whereof is hereby acknowledged, has granted, bargained, and sold to the said grantee, and grantee's heirs and assigns forever, the following described land, situate, lying and being in Columbia County, Florida to-wit:

Lot 19, of PINE WIND ESTATES, UNIT NO. II, according to the plat thereof on file in Plat Book 5, page 124, public records of Columbia County, Florida;

Parcel Identification Number: R00431-219

Together with all the tenements, hereditaments and appurtenances thereto belonging or in anywise appertaining,

To Have and to Hold, the same in fee simple forever.

And the grantor hereby covenants with said grantee that the grantor is lawfully seized of said land in fee simple; that the grantor has good right and lawful authority to sell and convey said land; that the grantor hereby fully warrants the title to said land and will defend the same against the lawful claims of all persons whomsoever; and that said land is free of all encumbrances, except taxes accruing subsequent to December 31, 2004.

In Witness Whereof, grantor has hereunto set grantor's hand and seal the day and year first above written.

DoubleTimes

This instrument was Prepared By:
STANLEY CRAWFORD CONSTRUCTION, INC.
1531 S.W. Commercial Glen.
Lake City, Florida 32025

PERMIT NO. _____

TAX FOLIO NO.: _____

NOTICE OF COMMENCEMENT

STATE OF FLORIDA
COUNTY OF COLUMBIA

The undersigned hereby gives notice that improvement will be made to certain real Property, and in accordance with Chapter 713, Florida Statutes, the following information Is provided in this Notice of Commencement.


1. Description of property: Pine Wind Estates Lot 19 Unit 2
2. General description of improvement: Construction of Dwelling
3. Owner information:
Name and address: Samuel E. Duncan
4821 Bethel Creek Dr.
Vero Beach, FL 32963-1416
- b. Interest in property: Fee Simple
- c. Name and address of fee simple title holder (if other Than owner): NONE
4. Contractor: Stanley Crawford Construction, Inc.
1531 S.W. Commercial Glen, Lake City, FL 32025
5. Surety N/A
 - a. Name and address:
 - b. Amount of bond:
6. Lender: N/A
7. Persons within the State of Florida designated by Owner upon whom notices Or other documents may be served as provided by Section 713.13 (1) (a) 7., Florida Statutes : NONE
8. In addition to himself, Owner designates _____ to receive a copy of the Lienor's Notice as provided in section 713.13 (1) (b), Florida Statutes.
9. Expiration date of notice of commencement (the expiration date is 1 year from The date of recording unless a different date is specified).

Sam Duncan

The foregoing instrument was acknowledged before me this 10th day of October, 2005, by Sam Duncan, who are personally known to me and who did not take an oath.


Janet L. Cheek
Notary Public

My Commission Expires: June 25, 2007



MAP OF BOUNDARY SURVEY

SHOWING LOT 19, PINE WIND ESTATES, UNIT 2, ACCORDING TO THE PLAT THEREOF AS RECORDED IN PLAT BOOK 5, PAGES 124 AND 124A, OF THE PUBLIC RECORDS OF COLUMBIA COUNTY, FLORIDA.



COLUMBIA COUNTY 9-1-1 ADDRESSING

263 NW Lake City Ave. * P. O. Box 1787 * Lake City, FL 32056-1787
PHONE: (386) 758-1125 * FAX: (386) 758-1365 * Email: ron_croft@columbiacountyfla.com

Addressing Maintenance

To maintain the Countywide Addressing Policy you must make application for a 9-1-1 Address at the time you apply for a building permit. The established standards for assigning and posting numbers to all principal buildings, dwellings, businesses and industries are contained in Columbia County Ordinance 2001-9. The addressing system is to enable Emergency Service Agencies to locate you in an emergency, and to assist the United States Postal Service and the public in the timely and efficient provision of services to residents and businesses of Columbia County.

DATE ISSUED: October 17, 2005

ENHANCED 9-1-1 ADDRESS:

461 SW QUAIL RIDGE CT (LAKE CITY, FL 32024)

Addressed Location 911 Phone Number: NOT AVAIL.

OCCUPANT NAME: NOT AVAIL.

OCCUPANT CURRENT MAILING ADDRESS: _____

PROPERTY APPRAISER PARCEL NUMBER: 11-5S-15-00431-219

Other Contact Phone Number (If any): _____

Building Permit Number (If known): _____

Remarks: LOT 19 PINE WIND ESTATES UNIT 2 S/D

Address Issued By: _____

Columbia County 9-1-1 Addressing / GIS Department

NOTICE: THIS ADDRESS WAS ISSUED BASED ON LOCATION INFORMATION RECEIVED FROM THE REQUESTER. SHOULD, AT A LATER DATE, THE LOCATION INFORMATION BE FOUND TO BE IN ERROR, THIS ADDRESS IS SUBJECT TO CHANGE.


COLUMBIA COUNTY
9-1-1 ADDRESSING
APPROVED

0510-61

**Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan**
Permit Application Number: 05-1078N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

DUNCAN/CR 05-3134



1 inch = 85 feet


Site Plan Submitted By Paul Lopez Date 10/17/05
Plan Approved ☒ Not Approved ☐ Date 10/25/05

By MM 072 Columbia CPHU

Notes: _____



Clyatt Well Drilling, Inc.
(Established in 1971)
POST OFFICE BOX 180
WORTHINGTON SPRINGS, FLORIDA 32697



Telephone Number (386)496-2488
FAX Number (386)496-4640

June 18, 2002

Columbia County Building Department
Post Office Box 1529
Lake City, Florida 32056

To Whom It May Concern:

As required by building code regulations for Columbia County in order that a building permit can be issued, the following well information is provided with regard to the above-referenced well:

| | |
|------------------------|-----------------------|
| Size of Pump Motor: | 1-1/2 Horse Power |
| Size of Pressure Tank: | 220 Gallon Equivalent |
| Cycle Stop Valve Used: | No |

Should you require any additional information, please do not hesitate to contact us.

Respectfully,

CLYATT WELL DRILLING, INC.

K. Melaine "Red" Clyatt
President

Clyatt Well Drilling, Inc.
(Established in 1971)
POST OFFICE BOX 180
WORTHINGTON SPRINGS, FLORIDA 32697

Telephone Number (386)496-2488
FAX Number (386)496-4640

**PUMP AND TANK SPECIFICATIONS FOR
STANDARD 4" RESIDENTIAL WELLS**

PUMPS

1 Horse Power Submersible Pump
20 Gallons Per Minute
Voltage: 240
Phase: (Single) 1

1.5 Horse Power Submersible Pump
25 Gallons Per Minute
Voltage: 240
Phase: (Single) 1

TANK

WF-255 Captive Air Tank
Capacity 81 Gallons
Equivalent 220 Gallons
Draw Down 25 Gallons

**FLORIDA ENERGY EFFICIENCY CODE
FOR BUILDING CONSTRUCTION**Florida Department of Community Affairs
Residential Whole Building Performance Method A

| | |
|--|---|
| Project Name: <u>DUNCAN</u> Address: _____ City, State: _____ Owner: <u>duncan</u> Climate Zone: <u>North</u> | Builder: <u>STANLEY CRAWFORD HOM</u> Permitting Office: <u>Columbia</u> Permit Number: <u>23785</u> Jurisdiction Number: <u>221000</u> |
|--|---|

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|--------------------------------|-----------------------|------|-------------------------------|--------------------|-----------------------|----------------------------|-------------|-----------------------|----------------------------------|--------------------|--|--------|--|--|--------|--|--|--------------------------|--------------------------------|--|--------|--|--|--------|--|--|--------|--|--|--------|--|--|----------------|--------------------------------|--|--------|--|--|--------|--|--|-------------------------------------|----------------------|--|--------|--|--|---|-----------------|-------------------|--|-------------|--------|--|--------|--|-----------------------|-------------------|--|------------|--------|--|--------|--|-----------|-------------------|--|----------|--------|--|-------------------------|--|---------------------------|--|--------------------------|--|
| <p>1. New construction or existing New <input type="checkbox"/></p> <p>2. Single family or multi-family Single family <input type="checkbox"/></p> <p>3. Number of units, if multi-family 1 <input type="checkbox"/></p> <p>4. Number of Bedrooms 2 <input type="checkbox"/></p> <p>5. Is this a worst case? Yes <input type="checkbox"/></p> <p>6. Conditioned floor area (ft²) 1399 ft² <input type="checkbox"/></p> <p>7. Glass type¹ and area: (Label reqd. by 13-104.4.5 if not default)</p> <table border="0" style="width: 100%;"><tr><td style="width: 30%;">a. U-factor:</td><td style="width: 30%; text-align: center;">Description</td><td style="width: 40%; text-align: center;">Area</td></tr><tr><td>(or Single or Double DEFAULT)</td><td>7a. (Dble Default)</td><td>205.0 ft²</td></tr></table> <p>b. SHGC:</p> <table border="0" style="width: 100%;"><tr><td style="width: 30%;">(or Clear or Tint DEFAULT)</td><td style="width: 30%;">7b. (Clear)</td><td style="width: 40%;">205.0 ft²</td></tr></table> <p>8. Floor types</p> <table border="0" style="width: 100%;"><tr><td style="width: 30%;">a. Slab-On-Grade Edge Insulation</td><td style="width: 30%;">R=4.0, 184.0(p) ft</td><td style="width: 40%;"></td></tr><tr><td>b. N/A</td><td></td><td></td></tr><tr><td>c. N/A</td><td></td><td></td></tr></table> <p>9. Wall types</p> <table border="0" style="width: 100%;"><tr><td style="width: 30%;">a. Frame, Wood, Exterior</td><td style="width: 30%;">R=13.0, 1776.0 ft²</td><td style="width: 40%;"></td></tr><tr><td>b. N/A</td><td></td><td></td></tr><tr><td>c. N/A</td><td></td><td></td></tr><tr><td>d. N/A</td><td></td><td></td></tr><tr><td>e. N/A</td><td></td><td></td></tr></table> <p>10. Ceiling types</p> <table border="0" style="width: 100%;"><tr><td style="width: 30%;">a. Under Attic</td><td style="width: 30%;">R=30.0, 1399.0 ft²</td><td style="width: 40%;"></td></tr><tr><td>b. N/A</td><td></td><td></td></tr><tr><td>c. N/A</td><td></td><td></td></tr></table> <p>11. Ducts</p> <table border="0" style="width: 100%;"><tr><td style="width: 30%;">a. Sup: Unc. Ret: Unc. AH: Interior</td><td style="width: 30%;">Sup. R=6.0, 188.0 ft</td><td style="width: 40%;"></td></tr><tr><td>b. N/A</td><td></td><td></td></tr></table> | a. U-factor: | Description | Area | (or Single or Double DEFAULT) | 7a. (Dble Default) | 205.0 ft ² | (or Clear or Tint DEFAULT) | 7b. (Clear) | 205.0 ft ² | a. Slab-On-Grade Edge Insulation | R=4.0, 184.0(p) ft | | b. N/A | | | c. N/A | | | a. Frame, Wood, Exterior | R=13.0, 1776.0 ft ² | | b. N/A | | | c. N/A | | | d. N/A | | | e. N/A | | | a. Under Attic | R=30.0, 1399.0 ft ² | | b. N/A | | | c. N/A | | | a. Sup: Unc. Ret: Unc. AH: Interior | Sup. R=6.0, 188.0 ft | | b. N/A | | | <p>12. Cooling systems</p> <table border="0" style="width: 100%;"><tr><td style="width: 50%;">a. Central Unit</td><td style="width: 50%;">Cap: 30.0 kBtu/hr</td></tr><tr><td></td><td>SEER: 13.00</td></tr><tr><td>b. N/A</td><td></td></tr><tr><td>c. N/A</td><td></td></tr></table> <p>13. Heating systems</p> <table border="0" style="width: 100%;"><tr><td style="width: 50%;">a. Electric Heat Pump</td><td style="width: 50%;">Cap: 30.0 kBtu/hr</td></tr><tr><td></td><td>HSPF: 7.60</td></tr><tr><td>b. N/A</td><td></td></tr><tr><td>c. N/A</td><td></td></tr></table> <p>14. Hot water systems</p> <table border="0" style="width: 100%;"><tr><td style="width: 50%;">a. LP Gas</td><td style="width: 50%;">Cap: 50.0 gallons</td></tr><tr><td></td><td>EF: 0.66</td></tr><tr><td>b. N/A</td><td></td></tr><tr><td>c. Conservation credits</td><td></td></tr><tr><td colspan="2">(HHR-Heat recovery, Solar</td></tr><tr><td colspan="2">DHP-Dedicated heat pump)</td></tr></table> <p>15. HVAC credits</p> <p>(CF-Ceiling fan, CV-Cross ventilation, HF-Whole house fan, PT-Programmable Thermostat, MZ-C-Multizone cooling, MZ-H-Multizone heating)</p> | a. Central Unit | Cap: 30.0 kBtu/hr | | SEER: 13.00 | b. N/A | | c. N/A | | a. Electric Heat Pump | Cap: 30.0 kBtu/hr | | HSPF: 7.60 | b. N/A | | c. N/A | | a. LP Gas | Cap: 50.0 gallons | | EF: 0.66 | b. N/A | | c. Conservation credits | | (HHR-Heat recovery, Solar | | DHP-Dedicated heat pump) | |
| a. U-factor: | Description | Area | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| (or Single or Double DEFAULT) | 7a. (Dble Default) | 205.0 ft ² | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| (or Clear or Tint DEFAULT) | 7b. (Clear) | 205.0 ft ² | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| a. Slab-On-Grade Edge Insulation | R=4.0, 184.0(p) ft | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| b. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| c. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| a. Frame, Wood, Exterior | R=13.0, 1776.0 ft ² | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| b. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| c. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| d. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| e. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| a. Under Attic | R=30.0, 1399.0 ft ² | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| b. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| c. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| a. Sup: Unc. Ret: Unc. AH: Interior | Sup. R=6.0, 188.0 ft | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| b. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| a. Central Unit | Cap: 30.0 kBtu/hr | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | SEER: 13.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| b. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| c. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| a. Electric Heat Pump | Cap: 30.0 kBtu/hr | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | HSPF: 7.60 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| b. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| c. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| a. LP Gas | Cap: 50.0 gallons | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | EF: 0.66 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| b. N/A | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| c. Conservation credits | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| (HHR-Heat recovery, Solar | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DHP-Dedicated heat pump) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Glass/Floor Area: 0.15

Total as-built points: 17307

Total base points: 22120

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: SUNCOAST INSULATORS**DATE:** 01/29/05

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: _____**DATE:** _____

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL: _____**DATE:** _____

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.
EnergyGauge® (Version: FLRCSB v4.0)

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 86.1

The higher the score, the more efficient the home.

duncan, . . .

| | | | |
|--|--|--|-------------------|
| 1. New construction or existing | New | 12. Cooling systems | |
| 2. Single family or multi-family | Single family | a. Central Unit | Cap: 30.0 kBtu/hr |
| 3. Number of units, if multi-family | 1 | | SEER: 13.00 |
| 4. Number of Bedrooms | 2 | b. N/A | |
| 5. Is this a worst case? | Yes | c. N/A | |
| 6. Conditioned floor area (ft ²) | 1399 ft ² | 13. Heating systems | |
| 7. Glass type ¹ and area: (Label req'd. by 13-104.4.5 if not default) | | a. Electric Heat Pump | Cap: 30.0 kBtu/hr |
| a. U-factor: | Description Area | | HSPF: 7.60 |
| (or Single or Double DEFAULT) | 7a. (Dble Default) 205.0 ft ² | b. N/A | |
| b. SHGC: | 7b. (Clear) 205.0 ft ² | c. N/A | |
| (or Clear or Tint DEFAULT) | | 14. Hot water systems | |
| 8. Floor types | | a. LP Gas | Cap: 50.0 gallons |
| a. Slab-On-Grade Edge Insulation | R-4.0, 184.0(p) ft ² | b. N/A | EF: 0.66 |
| b. N/A | | c. Conservation credits | |
| c. N/A | | (HR-Heat recovery, Solar | |
| 9. Wall types | | DHP-Dedicated heat pump) | |
| a. Frame, Wood, Exterior | R-13.0, 1776.0 ft ² | 15. HVAC credits | |
| b. N/A | | (CF-Ceiling fan, CV-Cross ventilation, | |
| c. N/A | | HF-Whole house fan, | |
| d. N/A | | PT-Programmable Thermostat, | |
| e. N/A | | MZ-C-Multizone cooling, | |
| 10. Ceiling types | | MZ-H-Multizone heating) | |
| a. Under Attic | R=30.0, 1399.0 ft ² | | |
| b. N/A | | | |
| c. N/A | | | |
| 11. Ducts | | | |
| a. Sup: Unc. Ret: Unc. AH: Interior | Sup. R-6.0, 188.0 ft ² | | |
| b. N/A | | | |

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____ Date: _____

Address of New Home: _____ City/FL Zip: _____



**NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStarTM designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.*

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.
EnergyGauge® (Version: FLRCSB v4.0)

SUMMER CALCULATIONS
Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

| BASE | | | | AS-BUILT | | | | | | | |
|---|----------|-------|---------|-------------------------------|-------------------------|-----|----------------------|---------------------------|-------------|---------|--------|
| GLASS TYPES | | | | | | | | | | | |
| .18 X Conditioned X BSPM = Points Floor Area | | | | Type/SC | Overhang Omt Len Hgt | | | Area X SPM X SOF = Points | | | |
| .18 | 1399.0 | 20.04 | 6048.6 | Double, Clear | E | 2.0 | 6.0 | 60.0 | 42.06 | 0.85 | 2140.3 |
| | | | | Double, Clear | N | 2.0 | 6.0 | 38.0 | 19.20 | 0.90 | 656.7 |
| | | | | Double, Clear | S | 2.0 | 6.0 | 9.0 | 35.87 | 0.78 | 250.5 |
| | | | | Double, Clear | W | 2.0 | 6.0 | 98.0 | 36.52 | 0.85 | 3206.6 |
| | | | | As-Built Total: | | | | | 206.0 | 6264.2 | |
| WALL TYPES Area X BSPM = Points | | | | Type | R-Value | | | Area X SPM = Points | | | |
| Adjacent | 0.0 | 0.00 | 0.0 | Frame, Wood, Exterior | 13.0 | | | 1776.0 | 1.50 | 2664.0 | |
| Exterior | 1776.0 | 1.70 | 3019.2 | | | | | | | | |
| Base Total: 1776.0 3019.2 | | | | As-Built Total: | | | | | 1776.0 | 2664.0 | |
| DOOR TYPES Area X BSPM = Points | | | | Type | | | | Area X SPM = Points | | | |
| Adjacent | 0.0 | 0.00 | 0.0 | Exterior Insulated | | | | 72.0 | 4.10 | 295.2 | |
| Exterior | 72.0 | 6.10 | 439.2 | | | | | | | | |
| Base Total: 72.0 439.2 | | | | As-Built Total: | | | | | 72.0 | 295.2 | |
| CEILING TYPES Area X BSPM = Points | | | | Type | R-Value | | | Area X SPM X SCM = Points | | | |
| Under Attic | 1399.0 | 1.73 | 2420.3 | Under Attic | 30.0 | | | 1399.0 | 1.73 X 1.00 | 2420.3 | |
| Base Total: 1399.0 2420.3 | | | | As-Built Total: | | | | | 1399.0 | 2420.3 | |
| FLOOR TYPES Area X BSPM = Points | | | | Type | R-Value | | | Area X SPM = Points | | | |
| Slab | 184.0(p) | -37.0 | -6808.0 | Slab-On-Grade Edge Insulation | 4.0 | | | 184.0(p) | -36.70 | -6752.8 | |
| Raised | 0.0 | 0.00 | 0.0 | | | | | | | | |
| Base Total: -6808.0 | | | | As-Built Total: | | | | | 184.0 | -6752.8 | |
| INFILTRATION Area X BSPM = Points | | | | | | | Area X SPM = Points | | | | |
| 1399.0 10.21 14263.6 | | | | | | | 1399.0 10.21 14263.6 | | | | |

SUMMER CALCULATIONS
Residential Whole Building Performance Method A - Details

| | |
|----------------|-----------|
| ADDRESS: , , , | PERMIT #. |
|----------------|-----------|

| BASE | | | AS-BUILT | | | | | | |
|-----------------------------|---------------------|------------------|-----------------------------------|-------------|------------------------------------|---------------------|---------------------|------------------|--|
| Summer Base Points: 18400.9 | | | Summer As-Built Points: 19164.7 | | | | | | |
| Total Summer Points | X System Multiplier | = Cooling Points | Total Component (System - Points) | X Cap Ratio | X Duct Multiplier (DM x DSM x AHU) | X System Multiplier | X Credit Multiplier | = Cooling Points | |
| 18400.9 | 0.4266 | 7849.8 | 19165 | 1.00 | (1.09 x 1.147 x 0.91) | 0.263 | 1.000 | 5724.4 | |
| | | | 19164.7 | 1.00 | 1.138 | 0.263 | 1.000 | 5724.4 | |

WINTER CALCULATIONS
Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

| BASE | | | | AS-BUILT | | | | | | | | |
|--|----------|-------|--------|-------------------------------|-------------------------|-----|---------------------|---------------------------|-------------|--------|--------|--|
| GLASS TYPES .18 X Conditioned X BWPM = Points Floor Area | | | | Type/SC | Overhang Omt Len Hgt | | | Area X WPM X WOF = Points | | | | |
| .18 | 1399.0 | 12.74 | 3208.2 | Double, Clear | E | 2.0 | 6.0 | 60.0 | 18.79 | 1.06 | 1195.8 | |
| | | | | Double, Clear | N | 2.0 | 6.0 | 38.0 | 24.58 | 1.00 | 938.3 | |
| | | | | Double, Clear | S | 2.0 | 6.0 | 9.0 | 13.30 | 1.26 | 150.6 | |
| | | | | Double, Clear | W | 2.0 | 6.0 | 98.0 | 20.73 | 1.04 | 2118.2 | |
| | | | | As-Built Total: | | | 206.0 | | 4402.8 | | | |
| WALL TYPES Area X BWPM = Points | | | | Type | R-Value | | | Area X WPM = Points | | | | |
| Adjacent | 0.0 | 0.00 | 0.0 | Frame, Wood, Exterior | 13.0 | | | 1776.0 | 3.40 | 6038.4 | | |
| Exterior | 1776.0 | 3.70 | 6571.2 | | | | | | | | | |
| Base Total: 1776.0 6571.2 | | | | As-Built Total: | | | 1776.0 | | 6038.4 | | | |
| DOOR TYPES Area X BWPM = Points | | | | Type | R-Value | | | Area X WPM = Points | | | | |
| Adjacent | 0.0 | 0.00 | 0.0 | Exterior Insulated | | | | 72.0 | 8.40 | 804.8 | | |
| Exterior | 72.0 | 12.30 | 885.6 | | | | | | | | | |
| Base Total: 72.0 885.6 | | | | As-Built Total: | | | 72.0 | | 804.8 | | | |
| CEILING TYPES Area X BWPM = Points | | | | Type | R-Value | | | Area X WPM X WCM = Points | | | | |
| Under Attic | 1399.0 | 2.05 | 2867.9 | Under Attic | 30.0 | | | 1399.0 | 2.05 X 1.00 | 2867.9 | | |
| Base Total: 1399.0 2867.9 | | | | As-Built Total: | | | 1399.0 | | 2867.9 | | | |
| FLOOR TYPES Area X BWPM = Points | | | | Type | R-Value | | | Area X WPM = Points | | | | |
| Slab | 184.0(p) | 8.9 | 1637.6 | Slab-On-Grade Edge Insulation | 4.0 | | | 184.0(p) | 8.45 | 1554.8 | | |
| Raised | 0.0 | 0.00 | 0.0 | | | | | | | | | |
| Base Total: 1637.6 | | | | As-Built Total: | | | 184.0 | | 1554.8 | | | |
| INFILTRATION Area X BWPM = Points | | | | | | | Area X WPM = Points | | | | | |
| 1399.0 -0.59 -825.4 | | | | | | | 1399.0 -0.59 -825.4 | | | | | |

WINTER CALCULATIONS
Residential Whole Building Performance Method A - Details

| | |
|----------------|-----------|
| ADDRESS: , , , | PERMIT #: |
|----------------|-----------|

| BASE | | | AS-BUILT | | | | | | |
|-----------------------------|---------------------|------------------|--|-------------|------------------------------------|---------------------|---------------------|------------------|--|
| Winter Base Points: 14345.1 | | | Winter As-Built Points: 14643.5 | | | | | | |
| Total Winter Points | X System Multiplier | = Heating Points | Total Component (System - Points) | X Cap Ratio | X Duct Multiplier (DM x DSM x AHU) | X System Multiplier | X Credit Multiplier | = Heating Points | |
| 14345.1 | 0.6274 | 9000.1 | (sys 1: Electric Heat Pump 30000 btuh ,EFF(7.6) Ducts:Unc(S),Unc(R),Int(AH),R6.0 14643.5 1.000 (1.069 x 1.169 x 0.93) 0.449 1.000 7635.9 14643.5 1.00 1.162 0.449 1.000 7635.9 | | | | | | |

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

| BASE | | | | AS-BUILT | | | | | |
|--------------------|---|------------|---------|-------------|------|--------------------|-----------------------------|---------------------------|--------|
| WATER HEATING | | | | | | | | | |
| Number of Bedrooms | X | Multiplier | = Total | Tank Volume | EF | Number of Bedrooms | X Tank X Multiplier X Ratio | Credit = Total Multiplier | |
| 2 | | 2635.00 | 5270.0 | 50.0 | 0.66 | 2 | 1.00 1973.45 | 1.00 | 3946.9 |
| As-Built Total: | | | | | | | | | 3946.9 |

| CODE COMPLIANCE STATUS | | | | | | | |
|------------------------|------------------|--------------------|----------------|----------------|------------------|--------------------|----------------|
| BASE | | | | AS-BUILT | | | |
| Cooling Points | + Heating Points | + Hot Water Points | = Total Points | Cooling Points | + Heating Points | + Hot Water Points | = Total Points |
| 7850 | 9000 | 5270 | 22120 | 5724 | 7636 | 3947 | 17307 |

PASS

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

| COMPONENTS | SECTION | REQUIREMENTS FOR EACH PRACTICE | CHECK |
|-------------------------------|-----------------|--|-------|
| Exterior Windows & Doors | 606.1.ABC.1.1 | Maximum: 3 cfm/sq.ft. window area; 5 cfm/sq.ft. door area. | |
| Exterior & Adjacent Walls | 606.1.ABC.1.2.1 | Caulk, gasket, weatherstrip or seal between windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate. | |
| Floors | 606.1.ABC.1.2.2 | Penetrations/openings > 1/8" sealed unless backed by truss or joist members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams. | |
| Ceilings | 606.1.ABC.1.2.3 | Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams. | |
| Recessed Lighting Fixtures | 606.1.ABC.1.2.4 | Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested. | |
| Multi-story Houses | 606.1.ABC.1.2.5 | Air barrier on perimeter of floor cavity between floors. | |
| Additional Infiltration reqts | 606.1.ABC.1.3 | Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air. | |

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

| COMPONENTS | SECTION | REQUIREMENTS | CHECK |
|--------------------------|--------------|---|-------|
| Water Heaters | 612.1 | Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required. | |
| Swimming Pools & Spas | 612.1 | Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%. | |
| Shower heads | 612.1 | Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG. | |
| Air Distribution Systems | 610.1 | All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation. | |
| HVAC Controls | 607.1 | Separate readily accessible manual or automatic thermostat for each system. | |
| Insulation | 604.1, 602.1 | Ceilings-Min. R-10. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11. | |

From: The Columbia County Building Department
Plans Review
135 NE Hernando Av.
P. O Box 1529
Lake City Florida, 32056-1529

0510-61

Reference to: Build permit application Number:

Matt Cason SCCI Owner Sam Duncan Lot 19 of Pine Wind Estates

On the date of October 25, 2005 application 0510-61 and plans for construction of a single family dwelling were reviewed and the following information or alteration to the plans will be required to continue processing this application. If you should have any question please contact the above address, or contact phone number (386) 758-1163 or fax any information to (386) 754-7088.

Please include application number 0510-61 when making reference to this application.

1. Please indicate the type of fireplace that will be installed (gas vented), (gas non-vented) or wood burning with hearth, **(Please circle applicable type)**. *mpc*

2. Show compliance with the 2004 Residential Code R308.4 Hazardous locations. Glazing in doors and enclosures for hot tubs, whirlpools, saunas, steam rooms, bathtubs and showers.

Glazing in any part of a building wall enclosing these compartments where the bottom exposed edge of the glazing is less than 60 inches (1524 mm) measured vertically above any standing or walking surface. As this code requirement relates to the dwelling bathrooms.

3. Show compliance with the 2004 Residential Code R313.1 Smoke alarms: Smoke alarms shall be installed in the following locations:

1. In each sleeping room.


2. Outside each separate sleeping area in the immediate vicinity of the bedrooms.

3. On each additional story of the dwelling, including basements but not including crawl spaces and uninhabitable attics. In dwellings or dwelling units with split levels and without an intervening door between the adjacent levels, a smoke alarm installed on the upper level shall suffice for the adjacent lower level provided that the lower level is less than one full story below the upper level.

When more than one smoke alarm is required to be installed within an individual dwelling unit the alarm devices shall be interconnected in such a manner that the actuation of one alarm will activate all of the alarms in the individual unit. The alarm shall be clearly audible in all bedrooms over background noise levels with all intervening doors closed.

4. The electrical outlets shown in the garage area will be required to be GFCI type receptacles please so indicate this code requirement on the electrical plan, along with the amperage rating of the electrical panel (and sub-panels) and the location of both the electrical panel and the service entrance.

Thank you,



Joe Haltiwanger
Plan Examiner
Columbia County Building Department

**Columbia County Building Department
Culvert Permit**

**Culvert Permit No.
000000871**

DATE 10/27/2005 PARCEL ID # 11-5S-15-00431-219

APPLICANT MATT CASON PHONE 752.5152

ADDRESS 1531 SW COMMERCIAL GLEN LAKE CITY FL 32024

OWNER SAM DUNCAN PHONE 752.5152

ADDRESS 461 SW QUAIL RIDGE CT LAKE CITY FL 32024

CONTRACTOR W. STANLEY CRAWFORD PHONE 752.5152

LOCATION OF PROPERTY 90-W TO SR 247-S TO QUAIL RIGE CT,TR JUST BEFORE C-240, LOT IS ON R.

SUBDIVISION/LOT/BLOCK/PHASE/UNIT PINE WIND ESTATES 19 II

SIGNATURE 

INSTALLATION REQUIREMENTS

☒

Culvert size will be 18 inches in diameter with a total lenth of 32 feet, leaving 24 feet of driving surface. Both ends will be mitered 4 foot with a 4 : 1 slope and poured with a 4 inch thick reinforced concrete slab.

INSTALLATION NOTE: Turnouts will be required as follows:

- a) a majority of the current and existing driveway turnouts are paved, or;
- b) the driveway to be served will be paved or formed with concrete.

Turnouts shall be concrete or paved a minimum of 12 feet wide or the width of the concrete or paved driveway, whichever is greater. The width shall conform to the current and existing paved or concreted turnouts.

☐

Culvert installation shall conform to the approved site plan standards.

☐

Department of Transportation Permit installation approved standards.

☐

Other _____

ALL PROPER SAFETY REQUIREMENTS SHOULD BE FOLLOWED
DURING THE INSTALATION OF THE CULVERT.

135 NE Hernando Ave., Suite B-21

Lake City, FL 32055

Phone: 386-758-1008 Fax: 386-758-2160

Amount Paid 25.00



COLUMBIA COUNTY, FLORIDA

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 11-5S-15-00431-219

Building permit No. 000023785

Use Classification SFD/UTILITY

Fire: 29.60

Permit Holder W. STANLEY CRAWFORD

Waste: 61.25

Owner of Building SAM DUNCAN

Total: 90.85

Location: 461 SW QUAIL RIDGE CT (PINE WIND EST., LOT 19)

Date: 05/08/2006



[Signature]

Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)

17 05 10:34a

Cal-Tech Testing

3867525456

P. 2



Cal-Tech Testing, Inc.
• Engineering
• Geotechnical
• Environmental
LABORATORIES

P.O. Box 1625 • Lake City, FL 32056-1625
6919 Distribution Avenue S., Unit #5 • Jacksonville, FL 32257

Tel. (386) 755-3633 • Fax (386) 752-5456
Tel. (904) 262-4046 • Fax (904) 262-4047

November 17, 2005

Stanley Crawford Construction
853 SW Sisters Welcome Rd.
Lake City, FL 32025

RE: Duncan Residence

Dear Mr. Crawford:

On November 17, I was dispatched to the Duncan Residence building pad on Quail Ridge Road. The footers were inspected in reference to suspected unsuitable building material. Samples were collected and sent to our lab for further inspection and testing. The tests revealed the material in question is suitable for use.

Please feel free to contact me or our office if you have any questions or require additional information. We appreciate your business.

Sincerely,

Robert D. Edwards
Senior Inspector

"Excellence in Engineering & Geoscience"

CAL-TECH

TESTING, INC.

FACSIMILE TRANSMITTAL SHEET

TO:

Johnny R

FROM:

Robert Edwards

COMPANY:

Columbia Co. Bldg Dept.

DATE:

11/17/05

FAX NUMBER:

TOTAL NO. OF PAGES INCLUDING COVER:

754-7088

REFERENCE:


2

NOTES/COMMENTS:


P.O. BOX 1625 LAKE CITY, FL 32056

PHONE • 386-755-3633
FAX • 386-752-5456

Scale: 3/32" = 1'



9/7/05
#5-383
STANLEY CRAWFORD
DUNCAN



Alpine Engineered Products, Inc.

1950 Marley Drive Haines City, FL 33844
Florida Engineering Certificate of Authorization Number: 567
Florida Certificate of Product Approval # FL1999
Page 1 of 1 Document ID:1SQA487-Z0107100124

Truss Fabricator: Anderson Truss Company
Job Identification: 5-383-STANLEY CRAWFORD-DUNCAN
Truss Count: 9
Model Code: Florida Building Code 2001
Truss Criteria: ANSI/TPI-1995(STD)/FBC
Engineering Software: Alpine Software, Versions 7.02, 7.04.
Structural Engineer of Record:

Address:

Minimum Design Loads: Roof - 40.0 PSF @ 1.25 Duration
Floor - N/A
Wind - 110 MPH ASCE 7-98 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1-1995 Section 2.2
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR487

Details: A11015EC-GBLLETIN-BRCLBSUB

Seal Date: 09/07/2005

-Truss Design Engineer-
Arthur R. Fisher
Florida License Number: 59687
1950 Marley Drive
Haines City, FL 33844

| # | Ref | Description | Drawing# | Date |
|---|--------------|-------------|----------|----------|
| 1 | 51026--A1-GE | | 05250082 | 09/07/05 |
| 2 | 51027--A2 | | 05250076 | 09/07/05 |
| 3 | 51028--A3 | | 05250077 | 09/07/05 |
| 4 | 51029--A4 | | 05250078 | 09/07/05 |
| 5 | 51030--A5-GE | | 05250084 | 09/07/05 |
| 6 | 51031--B1-GE | | 05250079 | 09/07/05 |
| 7 | 51032--B2 | | 05250081 | 09/07/05 |
| 8 | 51033--C1 | | 05250075 | 09/07/05 |
| 9 | 51034--C2 | | 05250080 | 09/07/05 |



Alpine Engineered Products, Inc.

1950 Marley Drive Haines City, FL 33844
Florida Engineering Certificate of Authorization Number: 567
Page 1 of 1 Document ID: ISQA487-Z0107100124

Truss Fabricator: Anderson Truss Company
Job Identification: 5-383-STANLEY CRAWFORD-DUNCAN (5-383|-STANLEY CRAWFORD-DUNCAN)
Truss Count: 2
Model Code: Florida Building Code 2001
Truss Criteria: ANSI/TPI-1995(STD)/FBC
Engineering Software: Alpine Software, Versions 7.02, 7.04.
Structural Engineer of Record:
Address:
Minimum Design Loads: Roof - 40.0 PSF @ 1.25 Duration
Floor - N/A
Wind - 110 MPH ASCE 7-98 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1-1995 Section 2.2
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR487

Seal Date: 09/07/2005

-Truss Design Engineer-
Arthur R. Fisher
Florida License Number: 59687
1950 Marley Drive
Haines City, FL 33844

Revised Trusses

| # | Ref | Description | Drawing# | Date |
|---|--------------|-------------|----------|----------|
| 1 | 51026--A1-GE | | 05250082 | 09/07/05 |
| 2 | 51030--A5-GE | | 05250084 | 09/07/05 |

ALPINE



| Top | chord | 2x4 | SP | #2 |
|-----|-------|-----|----|----|
| Bot | chord | 2x4 | SP | #2 |
| | webs | 2x4 | SP | #3 |

: Lt Slider 2x4 SP #3: BLOCK LENGTH = 1.777'

SPECIAL LOADS

| ----- (LUMBER DUR.FAC.=1.25 / PLATE DUR.FAC.=1.25) | |
|--|------------------------------------|
| TC - From | 60 PLF at -2.00 to 80 PLF at 0.00 |
| TC - From | 81 PLF at 0.00 to 61 PLF at 45.00 |
| TC - From | 60 PLF at 45.00 to 60 PLF at 47.00 |
| BC - From | 4 PLF at -2.00 to 4 PLF at 0.00 |
| BC - From | 20 PLF at 0.00 to 20 PLF at 45.00 |
| BC - From | 4 PLF at 45.00 to 4 PLF at 47.00 |

+ MEMBER TO BE Laterally Braced For Horizontal Wind Loads.
Bracing System To Be Designed And Furnished By Others.

(**) Plate relocated as shown.


110 mph wind, 12.78 ft mean hgt., ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

See DWGS A11015EC1103 & GBLLETIN1103 for more requirements.

Deflection meets L/360 live and L/240 total load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.

THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.



R=114 PLF U=21 PLF W=37-0-0

Note: All Plates Are 1.5X4 Except As Shown.


PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FRC

7.020527.10

Scale = .125"/Ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. ALWAYS FOLLOW THE FOLLOWING COMPONENT SAFETY INFORMATION. PUBLISHED BY TPI (TRUSS PACE INSTITUTE, 503 S. 5000 RD., SUITE 100, DALLAS, TEXAS 75243) OR TPI (TRUSS PACE INSTITUTE, 6300 INTERSTATE 10, MIDLAND, TX 79701). FOR SAFETY REASONS, ALL TRUSSES MUST BE PROPERLY BRACED AND SHIPPED UNLESS OTHERWISE INDICATED. TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

[illegible]

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
Fl. Certificate of Authorization # 567

| | | |
|--------|----------|----------|
| REF | R487 -- | 51026 |
| DATE | 09/07/05 | |
| DRW | HCUSR487 | 05250082 |
| HC-ENG | JB/AF | |
| SEQN- | 111648 | REV |
| FROM | JP | |
| JREF- | 1S0A487 | Z01 |

(5-383-STANLEY CRAWFORD-DUNCAN - A2)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3


:Lt Slider 2x4 SP #3: BLOCK LENGTH = 1.777'

Deflection meets L/360 live and L/240 total load.

110 mph wind, 12.95 ft mean hgt, ASCE 7-98, CLOSED bldg. Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

(A) Continuous lateral bracing equally spaced on member.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.




PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

Scale = .125" / Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFERENCE TO THE BUILDING CODES, SPECIFICATIONS, AND STANDARDS OF THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 1000 LEXINGTON AVENUE, SUITE 2000, NEW YORK, NY 10017, AND THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 1000 LEXINGTON AVENUE, SUITE 2000, NEW YORK, NY 10017, SHALL BE OBSERVED. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI SHALL BE THE RESPONSIBILITY OF THE INSTALLER. THE DESIGNER SHALL BE RESPONSIBLE FOR THE DESIGN OF THE TRUSS. THE INSTALLER SHALL BE RESPONSIBLE FOR THE INSTALLATION OF THE TRUSS. THE BUILDING DESIGNER SHALL BE RESPONSIBLE FOR THE DESIGN OF THE BUILDING. THE BUILDING DESIGNER SHALL BE RESPONSIBLE FOR THE DESIGN OF THE BUILDING. THE BUILDING DESIGNER SHALL BE RESPONSIBLE FOR THE DESIGN OF THE BUILDING.



Alpine Engineering Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567



ALPINE ENGINEERING
No. 59687
STATE OF FLORIDA
PROFESSIONAL ENGINEER

| | |
|-----------|----------|
| LL | 20.0 PSF |
| DL | 10.0 PSF |
| CL | 10.0 PSF |
| BC LL | 0.0 PSF |
| TOT. LD. | 40.0 PSF |
| DUR. FAC. | 1.25 |
| SPACING | 24.0" |

| | | |
|--------|-------------|----------|
| REF | R487 -- | 51027 |
| DATE | 09/07/05 | |
| DRW | HCUR487 | 05250076 |
| HC-ENG | JB/AF | |
| SEQN | 10036 | |
| FROM | JP | |
| JREF | 15QA487_Z01 | |

110 mph wind, 12.95 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.



Design Crit: TPI-1995 (STD) / FBC

04-0805-16-QT: 4 FL/-/3/-/-/R/-

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BESS 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 983 D'ORFORD DR., SUITE 200, MADISON, WI 53719) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI:
OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.
DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC, BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/R) ASTM A563 GRADE 40/60 (K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A OF TPI-2002 SEC.3. A SEAL OR THE DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENTS SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE

FL Certificate of Authorization # 567
Haines City, FL 33844

(5-383-STANLEY CRAWFORD-DUNCAN - A4)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3


:Lt Slider 2x4 SP #3: BLOCK LENGTH = 1.759'

Deflection meets L/360 live and L/240 total load.

110 mph wind, 12.95 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

(A) Continuous lateral bracing equally spaced on member.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04

QTY 17

Scale = .125"/Ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO THE TPI-1995(STD) FOR THE PROPER HANDLING AND BRACING PROCEDURES. THE TRUSS MANUFACTURER SHALL BE RESPONSIBLE FOR THE PROPER HANDLING AND BRACING PROCEDURES. THE TRUSS MANUFACTURER SHALL BE RESPONSIBLE FOR THE PROPER HANDLING AND BRACING PROCEDURES. THE TRUSS MANUFACTURER SHALL BE RESPONSIBLE FOR THE PROPER HANDLING AND BRACING PROCEDURES.

ARTHUR R. FISHER
LICENSE
No. 59687
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

TLL 20.0 PSF
DL 10.0 PSF
DL 10.0 PSF
BC LL 0.0 PSF
TOT.LD. 40.0 PSF
DUR.FAC. 1.25
SPACING 24.0"

REF R487 -- 51029
DATE 09/07/05
DRW HCUSR487 05250078
HC-ENG JB/AF
SEQN - 10026
FROM JP
JREF - 1SQA487_Z01

ALPINE
Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI-1995(STD) OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF HUD (NATIONAL DESIGN SPEC. BY AREA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W-H/SX) ASH 6053 GRADE 40/60 (W, K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. A SEAL OR THIS DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Top chord 2x4 SP #2
Bot chord 2x4 SP #2
 Webs 2x4 SP #3
:Lt Slider 2x4 SP #3

110 mph wind, 12.78 ft mean hgt., ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

(A) Continuous lateral bracing equally spaced on member.


Deflection meets L/360 live and L/240 total load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.

THE BUILDING DESIGNER IS RESPONSIBLE FOR THE DESIGN OF ROOF AND CEILING DIAPHRAGMS, GABLE END SHEAR WALLS, SUPPORTING SHEAR WALLS. SHEAR WALLS MUST PROVIDE CONTINUOUS LATERAL RESTRAINT TO GABLE END. ALL CONNECTIONS TO BE DESIGNED BY THE BUILDING DESIGNER.

+ MEMBER TO BE Laterally Braced For Horizontal Wind Loads.
Bracing System To Be Designed And Furnished By Others.

BALLOON FRAME WALL UP TO BOTTOM CHORD OF TRUSS.



Note: All Plates Are 1.5X4 Except As Shown.


PLT TYP. Wave TPI

Design Crit: TPI-1995 (STD)/FRC

Scale = .125"/Ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (CROSS PLAT, 6300 ENTERPRISE, 583 N. OGDEN RD., SUITE 200, MADISON, WI 53710) AND OSHA (29 CFR 1910.269, 1910.268, 1910.265, 1910.264, 1910.263, 1910.262, 1910.261, 1910.260, 1910.259, 1910.258, 1910.257, 1910.256, 1910.255, 1910.254, 1910.253, 1910.252, 1910.251, 1910.250, 1910.249, 1910.248, 1910.247, 1910.246, 1910.245, 1910.244, 1910.243, 1910.242, 1910.241, 1910.240, 1910.239, 1910.238, 1910.237, 1910.236, 1910.235, 1910.234, 1910.233, 1910.232, 1910.231, 1910.230, 1910.229, 1910.228, 1910.227, 1910.226, 1910.225, 1910.224, 1910.223, 1910.222, 1910.221, 1910.220, 1910.219, 1910.218, 1910.217, 1910.216, 1910.215, 1910.214, 1910.213, 1910.212, 1910.211, 1910.210, 1910.209, 1910.208, 1910.207, 1910.206, 1910.205, 1910.204, 1910.203, 1910.202, 1910.201, 1910.200, 1910.199, 1910.198, 1910.197, 1910.196, 1910.195, 1910.194, 1910.193, 1910.192, 1910.191, 1910.190, 1910.189, 1910.188, 1910.187, 1910.186, 1910.185, 1910.184, 1910.183, 1910.182, 1910.181, 1910.180, 1910.179, 1910.178, 1910.177, 1910.176, 1910.175, 1910.174, 1910.173, 1910.172, 1910.171, 1910.170, 1910.169, 1910.168, 1910.167, 1910.166, 1910.165, 1910.164, 1910.163, 1910.162, 1910.161, 1910.160, 1910.159, 1910.158, 1910.157, 1910.156, 1910.155, 1910.154, 1910.153, 1910.152, 1910.151, 1910.150, 1910.149, 1910.148, 1910.147, 1910.146, 1910.145, 1910.144, 1910.143, 1910.142, 1910.141, 1910.140, 1910.139, 1910.138, 1910.137, 1910.136, 1910.135, 1910.134, 1910.133, 1910.132, 1910.131, 1910.130, 1910.129, 1910.128, 1910.127, 1910.126, 1910.125, 1910.124, 1910.123, 1910.122, 1910.121, 1910.120, 1910.119, 1910.118, 1910.117, 1910.116, 1910.115, 1910.114, 1910.113, 1910.112, 1910.111, 1910.110, 1910.109, 1910.108, 1910.107, 1910.106, 1910.105, 1910.104, 1910.103, 1910.102, 1910.101, 1910.100, 1910.99, 1910.98, 1910.97, 1910.96, 1910.95, 1910.94, 1910.93, 1910.92, 1910.91, 1910.90, 1910.89, 1910.88, 1910.87, 1910.86, 1910.85, 1910.84, 1910.83, 1910.82, 1910.81, 1910.80, 1910.79, 1910.78, 1910.77, 1910.76, 1910.75, 1910.74, 1910.73, 1910.72, 1910.71, 1910.70, 1910.69, 1910.68, 1910.67, 1910.66, 1910.65, 1910.64, 1910.63, 1910.62, 1910.61, 1910.60, 1910.59, 1910.58, 1910.57, 1910.56, 1910.55, 1910.54, 1910.53, 1910.52, 1910.51, 1910.50, 1910.49, 1910.48, 1910.47, 1910.46, 1910.45, 1910.44, 1910.43, 1910.42, 1910.41, 1910.40, 1910.39, 1910.38, 1910.37, 1910.36, 1910.35, 1910.34, 1910.33, 1910.32, 1910.31, 1910.30, 1910.29, 1910.28, 1910.27, 1910.26, 1910.25, 1910.24, 1910.23, 1910.22, 1910.21, 1910.20, 1910.19, 1910.18, 1910.17, 1910.16, 1910.15, 1910.14, 1910.13, 1910.12, 1910.11, 1910.10, 1910.9, 1910.8, 1910.7, 1910.6, 1910.5, 1910.4, 1910.3, 1910.2, 1910.1) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED TIGHT CEILING.

*****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE DESIGNS IN CONFORMANCE WITH THIS DESIGN FOR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, CONNECTOR PLATES ARE MADE OF 2014-T3 ALUMINUM (NATIONAL DESIGN SPEC., BY A/P/MS) AND TPI. ALPINE TRUSSES TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS TRUSS SECTION PER DRAWING 1600-23. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANCHOR 43 OF TPI-2002 SECTION PER DRAWING 1600-23. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS CONSTRUCTION DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANS/TP1 1 SEC. 2.



Alpine Engineered Products, Inc.
 1950 Marley Drive
 Haines City, FL 33844
 FL Certificate of Authorization # 567

9-0 P-61000000 W-3.5

ARTHUR R. FISHER
LICENSE
No. 59687
07 STATE OF
FLORIDA
PROFESSIONAL ENGINEER

| | | | | | | |
|---|----------|-------|-----|--------|-------------------|-------|
| T | LL | 20.0 | PSF | REF | R487 - - | 51030 |
| ★ | DL | 10.0 | PSF | DATE | 09/07/05 | |
| | DL | 10.0 | PSF | DRW | HCUSR487 05250084 | |
| | BC LL | 0.0 | PSF | HC-ENG | JB/AF | |
| | TOT.LD. | 40.0 | PSF | SEQN- | 111652 | REV |
| | DUR.FAC. | 1.25 | | FROM | JP | |
| | SPACING | 24.0" | | JREF- | 1SQA487 | Z01 |

110 mph wind, 11.68 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.



100

Design Crit: TPI-1995 (STD) / FBC

80316 QTY: 2 FL/-/3/-/-/R/-



Alpine Engineered Products, Inc.
 1050 Monkey Drive
 Gaines City, FL 32644

FL Certificate of Authorization # 567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719), AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AIA/PFA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (4.0/5.0/3.0) ASTM A653 GRADE 40/60 (40, 42/45) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-7. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

No. 59687


STATE OF FLORIDA

PROFESSIONAL ENGINEER

| | | | | | |
|-------------|-------------------|----------|-------|------|-----|
| REF R487 -- | 51031 | T | LL | 20.0 | PSF |
| DATE | 09/07/05 | T | DL | 10.0 | PSF |
| DRW | HCUSR487 05250079 | T | DL | 10.0 | PSF |
| HC-ENG | JB/AF | T | BC LL | 0.0 | PSF |
| SEQN - | 9938 | TOT.LD. | | | |
| FROM | JP | DUR.FAC. | | | |
| JREF - | 1SQ487_Z01 | SPACING | | | |

110 mph wind, 11.85 ft mean hgt., ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04


Scale = .25"/Ft.




Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
Fl. Certificate of Authorization # 567

FL Certificate of Authorization # 567

*WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO THE FOLLOWING TECHNICAL INFORMATION: TRUSS COUNCIL OF AMERICA, 6800 ENTERPRISE LN., DOWNEY, CA 90242, (714) 951-2000; TRUSSING, INC., 10000 W. MADISON, WI 53219. FOR SAFETY PRACTICES PRIOR TO PERFORMING ANY TRUSSING, UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED HUNG PURLINS.


[illegible]

| | | | |
|---|----------|----------|-----------------------|
|  | C LL | 20.0 PSF | REF R487 -- 51032 |
| | C DL | 10.0 PSF | DATE 09/07/05 |
| | C DL | 10.0 PSF | DRW HCURS487 05250081 |
| | BC LL | 0.0 PSF | HC-ENG JB/AF * |
| | TOT.LD. | 40.0 PSF | SEQN - 9927 |
| | DUR.FAC. | 1.25 | FROM JP |
| | SPACING | 24.0" | JREF - 1SQA487_Z01 |

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3
:Lt Stubbed Wedge 2x6 SP #2::Rt Stubbed Wedge 2x6 SP #2:

110 mph wind, 8.82 ft mean hgt, ASCE 7-98, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0
psf.

Deflection meets L/360 live and L/240 total load.



PLT TYP. Wave TPI

Design Crit: TPI-1995 (SID)/FBC


7.04

FL/-/3/-/R/-

Scale =.375"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 O'DONOHIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS TO CONFORM WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. THE DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE INTERNATIONAL BUILDING CODE (IBC) AND THE ALPINE DESIGN CRITERIA. CONNECTOR PLATES ARE MADE OF 20/18/16GA (R-10/S-25) 45TH A563 GRADE 40/60 (R-10/S-25) ALPINE STEEL. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1000-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DESIGN SHOWS THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Alpine Engineered Products, Inc.
1850 Bailey Drive
Haines City, FL 33844
FL Certificate of Authorization # 567



| | |
|----------|----------|
| C LL | 20.0 PSF |
| C DL | 10.0 PSF |
| C DL | 10.0 PSF |
| BC LL | 0.0 PSF |
| TOT.LD. | 40.0 PSF |
| DUR.FAC. | 1.25 |
| SPACING | 24.0" |


| | | |
|--------|-------------|----------|
| REF | R487 -- | 51033 |
| DATE | 09/07/05 | |
| DRW | HCUSR487 | 05250075 |
| HC-ENG | JB/AF | * |
| SEQN | 9947 | |
| FROM | JP | |
| JREF | 1SQA487_Z01 | |

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

:Lt Stubbed Wedge 2x6 SP #2::Rt Stubbed Wedge 2x6 SP #2:

110 mph wind, 8.81 ft mean hgt, ASCE 7-98, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0
psf.

Deflection meets L/360 live and L/240 total load.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC


7.040803

FL/-/3/-/-/R/-


Scale = .375"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AF&PA) AND TPI. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGNER INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.





Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567



| | | |
|--------|-------------|----------|
| REF | R487-- | 51034 |
| DATE | 09/07/05 | |
| DRW | HCUSR487 | 05250080 |
| HC-ENG | JB/AF | |
| SEQN- | 9965 | |
| FROM | JP | |
| JREF- | 1S0A487_Z01 | |

ASCE 7-98: 110 MPH WIND SPEED, 15' MEAN HEIGHT, ENCLOSED, I = 1.00, EXPOSURE C

| 2X4 GABLE VERTICAL SPACING | | BRACE | | NO BRACES | | (1) 1X4 "L" BRACE | | (1) 2X4 "L" BRACE | | (2) 2X4 "L" BRACE | | (1) 2X6 "L" BRACE | | (2) 2X6 "L" BRACE | | (1) 2X6 "L" BRACE | | (2) 2X6 "L" BRACE | |
|----------------------------|----------|---------|----------|-----------|---------|-------------------|---------|-------------------|---------|-------------------|---------|-------------------|---------|-------------------|---------|-------------------|---------|-------------------|---------|
| | | SPECIES | GRADE | GROUP A | GROUP B | GROUP A | GROUP B | GROUP A | GROUP B | GROUP A | GROUP B | GROUP A | GROUP B | GROUP A | GROUP B | GROUP A | GROUP B | GROUP A | GROUP B |
| MAX GABLE VERTICAL LENGTH | 12" O.C. | SPF | #1 / #2 | 3' 10" | 6' 8" | 6' 10" | 7' 11" | 8' 1" | 9' 5" | 9' 5" | 9' 8" | 12' 5" | 12' 9" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | HF | STUD | 3' 9" | 6' 0" | 6' 0" | 7' 11" | 7' 11" | 9' 5" | 9' 5" | 9' 5" | 12' 4" | 12' 4" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | SP | STANDARD | 3' 9" | 5' 2" | 5' 2" | 6' 9" | 6' 9" | 9' 1" | 9' 1" | 9' 1" | 10' 7" | 10' 7" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | DFL | #1 | 4' 3" | 6' 8" | 7' 2" | 7' 11" | 8' 6" | 9' 5" | 10' 2" | 10' 2" | 12' 5" | 13' 5" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| 24" O.C. | 12" O.C. | SPF | #2 | 4' 2" | 6' 8" | 7' 2" | 7' 11" | 8' 6" | 9' 5" | 10' 2" | 10' 2" | 12' 5" | 13' 5" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | HF | #3 | 4' 0" | 6' 2" | 6' 2" | 7' 11" | 8' 1" | 9' 5" | 9' 11" | 9' 11" | 12' 5" | 12' 6" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | SP | STANDARD | 3' 10" | 5' 3" | 5' 3" | 6' 11" | 6' 11" | 9' 4" | 9' 4" | 9' 4" | 10' 10" | 10' 10" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | DFL | #1 / #2 | 4' 5" | 7' 8" | 7' 10" | 9' 1" | 9' 1" | 10' 10" | 10' 10" | 11' 1" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| 16" O.C. | 12" O.C. | SPF | #3 | 4' 4" | 7' 4" | 7' 4" | 9' 1" | 9' 1" | 10' 10" | 10' 10" | 10' 10" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | HF | STUD | 4' 4" | 7' 4" | 7' 4" | 9' 1" | 9' 1" | 10' 10" | 10' 10" | 10' 10" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | SP | STANDARD | 4' 4" | 6' 4" | 6' 4" | 8' 4" | 8' 4" | 10' 10" | 10' 10" | 10' 10" | 12' 11" | 12' 11" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | DFL | #1 | 4' 10" | 7' 8" | 8' 3" | 9' 1" | 9' 9" | 10' 10" | 11' 8" | 11' 8" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| 20" O.C. | 12" O.C. | SPF | #2 | 4' 6" | 7' 6" | 7' 6" | 9' 1" | 9' 9" | 10' 10" | 11' 8" | 11' 8" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | HF | #3 | 4' 6" | 7' 6" | 7' 6" | 9' 1" | 9' 9" | 10' 10" | 11' 8" | 11' 8" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | SP | STUD | 4' 6" | 7' 6" | 7' 6" | 9' 1" | 9' 9" | 10' 10" | 11' 8" | 11' 8" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | DFL | #1 | 4' 11" | 8' 5" | 8' 5" | 10' 0" | 10' 3" | 11' 11" | 12' 3" | 13' 3" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| 24" O.C. | 12" O.C. | SPF | #2 | 4' 9" | 8' 5" | 8' 5" | 10' 0" | 10' 3" | 11' 11" | 12' 3" | 13' 3" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | HF | #3 | 4' 9" | 8' 5" | 8' 5" | 10' 0" | 10' 3" | 11' 11" | 12' 3" | 13' 3" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | SP | STUD | 4' 9" | 8' 5" | 8' 5" | 10' 0" | 10' 3" | 11' 11" | 12' 3" | 13' 3" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | DFL | #1 | 5' 0" | 8' 7" | 8' 7" | 10' 0" | 10' 6" | 11' 11" | 12' 6" | 13' 6" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| 28" O.C. | 12" O.C. | SPF | #3 | 5' 0" | 8' 7" | 8' 7" | 10' 0" | 10' 6" | 11' 11" | 12' 6" | 13' 6" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | HF | STUD | 5' 0" | 8' 7" | 8' 7" | 10' 0" | 10' 6" | 11' 11" | 12' 6" | 13' 6" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | SP | STANDARD | 5' 0" | 8' 7" | 8' 7" | 10' 0" | 10' 6" | 11' 11" | 12' 6" | 13' 6" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |
| | | DFL | #1 | 5' 0" | 8' 7" | 8' 7" | 10' 0" | 10' 6" | 11' 11" | 12' 6" | 13' 6" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" | 14' 0" |



REFER TO CHART ABOVE FOR MAXIMUM LENGTH.

BRACING GROUP SPECIES AND GRADES:

GROUP A:

| | |
|------------------|----------|
| SPRUCE-PINE-FIR | HEM-FIR |
| #1 / #2 STANDARD | #2 STUD |
| #3 STUD | STANDARD |

DOUGLAS FIR-LARCH

| | |
|---------|----------|
| #3 STUD | STANDARD |
|---------|----------|

SOUTHERN PINE

| | |
|---------|----------|
| #3 STUD | STANDARD |
|---------|----------|

GROUP B:

| | |
|-------------|-------------------|
| HEM-FIR | DOUGLAS FIR-LARCH |
| #1 & BTR #1 | #1 #2 |

SOUTHERN PINE

| | |
|-------|--|
| #1 #2 | |
|-------|--|

GABLE TRUSS DETAIL NOTES:

LIVE LOAD DEFLECTION CRITERIA IS L/240.

PROVIDE UPLIFT CONNECTIONS FOR 80 PLF OVER CONTINUOUS BEARING (5 PSF TC DEAD LOAD).

GABLE END SUPPORTS LOAD FROM 4' 0" OUTLOOKERS WITH 2' 0" OVERHANG, OR 12" PLYWOOD OVERHANG.

ATTACH EACH "L" BRACE WITH 10d NAILS.

* FOR (1) "L" BRACE: SPACE NAILS AT 2" O.C. IN 18" END ZONES AND 4" O.C. BETWEEN ZONES.

** FOR (2) "L" BRACES: SPACE NAILS AT 3" O.C. IN 18" END ZONES AND 6" O.C. BETWEEN ZONES.

"L" BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

| GABLE VERTICAL PLATE SIZES | |
|--|------------|
| VERTICAL LENGTH | NO SPLICE |
| LESS THAN 4' 0" | 1X4 OR 2X3 |
| GREATER THAN 4' 0", BUT LESS THAN 11' 6" | 2X4 |
| GREATER THAN 11' 6" | 2.5X4 |

+ REFER TO COMMON TRUSS DESIGN FOR PEAK, SPLICE, AND HEEL PLATES.

ALPINE ENGINEERED PRODUCTS, INC.
POMPAHO BEACH, FLORIDA

ALPINE

WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 593 DUNDREID DR., SUITE 200, MADISON, WI 53719) AND VTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT** FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING OR BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THIS (NATIONAL DESIGN) SPECIFICATION FOR TRUSSES AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/A) ASTM A653 GRADE 40/60 (W/J/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (D) SHALL BE PERFORMED BY TPI 1-800-SEC-3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF THE DESIGN AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER. REF ANS1/TPI 1 SEC. 2.


ARTHUR R. FISHER
LICENSE
No. 59687
STATE OF FLORIDA
PROFESSIONAL ENGINEER

REF ASCE7-98-GABI1015
DATE 11/26/03
DRWG A11015EC1103
-ENG


MAX. SPACING 24.0"

GABLE DETAIL
FOR LET-IN VERTICALS

SYM.
ABOUT C



RIGID SHEATHING



ALPINE

ALPINE ENGINEERED PRODUCTS, INC.
POMPAHO BEACH, FLORIDA

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS DESIGN INSTITUTE, 583 PONDPPD DR., SUITE 200, MADISON, WI 53719) AND VTCA (WOOD TRUSS COUNCIL OF AMERICA, 14501 13TH AVE., SUITE 100, DENVER, CO 80227) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, ALL TOENAILS SHALL BE PROPERLY ATTACHED TO STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN, ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE NATIONAL DESIGN SPEC. FOR STEEL COMPOUND GIRLS. STEEL COMPOUND GIRLS ARE MADE OF 20/18/16GA (W/H/S/K) ASTM A553 GRADE 40/60 (W/L/H/S) GALV. STEEL. ALL PLATES SHALL BE PROPERLY ATTACHED TO THE TRUSS. UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 16A-2. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.


GABLE VERTICAL PLATE SIZES

| VERTICAL LENGTH BETWEEN CHORDS | PLATE SIZE | IF PLATES OVERLAP* |
|--|------------|--------------------|
| LESS THAN 4' 0" | 1X4 OR 2X3 | 2X8 |
| GREATER THAN 4' 0", BUT LESS THAN 11' 6" | 2X4 | 2X8 |
| GREATER THAN 11' 6" | 2-5X4 | 2-5X8 |

⊕ REFER TO ENGINEERED TRUSS DESIGN FOR PEAK, SPLICE, WEB AND HEEL PLATES.

* IF GABLE VERTICAL PLATES OVERLAP, USE A SINGLE PLATE TO SPAN THE WEB.

EXAMPLE:



TO CONVERT FROM "L" TO "T" REINFORCING MEMBERS, MULTIPLY "T" FACTOR BY LENGTH (BASED ON GABLE VERTICAL SPECIES, GRADE AND SPACING) FOR (1) 2X4 "L" BRACE, GROUP A, OBTAINED FROM THE APPROPRIATE ALPINE GABLE DETAIL, FOR ASCE OR SBCCI WIND LOAD.

MAXIMUM ALLOWABLE "T" REINFORCED GABLE VERTICAL LENGTH IS 14' FROM TOP TO BOTTOM CHORD.

WEB LENGTH INCREASE W/ "T" BRACE

| WIND SPEED AND MRH | "T" REINFORCING MEMBER SIZE | SBCCI | ASCE |
|--------------------|-----------------------------|-------|------|
| 110 MPH | 2x4 | 10 % | 10 % |
| 15 FT | 2x6 | 40 % | 50 % |
| 110 MPH | 2x4 | 10 % | 10 % |
| 30 FT | 2x6 | 50 % | 50 % |
| 100 MPH | 2x4 | 10 % | 10 % |
| 15 FT | 2x6 | 30 % | 50 % |
| 100 MPH | 2x4 | 10 % | 10 % |
| 30 FT | 2x6 | 40 % | 40 % |
| 90 MPH | 2x4 | 20 % | 10 % |
| 15 FT | 2x6 | 20 % | 40 % |
| 90 MPH | 2x4 | 10 % | 10 % |
| 30 FT | 2x6 | 30 % | 50 % |
| 80 MPH | 2x4 | 10 % | 20 % |
| 15 FT | 2x6 | 10 % | 30 % |
| 80 MPH | 2x4 | 20 % | 10 % |
| 30 FT | 2x6 | 20 % | 40 % |
| 70 MPH | 2x4 | 0 % | 20 % |
| 15 FT | 2x6 | 0 % | 20 % |
| 70 MPH | 2x4 | 10 % | 20 % |
| 30 FT | 2x6 | 10 % | 30 % |

EXAMPLE:

ASCE WIND SPEED = 100 MPH
MEAN ROOF HEIGHT = 30 FT
GABLE VERTICAL = 24' O.C. SP #3

"T" REINFORCING MEMBER SIZE = 2X4

"T" BRACE INCREASE (FROM ABOVE) = 10% = 1.10


(1) 2X4 "L" BRACE LENGTH = 6' 7"

MAXIMUM "T" REINFORCED GABLE VERTICAL LENGTH

1.10 x 6' 7" = 7' 3"

ALPINE ENGINEERED PRODUCTS, INC. DRAWINGS GAB981117 876,719 & HC26294035

| | |
|------|--------------|
| REF | LET-IN VERT |
| DATE | 01/16/04 |
| DRWG | GBLLETIN1103 |
| -ENG | DLJ/KAR |



THIS DETAIL IS TO BE USED WHEN CONTINUOUS LATERAL BRACING (CLB) IS SPECIFIED ON AN ALPINE TRUSS DESIGN BUT AN ALTERNATIVE WEB BRACING METHOD IS DESIRED.

THIS DETAIL IS ONLY APPLICABLE FOR CHANGING THE SPECIFIED CLB SHOWN ON SINGLE PLY SEALED DESIGNS TO T-BRACING OR SCAB BRACING.


ALTERNATIVE BRACING SPECIFIED IN CHART BELOW MAY BE CONSERVATIVE. FOR MINIMUM ALTERNATIVE BRACING, RE-RUN DESIGN WITH APPROPRIATE BRACING.

| WEB MEMBER SIZE | SPECIFIED CLB BRACING | T OR L-BRACE | ALTERNATIVE BRACING SCAB BRACE |
|--------------------|--------------------------|--------------|-----------------------------------|
| 2X3 OR 2X4 | 1 ROW | 2X4 | 1-2X4 |
| 2X3 OR 2X4 | 2 ROWS | 2X6 | 2-2X4 |
| 2X6 | 1 ROW | 2X4 | 1-2X6 |
| 2X6 | 2 ROWS | 2X6 | 2-2X4(*) |
| 2X8 | 1 ROW | 2X6 | 1-2X8 |
| 2X8 | 2 ROWS | 2X6 | 2-2X6(*) |


T-BRACE, L-BRACE AND SCAB BRACE TO BE SAME SPECIES AND GRADE OR BETTER THAN WEB MEMBER UNLESS SPECIFIED OTHERWISE ON ENGINEER'S SEALED DESIGN.

(*) CENTER SCAB ON WIDE FACE OF WEB. APPLY (1) SCAB TO EACH FACE OF WEB.

APPLY TO EITHER SIDE OF WEB
NARROW FACE
ATTACH WITH 16d NAILS AT 6" O.C.
BRACE IS A MINIMUM 80% OF WEB
MEMBER LENGTH



APPLY SCAB(S) TO WIDE FACE OF WEB.
NO MORE THAN (1) SCAB PER FACE.
ATTACH WITH 10d OR 128"x3" GUN
NAILS AT 6" O.C. BRACE IS A MINIMUM
80% OF WEB MEMBER LENGTH



THIS DRAWING REPLACES DRAWING 579 640

| | | | |
|-----------------------|---|-----|------------------|
| **VARIATIONS** | TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO DESIGN DRAWINGS FOR ALL CONNECTIONS, WELDING, BOLTING, ETC. SEE THE STEEL PLATE INSTITUTE, 593 DOWNGRIND DR., SUITE 200, MADISON, WI 53719 FOR SAFETY PRACTICES REGARDING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING. | PSF | CLB SUBST. |
| **IMPORTANT** | FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA&AS) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/18GA (A/H/S/N) ASTM A653 GRADE 50. (ALPINE'S GALVALUX STEEL APPLIES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, PER ANSD-2002 SECTION 1604-2). ANY INSPECTION OF PLATES FOLLOWED BY (C) SHALL BE PER ANSI/AISC 308 PART 5.2. THE DESIGNING ENGINEERING FIRM HAS REVIEWED THE DESIGN SHOWN THE FEASIBILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER. PER ANSD/TPI 1 SEC. 2. | PSF | DATE 11/26/03 |
| | | PSF | DRWG BRLBSUB1103 |
| | | PSF | -ENG MLH/KAR |



FLORIDA
 PROFESSIONAL ENGINEER
 STATE OF FLORIDA
 LICENSE NO. 59687

| | |
|-----------|---------|
| TOTAL | LL |
| TC DL | LL |
| DL | LD. |
| DUR. FAC. | SPACING |

COLUMBIA COUNTY BUILDING DEPARTMENT

RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR FLORIDA BUILDING CODE 2001 ONE (1) AND TWO (2) FAMILY DWELLINGS ALL REQUIREMENTS ARE SUBJECT TO CHANGE EFFECTIVE MARCH 1, 2002

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 1606 OF THE FLORIDA BUILDING CODE 2001 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1606 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE -----110 MPH
3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERAL REQUIREMENTS: Two (2) complete sets of plans containing the following:

| Applicant | Plans Examiner | |
|-------------------------------------|-------------------------------------|--|
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | All drawings must be clear, concise and drawn to scale ("Optional " details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans. |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | Designers name and signature on document (FBC 104.2.1). If licensed architect or engineer, official seal shall be affixed. |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | Site Plan including: a) Dimensions of lot b) Dimensions of building set backs c) Location of all other buildings on lot, well and septic tank if applicable, and all utility easements. d) Provide a full legal description of property. |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | Wind-load Engineering Summary, calculations and any details required a) Plans or specifications must state compliance with FBC Section 1606 b) The following information must be shown as per section 1606.1.7 FBC a. Basic wind speed (MPH) b. Wind importance factor (I) and building category c. Wind exposure - if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated d. The applicable internal pressure coefficient e. Components and Cladding. The design wind pressure in terms of psf (kN/m ²), to be used for the design of exterior component and cladding materials not specifically designed by the registered design professional |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | Elevations including: a) All sides b) Roof pitch c) Overhang dimensions and detail with attic ventilation d) Location, size and height above roof of chimneys e) Location and size of skylights f) Building height g) Number of stories |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | |

Floor Plan Including:

- a) Rooms labeled and dimensioned
- b) Shear walls
- c) Windows and doors (including garage doors) showing size, mfg., approval listing and attachment specs. (FBC 1707) and safety glazing where needed (egress windows in bedrooms to be shown)
- d) Fireplaces (gas appliance) (vented or non-vented) or wood burning with hearth
- e) Stairs with dimensions (width, tread and riser) and details of guardrails and handrails
- f) Must show and identify accessibility requirements (accessible bathroom)

Foundation Plan Including:

- a) Location of all load-bearing wall with required footings indicated as standard Or monolithic and dimensions and reinforcing
- b) All posts and/or column footing including size and reinforcing
- c) Any special support required by soil analysis such as piling
- d) Location of any vertical steel

Roof System:

- a) Truss package including:
 - 1. Truss layout and truss details signed and sealed by Fl. Pro. Eng.
 - 2. Roof assembly (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
- b) Conventional Framing Layout including:
 - 1. Rafter size, species and spacing
 - 2. Attachment to wall and uplift
 - 3. Ridge beam sized and valley framing and support details
 - 4. Roof assembly (FBC 104.2.1 Roofing systems, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)

Wall Sections Including:

- a) Masonry wall
 - 1. All materials making up wall
 - 2. Block size and mortar type with size and spacing of reinforcement
 - 3. Lintel, tie-beam sizes and reinforcement
 - 4. Gable ends with rake beams showing reinforcement or gable truss and wall brace details
 - 5. All required connectors with uplift rating and required number and size of fastener for continuous tie from roof to foundation
 - 6. Roof assembly shown here or on roof system detail (FBC 104.2.1 Roofing system materials, manufacturer, fastening requirements and product evaluation with resistance rating)
 - 7. Fire resistant construction (if required)
 - 8. Fireproofing requirements
 - 9. Shoe type of termite treatment (termicide or alternative method)
 - 10. Slab on grade
 - a. Vapor retardant (8mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or Welded fire fabric reinforcement and supports
 - 11. Indicate where pressure treated wood will be placed
 - 12. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

☒ ☒ b) Wood frame wall

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termicide or alternative method)
11. Slab on grade
 - a. Vapor retardant (6Mil. Polyethylene with joints lapped 6 inches and sealed
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide Insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

☐ ☐ c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)**Floor Framing System:**

- ☐
- ☐
- a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer

☐ ☐ b) Floor joist size and spacing☐ ☐ c) Girder size and spacing☐ ☐ d) Attachment of joist to girder☐ ☐ e) Wind load requirements where applicable☒ ☐ **Plumbing Fixture layout****Electrical layout including:**☒ ☐ a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified☒ ☐ b) Ceiling fans☒ ☐ c) Smoke detectors☒ ☐ d) Service panel and sub-panel size and location(s)☒ ☐ e) Meter location with type of service entrance (overhead or underground)☒ ☐ f) Appliances and HVAC equipment☒ ☐ g) Arc Fault Circuits (AFCI) in bedrooms**HVAC Information**☒ ☐ a) Manual J sizing equipment or equivalent computation☒ ☐ b) Exhaust fans in bathroom**Energy Calculations** (dimensions shall match plans)**Gas System** Type (LP or Natural) Location and BTU demand of equipment**Disclosure Statement for Owner Builders*******Notice Of Commencement Required Before Any Inspections Will Be Done**☒ ☐ **Private Potable Water**☐ ☐ a) Size of pump motor☐ ☐ b) Size of pressure tank☐ ☐ c) Cycle stop valve if used



RIGHT-J LOAD AND EQUIPMENT SUMMARY

Entire House

Touchstone Heating and Air, Inc.

Job: Duncan Job 09/13/05

490 SE 3rd Ave., Lake Butler, FL 32054 Phone: 386-496-3487 Fax: 386-496-3147

Project Information

For: Stanley Crawford Construction
1531 S.W. Commercial Glen, Lake City, FL 32025
Phone: 386-752-5152 Fax: 386-755-2165

Notes:

Design Information

Weather: Gainesville, FL, US

Winter Design Conditions

Outside db 33 °F
Inside db 70 °F
Design TD 37 °F

Summer Design Conditions

Outside db 92 °F
Inside db 75 °F
Design TD 17 °F
Daily range M
Relative humidity 50 %
Moisture difference 52 gr/lb

Heating Summary

Building heat loss 18477 Btuh
Ventilation air 0 cfm
Ventilation air loss 0 Btuh
Design heat load 18477 Btuh

Infiltration

Method Simplified
Construction quality Average
Fireplaces 0

| | Heating | Cooling |
|------------------|---------|---------|
| Area (ft²) | 1399 | 1399 |
| Volume (ft³) | 11892 | 11892 |
| Air changes/hour | 0.10 | 0.10 |
| Equiv. AVF (cfm) | 20 | 20 |

Heating Equipment Summary

Make Trane
Trade
2TWR3030
Efficiency 9.3 HSPF
Heating input 32600 Btuh @ 47°F
Heating output 27 °F
Heating temp rise 1114 cfm
Actual heating fan 0.060 cfm/Btuh
Heating air flow factor
Space thermostat

Sensible Cooling Equipment Load Sizing

Structure 20833 Btuh
Ventilation 935 Btuh
Design temperature swing 3.0 °F
Use mfg. data n
Rate/swing multiplier 0.97
Total sens. equip. load 21115 Btuh

Latent Cooling Equipment Load Sizing

Internal gains 1840 Btuh
Ventilation 1753 Btuh
Infiltration 695 Btuh
Total latent equip. load 4288 Btuh

Total equipment load 25403 Btuh
Req. total capacity at 0.70% SHR 2.5 ton

Cooling Equipment Summary


Make Trane
Trade
2TWR3030
2TEC3F30A1
Efficiency 13.0 EER
Sensible cooling 23800 Btuh
Latent cooling 10200 Btuh
Total cooling 34000 Btuh
Actual cooling fan 1114 cfm
Cooling air flow factor 0.053 cfm/Btuh
Load sensible heat ratio 84 %

Bold/italic values have been manually overridden

Printout certified by ACCA to meet all requirements of Manual J 7th Ed.

CERTIFIED TESTING LABORATORIES

Architectural Division • 7252 Narcoossee Rd. • Orlando, FL 32822
(407) 384-7744 • Fax (407) 384-7751
Web Site: www.ctllarch.com
E-mail: ctllarch.com



Report Number: CTLA-991W-1-AWT
Report Date: February 18, 2003

STRUCTURAL PERFORMANCE TEST REPORT

Client: ACTION WINDOOR TECHNOLOGY INC
1312 W. CROSBY ROAD
CARROLLTON, TX 75006

Product Type and Series: AWT Series 3950 Vinyl Fin Frame Single Hung Window with Reinforced Sash Top Rail, Stiles & Meeting Rail H-R40 (36"x 72")

Test Specifications: AAMA/NWWDA 101/I.S.2-97 "Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors"

Frame: Vinyl Fin frame measured 35.50" wide x 71.50" high overall. Mitered corner weld construction. Fixed meeting rail secured to each frame jamb with one (1) #8 x 2" PH., PH. screw.

Ventilator: Operable sash measured 33.375" wide x 35.25" high overall. Mitered corner weld construction. Clear lite measured 31.5625" high x 33.5625" high. Fixed lite measured 32.50" wide x 33.4375" high.

Weather Stripping: One (1) strip of woolpile .220" high with integral plastic fin frame sill. One (1) strip of woolpile .250" high with integral plastic fin sash top rail exterior. One (1) strip of woolpile .250" high each sash stile exterior leg. One (1) strip of woolpile .250" high with integral plastic fin each sash stile interior leg. One (1) strip of foam filled bulb weatherstrip sash bottom rail.

Hardware & Location: Two (2) metallic sweep locks located on sash top rail approx 8" from each end of rail. Two (2) metallic keepers located on fixed meeting rail. One (1) tilt latch at each end of sash top rail. One (1) block and tackle at each frame jamb. One (1) pivot bar at each end of sash bottom rail.

Glazing: 5/8" insulated annealed glass consisting of .125" glass .375" air space with swiggle .125" glass. Sash exterior glazed. Fixed lite interior glazed adhesive foam strip backbedding and vinyl snap in glazing bead.

Sealant: A silicone type sealant was used on sill and to seal specimen to test buck.

Weep System: Weep notch measuring 2.25" x leg height located each end of sill weeping to the exterior

Muntins: N/A

Reinforcement: Fixed meeting rail has one (1) piece of extruded aluminum reinforcement measuring .662" wide x .755" high x .099" thick x full length. Top rail, and sash stiles has one (1) piece of extruded aluminum reinforcement measuring .590" wide x .995" high x .115" thick x full length.

Additional Description: N/A

Screen: Roll formed aluminum frame, fiberglass mesh with vinyl spline. Two (2) metallic retainer clips and two (2) metallic plungers. Corners secured with plastic corner keys

Installation: Twenty-six (26) 1.75" roofing nails were used to secure the specimen to the wood test buck. Five (5) were located in head and sill measuring 4", 13", 21", 29", and 33" from left jamb. Eight (8) were located in each jamb measuring 4.50", 14.25", 24", 32.75", 42", 57.25", 60.50" and 70" from sill.

Surface Finish: White Vinyl

Comment: Nominal 2 mil polyethylene film was used to seal against air leakage during structural loads. The film was used in a manner that did not influence the test results.

Performance Test Results

| <u>Paragraph No</u> | <u>Title of Test</u> | <u>Method</u> | <u>Measured</u> | <u>Allowed</u> |
|--|--|---|-------------------------|-------------------------|
| 2.1.2 | Air Infiltration @1.57 psf | ASTM E283-91 | .18 cfm/ft ² | .34 cfm/ft ² |
| The tested specimen meets or exceeds the performance levels specified in AAMA/NWWDA 101/AS 2-97. Results recorded in two (2) decimals at the clients request. Unit tested with shims installed under cam locks. | | | | |
| 2.1.3 | Water Resistance @ 5.0 gph/ft ² | ASTM E547-93 Four (4) five (5) minute cycles | No Entry | No Entry |
| | WTP= 6.75 psf | ASTM E331-93 Fifteen (15) minute duration | No Entry | No Entry |
| Unit tested with insect screen. | | | | |
| 2.1.3 | Water Resistance @ 5.0 gph/ft ² | ASTM E547-93 Four (4) five (5) minute cycles | No Entry | No Entry |
| | WTP= 6 psf | ASTM E331-93 Fifteen (15) minute duration | No Entry | No Entry |
| Unit tested without insect screen. | | | | |
| 2.1.4.2 | Uniform Load Structural Permanent Deformation @ 60 psf positive @ 60 psf negative | ASTM E330-90 Ten (10) second load | .015" .005" | .134" .134" |
| 2.1.8 | Forced Entry Resistance | AAMA 1302.5-76 | | |
| | Test A | | 0" | 1/2" |
| | Test B | | 0" | 1/2" |
| | Test C | | 0" | 1/2" |
| | Test D, E and F | | 0" | 1/2" |
| | Test G | | 0" | 1/2" |

Performance Test Results (continued)

| Paragraph No | Title of Test | Method | Measured | Allowed |
|--------------|---|-------------------------|---|---------|
| 2.2.2.5.1 | Operating Force Sash | AAMA/NWWDA 101/1.S.2-97 | 18 lbs. | 30 lbs. |
| 2.2.2.5.2 | Deglazing Top Rail 70 lbs. Bottom Rail 70 lbs. Left Side 50 lbs. Right Side 50 lbs. | ASTM E987-88 | .039" = 7.8%<100% .038" = 7.6%<100% .050" = 10%<100% .035" = 7.0%<100% | |
| 2.1.7 | Welded Corner Test | AAMA/NWWDA 101/ IS2-97 | Passed | |

Test Date November 21, 2002


Test Completion Date: November 21, 2002

Remarks: Detailed drawings were available for laboratory records and comparison to the test specimen at the time of this report. A copy of this report along with representative sections of the test specimen will be retained by CTL for a period of four (4) years. The results obtained apply only to the specimen tested.

This test report does not constitute certification of this product, but only that the above test results were obtained using the designated test methods and they indicate compliance with the performance requirements (paragraphs as listed) of the above referenced specifications.

Certified Testing Laboratories assumes that all information provided by the client is accurate and that the physical and chemical properties of the components are as stated by the manufacturer.

Certified Testing Laboratories, Inc.



James W. Blakely
Vice President
Architectural Division

cc: Action Window Technology Inc. (3)
File (1)

Report Number: ETC-04-034-14644.0
Test Start Date: 04/10/03
Test Finish Date: 03/16/04
Report Date: 03/18/04
Expiration Date: 03/18/08

Fenestration Structural Test Report
Rendered To:

Vinyl Building Products, Inc.
One Raritan Road
Oakland, NJ 07436

Series/Model
2900 Horizontal Slider (OX)

Description: The product tested was a vinyl Horizontal Sliding window. The test specimen was glazed with 5/8-inch thick insulating glass units constructed with double strength annealed glass. The frame size was 69 inches wide by 48 inches high by 2-3/4 inches deep. See Appendix A.

Test Specification: ANSI/AAMA/NWDA 101/LS.2

Summary of Results

| | |
|--------------------------------------|---------------------------|
| Overall Design Pressure | 35.0 psf |
| Air Leakage Rate | 0.18 scfm/ft ² |
| Maximum Water Pressure Achieved | 5.25 psf |
| Maximum Structural Pressure Achieved | 60.0 psf |
| Forced Entry Resistance - (ASTM) | Grade 10 |

Product Designation **H-R35 69 x 48**

Specifications: The test specimen was evaluated in accordance with ANSI/AAMA/NWDA 101/I.S.2 "Voluntary Specification for Aluminum, Vinyl and Wood Windows and Glass Doors". Sections 1, 2 and 4 only. All performance specifications in this standard shall be met for full compliance to the standard and for product certification, labeling or represented as conforming to this standard.

Referenced Test Reports: NONE

Note - The test data in any section below with an "KTR" comment have not been obtained from this specimen but from the Referenced Test Report with a specimen of the same or larger size and identical construction.

Design Pressure (DP): The product tested herein has been first evaluated to the Gateway pressure in the referenced specification for the performance class rating achieved.

Gateway Performance Tests

| <u>Specification Paragraph</u> | <u>Title of Test</u> | <u>Results</u> | <u>Allowed</u> |
|--------------------------------|--|------------------------------|----------------------------------|
| 2.1.2 | <u>Air Infiltration - ASTM E283</u> Test Pressure - 1.57 psf The tested specimen exceeds the performance levels specified in ANSI/AAMA/NWDA 101/I.S.2 for air infiltration. | 0.18 scfm/ft ² | 0.30 scfm/ft ² |
| 2.1.3 | <u>Water Resistance - ASTM E547</u> 5 gal/hr-ft ² - 4 Test cycles - 24 Minutes Design Pressure - 15.0 psf Test Pressure - 2.86 psf With and Without Screen | Pass | No Leakage |
| 2.1.4.2 | <u>Uniform Structural Load - ASTM E330</u> Design Pressure - 15.0 psf Test Pressure Positive Load - 22.5 psf (150% x DP) Negative Load - 22.5 psf (150% x DP) Note: Measurement taken after load from center of the meeting stile | 0.033 in. 0.020 in. | 0.177 in. 0.177 in. |
| 2.1.7 | <u>Corner Weld</u> Frame - 4 Corners Sashes - 4 Corners | Pass Pass | < 100% < 100% |
| 2.1.8 | <u>Forced Entry Resistance - ASTM F588</u> Lock/Tool Manipulation Tests A1 through A7 Lock/Tool Manipulation | Pass Pass Pass | No Entry No Entry No Entry |
| 2.2.1.6.1 | <u>Operating Force - No Standardized Method</u> Right Sash - Open/Close | 18/18 lbf | 20 lbf |
| 2.2.1.6.2 | <u>Deglazing - ASTM E987</u> Right Sash: Left Stile - 70 lbf Right Stile - 70 lbf Top Rail - 50 lbf Bottom Rail - 50 lbf | 0.0% 0.0% 0.0% 0.0% | <100% <100% <100% <100% |

Optional Performance Tests

The manufacturer specified herein has successfully achieved all the required criteria in Section 2 of the referenced specification for the Gateway size of the achieved Performance Rating and has further successfully tested the product to higher performance levels as indicated below.

Design Pressure (DP): The product tested herein has been additionally evaluated to the Design Pressure referenced below.

| <u>Specification Paragraph</u> | <u>Title of Test</u> | <u>Results</u> | <u>Allowed</u> |
|--------------------------------|--|------------------------|------------------------|
| 4.3 | <u>Water Resistance - ASTM E547</u> 5 gal/hr-ft ² - 4 Test cycles - 24 Minutes Design Pressure - 35.0 psf Test Pressure - 5.25 psf (15% x DP) With and Without Screen | Pass | No Leakage |
| 4.4 | <u>Uniform Structural Load - ASTM E330</u> Design Pressure - 40.0 psf Test Pressure Positive Load - 60.0 psf (150% x DP) Negative Load - 60.0 psf (150% x DP) Note: Measurement taken after load from center of meeting stile | 0.069 in. 0.066 in. | 0.177 in. 0.177 in. |

Conditions, Terms, and General Notes Regarding These Tests

The product tested Has Been compared to the detailed drawings, bill of materials and fabrication information supplied by the client so named herein. Our analysis, which includes dimensional and component description comparisons, indicate the tested product and engineering information supplied by the client "Are Equivalent". See Appendix A. The report and representative samples will be retained for four years from the date of initial test.

These test results were obtained by employing all requirements of the designated test methods with no deviations. The test results and specimen supplied for testing are in compliance with the referenced specifications.

The test results are specific to the product tested by this laboratory and of the sample supplied by the client named herein, and they relate to no other product either manufactured by the client, a Fabricator of the client or of installed field performance.


This report does not constitute an AAMA or NWWDA certified product under the certification programs of these organizations. The program administrator of these programs and organizations may only grant product certification.

ETC Laboratories makes no opinions or endorsements regarding this product and its performance. This report may not be reproduced or quoted in partial form without the expressed written approval of ETC Laboratories.

No conclusions of any kind regarding the adequacy of the glass in the test specimen may be drawn from the test. Procedure "A" in ASTM E330 was used for this test.


ETC Laboratories letters, reports, its name or insignia or mark are for the exclusive use of the client so named herein and any other use is strictly prohibited. The report, letters and the name of ETC Laboratories, its seal or mark shall not be used in any circumstance to the general public or in any advertising.

Limitation of Liability: Due diligence was used in rendering this professional opinion. By acceptance of this report, this client agrees to hold harmless and indemnify ETC Laboratories, its employees and offices and owners against all claims and demands of any kind whatsoever, which arise out of or in any manner connected with the performance of work referred to herein.

FOR ETC LABORATORIES

Mark Sennett

AWS Supervisor



Arthur Murray, VP

Manager, Wind Engineering Laboratory



March 6, 2002

Subject: Elk Product Approval Information

All Prestique® and Capstone® products manufactured in Tuscaloosa, AL are certified under the Miami – Dade County Building Code Office (BCCO). These products also meet the requirements for the Florida Building Code since they are MD approved. The following test protocols must be passed by each of the products in order for MD product certification:

ASTM D3462

PA 100 (110 mph uplift and wind driven rain resistance)

PA 107 (Modified ASTM D3161 - 110 mph wind uplift resistance)

The nailing patterns that were used during the PA 100 and PA 107 wind test protocols for the Prestique and Capstone products are listed below. Also listed below are the Miami – Dade Notice of Acceptance Numbers (NOA).

Raised Profile, Prestique High Definition, Prestique 25, or Prestique 30 –

PA 100 = 4 nails

PA 107 = 5 nails

MD NOA# = 01-1226.04

Prestique I 35 or Prestique I* –

PA 100 = 4 nails

PA 107 = 5 nails

MD NOA# = 01-1226.05

Prestique Plus or Prestique Gallery Collection* –

PA 100 = 4 nails

PA 107 = 4 nails

MD NOA# = 01-1226.03

Capstone*

PA 100 = 4 Nails

PA 107 = 4 Nails

MD NOA# = 01-0523.01

* As per the Elk Limited Warranty, six nails are required for the Elk high wind warranty.

If there are any questions please contact:


Mike Reed – Technical Manager
(205) 342-0287

or


Daniel DeJarnette – QA Engineer
(205) 342-0298



ROOFING PRODUCTS SPECIFICATIONS – TUSCALOOSA, AL



**PRESTIQUE®
HIGH DEFINITION®**



RAISED PROFILE™

Prestique High Definition and *Raised Profile* – *High Definition*

| | | |
|----------------|-------------------|-------------------------------------|
| Product size | 13 1/2" x 39 3/4" | 50-year limited warranty period: |
| Exposure | 5 1/2" | non-prorated coverage for |
| Pieces/Bundle | 16 | shingles and application labor for |
| Bundles/Square | 4/98.5 sq.ft. | the initial 5 years, plus an option |
| Squares/Pallet | 11 | for transferability*; prorated |
| | | coverage for application labor and |
| | | shingles for balance of limited |
| | | warranty period; 5-year limited |
| | | wind warranty*. |

Raised Profile

| | | |
|----------------|-------------------|-------------------------------------|
| Product size | 13 1/2" x 38 3/4" | 30-year limited warranty period: |
| Exposure | 5 1/2" | non-prorated coverage for |
| Pieces/Bundle | 22 | shingles and application labor for |
| Bundles/Square | 3/100 sq.ft. | the initial 5 years, plus an option |
| Squares/Pallet | 16 | for transferability*; prorated |
| | | coverage for application labor and |
| | | shingles for balance of limited |
| | | warranty period; 5-year limited |
| | | wind warranty*. |

Prestique High Definition

| | | |
|----------------|-------------------|-------------------------------------|
| Product size | 13 1/2" x 39 3/4" | 40-year limited warranty period: |
| Exposure | 5 1/2" | non-prorated coverage for |
| Pieces/Bundle | 16 | shingles and application labor for |
| Bundles/Square | 4/98.5 sq.ft. | the initial 5 years, plus an option |
| Squares/Pallet | 14 | for transferability*; prorated |
| | | coverage for application labor and |
| | | shingles for balance of limited |
| | | warranty period; 5-year limited |
| | | wind warranty*. |

HIP AND RIDGE SHINGLES

| | |
|----------------|-----------------------------|
| Size: | 12" x 12" |
| Exposure: | 6 1/2" |
| Pieces/Bundle: | 45 |
| Coverage: | 4 Bundles = 100 linear feet |

Prestique High Definition

| | | |
|----------------|-------------------|-------------------------------------|
| Product size | 13 1/2" x 38 3/4" | 30-year limited warranty period: |
| Exposure | 5 1/2" | non-prorated coverage for |
| Pieces/Bundle | 22 | shingles and application labor for |
| Bundles/Square | 3/100 sq.ft. | the initial 5 years, plus an option |
| Squares/Pallet | 16 | for transferability*; prorated |
| | | coverage for application labor and |
| | | shingles for balance of limited |
| | | warranty period; 5-year limited |
| | | wind warranty*. |

Elk Sunset System

| |
|-------------------------------|
| 52 Bundles/Pallet |
| 18 Pallets/Truck |
| 936 Bundles/Truck |
| 19 Pieces/Bundle |
| 1 Bundle = 120.33 linear feet |

Available Colors: Antique Slate, Weatheredwood, Shakedown, Sablewood, Hickory, Barkwood**, Forest Green, Wedgewood**, Birchwood**, Sandalwood, Gallery Collection: Balsam Forest*, Weathered Sage*, Sienna Sunset*.

All Prestique, Raised Profile and Seal-A-Ridge roofing products contain Elk WindGuard® sealant. WindGuard activates with the sun's heat, bonding shingles into a wind and weather resistant cover that resists blow-offs and leaks.

Check for availability with built-in StainGuard® treatment to inhibit the discoloration of roofing granules caused by the growth of certain types of algae. Not available in Sablewood.

All Prestique and Raised Profile shingles meet UL® Wind Resistant (UL 997) and Class "A" Fire Ratings (UL 790); and ASTM Specifications D 3018, Type-I; D 3161, Type-I; E 108 and the requirements of ASTM D 3462.

All Prestique and Raised Profile shingles meet the latest Metro Dade building code requirements.

*See actual limited warranty for conditions and limitations.

**Check for product availability.

SPECIFICATIONS

SCOPE: Work includes furnishing all labor, materials and equipment necessary to complete installation of (name) shingles specified herein. Color shall be (name of color). Hip and ridge type to be Elk Seal-A-Ridge with formula FLX.

All exposed metal surfaces (flashing, vents, etc.) to be painted with matching Elk roof accessory paint.

PREPARATION OF ROOF DECK: Roof deck to be dry, well-seasoned 1" x 6" (25.4mm x 152.4mm) boards; exterior-grade plywood (exposure 1 rated sheathing) at least 3/8" (9.525mm) thick conforming to the specifications of the American Plywood Association; 7/16" (11.074mm) oriented strandboard; or chipboard. Most fire retardant plywood decks are NOT approved substrates for Elk shingles. Consult Elk Field Service for application specifications over other decks and other slopes.

MATERIALS: Underlayment for standard roof slopes, 4" per foot (101.6/304.8mm) or greater: apply non-perforated No. 15 or 30 asphalt-saturated felt underlayment. For low slopes [4" per foot (101.6/304.8mm) to a minimum of 2" per foot (50.8/304.8mm)], use two plies of underlayment overlapped a minimum of 19". Fasteners shall be of sufficient length and holding power for securing material as required by the application instructions printed on shingle wrapper.

For areas where algae is a problem, shingles shall be (name) with StainGuard treatment, as manufactured by the Elk Tuscaloosa plant. Hip and ridge type to be Seal-A-Ridge with formula FLX with StainGuard treatment.

Complete application instructions are published by Elk and printed on the back of every shingle bundle. All

warranties are contingent upon the correct installation as shown on the instructions. These instructions are the minimum required to meet Elk application requirements. In some areas, building codes may require additional application techniques or methods beyond our instructions. In these cases, the local code must be followed. Under no circumstances will Elk accept application requirements less than those contained in its application instructions.

For specifications in CSI format, call 800.354.SPEC (7732) or e-mail specinfo@elkcorp.com.

**SOUTHEAST &
ATLANTIC OFFICE:**
800.945.5551


CORPORATE HEADQUARTERS:
800.354.7732

PLANT LOCATION:
800.945.5545


ELK
www.elkcorp.com

DIRECTIONS FOR APPLICATION


Please read carefully. Failure to follow these instructions may void the product warranty. See specific application instructions for Prestique® Plus and Prestique Gallery Collection™ 110 MPH, and Prestique 190 MPH limited wind warranty requirements.




● **VALLEY CONSTRUCTION OPTION** (California Open and California Closed are also acceptable) NOTE: For complete ARMA valley installation details, see ARMA Residential Asphalt Roofing Manual.



VALLEY CENTER LINE



VALLEY CENTER LINE



VALLEY CENTER LINE

DIRECTIONS FOR APPLICATION

These application instructions are the minimum required to meet Elk's application requirements. Your failure to follow these instructions may void the product warranty. In some areas, the building codes may require additional application techniques or methods beyond our instructions. In these cases, the local code must be followed. Under no circumstances will Elk accept application requirements that are less than those printed here. Shingles should not be jammed tightly together. All attics should be properly ventilated. Note: It is not necessary to remove tape on back of shingle.

● DECK PREPARATION

Roof decks should be dry, well-seasoned 1" x 6" boards or exterior grade plywood minimum 3/8" thick and conform to the specifications of the American Plywood Association or 7/16" oriented strandboard, or 7/16" chipboard.

● UNDERLAYMENT

Apply underlayment (Non-Perforated No. 15 or 30 asphalt saturated felt). Cover drip edge at eaves only.

For low slope (2/12 up to 4/12), completely cover the deck with two plies of underlayment overlapping a minimum of 1'. Begin by fastening a 18" wide strip of underlayment placed along the eaves. Place a full 36" wide sheet over the starter, horizontally placed along the eaves and completely overlapping the starter strip.

EAVE FLASHING FOR ICE DAMS (ASK A ROOFING CONTRACTOR, REFER TO ARMA MANUAL OR CHECK LOCAL CODES)

For standard slope (4/12 to less than 21/12), use coated roll roofing of no less than 50 pounds over the felt underlayment extending from the eave edge to a point at least 24" beyond the inside wall of the living space below or one layer of a self-adhered eave and flashing membrane.

For low slope (2/12 up to 4/12), use a continuous layer of asphalt plastic cement between the two plies of underlayment from the eave edge up roof to a point at least 24" beyond the inside wall of the living space below or one layer of a self-adhered eave and flashing membrane.

Consult the Elk Field Service Department for application specifications over other decks and other slopes.

● STARTER SHINGLE COURSE

USE AN ELK STARTER STRIP OR A STRIP SHINGLE INVERTED WITH THE HEAD FLAP APPLIED AT THE EAVE EDGE. With at least 4" trimmed from the end of the first shingle, start at the rake edge overhanging the eave 1/2" to 3/4". Fasten 2" from the lower edge and 1" from each side. Shingles may be applied with a course alignment of 45° on the roof.

● FIRST COURSE

Start at rake and continue course with full shingles laid flush with the starter course.

● SECOND COURSE

Start at the rake with the shingle having 10" trimmed off and continue across roof with full shingles.

● THIRD COURSE

Start at the rake with the shingle having 20" trimmed off and continue across roof with full shingles.

● FOURTH COURSE

Start at the rake and continue with full shingles across roof.

FIFTH AND SUCCEEDING COURSES.

Repeat application as shown for second, third, and fourth courses. Do not rack shingles straight up the roof.

● VALLEY CONSTRUCTION

Open, woven and closed cut valleys are acceptable when applied by Asphalt Roofing Manufacturing Association (ARMA) recommended procedures. For metal valleys, use 36" wide vertical underlayment prior to applying 18" metal flashing (secure edge with nails). No nails are to be within 6" of valley center.

● RIDGE CONSTRUCTION

For ridge construction use Class "A" Seal-A-Ridge® with formula FLX™ (See ridge package for installation instructions.)

FASTENERS

While nailing is the preferred method for Elk shingles, Elk will accept fastening methods according to the following instructions.

Always nail or staple through the fastener line or on products without fastener lines, nail or staple between and in line with sealant dots.

NAILS: Corrosive resistant, 3/8" head, minimum 12-gauge roofing nails. Elk recommends 1-1/4" for new roofs and 1-1/2" for re-roofs. In cases where you are applying shingles to a roof that has an exposed overhang, for new roofs only, 3/4" ring shank nails are allowed to be used from the eave's edge to a point up the roof that is past the outside wall line. 1" ring shank nails allowed for re-roof.

STAPLES: Corrosive resistant, 16-gauge minimum, crown width minimum of 15/16". Note: An improperly adjusted staple gun can result in raised staples that can cause a fish-mouthed appearance and can prevent sealing.

Fasteners should be long enough to obtain 3/4" deck penetration or penetration through deck, whichever is less.


MANSARD APPLICATIONS

Correct fastening is critical to the performance of the roof. For slopes exceeding 60° (or 21/12) use six fasteners per shingle. Locate fasteners in the fastener area 1" from each side edge with the remaining four fasteners equally spaced along the length of the double thickness (laminated) area. Only fastening methods according to the above instructions are acceptable.

LIMITED WIND WARRANTY


• For a Limited Wind Warranty, all Prestique and Raised Profile™ shingles must be applied with 4 properly placed fasteners, or in the case of mansard applications, 6 properly placed fasteners per shingle.

• For a Limited Wind Warranty up to 110 MPH for Prestique 1, shingles must be applied with 6 properly placed NAILS per shingle. SHINGLES APPLIED WITH STAPLES WILL NOT QUALIFY FOR THIS ENHANCED LIMITED WIND WARRANTY. Also, Elk Starter Strip shingles must be applied at the eaves and rake edges to qualify Prestique Plus, Prestique Gallery Collection and Prestique 1 shingles for this enhanced Limited Wind Warranty. Under no circumstances should the Elk Shingles or the Elk Starter Strip overhang the eaves or rake edge more than 3/4" of an inch.



HELP STOP BLOW-OFFS AND CALL-BACKS

A minimum of four fasteners must be driven into the DOUBLE THICKNESS (laminated) area of the shingle. Nails or staples must be placed along – and through – the "fastener line" or on products without fastener lines, nail or staple between and in line with sealant dots. CAUTION: Do not use fastener line for shingle alignment.



Refer to local codes which in some areas may require specific application techniques beyond those Elk has specified. All Prestique and Raised Profile shingles have a U.L.® Wind Resistance Rating when applied in accordance with these instructions using nails or staples on re-roofs as well as new construction.

CAUTION TO WHOLESALE: Careless and improper storage or handling can harm fiberglass shingles. Keep these shingles completely covered, dry, reasonably cool, and protected from the weather. Do not store near various sources of heat. Do not store in direct sunlight until applied. DO NOT DOUBLE STACK. Systematically rotate all stock so that the material that has been stored the longest will be the first to be moved out.

© 2002 Elk Corporation of Dallas.

All trademarks, ®, are registered trademarks of Elk Corporation of Dallas, an ELCOR company. Raised Profile, RidgeCrest, Gallery Collection and FLX are trademarks pending registration of Elk Corporation of Dallas. U.L. is a registered trademark of Underwriters Laboratories, Inc.

ELK
www.elkcorp.com



333 Pringlen Road
Northbrook, Illinois 60062-2038
United States Country Code (1)
(847) 272-8800
FAX No. (847) 272-8129
<http://www.ul.com>

March 4, 2002

GAF Materials Corporation
Mr Randall Ziegler
1361 Alps Road
Wayne, NJ 07470

Our Reference: R21

Subject: UL Listed products

Dear Mr Ziegler:

This is in response to your request to identify some of the products that are currently Listed with Underwriters Laboratories relating to various Standards. Following are those products:


Royal Sovereign®
Marquis®/Marquis® WeatherMax®
SLATELINE®
Grand canyon™
Grand Sequoia®
Country Mansion™
Country Estates™
Timberline 30™
Timberline Select™ 40
Timberline Ultra™
Sentinel®


The above products have been tested to ASTM D3462, Class A UL790/ASTM E108 and UL 997/ ASTM D3161 (secured with 4 nails) with velocities up to 110 mph and have successfully met those test criteria.

If you have any questions please feel free to contact the writer.

Very truly yours,

Reviewed by,



Roger Anderson (Ext. 43283)
Senior Engineering Associate
Conformity Assessment Services- 3011E-NBK


Douglas C. Miller (Ext. 43262)
Engineering Group Leader
Conformity Assessment Services- 3011E-NBK

** TOTAL PAGE.01 **

APPLICATION INSTRUCTIONS

Note: These shingles must be nailed a nominal 5 5/8" (143mm) from bottom of shingles, not in or above self seal, as shown. Nails should remain unexposed.



GENERAL INSTRUCTIONS


- **ROOF DECKS:** For use on new or reroofing work over well-seasoned, supported wood deck, tightly-constructed with maximum 6" (152mm) wide lumber, having adequate nail-holding capacity and smooth surface. Plywood decking as recommended by The Engineered Wood Assn. is acceptable. Plywood decks for Class A installations must be 3/8" (10mm) thick or greater with underlayments as noted below. Shingles must not be fastened directly to insulation or insulated deck unless authorized in writing by GAF Materials Corporation. Roof decks and existing surfacing material must be dry prior to application of shingles.
- **UNDERLAYMENT:** Underlayment is required on new construction and required for reroofing when old roof is removed from the deck. Use only "breather type" material like GAF Materials Corporation Shingle-Mate® Underlayment or equivalent. Underlayments must be installed flat, without wrinkles.
- **FASTENERS:** Use of nails is recommended. (Staple specifications and application instructions are available from GAF Materials Corporation, Contractor Services Dept., 1361 Alps Road, Wayne, NJ 07470.) Use only zinc coated steel or aluminum, 10-12 gauge, barbed, deformed or smooth shank roofing nails with heads 3/8" (10mm) to 7/16" (12mm) in diameter. Fasteners should be long enough to penetrate at least 3/4" (19mm) into wood decks or just through the plywood decks. Fasteners must be driven flush with the surface of the shingle. Over driving will damage the shingle. Raised fasteners will interfere with the sealing of the shingles. For normal installation, four fasteners must be installed per shingle, a nominal 5 5/8" (143mm) up from the bottom of the shingle. Fasteners must be installed approximately 11-1/2" (292-318mm) and 11 1/2"-12 1/2" (292-318mm) from each side.
- **WIND RESISTANT:** These shingles have a special thermal sealant that firmly bonds the shingles together after application when exposed to sun and warm temperatures. Shingles installed in Fall or Winter may not seal until the following Spring. If shingles are damaged by winds before sealing or are not exposed to adequate surface temperatures, or if the self-sealant gets dirty, the shingles may never seal. Failure to seal under these circumstances results from the nature of self-sealing shingles and is not a manufacturing defect. To insure immediate sealing,

- apply 2 quarter-sized dabs of shingle tab adhesive on the back of each tab, approximately 1" (25mm) from end and 1" (25mm) up from bottom of each tab corner. The shingle must be pressed firmly into the adhesive.
- NOTE: Application of excess tab adhesive can cause blistering of the shingle.
- For maximum wind resistance along rakes, cement shingles to underlayment and each other in a 4" (102mm) width of asphalt plastic roof cement.
- NOTE: The film strips on the back of each shingle are to prevent sticking together of the shingles while in the bundle. Their removal is NOT required during application.
- **CANADIAN COLD WEATHER APPLICATIONS:** CSA A123.5-M90 mandates that shingles applied between September 1 and April 30 shall be adhered with a compatible field-applied adhesive. See Wind Resistant for GAF Materials Corporation's recommendations for the application of that adhesive.
- **MANSARD AND STEEP SLOPE APPLICATIONS:** For roof slopes greater than 21" (1750mm/m) per foot (do NOT use on vertical side walls), shingle sealing must be enhanced by hand sealing. After fastening the shingle in place, apply 2 quarter-sized dabs of shingle tab adhesive as indicated in Wind Resistant above. The shingle must be pressed firmly into the adhesive.
- **EXPOSURE: 5" (127mm)**
- **THROUGH VENTILATION:** All roof structures must be provided with through ventilation to prevent entrapment of moisture laden air behind roof sheathing. Ventilation provisions must at least meet or exceed current F.H.A., H.U.D. or local code minimum requirements.
- **NON-CORRODING METAL DRIP EDGES:** Recommended along rake and eave edges on all decks, especially plywood decks.
- **ASPHALT PLASTIC CEMENT:** For use as shingle tab adhesive. Must conform to ASTM D4586 Type I or II.

1 Underlayment: Standard Slope-4/12 (333mm/m) or more


Application of underlayment: Cover deck with one layer of underlayment installed without wrinkles. Use only enough nails to hold underlayment in place until covered by shingles.

Application of eave flashing: Install eave flashing such as GAF Materials Corporation Weather Watch® or StormGuard® Leak Barrier in localities where leaks may be caused by water backing up behind ice or debris dams. Eave flashing must overhang the roof edge by 3/8" (10mm) and extend 24" (610mm) beyond the inside wall line.




1a Underlayment: Low Slope 2/12-4/12 (167mm-333mm/m)

Application of underlayment and eave flashing: Completely cover the deck with two layers of underlayment as shown. Use only enough nails to hold underlayment in place until covered by shingles. Use blind nailing for eave flashings. At eaves and where ice dams can be expected, use one layer of GAF Materials Corporation Weather Watch® or StormGuard® Leak Barrier. Eave flashing must overhang the roof edge by 3/8" (10mm) and extend 24" (610mm) beyond the inside wall line. Where ice dams or debris dams are not expected, install 2 plies of Shingle-Mate® underlayment.




2 Starter Course

Use of any GAF MC 3-tab Shingle is recommended. Apply as shown.



3 First Course


Start and continue with full shingles laid flush with the starter course. Shingles may be laid from left to right or right to left. DO NOT lay shingles straight up the roof since this procedure can cause an incorrect color blend on the roof and may damage the shingles.



4 Second Course


Start and continue second course and all even numbered courses as shown. Position the shingle on the top of the cutouts of the underlying shingle so that there will be 5" (127mm) of each shingle exposed. Strike a chalk line about every 6 courses to check parallel alignment with eaves. Factory applied self-sealing dots on lower courses are designed to seal down the shingle tabs in an upper course.

NOTE: Shingles may be laid from either left or right hand side. Start at either rake edge with shingles having 6" (152mm) trimmed from rake.




5 Hip and Ridge


Use GAF hip & ridge shingles, or cut hip & ridge shingles from these full shingles, and apply as shown. Position laps away from prevailing wind direction.




6 Wall Flashing (Sloped Roof to Vertical Wall)




7 Chimney Flashing




8 Valley Construction - Closed or Woven Valley



9 Valley Construction—Open Cut



10 Valley Construction—Closed Cut



Precautionary Notes

These shingles are fiberglass, self-sealing asphalt shingles. Because of the natural characteristics of the high quality waterproofing material used, these shingles will be stiff in cold weather and flexible in hot weather.

1. Bundles should not be dropped on edge nor should attempt be made to separate shingles by "breaking" over ridge or other bundles.
2. Handle carefully. Shingles can easily be broken in cold weather or their edges damaged in hot weather.
3. All exposed materials must be of Class A type.
4. Storage should be in a covered, ventilated area—maximum temperature 110°F (43°C). Store on flat surface and use weight equalization boards if pallets are to be double stacked. Shingles must be protected from weather when stored at job site. Do not store near steam pipes, radiators, etc., or in sunlight. All rolled product must be stored on ends.
5. If shingles are to be applied during PROLONGED COLD periods or in areas where airborne dust or sand can be expected before sealing occurs, the shingles MUST be hand sealed. See Wind Resistant instructions.

Re-Roofing

If old asphalt shingles are to remain in place, nail down or cut away all loose, curled or lifted shingles; replace with new; and just before applying the new roofing, sweep the surface clean of all loose debris. Since any irregularities may show through the new shingles, be sure the underlying shingles provide a smooth surface. Fasteners must be of sufficient length to penetrate the wood deck at least 3/4" (19mm) or just through plywood. Follow other above instructions for application. Note: Shingles can be applied over wood shingles when precautions have been taken to provide an acceptable smooth surface. This includes cutting back old shingles at eaves and rakes and installing new wood edging strips as needed. Make surface smooth and use beveled wood strips if necessary. Install #30 underlayment to maintain Class A rating.

This product is sold with an express LIMITED WARRANTY only. A copy of the LIMITED WARRANTY stating its terms and restrictions is printed on the product wrapper or may be obtained from the distributor of this product or directly from GAF Materials Corporation. Any deviation from printed instructions shall be the responsibility of applicator and/or specifier.

©2000 GAF Materials Corporation

ENGLISH 110600




TIMBERLINE[®] Ultra[®] SHINGLES

TIMBERLINE[®] 40 SHINGLES TIMBERLINE[®] 30 SHINGLES

APPLICATION INSTRUCTIONS

Timberline[®] Series shingles come in either 36" (914mm) or 36-15/16" (938mm) lengths, depending on shingle brand. Application instructions apply to both.

These shingles must be nailed a nominal 5-5/8" (143mm) from bottom of shingles, as shown, to allow for penetration through the double ply area just above the tabs. Nails should remain unexposed.




GENERAL INSTRUCTIONS


- **ROOF DECKS:** For use on new or reroofing work over well-seasoned, supported wood deck, tightly-constructed with maximum 6" (152mm) wide lumber, having adequate nail-holding capacity and smooth surface. Plywood decking as recommended by The Engineered Wood Assn. is acceptable. Plywood decks for Class A installations must be 3/8" (10mm) thick or greater with underlayment as noted below. Shingles must not be fastened directly to insulation or insulated deck unless authorized in writing by GAF Materials Corporation. Roof decks and existing surfacing material must be dry prior to application of shingles.
- **UNDERLAYMENT:** Underlayment beneath shingles has many benefits, including preventing wind driven rain from reaching the interior of the building and preventing sap in some wood decking from reacting with asphalt shingles. Underlayment is also required by many code bodies. Consult your local building department for its requirements. Where an underlayment is to be installed, a breather-type underlayment such as GAFMC's Shingle-Mate[®] underlayment is recommended. Underlayment must be installed flat, without wrinkles.
- **FASTENERS:** Use of nails is recommended. (Staple Specifications and application instructions are available from GAF Materials Corporation, Contractor Services Dept., 1361 Alps Road, Wayne, NJ 07470.) Use only zinc coated steel or aluminum, 10-12 gauge, barbed, deformed or smooth shank roofing nails with heads 3/8" (10mm) to 7/16" (12mm) in diameter. Fasteners should be long enough to penetrate at least 3/4" (19mm) into wood decks or just through the plywood decks. Fasteners must be driven flush with the surface of the shingle. Over driving will damage the shingle. Raised fasteners will interfere with the sealing of the shingles. For normal installation, four fasteners must be installed per shingle, a nominal 5-5/8" (143mm) up from the bottom of the shingle, to penetrate both layers of the shingle. Fasteners must be installed approximately 1" - 1 1/2" (25-38mm) and 11-1/2" - 12-1/2" (292-318mm) from each side.
- **WIND RESISTANT:** These shingles have a special thermal sealant that firmly bonds the shingles together when exposed to sun and warm temperatures. Shingles installed in Fall or Winter may not seal until the following Spring. If shingles are damaged by winds

- before sealing or are not exposed to adequate surface temperatures, or if the self-sealant gets dirty, the shingles may never seal. Failure to seal under these circumstances results from the nature of self-sealing shingles and is not a manufacturing defect. To insure immediate sealing, apply 4 quarter-sized dabs of shingle tab adhesive on the back of the shingle 1" (25mm) and 13" (330mm) in from each side and 1" (25mm) up from bottom of the shingle. The shingle must be pressed firmly into the adhesive.
- NOTE: Application of excess tab adhesive can cause blistering of the shingle.
- For maximum wind resistance along rakes, cement shingles to underlayment and each other in a 4" (102mm) width of asphalt plastic roof cement.
- NOTE: The film strips on the back of each shingle are to prevent sticking together of the shingles while in the bundle. Their removal is NOT required during application.
- **CANADIAN COLD WEATHER APPLICATIONS:** CSA 123.5-M90 mandates that shingles applied between September 1 and April 30 shall be adhered with a compatible field-applied adhesive. See Wind Resistant for GAF Materials Corporation's recommendations for the application of that adhesive.
- **MANSARD AND STEEP SLOPE APPLICATIONS:** For roof slopes greater than 21° (1750mm/m) per foot (do NOT use on vertical side walls), shingle sealing must be enhanced by hand sealing. After fastening the shingle in place, apply 4 quarter-sized dabs of shingle tab adhesive as indicated in Wind Resistant above. The shingle must be pressed firmly into the adhesive.
- **EXPOSURE:** 5" (127mm)
- **THROUGH VENTILATION:** All roof structures must be provided with through ventilation to prevent entrapment of moisture laden air behind roof sheathing. Ventilation provisions must at least meet or exceed current F.H.A., H.U.D. or local code minimum requirements.
- **NON-CORRODING METAL DRIP EDGES:** Recommended along rake and eave edges on all decks, especially plywood decks.
- **ASPHALT PLASTIC CEMENT:** For use as shingle tab adhesive. Must conform to ASTM D4586 Type I or II.


- 1 Underlayment: Standard Slope 4/12 (333mm/m) or more**
Application of underlayment: Cover deck with one layer of underlayment installed without wrinkles. Use only enough nails to hold underlayment in place until covered by shingles.
Application of eave flashing: Install eave flashing such as GAF Materials Corporation Weather Watch[®] or StormGuard[®] Leak Barrier in localities where leaks may be caused by water backing up behind ice or debris dams. Eave flashing must overhang the roof edge by 3/8" (10mm) and extend 24" (610mm) beyond the inside wall line.




- 2 Starter Course**
Apply as shown.



- 1a Underlayment: Low Slope 2/12-4/12 (167mm-333mm/m)**
Application of underlayment and eave flashing: Completely cover the deck with two layers of underlayment as shown. Use only enough nails to hold underlayment in place until covered by shingles. Use blind nailing for eave flashings. At eaves and where ice dams can be expected, use one layer of GAF Materials Corporation Weather Watch[®] or StormGuard[®] Leak Barrier. Eave flashing must overhang the roof edge by 3/8" (10mm) and extend 24" (610mm) beyond the inside wall line. Where ice dams or debris dams are not expected, install 2 plies of Shingle-Mate[®] underlayment.




- 3 First Course**
Start and continue with full shingles laid flush with the starter course. Shingles may be laid from left to right or right to left. DO NOT lay shingles straight up the roof since this procedure can cause an incorrect color blend on the roof and may damage the shingles.




4 Second Course

Start and continue second course as shown. Trim 6" (152mm) from the end of the shingle. Position the shingles in the second and subsequent courses flush with the tops of the wide cutouts. This results in a 5" (127mm) exposure. Continue with full width shingles across the roof. Strike a chalk line about every 6 courses to check parallel alignment with eaves. NOTE: Shingles may be laid from either left or right hand side. Start at either rake edge with shingles having 6" (152mm) trimmed from rake.




6 Fourth Course and Remaining Courses


Trim 17" (432 mm) from first shingle in the course, then continue with full shingles across the roof. Fifth and subsequent courses repeat full shingle instructions from Step 3.



8 Wall Flashing (Sloped Roof to Vertical Wall)




10 Valley Construction-Closed Cut




5 Third Course

Trim 11" (279mm) from the first shingle in the course then continue with full shingles across the roof.




7 Hip and Ridge


For single layer application, use hip and ridge shingles and apply as shown. To enhance appearance, use GAF TIMBERTEX® or a double layer application of Universal Hip & Ridge. (One bundle of TIMBERTEX® Hip & Ridge covers 20 lineal ft.-6.1 meters.) For double application, start with triple thickness of precut Hip & Ridge shingles and continue remainder with double thickness. Fasten in same manner as single application shown. Apply laps away from prevailing wind direction.



9 Chimney Flashing



11 Valley Construction-Open



Precautionary Notes

Timberline® Series shingles are fiberglass, self-sealing asphalt shingles. Because of the natural characteristics of the high quality waterproofing material used, these shingles will be stiff in cold weather and flexible in hot weather.

1. Bundles should not be dropped on edge nor should attempt be made to separate shingles by "breaking" over ridge or other bundles.
2. Handle carefully. Shingles can easily be broken in cold weather or their edges damaged in hot weather.
3. All exposed materials must be of Class A type.
4. Storage should be in a covered, ventilated area-maximum temperature 110°F (43°C.). Store on flat surface and use weight equalization boards if pallets are to be double stacked. Shingles must be protected from weather when stored at job site. Do not store near steam pipes, radiators, etc., or in sunlight. All rolled product must be stored on ends.
5. If shingles are to be applied during PROLONGED COLD periods or in areas where airborne dust or sand can be expected before sealing occurs, the shingles MUST be hand sealed. See Wind Resistant instructions.

Re-Roofing

If old asphalt shingles are to remain in place, nail down or cut away all loose, curled or lifted shingles; replace with new; and just before applying the new roofing, sweep the surface clean of all loose debris. Since any irregularities may show through the new shingles, be sure the underlying shingles provide a smooth surface. Fasteners must be of sufficient length to penetrate the wood deck at least 3/4" (19mm) or just through plywood. Follow other above instructions for application.


Note: Shingles can be applied over wood shingles when precautions have been taken to provide an acceptable smooth surface. This includes cutting back old shingles at eaves and rakes and installing new wood edging strips as needed. Make surface smooth and use beveled wood strips if necessary. Install #30 underlayment to maintain Class A rating.

This product is sold with an express LIMITED WARRANTY only. A copy of the LIMITED WARRANTY stating its terms and restrictions is printed on the product wrapper or may be obtained from the distributor of this product or directly from GAF Materials Corporation. Any deviation from printed instructions shall be the responsibility of applicator and/or specifier.

©2002 GAF Materials Corporation

ENGLISH 121201

GLAZING OPTION CROSS SECTION
GLAZING NOT AVAILABLE ON V500-JUNE 15, 1982 REGION



8

VIEW (SIDE VIEW)

VIEWER OF CHANGE

ADD WITH THIS

VIEW 2

VIEW 1

VIEW 3

VIEW 4

VIEW 5

VIEW 6

VIEW 7

VIEW 8

VIEW 9

VIEW 10

VIEW 11

VIEW 12

VIEW 13

VIEW 14

VIEW 15

VIEW 16

VIEW 17

VIEW 18

VIEW 19

VIEW 20

VIEW 21

VIEW 22

VIEW 23

VIEW 24

VIEW 25

VIEW 26

VIEW 27

VIEW 28

VIEW 29

VIEW 30

VIEW 31

VIEW 32

VIEW 33

VIEW 34

VIEW 35

VIEW 36

VIEW 37

VIEW 38

VIEW 39

VIEW 40

VIEW 41

VIEW 42

VIEW 43

VIEW 44

VIEW 45

VIEW 46

VIEW 47

VIEW 48

VIEW 49

VIEW 50

VIEW 51

VIEW 52

VIEW 53

VIEW 54

VIEW 55

VIEW 56

VIEW 57

VIEW 58

VIEW 59

VIEW 60

VIEW 61

VIEW 62

VIEW 63

VIEW 64

VIEW 65

VIEW 66

VIEW 67

VIEW 68

VIEW 69

VIEW 70

VIEW 71

VIEW 72

VIEW 73

VIEW 74

VIEW 75

VIEW 76

VIEW 77

VIEW 78

VIEW 79

VIEW 80

VIEW 81

VIEW 82

VIEW 83

VIEW 84

VIEW 85

VIEW 86

VIEW 87

VIEW 88

VIEW 89

VIEW 90

VIEW 91

VIEW 92

VIEW 93

VIEW 94

VIEW 95

VIEW 96

VIEW 97

VIEW 98

VIEW 99

VIEW 100

VIEW 101

VIEW 102

VIEW 103

VIEW 104

VIEW 105

VIEW 106

VIEW 107

VIEW 108

VIEW 109

VIEW 110

VIEW 111

VIEW 112

VIEW 113

VIEW 114

VIEW 115

VIEW 116

VIEW 117

VIEW 118

VIEW 119

VIEW 120

VIEW 121

VIEW 122

VIEW 123

VIEW 124

VIEW 125

VIEW 126

VIEW 127

VIEW 128

VIEW 129

VIEW 130

VIEW 131

VIEW 132

VIEW 133

VIEW 134

VIEW 135

VIEW 136

VIEW 137

VIEW 138

VIEW 139

VIEW 140

VIEW 141

VIEW 142

VIEW 143

VIEW 144

VIEW 145

VIEW 146

VIEW 147

VIEW 148

VIEW 149

VIEW 150

VIEW 151

VIEW 152

VIEW 153

VIEW 154

VIEW 155

VIEW 156

VIEW 157

VIEW 158

VIEW 159

VIEW 160

VIEW 161

VIEW 162

VIEW 163

VIEW 164

VIEW 165

VIEW 166

VIEW 167

VIEW 168

VIEW 169

VIEW 170

VIEW 171

VIEW 172

VIEW 173

VIEW 174

VIEW 175

VIEW 176

VIEW 177

VIEW 178

VIEW 179

VIEW 180

VIEW 181

VIEW 182

VIEW 183

VIEW 184

VIEW 185

VIEW 186

VIEW 187

VIEW 188

VIEW 189

VIEW 190

VIEW 191

VIEW 192

VIEW 193

VIEW 194

VIEW 195

VIEW 196

VIEW 197

VIEW 198

VIEW 199

VIEW 200

VIEW 201

VIEW 202

VIEW 203

VIEW 204

VIEW 205

VIEW 206

VIEW 207

VIEW 208

VIEW 209

VIEW 210

VIEW 211

VIEW 212

VIEW 213

VIEW 214

VIEW 215

VIEW 216

VIEW 217

VIEW 218

VIEW 219

VIEW 220

VIEW 221

VIEW 222

VIEW 223

VIEW 224

VIEW 225

VIEW 226

VIEW 227

VIEW 228

VIEW 229

VIEW 230

VIEW 231

VIEW 232

VIEW 233

VIEW 234

VIEW 235

VIEW 236

VIEW 237

VIEW 238

VIEW 239

VIEW 240

VIEW 241

VIEW 242

VIEW 243

VIEW 244

VIEW 245

VIEW 246

VIEW 247

VIEW 248

VIEW 249

VIEW 250

VIEW 251

VIEW 252

VIEW 253

VIEW 254

VIEW 255

VIEW 256

VIEW 257

VIEW 258

VIEW 259

VIEW 260

VIEW 261

VIEW 262

VIEW 263

VIEW 264

VIEW 265

VIEW 266

VIEW 267

VIEW 268

VIEW 269

VIEW 270

VIEW 271

VIEW 272

VIEW 273

VIEW 274

VIEW 275

VIEW 276

VIEW 277

VIEW 278

VIEW 279

VIEW 280

VIEW 281

VIEW 282

VIEW 283

VIEW 284

VIEW 285

VIEW 286

VIEW 287

VIEW 288

VIEW 289

VIEW 290

VIEW 291

VIEW 292

VIEW 293

VIEW 294

VIEW 295

VIEW 296

VIEW 297

VIEW 298

VIEW 299

VIEW 300

VIEW 301

VIEW 302

VIEW 303

VIEW 304

VIEW 305

VIEW 306

VIEW 307

VIEW 308

VIEW 309

VIEW 310

VIEW 311

VIEW 312

VIEW 313

VIEW 314

VIEW 315

VIEW 316

VIEW 317

VIEW 318

VIEW 319

VIEW 320

VIEW 321

VIEW 322

VIEW 323

VIEW 324

VIEW 325

VIEW 326

VIEW 327

VIEW 328

VIEW 329

VIEW 330

VIEW 331

VIEW 332

VIEW 333

VIEW 334

VIEW 335

VIEW 336

VIEW 337

VIEW 338

VIEW 339

VIEW 340

VIEW 341

VIEW 342

VIEW 343

VIEW 344

VIEW 345

VIEW 346

VIEW 347

VIEW 348

VIEW 349

VIEW 350

VIEW 351

VIEW 352

VIEW 353

VIEW 354

VIEW 355

VIEW 356

VIEW 357

VIEW 358

VIEW 359

VIEW 360

VIEW 361

VIEW 362

VIEW 363

VIEW 364

VIEW 365

VIEW 366

VIEW 367

VIEW 368

VIEW 369

VIEW 370

VIEW 371

VIEW 372

VIEW 373

VIEW 374

VIEW 375

VIEW 376

VIEW 377

VIEW 378

VIEW 379

VIEW 380

VIEW 381

VIEW 382

VIEW 383

VIEW 384

VIEW 385

VIEW 386

VIEW 387

VIEW 388

VIEW 389

VIEW 390

VIEW 391

VIEW 392

VIEW 393

VIEW 394

VIEW 395

VIEW 396

VIEW 397

VIEW 398

VIEW 399

VIEW 400

VIEW 401

VIEW 402

VIEW 403

VIEW 404

VIEW 405

VIEW 406

VIEW 407

VIEW 408

VIEW 409

VIEW 410

VIEW 411

VIEW 412


VIEW 413

VIEW 414

VIEW 415

VIEW 416

VIEW 417



TYPICAL BOTTOM BRACKET

A
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

B
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

C
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

D
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

E
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

F
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

G
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

H
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

I
 1.6" (41.3 mm) MAX. CHAIN RING WIDTH
 1.6" (41.3 mm) MAX. CHAIN RING THICKNESS
 1.6" (41.3 mm) MAX. CHAIN RING BORE
 1.6" (41.3 mm) MAX. CHAIN RING OD

[illegible]



BUILDING CODE COMPLIANCE OFFICE
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

CONTRACTOR LICENSING SECTION
(305) 375-2527 FAX (305) 375-2558

CONTRACTOR ENFORCEMENT DIVISION
(305) 375-2966 FAX (305) 375-2908

PRODUCT CONTROL DIVISION
(305) 375-2902 FAX (305) 372-6339

PRODUCT CONTROL NOTICE OF ACCEPTANCE

Premdor Entry Systems
911 E. Jefferson, P.O. Box 76
Pittsburgh, KS 66762

Your application for Notice of Acceptance (NOA) of:

Entergy 6-8 S/E Inswing Opaque Double w/sidelites Residential Insulated Steel Door
under Chapter 8 of the Code of Miami-Dade County governing the use of Alternate Materials and Types of Construction, and completely described herein, has been recommended for acceptance by the Miami-Dade County Building Code Compliance Office (BCCO) under the conditions specified herein.

This NOA shall not be valid after the expiration date stated below. BCCO reserves the right to secure this product or material at any time from a jobsite or manufacturer's plant for quality control testing. If this product or material fails to perform in the approved manner, BCCO may revoke, modify, or suspend the use of such product or material immediately. BCCO reserves the right to revoke this approval, if it is determined by BCCO that this product or material fails to meet the requirements of the South Florida Building Code.

The expense of such testing will be incurred by the manufacturer.

ACCEPTANCE NO.: 01-0314.23
EXPIRES: 04/02/2006

Raul Rodriguez
Chief Product Control Division

THIS IS THE COVERSHEET, SEE ADDITIONAL PAGES FOR SPECIFIC AND GENERAL
CONDITIONS
BUILDING CODE & PRODUCT REVIEW COMMITTEE


This application for Product Approval has been reviewed by the BCCO and approved by the Building Code and Product Review Committee to be used in Miami-Dade County, Florida under the conditions set forth above.

Francisco J. Quintana, R.A.
Director
Miami-Dade County
Building Code Compliance Office

APPROVED: 06/05/2001

NOTICE OF ACCEPTANCE: SPECIFIC CONDITIONS


1. **SCOPE**
 - 1.1 This renews the Notice of Acceptance No. 00-0321.25 which was issued on April 28, 2000. It approves a residential insulated door, as described in Section 2 of this Notice of Acceptance, designed to comply with the South Florida Building Code (SFBC), 1994 Edition for Miami-Dade County, for the locations where the pressure requirements, as determined by SFBC Chapter 23, do not exceed the Design Pressure Rating values indicated in the approved drawings.
2. **PRODUCT DESCRIPTION**
 - 2.1 The Series Entergy 6-8 S/E Inswing Opaque Double Residential Insulated Steel Doors with Sidelites-Impact Resistant Door Slab Only and its components shall be constructed in strict compliance with the following documents: Drawing No 31-1029-EM-I, Sheets 1 through 6 of 6, titled "Premdor (Entergy Brand) Double Door with Sidelites in Wood Frames with Bumper Threshold (Inswing)," prepared by manufacturer, dated 7/29/97 with revision C dated 01/11/00, bearing the Miami-Dade County Product Control approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Division. These documents shall hereinafter be referred to as the approved drawings.
3. **LIMITATIONS**
 - 3.1 This approval applies to single unit applications of pair of doors and single door only, as shown in approved drawings. Single door units shall include all components described in the active leaf of this approval.
 - 3.2 Unit shall be installed only at locations protected by a canopy or overhang such that the angle between the edge of canopy or overhang to sill is less than 45 degrees. Unless unit is installed in non-habitable areas where the unit and the area are designed to accept water infiltration.
4. **INSTALLATION**
 - 4.1 The residential insulated steel door and its components shall be installed in strict compliance with the approved drawings.
 - 4.2 Hurricane protection system (shutters):
 - 4.2.1 Door: the installation of this unit will not require a hurricane protection system.
 - 4.2.2 Sidelite: the installation of this unit will require a hurricane protection system.
5. **LABELING**
 - 5.1 Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved".
6. **BUILDING PERMIT REQUIREMENTS**
 - 6.1 Application for building permit shall be accompanied by copies of the following:
 - 6.1.1 This Notice of Acceptance
 - 6.1.2 Duplicate copies of the approved drawings, as identified in Section 2 of this Notice of Acceptance, clearly marked to show the components selected for the proposed installation.
 - 6.1.3 Any other documents required by the Building Official or the South Florida Building Code (SFBC) in order to properly evaluate the installation of this system





Manuel Perez, P.E. Product Control Examiner
Product Control Division

NOTICE OF ACCEPTANCE: STANDARD CONDITIONS

1. Renewal of this Acceptance (approval) shall be considered after a renewal application has been filed and the original submitted documentation, including test supporting data, engineering documents, are no older than eight (8) years.
2. Any and all approved products shall be permanently labeled with the manufacturer's name, city, state, and the following statement: "Miami-Dade County Product Control Approved", or as specifically stated in the specific conditions of this Acceptance.
3. Renewals of Acceptance will not be considered if:
 - a. There has been a change in the South Florida Building Code affecting the evaluation of this product and the product is not in compliance with the code changes.
 - b. The product is no longer the same product (identical) as the one originally approved.
 - c. If the Acceptance holder has not complied with all the requirements of this acceptance, including the correct installation of the product.
 - d. The engineer who originally prepared, signed and sealed the required documentation initially submitted, is no longer practicing the engineering profession.
4. Any revision or change in the materials, use, and/or manufacture of the product or process shall automatically be cause for termination of this Acceptance, unless prior written approval has been requested (through the filing of a revision application with appropriate fee) and granted by this office.
5. Any of the following shall also be grounds for removal of this Acceptance:
 - a. Unsatisfactory performance of this product or process.
 - b. Misuse of this Acceptance as an endorsement of any product, for sales, advertising or any other purposes.
6. The Notice of Acceptance number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the Notice of Acceptance is displayed, then it shall be done in its entirety.
7. A copy of this Acceptance as well as approved drawings and other documents, where it applies, shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at all time. The engineer needs not reseal the copies.
8. Failure to comply with any section of this Acceptance shall be cause for termination and removal of Acceptance.
9. This Notice of Acceptance consists of pages 1, 2 and this last page 3.

END OF THIS ACCEPTANCE


Manuel Perez, P.E., Product Control Examiner
Product Control Division




APPROVED AS COMPLYING WITH THE
SCOTT COUNTY BUILDING CODE
DATE JUN 05 2011
BY *William J. [Signature]*
PROJECT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314-23

| REVISION | DATE | BY | CHK | DESCRIPTION |
|----------|----------|----|-----|-------------|
| 1 | 07-25-97 | WJ | WJ | PRELIMINARY |
| 2 | 07-25-97 | WJ | WJ | REVISION |
| 3 | 07-25-97 | WJ | WJ | REVISION |
| 4 | 07-25-97 | WJ | WJ | REVISION |
| 5 | 07-25-97 | WJ | WJ | REVISION |
| 6 | 07-25-97 | WJ | WJ | REVISION |
| 7 | 07-25-97 | WJ | WJ | REVISION |
| 8 | 07-25-97 | WJ | WJ | REVISION |
| 9 | 07-25-97 | WJ | WJ | REVISION |
| 10 | 07-25-97 | WJ | WJ | REVISION |
| 11 | 07-25-97 | WJ | WJ | REVISION |
| 12 | 07-25-97 | WJ | WJ | REVISION |
| 13 | 07-25-97 | WJ | WJ | REVISION |
| 14 | 07-25-97 | WJ | WJ | REVISION |
| 15 | 07-25-97 | WJ | WJ | REVISION |
| 16 | 07-25-97 | WJ | WJ | REVISION |
| 17 | 07-25-97 | WJ | WJ | REVISION |
| 18 | 07-25-97 | WJ | WJ | REVISION |
| 19 | 07-25-97 | WJ | WJ | REVISION |
| 20 | 07-25-97 | WJ | WJ | REVISION |
| 21 | 07-25-97 | WJ | WJ | REVISION |
| 22 | 07-25-97 | WJ | WJ | REVISION |
| 23 | 07-25-97 | WJ | WJ | REVISION |
| 24 | 07-25-97 | WJ | WJ | REVISION |
| 25 | 07-25-97 | WJ | WJ | REVISION |
| 26 | 07-25-97 | WJ | WJ | REVISION |
| 27 | 07-25-97 | WJ | WJ | REVISION |
| 28 | 07-25-97 | WJ | WJ | REVISION |
| 29 | 07-25-97 | WJ | WJ | REVISION |
| 30 | 07-25-97 | WJ | WJ | REVISION |
| 31 | 07-25-97 | WJ | WJ | REVISION |
| 32 | 07-25-97 | WJ | WJ | REVISION |
| 33 | 07-25-97 | WJ | WJ | REVISION |
| 34 | 07-25-97 | WJ | WJ | REVISION |
| 35 | 07-25-97 | WJ | WJ | REVISION |
| 36 | 07-25-97 | WJ | WJ | REVISION |
| 37 | 07-25-97 | WJ | WJ | REVISION |
| 38 | 07-25-97 | WJ | WJ | REVISION |
| 39 | 07-25-97 | WJ | WJ | REVISION |
| 40 | 07-25-97 | WJ | WJ | REVISION |
| 41 | 07-25-97 | WJ | WJ | REVISION |
| 42 | 07-25-97 | WJ | WJ | REVISION |
| 43 | 07-25-97 | WJ | WJ | REVISION |
| 44 | 07-25-97 | WJ | WJ | REVISION |
| 45 | 07-25-97 | WJ | WJ | REVISION |
| 46 | 07-25-97 | WJ | WJ | REVISION |
| 47 | 07-25-97 | WJ | WJ | REVISION |
| 48 | 07-25-97 | WJ | WJ | REVISION |
| 49 | 07-25-97 | WJ | WJ | REVISION |
| 50 | 07-25-97 | WJ | WJ | REVISION |

31-1029-EM-1
SHEET 2 OF 6
REVISION C

MATERIALS LIST

| ITEM NO. | DESCRIPTION | PART NUMBER | COMMENTS |
|----------|---|----------------------|--|
| 1 | WOOD HEAD JAMB | EM-14 | 1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT |
| 2 | COMPRESSION WEATHERSTRIP | EM-25 | LOCKSCREEN BRAND LKSEAL 9650-BRONZE |
| 3 | ALUMINUM ASTRAGAL | EM-12 | PREMIOR BRAND OR EQUIVALENT - 5/8" ALUMINUM ASTRAGA |
| 4 | ALUMINUM-BUMPER THRESHOLD | EM-15 | PREMIOR BRAND OR EQUIVALENT - 1 1/4" X 4 9/16" |
| 5 | TOP CHANNEL | EM-08 | PREMIOR BRAND - 1 1/16" - 20 GA STEEL |
| 6 | STEEL SKIN | 26 GA. (017.004.000) | MAX. THICKNESS PER TABLE TEST REPORT IS 267 |
| 7 | POLYURETHANE FOAM CORE | BASF FOAM - | DENSITY 2.0 TO 2.5 lbs./ft. ³ |
| 8 | BOTTOM CHANNEL | EM-07 | PREMIOR BRAND - 1 1/16" - 20 GA STEEL |
| 9 | WOOD LOCK BLOCK | EM-09 | 4" X 9 1/2" MTL. TO BE PINE OR EQUIVALENT |
| 10 | STRIKE STILE | EM-06 | PREMIOR BRAND - 1 1/16" - 20 GA STEEL |
| 11 | HINGE STILE | EM-05 | PREMIOR BRAND - 1 1/16" - 20 GA STEEL |
| 12 | LOCK PREP FILLER PLATE | EM-10 | PREMIOR BRAND - .050" THICK- MTL. TO BE POLYETHYLEN |
| 13 | 4"x4" HINGE | EM-16 | HAGER BRAND HINGE OR EQUIVALENT - .097 THICK CSTEEL |
| 14 | WOOD HINGE JAMB | EM-13 | 1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT |
| 15 | #10-24 x 1/2" F.H.W.S. | | (4) SCREWS PER HINGE INTO DOOR |
| 16 | #10 X 2" F.H.W.S. | | (5) SCREWS THROUGH HINGE JAMB INTO SIDELITE JAMB, 8" DOWN FROM TO MAX 18" O.C. THEREAFTER (10) SCREWS THROUGH STRIKE JAMB INTO SIDELITE JAMB, 4" DOWN FROM TI MAX 18" O.C. THEREAFTER (10) SCREWS THROUGH EACH SIDELITE JAMB INTO SIDELITE, 4" DOWN FROM TOP, MAX 15" O.C. THEREAFTER |
| 17 | #10 F.H.W.S. VARIATION 1 1/2" EMBEDMENT OR 3/16" PER TABS VARIATION 1 1/2" EMBEDMENT | | REFER TO ELEVATION VIEW, FOR # OF SCREWS USED AND LOCATIONS |
| 18 | #10 X 3/4" F.H.W.S. | | (2) SCREWS PER HINGE INTO JAMB |
| 19 | #8 X 2" F.H.W.S. | | (2) SCREWS AT EACH STRIKE PLATE |
| 20 | LOCKSET | | KVIRKSET BRAND 200 LOCK OR HARLOC BRAND 100 LOCK |
| 21 | #10 X 1 3/4" F.H.W.S. | | (2) SCREWS PER HINGE INTO JAMB |
| 22 | WOOD SIDELITE JAMB | EM-18 | 1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT |
| 23 | 22" X 64" SINGLE PANEL GLASS | EM-19 | TEMPERED GLASS IN POLYPROPYLENE FRAME- DC-1643 - CODL - 1/8" CLEAR TEMPERED GLASS |
| 24 | SIDELITE TRIM (WOOD) | EM-20 | 5/16" X 1/2" MTL. TO BE PINE OR EQUIVALENT |
| 25 | WOOD CASING | EM-21 | 1/8" X 1" MTL. TO BE PINE OR EQUIVALENT - ITEMS ARE HOLDINGS USE FOR "SIDE BY SIDE" JAMBS" AS NULLIONS |
| 26 | WOOD SIDELITE HEAD JAMB | EM-22 | 1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT |
| 27 | WOOD SIDELITE BASE | EM-23 | 1 1/4" X 4 9/16" MTL. TO BE PINE OR EQUIVALENT |
| 28 | POLYPROPYLENE LITE FRAME | DC-1643, DNL-2 | HP Polypropylene by DDL |
| 29 | #6 X 1 1/2" PAN HEAD SCREWS | | 18 PER FRAME TO EXCEED 14" BE THERE AFTER |
| 30 | SIDELITE STILES | | 15/16" X 1 1/16" MTL. TO BE PINE OR EQUIVALENT |
| 31 | PIN NAIL | | 3/4" LONG NAIL, 4" IN FROM END, MAX 8" O.C. THEREAFTER, USED ON NULLIONS AND TRI |



SECTION B-B

APPROVED AS COMPLYING WITH THE
SOUTH FLORIDA BUILDING CODE
DATE: JUN 05 2001
BY: [Signature]
PRODUCED BY CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314, 2, 3


PREMIOR ENTRY SYSTEMS

911 E. JEFFERSON
PITTSBURGH, KS. 66102

DR. BY: R.S. DATE: 7-29-97 SCALE: 1/4" = 1'-0"

31-1029-EM-I
SHEET 3 OF 6

REVISION LETTER B



PLEASE SEE "GLAZING DETAIL"
DRAWING #31-1029-EM-I
SHEET 2 OF 6

SECTION C-C

APPROVED AS COMPLYING WITH THE
SEALING BUILDING CODE
DATE JUN 05 2005
BY Signature
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO 01-0314.23

LIMITS: UNLESS NOTED, FRAM. : REC. : ANG. :
EXTRUSIONS: UNLESS NOTED, STD. COM. TOL. S.

| D | DATE | COUNTY | MODIFICATIONS | DATE | BY |
|-----|-----------|--------|-----------------|----------|-----------------------|
| C | MATERIAL | WAS | PMI | YSTYRENE | RS |
| B | ADDED | PAGE 5 | (OTHER OPTIONS) | 10-1-99 | RS |
| A | AND | SCREWS | TO | LITE | FRAM. & MATERIAL LIST |
| LIR | REVISIONS | | | DATE | BY |


PART NAME: ENERGY METAL EDGE SUBMITTAL GC-CO
SCALE:

PREMIER ENTRY SYSTEMS
911 E. JEFFERSON
PITTSBURGH, PA 15202


31-1029-EM-I
SHEET 4 OF 6

REVISION LETTER D


OTHER DOOR CONFIGURATIONS




DXXX




DXX




DXXD




DXX




DX



XD



DXXD




DX

APPROVED AS COMPLYING WITH THE
SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2009
BY *[Signature]*
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314-23

| | | | |
|---|--------------|---|---------|
| LIMITS UNLESS NOTED. ENG. : DEC : ANG : | | EXTRUSIONS UNLESS NOTED. STD. COMP. 101'S | |
| ENGINEER: | LIR | REVISIONS | DATE BY |
| DR. BT. LD. | DATE 1-11-01 | PART NAME: | SCALE: |
| PREMIOR ENTRY SYSTEMS | | 31-1029-EM-I | |
| 911 E. JEFFERSON | | SHEET 5 OF 6 | |
| PHILADELPHIA, KS 66102 | | REVISION LETTER | |



OTHER DOOR PANEL STYLES

79 5/16" MAX
36" MAX



OTHER SIDELITE STYLES

79 3/16" MAX
36" MAX




APPROVED AS COMPLYING WITH THE
SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2001
BY *Mark*
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO 01-0314.23

LIMITS UNLESS NOTED, FRAM : IRL : ANG :
ENGINEER:

| REV | BY | J.D. | DATE | 12/15/01 | REVISIONS | DATE | BY |
|-----|----|------|------|----------|-----------------------|------|----|
| | | | | | PREMIOR ENTRY SYSTEMS | | |
| | | | | | 31-1029-EM-1 | | |
| | | | | | SHEET 6 OF 6 | | |
| | | | | | REVISION 111119 | | |


PREMIOR ENTRY SYSTEMS
901 E. JEFFERSON
PITTSBURGH, KS 66762

PREMDOR (ENERGY BRAND) DOUBLE DOOR WITH SIDELITES IN WOOD FRAMES WITH BUMPER THRESHOLD (INSWING)



ATTACH ASTRAGAL THRU BOLT
AND THRESHOLD WITH 1/2\"/>

NOTES:
1. WOOD BUCKS BY OTHERS, MUST BE ANCHORED
PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY
STRUCTURAL WOOD BUCK.
5. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>



| DESIGN PRESSURE RATINGS | |
|---|----------|
| WHERE WATER INFILTRATION REQUIREMENT IS NOT NEEDED | Positive |
| WHERE WATER INFILTRATION REQUIREMENT IS NOT NEEDED | Negative |
| NOT APPROVED * -55.0 psf | |
| NOT APPROVED * -55.0 psf | |

APPROVED AS COMPLYING WITH THE
SOUTH FLORIDA BUILDING CODE
DATE JUN 05 2001
BY *Michael J. ...*
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 01-0314, 23

| | |
|--|-----------------|
| PREMDOR ENTRY SYSTEMS | |
| DATE: 7-29-97 | REV: 1 |
| LIMITS: WATER INFILTRATION: 0.01 INCHES PER HOUR | |
| ENGINEER: [Signature] | |
| REVISIONS: | |
| DATE: 7-29-97 | BY: [Signature] |
| SCALE: N.T.S. | |
| SHEET 1 OF 6 | |

* UNITS SHALL BE INSTALLED ONLY AT LOCATIONS PROTECTED BY A CANOPY OR
OVERHANG SUCH THAT THE ANGLE BETWEEN THE EDGE OF CANOPY OR OVERHANG
TO SILL IS LESS THAN 45 DEGREES. UNLESS UNIT IS INSTALLED IN
NON-HABITABLE AREAS WHERE THE UNIT AND THE AREA ARE DESIGNED TO
ACCEPT WATER INFILTRATION.

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

1. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
2. THE PRECEDING DRAWINGS ARE INTENDED TO
QUALIFY THE FOLLOWING INSTALLATIONS.
3. WOOD FRAME CONSTRUCTION WHERE DOOR
SYSTEM IS ANCHORED TO A MINIMUM TWO BY WOOD
JPCING.
4. MASONRY OR CONCRETE CONSTRUCTION WHERE
DOOR SYSTEM IS ANCHORED DIRECTLY TO CONCRETE
OR MASONRY WITH OR WITHOUT A NON-STRUCTURAL
ANCHORING SCREWS TO BE 1/2\"/>

(Address of Treatment or Lot/Block of Treatment)

City

Florida Pest Control & Chemical Co.

www.flapest.com

Product to be used: Bora-Care Termiticide (Wood Treatment)

Chemical to be used: 23% Disodium Octaborate Tetrahydrate

Application will be performed onto structural wood at dried-in stage of construction. Bora-Care Termiticide application shall be applied according to EPA registered label directions as stated in the Florida Building Code Section 1861.1.8

(Information to be provided to local building code offices prior to concrete foundation installation.)

Notice of Intent for Preventative Treatment for Termites

(As required by Florida Building Code 104.2.6)

Date: 10/26/05

~~461~~ 461 SW Quail Ridge Ct
(Address of Treatment or Lot/Block of Treatment)

Lake City
City

Florida Pest Control & Chemical Co.

www.flapest.com

Product to be used: Bora-Care Termiticide (Wood Treatment)

Chemical to be used: 23% Disodium Octaborate Tetrahydrate

Application will be performed onto structural wood at dried-in stage of construction. Bora-Care Termiticide application shall be applied according to EPA registered label directions as stated in the Florida Building Code Section 1861.1.8

(Information to be provided to local building code offices prior to concrete foundation installation.)