

Cal-Tech Testing, Inc.

- Engineering
- Geotechnical
- Environmental

 LABORATORIES

P O Box 1625 • Lake City, FL 32056 Tel (386) 755-3633 • Fax (386) 752-5456

450 SR 13N, Suite 106-308, Jacksonville, FL 32259 Tel (904) 381-8901 • Fax (904) 381-8902

March 6, 2020

Mr. Kris Fase 456 Swain Blvd. Greenacres, Florida 33463

RE: Geotechnical Engineering Exploration Report

1003 NW Tiger Drain Road-House & Steel Building Structures

White Springs, Florida 32096

Cal-Tech Testing Inc. Project No. 20-00068-01

Dear Mr. Kris Fase:

This report presents the results of our geotechnical engineering exploration performed for the proposed House & Steel Building Structures at 1003 NW Tiger Drain Road in White Springs, Florida.

The purposes of the exploration were to determine and evaluate the general soil subsurface conditions at the property site and provide site preparation and foundation recommendations in regards to design and construction of the proposed residential home and work shop steel structures.

SITE AND PROJECT INFORMATION

Based on our observations during our field work, the site consists of a relatively flat and cleared vacant property surrounded by woods and trees.

Information you provided to us indicates the residential home will consists of an approximately 3,200 ft², 1-story structure, and a detach 2400 ft², 1-story, work shop steel structure. No information regarding the proposed structural loading system was provided.

SUBSURFACE SOIL EXPLORATION

Our subsurface soil exploration was performed on February 21, 2020 and consisted of drilling four (4) Standard Penetration Test (SPT) borings (B1 through B4) to a depth of 15 ft. at locations within the structures footprints you marked onsite. Refer to the enclosed Boring Location Plan.

We contacted Sunshine State One Call of Florida to mark out existing, known underground utilities prior to the beginning of our field investigation.

The SPT borings were advanced using a continuous flight auger and manual hammer. The split-spoon sampling was performed continuously in the upper 10 ft. and at 5 ft. intervals thereafter to the termination depth of the borings at 15 ft. The penetration test was performed by driving a 2-inch O.D. split spoon sampler with the hammer falling 30 inches. The number of hammer blows required to drive the sampler a total of 24 inches (upper 10 ft.) and 18 inches in 6-inch increments



Geotechnical Engineering Exploration Report 1003 NW Tiger Drain Road-House & Steel Building Structures White Springs, Florida 32096 Cal-Tech Testing, Inc. Project No.20-00068-01

were recorded in boring logs. The penetration resistance, N-values, is the summation of the second and third 6-inch increments and is used to derive soil engineering parameter indexes from empirical correlations. The boreholes were backfilled with soil cuttings at completion.

All soil samples were delivered to our geotechnical laboratory for their review and classification by our geotechnical engineer.

SUBSURFACE SOIL CONDITIONS

Generalized Subsurface Soil Profile

The generalized subsurface soil profile inferred from the results of the subsurface soil exploration consists of a 2 ft. to 5 ft. thick stratum of poorly graded SAND (SP) underlain by a 2 ft. to 3 ft. thick layer of SILTY SAND (SM), a 8 ft. to 10 ft. thick SANDY CLAY (CH) stratum and the BOTTOM SILTY SAND to the boring termination depths at 15 ft.

The recorded N-values indicate a predominate Very Loose (i.e. N<4) Relative Density in the SAND stratum and Loose (i.e. 5<N<10) to Medium Dense (i.e. 11<N<30) SILTY SAND. The SANDY CLAY stratum presented a Stiff (i.e. 9<N<15) to Very Stiff (i.e. 16<N<30) consistency. The BOTTOM SILTY SAND was encountered in a Medium Dense condition.

Analyses of the soil laboratory test results (i.e. Fine content and Atterberg Limits) suggest the SANDY CLAY stratum is inactive in terms of expansion with changes of moisture content and slightly over-consolidated.

Details of the subsurface soil strata, SPT blows/foot (N-value) and laboratory test results are presented in the log of borings enclosed to this report.

Groundwater

The groundwater was encountered first at a depth of 7 ft. at boring location B1 only. The USDA NRCS indicates groundwater at depths of 42 inches to 72 inches for the soil map unit covering the site.

Based on the Federal Emergency Administration (FEMA) Flood No. 12023C0167D, effective November 2, 2018 (enclosed), the property is located within an "Area of Minimal Flood Hazard."

FOUNDATION EVALUATION AND RECOMMENDATIONS

The primary geotechnical considerations for the support of the proposed residence home and work shop steel structures is the Very Loose and Loose relative density in the SAND and SILTY SAND strata; however, the proposed structures could be supported on a system of shallow foundations after performance of a site preparation work as indicated in the following paragraphs.

The recommended site preparation work should consist of the excavation and backfilling of the existing soils to a depth of 5 ft. and to 5 ft. beyond the structure's footprints. During the excavation the clay soils, if encountered, should be segregated from the sand and silty sand soils. Subsequently, the excavated sand and silty sand soils, or approved material, should be used to backfill in 12-in thick lifts compacted to at least 95% of the material's Maximum Dry Density (ASTM D-1557) and to the general ground surface elevations.

Rising of the existing ground levels, if required, to establish the finished floor elevations after excavation and backfilling, should be performed by placing and compacting 12-inch thick lifts of approved material up to the proposed finish grades. Each lift should be compacted to at least 95% of the material's Maximum Dry Density (ASTM D 1557).

Geotechnical Engineering Exploration Report 1003 NW Tiger Drain Road-House & Steel Building Structures White Springs, Florida 32096 Cal-Tech Testing, Inc. Project No.20-00068-01

Approved material should consist of granular soils with size particles not larger than 3 inches, maximum 12% of fines (i.e. wash 200) and no organic content. Soils with higher fines content are acceptable; however, may result difficult to compact.

After satisfactory performance of the recommended site preparation work the proposed structures could be supported on footings bearing on the backfilled sand a silty sand or approved material and designed with a safe soil contact pressure of 2,000 lb/ft² and settlements within 1 inch.

An allowable sliding resistance of 0.35 could be used for the concrete footings cast directly on the backfilled sand, silty sand or approved soils.

The footing subgrade upper 12 inches should be compacted to at least 95% of the material's Maximum Dry Density (ASTM D 1557).

The ground floor slabs could be supported on grade after performance of the recommended site preparation work.

Positive drainage of stormwater should be directed away from the structures to avoid moisture accumulation beneath the structure footings and slabs.

LIMITATIONS

Information on subsurface strata and groundwater levels shown on the logs represent conditions encountered only at the locations and depths indicated and at the time of the exploration. If different conditions are encountered during construction, they should be immediately brought to our attention for evaluation as they may affect our recommendations.

The project site is located within Sinkhole Area III; however, sinkhole investigation was outside the scope of services of the exploration work.

CLOSURE

We are available for inspection of the site during the exploratory test pits and to test the backfill and fill compaction.

It has been a pleasure working with you and we look forward to continuing our work on this project.

Mike Stalvey, Ir.

Vice-President

Sincerely,

CITLAT

al-Lecti Testing, Inc.

Ivante. Marcannovi.S. P.L.


Sr. Ceotechnicar Engineer...

Enclosures:

Boring Location Plan

FEMA Map

Boring Logs



National Flood Hazard Layer FIRMette





Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

OTHER AREAS OF FLOOD HAZARD SPECIAL FLOOD HAZARD AREAS OTHER AREAS STRUCTURES 1111111 Levee, Dike, or Floodwall MAP PANELS FEATURES GENERAL ---- Channel, Culvert, or Storm Sewer OTHER NO SCREEN Area of Minimal Flood Hazard Line x 17.5 Future Conditions 1% Annual Coastal Transect Baseline Limit of Study Water Surface Elevation Cross Sections with 1% Annual Chance Area with Flood Risk due to Levee Zune L Digital Data Available Hydrographic Feature Profile Baseline Jurisdiction Boundary Base Flood Elevation Line (BFE) Area of Undetermined Flood Hazard 2011 **Effective LOMRs** Chance Flood Hazard Zune X 0.2% Annual Chance Flood Hazard, Areof 1% annual chance flood with average depth less than one foot or with drainage Coastal Transect Levee. See Notes, Zinn: X Regulatory Floodway With BFE or Depth zone AE, AO, AH, VE, AR Without Base Flood Elevation (BFE) No Digital Data Available Area with Reduced Flood Risk due to areas of less than one square mile tone

The pin displayed on the map is an approximat point selected by the user and does not represa an authoritative property location.

digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards This map complies with FEMA's standards for the use of

become superseded by new data over time. time. The NFHL and effective information may change or reflect changes or amendments subsequent to this date and was exported on 3 6 2020 at 2:45:56 PM and does not authoritative NFHL web services provided by FEMA. This map The flood hazard information is derived directly from the

FIRM panel number, and FIRM effective date. Map images for elements do not appear. basemap imagery, flood zone labels, This map image is void if the one or more of the following map regulatory purposes. unmapped and unmodernized areas cannot be used for legend, scale bar, map creation date, community identifiers,

250

500

1,000

1,500

2,000

Cal-Tech Testing, Inc. 3309 SR 247 Lake City, FL 32024 Telephone: 386-755-3633

BORING NUMBER B1 PAGE 1 OF 1

L	Fax: 386-755-3633		DO IEC	* 51.01		11	0 Ot1 D	ildia - Charles
		PROJECT NAME House & Steel Building Structures PROJECT LOCATION White Springs Florida						
	### STARTED 2/21/20 COMPLETED 2/21/20							HOLE SIZE 3-in dia. x 15 ft. depth
	ING CONTRACTOR Cal-Tech Testing, Inc.		ROUND					HOLE GILL SAITGIE, X 15 IL GEPUI
	ING METHOD Continuous Flight Auger/Split Spoon							ft / Elev -7.00 ft
	ED BY M.S. CHECKED BY I.M.						LING	
	S Elev. refered to ground surface	_						
	Elevitorios la grania dendo		_				DATA	
ELEV. (ft)	MATERIAL DESCRIPTION	SYMBOL	DEPTH SCALE (ft)		TYPE	(%)	BLOW COUNTS (N VALUE)	REMARKS (DRILLING FLUID, DEPTH OF CASING, FLUID LOSS, DRILLING RESISTANCE, ETC.)
9	(SP) Yellowish brown SAND		2	1	ss	71	1-2-2-2 (4)	Boring Location Coordinates: N30°18'7.51" W82°46'36.67" SS=Split Spoon sampler
	(SM) Yellowish brown SILTY SAND		4_	2	ss	75	2-1-2-4 (3)	Laboratory Test Result SS-2B Fines content=24.9%
-5	(SM) Gray SILTY SAND		_ 6 _	3	SS	83	3-5-8-9 (13)	55-25 Files 65 Roll 24.5 %
	☑ (CH) Greenish gray CLAY		 - 8 _	4	ss	75	5-8-8-9 (16)	
-10			- - - 10_	5	SS	83	5-10-11-14 (21)	
			12					
-15	(SM) Light gray SILTY SAND Bottom of borehole at 15.0 feet.		14	6	ss	78	4-6-6 (12)	Laboratory Test Result SS-6 Fines content=15.2%

Cal-Tech Testing, Inc 3309 SR 247 Lake City, FL 32024 Telephone: 386-755-3633

BORING NUMBER B2 PAGE 1 OF 1

1	Fax: 386-755-3633							
CLIEN	T Mr. Kris Fase	F	PROJEC	T NA	ME	Hou	se & Steel Bu	uilding Structures
PROJE	ECT NUMBER 20-00068-01	P	ROJEC	T LO	CAT	ION	White Spring	gs Florida
	STARTED 2/21/20 COMPLETED 2/21/20		ROUNE	ELE	VA	TION	0 ft	HOLE SIZE 3-in dia. x 15 ft. depth
DRILLI	ING CONTRACTOR Cal-Tech Testing, Inc.		ROUNE	WA1	TER	LEV	ELS:	
	ING METHOD Continuous Flight Auger/Split Spoon		AT	TIME	OF	DRII	LLING - No	ot encountered
LOGGI	ED BY M.S. CHECKED BY I.M.		AT	END	OF	DRIL	LING —	
NOTES	Elev. refered to ground surface		AF	TER	DRII	LLING	·	
			шi		SAI	MPLE	DATA	
ELEV.	MATERIAL DESCRIPTION	SYMBOL	DEPTH SCALE (ft)	NUMBER	TYPE	RECOVERY (%) (ROD) %	BLOW COUNTS (N VALUE)	REMARKS (DRILLING FLUID, DEPTH OF CASING, FLUID LOSS, DRILLING RESISTANCE, ETC.)
	(SP) Yellowish brown SAND		2	1	ss	67	1-2-2-2 (4)	Boring Location Coordinates: N30°18'7.55" W82°46'36.23" SS=Split Spoon sampler
- -			4_	2	ss	58	1-2-2-2 (4)	Î
5	(SM) Gray CLAY		6_	3	ss	71	2-5-5-2 (10)	Laboratory Test Result SS-3B Fines content=47.9% SS-3B Moisture content=26,2%
-	(CH) Greenish gray CLAY			4	ss	54	5-6-8-12 (14)	SS-3B Liquid Limit=33 SS-3B Plasticity Index=21 Laboratory Test Result SS-4 Fines content=73,1%
-10			10_	5	ss	67	8-10-10-10 (20)	SS-4 Moisture content=4212% SS-4 Liquid Limit=57 SS-4 Plasticity Index=25
			12					
-15	(SM) Light gray SILTY SAND Bottom of borehole at 15.0 feet.		14	6	ss	72	7-8-7 (15)	
10 15	3							

Cal-Tech Testing, Inc. 3309 SR 247 Lake City, FL 32024 Telephone: 386-755-3633

BORING NUMBER B3 PAGE 1 OF 1

1,7	Fax: 386-755-3633							
CLIEN	Mr. Kris Fase	P	ROJEC	T NA	ME	Hou	se & Steel B	uilding Structures
1	ECT NUMBER 20-00068-01						White Sprin	
	STARTED 2/21/20 COMPLETED 2/21/20) G	ROUND	ELE	VAT	ION	0 ft	HOLE SIZE 3-in dia. x 15 ft. depth
DRILL	ING CONTRACTOR Cal-Tech Testing, Inc.	G	ROUND) WAT	TER	LEVI	ELS:	
DRILL	ING METHOD Continuous Flight Auger/Split Spoon		AT	TIME	OF	DRIL	LING N	ot encountered
	ED BY M.S. CHECKED BY I.M.						LING	
NOTE	S Elev. refered to ground surface		AF	TER I	DRII	LLING	· <u></u>	
			ш		SAN	MPLE	DATA	
INGS.GPJ ELEV. (ft)	MATERIAL DESCRIPTION	SYMBOL	DEPTH SCALE (ft)	NUMBER	TYPE	RECOVERY (%) (RQD) %	BLOW COUNTS (N VALUE)	REMARKS (DRILLING FLUID, DEPTH OF CASING, FLUID LOSS, DRILLING RESISTANCE, ETC.)
ES-WHITE SPR	(SP) Yellowish brown SAND		2	1	ss	/5	1-2-1-2 (3)	Boring Location Coordinates: N30°18'9.47" W82°46'36.06" SS=Split-Spoon sampler
NG STRUCTUR			4_	2	ss	71	2-2-2-2 (4)	A
STEEL BUILDIR	(SM) Gray SILTY SAND		6	3	ss	71	3-4-5-7 (9)	
Is:House &	(CH) Greenish gray CLAY		_ 8 _	4	SS	79	5-7-8-9 (15)	
-10			10	5	ss	67	5-8-11-14 (19)	
PROGRAM FILES (X80			_12_					
0 2 2 2 -15	(SM) Light brownish gray SILTY SAND Bottom of borehole at 15.0 feet.		_ 14	6	ss	78	8-8-8 (16)	Laboratory Test Result SS-6 Fines content=24.6%
CECUTECH BH COLUMNS - DATA ENTRY LATEST UPDATE.GDT - 3.6(20) 16.223 - C.: PROGRAM FILES (X86WGINTYPROJECTS:HOUSE & STEEL BUILDING STRUCTURES-WHITE SPRINGS.GPJ								

Cal-Tech Testing, Inc. 3309 SR 247 Lake City, FL 32024 Telephone: 386-755-3

BORING NUMBER B4 PAGE 1 OF 1

il in	Fax: 386-755-3633							
1	T Mr. Kris Fase	Р	ROJEC	T NA	ME	Hous	se & Steel B	uilding Structures
PROJE	ECT NUMBER 20-00068-01	P	ROJEC	T LO	CAT	ION _	White Sprin	gs Florida
DATE	STARTED 2/21/20	20 G	ROUNE	ELE	VAT	TION	0 ft	HOLE SIZE 3-in dia. x 15 ft. depth
DRILLI	ING CONTRACTOR Cal-Tech Testing, Inc.	G	ROUND	WA1	ΓER	LEVE	LS:	
DRILLI	ING METHOD Continuous Flight Auger/Split Spoon		AT	TIME	OF	DRIL	LING N	ot encountered
LOGGE	ED BY M.S. CHECKED BY I.M.		AT	END	OF	DRIL	LING	
NOTES	S Elev. refered to ground surface		AF	TER I	DRIL	LLING		
			ш		SAN	MPLE	DATA	
ELEV. (ft)	MATERIAL DESCRIPTION	SYMBOL	DEPTH SCALE (ft)	NUMBER	TYPE	RECOVERY (%) (RQD) %	BLOW COUNTS (N VALUE)	REMARKS (DRILLING FLUID, DEPTH OF CASING, FLUID LOSS, DRILLING RESISTANCE, ETC.)
,	(SP) Yellowish brown SAND		2	1	SS	71	1-2-1-2 (3)	Boring Location Coordinates: N30°18'8.94" W82°46'36.06" SS=Split-Spoon sampler
	(SM) Yellowish brown SILTY SAND		4	2	ss	75	2-2-2-5 (4)	я
-5	(CH) Greenish gray CLAY		6	3	ss	83	5-6-6-9 (12)	
			8	4	ss	71	5-8-8-13 (16)	
-10				5	ss	67	6-8-9-13 (17)	
			12_					
-15	(SM) Light brownish gray SILTY SAND		14_	6	ss	72	5-7-7 (14)	
	Bottom of borehole at 15.0 feet.							
-5 -10	,							
					The state of the s			5

If the twee to want Agrand : Building a XEQB a Y Land Breakdown farms) permany percent Columbia County Property Appraiser CHANG Willed . Owner & Property Info ▼ Extra Features & Out Buildings → Building Characteristics Property & Assessment Values Use Code 110 AG ACRE (000500) Parcel -- 24.25.15.09097.000 --Description STL OF NOTA 1114/8 GC 105/302 PROESD 105/02 VID KISHKKII Area GGAG To off decidence Contributes and a father of contribute and strategy to the strategy of the strategy of the strategy to the st Code FASE KRISTOPHER J & KAREN 4% STRATIBUD GREENAGRES FL 11411 Cand Case 009930 Bidg Sheton Sale Date 2019 Certified Values 115293 50 Class
50 397 Accusated
50 504 Can
50 397 Accessed
50 504 Accessed
504 504 504 504
604 504 504 504
604 504 504 504
604 504 504 504
604 504 504 504
604 504 504 504
604 504 504 504
604 504 504 504
604 504 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 504 504
604 5 0 133 JOT MALLAND 1 50 AGLAND 1 50 Building 5 50 XFOB 1 503 JOT JUST HO STANDER OF THE STA Eldy Item Sale Price ц 6) (1) 200 000 the te harten with a teach of the 2 SATIR Tay District **B** 2020 Working Values E Bid; Delt 24-25-15 1 Value Book, Page 10 MT 副 00000 AC Ser. 142 33 231 FEE the contract Bares. 3101 100 Map P : 2 West .. Satellite 1 00 1 00 1 00 1 00 DITE < < 5 Base SF Retrays Tax Record 2019 TRUS (pdf) Property Card Parcel Lst Generator Show on GIS Map 0 0 0 0 0 Actual SF 51 042 Condition (% Good) Treatmentagement - a college Campraga Bidg Value ELECTRICAL SECTION AND THE SEC 2020 Working Yalues A do sustain 明 RC034 i : + 1

>

Ð

8

Columbia County Property Appraiser

The state of

r, a 6

Q

I

×

7

2

C

E

Address of the control of the second of the control of the control

representation commission

Arcard Search Search Resum Parcel Details

CIGIUM

Fase Farm

6/3/2020

Kris Fase (561) 644-1284 Karen Fase (561) 767-6391

Current residence: 456 Swain Blvd, Greenacres, FL 33463

Columbia County Site Location for Steel Building:

1003 NW Tiger Drain Rd White Springs FL 32096

Steel Building

Apex Metal Building Jason Bullock 386-209-3779

Septic

Lundy Septic Adam Lundy 386-590-6272

Slab

Parrish Concrete Larry Parrish 386-623-6374

Plumbing

Paradise Plumbing Services Mark Dawson 386-288-6407

Electrical

TBD - Holly Electric?