CAROL CHADWICK, P.E.

Civil Engineer
1208 S.W. Fairfax Glen
Lake City, FL 32025
307.680.1772
ccpewyo@gmail.com
www.carolchadwickpe.com

September 15, 2021

Little \$ Williams, Inc. 386.755.3139 littleawilliams@qmail.com

re: ELEVATION LETTER - 525 SW PINEHURST DRIVE, LAKE CITY, FL

As requested, I inspected the building site for the proposed construction at the above referenced site. The footing for the foundation had been excavated at the time of the inspection. The photo was taken from corner of the proposed home location looking southwest. The site drains to the west and then to the south to a borrow ditch adjacent to the road.



CAROL CHADWICK, P.E. Page 2

Per the Forest Country 6^{th} Addition Plat, the minimum finished floor elevation is listed as I I O.70. The revised finished floor elevation shall be 109.80. The elevation of the street centerline is 109.6 +/-. The revised finished floor elevation is sufficient to protect the structure against water damage from a base flood event. The site will be graded to channel direct precipitation runoff from the home and to the street.

I certify that the existing finished floor elevation listed above will protect the structure against water damage from a base flood event, as defined in Article 8 of the Land Development Regulations.

Should you have any questions, please don't hesitate to contact me.

Respectfully,

Digitally signed by Carol Chadwick
DN: c=US,
o=Unaffiliated,
ou=A01410D000001711
349D4A70001621F,
cn=Carol Chadwick
Date: 2021.09.15
11:36:15-04'00'

Carol Chadwick, P.E.

attachments: Aerial Photo

