

CERTIFICATE OF COMPLETION

ISSUED BY COLUMBIA COUNTY, FLORIDA

BUILDING PERMIT NUMBER: 000046584

CONTRACTOR: BRECK A WEINGART CHARLES PERRY PARTNERS INC CGC1519789

JOB ADDRESS: FLORIDA CORRECTIONAL FINANCE CORPORATION 7906 E US HIGHWAY90 LAKE CITY, FL 32055 34-3S-18-10339-002

This certificate is issued in compliance with the requirements of this code for the occupancy and division of occupancy and the use for which the proposed occupancy is classified.

Type of development: Building to be occupied as: Occupancy Type: Construction Type: Building Code Used: Sprinkler: Occupant Load: Notes:

Jay Gen

KOOI Replacement of Repair

Phase IV Roof 'A' and Phase V Roof 'D': Scope of work includes removal of the existing low slope single ply ketone ethylene ester(kee) roofing system and insulation system, down to the existing structural concrete deck. Install a fully adhered temporary membrane/vapor barrier and a rigid isocyanurate insulation with a high density coverboard, for an overall average R-25 insulation value to meet minimum FM I-90 (FBC-I 10 MPH) wind uplift requirements. A 'hybrid' fully adhered modified bitumen interplay roofing membrane with high solar reflectance index (SRI) 80 mil PVC fleeced back cap sheet & flashing to provide a roofing manufacturer's standard 20-year warranty. Also includes installing new prefinished aluminum counterflashing and PVC clad metal scupper throats in the existing scupper locations. Removal of abandoned rooftop equipment and raise existing curbed rooftop equipment and VTRs a minimum height (8 in.) above the finished roof surface. Lastly, includes the installation of two structural metal bridges (the first spanning from roof 'A' to roof 'H-E' and the second spanning from roof 'D' to roof 'J-N'. NA NA

2020 Florida Building Code 7th Edition and Florida Statute 553.844 NA NA

November 17, 2023

AUTHORIZING SIGNATURE: Troy Crews

DATE SIGNED